# 2023
# UNDERGROUND CONSTRUCTION STANDARDS

Historical Record: 5/19/2023
External Version




SDGE™


| | |
|---|---|
| GENERAL INFORMATION | 3000 |
| PRACTICES | 3100 |
| IDENTIFICATION | 3200 |
| SUBSTRUCTURES | 3300 |
| PADS, RETAINING WALLS & CLEARANCES | 3400 |
| PAD & WALL MOUNTED SECTIONALIZING EQUIPMENT | 3500 |
| SUBSURFACE SECTIONALIZING EQUIPMENT | 3600 |
| TRANSFORMERS | 3700 |
| CAPACITORS | 3800 |
| SECONDARIES/SERVICES | 3900 |
| CABLES | 4000 |
| TERMINATIONS SPLICING CONNECTIONS | 4100 |
| CABLE POLES | 4200 |
| FUSES & FAULT INDICATORS | 4300 |
| LIGHTING | 4400 |
| GROUNDING | 4500 |
| TELECOMMUNICATIONS & SCADA | 4600 |
| PRIMARY METER, REGULATOR & BOOSTER STATION | 4700 |
| VAULT STANDARDS | 4800 |
| TRENCHLESS CONSTRUCTION | 5000 |
| DISCLAIMER & CONTACTS | |
| SUMMARY OF CHANGES | |
| REFERENCE | |

# ATTENTION:

THESE STANDARDS WERE DEVELOPED FOR MAINTAINING SAFETY AND RELIABILITY OF THE ELECTRIC DISTRIBUTION AND SERVICE SYSTEMS.

THE INTENT OF THIS STANDARD IS TO GUIDE ENGINEERS, DESIGNERS/PLANNERS AND CONSTRUCTION PERSONNEL AND PROVIDE TYPICAL CONSTRUCTION METHODS FOR ELECTRIC DISTRIBUTION. NOT ALL ARRANGEMENTS ARE DEPICTED AND IT IS THE USER'S RESPONSIBILITY TO APPLY THESE STANDARDS APPROPRIATELY. ALL USERS MUST USE GOOD JUDGMENT. STANDARDS ARE UPDATED AS NEEDED. CONSULT EDE FOR LATEST VERSION. SDG&E STANDARDS MUST BE APPLIED. PRE-CONSTRUCTION APPROVAL OF A "DEVIATION REQUEST" IS REQUIRED FOR ANY EXCEPTION TO THESE STANDARDS. ANY ALTERATIONS, MODIFICATIONS OR IMPROVEMENTS TO THIS AND ALL STANDARDS MUST BE REVIEWED, APPROVED AND DOCUMENTED BY EDE-CONSTRUCTION STANDARDS AND DISTRICT C&O'S.

THE CPUC'S GENERAL ORDER 95 RULES/REQUIREMENTS ARE NOT INTENDED FOR USE AS COMPLETE CONSTRUCTION SPECIFICATIONS BUT EMPLOY ONLY THE MINUMUM REQUIREMENTS WHICH ARE MOST IMPORTANT FROM THE STANDPOINT OF **SAFETY AND RELIABILITY.** SDG&E MAY IMPOSE STRICTER RULES AND REQUIREMENT IN THE INTREST MAINTANANING SAFETY AND RELIABILTY OF OUR ELECTRICAL SYSTEM.

CONSTRUCTION SHALL BE ACCORDING TO ACCEPTED GOOD PRACTICE FOR GIVEN LOCAL CONDITIONS IN ALL SITUATIONS NOT SPECIFIED IN THE STANDARD.

SDG&E WILL NOT ACCEPT ANY SYSTEM DESIGN OR INSTALLATION WHICH DOES NOT CONFORM TO THESE STANDARDS

DEVIATIONS CANNOT BE GRANTED WHICH CONFLICT WITH THE CPUC GENERAL ORDERS OR OTHER GOVERNING AGENCIES. THESE MAY INCLUDE SEPARATION FROM ENERGIZED FACILITIES AND WORKING CLEARANCES.

BASED ON UNUSUAL OR UNSAFE SITE CONDITIONS SDG&E MAY IN THE INTEREST OF SAFETY OR RELIABILITY REQUIRE CONSTRUCTION MEASURES BEYOND THOSE SPECIFICALLY STATED IN THIS MANUAL.

EXCEPT FOR A REQUIREMENT TO IMMEDIATELY ADOPT NEWLY PUBLISHED STANDARDS, THE APPLICATION OF NEWLY PUBLISHED STANDARDS IS REQUIRED FOR ALL WORK UP TO THE 30% PROJECT DESIGN APPROVAL LEVEL. ALL DESIGN AND CONSTRUCTION WORK AFTER 30% PROJECT DESIGN APPROVAL MAY USE CONSTRUCTION STANDARDS THAT IMMEDIATELY PRECEDE THE NEWLY UPDATED STANDARD, UNLESS THE IMMEDIATE ADOPTION OF NEWLY PUBLISHED STANDARDS IS MANDATED.

USE OF "BLOCK STOCK" MUST BE COORDINATED WITH INVENTORY & LOGISTICS AND IS GENERALLY ONLY APPLIED AS A "LAST RESORT" AFTER CONSULTATION AND AGREEMENT WITH STAKEHOLDERS AND AN ALTERNATE SOLUTION, SUPPLIER, MATERIAL OR METHOD IS DEEMED ACCEPTABLE AND AVAILABLE.

MAIN TABLE OF CONTENTS

IF YOU HAVE ANY QUESTIONS REGARDING THE CONTENT OF THESE MANUALS PLEASE EMAIL CONSTRUCTIONSTANDARDSADMINISTRATORS@SEMPRAUTILITIES.COM OR CONTACT:

| MANUAL | CONTACT | EMAIL ADDRESS | PHONE |
|---|---|---|---|
| Electric Distribution Design Manual | Martha Lachmayr | mlachmayr@sdge.com | (858) 654-8245 |
| Overhead Construction Standards | Mike Forchette | mforchette@sdge.com | (619) 244-7495 |
| Service Standards & Guide | Israel Juarez | ijuarez@sdge.com | (858) 636-3941 |
| Electric Vehicle Supply Equipment Standards | Israel Juarez | ijuarez@sdge.com | (858) 636-3941 |
| Underground Construction Standards | Eddie Alcobia | ealcobia@sdge.com | (619) 574-4988 |
| Electric Standard Practices | Joey Kucharyski | jkucharyski@sdge.com | (760) 566-5919 |
| Tool Catalog | Roy Guilao | rguilao@sdge.com | (760) 672-6211 |

PRINTED COPIES:

FOR PRINTED VERSIONS, WITH BINDER AND TAPS, OF THE **OVERHEAD CONSTRUCTION STANDARDS** PLEASE CONTACT CONSTRUCTIONSTANDARDSADMINISTRATORS@SEMPRAUTILITIES.COM. THESE WILL BE PROVIDED AT THE COST OF YOUR DEPARTMENT. PLEASE INCLUDE IN THE EMAIL:

- NAME, COST CENTER #, I/O #, MAIL STOP #

# SUMMARY OF CHANGES

| DATE | STANDARD PAGES | FILE NAME |
|---|---|---|
| 01/23/19 | NEW FORMAT RELEASE | UGCS2019v0123.pdf |
| 02/22/19 | 3409, (Formatting Updates: 3104, 3111, 3140, 3238, 4307, 4308, 4359, 4202, 4203, 4204, 4206, 4214, 4218, 4232, 4235, 4244, 4247, 4251, 4252, 4410, 4411, 4412, 4414) | UGCS2019v0222.pdf |
| 03/20/19 | 4198, 4201, (4232 to FMO), 4306, 4354, 4647, 4650, 4660 | UGCS2019v0320.pdf |
| 04/19/19 | 3111, 3140, 3238, 3312, 4172, 4308, 4701, 4713, 4714 | UGCS2019v0419.pdf |
| 05/23/19 | 3376 | UGCS2019v0523.pdf |
| 06/13/19 | 3415 | UGCS2019v0613.pdf |
| 07/15/19 | 4308, 4601, 4649 | UGCS2019v0715.pdf |
| 08/19/19 | 4244, 4647 | UGCS2019v0819.pdf |
| 09/20/19 | 4201 | UGCS2019v0920.pdf |
| 10/25/19 | 4307, 4401, 4470, 4471 | UGCS2019v1025.pdf |
| 11/19/19 | 3316, 3405, 3483, 3522, (3551.1-.9 Removed Temporarily), 3752,4172.2, 4172.3, 4172.3A, 4235, 4354 | UGCS2019v1119.pdf |
| 12/20/19 | 4101, 4181, 4189, 4601, 4620, 4621, 4622, 4623, 4624, 4625, 4626 | UGCS2019v1220.pdf |
| 01/24/20 | COVER PAGE | UGCS2020v0124.pdf |
| 02/19/20 | 3518, 4301, 4344 | UGCS2020v0219.pdf |
| 03/20/20 | 3111, 3228, 3376, 4308, 4601, 4640, 4641, 4642, 4643, 4644, 4645, 4646, 4647, 4648, 4651, 4653, 4661, 5001, 5010, 5020, 5030, 5040, 5050,5060, 5070 | UGCS2020v0320.pdf |
| 04/24/20 | 3517, 4101, 4172, 4174, 4201, 4242, 4244, 4247, 4306, 4471 | UGCS2020v0424.pdf |
| 05/22/20 | 3315, 3373, INTERNAL SERVER UPGRADE | UGCS2020v0522.pdf |
| 06/19/20 | 4101, 4106, 4108, 4109, 4110, 4111, 4113, 4121, 4122, 4127, 4147, 4148, 4167, 4168, 4169, 4170, 4171, 4172, 4173, 4174, 4175, 4176, 4177, 4178, 4179, 4180, 4181, 4182, 4183, 4184, 4185, 4186, 4187, 4188, 4190, 4191, 4195, 4196, 4197, 4198 | UGCS2020v0619.pdf |
| 07/24/20 | 4101, (4411 to FMO) | UGCS2020v0724.pdf |
| 08/21/20 | 3646, 4205 | UGCS2020v0821.pdf |
| 09/25/20 | 4195 | UGCS2020v0925.pdf |
| 10/23/20 | 3701, (3720 to FMO), 4111, 4201, (4207 to FMO), 4252, 4301, 4302, 4305, 4306, 4307, 4309, 4310, 4311, 4312, 4313, 4314, 4344, 4352, 4354, 4355, 4359 | UGCS2020v1023.pdf |
| 10/28/20 | 3005 | UGCS2020v1028.pdf |
| 11/20/20 | 3316, 3365, 3374, 3401, 3405, 3408, 3409, 3410, 3414, 3415, 3416, 3417, 3418, 3419, 3421, 3423, 3425, 3426, 3427, 3428, 3429, 3478, 3479, 3480, 3481, 3482, 3483, 3484, 3485, 3486, 3487, 3488, 3489, 3649, 4101, 4192, 4240, 4649 | UGCS2020v1120.pdf |
| 12/18/20 | 3001, 3002, 3003, 4242 | UGCS2020v1218.pdf |
| 01/22/21 | COVER PAGE, DISCLAIMER, 3101, 3104, 3111, 3113, 3140, 3150, 3560 | UGCS2021v0122.pdf |
| 02/19/21 | 3201, 3202, 3203, 3204, 3211, 3212, 3213, 3214, 3215, 3216, 3217, 3218, 3221, 3225, 3230, 3232, 3233, 3234, 3238, 3239,3240, 4202, 4203, 4235, 4601, 4630 | UGCS2021v0219.pdf |
| 03/19/21 | 3309, 3680 | UGCS2021v0319.pdf |
| 05/21/21 | 3501, 3511, 3512, 3514, 3515, 3516, 3517, 3518, 3522, 3523, 3524, 3525, 3550, 3551, 3552, 3553, 3554, 3555, 3568, 3580, 3583, 3584, 3585, 3586, 3588, 3590, 3591, 4401, 4472 | UGCS2021v0521.pdf |
| 06/25/21 | 3301, 3365, 3366, 3703, 3801, 3815, 3821,4501, 4505, 4510, 4512, 4514, 4520, 4521, 4525, 4530, 4540, 4550 | UGCS2021v0625.pdf |
| 07/23/21 | 3675 | UGCS2021v0723.pdf |
| 08/20/21 | 3140, 3314, 3369, 3370, 3379, 3401, 3414, 3428, 3443, 3550, 3647, 4111, 4167, 4201, (4230 to FMO), 4251, 4301, 4360 | UGCS2021v0820.pdf |
| 09/24/21 | 3901, 3903, 3904, 3941, 3942, 3944, 3948, 3950, 3960, 4001, 4002, 4003, 4004, 4005, 4006, 4007, 4008, 4009, 4011, 4010, 4012, 4201,4204, 4206, 4214, 4218, 4240, 4244 | UGCS2021v0924.pdf |
| 10/22/21 | 3301, 3313, 3368, 4305, 4645 | UGCS2021v1022.pdf |
| 11/19/21 | 3301, 3302, 3303, 3304, 3305, 3306, 3308, 3310, 3311, 3315, 3316, 3317, 3325, 3326, 3327, 3332, 3360, 3361, 3362, 3363, 3364, 3367, 3371, 3372, 3373, 3375, 3376, 3377, 3378, 3382, 3383, 3390, 4701, 4705, 4710, 4712, 4713, 4714, 4720, 3821 | UGCS2021v1119.pdf |
| 12/17/21 | 3523, 3580, 4101, (4122 to FMO), 4174, (4183 to FMO), 4204 | UGCS2021v1217.pdf |
| 01/21/22 | 3601, 3605, 3644, 3645, 3648, 3649, 3660, 3669, 3670, 3671, 3672, 3677, 3678, 3679, 3680 | UGCS2022v0121.pdf |

**ARCHIVED BOOKS AVAILABLE ON THE INTERNAL VERSION**

MAIN TABLE OF CONTENTS

# SUMMARY OF CHANGES

| | | |
|---|---|---|
| 02/25/22 | 3372, 3518, 3646, 3702, 4002, 4101, (4113 to FMO), 4169, 4170, 4177, 4202, 4206, 4301, 4307, (4308 to FMO), 4401, 4405, 4410, 4412, 4413, 4414, 4422, 4423, 4424, 4430, 4431, 4432, 4433, 4434, 4435, 4470, 4471, 4473 | UGCS2022v0225.pdf |
| 03/25/22 | 3003, 3005, 3479, 4214, 4720 | UGCS2022v0325.pdf |
| 04/22/22 | 3002, 4218, 4630 | UGCS2022v0422.pdf |
| 05/20/22 | 4203, 4235, 4306 | UGCS2022v0520.pdf |
| 06/24/22 | 3517, 4001, (4009 REMOVED), 4110 | UGCS2022v0624.pdf |
| 07/22/22 | 3311, 3428, 3551, 3552, 3553, 3554, 3555, 3821, 4178, 4182, 4206, 4244, 4251, 4650 | UGCS2022v0722.pdf |
| 08/17/22 | 4651 | UGCS2022v0817.pdf |
| 09/23/22 | 4470, DISCLAIMER | UGCS2022v0923.pdf |
| 10/14/22 | 3501, (3525 to FMO), 3405, 4191, 4430, 4431 | UGCS2022v1014.pdf |
| 11/22/22 | 3369, 3421, 3517, 3713, 4004, 4186, 4240, 4306, 4312, 4645, 4646, 4647 | UGCS2022v1122.pdf |
| 01/20/23 | COVER PAGE, DISCLAIMER, 3111, 3313, 3314, 3315, 3316, 4182 | UGCS2023v0120.pdf |
| 02/07/23 | (4240 REVERTED TO PREVIOUS VERSION) | UGCS2023v0207.pdf |
| 03/24/23 | 3315, 3366, 3429, 4167, 4244, 4434, 4471, 4601, 4641 | UGCS2023v0324.pdf |
| 04/21/23 | 3360, 3518, 4198, 4310, 4360 | UGCS2023v0421.pdf |
| 05/19/23 | 3104, 3140, 3238, 3301, (3383 to FMO), 3567, 4630 | UGCS2023v0519.pdf |

MAIN TABLE OF CONTENTS

**ARCHIVED BOOKS AVAILABLE ON THE INTERNAL VERSION**

# UNDERGROUND CONSTRUCTION STANDARDS


**3000 General Information**
Construction Standards Request form and Procedure. Deviation Request Form.

**3100 Practices**
Switch Numbering, Structure Numbering. GFIS Maps Electric Conduit Field Mapping

**3200 Identification**
Pull String, Communication Conduit, Transformer, Fuse and Conduit Identification. Decals and Tags.

**3300 Substructures, Conduits**
Handholes, Manholes, False Curbs. Sump Pumps, Trenching and Backfills. Conduit Installation and Stub Markers.

**3400 Pads, Retaining Walls, Clearances**
Pads, Box Pads Masonry Retaining Walls, Clearance Requirements for Pad-mounted and subsurface equipment, Sound Enclosures.

**3500 Pad Mounted/Wall Mounted Sectionalizing Equipment**
Single and Three Phase Fuse Cabinets, Single and Three Phase Terminators, Cable Junction Pedestal, PME Air Break Switchgear, Vista Gas Insulated Vacuum Switchgear - SCADA and Manual, and Trayer Oil Insulated Vacuum Switchgear - SCADA and Manual.

**3600 Subsurface Sectionalizing Equipment**
Substructure Use and Limitations Reference Sheet, Unobstructed Space, Cable and Connector Placement, Equipment Assemblies, Vista Gas Insulated Vacuum Switchgear, and G&W Gas Insulated Switchgear.

**3700 Transformers**
Single and Three Phase Transformers, Bay-o-net Fuses, XD Transformers

**3800 Capacitors**
Pad-Mounted Capacitors

**3900 Secondaries/Services**
Cathodic Protection Station, Secondary Test Procedure, Services, Sealing Service Lateral Conduit Instructions.


MAIN TABLE OF CONTENTS

## 4000 Cables

Six Hundred Volt Cable Sizes, 12kV Cable Sizes, Minimum Bending Radius for Underground Cables, Cable Pulling Eyes.

## 4100 Terminations, Splicing Connections

Cable End Seals, Outdoor Cable Terminals for Polyethylene Cable, Transition Module, Stacking Adaptors, Slip-Fit Connectors, 200A Dead Break and Loadbreak, 600A Elbow Tees, Cam-Link Connectors, 600A CLEER Cable Tap.

## 4200 Cable Poles

Joint Cable Pole Riser Positions, Pole Quadrant and Riser Identification, Underground Service from an Overhead Line, 12.47kV Cable Poles.

## 4300 Fuses, Fault Indicators

Fuse Application Guide, Primary Current-Limiting Fuse Installation, Electronic Sectionalizer, Current Limiting to SM-4 Conversion for PME Switch, Transformer Fusing Table, Fault Indicator Installation.

## 4400 Lighting

High Intensity Discharge Lamps, Replacement Refractors, High and Low-Pressure Sodium Vapor Luminaires, Walk Way Lighting, Direct Burial Pole Installation.

MAIN TABLE OF CONTENTS

## 4500 Grounding

Trench Ground Wire, Equipment Grounding, Grounding Telco Conductors in Pad-Mounted Equipment, Neutral and Ground Wire Schematic Diagram.

## 4600 Telecommunications, SCADA

Telecommunications Splicing Pedestal, Conduit Trenches and Riser, Pulling Grips, Handhole Installation for Locating Stations for Fiber Optic Cable. Pad-Mounted vista SCADA installation, PME SCADA installation, Subsurface Vista Installation. Antenna Poles.

## 4700 Miscellaneous Equipment

Padmounted Voltage Regulation. Misc Equipment

## 4800 Vault Standards

Electric Vault Requirements & Specification.

| PAGE | SUBJECT |
|---|---|
| 3002 | PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY |
| 3003 | STANDARD PAGE FORMAT |
| 3005 | DEVIATION REQUEST FORM AND PROCEDURE |

MAIN TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 12/7/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | JS | MDJ | 5/1/2018 | D | | | | | | |

TABLE OF CONTENTS

**SCOPE:** TO PROVIDE GUIDELINES FOR ACCOMMODATING THE NEEDS OF ALL PEDESTRIANS INCLUDING THOSE WITH MOBILITY, VISUAL OR HEARING DISABILITIES, AT WORKSITES THAT ENCROACH UPON A SIDEWALK, WALKWAY OR CROSSWALK.

**DEFINITIONS:**

- **ALTERNATE CIRCULATION PATH:** A TEMPORARY ROUTE OR DETOUR PROVIDED AS A SUBSTITUTE FOR THE NORMAL PEDESTRIAN ACCESS ROUTE.
- **BARRICADE:** AN OBSTRUCTION TO DETER THE PASSAGE OF PERSONS OR VEHICLES.
- **CONTRAST:** LIGHT-VERSUS-DARK COMPARISON BETWEEN TWO SURFACES, AN OBJECT AND ITS IMMEDIATE SURROUNDINGS, OR, AN OBJECT AND ITS PERCEIVED BACKGROUND. IT IS NEITHER AN EXPRESSION OF, NOR NECESSARILY ACHIEVED BY, COLOR DIFFERENCES.
- **CROSS-SLOPE:** THE SLOPE OR GRADE OF A SURFACE PERPENDICULAR TO THE RUNNING GRADE.
- **CROSSWALK:** THAT PART OF A ROADWAY WHERE MOTORISTS ARE REQUIRED TO YIELD TO PEDESTRIANS CROSSING, AS DEFINED BY STATE AND LOCAL REGULATIONS, WHETHER MARKED OR UNMARKED.
- **CURB LINE:** A LINE THAT REPRESENTS THE EXTENSION OF THE FACE OF THE CURB AND MARKS THE TRANSITION BETWEEN THE PUBLIC SIDEWALK AND THE GUTTER OR ROADWAY AT A CURB RAMP OR FLUSH LANDING.
- **CURB RAMP:** A SHORT SECTION OF THE PEDESTRIAN ACCESS ROUTE, WITH A RUNNING GRADE GREATER THAN 1:20 (5%) JOINING THE STREET ELEVATION TO THE PUBLIC SIDEWALK ELEVATION THROUGH A CUT IN THE CURB FACE.
- **DETECTABLE WARNING:** A SPECIFIED SURFACE TREATMENT FOR IMPROVED SURFACES THAT CAN BE DETECTED BY MOST PEDESTRIANS WHO USE A LONG CANE FOR NAVIGATION.
- **DRIVEWAY:** A PRIVATE VEHICULAR WAY GIVING ACCESS FROM A PUBLIC RIGHT-OF-WAY TO ADJACENT PROPERTY.
- **FIXTURE:** A FIXED ELEMENT IN THE PUBLIC RIGHT-OF-WAY THAT IS NOT INTENDED FOR PUBLIC USE AND DOES NOT REQUIRE CLEAR GROUND SPACE FOR APPROACH OR USE, SUCH AS A STREET LIGHTING POLE, FIRE HYDRANT OR SIGNAL CONTROLLER CABINET.
- **FLUSH:** WHEN TWO PORTIONS OF PUBLIC SIDEWALK AND/OR ROADWAY JOIN, WITHOUT VERTICAL SEPARATION OR LIP.
- **GRADE:** THE RATE OF ASCENT OR DESCENT OF A SURFACE WITH RESPECT TO A LEVEL PLANE, EXPRESSED AS A PERCENT; THE CHANGE IN ELEVATION PER UNIT OF HORIZONTAL LENGTH.
- **HANDRAIL:** A FIXED CONTINUOUS ELEMENT AT A SPECIFIED HEIGHT PROVIDED FOR PEDESTRIAN USE WHERE THERE IS A CHANGE OF ELEVATION, SUCH AS RAMPS, STAIRS, AND LANDINGS.
- **IMPROVED SURFACE:** AN AREA THAT, BY THE ADDITION OF MATERIALS OR ITS TREATMENT, PROVIDES A FIRM, STABLE AND SLIP-RESISTANT BASE FOR PEDESTRIAN MOVEMENT. EXAMPLES OF SUCH MATERIALS INCLUDE ASPHALT CONCRETE PAVING, PORTLAND-CEMENT CONCRETE PAVING, STONE, CERAMICS, WOOD, METAL, FIBERGLASS OR OTHER GENERALLY FIRM AND STABLE MATERIAL. SURFACES THAT HAVE ONLY FIRMLY PACKED EARTH, GRAVEL BASE, GRAVEL, VEGETATION, WOOD CHIPS, SHELLS OR OTHER MALLEABLE MATERIAL ARE NOT CONSIDERED, FOR THE PURPOSE OF THIS DEFINITION, TO BE IMPROVED SURFACES.
- **LANDING:** A LEVEL AREA WITH A CROSS-SLOPE OF LESS THAN 1:48 (2%) IN ANY DIRECTION ALONG A PUBLIC SIDEWALK, TRANSITION RAMP, CURB RAMP OR RAMP, USED FOR MANEUVERING OR WAITING.
- **MUTCD:** MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, CURRENT EDITION, AS APPROVED BY THE STATE OF CALIFORNIA-DEPARTMENT OF TRANSPORTATION.
- **PEDESTRIAN:** A PERSON TRAVELING THE PUBLIC RIGHT-OF-WAY BY MEANS OF A WHEELCHAIR, ELECTRIC SCOOTER, LEGS, CRUTCHES OR OTHER WALKING DEVICES OR MOBILITY AIDS.
- **PEDESTRIAN ACCESS ROUTE (PAR):** A CORRIDOR OF ACCESSIBLE TRAVEL THROUGH THE PUBLIC RIGHT-OF-WAY THAT HAS, AMONG OTHER PROPERTIES, A SPECIFIED MINIMUM WIDTH AND CROSS-SLOPE.
- **PEDESTRIAN CONTROL PLAN:** AN ON-SITE, TEXT, OR GRAPHIC DESIGN, LAYOUT, OR PLAN THAT PROVIDES FOR THE PROPER USAGE OF ALL PEDESTRIAN ACCESS ROUTES THROUGH OR AROUND A WORKSITE, INCLUDING TEMPORARY PATHS OF TRAVEL, CURB RAMPS, BARRICADES, SIGNS, AND OTHER DEVICES PLACED ON A STREET, SIDEWALK OR WALKWAY. THE PEDESTRIAN CONTROL PLAN MAY DEPICT AN AREA OR WORK ZONE TO BE USED FOR THE FACILITATION OF PEDESTRIAN TRAFFIC THROUGH A TEMPORARY TRAFFIC CONTROL ZONE, AND MAY BE USED IN CONJUNCTION WITH A TRAFFIC CONTROL PLAN.
- **PROJECT AREA:** THE ENTIRE WIDTH OF THE PUBLIC RIGHT-OF-WAY THROUGHOUT THE LENGTH UPON WHICH WORK IS PROPOSED OR UNDERTAKEN. PROJECT AREA MAY CONSIST OF A SINGLE ROUTE OR MULTIPLE ROUTES.
- **PUBLIC RIGHT-OF-WAY:** LAND, PROPERTY, OR INTEREST THEREIN, USUALLY IN A CORRIDOR, ACQUIRED FOR OR DEVOTED TO TRANSPORTATION PURPOSES AND SUBJECT TO THE CONTROL OF A PUBLIC AGENCY.
- **RAILING:** A BARRIER LOCATED NEAR THE OPEN SIDES OF ELEVATED WALKING SURFACES TO MINIMIZE THE POSSIBILITY OF AN ACCIDENTAL FALL OR SLIP FROM THE WALKING SURFACE TO THE LOWER LEVEL.
- **RUNNING GRADE:** THE GRADE THAT IS PARALLEL TO THE DIRECTION OF TRAVEL.
- **SIDEWALK:** THAT PORTION OF A PUBLIC RIGHT-OF-WAY BETWEEN THE BACK OF THE CURB LINE OR LATERAL LINE OF A ROADWAY AND THE ADJACENT PROPERTY LINE, THAT IS DEFINED BY AN IMPROVED SURFACE AND INTENDED FOR USE BY PEDESTRIANS.
- **SIDEWALK/STREET TRANSITION:** THE TRANSITION BETWEEN THE PUBLIC SIDEWALK AND A MARKED CROSSWALK OR INTENDED STREET CROSSING, MEDIAN REFUGE, ISLAND, OR OTHER LOCATION WHERE A PEDESTRIAN ACCESS ROUTE CROSSES OR ENTERS THE ROADWAY OR A DRIVEWAY.
- **SIGN:** ANY PEDESTRIAN OR TRAFFIC CONTROL DEVICE THAT COMMUNICATES INFORMATION TO PEDESTRIANS OR ROAD USERS THROUGH A WORD OR SYMBOL LEGEND. SIGNS DO NOT INCLUDE TRAFFIC CONTROL SIGNALS, PAVEMENT MARKINGS, DELINEATORS, OR CHANNELIZATION DEVICES.
- **WORKSITE OR ZONE:** AN AREA OF A PUBLIC RIGHT-OF-WAY WITH CONSTRUCTION, MAINTENANCE OR UTILITY WORK ACTIVITIES. IT MAY CONSIST OF A SINGLE ROUTE OR MULTIPLE ROUTES, AND INCLUDES THE ENTIRE WIDTH OF THE PUBLIC RIGHT-OF-WAY THROUGHOUT THE LENGTH UPON WHICH WORK IS PROPOSED OR UNDERTAKEN.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**POLICY**:

I. ALL WORKSITES THAT ENCROACH UPON A SIDEWALK, WALKWAY OR CROSSWALK SHALL ACCOMMODATE THE NEEDS OF ALL PEDESTRIANS. SPECIAL CONSIDERATION SHALL BE GIVEN TO ACCESSIBILITY FOR PERSONS WITH DISABILITIES, INCLUDING THOSE WHO USE WHEELCHAIRS OR OTHER MOBILITY DEVICES, WHO ARE BLIND OR VISUALLY IMPAIRED OR WHO ARE DEAF OR HARD OF HEARING.

II. PEDESTRIAN SAFETY AND ACCESSIBILITY CONSIDERATIONS, INCLUDING CONSIDERATION OF NECESSARY EQUIPMENT TO CREATE A SAFE AND ACCESSIBLE PATH OF TRAVEL AROUND THE WORKSITE, SHALL BE INCLUDED DURING WORKSITE PLANNING ASSESSMENTS.

III. PEDESTRIANS SHALL HAVE A SMOOTH, CLEARLY DELINEATED PATH OF TRAVEL THROUGH OR AROUND A WORK AREA UNTIL A PROJECT IS COMPLETED AND SHALL BE PROTECTED FROM POTENTIAL INJURY CAUSED BY ELECTRIC CONSTRUCTION WORK.

**RESPONSIBILITIES**:

IV. CONSTRUCTION AND OPERATIONS AND MAINTENANCE AND OPERATIONS DISTRICTS ARE RESPONSIBLE FOR COMPLIANCE AND IMPLEMENTATION OF THIS STANDARD AND ITS ASSOCIATED STANDARDS AND/OR ELECTRIC STANDARD PRACTICES AS THEY RELATE TO PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY.

V. EMPLOYEES ARE RESPONSIBLE FOR ADHERENCE TO STANDARDS, GUIDELINES, ELECTRIC STANDARD PRACTICES, AND POLICIES AND PROCEDURES WHILE PERFORMING ALL DUTIES.

**GENERAL DESCRIPTION OF REQUIREMENTS**:

VI. THIS STANDARD IS DESIGNED TO ENSURE THE PROVISION OF ONE OR MORE TEMPORARY, ACCESSIBLE PATHS OF TRAVEL AROUND THE WORKSITE, FOR ALL DISRUPTED SURFACES WITHIN THE SCOPE OF THE PROJECT. THIS PROCEDURE APPLIES TO ALL WORKSITES WHERE THE WORK AREA ENCROACHES UPON A DESIGNATED PUBLIC RIGHT-OF-WAY PEDESTRIAN PATH OF TRAVEL (SIDEWALK, WALKWAY OR CROSSWALK AREA).

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | ARC | JIK | - | - | 4/12/2022 |
| C | FORMATTING | EDM | JIK | - | - | 12/7/2020 |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/17/2018 |

SDG&E

A Sempra Energy utility®

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY**

SCALE: NOT TO SCALE

DRAWING NO: OH102.1 UG3002.1



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS

**NOTES (CONT'D):**

VII. EMPLOYEES WORKING ON A SIDEWALK THAT ARE UNABLE TO PROVIDE A SUITABLE AND PROTECTED 48-INCH WIDE PEDESTRIAN PATH OF TRAVEL ON THE SIDEWALK, SHALL ENSURE A SAFE AND ACCESSIBLE PATH OF TRAVEL FOR PEDESTRIANS AROUND THE WORKSITE, OR CLOSE THE SIDEWALK TO ALL TRAFFIC AND DIRECT ALL PEDESTRIANS TO AN ALTERNATE CIRCULATION PATH.

VIII. IMPROVEMENTS WITHIN A WORKSITE IN THE PUBLIC RIGHT-OF-WAY THAT ARE REMOVED OR DISTURBED DURING THE COMPANY'S ACTIVITIES AT THE SITE, SHALL BE REPLACED WITH CONSTRUCTION THAT MEETS THE ACCESSIBILITY REQUIREMENTS AS DESCRIBED IN THESE GUIDELINES.

**PEDESTRIAN CONTROL PLANS FOR TEMPORARY MAINTENANCE AND CONSTRUCTION PROJECTS:**

(IX) EVERY WORKSITE OR ZONE WHERE THE NORMAL PEDESTRIAN PATH OF TRAVEL IS INTERRUPTED, BLOCKED, LOCATED DIRECTLY ADJACENT TO A WORK AREA OR OTHERWISE IMPACTED BY THE WORK, SHALL HAVE AT LEAST ONE, AND POTENTIALLY SEVERAL, TEMPORARY AND ACCESSIBLE PATHS OF TRAVEL PROVIDED. WHERE THE AUTHORITY HAVING JURISDICTION DICTATES SPECIFIC REQUIREMENTS, THE COMPANY SHALL PERFORM ITS CONSTRUCTION IN COMPLIANCE WITH THAT AUTHORITY. IN SITUATIONS WHERE THE AUTHORITY HAVING JURISDICTION HAS SPECIFIED REQUIREMENTS WHICH PROVIDE LESS ACCESS THAN THE REQUIREMENTS IN THIS SECTION, THE COMPANY SHALL USE THE REQUIREMENTS IN THIS SECTION WHICH PROVIDE MORE ACCESS, UNLESS THE AUTHORITY HAVING JURISDICTION EXPLICITLY CONTRADICTS OUR REQUIREMENTS.

a. **PEDESTRIAN CONTROL PLAN:** AN APPROPRIATELY DETAILED PEDESTRIAN CONTROL PLAN SHALL BE FORMULATED AND IMPLEMENTED PRIOR TO ANY WORK BEING UNDERTAKEN AT THE WORKSITE.

b. **MAJOR CONSIDERATIONS:** THE MAJOR CONSIDERATIONS IN PLANNING FOR PEDESTRIAN ACCESS IN TEMPORARY PEDESTRIAN CONTROL ZONES WITHIN THE PUBLIC RIGHT-OF-WAY ARE AS FOLLOWS:

PEDESTRIANS SHALL NOT BE LED INTO CONFLICTS WITH WORKSITE VEHICLES, EQUIPMENT, EXCAVATIONS OR OTHER OPERATIONS.

PEDESTRIANS SHALL NOT BE LED INTO CONFLICTS WITH VEHICULAR TRAFFIC.

PEDESTRIANS SHALL BE PROVIDED WITH A CONVENIENT, SAFE, AND ACCESSIBLE PATH OF TRAVEL THAT REPLICATES, AS NEARLY AS POSSIBLE, THE MOST DESIRABLE CHARACTERISTICS OF EXISTING SIDEWALKS OR WALKWAYS IN THE AREA.

PEDESTRIANS SHALL BE INFORMED OF CHANGES IN THE TRAVEL PATH IN A MANNER THAT IS READILY UNDERSTANDABLE.

c. **EXCEPTIONS**: THE FOLLOWING TYPES OF TEMPORARY MAINTENANCE AND CONSTRUCTION WORK AND WORKSITES ARE EXCLUDED:

WORKSITES THAT ARE TO BE USED SHORT TERM, DEFINED AS BEING FOUR HOURS OR LESS.

WORKSITES THAT ARE REQUIRED FOR THE RESOLUTION OF PROBLEMS CAUSED BY AN EMERGENCY, NATURAL DISASTER, SUBSTANTIAL ACCIDENT OR SIMILAR UNUSUAL OR EXTREME CONDITIONS WHERE PROTECTION OF THE HEALTH AND SAFETY OF THE PUBLIC SUPERSEDES ANY OTHER CONSIDERATIONS. SUCH CONDITIONS SHALL NOT EXCEED A DURATION OF ONE WEEK.

(X) THIS ITEM IS EXEMPT.

(XI) **ALTERNATE CIRCULATION PATHS:**

AN ALTERNATE CIRCULATION PATH SHALL BE PROVIDED WHENEVER THE NORMAL PEDESTRIAN ACCESS ROUTE IN THE PUBLIC RIGHT-OF-WAY IS BLOCKED OR ALTERED BY CONSTRUCTION, ALTERATION, MAINTENANCE OR OTHER TEMPORARY CONDITIONS.

a. **LOCATION:** WHERE FEASIBLE, THE ALTERNATE CIRCULATION PATH SHALL PARALLEL THE DISRUPTED PEDESTRIAN ACCESS ROUTE ON THE SAME SIDE OF THE STREET. SIDEWALK CLOSURES TO ALL PEDESTRIAN TRAFFIC SHOULD ONLY OCCUR WHERE A SAFE PASSAGE FOR ALL PEDESTRIANS AROUND THE WORKSITE CANNOT BE ESTABLISHED.

b. **ALTERNATE CIRCULATION PATH PROTECTION:** THE ALTERNATE CIRCULATION PATH SHALL NOT HAVE ABRUPT CHANGES IN GRADE, ELEVATION OR TERRAIN. THE ALTERNATE CIRCULATION PATH SHALL HAVE NO PROTRUSIONS UP TO A HEIGHT OF 80 INCHES, INCLUDING SCAFFOLDING AND SCAFFOLDING BRACES. WHEN OVERHEAD WORK IS CONDUCTED, THE PEDESTRIAN PASSAGE AREA BELOW SHALL BE PROTECTED OR REROUTED. WHERE THE ALTERNATE CIRCULATION PATH IS ADJACENT TO HAZARDOUS CONDITIONS, THE PATH SHALL BE PROTECTED WITH A BARRICADE, CONSISTENT WITH THE REQUIREMENTS DESCRIBED IN THIS STANDARD. MOVEMENT BY WORK VEHICLES AND EQUIPMENT ACROSS AN ALTERNATE CIRCULATION PATH SHOULD BE AVOIDED WHENEVER POSSIBLE. IF VEHICLES AND EQUIPMENT NEED TO TRAVEL ACROSS AN ALTERNATE CIRCULATION PATH, EMPLOYEES SHALL USE FLAGGERS OR EQUAL METHODS TO DIRECT VEHICULAR TRAFFIC.

c. **TEMPORARY FACILITIES:** TEMPORARY FACILITIES IN THE PUBLIC RIGHT-OF-WAY, INCLUDING TEMPORARY WALKING SURFACES, CURB RAMPS, AND SIMILAR FEATURES, SHALL CONFORM TO THE ACCESSIBILITY REQUIREMENTS FOR NEW OR REPLACEMENT CONSTRUCTION, EXCEPT AS DESCRIBED IN THIS SECTION.(XVI)(XVII)(XVIII)(XIX)

d. **PROHIBITED REDUCTION IN ACCESSIBILITY:** TEMPORARY FACILITIES SHALL NOT HAVE AN EFFECT THAT DECREASES THE ACCESSIBILITY OF AN EXISTING PUBLIC RIGHT-OF-WAY OR SITE ARRIVAL POINTS TO BUILDINGS OR FACILITIES ADJACENT TO THE ALTERED PORTION OF THE PUBLIC RIGHT-OF-WAY. HOWEVER, WHERE ACCESSIBLE PEDESTRIAN FACILITIES DO NOT EXIST OR ARE DEFICIENT, TEMPORARY FACILITIES ARE NOT REQUIRED TO BE PROVIDED IN EXCESS OF THE DEGREE OF ACCESSIBILITY PRESENT PRIOR TO THE BEGINNING OF THE WORK.

e. **WORKSITE CONDITIONS:** TOOLS, EQUIPMENT OR MATERIALS MAY NOT BE STORED WITHIN THE ALTERNATE CIRCULATION PATH. HEAVY EQUIPMENT WITH PROTRUDING PARTS SHALL NOT BE LOCATED IN OR PROJECTED INTO THE PATH OF TRAVEL. DEBRIS SHOULD BE REMOVED FROM ALL TEMPORARY PATHS OF TRAVEL, AND SUCH AREAS SHALL BE PROPERLY DRAINED.

(XII) **DESIGN REQUIREMENTS FOR SIDEWALKS AND PEDESTRIAN PATHS OF TRAVEL:**

a. **SURFACES:** EACH PART OF THE UNALTERED PATH OF TRAVEL OR THE ALTERNATE CIRCULATION PATH SHALL BE AN "IMPROVED SURFACE" THAT IS FIRM, STABLE, AND SLIP-RESISTANT. SEE DEFINITIONS.

b. **CLEAR WIDTH:** EACH PART OF THE UNALTERED PATH OF TRAVEL OR THE ALTERNATE CIRCULATION PATH SHALL BE AT LEAST FOUR FEET (48 INCHES) WIDE.

**EXCEPTION 1:** THE CLEAR WIDTH NEED NOT BE WIDER THAN THE EXISTING CLEAR WIDTH OF THE IMPROVED SURFACE OF THE SIDEWALK OR WALKWAY.

**EXCEPTION 2:** THE CLEAR WIDTH MAY BE REDUCED TO 36 INCHES FOR A DISTANCE OF 48 INCHES.

**EXCEPTION 3:** THE CLEAR WIDTH MAY BE REDUCED TO 36 INCHES IF UNUSUAL SITE CONSTRAINTS (SUCH AS PERMANENT FENCES OR REDUCED RIGHT-OF-WAY WIDTH) PRECLUDE AN EFFECTIVE METHOD FOR PROVIDING THE FULL WIDTH, BUT IN NO CASE SHALL THE DISTANCE OF SUCH REDUCTION BE MORE THAN 20 FEET.

c. SLOPES AND CROSS-SLOPES OF THE ALTERNATE CIRCULATION PATH SHALL NOT EXCEED 5% OR 2%, RESPECTIVELY.

d. **CHANGES IN LEVEL**: CHANGES IN LEVEL IN THE UNALTERED PATH OF TRAVEL OR THE ALTERNATE CIRCULATION PATH SHALL NOT EXCEED 1/2-INCH VERTICAL. A 1/4-INCH VERTICAL CHANGE IN LEVEL MAY BE MADE WITHOUT PROVISIONS FOR BEVELING THE LIP OF THE CHANGE. CHANGES BETWEEN 1/4-INCH AND 1/2-INCH MUST BE BEVELED AT A 1:2 RATIO.

e. **PEDESTRIAN TRAFFIC PLATES:** WORKSITE TRENCHES OR EXCAVATIONS MAY BE BRIDGED WITH STURDY PLYWOOD OR METAL PLATES AS LONG AS THE SURFACE IS CONTINUOUS AND STABLE, WITH NO GAPS OR CHANGES IN LEVEL, INCLUDING LIP EDGES FACING THE PATH OF TRAVEL, GREATER THAN 1/2-INCH. A 1/4-INCH VERTICAL CHANGE IN LEVEL MAY BE MADE WITHOUT PROVISIONS FOR BEVELING THE LIP OF THE CHANGE. CHANGES BETWEEN 1/4-INCH AND 1/2-INCH MUST BE BEVELED AT A 1:2 RATIO. TRENCH PLATES SHALL BE USED WITH AN APPROPRIATE AMOUNT OF COLD MIX PACK OR SIMILAR MATERIALS TO PROVIDE A SMOOTH TRANSITION FROM THE SIDEWALK OR STREET TO THE PLATE. IF PLATES HAVE THE POTENTIAL TO MOVE AND CAUSE A HAZARD, THEY MAY BE RECESSED INTO THE WALKWAY. OTHER METHODS SUCH AS EXPANSION BOLTS MAY ALSO BE USED TO PREVENT PLATE MOVEMENT. BEVELED EDGES OR FEATHERED/COMPACTED ASPHALT OR CONCRETE SHALL BE PROVIDED AT A BEVEL OF ONE VERTICAL TO TWO HORIZONTAL. IF METAL TRENCH PLATES IN THE PATH OF TRAVEL HAVE "LIFT HOLES" TO ALLOW A CHAIN WITH A HOOK TO MOVE THE PLATES, SUCH HOLES SHALL BE PLUGGED WITH MATERIAL SUCH AS WOOD OR PLASTIC PLUGS TO FILL IN THE LIFT HOLES AND AVOID CREATING A TRIPPING HAZARD.

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | ARC | JIK | - | - | 4/12/2022 |
| C | FORMATTING | EDM | JIK | - | - | 12/7/2020 |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/17/2018 |

SDG&E A Sempra Energy utility

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY**

SCALE: NOT TO SCALE

DRAWING NO: OH102.2 UG3002.2

SHEET: 2 OF 4

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS

**NOTES (CONT'D):**

(XIII) **DESIGN REQUIREMENTS FOR TEMPORARY CURB RAMPS:**

a. TEMPORARY CURB RAMPS SHALL BE USED WHEN PEDESTRIANS ARE DIVERTED OFF THE SIDEWALK OR WALKWAY INTO THE STREET ADJACENT TO THE WORKSITE. CURB RAMPS SHALL PROVIDE ALL PEDESTRIANS ADEQUATE TRANSITION FROM THE SIDEWALK INTO THE STREET AND BACK ONTO THE SIDEWALK.

b. TEMPORARY CURB RAMPS SHALL BE A MINIMUM OF 48 INCHES WIDE. CURB RAMPS SHALL HAVE A MAXIMUM RUNNING SLOPE OF 1:12 (ONE FOOT RUN FOR EVERY INCH OF THE CURB) OR 8.33%. ALL CURB RAMPS MUST HAVE SMOOTH ON AND OFF TRANSITIONS AT THE TOP AND BOTTOM. CURB RAMPS SHALL BE LOCATED SO THAT THEY DO NOT PROJECT INTO VEHICULAR TRAFFIC LANES OR CAUSE PEDESTRIANS TO ENTER OR EXIT INTO TRAFFIC LANES. RAISED CURB RAMPS SHALL HAVE "CURBING" AT LEAST TWO-INCH HIGH AROUND ANY OPEN SIDES TO PREVENT AGAINST FALLING HAZARDS. TEMPORARY CURB RAMPS DO NOT REQUIRE THE USE OF DETECTABLE WARNINGS.

c. TEMPORARY CURB RAMPS MAY BE ANY OF THE THREE FOLLOWING TYPES:

**PREFABRICATED METAL RAMPS AND LANDINGS:** STANDARD METAL CURB RAMPS PROVIDED BY THE COMPANY, INCLUDING A FIVE-FOOT BY FIVE-FOOT LANDING WITH ADJUSTABLE "FEET" AND WITH A TWO-INCH HIGH CURB AT THE BACK AND SIDE, A FOUR-FOOT WIDE ADJUSTABLE SLOPING RAMP SECTION, WITH ADJUSTABLE BOTTOM TRANSITION PLATE AND A TWO-INCH HIGH CURB AT EACH SIDE, AND METAL RAILINGS AT THE SIDE OF THE LANDING AND SLOPING RAMP. (a)

**SITE CONSTRUCTED RAMPS:** CURB RAMPS CONSTRUCTED FROM ONE-INCH OR THICKER PLYWOOD, WITH TWO-INCH HIGH WOOD CURBING, AND WITH THE BOTTOM BEVELED TO CONFORM TO THE STREET SURFACE. (b)

**EXISTING DRIVEWAYS** MAY BE UTILIZED FOR CURB RAMPS UNDER THE FOLLOWING CONDITIONS:

THE DRIVEWAY SLOPE DOES NOT EXCEED 1:10 (10%)

A 1.5-INCH WIDE X ONE-INCH HIGH X FOUR-FOOT LONG METAL OR WOOD WEDGE IS POSITIONED AT THE BOTTOM OF THE DRIVEWAY RAMP,

FOR COMMERCIAL DRIVEWAYS WIDE ENOUGH TO PROVIDE FOR SAFE IN AND OUT VEHICULAR TRAFFIC, A FOUR-FOOT PORTION OF THE DRIVEWAY IS BARRICADED FROM VEHICULAR USE.

FOR RESIDENTIAL DRIVEWAYS, EITHER A FOUR-FOOT PORTION OF THE DRIVEWAY IS BARRICADED FROM VEHICULAR USE AND THE DRIVEWAY CLOSED TO ALL VEHICULAR USE, OR THE VEHICULAR TRAFFIC ACROSS THE DRIVEWAY IS CONTINUOUSLY MONITORED BY WORKERS.

(XIV) **DESIGN REQUIREMENTS FOR BARRICADES:**

a. BARRICADES SHALL BE PROVIDED AT THE FOLLOWING LOCATIONS:

BETWEEN THE EXISTING PEDESTRIAN ACCESS ROUTE, IF UNALTERED, AND ANY ADJACENT WORKSITE OR ZONE,

BETWEEN AN ALTERNATE CIRCULATION PATH AND ANY ADJACENT WORKSITE OR ZONE,

BETWEEN AN ALTERNATE CIRCULATION PATH AND THE VEHICULAR WAY, IF THE ALTERNATE CIRCULATION PATH IS DIVERTED INTO THE STREET,

BETWEEN AN ALTERNATE CIRCULATION PATH AND ANY PROTRUDING OBJECTS, DROP-OFFS OR OTHER HAZARDS TO PEDESTRIANS.

b. **VEHICULAR BARRICADES:** BARRICADES SUCH AS K-RAILS OR SIMILAR SOLID RAILINGS SHALL BE USED TO SEPARATE VEHICULAR TRAFFIC AND THE ALTERNATE PEDESTRIAN ROUTE IN AREAS WHERE THE VOLUME AND SPEED OF VEHICULAR TRAFFIC IS HIGH. SUCH BARRICADES SHALL HAVE SUFFICIENT STRENGTH AND LOW DEFLECTION CHARACTERISTICS TO KEEP VEHICLES FROM INTRUDING INTO THE ALTERNATE PEDESTRIAN ROUTE OR WORKSITES. SHORT, NON-CONTINUOUS SEGMENTS SHOULD BE AVOIDED, AS THEY INCREASE THE POTENTIAL FOR INJURY TO BOTH VEHICLE OCCUPANTS AND PEDESTRIANS, AND PRESENT BLUNT LEADING ENDS. WHEN USING SUCH BARRICADES, ADJACENT SEGMENTS SHOULD BE CONTINUOUS AND PROPERLY JOINED.

c. **PEDESTRIAN BARRICADES:** A BARRICADE AT THE EXISTING PEDESTRIAN ACCESS ROUTE OR THE ALTERNATE CIRCULATION PATH SHALL BE CONTINUOUS, STABLE AND NON-FLEXIBLE. A BARRICADE CAN BE ANY MATERIAL THAT PROTECTS PEDESTRIANS WITHOUT MATERIALLY IMPAIRING THE PEDESTRIAN PATH OF TRAVEL. IT SHALL HAVE A SOLID TOE RAIL WITH ITS TOP EDGE AT SIX INCHES MINIMUM IN HEIGHT AND ITS BOTTOM EDGE NO HIGHER THAN 1.5 INCHES OFF THE ADJACENT SURFACE. IT SHALL HAVE A CONTINUOUS TOP RAILING MOUNTED AT A HEIGHT OF 36 TO 42 INCHES. BASES SHALL BE USED AT EACH END OF EACH BARRICADE AND TAPED OR TIED AT THE TOP TO PROVIDE PROPER SUPPORT AND STABILITY.

**CAUTION:**

* TAPE ALONE WOULD NOT PROVIDE AN ADEQUATE BARRICADE AND SHOULD NOT BE USED TO DELINEATE THE ALTERNATE CIRCULATION PATH.

** CONES OR UNCONNECTED "A-FRAMES" OR CONNECTED A-FRAMES WITHOUT A HANDRAIL AND TOE RAIL SHOULD NOT BE USED TO DIRECT PEDESTRIAN TRAFFIC. NO BARRIER SUPPORT MEMBER SHALL PROTRUDE MORE THAN FOUR INCHES BEYOND THE TOP RAIL INTO THE ALTERNATE CIRCULATION PATH.

**EXCEPTION 1:** BARRICADES SHALL NOT BE REQUIRED WHERE THE WORKSITE OR ALTERNATE CIRCULATION PATH IS ENCLOSED WITH A SOLID FENCE OR WALL.

**EXCEPTION 2:** BARRICADES SHALL NOT BE REQUIRED WHEN THE WORKSITE OR ZONE REQUIRES ONLY THE USE OF HAND TOOLS AND NO HOLES OR EXCAVATIONS AS LONG AS WORKERS ARE PRESENT TO MONITOR AND ASSIST ANY PEDESTRIAN TRAFFIC.

(XV) **WARNINGS AND SIGNAGE:**

WHEN AN ALTERNATE CIRCULATION PATH OR A BARRICADE IS CREATED IN THE PUBLIC RIGHT-OF-WAY, A WARNING AND/OR APPROPRIATE SIGNAGE SHALL BE PROVIDED.

a. WARNINGS SHALL BE LOCATED AT BOTH THE NEAR-SIDE AND THE FAR-SIDE OF THE INTERSECTION PRECEDING A TEMPORARY AND COMPLETELY BLOCKED PEDESTRIAN ACCESS ROUTE. SIGNAGE LOCATED AT THE INTERSECTION PRECEDING THE BLOCKED WAY SHALL BE PROVIDED.

b. SIGNS SHALL BE PLACED AT INTERSECTIONS SO PEDESTRIANS ARE NOT CONFRONTED WITH MID-BLOCK WORKSITES THAT COULD CAUSE THEM TO SKIRT THE WORK ZONE OR MAKE A MID-BLOCK CROSSING. AMPLE ADVANCE NOTIFICATION OF SIDEWALK CLOSURES IS IMPORTANT. DETOUR SIGNS ARE REQUIRED TO DIRECT ALL PEDESTRIANS TO USE THE ALTERNATE CIRCULATION PATH, IF PROVIDED. IF CONSTRUCTION TEMPORARILY AFFECTS TRAFFIC SIGNALS, ALTERNATIVE VISUAL SIGNALS ARE REQUIRED. (c)

(XVI) **NEW OR REPLACEMENT CONSTRUCTION:**

WHERE THE REQUIRED SCOPE OF WORK AT A WORKSITE OR ZONE REQUIRES THE REMOVAL OF EXISTING FACILITIES, INCLUDING SIDEWALKS, WALKWAYS, DRIVEWAY APPROACHES, CURB RAMPS, AND SIMILAR ELEMENTS WITHIN THE PUBLIC RIGHT-OF-WAY OR WHERE LOCAL PERMITTING PROCESSES REQUIRE IT, NEW OR REPLACEMENT FACILITIES SHALL BE CONSTRUCTED BY THE COMPANY AFTER THE COMPLETION OF ALL WORK WITHIN THE WORKSITE OR ZONE. WHERE THE AUTHORITY HAVING JURISDICTION DICTATES SPECIFIC REQUIREMENTS, THE COMPANY SHALL PERFORM ITS CONSTRUCTION IN COMPLIANCE WITH THAT AUTHORITY. IN SITUATIONS WHERE THE AUTHORITY HAVING JURISDICTION HAS SPECIFIED REQUIREMENTS WHICH PROVIDE LESS ACCESS THAN THE REQUIREMENTS IN THIS SECTION, THE COMPANY SHALL USE THE REQUIREMENTS IN THIS SECTION WHICH PROVIDE MORE ACCESS, UNLESS THE AUTHORITY HAVING JURISDICTION EXPLICITLY CONTRADICTS OUR REQUIREMENTS.

(XVII) **PUBLIC SIDEWALKS:**

WHERE REPLACED OR NEWLY CONSTRUCTED, PUBLIC SIDEWALKS SHALL COMPLY WITH THIS SECTION.

a. **PEDESTRIAN ACCESS ROUTE:** WHERE PUBLIC SIDEWALKS ARE PROVIDED, THEY SHALL CONTAIN A PEDESTRIAN ACCESS ROUTE.

b. **CLEAR WIDTH:** THE MINIMUM CLEAR WIDTH OF A PEDESTRIAN ACCESS ROUTE SHALL BE 48 INCHES, EXCLUSIVE OF THE WIDTH OF THE CURB.

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | ARC | JIK | - | - | 4/12/2022 |
| C | FORMATTING | EDM | JIK | - | - | 12/7/2020 |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/17/2018 |

SDG&E — A Sempra Energy utility

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

SCALE: NOT TO SCALE

**PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY**

DRAWING NO: OH102.3 UG3002.3



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS

**NOTES (CONT'D):**

**EXCEPTION 1:** THE CLEAR WIDTH MAY BE REDUCED TO 36 INCHES IF UNUSUAL SITE CONSTRAINTS (SUCH AS PERMANENT FENCES OR REDUCED RIGHT-OF-WAY WIDTH) PRECLUDE AN EFFECTIVE METHOD FOR PROVIDING THE FULL WIDTH. BUT IN NO CASE SHALL THE DISTANCE OF SUCH REDUCTION BE MORE THAN 20 FEET.

c. **CROSS-SLOPE:** THE CROSS-SLOPE OF THE PEDESTRIAN ACCESS ROUTE SHALL NOT EXCEED 1:48 (2%).

d. **RUNNING GRADE:** THE RUNNING GRADE OF THE PEDESTRIAN ACCESS ROUTE SHALL NOT EXCEED 1:20 (5%), EXCEPT THAT STEEPER GRADES CONSISTENT WITH GRADES ESTABLISHED FOR THE ADJACENT ROADWAY MAY BE PROVIDED.

e. **SURFACES:** THE SURFACES OF THE PEDESTRIAN ACCESS ROUTE SHALL BE SMOOTH, FIRM, AND SLIP-RESISTANT.

f. **CHANGES IN LEVEL:** CHANGES IN LEVEL IN THE PEDESTRIAN ACCESS ROUTE SHALL NOT EXCEED 1/2-INCH VERTICAL. A 1/4-INCH VERTICAL CHANGE IN LEVEL MAY BE MADE WITHOUT PROVISIONS FOR BEVELING THE LIP OF THE CHANGE. CHANGES BETWEEN 1/4-INCH AND 1/2-INCH MUST BE BEVELED AT A 1:2 RATIO.

g. **WALL MOUNTED OBJECTS:** OBJECTS WITH LEADING EDGES MORE THAN 27 INCHES FROM THE GROUND AND NOT MORE THAN 80 INCHES ABOVE THE GROUND SHALL PROTRUDE NO MORE THAN FOUR INCHES HORIZONTALLY INTO THE PUBLIC SIDEWALK.

h. **POST-MOUNTED OBJECTS:** FREE STANDING OBJECTS MOUNTED ON POSTS OR PYLONS SHALL OVERHANG A MAXIMUM OF FOUR INCHES WHEN LOCATED MORE THAN 27 INCHES FROM THE GROUND AND LESS THAN 80 INCHES ABOVE THE GROUND. WHERE A SIGN OR OTHER OBSTRUCTION IS MOUNTED BETWEEN POSTS OR PYLONS AND THE CLEAR DISTANCE BETWEEN THE POSTS OR PYLONS IS GREATER THAN 12 INCHES, THERE SHALL BE A BAR OR SIMILARLY DETECTABLE ELEMENT 15 INCHES ABOVE THE GROUND CONNECTING THE TWO POSTS OR PYLONS. SUCH BAR OR OTHER ELEMENT SHALL PROVIDE VISUAL CONTRAST WITH THE GROUND SURFACE.

i. **REDUCED VERTICAL CLEARANCE:** RAILINGS OR OTHER BARRIERS SHALL BE PROVIDED WHERE THE VERTICAL CLEARANCE IS LESS THAN 80 INCHES HIGH. THE LEADING EDGE OF SUCH RAILING OR BARRIER SHALL BE LOCATED NO MORE THAN 27 INCHES ABOVE THE GROUND.

j. **PASSING SPACE:** PATHS OF TRAVEL THAT EXCEED 200 FEET ALONG THE PEDESTRIAN ACCESS ROUTE THAT ARE LESS THAN FIVE FEET IN CLEAR WIDTH SHALL PROVIDE PASSING SPACES FIVE FEET WIDE FOR A DISTANCE OF FIVE FEET TO ALLOW PEDESTRIANS IN WHEELCHAIRS ADEQUATE SPACE TO PASS.

(XVIII) **CURB RAMPS:**

WHERE REPLACED OR NEWLY CONSTRUCTED, CURB RAMPS SHALL COMPLY WITH THIS SECTION.

a. **WHERE REQUIRED:** A CURB RAMP OR FLUSH LANDING SHALL BE PROVIDED WHEREVER THE PEDESTRIAN ACCESS ROUTE CROSSES A SIDEWALK/STREET TRANSITION, INCLUDING INTERSECTIONS, MID-BLOCK CROSSWALKS, MEDIANS AND ISLANDS TRAVERSED BY CROSSWALKS, ALLEYS, ACCESSIBLE PARKING AISLES, PASSENGER LOADING ZONES, AND LOCATIONS WHERE THE PUBLIC SIDEWALK ENDS AND PEDESTRIAN TRAVEL CONTINUES IN THE ROADWAY. SIDEWALK/STREET TRANSITIONS SHALL HAVE DETECTABLE WARNINGS COMPLYING WITH THE SECTION BELOW.

b. **RUNNING SLOPE:** THE RUNNING SLOPE OF THE MAIN PORTION OF THE CURB RAMP SHALL BE 1:12 (8.33%) MAXIMUM.

c. **CROSS-SLOPE:** THE CROSS-SLOPE OF THE MAIN PORTION OF THE CURB RAMP SHALL BE 2% MAXIMUM.

d. **LANDING:** A LANDING MEASURING 48 INCHES, MINIMUM, BY 48 INCHES, MINIMUM, SHALL BE PROVIDED AT THE TOP OF THE CURB RAMP AND SHALL BE PERMITTED TO OVERLAP OTHER LANDINGS AND CLEAR SPACES. RUNNING AND CROSS-SLOPES OF THE LANDING SHALL BE 2% MAXIMUM.

e. **FLARED SIDES:** FLARED SIDES WITH A MAXIMUM SLOPE OF 1:10 (10%). MEASURED ALONG THE CURB LINE, SHALL BE PROVIDED WHERE A CIRCULATION PATH CROSSES THE CURB RAMP.

f. **CLEAR WIDTH:** THE CLEAR WIDTH OF THE MAIN PORTION OF THE CURB RAMP, EXCLUDING FLARED SIDES, SHALL BE 48 INCHES, MINIMUM.

g. **DETECTABLE WARNINGS:** DETECTABLE WARNING SURFACES SHALL BE PROVIDED FOR THE FULL WIDTH OF THE MAIN PORTION OF THE CURB RAMP AND FOR A DEPTH OF 24 INCHES MINIMUM, WITH THE FRONT EDGE LOCATED APPROXIMATELY SIX INCHES BEHIND THE CURB LINE. THE DETECTABLE WARNING SURFACE SHALL BE A PREFABRICATED, VITRIFIED POLYMER COMPOSITE, EMBEDDED TYPE MATERIAL. THE DETECTABLE WARNING SURFACE SHALL HAVE IN-LINE, SQUARE GRID PATTERN TRUNCATED DOMES 0.2-INCH HIGH, WITH 0.9-INCH MINIMUM AND 1.4-INCH MAXIMUM BASE DIAMETER, TAPERING UP TO A TOP DIAMETER OF 0.4-INCH, MINIMUM AND 0.5-INCH, MAXIMUM, WITH A CENTER TO CENTER SPACING OF APPROXIMATELY 2.3 INCHES MEASURED DIAGONALLY, AND WITH SAFETY FIELD DOTS 30 PER SQUARE INCH BETWEEN TRUNCATED DOMES. DETECTABLE WARNINGS SHALL BE SAFETY YELLOW CONFORMING TO FEDERAL COLOR NO. 33538.

h. **GROOVED BORDER:** A 12-INCH WIDE GROOVED BORDER WITH 1/4-INCH GROOVES APPROXIMATELY 3/4-INCH ON CENTER SHALL BE PROVIDED AT THE TOP OF THE MAIN SLOPE AND AT THE SIDE OF EACH SIDE SLOPE.

i. **SURFACES:** SURFACES OF CURB RAMPS AND LANDINGS SHALL COMPLY WITH THE PEDESTRIAN CONTROL PLANS FOR TEMPORARY MAINTENANCE AND CONSTRUCTION PROJECTS SECTION OF THIS STANDARD. GRATINGS, ACCESS COVERS, AND OTHER APPURTENANCES SHALL NOT BE LOCATED ON CURB RAMPS, LANDINGS, AND GUTTER AREAS DIRECTLY IN FRONT OF CURB RAMPS. (IX)(XI)(XII)(XIII)(XIV)(XV)

j. **CHANGES IN LEVEL:** VERTICAL CHANGES IN LEVEL SHALL NOT BE PERMITTED ON CURB RAMPS, LANDINGS OR GUTTER AREAS DIRECTLY IN FRONT OF CURB RAMPS.

k. **GUTTER SLOPE:** THE COUNTER SLOPE OF THE GUTTER AREA OR STREET AT THE FOOT OF A CURB RAMP OR LANDING SHALL BE 1:20 (5%) MAXIMUM, MEASURED FOR A DISTANCE OF 8 INCHES FROM THE CURB LINE.

(XIX) **DRIVEWAY APPROACHES OR RAMPS:**

a. **WHERE REQUIRED:** WHERE THE PEDESTRIAN ACCESS ROUTE CROSSES A VEHICULAR ENTRANCE TO AN ADJACENT PROPERTY, A DRIVEWAY APPROACH SHALL BE PROVIDED THAT MEETS THE REQUIREMENTS OF THIS SECTION.

b. **PEDESTRIAN ACCESS ROUTE WIDTH:** EACH DRIVEWAY APPROACH SHALL INCLUDE A LEVEL AREA WITH A CROSS-SLOPE OF NO MORE THAN 2% FOR A CLEAR WIDTH OF FOUR FEET (48 INCHES).

**EXCEPTION 1:** THE CLEAR WIDTH MAY BE REDUCED TO 36 INCHES IF UNUSUAL SITE CONSTRAINTS (SUCH AS PERMANENT FENCES OR REDUCED RIGHT-OF-WAY WIDTH) PRECLUDE AN EFFECTIVE METHOD FOR PROVIDING THE FULL WIDTH, BUT IN NO CASE SHALL THE DISTANCE OF SUCH REDUCTION BE MORE THAN 20 FEET.

c. **DRIVEWAY LIP:** EACH DRIVEWAY RAMP SHALL HAVE A ONE-INCH VERTICAL LIP AT THE STREET.

**REFERENCE:**

(a) REFER TO ESP138, ATTACHMENT "C".
(b) REFER TO ESP138, ATTACHMENT "D".
(c) FOR TYPICAL TRAFFIC CONTROL DEVICE USAGE AND TECHNIQUES FOR PEDESTRIAN MOVEMENT THROUGH WORK ZONES, SEE ESP138, ATTACHMENTS "E" & "G".

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | ARC | JIK | - | - | 4/12/2022 |
| C | FORMATTING | EDM | JIK | - | - | 12/7/2020 |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/17/2018 |

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY**

SCALE: NOT TO SCALE

DRAWING NO: OH102.4 UG3002.4

SHEET: 4 OF 4

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS PAGE DESCRIBES GENERAL INFORMATION CONCERNING THE FORMAT FOR STANDARD PAGES.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**PAGE FORMAT**

I. NOTE CALL-OUT:
   a. AN UNCIRCLED LETTERED NOTE (E.G., A) REFERS TO THE ENTIRE PAGE. REFERENCE TO THAT NOTE DOES NOT NORMALLY APPEAR ELSEWHERE ON THAT PAGE.
   b. CIRCLED LETTERED NOTE (E.G., (A)) REFERS TO A SPECIFIC PORTION OF THE PAGE. THE CIRCLED LETTER WILL BE REPLACED ELSEWHERE ON THAT PAGE.

II. THE FOLLOWING NOTES FOUND IN THE TITLE BLOCK (AT THE BOTTOM OF PAGE), ARE METHODS OF INDICATING PAGE CHANGES AND/OR ADDITIONS.
   a. [X] "INDICATES LATEST REVISION" (OLD VERSIONS) OR "INDICATES LATEST REVISION" (NEW VERSIONS)
      SHADING OR ORANGE FONT INDICATES THE MOST RECENT CHANGES AND/OR ADDITIONS ON A PAGE.
   b. [X] "COMPLETELY REVISED"
      THIS NOTE IS USED TO INDICATE THE PAGE HAS HAD MAJOR CHANGES.
   c. [X] "NEW PAGE"
      THIS NOTE IS USED TO INDICATE THE PAGE IS NEW.
   d. [X] "INFORMATION REMOVED"
      THIS NOTE INDICATES INFORMATION HAS BEEN DELETED.

III. PAGE NUMBERS WITH A DECIMAL INDICATE THAT THE STANDARD TAKES MORE THAN ONE PAGE.

IV. ALL STANDARD PAGES WILL BE MARKED WITH THE ABBREVIATION FOR THE MANUAL THEY EXIST IN. IF THE STANDARD EXISTS IN MORE THAN ONE MANUAL ALL ABBREVIATIONS AND STANDARD NUMBERS WILL BE INDICATED.

V. STANDARD PAGES WHICH APPEAR IN THE SERVICES STANDARDS & GUIDE MANUAL WILL BE INDICATED IN THE REFERENCE SECTION.

**REFERENCE:** NONE

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | ARC | JIK | - | - | 03/09/2022 |
| C | UPDATED STANDARDS | - | GW | JS | CZH | 11/15/2018 |
| B | NOTES UPDATE | - | GW | JS | MDJ | 03/01/2018 |

SDGE — A Sempra Energy utility

© 1998 - 2022 San Diego San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**STANDARD PAGE FORMAT**

SCALE: NOT TO SCALE

DRAWING NO: OH103.1 UG3003.1

SHEET: 1 OF 1

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD EXPLAINS HOW TO SUBMIT A REQUEST FOR A CONSTRUCTION STANDARDS DEVIATION, AN ELECTRIC DESIGN MANUAL DEVIATION, A REQUEST FOR CLARIFICATION OR UPDATES TO A CONSTRUCTION STANDARD, ELECTRIC STANDARD PRACTICE, ELECTRIC DESIGN MANUAL OR SERVICE STANDARDS & GUIDE.

**ATTENTION:**

* THE PROCESS INCLUDES ELECTRONIC FORMS BACKED BY A DATA REPOSITORY WHICH WILL SIMPLIFY THE PROCESS OF SUBMISSION, DOCUMENTATION AND PRIORITIZATION OF REQUESTS.

** INCOMPLETE INFORMATION WILL RESULT IN DELAYED RESPONSE TIME.

**INSTALLATION:**

A. FORMS FOR EACH TYPE OF REQUEST CAN BE FOUND AT THIS SITE.

B. ACCESS IS GRANTED TO APPROVED USERS WITH VALID SDG&E ID'S.

C. FROM THE DASHBOARD, SELECT THE APPROPRIATE REQUEST TYPE AND FILL OUT THE REQUIRED FIELDS.

D. THEN CLICK ON THE BUTTON TO SEND TO SUPERVISOR OR DESIGNATED APPROVER FROM THE REQUESTING DEPARTMENT.

E. EMAIL NOTIFICATIONS ARE SENT TO THE SUPERVISOR OR DESIGNATED APPROVER AND THE REQUESTER.

F. ONCE THE SUPERVISOR OR DESIGNATED APPROVER COMPLETES THEIR COMMENTS AND APPROVAL, THE REQUESTS ENTERS THE ELECTRIC DISTRIBUTION ENGINEERING (EDE) QUEUE FOR REVIEW BY THE APPROPRIATE TEAM.

G. THE REQUEST MAY BE SENT TO ADDITIONAL REVIEWERS AND NON-EDE APPROVERS AT EDE'S DISCRETION.

H. THE REQUESTER IS NOTIFIED VIA EMAIL ANY TIME THE REQUEST IS EDITED AND WHEN REQUEST IS EITHER APPROVED OR DENIED.

**BILL OF MATERIALS:** NONE

**NOTES:**

**DEVIATION REQUESTS**

I. FOR NON-STANDARD INSTALLATIONS NOT SHOWN IN THE OVERHEAD/UNDERGROUND CONSTRUCTION STANDARDS.

II. TO BE SUBMITTED BY PLANNERS AND ENGINEERS.

III. PRIOR TO REVIEW BY THE ELECTRIC DISTRIBUTION ENGINEERING TEAM, THE REQUEST MUST BE APPROVED BY THE REQUESTER'S SDG&E SUPERVISOR OR DESIGNATED SDG&E EMPLOYEE.

IV. REQUEST MAY REQUIRE FURTHER REVIEW BY CIVIL & STRUCTURAL ENGINEERING OR OTHER DEPARTMENTS IF DEEMED NECESSARY BY THE REVIEWING EDE TEAM.

V. REQUESTS MAY BE REVIEWED AND APPROVED BY THE DISTRICT CONSTRUCTION SUPERVISOR, GENERAL FOREMAN, OR CONSTRUCTION PROJECT COORDINATOR.

VI. DEVIATIONS SHOULD BE THE EXCEPTION AND NOT THE RULE AND SHOULD BE CONSIDERED ONLY AS A LAST ALTERNATIVE.

VII. RESPONSE WILL BE PROVIDED PER THE REQUEST PRIORITY AND DUE DATE, AND MAY EXTEND DEPENDING ON TIME REQUIRED FOR STUDY, MEETINGS, ETC. REQUEST WILL BE RETURNED EITHER APPROVED OR DENIED WITH COMMENTS AND EXPLANATIONS GIVEN.

**CONSTRUCTION STANDARDS, DESIGN MANUAL, SERVICE STANDARDS & GUIDE AND DESIGN UNIT REQUESTS**

VIII. FOR REQUESTING CLARIFICATION, ADDITIONS, REVISIONS OR CORRECTIONS.

IX. THIS INSTRUCTION APPLIES TO ALL PERSONS INVOLVED IN THE USE OR DEVELOPMENT OF CONSTRUCTION STANDARDS, DESIGN MANUAL, SERVICE STANDARDS & GUIDE AND DESIGN UNITS.

XI. PRIOR TO REVIEW BY THE ELECTRIC DISTRIBUTION ENGINEERING TEAM, THE REQUEST MUST BE APPROVED BY THE REQUESTER'S SDG&E SUPERVISOR OR DESIGNATED SDG&E EMPLOYEE.

XII. UPON RECEIPT OF REQUEST BY EDE, REQUESTOR WILL BE NOTIFIED OF ACTION TO BE TAKEN WITH A SPECIFIED MAXIMUM TIME FRAME, DEPENDING ON REQUEST PRIORITY.

**REFERENCE:**

a. ELECTRIC DISTRIBUTION ENGINEERING **WEBSITE**.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | ARC | JIK | - | - | 03/09/2022 |
| C | COMPLETELY REVISED | EDM | JIK | JES | CZH | 10/21/2020 |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 09/21/2018 |

SDG&E

A Sempra Energy utility®

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**CONSTRUCTION STANDARDS / DEVIATION REQUEST FORM AND PROCEDURE**

SCALE: NOT TO SCALE

DRAWING NO: OH105.1 UG3005.1

SHEET: 1 OF 1

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

| PAGE | SUBJECT |
|---|---|
| 3104 | DISTRIBUTION SWITCH NUMBERING |
| 3111 | DISTRIBUTION STRUCTURE NUMBERING |
| 3113 | GIS UG MAP SYMBOL TABLE |
| 3140 | CONTAMINATION DISTRICTS |
| 3150 | ELECTRIC CONDUIT FIELD MAPPING |

MAIN TABLE OF CONTENTS

THIS SECTION HAS BEEN REMOVED FROM THE EXTERNAL VERSION.
DUE TO CONFIDENTIAL INFORMATION.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | UPDATES TO 3104 | - | GW | TR/GW | MDJ | 9/27/2016 | F | | | | | | |
| B | UPDATES TO 3140 | - | JS | TR | MDJ | 8/3/2016 | E | FORMATTING | EDM | JIK | - | - | 1/13/2021 |
| A | 3112 MOVED TO FMO | - | JC | TR | JS/MDJ | 10/7/2015 | D | EDITORIAL CHANGES | - | JK | JS | CZH | 5/18/2018 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDRERGROUND CONSTRUCTION STANDARDS

PRACTICES
TABLE OF CONTENTS

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 3202 | CABLE IDENTIFICATION |
| 3203 | PULL AND MEASURING TAPE, CONDUIT AND CONDUIT KNOCKOUT IDENTIFICATION |
| 3204 | COMMUNICATION CONDUIT IDENTIFICATION |
| 3211 | STRUCTURE/EQUIPMENT IDENTIFICATION - SUBSURFACE AND PAD MOUNTED |
| 3212 | FIRE PUMP WARNING LABEL |
| 3213 | PRIMARY METERING STATION IDENTIFICATION |
| 3214 | TRANSFORMER STATION IDENTIFICATION |
| 3215 | SUBSURFACE/SURFACE OPERABLE AND PAD MOUNTED SWITCH IDENTIFICATION |
| 3216 | FAULT INDICATOR IDENTIFICATION |
| 3217 | FUSE IDENTIFICATION |
| 3218 | IDENTIFICATION DECALS |
| 3221 | PAD MOUNTED EQUIPMENT - HIGH VOLTAGE DECALS |
| 3225 | TRANSFORMER COMPANY NUMBER |
| 3230 | CUSTOMER GENERATOR IDENTIFICATION - WARNING DECAL |
| 3232 | LOADBREAK AND DEADBREAK ELBOW IDENTIFICATION - TAG AND STRAP |
| 3233 | NORMALLY OPEN POINT IDENTIFICATION - TAG AND STRAP |
| 3234 | CIRCUIT TIE - DO NOT OPERATE ENERGIZED - TAG AND STRAP |
| 3238 | SCADA SITE IDENTIFICATION DECAL |
| 3239 | BURIED FIBER OPTIC CABLE WARNING DECAL |
| 3240 | PAD MOUNTED EQUIPMENT - WORKING SPACE DECALS |


THIS SECTION HAS BEEN REMOVED FROM THE EXTERNAL VERSION.
DUE TO CONFIDENTIAL INFORMATION.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | UPDATES TO 3204 | - | JS | JS | MDJ | 10/25/2016 | G | FORMATTING | EDM | JIK | - | - | 2/4/2021 |
| C | UPDATES TO 3203 | - | JS | TR | MDJ | 9/27/16 | F | EDITORIAL CHANGES | - | JK | JS | CZH | 5/18/2018 |
| B | UPDATES 3238 | - | JS | TR | MDJ | 8/25/2016 | E | UPDATES TO 3240 | - | JS | JS | MDJ | 10/25/2016 |

| PAGE | SUBJECT |
|---|---|
| 3302 | SUBSTRUCTURE APPLICATIONS |
| 3303 | CONCRETE PRODUCTS - MANHOLES, HANDHOLES, COVERS AND ENCLOSURES |
| 3304 | FALSE CURB |
| 3305 | INSTALLATION OF SUBSTRUCTURES ON SLOPING GRADES |
| 3306 | JOINT (PLASTIC-MASTIC) SEALING COMPOUND - INSTALLATION |
| 3308 | HANDHOLE - CITY OF SAN DIEGO STREET LIGHT (INSIDE DIMENSIONS 10 1/4" X 15 3/8") |
| 3309 | HANDHOLE POLYMER CONCRETE (37 5/8" X 26" X 18" OR 37 5/8" X 26" X 26") |
| 3310 | PENCELL SECONDARY BOX PEDESTAL WITH DOME |
| 3311 | HANDHOLE - CONCRETE (INSIDE DIMENSIONS - 14" X 66" X 14" OR 14" X 108" X 14") |
| 3312 | HANDHOLE - HIGH DENSITY POLYETHYLENE (HDPE), CONCRETE (INSIDE DIMENSIONS - 17" X 30") |
| 3313 | HANDHOLE - CONCRETE (INSIDE DIMENSIONS - 24" X 36" OR 30" X 48") |
| 3314 | HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE (INSIDE DIMENSIONS 3'-0" X 6'-0") |
| 3315 | HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE (INSIDE DIMENSIONS 4'-0" X 6'-6") |
| 3316 | HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE (INSIDE DIMENSIONS 5'-0" X 8'-6") |
| 3317 | HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE (INSIDE DIMENSIONS 6'-0" X 8'-0") |
| 3325 | MANHOLE - TUB TYPE (INSIDE DIMENSIONS 8'-0" X 14'-0" X 9'-6") |
| 3326 | MANHOLE - TUB TYPE (INSIDE DIMENSIONS 8'-0" X 20'-0" X 9'-6") |
| 3327 | SUBSTATION MANHOLE VAULT 10'-0" X 24'-0" X 8'-0" |
| 3332 | MANHOLE NECK AND COVER - TRAFFIC BEARING (INSIDE DIMENSIONS 48" X 60") |
| | **SUBSTRUCTURE AND VAULT ACCESSORIES** |
| 3360 | SUMP PUMP INSTALLATION FOR MANHOLES 3324, 3325, 3326, 3327 |
| 3361 | STREET RESURFACING |
| 3362 | UTILITY LOCATIONS IN LOCAL AND COLLECTOR STREETS IN S.D. COUNTY |
| 3363 | UTILITY LOCATIONS IN MAJOR STREETS, PRIME ARTERIALS, AND EXPRESSWAYS IN S.D. COUNTY |
| 3364 | JOINT TRENCH TYPICAL LOCATION FOR UNDERGROUND CONVERSIONS IN S.D. COUNTY |


MAIN TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | EDITORIAL CHANGES | EDM | DEC | JES | CZH | 06/07/2021 | G | 3383 MOVED TO FMO | ARC | ADW | JES | KRG | 05/08/2023 |
| C | ADDED 3327 | - | JS | JS | CZH | 11/01/2018 | F | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| B | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | E | ADDED 3368 | NV5 | ADW | JES | CZH | 10/01/2021 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUBSTRUCTURES, CONDUIT
TABLE OF CONTENTS

UG3301.1

| PAGE | SUBJECT |
|---|---|
| 3365 | IMPORTED OR NATIVE BACKFILL |
| 3366 | SLURRY BACKFILL |
| 3367 | TRENCH PARALLELING FOUNDATIONS |
| 3368 | SHALLOW TRENCHING |
| 3369 | BIO RETENTION/WET FACILITIES STANDARD |
| 3370 | UNDERGROUND DISTRIBUTION (UD) TRENCHES AND UTILITY POSITIONING - S.D. COUNTY |
| 3371 | UNDERGROUND DISTRIBUTION (UD) TRENCHES AND UTILITY POSITIONING - ORANGE COUNTY |
| 3372 | CONDUIT SIZING FOR UNDERGROUND CABLES |
| 3373 | CONDUIT AND CONDUIT FITTINGS - EB, & POLYETHYLENE |
| 3374 | CONDUIT INSTALLATION PRACTICES |
| 3375 | CONDUIT SPACER DATA |
| 3376 | CONDUIT, ENCASED MULTI-CONDUIT INSTALLATION |
| 3377 | CONDUIT STUB MARKER AND BALL MARKER LOCATING SYSTEM |
| 3378 | CONDUIT INSTALLATION IN BRIDGES |
| 3379 | CONDUIT MANDRELING |
| 3382 | CONDUIT SUBSTRUCTURE ADAPTORS |
| 3390 | GAS STUB MARKER |


MAIN TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | EDITORIAL CHANGES | EDM | DEC | JES | CZH | 06/07/2021 | G | 3383 MOVED TO FMO | ARC | ADW | JES | KRG | 05/08/2023 |
| C | ADDED 3327 | - | JS | JS | CZH | 11/01/2018 | F | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| B | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | E | ADDED 3368 | NV5 | ADW | JES | CZH | 10/01/2021 |

**SCOPE:** THIS STANDARD DESCRIBES SUBSTRUCTURE APPLICATIONS FOR EQUIPMENT LIMITATIONS, TERMINATION CONFIGURATIONS AND UNOBSTRUCTED SPACE REQUIREMENTS. (a)

## TABLE 1

| SUBSTRUCTURE APPLICATIONS | |
|---|---|
| **SUBSTRUCTURE** | **APPLICATION** |
| 3309<br>36" X 24 1/4" X 18"<br>HANDHOLE | HANDHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR THE TERMINATION AND CONNECTION OF SINGLE-PHASE SECONDARIES AND SERVICES. HANDHOLE MUST BE INSTALLED IN NON-TRAFFIC AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. NEVER INSTALL IN STREETS OR DRIVEWAYS. |
| 3309<br>36" X 24 1/4" X 26"<br>HANDHOLE | HANDHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR THE TERMINATION AND CONNECTION OF SINGLE-PHASE AND LIMITED THREE-PHASE SECONDARIES AND SERVICES. HANDHOLE MUST BE INSTALLED IN NON-TRAFFIC AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. NEVER INSTALL IN STREETS OR DRIVEWAYS. WHEN A 3309 IS REQUIRED IN A TRAFFIC AREA, SUBSTITUTE THE 3309 WITH THE 3313 AND TRAFFIC COVER. 3313 REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. |
| 3311<br>14" X 66" X 14"<br>HANDHOLE | FOR PRIMARY AND SECONDARY CABLE TRAINING BETWEEN TWO SINGLE-PHASE PAD MOUNTED TRANSFORMERS CONNECTED IN AN OPEN-DELTA BANK. |
| 3311<br>14" X 108" X 14"<br>HANDHOLE | FOR PRIMARY AND SECONDARY CABLE TRAINING BETWEEN THREE SINGLE-PHASE PAD MOUNTED TRANSFORMERS CONNECTED IN A CLOSED DELTA-BANK WHEN HKR TRANSFORMER CANNOT BE USED. |
| 3312<br>17" X 30" X 12"<br>HANDHOLE-1 BODY SECONDARY AND UNDER PAD | 3312 HANDHOLE MAY BE USED FOR REPLACEMENT OF EXISTING FACILITIES. USE 3309 IF POSSIBLE. ALL FACILITIES REQUIRING 30" X 17" BOX UNDER PAD MOUNTED EQUIPMENT. |
| 3313<br>24" X 36" X 24"<br>HANDHOLE | HANDHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR TERMINATION AND CONNECTION OF SINGLE-PHASE OR THREE-PHASE SECONDARIES AND SERVICES OR SINGLE-PHASE PRIMARY. SECONDARIES AND PRIMARY ARE NOT PERMITTED IN THE SAME HANDHOLE. HANDHOLE WITH PARKWAY COVER MUST BE INSTALLED IN AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. HANDHOLE WITH A TRAFFIC COVER MAY BE INSTALLED IN STREETS OR DRIVEWAYS BUT ONLY WHEN A **NON-TRAFFIC LOCATION IS UNAVAILABLE.** REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

## TABLE 1 (CONT'D)

| SUBSTRUCTURE APPLICATIONS | |
|---|---|
| **SUBSTRUCTURE** | **APPLICATION** |
| 3314<br>3'-0" X 6'-0" X 4'-0"<br>HANDHOLE | HANDHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR THE TERMINATION AND CONNECTION OF SINGLE-PHASE AND THREE-PHASE PRIMARY LOCAL DISTRIBUTION AND/OR SECONDARIES AND SERVICES. HANDHOLE WITH PARKWAY COVER MUST BE INSTALLED IN AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. IF A NEW 3314 HANDHOLE IS REQUIRED IN A STREET OR DRIVEWAY WHERE A **NON-TRAFFIC LOCATION IS UNAVAILABLE,** IT MUST BE SUBSTITUTED WITH A 3315 HANDHOLE AND TRAFFIC COVER. IF A TRAFFIC COVER IS REQUIRED ON AN EXISTING 3314 HANDHOLE LOCATED IN A VEHICULAR AREA, USE THE 3315 "TRAFFIC COVER ASSEMBLY". REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. (THE 3523 IS PREFERRED) |
| 3315<br>4'-0" X 6'-6" X 6'-0"<br>HANDHOLE | HANDHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR THE TERMINATION AND CONNECTION OF SINGLE-PHASE AND THREE-PHASE PRIMARY LOCAL DISTRIBUTION, THREE-PHASE PRIMARY FEEDERS, SECONDARIES AND SERVICES. HANDHOLE WITH PARKWAY COVER MUST BE INSTALLED IN AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. HANDHOLE WITH A TRAFFIC COVER MAY BE INSTALLED IN STREETS OR DRIVEWAYS BUT ONLY WHEN A **NON-TRAFFIC LOCATION IS UNAVAILABLE.** REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. |
| 3316<br>5'-0" X 8'-6" X 6'-6"<br>HANDHOLE | HANDHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR THE TERMINATION AND CONNECTION OF SINGLE-PHASE AND THREE-PHASE PRIMARY LOCAL DISTRIBUTION, THREE-PHASE PRIMARY FEEDERS, 4-WAY SWITCH, SECONDARIES AND SERVICES. HANDHOLES WITH PARKWAY COVER MUST BE INSTALLED IN AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. HANDHOLES WITH TRAFFIC COVER MAY BE INSTALLED IN STREETS OR DRIVEWAYS BUT ONLY WHEN A **NON-TRAFFIC LOCATION IS UNAVAILABLE.** REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. |
| 3317<br>6'-0" X 8'-0" X 5'-10"<br>HANDHOLE | HANDHOLE CAN BE USED IN EXISTING SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS AND OTHER NON-NEW DEVELOPMENT PROJECTS. TO BE USED **ONLY** TO INSTALL THE "VISTA" SUB-SURFACE, SURFACE OPERABLE 4-WAY SWITCH, AND TERMINATE ON SWITCH THREE-PHASE PRIMARY FEEDERS, SINGLE & THREE-PHASE LOCAL DISTRIBUTION CABLES. HANDHOLE MUST BE INSTALLED IN NON-TRAFFIC AREAS WHERE VEHICLES CANNOT DRIVE OVER OR PARK ON TOP OF HANDHOLE. REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. |
| 3325<br>8'-0" X 14'-0" X 9'-6"<br>3326<br>8'-0" X 20'-0" X 9'-6"<br>MANHOLE | MANHOLE CAN BE USED IN SINGLE-FAMILY RESIDENTIAL, MULTI-FAMILY, AND COMMERCIAL DEVELOPMENTS FOR TERMINATION AND CONNECTION OF LOCAL PRIMARY DISTRIBUTION THREE-PHASE PRIMARY FEEDERS, SECONDARIES AND SERVICES AND ON-OFF OR 4-WAY SWITCHES. MANHOLE CAN BE INSTALLED IN NON-TRAFFIC OR STREET LOCATIONS. REQUIRES TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE. (b) |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) SEE UG3605, UG3644, UG3646, UG3647, UG3648, AND UG3649.

(b) FOR 4-WAY SWITCH MANHOLE REQUIREMENTS, SEE UG3605.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD LISTS THE CONCRETE PRODUCTS USED IN SUBSURFACE INSTALLATIONS.

## TABLE 1

| CONCRETE PRODUCTS | | | | |
|---|---|---|---|---|
| **TYPE** | **DIMENSIONS** | **STANDARD PAGE** | **INSTALLED BY** | **CRANE REQUIRED** (B) |
| HANDHOLE | 3309 - 37" X 26 X 18" | 3309 | CREWS OR CONTRACTOR | NO |
| | 3309 - 37" X 26" X 26" | | | |
| | 14" X 66" X 14" | 3311 | CREWS OR CONTRACTOR | NO |
| | 14" X 108" X 14" | | | |
| | 17" X 30" X 12" | 3312 | CREWS OR CONTRACTOR | NO |
| | 24" X 36" X 24" | 3313 | CREWS OR CONTRACTOR | NO |
| | 36" X 72" X 48" | 3314 | CREWS OR CONTRACTOR (A) | NO |
| | 4'-0" X 6'-6" X 6'-0" | 3315 | CREWS OR CONTRACTOR (A) | NO |
| | 5'-0" X 8'-6" X 6'-6" | 3316 | CREWS, CONTRACTOR OR SUPPLIER (A) | NO |
| | 6'-0" X 8" X 6'-6" | 3317 | CREWS OR CONTRACTOR (A) | YES |
| MANHOLE | 8'-0" X 14'-0" X 8'-6" | 3325 | CREWS, CONTRACTOR OR SUPPLIER | YES |
| | 8'-0" X 20'-0" X 9'-6" | 3326 | CREWS, CONTRACTOR OR SUPPLIER | YES |
| MANHOLE NECK & COVER-TRAFFIC BEARING | 48" X 60" | 3332 | CREWS OR CONTRACTOR | NO |

## INSTALLATION:

(A) SUPPLIER WILL SET SUBSTRUCTURE ON JOB SITE IF EXCAVATION IS COMPLETED.

(B) WHEN SUPPLIER'S OR SDG&E'S EQUIPMENT CANNOT GET CLOSE ENOUGH TO EXCAVATE DUE TO SOFT SAND, ETC. A CRANE WILL BE REQUIRED.

**BILL OF MATERIALS:** NONE

## NOTES:

I. SPECIAL ORDER MANHOLES LARGER THAN THOSE LISTED WILL BE INSTALLED BY SUPPLIER/CONTRACTOR.

## REFERENCE:

a. FOR WATER SEALING CONCRETE SECTIONS, SEE UG3306.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD PROVIDES INFORMATION ON HOW TO APPLY, ORDER, AND INSTALL FALSE CURBS.





**FIGURE 1**

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FALSE CURB

UG3304.1

**ATTENTION:**

* FALSE CURBS ARE PRIMARILY USED IN ASSOCIATION WITH ROAD IMPROVEMENT PROJECTS. THE FALSE CURB IS AN EFFECTIVE WAY TO ELIMINATE THE NEED TO RELOCATE A PRIMARY HANDHOLE OR MANHOLE WHEN THE OPENING TO THE STRUCTURE ENDS UP IN THE CURB AND GUTTER. FALSE CURBS ARE NOT RECOMMENDED FOR SECONDARY HANDHOLES.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**PREPARATION**

I. IF IT IS DETERMINED BY THE PLANNER DESIGNING THE JOB THAT A FALSE CURB COULD BE USED, THEY SHOULD CONTACT THE LIAISON PLANNER TO ESTABLISH IF IT IS APPROPRIATE FOR THE LOCATION. THE LIAISON PLANNER WILL THEN CONTACT THE APPROPRIATE MUNICIPALITY TO GET APPROVAL FOR THE INSTALLATION.

II. ONCE APPROVAL IS GIVEN BY THE MUNICIPALITY, THE PLANNER SHOULD MAKE ARRANGEMENTS WITH THE C&O CENTER TO DETERMINE IF THE TOP SECTION OF THE STRUCTURE CAN BE LOWERED AND A TRAFFIC COVER INSTALLED. THE FIELD ENGINEER CAN ASSIST WITH MEASUREMENTS FOR THE FALSE CURB AND NEW CURB ALIGNMENT. IF ADDITIONAL HELP IS NEEDED, CONTACT ELECTRIC DISTRIBUTION STANDARDS.

III. ONCE THE DIMENSIONS OF THE FALSE CURB ARE DETERMINED, CONTACT MADRUGA IRON WORKS AT (209) 832-7003, OR FAX (209) 832-2444. IF YOU HAVE MORE THAN ONE FALSE CURB, THEY SHOULD BE LISTED SEPARATELY WITH SPECIFIC DIMENSIONS.

IV. A REPRESENTATIVE FROM MADRUGA IRON WORKS WILL THEN FAX A COST QUOTE TO THE REQUESTOR FOR THE COST OF EACH FALSE CURB. THE REQUESTOR WILL NOW NEED TO COMPLETE A REQUISITION FOR MATERIAL AND SERVICE FORM (RMS).

**DIMENSIONS:**

V. WHEN ORDERING A FALSE CURB MAKE SURE TO INDICATE THAT ALL DIMENSIONS ARE INSIDE DIMENSIONS (ID).

a. WIDTH (SIDE TO SIDE): THE INSIDE MEASUREMENT FOR THE FALSE CURB IS BASED ON THE OUTSIDE MEASUREMENT OF THE TRAFFIC COVER ON WHICH THE FALSE CURB IS TO BE PLACED. A 3314 OR 3315 HANDHOLE WILL MEASURE 96 INCHES WIDE. A 3316 MEASURES 120 INCHES WIDE. MANHOLES WILL VARY DEPENDING ON THE VINTAGE OF THE STRUCTURE. ALL MEASUREMENTS SHOULD BE FIELD VERIFIED.

b. DEPTH (FRONT TO BACK): MEASURE FROM WHERE THE FACE OF THE NEW CURB AND THE GUTTER MEET THE BACK EDGE OF THE STRUCTURE, ADD SIX INCHES TO THIS MEASUREMENT. THIS MEASUREMENT IS THE INSIDE DIMENSION FOR DEPTH.

c. HEIGHT: SPECIFY EITHER A SIX-INCH OR EIGHT-INCH CURB.

**MISCELLANEOUS:**

VI. IN ADDITION TO THE DIMENSIONS OF THE FALSE CURB, THE FOLLOWING INFORMATION WILL NEED TO BE INCLUDED IN THE RMS:

a. SPECIFY THAT THE FALSE CURB ASSEMBLY IS THE BOLT DOWN STYLE.

b. AFFIX SDG&E TO THE LOWER FACE OF THE CURB.

**ATTENTION:**

* MADRUGA IRON WORKS WILL DETERMINE THE NUMBER OF COVERS ON THE FALSE CURB BASED ON THE OVERALL SIZE OF THE ASSEMBLY.

**PURCHASING**

VII. A PURCHASE ORDER MUST BE SUBMITTED.

VIII. WORK WITH THE LIAISON PLANNER TO SEE IF THE MUNICIPALITY'S CONTRACTOR WILL INSTALL THE FALSE CURBS. IF THEY ARE INTERESTED AND THE MUNICIPALITY APPROVES, THEN THEY ARE TO SUBMIT A BID FOR THE INSTALLATION COST. IF THE BID IS APPROVED BY THE LIAISON PLANNER AND SUPERVISOR, THE LIAISON PLANNER WILL NOTIFY THE CONTRACTOR. THE CONTRACTOR, AT THIS TIME, MAY ALSO PROVIDE SDG&E WITH A RELEASE FORM, WHICH, AS THE MUNICIPALITY'S CONTRACTOR, ALLOWS THEM TO INSTALL THE FALSE CURBS. IF WE DO NOT ACCEPT THE BID, THEN SDG&E WILL INSTALL THE CURBS AND COORDINATE WITH THE CONTRACTOR. PROVIDE CITY CONTRACTOR WITH A COPY OF THE WORK ORDER.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FALSE CURB

UG3304.2

## NOTES (CONT'D):

**INSTALLATION:**

IX. THE MUNICIPALITY'S CONTRACTOR WILL WORK WITH THE DISTRICT AND PROJECT COORDINATOR ON THE ACTUAL INSTALLATION OF THE FALSE CURBS. THE CONTRACTOR IS RESPONSIBLE FOR PICK-UP OF MATERIAL FROM THE C&O DISTRICT.

XI. UPON COMPLETION OF THE WORK BY THE MUNICIPALITY'S CONTRACTOR, THEY ARE TO SUBMIT A REQUEST FOR PAYMENT. UPON RECEIPT, THE LIAISON PLANNER WILL PREPARE A REQUEST FOR VOUCHER CHECK FORM. PAYMENT IS TO BE MADE TO THE CONTRACTOR AND CHARGED TO THE APPROPRIATE BUDGET.

**DESIGN (DPSS)**

XII. BE SURE TO INDICATE AT THE LOCATION (WHERE THE FALSE CURBS ARE BEING INSTALLED) THAT THE MUNICIPALITY'S CONTRACTOR IS DOING THE INSTALLATION. SDG&E WILL BE LOWERING THE SUBSTRUCTURE AND INSTALLING A TRAFFIC COVER.

## REFERENCE:

a. FOR HANDHOLE EQUIPMENT ENCLOSURE (INSIDE DIMENSIONS - 3'-0" X 6'-0"), SEE UG3314.

b. FOR HANDHOLE EQUIPMENT ENCLOSURE (INSIDE DIMENSIONS - 4'-0" X 6'-0"), SEE UG3315.

c. FOR HANDHOLE EQUIPMENT ENCLOSURE (INSIDE DIMENSIONS - 5'-0" X 8'-6"), SEE UG3316.

d. FOR 48" X 60" NECK AND COVER TRAFFIC BEARING, SEE UG3332.

e. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIRED TO SET SUBSTRUCTURES ON SLOPING GRADES.





**FIGURE 1**
SUBSURFACE TRANSFORMER ENCLOSURE (c)
(FIELD MAINTENANCE ONLY)





**FIGURE 2**





**FIGURE 3**
MULTI-SECTION MANHOLES (d)





**FIGURE 4**
MANHOLES - 36" OPENING (e)
(FIELD MAINTENANCE ONLY)





**FIGURE 5**
MANHOLES - 48" OPENING (f)

## INSTALLATION:

A. ALIGN TOP SECTION TO FINAL GRADE. POUR CONCRETE (4 SACK MIX WITH 3/8" PEA GRAVEL OR AS REQUIRED BY CITY OR COUNTY, CAL. TRANS. OR U.S. GOVERNMENT CODES).

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (SUBSTRUCTURE PLACEMENT), SEE UG3480, UG3481, UG3482 AND UG3483.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF SUBSTRUCTURES ON SLOPING SURFACES



UG3305.1

TABLE OF CONTENTS

**REFERENCE (CONT'D):**

b. FOR RETAINING WALLS WHERE BANKS OR EXCESSIVE SLOPES EXIST, SEE UG3484 AND UG3489.

(c) SEE FMO UG3399.401 AND FMO UG3399.404.

(d) SEE FMO UG3399.101, UG3314, UG3315, AND UG3316.

(e) SEE FMO UG3399.201, FMO UG3399.202, FMO UG3399.306, AND FMO UG3399.307

(f) SEE FMO UG3399.203, FMO UG3399.205, AND FMO UG3399.305.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF SUBSTRUCTURES ON SLOPING SURFACES

UG3305.2

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION PROCEDURE FOR PLASTIC-MASTIC SEALANT ON CONCRETE SUBSTRUCTURES.





**FIGURE 1**
TYPICAL SUBSTRUCTURE JOINTS

## INSTALLATION:

A. CLEAN JOINT SURFACES WITH BRUSH AND ASSURE THE JOINTS ARE DRY. REMOVE SILICONE-TREATED PROTECTING PAPER WRAPPING FROM ONE SIDE OF MASTIC SEALING STRIPS.

B. LAY MASTIC STRIPS, PAPER SIDE UP, ON CLEANED, DRY, JOINT SURFACE. FIRMLY PRESS STRIPS TO SURFACE END-TO-END AROUND ENTIRE JOINT. ALLOW ONE-INCH OVERLAPS WHEN ABUTTING.

C. REMOVE PROTECTIVE PAPER COVERING FROM STRIPS. NEXT SECTION IS THEN LOWERED INTO DRY BEFORE SECTIONS POSITION. MAKE SURE SECTION IS POSITIONED PROPERLY AND JOINTS AND SEALANT ARE ADJOIN.

D. FOLLOW PLACEMENT PROCEDURES ABOVE FOR VARIOUS TYPES OF JOINTS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | SEALANT, PLASTIC-MASTIC | AS REQ'D | -- | S631872 | -- |

## NOTES:

I. ON 3315 AND LARGER SUBSTRUCTURES, USE DOUBLE SEAL IF FIELD CONDITIONS INDICATE THAT WATER WILL PENETRATE THE JOINTS.

II. PLASTIC-MASTIC SEALANT, SUFFICIENT FOR SETTING EACH SUBSTRUCTURE IS SUPPLIED BY THE MANUFACTURER.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 10/27/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

JOINT (PLASTIC-MASTIC) SEALING COMPOUND INSTALLATION



UG3306.1

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3 1/2 STREET LIGHT HANDHOLE FOR THE CITY OF SAN DIEGO "ONLY".





**FIGURE 1**
NO. 3 1/2 STREET LIGHT HANDHOLE (IV)





**FIGURE 2**
TYPICAL PLAN VIEW





**FIGURE 3**
EXCAVATION DIMENSIONS
SINGLE HANDHOLE INSTALLATION

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/02/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE - CITY OF SAN DIEGO STREET LIGHT
(INSIDE DIMENSIONS 10 1/4" X 15 3/8")



UG3308.1

TABLE OF CONTENTS

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO GAS AND FOREIGN UTILITY PLACEMENTS. ANY CHANGE IN LOCATION BY DISTRICT CONSTRUCTION REQUIRES PRIOR APPROVAL FROM SERVICE PLANNING.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER DRAWING ABOVE. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW EXTRA SPACE FOR SETTING THE SUBSTRUCTURE AND TAMPING THE BACKFILL.

C. TO DETERMINE FINAL GRADE, MEASURE FROM THE TOP OF CURB OR ESTABLISHED GRADE.

D. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTION. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE. SET HANDHOLE AT FINAL GRADE.

(E) APPLY SILICONE GREASE, TO THE BOLTS WHEN SECURING THE COVER TO REDUCE REMOVAL AND INSTALLATION DIFFICULTIES.

(F) IF RIGHT-OF-WAY OR OBSTRUCTIONS CAUSE A PROBLEM, THE HANDHOLE MAY BE TURNED TO WHERE THE LONG SIDE OF THE HANDHOLE PARALLELS THE SIDEWALK OR PROPERTY LINE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | NO. 3 1/2 HANDHOLE | 1 | -- | -- (IV) | 31/2PB |
| 2 | GREASE, SILICONE | AS REQ'D | -- | S391424 | -- |

## NOTES:

I. THE ONLY LOCATION FOR A NO. 3 1/2 HANDHOLE IS IN NON-VEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.).

(II) CONDUIT TERMINATION AREA SHALL BE WITHIN FIVE INCHES MAX. FROM END OF SUBSTRUCTURE.

(III) LOCATE HANDHOLE A MINIMUM OF TWO FEET TO A MAXIMUM OF FIVE FEET FROM THE SERVICE POINT, PREFERABLY BETWEEN THE SERVICE POINT AND THE STREET LIGHT BEING SERVED.

(IV) SUPPLIED BY CITY OF SAN DIEGO.

## REFERENCE:

a. FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483. (USE 3312)

b. FOR SETTING HANDHOLE ON A SLOPING GRADE, SEE UG3485.

c. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488. (USE 3312)

d. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/02/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE - CITY OF SAN DIEGO STREET LIGHT
(INSIDE DIMENSIONS 10 1/4" X 15 3/8")



UG3308.2

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR 3309 HANDHOLES.





**FIGURE 1**
3309.1 HANDHOLE BODY





**FIGURE 2**
3309.2 HANDHOLE BODY





**FIGURE 3**
3309.1 & 3309.2 HANDHOLE COVER

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 3/5/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 09/18/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE POLYMER CONCRETE
(37" X 26" X 18")

UG3309.1

TABLE OF CONTENTS






**FIGURE 4**
3309.3 HANDHOLE BODY WITH
3309.3 (TIER 22) COVER

HANDHOLE MAY BE INSTALLED ON EITHER SIDE OF LOT LINE OR IN CENTER OF LOT LINE IN AREA WITH LIMITED SPACE. BUTT AGAINST BACK OF SIDEWALK.




CONDUIT TERMINATION AREA SHALL BE WITHIN 12" MAX. FROM END OF SUBSTRUCTURE

**FIGURE 5**
TYPICAL PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 3/5/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 09/18/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE POLYMER CONCRETE
(HEAVY DUTY COVER FOR 3309)

UG3309.2

TABLE OF CONTENTS





**FIGURE 6**
3309.1 & 3309.2 EXCAVATION DIMENSIONS





**FIGURE 7**
3309.3 EXCAVATION DIMENSIONS

## INSTALLATION:

A. ESTABLISH HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO GAS AND FOREIGN UTILITY PLACEMENTS. ANY CHANGE IN LOCATION BY CONSTRUCTION REQUIRES PRIOR APPROVAL FROM SERVICE PLANNING.

B. AFTER LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR EXCAVATION WIDTH, LENGTH AND DEPTH PER DRAWING ABOVE. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW EXTRA SPACE FOR SETTING THE SUBSTRUCTURE AND TAMPING THE BACKFILL.

C. TO DETERMINE FINAL GRADE, MEASURE FROM TOP OF CURB OR ESTABLISHED GRADE.

D. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE. SET HANDHOLE TOP AT FINAL GRADE.

(E) BOX SHALL BE SET ON 2 INCHES OF COMPACT 1/4-INCH GRAVEL.

(F) IF RIGHT OF WAY OR OBSTRUCTIONS CAUSE A PROBLEM, LONG SIDE OF HANDHOLE MAY BE PLACED PARALLEL TO THE SIDEWALK OR PROPERTY LINE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | DIMENSIONS | WEIGHT | QUANITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|---|
| 1<br>3 | BOX, HANDHOLE, 3309.1, SECONDARY<br>COVER, HANDHOLE, 3309.1 & 3309.2 | 37 5/8" X 26" X 18"<br>35 5/8" X 24" | 144 LBS. MAX.<br>55 LBS. MAX. | 1<br>1 | -- | S162688 | 330913 | 330913HH |
| 2<br>3 | BOX, HANDHOLE, 3309.2, SECONDARY<br>COVER, HANDHOLE, 3309.1 & 3309.2 | 37 5/8" X 26" X 26"<br>35 5/8" X 24" | 199 LBS. MAX.<br>55 LBS. MAX. | 1<br>1 | -- | S162690 | 330926 | 330926HH |
| 3 | COVER, HANDHOLE, 3309.1 & 3309.2 | 35 5/8" X 24" | 55 LBS. MAX. (I) | 1 | -- | S459952 | 09-COV | -- |
| 4<br>5 | BOX, HANDHOLE, 3309.3<br>COVER, HANDHOLE, 3309.3 | 40 1/4" X 38 5/8" X 24"<br>35 5/8" X 24" | 80 LBS.<br>151 LBS. | 1<br>1 | -- | S162422<br>S459950 | --<br>-- | --<br>-- |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 3/5/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 09/18/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE POLYMER CONCRETE (EXCAVATION DIMENSIONS)

UG3309.3

TABLE OF CONTENTS

**NOTES:**

(I) WEIGHT OF PREVIOUS LID: 115 LBS.

(II) IF CUSTOMER IS REQUIRED TO INSTALL A HANDHOLE IN A SERVICE LATERAL, THE LID SHALL BE TAGGED WITH MONEL STAINLESS STEEL TAG "CUSTOMER OWNED" BELOW SDG&E LOGO. FOLLOW UNDERGROUND CONSTRUCTION STANDARD 3211 FOR TAGGING INSTRUCTIONS.

(III) FOR TRAFFIC INSTALLATIONS, USE THE 3313 HANDHOLE AND STEEL TRAFFIC COVER.

**REFERENCE:**

a. SEE UG3302 FOR SUBSTRUCTURE APPLICATIONS.

b. SEE UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

c. SEE UG3485 WHEN SETTING HANDHOLE ON A SLOPING GRADE.

d. SEE UG3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

e. SEE UG3605 FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS).

f. SEE UG4173 FOR TRENCH DEPTH, CONDUIT AND CABLE INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 3/5/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 09/18/2015 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE POLYMER CONCRETE (EXCAVATION DIMENSIONS)

UG3309.4

**SCOPE:** THIS STANDARD COVERS THE PENCELL SECONDARY BOX PEDESTAL.

**ATTENTION:**

* THIS SECONDARY PEDESTAL IS DESIGNED FOR AND SHALL BE LOCATED IN GREEN BELTS, EXTREME WET ENVIRONMENTS, AREAS WITH HIGH VEGETATION THAT MAY COVER A SECONDARY BOX AND OTHER SIMILAR AREAS.

** ANY SPECIAL APPLICATION OF THIS FACILITY SHALL REQUIRE A DEVIATION REQUEST.





**FIGURE 1**
TOP SECTION OF COVER
FRONT VIEW





**FIGURE 1**
TOP SECTION OF COVER
SIDE VIEW



**FIGURE 1**





**FIGURE 2**
MID-SECTION OF COVER
FRONT VIEW





**FIGURE 2**
MID-SECTION OF COVER
SIDE VIEW



**FIGURE 3**





**FIGURE 4**
PE-20 ENCLOSURE
LOWER SECTION OF COVER
ISOMETRIC VIEW



**FIGURE 5**
PENCELL PLASTICS AG-18
PEDESTAL WITH DOME

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/01/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PENCELL SECONDARY BOX
PEDESTAL WITH DOME

UG3310.1




**FIGURE 6**





**FIGURE 7**





**FIGURE 8**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/01/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PENCELL SECONDARY BOX
PEDESTAL WITH DOME

UG3310.2



TABLE OF CONTENTS

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO GAS AND FOREIGN UTILITY PLACEMENTS. ANY CHANGE IN LOCATION BY DISTRICT CONSTRUCTION REQUIRES PRIOR APPROVAL FROM SERVICE PLANNING.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH, AND DEPTH PER FIGURES 7 AND 8 ABOVE. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW EXTRA SPACE FOR SETTING THE SUBSTRUCTURE AND TAMPING THE BACKFILL.

C. TO DETERMINE FINAL GRADE, MEASURE FROM THE TOP OF CURB OR ESTABLISHED GRADE.

(D) ADD FOUR INCHES OF GRAVEL AND COMPACT BOTTOM OF EXCAVATION AND SET FINAL GRADE.

(E) EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE. SET HANDHOLE AT FINAL GRADE. BOX SHOULD BE SET ONE-INCH ABOVE GRADE. DO NOT BACK FILL WITH LARGE ROCKS.

(F) INSTALL PULLING AND MEASURING TAPE IN CONDUIT.

## CABLE AND CONNECTIONS

G. WITH PEDESTAL BASE AND COVER REMOVED, PULL IN CABLE AS NEEDED. CUT CABLE AND AVOID EXCESS WASTE.

H. INSTALL PEDESTAL BASE, TERMINATE CABLE WITH CORRECT SECONDARY MOLDS.

J. WHEN THE MOLDS ARE INSTALLED, THEY SHOULD NOT BE TERMINATED HIGHER THAN THE PEDESTAL BASE.

K. APPLY SILICON GREASE TO THE PENTA BOLT ON THE PEDESTAL BASE AND TIGHTEN BOLT TO PEDESTAL BOX BY HAND.

L. APPLY LARGE BLACK STRAPS (S738440) TO MOLDS AND BLACK CABLE MOUNTING BRACKETS TO HOLD CABLE IN PLACE.

M. INSTALL PEDESTAL COVER. APPLY SILICON GREASE TO PENTA BOLT AND TIGHTEN BY HAND. APPLY KEYLESS LOCK AND SHEAR BOLT.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | COVER, PEDESTAL | 1 | -- | S525348 | 3310 |
| 2 | BASE, PEDESTAL | 1 | -- | | |
| 3 | ENCLOSURE, BOX | 1 | -- | | |
| 4 | BOLT, PENTA | 1 | -- | INCLUDED | -- |
| 5 | LATCH, LOCKING | 1 | -- | INCLUDED | -- |
| 6 | LOCK, MOLDED KEY | 1 | -- | INCLUDED | -- |
| 7 | LOCK, KEYLESS | 2 | -- | S738440 | -- |
| 8 | BRACKET, CONNECTION MOUNTING, CABLE | 3 | -- | INCLUDED | -- |
| 9 | EXCAVATION, 3310 | 1 | -- | -- | X10H |

TABLE OF CONTENTS

**NOTES:** NONE

## REFERENCE:

a. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

b. FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

(c) FOR TRENCH DEPTHS, BASE SHADING AND BACKFILL REQUIREMENTS, SEE UG3370.

d. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488.

e. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS, AND CONDUITS), SEE UG3605.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/01/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PENCELL SECONDARY BOX
PEDESTAL WITH DOME

UG3310.3

**SCOPE:** THIS STANDARD COVERS THE 3311-S AND 3311-L TROUGHS.

**ATTENTION:**

* THESE STRUCTURES GO BELOW THE PAD FOR OPEN/CLOSED DELTA TRANSFORMER INSTALLATIONS FOR CABLE TRAINING BETWEEN SINGLE-PHASE PAD MOUNTED TRANSFORMERS.





**FIGURE 1** (I)





**FIGURE 2** (II)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | KRG | 06/27/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/02/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE - CONCRETE
(INSIDE DIMENSIONS 14" X 66" X 14" OR 14" X 108" X 14")



UG3311.1

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | 3311-S TROUGH | 986 MAX. | -- | -- | S162660 | 3311-S |
| 2 | 3311-L TROUGH | 1,605 MAX. | -- | -- | S162662 | 3311-L |

**NOTES:**

(I) USED FOR TWO 12KV PAD MOUNTED TRANSFORMERS IN OPEN DELTA BANKS AND PAD MOUNTED SWITCH INSTALLATION.

(II) USED FOR THREE 12KV PAD MOUNTED TRANSFORMERS IN CLOSED DELTA BANKS.

**REFERENCE:**

a. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

MAIN TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | KRG | 06/27/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/02/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD ILLUSTRATES 37" X 39", 83" X 39", AND 129" X 39" CONCRETE HANDHOLES.





**FIGURE 1**
SINGLE-PHASE
37" X 39"
(INSIDE DIMENSIONS)





**FIGURE 2**
TWO-PHASE
83" X 39"
(INSIDE DIMENSIONS)





**FIGURE 3**
THREE-PHASE
129" X 39"
(INSIDE DIMENSIONS)

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | KRG | 06/27/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/02/2016 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE - CONCRETE
INSIDE DIMENSIONS
37" X 39" X 24", 83" X 39" X 24", 129" X 39" X 24"

UG3311.3

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | INSIDE DIMENSIONS | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | HANDHOLE, SINGLE-PHASE | 37" X 39" X 24" | AS REQ'D | -- | S162432 | 3311-1 |
| 2 | HANDHOLE, TWO-PHASE | 83" X 39" X 24" | AS REQ'D | -- | S162434 | 3311-2 |
| 3 | HANDHOLE, THREE-PHASE | 129" X 39" X 24" | AS REQ'D | -- | S162436 | 3311-3 |

**NOTES:** NONE

**REFERENCE:**

a. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | KRG | 06/27/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/02/2016 | D | | | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| | Indicates Latest Revision | | Completely Revised | X | New Page | Information Removed |




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE - CONCRETE
INSIDE DIMENSIONS
37" X 39" X 24", 83" X 39" X 24", 129" X 39" X 24"

UG3311.4

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF HIGH DENSITY POLYETHYLENE (HDPE) BOXES AND LIDS.

**ATTENTION:** THESE BOXES AND LIDS ARE TO BE USED ON SECONDARY ONLY. THE STRENGTH DESIGN RATING OF BOX AND LID IS TIER 22 (22,500 LBS). NOT TRAFFIC RATED.




## INSTALLATION:

A. TO SECURE THE SHIELD COVER TO THE BOX, USE TWO PENTA LAG SCREWS PROVIDED WITH THE UNIT.

B. TO SECURE THE RAISING RING TO THE BOX, LOCATE THE LARGER HOLES ON THE RING AND ATTACH TO THE BOX USING TWO LAG SCREWS. ATTACH THE SHIELD COVER TO THE RING USING THE TWO PENTA LAG SCREWS.

C. A SHIELD COVER MAY BE USED TO REPLACE A CONCRETE LID. TO ATTACH THE SHIELD COVER TO A CONCRETE BOX, TWO SWING BOLTS MUST BE USED.

D. A RAISING RING MAY BE USED TO RAISE THE HEIGHT OF A CONCRETE BOX. TO ATTACH THE RING TO THE BOX, CLEAN THE TOP OF THE BOX AND INSERT THE RING BY APPLYING PRESSURE. NO BOLTS ARE REQUIRED. USE TWO PENTA LAG SCREWS TO SECURE THE SHIELD COVER TO THE RAISING RING.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STOCK NUMBER | ASSEMBLY UNIT |
|---|---|---|---|---|
| 1 | SHIELD COVER | 1 | S286750 | 3312SH |
| 2 | HDPE AND SHIELD COVER | 1 | S162424 | 3312CB |
| 3 | RAISING RING | 1 | S596750 | 3312RR |
| 4 | LIFT PIN COVER | 1 | -- | -- |

## NOTES:

(I) THE RAISING RING CAN BE USED FOR RAISING THE LID 2-1/2".

(II) TO LIFT THE LID, REMOVE THE LIFT PIN COVER AND REPLACE WHEN DONE. (MUST BE IN PLACE TO PREVENT TRIPPING HAZARD PER AMERICAN DISABILITY ACT.)

**REFERENCE:** NONE

© 1998 - 2019 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | JC | JS | CZH | 4/22/2019 | F | | | | | |
| B | BILL OF MATERIALS & NOTES UPDATE | JC | JS | CZH | 12/1/2018 | E | | | | | |
| A | ORIGINAL ISSUE | JC | JS | CZH | 7/9/2018 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRCUTION STANDARD



HDPE HANDHOLE
(HIGH DENSITY POLYETHYLENE)

UG3312.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3312 HANDHOLE.


**ATTENTION:** THE 3312 IS FOR LIKE IN-KIND REPLACEMENT **ONLY**. IF SPACE IS AVAILABLE, A 3309.1 OR 2 SHOULD BE USE TO REPLACE THEM. THE 3309.1&2 IS THE PREFERRED BOX FOR PARKWAY SECONDARY INSTALLATIONS.

THE 3312 WILL STILL BE THE BOX USED FOR UNDER PAD APPLICATION AT THIS TIME


3312 HANDHOLE

**CONCRETE PARKWAY COVER**
WEIGHT: 110 POUNDS (MAX.)
(II) PEDESTRIAN LOADING


"ELECTRIC"
IF THE CUSTOMER IS REQUIRED TO INSTALL A HANDHOLE IN A SERVICE LATERAL, THE LID SHALL BE MARKED "ELECTRIC" NOT SDG&E.





(I) **POLYMER PARKWAY COVER**
WEIGHT: 64 POUNDS (MAX.)
(II) PEDESTRIAN LOADING




**BODY**
WEIGHT: 185 POUNDS (MAX.)





TYPICAL PLAN VIEW





EXCAVATION DIMENSIONS

SINGLE HANDHOLE INSTALLATION




DOUBLE HANDHOLE INSTALLATION




© 1998 - 2019 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | JC | JS | CZH | 4/22/2019 | F | | | | | |
| B | BILL OF MATERIALS & NOTES UPDATE | JC | JS | CZH | 12/1/2018 | E | | | | | |
| A | ORIGINAL ISSUE | JC | JS | CZH | 7/9/2018 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRCUTION STANDARD

HANDHOLE
(INSIDE DIMENSIONS - 17" X 30")



UG3312.2

TABLE OF CONTENTS

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO GAS AND FOREIGN UTILITY PLACEMENTS. ANY CHANGE IN LOCATION BY DISTRICT CONSTRUCTION REQUIRES PRIOR APPROVAL FROM SERVICE PLANNING.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER DRAWING ABOVE. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW EXTRA SPACE FOR SETTING THE SUBSTRUCTURE AND TAMPING THE BACKFILL.

C. TO DETERMINE FINAL GRADE, MEASURE FROM THE TOP OF CURB OR ESTABLISHED GRADE.

D. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE. SET HANDHOLE AT FINAL GRADE.

(E) IF RIGHT OF WAY OR OBSTRUCTIONS CAUSE A PROBLEM, THE HANDHOLE MAY BE TURNED TO WHERE THE LONG SIDE OF THE HANDHOLE PARALLELS THE SIDEWALK OR PROPERTY LINE.

## BILL OF MATERIALS FOR SINGLE-BODY HANDHOLE:

| ITEM | DESCRIPTION | QUANTITY | STOCK NUMBER | STOCK NUMBER | ASSEMBLY UNITS | |
|---|---|---|---|---|---|---|
| 1 | COVER, PARKWAY (CONCRETE) | 1 | S286808 | COMPLETE HANDHOLE S162676 | 3312C0 | COMPLETE HANDHOLE 3312-1 |
| 2 | BODY, HANDHOLE | 1 | S162426 | | 3312-0 | |
| 3 (I) | COVER, PARKWAY (POLYMER) | 1 | S286818 | -- | 3312CP | -- |

## BILL OF MATERIALS FOR DOUBLE-BODY HANDHOLE:

| ITEM | DESCRIPTION | QUANTITY | STOCK NUMBER | STOCK NUMBER | ASSEMBLY UNITS | |
|---|---|---|---|---|---|---|
| 1 | COVER, PARKWAY (CONCRETE) | 1 | S286808 | COMPLETE DOUBLE-BODY HANDHOLE S162678 | 3312C0 | COMPLETE HANDHOLE 3312-2 |
| 2 | BODY, HANDHOLE | 2 | S162426 | | 3312-0 | |
| 3 (I) | COVER, PARKWAY (POLYMER) | 1 | S286818 | -- | 3312CP | -- |

## NOTES:

(I) THE POLYMER COVER CAN BE USED FOR REPLACEMENT OF BROKEN CONCRETE LIDS.

(II) USE THE 3313 HANDHOLE AND STEEL TRAFFIC COVER FOR TRAFFIC INSTALLATIONS.

## REFERENCE:

a. SEE STANDARD 3302 FOR SUBSTRUCTURE APPLICATIONS.

b. SEE STANDARD 3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

c. SEE STANDARD 3485 WHEN SETTING HANDHOLE ON A SLOPING GRADE.

d. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

e. SEE STANDARD 3605 FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS).

f. SEE STANDARD 4173 FOR TRENCH DEPTH, CONDUIT AND CABLE INSTALLATION.

g. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

© 1998 - 2019 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | JC | JS | CZH | 4/22/2019 | F | | | | | |
| B | BILL OF MATERIALS & NOTES UPDATE | JC | JS | CZH | 12/1/2018 | E | | | | | |
| A | ORIGINAL ISSUE | JC | JS | CZH | 7/9/2018 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRCUTION STANDARD

HANDHOLE
(INSIDE DIMENSIONS - 17" X 30")



UG3312.3

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3313 NON-TRAFFIC RATED, ELECTRIC DISTRIBUTION AND COMMUNICATION HANDHOLES.





**FIGURE 1**
PARKWAY EZ-LIFT ALUMINUM COVER (V)
3313 HANDHOLE





**FIGURE 4**
6" TOP SECTION
3313 HANDHOLE





**FIGURE 5**
6" INTERMEDIATE
EXTENSION SECTION
3313 HANDHOLE





**FIGURE 2**
STEEL PARKWAY COVER
3313 HANDHOLE
FIELD MAINTENANCE
ONLY





**FIGURE 6**
18" BASE SECTION
3313 HANDLE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3313 NON-TRAFFIC RATED ELECTRIC DISTRIBUTION HANDHOLE
PRECAST CONCRETE
(OD - 44" X 32")



UG3313.1





**FIGURE 7**
EXCAVATION DIMENSIONS





**FIGURE 8**
TYPICAL PLAN VIEW

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO GAS AND FOREIGN UTILITY PLACEMENTS. RELOCATING THE HANDHOLE REQUIRES PRIOR APPROVAL FROM A CUSTOMER PROJECT PLANNER.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER FIGURES 7 & 8. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW EXTRA SPACE FOR SETTING THE SUBSTRUCTURE AND TAMPING THE BACKFILL.

C. TO DETERMINE FINAL GRADE, MEASURE FROM THE TOP OF CURB OR ESTABLISHED GRADE.

D. WHEN EXCAVATION IS PREPARED, INSTALL A MINIMUM OF 2 INCHES CLASS 2 BASE, THEN INSTALL SUBSTRUCTURE SECTION(S). SET HANDHOLE AT FINAL GRADE. PLACE PLASTIC-MASTIC SEALANT BETWEEN ALL SECTIONS.

(E) APPLY LUBRICANT (EZ-1) TO THE BOLTS WHEN SECURING THE COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. TIGHTEN DOWN BOLTS WITH TORQUE WRENCH TO 30 FT-LBS. MIN., 40 FT-LBS. MAX.

(F) IF RIGHT OF WAY OR OBSTRUCTIONS CAUSE A PROBLEM, THE HANDHOLE MAY BE TURNED TO WHERE THE LONG SIDE OF THE HANDHOLE PARALLELS THE SIDEWALK OR PROPERTY LINE. IF THE HANDHOLE HOUSES A CABLE TAP, THE HANDHOLE IS NOT TO BE TURNED AND THE TYPICAL PLAN VIEW OUTLINED IN THE STANDARD MUST BE FOLLOWED (CABLE TAP IS MOUNTED ON THE END OF HANDHOLE AND THE FIVE-FOOT CLEARANCE FOR HOT STICK OPERATION WOULD BE ON THE SIDEWALK SIDE).

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

## INSTALLATION (CONT'D):

(G) THE 6-INCH INTERMEDIATE SECTION IS NEEDED IN THE 3313 HANDHOLE FOR THE FOLLOWING SCENARIOS:

1. SECONDARY HANDHOLE WITH 2 OR MORE RUNS OF 350 CABLE
2. SECONDARY HANDHOLE WITH 7 OR 8 SECONDARY/SERVICE RUNS
3. PRIMARY ONLY HANDHOLE

(H) IF STANDARD DIMENSION CANNOT BE MET, FILL WITH 1-SACK SLURRY.

## ATTENTION:

* LOCATE SECONDARY CONDUITS WITHIN 12 INCHES OF THE END OF THE HANDHOLE CLOSEST TO THE SIDEWALK.

** GENERAL INSTALLATION NOTES:

1. INSTALL HINGED SIDE ON SAME SIDE OF RACK OR EQUIPMENT.
2. RACKS SHOULD BE LOCATED IN SUCH A WAY THAT THE OPEN LID DOES NOT IMPEDE ACCESS TO HANDHOLE EQUIPMENT.
3. INSTALL HINGED SIDE AS THE SAME SIDE AS ROADSIDE OR CURB (IN MOST APPLICATIONS).

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS MAX) | QUANTITY | STANDARD PAGE | STOCK NUMBER | | DESIGN UNITS | |
|---|---|---|---|---|---|---|---|---|
| **INTERMEDIATE SECTION AND MISCELLANEOUS ITEMS - ADD AS NEEDED** | | | | | | | | |
| 1 | EXTENSION SECTION, INTERMEDIATE, 6", 2'-0" X 3'-0" (FIG. 5) | 267 | AS REQ'D | -- | S336368 | -- | 3313X1 | -- |
| 2 | LUBRICANT, EZ-1 | -- | AS REQ'D | -- | S469764 | -- | -- | |
| 3 | BOLT, PENTAHEAD, 1/2" X 1 1/2" | -- | 6 | -- | S156004 | -- | -- | |
| 4 | SEALANT, PLASTIC-MASTIC | -- | AS REQ'D | -- | S631872 | -- | -- | |
| **PARKWAY 3313 EZ-LIFT ELECTRIC DISTRIBUTION HANDHOLE** | | | | | | | | |
| 5 | COVER, PARKWAY, EZ-LIFT TILT-UP, (FIG. 1) | 96 | 1 | -- | S286836 | -- | 3313PKEZ | 3313PCEZ |
| 9 | TOP SECTION, 6", (FIG. 4) | 285 | 1 | -- | S336218 | -- | 3313X6 | |
| 10 | BASE SECTION, 18", (FIG. 6) | 885 | 1 | -- | S162664 | -- | 3313-B | |

## NOTES:

(I) IF THE CUSTOMER IS REQUIRED TO INSTALL A HANDHOLE IN A SERVICE LATERAL, THE LID SHALL BE MARKED. "ELECTRIC" NOT "SDG&E".

(II) TO BE ORDERED ONLY FOR ADDITIONAL HEIGHT.

(III) NOT TO BE INSTALLED IN DIRECT TRAFFIC. APPROVED FOR USE IN AREAS OF INDIRECT TRAFFIC SUCH AS ALLEYWAYS, DRIVEWAYS, PARKING LOTS, ETC.

(IV) NOT SHOWN ON FIGURES

(V) ALLOWED ONLY IN AREAS WHERE NO TRAFFIC IS PERMITTED (E.G. SIDEWALKS, GRASS, ETC.)

(VI) INCLUDES ITEMS 9 AND 10.

VII. ONLY HINGED COVERS SHOULD BE INSTALLED NEW INSTALLATIONS OR HH REBUILD.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3313 NON-TRAFFIC RATED ELECTRIC DISTRIBUTION HANDHOLE
PRECAST CONCRETE
(OD - 44" X 32")

**REFERENCE:**

(a) FOR INSTALLATION ON IDENTIFICATION TAG, SEE UG3211.

b. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

c. FOR INSTALLATION OF PLASTIC-MASTIC SEALANT, SEE UG3306.

d. FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UG3480, UG3482 AND UG3483.

e. FOR SETTING HANDHOLE ON A SLOPING GRADE, SEE UG3485.

f. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487 AND UG3488.

g. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS), SEE UG3605.

h. FOR CABLE TAP, GROUND GRID AND CONDUIT INSTALLATION ON 6.9 ONE-PHASE SYSTEM, SEE UG3660.

i. FOR POSITIONING SECONDARY CONDUITS, SEE UG3312.

j. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3313 NON-TRAFFIC RATED ELECTRIC DISTRIBUTION HANDHOLE
PRECAST CONCRETE
(OD - 44" X 32")

UG3313.4

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR 3313-L, 3313-T, AND 3313-XL HANDHOLES.





**FIGURE 1**
STEEL DIRECT TRAFFIC
FRAME AND HINGED COVER
3313-T ELECTRIC - HANDHOLE
PLAN VIEW






**FIGURE 2**
STEEL DIRECT TRAFFIC
FRAME AND HINGED COVER
3313-L COMM - HANDHOLE
PLAN VIEW




**FIGURES 1 AND 2**
STEEL DIRECT TRAFFIC FRAME AND HINGED COVER
3313-L COMM - HANDHOLE
3313-T ELECTRIC - HANDHOLE
VIEW A-A





**FIGURE 3**
18" BASE SECTION
3313-L COMM - HANDHOLE
3313-T ELECTRIC - HANDHOLE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |





**FIGURE 4**
STEEL DIRECT TRAFFIC
FRAME AND HINGED COVER
3313-XL COMM - HANDHOLE
PLAN VIEW





**FIGURE 4**
STEEL DIRECT TRAFFIC FRAME AND HINGED COVER
3313-XL COMM - HANDHOLE
VIEW A-A





**FIGURE 5**
18" BASE SECTION
3313-XL COMM - HANDHOLE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

Indicates Latest Revision | X Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3313-XL DIRECT TRAFFIC RATED COMM HANDHOLE
PRECAST CONCRETE
(OD - 60" X 42")

UG3313.6





**FIGURE 6**
EXCAVATION DIMENSIONS





**FIGURE 7**
TYPICAL PLAN VIEW

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO GAS AND FOREIGN UTILITY PLACEMENTS. RELOCATING THE HANDHOLE REQUIRES PRIOR APPROVAL FROM A CUSTOMER PROJECT PLANNER.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER FIGURES 6 & 7. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW EXTRA SPACE FOR SETTING THE SUBSTRUCTURE AND TAMPING THE BACKFILL.

C. TO DETERMINE FINAL GRADE, MEASURE FROM THE TOP OF CURB OR ESTABLISHED GRADE.

D. WHEN EXCAVATION IS PREPARED, INSTALL A MINIMUM OF 2 INCHES CLASS 2 BASE, THEN INSTALL SUBSTRUCTURE SECTION. SET HANDHOLE AT FINAL GRADE. PLACE PLASTIC-MASTIC SEALANT BETWEEN ALL SECTIONS.

E. APPLY LUBRICANT (EZ-1) TO BOLTS WHEN SECURING THE COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. TIGHTEN DOWN BOLTS WITH TORQUE WRENCH TO 30 FT-LBS. MIN., 40 FT-LBS. MAX.

(F) IF RIGHT OF WAY OR OBSTRUCTIONS CAUSE A PROBLEM, THE HANDHOLE MAY BE TURNED TO WHERE THE LONG SIDE OF THE HANDHOLE PARALLELS THE SIDEWALK OR PROPERTY LINE. IF THE HANDHOLE HOUSES A CABLE TAP, THE HANDHOLE IS NOT TO BE TURNED AND THE TYPICAL PLAN VIEW OUTLINED IN THE STANDARD MUST BE FOLLOWED (CABLE TAP IS MOUNTED ON THE END OF HANDHOLE AND THE FIVE-FOOT CLEARANCE FOR HOT STICK OPERATION WOULD BE ON THE SIDEWALK SIDE).

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |



TABLE OF CONTENTS

## ATTENTION:

* LOCATE SECONDARY CONDUITS WITHIN 12 INCHES OF THE END OF THE HANDHOLE CLOSEST TO THE SIDEWALK.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS MAX) | QUANTITY | STANDARD PAGE | STOCK NUMBER | | DESIGN UNITS | |
|---|---|---|---|---|---|---|---|---|
| **DIRECT TRAFFIC RATED 3313-T AND 3313-L HANDHOLE (OD - 48" X 36")** | | | | | | | | |
| 1 | COVER, FRAME AND LID, DIRECT TRAFFIC - ELECTRIC, 3313-T | 921 | 1 | -- | S286752 | -- | 3313T | -- |
| 2 | COVER, FRAME AND LID, DIRECT TRAFFIC - SDG&E COMM, 3313-L | 921 | 1 | -- | -- | S400314 | -- | 3313COMM |
| 3 | BASE SECTION, 18" (3313-L) (VIII) | 878 | 1 | -- | S286754 | | 3313LB | |
| **DIRECT TRAFFIC RATED 3313-XL HANDHOLE (OD - 60" X 42")** | | | | | | | | |
| 4 | COVER, FRAME AND LID, DIRECT TRAFFIC - SDG&E COMM | 1,632 | 1 | -- | -- | S400316 | -- | 3313CM |
| 5 | BASE SECTION, 18" (3313-XL) | 1,169 | 1 | -- | -- | | -- | |

## NOTES:

I. HANDHOLE SECTIONS AND PARKWAY COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE.

II. THE PREFERRED LOCATION FOR A 3313 HANDHOLE IS IN NON-VEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.). USE A PARKWAY COVER IN THESE AREAS.

III. HANDHOLES WITH A DIRECT TRAFFIC COVER MAY BE INSTALLED IN AREAS WITH VEHICULAR TRAFFIC, BUT ONLY WHEN THERE IS NO NON-TRAFFIC LOCATION AVAILABLE.

IV. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

(V) IF THE CUSTOMER IS REQUIRED TO INSTALL A HANDHOLE IN A SERVICE LATERAL, THE LID SHALL BE MARKED. "ELECTRIC" NOT "SDG&E".

(VI) INCLUDES ITEMS 2 AND 3

(VII) INCLUDES ITEMS 4 AND 5

(VIII) FOR 3313-T, THIS ITEM MAY BE ORDERED SEPARATELY.

## REFERENCE:

(a) FOR INSTALLATION ON IDENTIFICATION TAG, SEE UG3211.

b. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

c. FOR INSTALLATION OF PLASTIC-MASTIC SEALANT, SEE UG3306.

d. FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UG3480, UG3482 AND UG3483.

e. FOR SETTING HANDHOLE ON A SLOPING GRADE, SEE UG3485.

f. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487 AND UG3488.

g. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS), SEE UG3605.

h. FOR CABLE TAP, GROUND GRID AND CONDUIT INSTALLATION ON 6.9 ONE-PHASE SYSTEM, SEE UG3660.

i. FOR POSITIONING SECONDARY CONDUITS, SEE UG3312.

j. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

(k) SEE CITY CODE FOR ASPHALT REQUIREMENTS.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | JES | CZH | 10/04/2021 | F | | | | | | |
| B | ADD 3313 L & XL | - | - | GW | JS | 06/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | - | JS | TR | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

**SCOPE:** THIS STANDARD SHOWS THE MATERIAL AND INSTALLATION REQUIREMENTS FOR A 3314 HANDHOLE.

**ATTENTION:**

* SLIP RESISTANT SURFACE REQUIRED






**FIGURE 1**
3314 CONCRETE PARKWAY
HANDHOLE COVER ASSEMBLY







**FIGURE 2**
3314 CONCRETE TRAFFIC
HANDHOLE COVER ASSEMBLY

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |



TABLE OF CONTENTS




(OPEN FRONT VIEW)



(OPEN BACK VIEW)

**FIGURE 2**
3314 CONCRETE HANDHOLE COVER ASSEMBLY








**FIGURE 3**
B-BOX COVER





**FIGURE 4**
6" INTERMEDIATE EXTENSION SECTION





**FIGURE 5**
12" INTERMEDIATE EXTENSION SECTION (IV)

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |





**FIGURE 6**
BASE ENCLOSURE
(3'X6'X3')





**FIGURE 7**
EXCAVATION DIMENSIONS
PARKWAY COVER ASSEMBLY

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 3'-0" X 6'-0")

UG3314.3

TABLE OF CONTENTS





**FIGURE 8**
EXCAVATION DIMENSIONS TOP VIEW
TRAFFIC COVER ASSEMBLY
EXISTING HANDHOLE
WITH CABLE TAPS ON "CURB SIDE"





**FIGURE 9**
EXCAVATION DIMENSIONS TOP VIEW
TRAFFIC COVER ASSEMBLY
EXISTING HANDHOLE
WITH CABLE TAPS ON "STREET SIDE"





**FIGURE 10**
EXCAVATION DIMENSIONS TOP VIEW
TRAFFIC COVER ASSEMBLY
EXISTING HANDHOLE
NO CABLE TAPS





**FIGURE 11**
INSTALLATION DRAWING
BASE ENCLOSURE

TABLE OF CONTENTS

## INSTALLATION:

### HANDHOLE WITH PARKWAY COVER ASSEMBLY

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE HANDHOLE REQUIRES APPROVAL FROM PROJECT MANAGEMENT.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER FIGURE 8. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW AN EXTRA 8 INCHES FOR SETTING THE SUBSTRUCTURE.

C. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. PLACE PLASTIC-MASTIC SEALANT BETWEEN ALL SECTIONS. DO NOT APPLY SEALANT UNDER THE TOP SECTION IF CONCRETE IS REQUIRED FOR GRADE ADJUSTMENT. ASSURE THE SUBSTRUCTURE WALLS ARE STRAIGHT AND THE FLOOR IS LEVEL.

D. TO DETERMINE FINAL GRADE ONE OF THE TWO FOLLOWING METHODS MAY BE USED:

1. WHEN CURB OR GRADE LEVEL IS ALREADY ESTABLISHED, MEASURE FROM THE TOP OF CURB OR GRADE.
2. HAVE THE FIELD ENGINEER SET GRADE STAKES. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE LEVEL.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## INSTALLATION (CONT'D):

(E) EXCAVATION DEPTH ALLOWS 3 INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL 3 INCHES FOR PLACEMENT OF GRAVEL AS BASE SUPPORT.

F. ALIGN HANDHOLE COVER TO FINAL GRADE USING BRICKS OR WOODEN WEDGES. BEFORE POURING CONCRETE (4-SACK MIX WITH 3/8 INCH PEA GRAVEL, OR AS REQUIRED BY CITY OR COUNTY CODES), FRAME THE INSIDE OPEN AREA BETWEEN SECTIONS CONCRETE CAN BE POURED FROM THE OUTSIDE OF THE TOP COVER SECTION. MAKE SURE THE BRICKS OR WOODEN WEDGES DO NOT SHOW FROM THE INSIDE ONCE THE CONCRETE IS POURED. THE INSIDE FRAME MAY BE OMITTED IF THE CONCRETE IS NOT TOO WET. IF FRAME IS OMITTED, TROWEL CONCRETE SMOOTH ON THE INSIDE.

(G) APPLY EZ-1 TO THE PENTAHEAD BOLTS WHEN SECURING THE COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. TIGHTEN DOWN BOLTS WITH TORQUE WRENCH TO 30 FT-LBS MIN., 40 FT-LBS MAX.

**EXISTING HANDHOLE WITH A 3315 TRAFFIC COVER ASSEMBLY**

H. ESTABLISH THE COVER LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS AND CHECK THE LOCATION OF ANY EXISTING CABLE TAPS.

J. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER FIGURES 8-10. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW AN EXTRA 8 INCHES FOR SETTING THE 3315 TRAFFIC COVER ASSEMBLY. EXCAVATING MUST BE DONE ACCURATELY FOR PROPER PLACEMENT OF THE "TRAFFIC COVER ASSEMBLY" ASSURING CABLE TAP ACCESS FOR HOT STICK OPERATION.

K. IF COVER IS GOING TO BE SET IN ANY PORTION OF A CONCRETE GUTTER OR STREET, THE CONCRETE MUST BE "SAWCUT" BEFORE EXCAVATING. ASPHALT MUST BE SCORED WITH A JACKHAMMER OR CLAYDIGGER. MEASURE AROUND EXISTING HANDHOLE AND CUT ACCORDINGLY.

L. DIG DOWN 18 INCHES AND REMOVE THE EXISTING TOP SECTION (OLD STYLE TWO PIECE METAL TRAFFIC COVER, SEE 3399.104). IF THE EXISTING TOP SECTION IS 24 INCHES, REMOVE IT AND REPLACE WITH A 12 INCH INTERMEDIATE SECTION.

(M) BEFORE SETTING TRAFFIC COVER NECKING, PAINT THE UNDERSIDE WITH PRIMER. THIS WILL REDUCE ANY REMOVAL DIFFICULTIES IN CASE OF RETROFIT OR GRADE ADJUSTMENTS. SEE FIGURE 11.

(N) SET THE TRAFFIC COVER USING THE INSIDE LIFTING ANCHORS TO PREVENT ANY PROBLEMS REMOVING THE LIFTING DEVICE. LINE UP THE INSIDE EDGE OF THE TRAFFIC COVER NECKING WITH THE INSIDE EDGE OF THE HANDHOLE INTERMEDIATE SECTION ON THE SAME SIDE THE CABLE TAPS ARE LOCATED. IF HANDHOLE DOES NOT HOUSE CABLE TAPS, ALIGN THE INSIDE EDGE OF THE 3315 HANDHOLE TRAFFIC COVER NECKING WITH THE INSIDE EDGE OF THE INTERMEDIATE HANDHOLE SECTION ON THE STREET SIDE. THIS IS THE KEY ALIGNMENT TO THE ENTIRE INSTALLATION. SEE FIGURE 11.

(O) IF ANY OF THE TRAFFIC COVER NECKING WILL BE SET IN CONCRETE (ALONG A CURB OR IN A CONCRETE STREET), WRAP 4 OR 6 MIL POLYETHYLENE SHEETING COMPLETELY AROUND THE NECKING AND TIE WITH TAPE. THIS WILL PREVENT EXISTING CONCRETE AND NEW CONCRETE FROM BONDING MAKING IT EASIER TO RAISE COVER IN THE FUTURE. SEE FIGURE 11.

P. TO DETERMINE FINAL GRADE, ONE OF THE TWO FOLLOWING METHODS MAY BE USED:

1. WHEN CURB OR GRADE LEVEL IS ALREADY ESTABLISHED, MEASURE FROM THE TOP OF CURB OR GRADE.
2. HAVE THE FIELD ENGINEER SET GRADE STAKES. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE LEVEL.

(Q) ALIGN TRAFFIC COVER NECKING TO GRADE USING BRICKS OR WOODEN WEDGES. POUR CONCRETE (4-SACK MIX WITH 3/8 INCH PEA GRAVEL OR AS REQUIRED BY CITY OR COUNTY CODES) INSIDE OF NECKING AND INTO THE OVERLAPPING AREA OF SECTIONS. SMOOTH CONCRETE WITH GROUT AND TROWEL. SEE FIGURE 11.

(R) ON THE OUTSIDE OF THE NECKING, POUR AND PACK CONCRETE UNDERNEATH WITH A SHOVEL UP TO THE BOTTOM OF THE NECKING AND UP TO FINAL GRADE LEVEL AT THE CURB. SMOOTH OUT ANY EXCESS CONCRETE COMING THROUGH ON INSIDE OF HANDHOLE. TRIM AWAY EXCESS PLASTIC SHEETING. SEE FIGURE 11.

(S) INSTALL THE CONCRETE COVER AND CAST IRON COVERS. SLIDE OUTSIDE CAST IRON COVERS ON FIRST AND THE CENTER CAST IRON COVER ON LAST. WHEN REMOVING COVERS, SLIDE CENTER COVER OFF FIRST. SEE FIGURES 1 & 2.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 3'-0" X 6'-0")

UG3314.5

## INSTALLATION (CONT'D):

(T) BEFORE BACKFILLING, SPRAY RS-1 EMULSION TO THE INSIDE OF THE EXCAVATION TO HELP THE ASPHALT ADHERE. BACKFILL EXCAVATION WITH ASPHALT AND TAMP DOWN.

(U) APPLY LUBRICANT (EZ-1) TO THE PENTAHEAD BOLTS WHEN SECURING THE COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. TIGHTEN DOWN BOLTS WITH TORQUE WRENCH TO 30 FT-LBS MIN., 40 FT-LBS MAX.

## ATTENTION:

* GENERAL INSTALLATION NOTES:

1. INSTALL HINGED SIDE ON SAME SIDE OF RACK OR EQUIPMENT.
2. RACKS SHOULD BE LOCATED IN SUCH A WAY THAT THE OPEN LID DOES NOT IMPEDE ACCESS TO HANDHOLE EQUIPMENT.
3. INSTALL HINGED SIDE AS THE SAME SIDE AS ROADSIDE OR CURB (IN MOST APPLICATIONS).

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS MAX.) | QUANTITY | STANDARD PAGE | STOCK NUMBER | | DESIGN UNITS | |
|---|---|---|---|---|---|---|---|---|
| **PARKWAY 3314 HANDHOLE** | | | | | | | | |
| 1 | EXTENSION, TOP SECTION, 12" (VII) | 952 | 1 | -- | S336210 | S400304 | 3314FO | 3314-PC |
| 2 | COVER, PARKWAY. FRAME AND LIDS | 225 | 1 | -- | S636036 | | 3314PC | |
| 3 | ENCLOSURE, BASE, 3'-0" X 6'-0" X 3'-0 (INSIDE DIMENSIONS) | 4,470 | 1 | -- | S162680 | | 3314-B | |
| 4 | SEALANT, PLASTIC-MASTIC (NOT SHOWN) | -- | AS REQ'D | -- | S631872 | | -- | |
| 12 | SILICONE GREASE (NOT SHOWN) | -- | AS REQ'D | -- | S391424 | -- | -- | -- |
| 13 | PRIMER (NOT SHOWN) | -- | AS REQ'D | -- | S557696 | -- | -- | -- |
| 14 | GRAVEL, 3/8"-3/4" | -- | AS REQ'D | -- | -- | -- | -- | -- |
| **TRAFFIC 3314 HANDHOLE** | | | | | | | | |
| 5 | COVER, TRAFFIC, FRAME AND COVER ASSEMBLY (IX) | 2393 | 1 | -- | S286758 | -- | 3314-T | -- |
| 12 | SILICONE GREASE (NOT SHOWN) | -- | AS REQ'D | -- | S391424 | -- | -- | -- |
| 13 | PRIMER (NOT SHOWN) | -- | AS REQ'D | -- | S557696 | -- | -- | -- |
| 14 | GRAVEL, 3/8"-3/4" | -- | AS REQ'D | -- | -- | -- | -- | -- |
| 6 | ITEMS INTENTIONALLY LEFT BLANK | | | | | | | |
| 7 | | | | | | | | |
| 8 | | | | | | | | |
| 9 | | | | | | | | |
| 10 | | | | | | | | |
| **B-BOX & EXTENSION SECTIONS - AS REQUIRED** | | | | | | | | |
| 11 | EXTENSION SECTION, INTERMEDIATE, 12" | 970 | AS REQ'D | -- | S336212 | -- | 3314X1 | -- |
| 15 | COVER, B-BOX | -- | 1 | -- | S514238 | -- | -- | -- |
| 16 | EXTENSION, INTERMEDIATE SECTION, 6" | 485 | 1 | -- | S336214 | -- | -- | -- |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

**NOTES:**

I. HANDHOLE SECTIONS AND PARKWAY COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE.

II. CAST IRON COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE.

III. 3314 PARKWAY COVER ASSEMBLY IS TO BE USED IN NON-TRAFFIC AREAS. 3314 TRAFFIC COVER ASSEMBLY TO BE USED IN TRAFFIC AREAS.

(IV) TO BE ORDERED ONLY FOR ADDITIONAL HEIGHT.

(V) FOR USE IN TRANSFORMER INSTALLATIONS.

VI. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

(VII) WHEN TRAFFIC COVER IS REMOVED CHECK GASKET MATERIAL AND REPLACE AS NEEDED. SDG&E STOCK NUMBER (S341020).

(VIII) WEIGHT DOES NOT INCLUDE COVERS.

(IX) DESIGNED TO BE LIFTED AT 5,500 PSI WITH 4 LIFT CONNECTIONS EQUALLY LOADED TO 4 LIFTING POINTS AT A MINIMUM 90 DEG SLING ANGLE, MEASURED FROM HORIZONTAL.

XI. ONLY HINGED COVERS SHOULD BE USED ON NEW INSTALLATIONS OR HH REBUILD.

**REFERENCE:**

(a) SEE UG3211 FOR INSTALLATION OF IDENTIFICATION TAG.

b. SEE UG3302 FOR SUBSTRUCTURE APPLICATIONS.

c. SEE UG3306 FOR INSTALLATION OF PLASTIC-MASTIC SEALANT.

(d) SEE UG3366 FOR SLURRY BACKFILL.

e. SEE UG3482 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

f. SEE UG3485 WHEN SETTING HANDHOLE ON A SLOPING GRADE.

g. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3605 FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS).

i. SEE PAGES 3399.105 AND 3399.106 FOR REPAIRING "OLD STYLE" 3314 HANDHOLES WITH PARKWAY COVERS.

j. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 | F | | | | | | |
| B | FIGURE UPDATE | EDM | ADW | JES | CZH | 08/13/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENT FOR A 3315 HANDHOLE.

**ATTENTION:**

* SLIP RESISTANT COATING REQUIRED.





**FIGURE 1**
PARKWAY COVER ASSEMBLY
3315 HANDHOLE





**FIGURE 2**
TRAFFIC COVER ONLY
3315 HANDHOLE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/27/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | ADW | JES | CZH | 04/13/2020 | E | FIGURE UPDATE | ARC | ADW | JES | KRG | 03/09/2023 |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 4'-0" X 6'-6")

UG3315.1

TABLE OF CONTENTS





**FIGURE 3**
PARKWAY FLUSH COVER ASSEMBLY (G)

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/27/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | ADW | JES | CZH | 04/13/2020 | E | FIGURE UPDATE | ARC | ADW | JES | KRG | 03/09/2023 |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 4'-0" X 6'-6")

UG3315.2

TABLE OF CONTENTS





**FIGURE 4**
HANDHOLE BODY SECTIONS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/27/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | ADW | JES | CZH | 04/13/2020 | E | FIGURE UPDATE | ARC | ADW | JES | KRG | 03/09/2023 |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 4'-0" X 6'-6")

UG3315.3





**FIGURE 5**
EXCAVATION DIMENSIONS

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE HANDHOLE REQUIRES APPROVAL FROM PROJECT MANAGEMENT.

B. AFTER THE LOCATION IS ESTABLISHED MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER FIGURE 5. THE WIDTH AND LENGTH DIMENSIONS GIVEN, ALLOW AN EXTRA 8 INCHES FOR SETTING THE SUBSTRUCTURE.

C. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. PLACE PLASTIC-MASTIC SEALANT BETWEEN ALL SECTIONS. USE DOUBLE SEAL IF FIELD CONDITIONS INDICATE THAT WATER WILL PENETRATE THE JOINTS. DO NOT APPLY SEALANT UNDER THE TOP SECTION IF CONCRETE IS REQUIRED FOR GRADE ADJUSTMENT. ASSURE THE SUBSTRUCTURE WALLS ARE STRAIGHT AND THE FLOOR IS LEVEL.

D. TO DETERMINE FINAL GRADE, ONE OF THE FOLLOWING METHODS MAY BE USED:

1. WHEN CURB OR GRADE LEVEL IS ALREADY ESTABLISHED, MEASURE FROM THE TOP OF CURB OR GRADE OR
2. HAVE THE FIELD ENGINEER SET THE GRADE STAKES. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE LEVEL.

E. ALIGN HANDHOLE COVER TO FINAL GRADE USING BRICKS OR WOODEN WEDGES. BEFORE POURING CONCRETE (4-SACK MIX WITH 3/8-INCH PEA GRAVEL OR AS REQUIRED BY CITY OR COUNTY CODES), FRAME THE INSIDE OPEN AREA BETWEEN SECTIONS SO CONCRETE CAN BE POURED FROM THE OUTSIDE OF THE TOP COVER SECTION. MAKE SURE THE BRICKS OR WOODEN WEDGES DO NOT SHOW FROM THE INSIDE ONCE THE CONCRETE IS POURED. THE INSIDE FRAME MAY BE OMITTED IF THE CONCRETE IS NOT TOO WET. IF FRAME IS OMITTED, TROWEL CONCRETE SMOOTH ON THE INSIDE.

F. INSTALL CONDUITS USING THE BOTTOM OUTSIDE (CLOSEST TO THE WALL) KNOCKOUTS FIRST.

(G) EXCAVATION DEPTH ALLOWS 3 INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL 3 INCHES FOR REPLACEMENT OF GRAVEL AS BASE SUPPORT.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/27/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | ADW | JES | CZH | 04/13/2020 | E | FIGURE UPDATE | ARC | ADW | JES | KRG | 03/09/2023 |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

## ATTENTION:

* GENERAL INSTALLATION NOTES:

1. INSTALL HINGED SIDE ON SAME SIDE OF RACK OR EQUIPMENT.
2. RACKS SHOULD BE LOCATED IN SUCH A WAY THAT THE OPEN LID DOES NOT IMPEDE ACCESS TO HANDHOLE EQUIPMENT.
3. INSTALL HINGED SIDE AS THE SAME SIDE AS ROADSIDE OR CURB (IN MOST APPLICATIONS).

## BILL OF MATERIALS:

| PARKWAY 3315 HANDHOLE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| **ITEM** | **DESCRIPTION** | **WEIGHT (LBS.)** | **QUANTITY** | **STANDARD PAGE** | **STOCK NUMBER** | **STOCK NUMBER** | **DESIGN UNITS** | |
| 1 | FRAME, PARKWAY, 12" (IX) | 1,690 MAX. | 1 | - | S361354 | S400306 (VIII) | 3315FO | 3315PC |
| 2 | COVER, ALUMINUM PARKWAY FRAME & COVERS | 290 MAX. | 1 | - | S636040 | | 3315A1 | |
| | COVER, ALUMINUM PARKWAY, FLUSH MOUNT, HINGED | - | 1 | - | S286986 (XI) | | 3315OT (XI) | |
| | | | | | S286736 (XII) | | 7CO-15 (XII) | |
| 6 | ENCLOSURE, 60" BASE | 11,320 MAX. | 1 | - | S334356 | | - | |
| 7 | BOLT, PENTAHEAD, 1/2" X 2 1/2" | - | 12 | - | S156012 | | - | |
| 8 | SEALANT, PLASTIC-MASTIC (XIII) | - | AS REQ'D | - | S631872 | - | - | |
| 9 | LUBRICANT, EZ-1 (XIII) | - | AS REQ'D | - | S469764 | - | - | - |
| 10 | EXTENSION SECTION, SPECIAL 12" (FOR USE IN 3440 SWITCH PAD INST. OR FOR GRADING AND/OR ADDITIONAL HEADROOM) | 1,725 MAX. | AS REQ'D | - | S336246 | - | 3315X1 | - |
| 11 | EXTENSION SECTION, 24" (USE FOR GRADING AND/OR ADDITIONAL HEADROOM) | 3,450 MAX. | AS REQ'D | - | S336240 | - | 3315X2 | - |
| 12 | GRAVEL, 3/8" - 3/4" | - | AS REQ'D | - | - | - | - | - |
| **TRAFFIC 3315 HANDHOLE** | | | | | | | | |
| 3 | 3315 CONCRETE TRAFFIC PLUG W/HINGED COVER | 3,037 LB | 1 | - | S400328 | - | 3315HTC | 3315HTA |
| 4 | ENCLOSURE, BASE, 60" (INSIDE DIMENSION) | 11,320 MAX. | 1 | - | S334356 | - | 3315BSEC | |
| 5 | SEALANT, PLASTIC-MASTIC | - | AS REQ'D | - | S631872 | - | - | |
| 6 | LUBRICANT EZ-1 (XIII) | - | AS REQ'D | - | S469764 | - | - | |
| 7 | EXTENSION SECTION, 12" (FOR USE IN 3440 SWITCH PAD INST. OR FOR GRADING AND/OR ADDITIONAL HEADROOM) | 1,725 MAX. | AS REQ'D | - | S336246 | - | 3315X1 | - |
| 8 | EXTENSION SECTION, 24" (USE FOR GRADING AND/OR ADDITIONAL HEADROOM) | 3,450 MAX. | AS REQ'D | - | S336240 | - | 3315X2 | - |
| 9 | GRAVEL, 3/8"-3/4" | - | AS REQ'D | - | - | - | - | - |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/27/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | ADW | JES | CZH | 04/13/2020 | E | FIGURE UPDATE | ARC | ADW | JES | KRG | 03/09/2023 |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

**NOTES:**

I. HANDHOLE SECTIONS AND PARKWAY COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE.

II. CAST IRON COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE.

III. THE PREFERRED LOCATION FOR A 3315 HANDHOLE IS IN NONVEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.). USE A PARKWAY COVER IN THESE AREAS.

IV. HANDHOLES WITH A TRAFFIC COVER MAY BE INSTALLED IN AREAS WITH VEHICULAR TRAFFIC, BUT ONLY WHEN THERE IS NO NON-TRAFFIC LOCATION AVAILABLE.

V. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

VI. 3315 HANDHOLES ARE DELIVERED BY THE SUPPLIER TO JOB SITE.

(VII) WHEN TRAFFIC COVER IS REMOVED CHECK GASKET MATERIAL AND REPLACE AS NEEDED. SDG&E STOCK NUMBER (S341020).

(VIII) DOES NOT INCLUDE FLUSH MOUNT COVER.

(IX) WEIGHT DOES NOT INCLUDE COVERS.

(XI) USED ONLY FOR CMP REPLACEMENTS.

(XII) USED FOR NEW CONSTRUCTION AND NON-CMP RELATED REPLACEMENTS.

(XIII) NOT SHOWN OF FIGURES.

**REFERENCE:**

(a) FOR INSTALLATION OF IDENTIFICATION TAG, SEE UG3211 AND UG3212.

b. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

c. FOR INSTALLATION OF PLASTIC-MASTIC SEALANT, SEE UG3306.

(d) FOR SLURRY BACKFILL, SEE UG3365 AND UG3366.

e. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

f. FOR SETTING HANDHOLE ON A SLOPING GRADE, SEE UG3485.

g. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488.

h. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS), SEE UG3605.

i. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/27/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | ADW | JES | CZH | 04/13/2020 | E | FIGURE UPDATE | ARC | ADW | JES | KRG | 03/09/2023 |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 4'-0" X 6'-6")

UG3315.6

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3316 HANDHOLE.

**ATTENTION:**

* SLIP RESISTANT COATING REQUIRED.





**FIGURE 1**
PARKWAY COVER ASSEMBLY





**FIGURE 2**
TRAFFIC COVER ASSEMBLY

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | ADW | JES | CZH | 11/12/2019 | F | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |
| B | EDITORIAL CHANGES | - | DG | JS | CZH | 12/01/2018 | E | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 08/12/2015 | D | BILL OF MATERIALS UPDATE | EDM | ADW | JES | CZH | 11/09/2020 |



TABLE OF CONTENTS





**FIGURE 3**
PARKWAY FLUSH COVER ASSEMBLY

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | ADW | JES | CZH | 11/12/2019 | F | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |
| B | EDITORIAL CHANGES | - | DG | JS | CZH | 12/01/2018 | E | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 08/12/2015 | D | BILL OF MATERIALS UPDATE | EDM | ADW | JES | CZH | 11/09/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 5'-0" X 8'-6")

UG3316.2

TABLE OF CONTENTS





**FIGURE 4**
HANDHOLE ASSEMBLY

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | ADW | JES | CZH | 11/12/2019 | F | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |
| B | EDITORIAL CHANGES | - | DG | JS | CZH | 12/01/2018 | E | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 08/12/2015 | D | BILL OF MATERIALS UPDATE | EDM | ADW | JES | CZH | 11/09/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 5'-0" X 8'-6")



UG3316.3

TABLE OF CONTENTS





**FIGURE 5**
EXCAVATION DIMENSIONS

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE HANDHOLE TO ANOTHER LOCATION REQUIRES APPROVAL FROM PROJECT MANAGEMENT.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER FIGURE 5. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW AN EXTRA 8 INCHES FOR SETTING THE SUBSTRUCTURE.

C. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. PLACE PLASTIC-MASTIC SEALANT BETWEEN ALL SECTIONS. USE DOUBLE SEAL IF FIELD CONDITIONS INDICATE THAT WATER WILL PENETRATE THE JOINTS. DO NOT APPLY SEALANT UNDER THE TOP SECTION IF CONCRETE IS REQUIRED FOR GRADE ADJUSTMENT. ASSURE THE SUBSTRUCTURE WALLS ARE STRAIGHT AND THE FLOOR IS LEVEL.

D. TO DETERMINE FINAL GRADE, ONE OF THE TWO FOLLOWING METHODS MAY BE USED:

1. WHEN CURB OR GRADE LEVEL IS ALREADY ESTABLISHED, MEASURE FROM TOP OF CURB OR GRADE OR
2. HAVE THE FIELD ENGINEER SET GRADE STAKES. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE LEVEL.

E. ALIGN HANDHOLE COVER TO FINAL GRADE USING BRICKS OR WOODEN WEDGES. BEFORE POURING CONCRETE (4-SACK MIX WITH 3/8-INCH GRAVEL OR AS REQUIRED BY CITY OR COUNTY CODES), FRAME INSIDE OPEN AREA BETWEEN SECTIONS SO CONCRETE CAN BE POURED FROM OUTSIDE OF TOP COVER SECTION. MAKE SURE BRICKS OR WOODEN WEDGES DO NOT SHOW FROM THE INSIDE ONCE CONCRETE IS POURED. THE INSIDE FRAME MAY BE OMITTED IF THE CONCRETE IS NOT TOO WET. IF FRAME IS OMITTED, TROWEL CONCRETE SMOOTH ON THE INSIDE.

F. INSTALL CONDUITS USING THE BOTTOM OUTSIDE (CLOSEST TO THE WALL) KNOCKOUTS FIRST.

(G) WHEN INSTALLING TRAFFIC COVER, PLACE THE OUTSIDE CAST IRON COVERS ON FIRST, THEN SLIDE THE CENTER CAST IRON COVER ON LAST. WHEN REMOVING CAST IRON COVERS, SLIDE CENTER COVER OFF FIRST. SEE FIGURES 1-4.

(H) APPLY LUBRICANT (EZ-1) TO THE PENTAHEAD BOLTS WHEN SECURING COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. TIGHTEN DOWN BOLTS WITH TORQUE WRENCH TO 30 FT-LBS MIN., 40 FT-LBS MAX.

J. CORE BORE INDENTATIONS ARE PROVIDED AND SHOULD BE UTILIZED WHEN INSTALLING CONDUITS FROM THE SIDE. THESE INDENTATIONS ARE EITHER ON THE INSIDE OR OUTSIDE OF THE LONG SIDE WALLS. DO NOT CORE BORE OTHER THAN THE PROVIDED INDENTATIONS AS IT MAY REDUCE THE STRUCTURAL INTEGRITY.

(K) MAY BE USED WITH UG3341 SWITCH PAD INSTALLATION.

(L) MAY BE USED FOR GRADING AND/OR ADDITIONAL HEADROOM.

(M) EXCAVATION DEPTH ALLOWS 3 INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL 3 INCHES FOR REPLACEMENT OF GRAVEL AS BASE SUPPORT.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | ADW | JES | CZH | 11/12/2019 | F | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |
| B | EDITORIAL CHANGES | - | DG | JS | CZH | 12/01/2018 | E | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 08/12/2015 | D | BILL OF MATERIALS UPDATE | EDM | ADW | JES | CZH | 11/09/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 5'-0" X 8'-6")

UG3316.4

TABLE OF CONTENTS

## ATTENTION:

* GENERAL INSTALLATION NOTES:

1. INSTALL HINGED SIDE ON SAME SIDE OF RACK OR EQUIPMENT.
2. RACKS SHOULD BE LOCATED IN SUCH A WAY THAT THE OPEN LID DOES NOT IMPEDE ACCESS TO HANDHOLE EQUIPMENT.
3. INSTALL HINGED SIDE AS THE SAME SIDE AS ROADSIDE OR CURB (IN MOST APPLICATIONS).

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| **3316 PARKWAY HANDHOLE** | | | | | | | |
| 1 | COVER, PARKWAY, ALUMINUM 4-PC. | 445 TOTAL | 1 | -- | S248164 | COMPLETE PARKWAY HANDHOLE S400310 (VII) | 3316CA |
| | COVER, PARKWAY, ALUMINUM, FLUSH MOUNT, HINGED | -- | 1 | -- | S286756 | | 3316FH |
| 2 | FRAME, PARKWAY, 12" (VIII) | 1,960 MAX. | 1 | -- | S248170 | | 3316FO |
| 8 | ENCLOSURE, BASE, 72" | 16,220 MAX. | 1 | -- | S248174 | | COMPLETE PARKWAY HANDHOLE 3316PC |
| 9 | BOLT, PENTAHEAD, 1/2" X 2 1/2" | -- | 16 | -- | S156012 | | |
| | WASHER, 1/2", FLAT ROUND STAINLESS STEEL | -- | 16 | -- | 799680 | | |
| 10 | SEALANT, PLASTIC-MASTIC (IX) | -- | AS REQ'D | -- | S631872 | | |
| 11 | LUBRICANT EZ-1 (IX) | -- | AS REQ'D | -- | S469764 | | |
| 12 | GRAVEL, 3/8" - 3/4" (3" BASE) | -- | AS REQ'D | -- | -- | | |
| **3316 TRAFFIC HANDHOLE** | | | | | | | |
| 3 | 3316 TRAFFIC PLUG WITH HINGED COVERS | 4,899 MAX. | AS REQ'D | -- | S400326 | -- | 3316HTC |
| 8 | ENCLOSURE, BASE, 72" | 16,220 MAX. | 1 | -- | S248174 | -- | -- |
| 10 | SEALANT, PLASTIC-MASTIC (IX) | -- | AS REQ'D | -- | S631872 | | |
| 11 | LUBRICANT EZ-1 (IX) | -- | AS REQ'D | -- | S469764 | | |
| 12 | GRAVEL, 3/8" - 3/4" (3" BASE) | -- | AS REQ'D | -- | -- | | |
| **3316 SPECIAL EXTENSION SECTIONS** | | | | | | | |
| 6 | EXTENSION SECTION, SPECIAL 12" | 2,175 MAX. | AS REQ'D | -- | S336208 | -- | 3316X1 |
| 7 | EXTENSION SECTION, SPECIAL 24" | 4,350 MAX. | AS REQ'D | -- | S248162 | -- | 3316X2 |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | ADW | JES | CZH | 11/12/2019 | F | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |
| B | EDITORIAL CHANGES | - | DG | JS | CZH | 12/01/2018 | E | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 08/12/2015 | D | BILL OF MATERIALS UPDATE | EDM | ADW | JES | CZH | 11/09/2020 |

**NOTES:**

I. HANDHOLE SECTIONS AND COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE.

II. THE PREFERRED LOCATION FOR A 3316 HANDHOLE IS IN NONVEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.). USE A PARKWAY COVER IN THESE AREAS.

III. HANDHOLES WITH A TRAFFIC COVER MAY BE INSTALLED IN AREAS WITH VEHICULAR TRAFFIC, BUT ONLY WHEN THERE IS NO NON-TRAFFIC LOCATION AVAILABLE.

IV. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

V. 3316 HANDHOLES ARE DELIVERED BY THE SUPPLIER TO JOB SITE.

(VI) WHEN TRAFFIC COVER IS REMOVED, CHECK GASKET MATERIAL AND REPLACE AS NEEDED. SDG&E STOCK NUMBER (S341020).

(VII) DOES NOT INCLUDE FLUSH MOUNT COVER.

(VIII) WEIGHT DOES NOT INCLUDE COVERS.

(IX) NOT SHOWN OF FIGURES.

**REFERENCE:**

(a) FOR INSTALLATION OF IDENTIFICATION TAG, SEE UG3211 AND UG3212.

b. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

c. FOR INSTALLATION OF PLASTIC-MASTIC SEALANT, SEE UG3306.

(d) FOR SLURRY BACKFILL, SEE UG3366.

e. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

f. WHEN SETTING HANDHOLE ON A SLOPING GRADE, SEE UG3485.

g. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488.

h. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS, AND CONDUITS), SEE UG3605.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | ADW | JES | CZH | 11/12/2019 | F | BILL OF MATERIALS UPDATE | ARC | ADW | JES | KRG | 01/16/2023 |
| B | EDITORIAL CHANGES | - | DG | JS | CZH | 12/01/2018 | E | FORMATTING | EDM | JIK | - | - | 10/27/2021 |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 08/12/2015 | D | BILL OF MATERIALS UPDATE | EDM | ADW | JES | CZH | 11/09/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 5'-0" X 8'-6")

UG3316.6

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIRE FOR THE 3317 HANDHOLE.





**FIGURE 1**
12" PARKWAY TOP SECTION AND COVER





**FIGURE 2**
24" EXTENSION SECTION





**FIGURE 3**
47" BASE ENCLOSURE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 6'-0" X 8'-0")



UG3317.1





**FIGURE 4**





**FIGURE 5**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 6'-0" X 8'-0")

UG3317.2

TABLE OF CONTENTS





**FIGURE 6**
EXCAVATION DIMENSIONS

## INSTALLATION:

A. ESTABLISH THE HANDHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE HANDHOLE TO ANOTHER LOCATION REQUIRES APPROVAL FROM PROJECT MANAGEMENT.

B. AFTER THE LOCATION IS ESTABLISHED, MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH, LENGTH AND DEPTH PER DRAWING BELOW. THE WIDTH AND LENGTH DIMENSIONS GIVEN, ALLOW AN EXTRA 8 INCHES MIN. FOR SETTING THE SUBSTRUCTURE.

C. EXCAVATION IS NOW PREPARED FOR INSTALLATION OF SUBSTRUCTURE SECTIONS. PLACE PLASTICMASTIC SEALANT BETWEEN SECTIONS. USE DOUBLE SEAL IF FIELD CONDITIONS INDICATE THAT WATER WILL PENETRATE THE JOINTS. DO NOT APPLY SEALANT UNDER THE TOP SECTION IF CONCRETE IS REQUIRED FOR GRADE ADJUSTMENT. ASSURE THE SUBSTRUCTURE WALLS ARE STRAIGHT AND THE FLOOR IS LEVEL.

D. TO DETERMINE FINAL GRADE, ONE OF THE TWO FOLLOWING METHODS MAY BE USED:

1. WHEN CURB OR GRADE LEVEL IS ALREADY ESTABLISHED, MEASURE FROM THE TOP OF CURB OR GRADE OR
2. HAVE THE FIELD ENGINEER SET THE GRADE STAKES. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE LEVEL.

E. ALIGN HANDHOLE COVER TO FINAL GRADE USING BRICKS OR WOODEN WEDGES. BEFORE POURING CONCRETE (4-SACK MIX WITH 3/8-INCH GRAVEL OR AS REQUIRED BY CITY OR COUNTY CODES). FRAME THE INSIDE OPEN AREA BETWEEN SECTIONS SO CONCRETE CAN BE POURED FROM THE OUTSIDE OF THE TOP COVER SECTION. MAKE SURE THE BRICKS OR WOODEN WEDGES DO NOT SHOW FROM THE INSIDE ONCE THE CONCRETE IS POURED. THE INSIDE FRAME MAY BE OMITTED IF THE CONCRETE IS NOT TOO WET. IF FRAME IS OMITTED, TROWEL CONCRETE SMOOTH ON THE INSIDE.

F. INSTALL CONDUITS USING THE BOTTOM KNOCKOUTS FIRST.

G. INSTALL (2) 5-INCH CONDUITS IN THE TWO UPPERMOST KNOCKOUTS OPPOSITE OR UNDER SWITCH WAY 4 FOR SCADA.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HANDHOLE EQUIPMENT ENCLOSURE - CONCRETE
(INSIDE DIMENSIONS - 6'-0" X 8'-0")

UG3317.3

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TOP SECTION, W/ COVERS | 4,200 | 1 | -- | S334430 | 3317SE |
| 2 | INTERMEDIATE SECTION, 24" | 5,000 | 1 | -- | -- | -- |
| 3 | BASE SECTION, 47" | 14,500 | 1 | -- | -- | -- |
| 4 | UPPER PLATFORM, W/ SUPPORTS (VIII) | -- | 1 | -- | -- | -- |
| 5 | COVERS, SPRING ASSISTED | -- | 2 | -- | -- | -- |
| 6 | SWITCH SUPPORT | -- | 1 | -- | -- | -- |
| 7 | BRACKET, CABLE SUPPORT | -- | 1 | -- | -- | -- |
| 8 | LOWER PLATFORM, W/ SUPPORTS | -- | 1 | -- | -- | -- |
| 9 | KNOCKOUT, SIDE CONDUIT, 5" | -- | 2 | -- | -- | -- |
| 10 | PULLING IRON | -- | 4 | -- | -- | -- |
| 11 | GRAVEL, 3/8" - 3/4" | -- | AS REQ'D | -- | -- | -- |

## NOTES:

I. ALL INTERIOR HARDWARE SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION.

II. HANDHOLE SECTIONS AND COVERS FROM DIFFERENT SUPPLIERS ARE NOT INTERCHANGEABLE.

III. THE ONLY LOCATION FOR A 3317 HANDHOLE IS IN NONVEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.). THE 3317 IS SUPPLIED WITH PARKWAY COVERS ONLY.

IV. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

V. 3317 HANDHOLES ARE DELIVERED BY THE SUPPLIER TO JOB SITE.

VI. THIS HANDHOLE TO BE INSTALLED ONLY WHEN THERE IS INSUFFICIENT SPACE FOR PME, TRAYER SWITCH.

VII. EXCAVATION DEPTH ALLOWS 3 INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL 3 INCHES FOR REPLACEMENT OF GRAVEL AS BASE SUPPORT.

(VIII) NOT SHOWN ON FIGURES.

## REFERENCE:

(a) FOR INSTALLATION OF IDENTIFICATION TAG, SEE UG3211 AND UG3212.

b. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

c. FOR INSTALLATION OF PLASTIC-MASTIC SEALANT, SEE UG3306.

(d) FOR SLURRY BACKFILL, SEE UG3365 AND UG3366.

e. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

f. WHEN SETTING HANDHOLE ON A SLOPING GRADE, SEE UG3485.

g. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488.

h. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM), SEE UG3605.

i. FOR SUBSURFACE/SURFACE SWITCH, SEE UG3669 (PREVIOUS #UG3670.1, .2) AND UG3670.

j. FOR INSTALLATION OF SUBSURFACE/SURFACE OPERABLE SWITCH, SEE UG3671.

k. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3325 MANHOLE.





**FIGURE 1**
3325 MANHOLE
TOP SECTION

**FIGURE 2**
3325 MANHOLE
BASE SECTION





**FIGURE 3**
EXCAVATION DIMENSIONS

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | COMPLETELY REVISED | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

MANHOLE - TUB TYPE
(INSIDE DIMENSIONS 8'-0" X 14'-0" X 9'-6")

UG3325.1

## INSTALLATION:

A. ESTABLISH THE MANHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE MANHOLE TO ANOTHER LOCATION REQUIRES APPROVAL FROM SERVICE PLANNING.

(B) PLACE GRAVEL 6 INCHES DEEP ON EXCAVATION BOTTOM AND SET MANHOLE LEVEL.

(C) USE MASTIC SEALING COMPOUND IN ALL SECTIONS. (d)

D. INSTALL CONDUITS USING THE BOTTOM OUTSIDE (CLOSEST TO THE WALL) KNOCKOUTS FIRST.

E. USE #2 AWG BARE COPPER (S812818) FOR GROUNDS WITH SERVICE POST CONNECTOR (S262560).

F. ON INITIAL CABLE INSTALLATION, OCCUPY LOWEST CONDUIT OPENINGS FIRST.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TOP SECTION, 4'-9" | 33,280 | 1 | -- | S475902 | 3325MH |
| 2 | BASE SECTION, 4'-9" | 33,915 | 1 | -- | | |
| 3 | SEALANT, PLASTIC MASTIC (C) | -- | AS REQ'D | 3306 | S631872 | -- |
| 4 | GRAVEL, 3/8" - 3/4" (B) | -- | AS REQ'D | -- | -- | -- |

## NOTES:

I. MANHOLE SECTIONS AND COVERS FROM DIFFERENT SUPPLIERS ARE NOT INTERCHANGEABLE.

II. THE PREFERRED LOCATION FOR A 3325 MANHOLE IS IN NONVEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.).

III. 3325 MANHOLES ARE DELIVERED BY THE SUPPLIER TO JOB SITE.

IV. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

(V) EXCAVATION DEPTH ALLOWS 3 INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL 6 INCHES FOR PLACEMENT OF GRAVEL AS BASE SUPPORT.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) FOR MANHOLE NECK AND COVER TRAFFIC BEARING, SEE UG3332.

(b) FOR SLURRY BACKFILL, SEE UG3365 AND UG3366.

c. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

(d) SEE UG3306.

e. FOR 48" X 60" MANHOLE NECK AND COVER, SEE UG3332.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | COMPLETELY REVISED | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3326 MANHOLE.





**FIGURE 1**
3326 MANHOLE
TOP SECTION





**FIGURE 1**
3326 MANHOLE
BASE SECTION

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | COMPLETELY REVISED | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MANHOLE - TUB TYPE
INSIDE DIMENSIONS 8'-0" X 20'-0" X 9'-6"



UG3326.1

TABLE OF CONTENTS





**FIGURE 2**
EXCAVATION DIMENSIONS

## INSTALLATION:

A. ESTABLISH THE MANHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE MANHOLE TO ANOTHER LOCATION REQUIRES APPROVAL FROM SERVICE PLANNING.

(B) PLACE GRAVEL SIX INCHES DEEP ON EXCAVATION BOTTOM AND SET MANHOLE LEVEL.

(C) USE MASTIC SEALING COMPOUND IN ALL SECTIONS.(c)

D. INSTALL CONDUITS USING THE BOTTOM OUTSIDE (CLOSEST TO THE WALL) KNOCKOUTS FIRST.

E. USE #2 AWG BARE COPPER (S812818 (X)) FOR GROUNDS WITH SERVICE POST CONNECTOR (S262560).

F. ON INITIAL CABLE INSTALLATION, OCCUPY LOWEST CONDUIT OPENINGS FIRST.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TOP SECTION, 4'-9" | 40,000 | 1 | -- | S475904 | 3326MH |
| 2 | BASE SECTION, 4'-9" | 41,500 | | | | |
| 3 | SEALANT, PLASTIC MASTIC (C) | -- | AS REQ'D | 3306 | S631872 | -- |
| 4 | GRAVEL, 3/8" - 3/4" (B) | -- | AS REQ'D | -- | -- | -- |

## NOTES:

I. MANHOLE SECTIONS AND COVERS FROM DIFFERENT SUPPLIERS ARE NOT INTERCHANGEABLE.

II. THE PREFERRED LOCATION FOR A 3326 MANHOLE IS IN NON-VEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.).

III. 3325 MANHOLES ARE DELIVERED BY THE SUPPLIER TO JOB SITE.

IV. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

(V) EXCAVATION DEPTH ALLOWS THREE INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL SIX INCHES FOR PLACEMENT OF GRAVEL AS BASE SUPPORT.

(X) THIS ITEM IS EXEMPT.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | COMPLETELY REVISED | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE:**

(a) FOR MANHOLE NECK AND COVER TRAFFIC BEARING, SEE UG3332.

(b) FOR SLURRY BACKFILL, SEE UG3365 AND UG3366.

(c) FOR MASTIC SEALING COMPOUND, SEE UG3306.

d. FOR 48-INCH X 60-INCH MANHOLE NECK AND COVER, SEE UG3332.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | COMPLETELY REVISED | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MANHOLE - TUB TYPE
INSIDE DIMENSIONS 8'-0" X 20'-0" X 9'-6"

UG3326.3

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR A 3327 MANHOLE.





**FIGURE 1**
3327 MANHOLE
TOP SECTION





**FIGURE 1**
3327 MANHOLE
INTERMEDIATE SECTION





**FIGURE 1**
3327 MANHOLE
BASE SECTION

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | GW | JS | CZH | 11/01/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET
1 OF 3

SUBSTATION MANHOLE VAULT
10'-0" X 24'-0" X 8'-0"

UG3327.1

TABLE OF CONTENTS





**FIGURE 2**
EXCAVATION DIMENSIONS

## INSTALLATION:

A. ESTABLISH THE MANHOLE LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE MANHOLE TO ANOTHER LOCATION REQUIRES APPROVAL FROM SERVICE PLANNING.

B. PLACE GRAVEL SIX INCHES DEEP ON EXCAVATION BOTTOM AND SET MANHOLE LEVEL.

(C) USE MASTIC SEALING COMPOUND IN ALL SECTIONS. (c)

D. INSTALL CONDUITS USING THE BOTTOM OUTSIDE (CLOSEST TO THE WALL) KNOCKOUTS FIRST.

E. USE #2 AWG BARE COPPER (S812818 (X)) FOR GROUNDS WITH SERVICE POST CONNECTOR (S262560).

F. ON INITIAL CABLE INSTALLATION, OCCUPY LOWEST CONDUIT OPENINGS FIRST.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TOP SECTION | 55,550 | 1 | -- | S475906 | 3327MH |
| 2 | BASE SECTION | 60,382 | | | | |
| 3 | SEALANT, PLASTIC MASTIC | -- | AS REQ'D | 3306 | S631875 | -- |
| 4 | GRAVEL, 3/8" - 3/4" | -- | AS REQ'D | -- | -- | -- |
| 5 | BASE SECTION | 58,221 | -- | -- | -- | -- |

## NOTES:

I. MANHOLE SECTIONS AND COVERS FROM DIFFERENT SUPPLIERS ARE NOT INTERCHANGEABLE.

II. THE PREFERRED LOCATION FOR A 3327 MANHOLE IS IN NONVEHICULAR TRAFFIC AREAS (BEHIND CURBS, PARKWAY POSITION, ETC.).

III. 3325 MANHOLES ARE DELIVERED BY THE SUPPLIER TO JOB SITE.

IV. LIFTING ANCHORS ARE NOT TO BE USED FOR CABLE PULLING.

(V) EXCAVATION DEPTH ALLOWS THREE INCHES FOR ADJUSTMENT TO FINAL GRADE AND AN ADDITIONAL SIX INCHES FOR PLACEMENT OF GRAVEL AS BASE SUPPORT.

(X) THIS ITEM IS EXEMPT.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | GW | JS | CZH | 11/01/2018 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE:**

(a) FOR MANHOLE NECK AND COVER TRAFFIC BEARING, SEE UG3332.

(b) FOR SLURRY BACKFILL, SEE UG3365 AND UG3366.

(c) FOR SEALING COMPOUND, SEE UG3306.

d. FOR 48-INCH X 60-INCH MANHOLE NECK AND COVER, SEE UG3332.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | GW | JS | CZH | 11/01/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUBSTATION MANHOLE VAULT
10'-0" X 24'-0" X 8'-0"

UG3327.3

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIREMENTS FOR THE MANHOLE NECK, NECK EXTENSION, AND COVER USED FOR ACCESS TO A 3325 AND 3326 MANHOLE.





**FIGURE 1**
CAST IRON COVER





**FIGURE 2**
CONCRETE COVER





**FIGURE 3**
NECK SECTION





**FIGURE 4**
NECK EXTENSION SECTION

## INSTALLATION:

A. PLACE PLASTIC-MASTIC SEALANT BETWEEN ALL SECTIONS. DO NOT APPLY SEALANT UNDER THE TOP SECTION IF CONCRETE IS REQUIRED FOR GRADE ADJUSTMENT.

B. TO DETERMINE FINAL GRADE, ONE OF THE TWO FOLLOWING METHODS MAY BE USED:

1. CURB OR GRADE LEVEL IS ALREADY ESTABLISHED, MEASURE FROM THE TOP OF CURB OR GRADE.
2. HAVE THE FIELD ENGINEER SET THE GRADE STAKES. AFTER GRADE LEVEL IS ESTABLISHED, SET A STRING LINE FOR CHECKING GRADE LEVEL.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 09/08/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MANHOLE NECK & COVER - TRAFFIC BEARING
(INSIDE DIMENSIONS 48" X 60")



UG3332.1

TABLE OF CONTENTS

## INSTALLATION (CONT'D):

C. ALIGN MANHOLE COVER TO FINAL GRADE USING BRICKS OR WOODEN WEDGES. BEFORE POURING CONCRETE (4-SACK MIX WITH 3/8-INCH PEA GRAVEL OR AS REQUIRED BY CITY OR COUNTY CODES), FRAME THE INSIDE OPEN AREA BETWEEN SECTIONS SO CONCRETE CAN BE POURED FROM THE OUTSIDE OF THE TOP COVER SECTION. MAKE SURE THE BRICKS OR WOODEN WEDGES DO NOT SHOW FROM THE INSIDE ONCE THE CONCRETE IS POURED. THE INSIDE FRAME MAY BE OMITTED IF THE CONCRETE IS NOT TOO WET. IF FRAME IS OMITTED, TROWEL CONCRETE SMOOTH ON THE INSIDE.

D. **TABLE 1**

| DEPTHS OF MANHOLE ROOF BELOW GRADE | |
|---|---|
| **EXTENSION** | **DEPTH BELOW GRADE** |
| 0" | 1'-0" |
| 6" | 1'-6" |
| 9" | 1'-9" |
| 12" | 2'-0" |

(E) APPLY INHIBITOR TO THE BOLTS WHEN SECURING THE COVER TO REDUCE INSTALLATION OR REMOVAL DIFFICULTIES.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | |
|---|---|---|---|---|---|---|---|---|
| 1 | COVER, DUCTILE IRON, 34" | | 205 | 1 | -- | S287056 | MH-COV | 24NKCV |
| 2 | COVER, CONCRETE | | 2,077 | 1 | -- | S287110 | -- | |
| 3 | NECK, SECTION | | 1,949 | 1 | -- | S597300 | 24MHNK | |
| 4 | NECK, EXTENSION SECTION | 6" | 1,040 | AS REQ'D | -- | S493550 | 24NK06 | |
| | | 9" | 1,560 | | | S493564 | 24NK09 | |
| | | 12" | 2,040 | | | S493495 | 24NK12 | |
| 5 | BOLT, HEX HEAD, 5/8" X 1 1/2" | | -- | 4 | -- | S156758 | -- | |
| 6 | SEALANT, PLASTIC-MASTIC (III) | | -- | AS REQ'D | 3306 | S631872 | -- | |
| 7 | INHIBITOR (III) | | -- | AS REQ'D | -- | S247200 | -- | |

## NOTES:

I. CAST IRON COVERS FROM DIFFERENT SUPPLIERS ARE INTERCHANGEABLE. THE CONCRETE COVER, NECK SECTION AND NECK EXTENSION SECTION FROM DIFFERENT SUPPLIERS ARE NOT INTERCHANGEABLE.

(II) WHEN TRAFFIC COVER IS REMOVED CHECK GASKET MATERIAL AND REPLACE AS NEEDED (S341020).

## REFERENCE:

(a) FOR INSTALLATION OF IDENTIFICATION TAG, SEE UG3211 AND UG3212.

b. FOR SUBSTRUCTURE APPLICATIONS, SEE UG3302.

c. FOR INSTALLATION OF PLASTIC-MASTIC SEALANT, SEE UG3306.

d. FOR SLURRY BACKFILL, SEE UG3365 AND UG3366.

e. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

f. FOR SETTING MANHOLE ON SLOPING GRADE, SEE UG3485.

g. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488.

h. FOR SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET (MAXIMUM NUMBER OF CABLES, CONNECTORS AND CONDUITS), SEE UG3605.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 09/08/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND APPLICATION OF SUMP PUMPS INSTALLED IN MANHOLES THAT CONTAIN OR WILL CONTAIN SWITCHES.





**FIGURE 2**
SUMP PUMP INSTALLATION IN A 3324/25/26/27 MANHOLE
TOP VIEW OF MANHOLE CENTER SECTION

**FIGURE 1**
SUMP PUMP INSTALLATION IN A 3324/25/26/27 MANHOLE

**FIGURE 3**
SUMP PUMP INSTALLATION IN A 3324/25/26/27 MANHOLE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | TSA | EJA | EJA | KRG | 03/27/2023 | F | | | | | | |
| B | MOVED FROM UG3362 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | REPL'D PUMP MODEL | - | ML | AW | MDJ | 02/13/2018 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

SUMP PUMP INSTALLATION
FOR MANHOLES 3324, 3325, 3326, 3327

UG3360.1

## INSTALLATION:

(A) PROVIDE A 120V, SINGLE-PHASE SERVICE TO PUMP LOCATION. IF SECONDARY DOES NOT EXIST IN SUBSTRUCTURE AND A SPARE SECONDARY CONDUIT IS NOT AVAILABLE, A PRIMARY CONDUIT MAY BE SUBSTITUTED.

(B) CORE BORE WITH A 3 1/2-INCH BIT TO MAKE THE HOLE THROUGH THE CURB AND 2-INCH BIT TO MAKE THE HOLE THROUGH THE MANHOLE. CORE BORE THE CURB AT A 45 DEGREE ANGLE TOWARD THE GRAVITY LOW OF THE WATER ON THE DOWNWARD SIDE OF THE SUBSTRUCTURE. REDUCE CONDUIT TO 1 1/2 INCHES AFTER THE SECOND 3-INCH 90 DEGREE BEND. BRING THE CONDUIT IN ON THE SHORT SIDE OF THE SUBSTRUCTURE WHENEVER POSSIBLE.

(C) INSTALL THE DISCHARGE CONDUIT AS SHOWN IN FIGURES 1 OR 3, MAKING SURE THAT ARROW ON CHECK VALVE IS DIRECTING WATER FLOW UPWARD TOWARD STREET.

D. SOLVENT CEMENT IS REQUIRED WHEN ATTACHING P.V.C HOSE TO FITTINGS.

(E) WHEN PUMP IS DISCONNECTED FROM HOSE, CUT THE HOSE AS CLOSE TO THE PUMP AS POSSIBLE. FOR RE-ATTACHMENT, USE A 1 1/2-INCH COUPLING.

(F) CUT 120V ELECTRICAL PLUG FROM END OF PUMP CORD. USING STA-KON OR EQUIVALENT CONNECTORS AND HEAT SHRINK TUBES, ATTACH WIRE AS SHOWN IN FIGURES 1 OR 3.

(G) SPLICE THE PUMP GROUND WIRE (GREEN) TO A #8 CU WIRE (ITEM 7) USING A STA-KON OR EQUIVALENT CONNECTOR. ATTACH THE #8 CU WIRE TO SUBSTRUCTURE GROUND.

(H) INSTALL FUSE HOLDER WITH FUSE INSIDE AS HIGH AS POSSIBLE AND ABOVE WATER MARKS ON SUBSTRUCTURE WALL WHERE FUSE CAN BE CHANGED FROM LADDER. APPLY SEALING COMPOUND TO ASSURE A WATERTIGHT CONNECTION.

J. WHEN CORE BORING CURB, ENSURE DISCHARGE IS ON THE LOWER SIDE OF THE MANHOLE OPENING IF OPENING IS IN THE STREET.

(K) THIS PUMP SHALL NOT BE USED TO PUMP THE SUBSTRUCTURE DRY. MANUAL OPERATION OF SUMP PUMP WITHOUT 2 INCHES MINIMUM OF WATER SURROUNDING PUMP AT ALL TIMES WILL DAMAGE THE PUMP UNIT.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | |
|---|---|---|---|---|---|---|
| 1 | SUMP PUMP, AUTOMATED | 1 | -- | S561570 | ECOPMP | SUMPAS |
| 2 | HOSE, 1 1/2", PVC (E)(F) | AS REQ'D | -- | S417200 | 1-1/2F | |
| 3 | VALVE, CHECK, 1 1/2" | 1 | -- | S783110 | -- | |
| 4 | CONDUIT, SCH 40 PVC, 1 1/2" | AS REQ'D | -- | S251232 | 1-1/2C | |
| 5 | ELBOW, 90°, 1 1/2" | 3 | -- | S325476 | -- | |
| 6 | COUPLING, SCH 40 PVC, 1 1/2" (E)(F) | AS REQ'D | -- | S280320 | | |
| 7 | WIRE, #8 THW 600V COPPER | AS REQ'D | -- | S808320 | | |
| 8 | HOLDER, FUSE | 1 | -- | S443392 | | |
| 9 | CARTRIDGE, FUSE, 15A, BUSS FNM15 | 1 | -- | S363790 | | |
| 10 | HEAT-SHRINK, TUBE, 1.3" ID X 6" | 3 | -- | S777984 | | |
| 11 | SERVICE CONNECTOR | 1 | -- | S258496 | -- | |
| 12 | TIE STRAP | AS REQ'D | -- | S738440 | -- | |
| 13 | SOLVENT CEMENT (E)(VI) | AS REQ'D | -- | S213232 | -- | |
| 14 | SEALING COMPOUND (K) | 1 | -- | S442976 | -- | |
| 15 | WIRE, TWO #8, 600V ALUMINUM INSULATED CABLE (U10.011) (VI) | AS REQ'D | -- | S196176 | -- | |
| 16 | CONNECTOR, STA-KON OR EQUIVALENT | 3 | -- | S258712 | -- | |
| 17 | PIPE STRAP, TWO HOLE, 1 1/2", STAINLESS STEEL | AS REQ'D | -- | S697664 | -- | |
| 18 | ANCHOR BOLT, 1/4" X 2 1/4", STAINLESS STEEL | AS REQ'D | -- | S107660 | -- | |
| 19 | ADAPTER, THREADED 1 1/4" TO 1 1/2" SLIP | 1 | -- | S102064 | -- | |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | TSA | EJA | EJA | KRG | 03/27/2023 | F | | | | | | |
| B | MOVED FROM UG3362 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | REPL'D PUMP MODEL | - | ML | AW | MDJ | 02/13/2018 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUMP PUMP INSTALLATION
FOR MANHOLES 3324, 3325, 3326, 3327

UG3360.2

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | |
|---|---|---|---|---|---|---|
| 20 | REDUCER, SCH 80 PVC, 3"-2" | 1 | -- | S573392 | -- | |
| 21 | REDUCER, NESTING BUSHING, SCH 40 PVC, 2" X 1 1/2" | 1 | -- | S573411 | -- | |
| 22 | COUPLING, SCH 40 PVC, 2" | 1 | -- | S280384 | -- | |
| 4 | CONDUIT, SCH 40 PVC, 1 1/2" | AS REQ'D | -- | S251232 | 1-1/2C | X-COND |
| 23 | CONDUIT, SCH 40 PVC, 3" | 10'-0" MAX. | -- | S251360 | -- | |
| 24 | ELBOW, 90°, SCH 40 PVC, 3" | 2 | -- | S321818 | -- | |
| 25 | COUPLING, SCH 40 PVC, 3" | AS REQ'D | -- | S280448 | -- | |

## NOTES:

**THE INSTALLATION CRITERIA SHALL BE THE FOLLOWING FOR SWITCHES:**

I. IN MANHOLES WHICH WILL HOUSE NEW SWITCH(ES), INSTALL A SUMP PUMP AND DISCHARGE CONDUIT AS SHOWN IN THIS STANDARD AND PROVIDE 120V POWER FOR THE PUMP.

II. IN MANHOLES WHICH MAY ULTIMATELY HOUSE SWITCH(ES), INSTALL THE DISCHARGE CONDUIT FROM THE CURB TO A POINT 6 INCHES INSIDE THE SUBSTRUCTURE. INSTALL A TEMPORARY CAP ON THE 6-INCH PORTION WITH SOLVENT CEMENT. INSTALL THE ELECTRIC CONDUIT THAT WILL BE USED FOR THE SERVICE TO THE PUMP IN THE KNOCKOUT DIRECTLY ABOVE THE DESIGNATED CONDUITS TOWARD THE SOURCE OR FUTURE SOURCE OF FEED.

III. INSTALL A SUMP PUMP WHENEVER THE WATER LEVEL REACHES THE BOTTOM OF AN EXISTING SUBSURFACE SWITCH OR 9 INCHES, WHICHEVER IS LESS.

**THE INSTALLATION CRITERIA SHALL BE THE FOLLOWING FOR ON-OFF SWITCHES:**

IV. IN MANHOLES WHICH WILL HOUSE NEW SWITCH(ES), INSTALL A SUMP PUMP AND DISCHARGE CONDUIT AS SHOWN IN THIS STANDARD AND PROVIDE 120V POWER FOR THE PUMP.

V. IN MANHOLES WHICH MAY ULTIMATELY HOUSE SWITCH(ES) AT A LATER DATE, INSTALL THE DISCHARGE CONDUIT FROM THE CURB TO A POINT 6 INCHES INSIDE THE SUBSTRUCTURE. INSTALL A TEMPORARY CAP ON THE 6-INCH PORTION WITH SOLVENT CEMENT. INSTALL THE ELECTRIC CONDUIT THAT WILL BE USED FOR SERVICE TO THE PUMP IN THE KNOCKOUT DIRECTLY ABOVE THE DESIGNATED CONDUITS TOWARD THE SOURCE OR FUTURE SOURCE OF FEED.

(VI) NOT SHOWN ON FIGURES.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | TSA | EJA | EJA | KRG | 03/27/2023 | F | | | | | | |
| B | MOVED FROM UG3362 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | REPL'D PUMP MODEL | - | ML | AW | MDJ | 02/13/2018 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUMP PUMP INSTALLATION
FOR MANHOLES 3324, 3325, 3326, 3327

UG3360.3

**SCOPE:** THIS STANDARD SHOWS RESURFACING OF AN EXISTING STREET AFTER THE INSTALLATION OR RAISING OF A 3300 SUBSTRUCTURE.





**FIGURE 1**

## INSTALLATION:

(A) CONCRETE 6 SACK MIX (560-C-3250) WITH ONE-INCH ROCK.

(B) INSTALL 1/2-INCH LAYER OF WASHED CONCRETE SAND OR OTHER BOND BREAKERS EVERY SIX INCHES FOR POSITIVE CONSTRUCTION BREAKER JOINTS. IF SUBSTRUCTURE IS RAISED AT A LATER DAY DUE TO STREET RESURFACING, ETC., BREAKER JOINT WILL EASE RAISING SUBSTRUCTURE.

(C) CONCRETE 6 SACK MIX (560-C-3250). APRON EIGHT INCHES IN WIDTH, TROWELED SURFACE 1/4-INCH ROLLED EDGE (SIDEWALK EDGING TOOL). CONCRETE APRON SERVES AS PROTECTION FOR SUBSTRUCTURE.

(D) ASPHALT ROAD BASE, SIX-INCH MINIMUM DEPTH.

(E) FOR AC SURFACES, MAINTAIN CONCRETE BASE SURFACE 1/8-INCH LOW TO LEAVE ENOUGH ROOM FOR CLASS 'F' ASPHALT TO BE EVENLY SPREAD, RESULTING IN A SMOOTH (FLAT) EXISTING SURFACE BETWEEN EXISTING ROADWAY AND 3300 TOP (NECK) SECTION.

(F) CLASS 'F' ASPHALT SPREAD EVENLY, RESULTING IN A SMOOTH TRANSITION SURFACE FROM ROADWAY TO 3300 TOP (NECK) SECTION.

G. INSTALL 1/2-INCH LAYER OF WASHED CONCRETE SAND OR OTHER BOND BREAKERS IF CONCRETE UNDER TOP (NECK) SECTION EXCEEDS THREE INCHES.

(H) FOR AC SURFACES CLASS 'F' ASPHALT SHALL BE SEALED WITH ASPHALTIC TYPE EMULSION THEN SAND SEALED.

(J) FRAME THE INSIDE OPEN AREA BETWEEN SECTIONS SO CONCRETE CAN BE POURED FROM OUTSIDE THE SUBSTRUCTURE.

K. THE INSTALLATION SHALL MEET LOCAL GOVERNMENTAL REQUIREMENTS. IF THIS STANDARD DOES NOT CONFORM, FOLLOW AGENCY, GOVERNMENTAL REQUIREMENTS.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3363 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGE | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

STREET RESURFACING



UG3361.1

**SCOPE:** THIS STANDARD SHOWS TYPICAL UTILITY LOCATIONS IN LOCAL AND COLLECTOR STREETS IN SAN DIEGO COUNTY.





**FIGURE 1**
NEW CONSTRUCTION
TYPICAL STREET

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) AT CATCH BASIN LOCATIONS, JOINT TRENCH SHALL BE 4 FEET MINIMUM FROM BACK OF CURB TO INSIDE WALL OF TRENCH.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3364 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/06/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET
1 OF 1


UTILITY LOCATIONS IN LOCAL AND
COLLECTOR STREETS IN S.D. COUNTY

UG3362.1


**SCOPE:** THIS STANDARD SHOWS TYPICAL UTILITY LOCATIONS IN MAJOR STREETS, PRIME ARTERIALS, AND EXPRESSWAYS IN SAN DIEGO COUNTY.




CONFIGURATION 1
MAJOR STREET
FOUR LANE, 78'-0" CURB TO CURB, 90'-0" P/L TO P/L




CONFIGURATION 2
PRIME ARTERIAL
SIX LANE, 102'-0" CURB TO CURB, 122'-0" P/L TO P/L




CONFIGURATION 3
EXPRESSWAY
SIX LANE, 102'-0" CURB TO CURB, 122'-0" P/L TO P/L GREATER SPEEDS

**FIGURE 1**
NEW CONSTRUCTION

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3364 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/06/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

UTILITY LOCATIONS IN MAJOR STREETS, PRIME ARTERIALS, AND ESPRESSWAYS IN S.D. COUNTY



UG3363.1

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) AT CATCH BASIN LOCATIONS, JOINT TRENCH SHALL BE 4 FEET MINIMUM FROM BACK OF CURB TO INSIDE WALL OF TRENCH.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3364 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/06/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


UTILITY LOCATIONS IN MAJOR STREETS, PRIME ARTERIALS, AND ESPRESSWAYS IN S.D. COUNTY

UG3363.2


**SCOPE:** THIS STANDARD SHOWS TYPICAL JOINT TRENCH LOCATION FOR UNDERGROUND CONVERSIONS IN SAN DIEGO COUNTY.




EXAMPLE 1
SIDEWALK NEXT TO CURB




EXAMPLE 2
SIDEWALK NEXT TO PROPERTY LINE




EXAMPLE 3
SIDEWALK NEXT TO CURB AND PROPERTY LINE

**FIGURE 1**
UNDERGROUND CONVERSIONS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/06/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

JOINT TRENCH TYPICAL LOCATION
FOR UNDERGROUND CONVERSIONS IN S.D. COUNTY

UG3364.1

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. SIDEWALK SHALL HAVE A MINIMUM OF 4-FOOT CLEAR AREA (PATH, NOT INCLUDING CURB) PASSING PEDESTALS, PULLBOXES AND OTHER STRUCTURES. (b)

(II) STREET LIGHTS, GAS, UNDERGROUND ELECTRIC, TELEPHONE AND CATV.

**REFERENCE:**

a. SEE GAS STANDARDS 7425.1, 7425.2, AND 7425.3 [FOR INTERNAL USE ONLY].

(b) FOR PEDESTRIAN PATH OF TRAVEL AND ACCESSIBILITY, SEE UG3002.

(c) FOR CLEARANCES, SEE UG3479, UG3480, UG3481, UG3482, UG3483, UG3486, UG3487, AND UG3488.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 06/06/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

JOINT TRENCH TYPICAL LOCATION
FOR UNDERGROUND CONVERSIONS IN S.D. COUNTY

UG3364.2

**SCOPE:** THIS STANDARD SHOWS TYPICAL PLACEMENT OF BASE, SHADING, AND IMPORTED OR NATIVE BACKFILL MATERIAL FOR SDG&E FACILITIES IN SAN DIEGO COUNTY. IMPORTED OR NATIVE BACKFILL IS THE ALTERNATE BACKFILL MATERIAL, ONE SACK SLURRY IS THE PREFERRED BACKFILL MATERIAL.





**FIGURE 1**
JOINT TRENCH





**FIGURE 2**
ELECTRIC ONLY





**FIGURE 3**
SINGLE GAS ONLY





**FIGURE 4**
ELECTRIC ONLY





**FIGURE 5**
JOINT TRENCH
WITH SLURRY





**FIGURE 6**
SERVICE TRENCH ON
PRIVATE PROPERTY

## INSTALLATION:

(A) DOES NOT CONFORM, FOLLOW AGENCY AND GOVERNMENTAL REQUIREMENTS.

B. SHADING MATERIAL SHALL MEET GAS STANDARD 7405 OR UNDERGROUND 3370/3371 SPECIFICATIONS AND MUST BE APPROVED BY AN SDG&E INSPECTOR.

(C) BACKFILL MATERIAL SHALL MEET THE GOVERNMENTAL (PERMITTING) AGENCIES REQUIREMENTS AND SDG&E STANDARDS. ROCKS GREATER THAN 6 INCHES ARE NOT ALLOWED IN BACKFILL MATERIAL. (b)

D. IF FOREIGN UTILITIES REQUIRE ENCASEMENT, MAINTAIN CLEARANCES AND PROVIDE BASE FOR GAS MAIN.

(E) ALL 5-INCH PRIMARY CONDUITS SHALL BE INSTALLED WITH SPACERS AND ENCASED WITH CONCRETE SLURRY (1 SACK MIX).

(F) THE MINIMUM COMPACTED SHADING MATERIAL OVER THE UPPERMOST GAS PIPE OR CONDUIT SHALL BE 4 INCHES.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | EDM | DEC | JES | CZH | 06/07/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 11/11/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/28/2016 | D | | | | | | |



TABLE OF CONTENTS

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG3365 (GAS STANDARD 7410) FOR SLURRY BACKFILL.

b. SEE UG3370, UG3371 NOTE D (GAS STANDARD 7403 NOTE D) FOR UTILITY PLACEMENT, CLEARANCES, MINIMUM SHADING, COVER, AND COMPACTION.

c. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

d. SEE GAS STANDARD G7409.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | EDM | DEC | JES | CZH | 06/07/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 11/11/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/28/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS TYPICAL PLACEMENT OF BASE, SHADING, AND SLURRY BACKFILL FOR SDG&E FACILITIES IN SAN DIEGO COUNTY.





**FIGURE 1**
JOINT TRENCH





**FIGURE 2**
ELECTRIC ONLY





**FIGURE 3**
SINGLE GAS ONLY





**FIGURE 4**
ELECTRIC ONLY





**FIGURE 5**
JOINT TRENCH





**FIGURE 6**
SERVICE TRENCH ON PRIVATE PROPERTY

## INSTALLATION:

(A) ALL TRENCH RESURFACING SHALL BE DONE ACCORDING TO GOVERNMENTAL AGENCIES REQUIREMENTS.

B. SHADING MATERIAL SHALL MEET GAS STANDARD 7405 OR UG3370 & UG3371 SPECIFICATIONS AND MUST BE APPROVED BY AN SDG&E AUTHORIZED INSPECTOR.

(C) BACKFILL MATERIAL SHALL MEET THE GOVERNMENTAL (PERMITTING) AGENCIES REQUIREMENTS AND SDG&E STANDARDS. THE SAND USED FOR THE ONE SACK SLURRY OR TWO SACK, IF REQUIRED BY GOVERNMENTAL AGENCIES, MUST MEET THE CONCRETE SAND SPECIFICATION LISTED IN THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (GREEN BOOK) AND CONTAIN NO GRAVEL. SLURRY MUST BE FIRM BEFORE A PAVEMENT CONCRETE CAP IS INSTALLED. SLURRY IS TYPICALLY USED FOR BACKFILLING AROUND SUBSTRUCTURES, UNDER EQUIPMENT PADS, FOR TRENCHES IN EXISTING PAVED AREAS, AND UNDER CONCRETE OR PAVED DRIVEWAYS.

D. IT MAY NOT BE APPROPRIATE TO USE ONE SACK SLURRY UNDER THE THE FOLLOWING CIRCUMSTANCES:

1. GOVERNMENTAL AGENCIES DO NOT ALLOW ONE SACK OR MAY REQUIRE TWO SACK SLURRY BACKFILL.
2. INACCESSIBILITY OF CONCRETE TRUCKS DELIVERING SLURRY.
3. WHEN SLURRY IS NOT COST EFFECTIVE.
4. NEW RESIDENTIAL SUBDIVISIONS, SINGLE FAMILY RESIDENCE SERVICE TRENCH
5. SHALLOW WELD HOLES, POT HOLES, ETC.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3365 | EDM | DEC | JES | CZH | 06/07/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 11/11/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/28/2016 | D | ADD RED DYE | NV5 | ADW | JES | CZH | 09/07/2022 |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(E) ALL 5-INCH PRIMARY CONDUITS SHALL BE INSTALLED WITH SPACERS AND ENCASED WITH CONCRETE SLURRY (1 SACK MIX).

(F) MINIMUM COMPACTED SHADING MATERIAL OVER THE UPPERMOST GAS PIPE OR CONDUIT SHALL BE 4 INCHES. THE GAS MAIN OR GAS SERVICE SHALL NEVER BE CONCRETE OR SLURRY ENCASED AND SHALL HAVE THE PROPER BASE, SHADING, BACKFILL AND COMPACTION.

(G) MAINTAIN A MINIMUM 24 INCHES COVER FROM FINISHED SURFACE TO TOP OF ELECTRIC CONDUIT PACKAGE OVER PRIMARY.

(H) USE APPROVED SDG&E CONDUIT AND SPACERS. THE USE OF CONDUIT SPACERS DOES NOT REQUIRE THE 1 ½" OF EARTH BASE.

(J) ON SERVICES IN PRIVATE YARDS, ALLOW FOR 6 INCHES OF TOP SOIL FOR LANDSCAPING PURPOSES.

K. IF FOREIGN UTILITIES REQUIRE ENCASEMENT, MAINTAIN CLEARANCES AND PROVIDE BASE FOR GAS MAIN.

(L) ALL SLURRY THAT ENCASES PRIMARY CONDUITS SHALL BE RED IN COLOR. COLOR SHALL BE INTEGRAL AND OBTAINED BY USING QUIKCRETE LIQUID COLORANT AT A RATE OF 16 FLUID OUNCES TO ONE CUBIC YARD OF SLURRY, OR APPROVED EQUIVALENT.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG3370 & UG3371 (GAS STANDARD 7403) FOR UTILITY PLACEMENT, CLEARANCES, MINIMUM SHADING, COVER, AND COMPACTION.

b. SEE UG3376.1 FOR 1 SACK CONCRETE SLURRY MIX AND 2 SACK 3/8-INCH GRAVEL CONCRETE MIX OR AS REQUIRED BY GOVERNMENTAL AGENCY.


c. SEE UG3365.1 OR GAS STANDARD 7409 FOR ALTERNATE IMPORTED OR NATIVE BACKFILL.

TABLE OF CONTENTS


© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3365 | EDM | DEC | JES | CZH | 06/07/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 11/11/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/28/2016 | D | ADD RED DYE | NV5 | ADW | JES | CZH | 09/07/2022 |


**SCOPE:** THIS STANDARD SHOWS TYPICAL PLACEMENT OF BASE, SHADING AND ONE SACK SLURRY BACKFILL AS A PREFERRED METHOD OF BACKFILL FOR SDG&E FACILITIES.




INSTALLATION 1
3418, 3419, & 3423
BOX PAD





INSTALLATION 2
3713 INSTALLATION
OPEN DELTA BANK THREE-PHASE




INSTALLATION 3
3315/3316 HANDHOLE




INSTALLATION 4
3314 HANDHOLE




INSTALLATION 5
3325/3326 MANHOLES




INSTALLATION 6
3714 INSTALLATION
CLOSED DELTA BANK THREE-PHASE




INSTALLATION 7
3426/3427 TRANSFORMER PAD
WITH 3314 SECTIONS




INSTALLATION 8
UNDERGROUND CONVERSIONS CONCRETE
DRIVEWAYS, PAVED ROADWAYS

**FIGURE 1**
TYPICAL SLURRY INSTALLATIONS

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3365 | EDM | DEC | JES | CZH | 06/07/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 11/11/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/28/2016 | D | ADD RED DYE | NV5 | ADW | JES | CZH | 09/07/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed





**FIGURE 1 (CONT'D)**
TYPICAL SLURRY INSTALLATIONS

## INSTALLATION:

A. ONE SACK SLURRY IS THE PREFERRED METHOD FOR BACKFILL.

B. IMPORTED OR NATIVE BACKFILL IS THE ALTERNATE METHOD FOR BACKFILL.

C. SLURRY IS TYPICALLY USED FOR BACKFILLING AROUND SUBSTRUCTURES, UNDER EQUIPMENT PADS, FOR TRENCHES IN EXISTING PAVED AREAS AND UNDER CONCRETE OR PAVED DRIVEWAYS.

D. SLURRY IS THE ONLY ALLOWED BACKFILL AROUND FIBERGLASS BOX PADS.

E. IT MAY NOT BE APPROPRIATE TO USE ONE SACK SLURRY UNDER THE FOLLOWING CIRCUMSTANCES:

1. GOVERNMENTAL (PERMITTING) AGENCIES DO NOT ALLOW ONE SACK SLURRY OR MAY REQUIRE TWO SACK SLURRY BACKFILL.
2. INACCESSIBILITY OF CONCRETE TRUCKS DELIVERING SLURRY.
3. WHEN SLURRY IS NOT COST EFFECTIVE.
4. NEW RESIDENTIAL SUBDIVISIONS, SINGLE FAMILY RESIDENT SERVICES.
5. SHALLOW WELD HOLES, POT HOLES, ETC.

(F) MINIMUM COMPACTED SHADING MATERIAL OVER THE UPPERMOST GAS PIPE OR CONDUIT SHALL BE 4 INCHES. THE GAS MAIN OR GAS SERVICE SHALL NEVER BE CONCRETE OR SLURRY ENCASED AND SHALL HAVE THE PROPER BASE, SHADING, BACKFILL AND COMPACTION.

**BILL OF MATERIALS:** NONE

## NOTES:

I. GAS PIPE SHALL NOT BE SLURRY ENCASED. (F)

## REFERENCE:

a. SEE UG3365.1 (GAS STANDARD G7409) FOR ALTERNATE IMPORTED OR NATIVE BACKFILL.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3365 | EDM | DEC | JES | CZH | 06/07/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 11/11/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/28/2016 | D | ADD RED DYE | NV5 | ADW | JES | CZH | 09/07/2022 |

**SCOPE:** THIS STANDARD DEMONSTRATES THE 45 DEGREE RULE THAT SHALL BE FOLLOWED WHEN EXCAVATING A TRENCH THAT PARALLELS ANY FOUNDATION.





**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WHERE TRENCHES ARE MADE PARALLEL TO A BUILDING OR STRUCTURE AND ARE DEEPER THAN THE BUILDING OR STRUCTURE FOOTING, SUCH TRENCHES SHALL BE A MINIMUM DISTANCE AWAY FROM THE FOOTING AT LEAST EQUAL TO DEPTH OF THE TRENCH UNLESS PERMISSION TO VARY HEREFROM IS GRANTED BY THE ENFORCING AGENCY.

II. NOTE THAT THE DEPTH FOR A TRENCH PARALLELING ANY FOUNDATION IS LIMITED BY THE DISTANCE FROM THE FOUNDATION. FOR EXAMPLE, TRENCH DEPTH FOR A TRENCH WITH NEAREST SIDE TWO FEET FROM A FOUNDATION IS LIMITED TO A 2-FOOT DEPTH.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



TRENCH PARALLELING FOUNDATIONS

UG3367.1

**SCOPE:** THIS STANDARD SHOWS A TYPICAL SERVICE TRENCH EXCAVATION PARALLELING A RESIDENTIAL BUILDING. (EXCEPTION TO 45 DEGREE RULE ON SHEET 1/GAS STANDARD. 7415.1)





**FIGURE 2**

## INSTALLATION:

A. THE FOLLOWING CONDITION(S) MUST BE MET:
   1. BUILDING HAS A CONTINUOUS CONCRETE SLAB.
   2. BUILDING HEIGHT IS LIMITED TO TWO STORIES.
   3. BUILDING HEIGHT IS LIMITED TO TWO STORIES. 12-FOOT LENGTH ALONG THE FOUNDATION, AND MUST NOT EXCEED A 4-FOOT DEPTH.
   4. SOIL CONDITIONS MUST BE STABLE AND MUST NOT CAUSE UNDERMINING OF THE FOUNDATION.
   5. TRENCH WALLS MUST BE STABLE DURING AND AFTER EXCAVATION.

B. IF THE CONDITION(S) IN NOTE A CANNOT BE MET, THEN THE 45 DEGREE RULE MUST BE FOLLOWED. SEE SHEET 1.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE GAS STANDARDS 7415.1 & 7415.2 (FOR INTERNAL USE ONLY).
b. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



TRENCH PARALLELING FOUNDATIONS

UG3367.2

**SCOPE:** THIS IS A SHALLOW TRENCH CONFIGURATION FOR PRIMARY TRENCHES.

**ATTENTION:**

* THIS STANDARD IS RESERVED FOR AVOIDANCE OF UTILITIES, ENVIRONMENTAL CONDITIONS OR HARD DIGGING. THIS IS NOT A CONFIGURATION TO BE USED IN NORMAL CONDITIONS.






**FIGURE 1**
SHALLOW TRENCH




**DETAIL 1** (2) (I)
CONDUIT SPACER





**FIGURE 2**
SHALLOW TRENCH

**INSTALLATION:**

(A) NUMBER AND SIZE OF CONDUITS MAY VARY. A STANDARD DESIGN PACKAGE IS SHOWN WITH 2-5" AND 2-4" DIAMETER SCHEDULE 40 PVC CONDUITS IN DETAIL 1. DETAIL 2 SHOWS 2-4" DIAMETER SCHEDULE 40 PVC CONDUITS. DEVIATION REQUIRED FOR MORE THAN EIGHT CONDUITS.

(B) TRENCH WIDTH IS EQUAL TO THE NUMBER OF SPACERS TIMES THE WIDTH OF SPACER PLUS 8". ROUND UP TO NEAREST BUCKET SIZE. STANDARD BUCKET SIZES ARE: 12", 18", 24", 30", 36", 42", 48".

(C) 6" WARNING TAPE TO BE PLACED IN THE TRENCH AT TWO LEVELS, AT THE TOP OF THE TWO SACK SLURRY AND ON TOP OF THE CONCRETE MECHANICAL PROTECTION. SPACING TO BE 3" MIN.AND 12" MAX EDGE TO EDGE OF TAPE.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORGINAL ISSUE | NV5 | ADW | JES | CZH | 10/01/2021 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

SHALLOW TRENCHING
PRIMARY TRENCH

UG3368.1

TABLE OF CONTENTS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU | MACRO |
|---|---|---|---|---|---|---|---|
| 1 | 3" SCHEDULE 40 PVC CONDUIT (A) | AS REQ'D | UG 4204.4 | S251360 | LINEAR FEET | S40-3" | -- |
| | 4" SCHEDULE 40 PVC CONDUIT (A) | AS REQ'D | UG 4204.4 | S251392 | LINEAR FEET | S40-4" | |
| | 5" SCHEDULE 40 PVC CONDUIT (A) | AS REQ'D | UG 4204.4 | S251408 | LINEAR FEET | S40-5" | |
| 2 | 5" CONDUIT SPACER / 1" BASE SPACER (I) | AT 5' SPACING | UG 3375 | S663530 | EACH | -- | -- |
| 3 | TWO SACK SLURRY, DYED RED | AS REQ'D | UG 3366 | S248201 | LINEAR FEET | -- | -- |
| 4 | 3000 PSI CONCRETE WITH 4" SLUMP (II) | AS REQ'D | -- | -- | CUBIC YARDS | -- | -- |
| 5 | 6" WIDE RED WARNING TAPE WITH BLACK LETTERS | AS REQ'D | -- | -- | -- | (X) | -- |
| 6 | ASPHALT RESURFACING, PER AGENCY REQUIREMENTS (III) | AS REQ'D | UG 3363 | S114201 | LINEAR FEET | -- | AB-M24 |

## NOTES:

(I) CONDUIT SPACERS MAY VARY IN SIZE BASED ON MANUFACTURER AND TYPE. UNDERGROUND DEVICES, STACKABLE BOTTOM UNIT SHOWN IN DETAIL. VERIFY DIMENSIONS WITH MANUFACTURER.

(II) CONCRETE IS MECHANICAL PROTECTION PER G.O. 128.

(III) MACRO GIVEN FOR 24" WIDE TRENCH. QUANTITIES CAN BE ADJUSTED OR A DIFFERENT MACRO CAN BE USED FOR OTHER WIDTHS

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORGINAL ISSUE | NV5 | ADW | JES | CZH | 10/01/2021 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 2 OF 2

SHALLOW TRENCHING
PRIMARY TRENCH

UG3368.2

**SCOPE:** THIS STANDARD COVERS BIO-RETENTION FACILITIES AND SDG&E'S 600A AND 200A UNDERGROUND ELECTRIC SECONDARY, SERVICES AND GAS FACILITIES LOCATED ON RESIDENTIAL, COMMERCIAL, FEDERAL, STATE, AND MUNICIPAL LAND AND ALL OTHER PROPERTY TYPES. THE STANDARD APPLIES, BUT IS NOT LIMITED TO BIO-RETENTION BASINS AND/OR SWALES.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. BIO-RETENTION FACILITIES ARE WET FACILITIES THAT WILL REQUIRE MAINTENANCE OVER TIME. THESE FACILITIES WILL REQUIRE MAJOR TRENCHING AND MAY BE LOCATED WITHIN STREETS AND PRIVATE PROPERTY PRESENTING POTENTIAL CONFLICTS WITH SDG&E PRIMARY AND SECONDARY ELECTRIC CABLE AND CONDUITS, ELECTRIC SERVICES, GAS AND ANY OTHER SDG&E FACILITIES.

II. BIO-RETENTION FACILITIES ARE DESIGNED TO CONTROL WATER RUN-OFF AND POSSIBLE DRAINAGE OVER-FLOW OF STORM WATER.

III. DURING THE DESIGN PHASE FOR THESE FACILITIES CUSTOMERS MUST DESIGN TO MEET THE REQUIREMENTS OF UG3364 FOR LOCATION, AND NOT ENCROACH ON SDG&E'S STANDARD FACILITY LOCATIONS. (a)

IV. SINCE BIO-RETENTION FACILITIES ARE A WET UTILITY, SIMILAR TO STORM DRAINS AND WATER RELATED FACILITIES, THEY MUST COORDINATE WITH SDG&E TRENCHING AND FACILITY LOCATIONS, AND MEET FACILITY SEPARATION REQUIREMENTS SHOWN IN UG3370 FOR SAN DIEGO COUNTY AND UG3371 FOR ORANGE COUNTY. (b)

V. IN ACCORDANCE WITH THESE UNDERGROUND CONSTRUCTION STANDARDS, BIO-RETENTION FACILITIES MUST MAINTAIN 5 FEET SEPARATION WHEN INSTALLED PARALLEL TO ALL SDG&E FACILITIES. A MINIMUM 6-INCH SEPARATION SHALL BE MAINTAINED WHEN BIO-RETENTION DUCTS AND/OR CONDUITS CROSS SDG&E FACILITIES.

VI. BIO-RETENTION DUCTS OR CONDUITS THAT CROSS SDG&E FACILITIES MUST BE RIGID PIPE WITHOUT ANY PERFORATION FOR A DISTANCE OF 5 FEET MINIMUM ON EITHER SIDE OF, AND IN THE AREA OF, WHERE THEY CROSS SDG&E FACILITIES.

VII. IN ORDER TO MAINTAIN SAFE OPERATIONAL AND MAINTENANCE ACCESS, SDG&E FACILITIES SHALL NOT BE INSTALLED OVER, UNDER OR WITHIN BIO-RETENTION SWALES, BASINS, CELLS OR ANY OTHER OPEN HOLDING AREA FOR BIO-RETENTION.

VIII. BIO-RETENTION FACILITIES SHALL NOT ENCROACH ON SDG&E MANHOLES, HAND-HOLES, PAD MOUNTED EQUIPMENT, OVERHEAD POLES AND ANCHORS, AND ANY OTHER OVERHEAD FACILITIES. THIS APPLIES TO GAS METERS, GAS VALVES AND RELATED GAS FACILITIES SUCH AS GAS REGULATION FACILITIES.

IX. AS A GENERAL RULE, GAS AND ELECTRIC FACILITIES ARE ALLOWED UNDER PERVIOUS PAVERS UNDER WHICH THERE IS NO MEMBRANE, LINER, NOR PERFORATED DRAIN LINES. GAS AND ELECTRIC FACILITIES MUST NOT BE DEEPER THAN 5 FEET FROM FINISHED GRADE AND THERE MUST BE 12 INCHES MINIMUM OF SDG&E APPROVED SHADE MATERIAL OVER SDG&E FACILITIES.

TABLE OF CONTENTS

**REFERENCE:**

(a) FOR UTILITY LOCATIONS, SEE UG3364.

(b) FOR UNDERGROUND DISTRIBUTION TRENCHES AND UTILITY POSITIONS, SEE UG3370 AND UG3371.

c. SEE BIO-RETENTION APPLICATION GUIDE FOR MORE INFORMATION ABOUT HOW TO APPLY BIO-RETENTION/WET FACILITIES STANDARD.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | NOTES UPDATE | EDM | EJA | EJA | KRG | 11/03/2022 | F | | | | | | |
| B | NOTES UPDATE | EDM | EJA | GLW | CZH | 08/10/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JS | TR | MDJ | 06/10/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS TYPICAL PLACEMENT OF UTILITIES WITHIN TRENCHES FOR DISTRIBUTION AND SERVICE IN DEDICATED R/W (STREET) AND PRIVATE PROPERTY, AND PROVIDES THE MINIMUM DEPTH AND CLEARANCE THAT MUST BE MAINTAINED BETWEEN VARIOUS UTILITIES OCCUPYING THE SAME TRENCH IN SAN DIEGO COUNTY.





**FIGURE 1**





**FIGURE 2**





**FIGURE 3** (I)





**FIGURE 4**





**FIGURE 5**





**FIGURE 6**





**FIGURE 7**
SERVICE TRENCH ON PRIVATE PROPERTY





**FIGURE 8**
SERVICE TRENCH ON PRIVATE PROPERTY

**TABLE 1**

| LEGEND | |
|---|---|
| GM | GAS MAIN |
| GS | GAS SERVICE |
| P | PRIMARY ELECTRIC |
| S | SECONDARY ELECTRIC |
| ES | ELECTRIC SERVICE |
| ME | MULTIPLE ELECTRIC (P OR S OR ES OR T, STACKED CONFIGURATION INCLUDING SPACERS AND 2-SACK CONCRETE SLURRY) |
| SL | SDG&E STREET LIGHT |
| L | FOREIGN UTILITY STREET LIGHT |
| U | FOREIGN UTILITY (TELCO, CATV) |
| T | SDG&E TELECOMMUNICATIONS (Q) |
| EV | SDG&E ELECTRIC VEHICLE CHARGER (120V THRU 480V) |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



UNDERGROUND DISTRIBUTION (UD) TRENCHES AND UTILITY POSITIONING - S.D. COUNTY

UG3370.1





**FIGURE 9**
TIER 2 AND TIER 3





**FIGURE 10**
TIER 2 AND TIER 3

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TIER 2 AND TIER 3
UNDERGROUND DISTRIBUTION (UD) TRENCHES AND
UTILITY POSITIONING - S.D. COUNTY

UG3370.2

**ATTENTION:**

* THE FOLLOWING CHARTS SHOW THE MINIMUM COVER FOR EACH UTILITY, THE MINIMUM SEPARATION BETWEEN SPACE ALLOTMENTS AND THE MAXIMUM SIZE FOR EACH SPACE ALLOTMENT. TO READ THE CHARTS, READ ACROSS AND DOWN UNTIL THE TWO JOIN IN A SQUARE, AND THAT IS THE DISTANCE REQUIRED BETWEEN THE TWO UTILITIES.

** IN REFERENCE TO THE EXAMPLE BELOW (TABLE 2), UNDER VERTICAL, "ES" & "ES" JOIN AT (C) WHICH REFERS TO INSTALLATION NOTE (C).

*** UNDER HORIZONTAL, "ES" & "GS" JOIN AT 12 INCHES WHICH WOULD BE THE DISTANCE REQUIRED FROM THE OUTER EDGE OF THE ELECTRIC SERVICE (SPACE ALLOTMENT) TO THE OUTER EDGE OF GAS SERVICE (SPACE ALLOTMENT).

**TABLE 2**

| EXAMPLE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | | VERTICAL | | | HORIZONTAL | | | |
| | | | ES | | GS | | | |
| | | | ↓ | | ↓ | | | |
| ES | ELECTRIC SERVICE | → | C | → | 12" | | | |

**TABLE 3**

| MAIN TRENCH, [SERVICE TRENCH PUBLIC PROPERTY] (MINIMUM SEPARATION FROM) | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | VERTICAL (IN) | | | | | | | | | HORIZONTAL (IN) | | | | | | | | | | | |
| | | GM GS | P | S | ES | SL | ME | L | U | EV | GM GS | P | S | ES | SL | ME | L | U | EV | MIN. COVER (V) | FACILITY SPACE ALLOTMENT (MAX) |
| GM GS | GAS MAIN GAS SERVICE (D) (G) (N6) (N9) (N10) (N11) (d) (e) | - | 12" | 12" | 12" | 12" | 12" | 12" | (J) | (R) | - | - | - | - | - | - | - | (J) | (R) | 30" MIN. 42" MAX. | 4 1/2" X 4 1/2" |
| P | PRIMARY ELECTRIC (D) (N8) (N11) (d) (m) (e) (f) | 12" | (C) | (C) | (C) | (C) | (C) | - | 12" | (R) | - | (C) | (C) | (C) | (C) | (C) | 12" | - | (R) | 24" | 5 1/2" X 5 1/2" |
| S | SECONDARY ELECTRIC (D) (N11) (d) (e) (f) | 12" | (C) | (C) | (C) | (C) | (C) | - | 12" | 12" | - | (C) | (C) | (C) | (C) | (C) | 12" | 12" | 12" | 30" | 5 1/2" X 5 1/2" |
| ES | ELECTRIC SERVICE (D) (N11) (d) (e) (f) | 12" | (C) | (C) | (C) | (C) | (C) | - | 12" | 12" | - | (C) | (C) | (C) | (C) | (C) | 12" | 12" | 12" | 30" | 5 1/2" X 5 1/2" |
| SL | SDG&E STREET LIGHT (D) (N7) (N8) (N11) (d) (e) (f) | 12" | (C) | (C) | (C) | (C) | (C) | - | 12" | 12" | - | (C) | (C) | (C) | (C) | (C) | 12" | 12" | 12" | 30" | 2 1/2" X 2 1/2" |
| ME | MULTIPLE ELECTRIC (J) (K) (N11) (a) (f) | 12" | (C) | (C) | (C) | (C) | (C) | 12" | 12" | 12" | - | (C) | (C) | (C) | (C) | (C) | - | - | 12" | 30" | 18" X 14" (4 DUCTS) |
| L | FOREIGN UTILITY STREET LIGHT (F) (N8) (d) (e) | 12" | - | - | - | - | 12" | - | 12" | 12" | - | 12" | 12" | 12" | 12" | - | 1" OR LESS | 12" | 12" | 24" | 2 1/2" X 2 1/2" |
| U | FOREIGN UTILITY (TELCO, CATV) (F) (J) (L) (d) (e) | (J) | 12" | 12" | 12" | 12" | 12" | 12" | - | 12" | (J) | - | 12" | 12" | 12" | - | 12" | - | 12" | 24" | 9" X 24" |
| T | SDG&E TELECOMMUNICATIONS (C) | 12" | (C) | (C) | (C) | (C) | (C) | - | 12" | 12" | - | (C) | (C) | (C) | (C) | (C) | 12" | 12" | 12" | 30" | 4 1/2" X 4 1/2" |
| EV | SDG&E ELECTRIC VEHICLE CHARGER (480V THRU 120V) | (R) | (R) | 12" | 12" | 12" | 12" | 12" | 12" | - | (R) | (R) | 12" | 12" | 12" | 12" | 12" | 12" | - | 30" | 4 1/2" X 4 1/2" |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## TABLE 4

| SERVICE TRENCH PRIVATE PROPERTY (MINIMUM SEPARATION FROM) | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | VERTICAL | | | | | | HORIZONTAL | | | | | | | |
| | | GS | ES | ME | U | L | EV | GS | ES | ME | U | L | EV | MIN. COVER (V) | FACILITY SPACE ALLOTMENT (MAX) |
| GS | GAS SERVICE (D) (G) (N6) (N9) (N10) (N11) (d) (e) | - | 12" | 12" | - | 12" | (R) | - | 12" | - | 12" | 12" | (R) | 24" MIN. 42" MAX. | 2 1/2" X 2 1/2" |
| ES | ELECTRIC SERVICE (D) (G) (N11) (d) (e) (f) | 12" | (C) | (C) | 12" | 12" | 12" | 12" | (C) | (C) | 12" | 12" | 12" | 24" | 5 1/2" X 5 1/2" |
| ME | MULTIPLE ELECTRIC (K) (N11) (f) | 12" | (C) | (C) | 12" | 12" | 12" | - | (C) | (C) | - | - | 12" | 24" | WILL VARY DUE TO BOARD AMPACITY |
| U | FOREIGN UTILITY (TELCO, CATV) (F) (J) (L) (d) (e) | - | 12" | 6" | - | 12" | 12" | 12" | 12" | - | - | 12" | 12" | 18" | 9" X 9" |
| L | FOREIGN UTILITY STREET LIGHT (F) (N8) (d) (e) | 12" | 12" | 12" | 12" | - | 12" | 12" | 12" | - | 12" | 1" OR LESS | 12" | 18" | 2 1/2" X 2 1/2" |
| EV | SDG&E ELECTRIC VEHICLE CHARGER (480V THRU 120V) | (R) | 12" | 12" | 12" | 12" | - | (R) | 12" | 12" | 12" | 12" | - | 24" | 5 1/2" X 5 1/2" |

## INSTALLATION:

A. AN EFFORT SHOULD BE MADE TO KEEP THE TRENCH DEPTH LESS THAN 60 INCHES. IF A PERSON IS REQUIRED TO ENTER A TRENCH 60 INCHES OR DEEPER, IT SHALL BE SHORED, BENCHED, OR SLOPED TO PREVENT MOVEMENT OF EARTH THAT MAY ENDANGER LIFE OR PROPERTY. THE TRENCH CONFIGURATION, UTILITY POSITIONING AND ALL OTHER RELATED CONSTRUCTION MUST CONFORM TO THIS STANDARD AND THE STATE OF CALIFORNIA PUBLIC UTILITIES COMMISSION GENERAL ORDERS 128 AND 112D, AND ANY OTHER APPROPRIATE GOVERNMENTAL AGENCY HAVING JURISDICTION OVER CONSTRUCTION.

### CAUTION:

* BENCHING THE TRENCH IS FOR SAFETY REASONS ONLY AND NOT TO BE USED FOR INSTALLATION PURPOSES.

(B) THIS NOTE INTENTIONALLY LEFT BLANK

(C) ANY CONDUIT COMBINATION SMALLER THAN 5-INCH, (NOT MULTIPLE ELECTRIC-ME OR SERVICE CONDUITS) ARE PERMITTED WITHOUT SEPARATION WHEN INSTALLED IN A HORIZONTAL CONFIGURATION. SDG&E TELECOMMUNICATIONS SPACE ALLOTMENT IS PERMITTED NEXT TO THE ELECTRIC SPACE ALLOTMENTS WITHOUT SEPARATION. (6-INCH MINIMUM TRENCH WIDTH, 24-INCH MAXIMUM TRENCH WIDTH). (o)

(D) **BASE, SHADING, AND BACKFILL MATERIAL**

1. BASE AND SHADING MATERIAL FOR GAS TRENCH ONLY:

   IMPORTED MATERIAL CONSISTING OF NATURAL SAND OR MANUFACTURED SAND, EXISTING NATIVE MATERIAL, OR COMBINATIONS MAY BE USED FOR BASE AND SHADING MATERIAL PROVIDED IT COMPLIES WITH GAS STANDARD G7405 AND IS OF A QUALITY THAT WILL COMPLY WITH COMPACTION REQUIREMENTS OF GOVERNMENTAL AGENCIES. STANDARD G7405 SPECIFIES THAT THE MATERIAL MUST HAVE A MIXTURE OF PARTICLE SIZES ALL SMALLER THAN 1/2-INCH. EXISTING NATIVE MATERIAL AND IMPORTED MATERIAL PROVIDED BY A DEVELOPER DOES NOT HAVE TO BE TESTED BY AN INDEPENDENT PROFESSIONAL TESTING FIRM IF, IN THE OPINION OF THE INSPECTOR, IT MEETS THE G7405 SPECIFICATION.

2. SHADING MATERIAL FOR ELECTRIC TRENCH ONLY: ELECTRIC SHADING MATERIAL (ESM) SPECIFICATION.

   ACCEPTABLE MATERIAL FOR (DB) DIRECT BURIED CONDUITS. NATURAL SAND, MANUFACTURED SAND, DECOMPOSED GRANITE, ROCK FREE SANDY LOAM, EXISTING NATIVE MATERIAL OR COMBINATION THEREOF. AGGREGATE COMPOSITION SHALL BE CAPABLE OF PASSING THROUGH A 1/2-INCH SIEVE. GRAVELS SHALL NOT AMOUNT TO MORE THAN 50% OF THE MIXTURE. SCREENING OR OTHER SUITABLE MEANS MAY BE REQUIRED AT THE DISCRETION OF THE SDG&E INSPECTOR TO MEET THIS (ESM) SHADING MATERIAL SPECIFICATION. NOT ACCEPTABLE ARE SOILS OF HIGHLY ORGANIC CONTENT IDENTIFIED BY ODOR OR SPONGY FEEL AND HIGHLY PLASTIC (SOGGY) CLAYS, SILTS OR METALLIC SLAG.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## INSTALLATION (CONT'D):

3. BASE AND SHADING MATERIAL FOR JOINT GAS AND ELECTRIC TRENCH:

   WHEN BOTH GAS AND ELECTRIC ARE INSTALLED IN THE SAME TRENCH, THE BASE AND SHADING MATERIAL WHICH COMPLIES WITH GAS STANDARD G7405 SHALL BE USED FOR THE GAS PIPE. ELECTRIC SHADING MATERIAL (ESM) MAY BE USED FOR SHADING MATERIAL ON ELECTRIC CONDUIT.

4. BACKFILL MATERIAL FOR GAS AND/OR ELECTRIC:

   THE MATERIAL USED FOR BACKFILLING THE TRENCH ABOVE THE SHADING MATERIAL AND EXTENDING UPWARD TO THE SUBGRADE SHALL BE FREE OF ROCKS OR CLODS LARGER THAN 6 INCHES IN ANY DIMENSION. THE COARSE MATERIAL SHALL BE WELL DISTRIBUTED THROUGHOUT THE FINER MATERIAL. THE AMOUNT OF ROCKS OR CLODS SHALL BE LIMITED, IN THE OPINION OF THE INSPECTOR, TO ALLOW FOR BAR TESTING FOR GAS LEAKS. THE BACKFILL MATERIAL SHALL MEET THE REQUIREMENTS OF ALL APPLICABLE CODES, ORDINANCES AND SDG&E STANDARDS AND BE FREE OF DEBRIS AND ORGANIC MATTER. 2-SACK RED DYE CONCRETE SLURRY MIX MAY BE USED FOR FOR BACKFILL MATERIAL IF THE PIPE GAS IS SHADED WITH A MINIMUM OF 4 INCHES OF COMPACTED SHADING MATERIAL. 2-SACK RED DYE CONCRETE SLURRY MIX IS PREFERRED FOR BACKFILL. THE SLURRY INSTALLATION SHALL MEET THE REQUIREMENTS OF GOVERNMENTAL AGENCIES AND SDG&E STANDARDS.

5. BASE INSTALLATION FOR GAS:

   FOR GAS, 3 INCHES OF BASE MATERIAL IS REQUIRED ON THE BOTTOM OF THE TRENCH TO PREVENT DAMAGE FROM ROCKS, SAGS, OR POCKETS.

6. EARTH TRENCH BOTTOM INSTALLATION FOR ELECTRIC: (ENCASED BURIED & DIRECT BURIED CONDUIT)

   THE 1 1/2-INCH EARTH TRENCH BOTTOM SHALL BE STABLE WITH A UNIFORM GRADE CONTAINING NO HARD CLODS, ROCKS, ETC. THAT MAY DAMAGE THE CONDUIT. IF, IN THE OPINION OF THE SDG&E INSPECTOR, THE CONDUIT MAY BE DAMAGED, TAMPING, WETTING OR A 3-INCH BASE ELECTRIC SHADING MATERIAL (ESM) MAY BE REQUIRED.

7. SHADING INSTALLATION:

   A MINIMUM COVER OF 4 INCHES OF COMPACTED SHADING MATERIAL (4 INCHES AFTER COMPACTION) SHALL BE REQUIRED ABOVE THE GAS PIPE AND ELECTRIC CONDUIT. A MINIMUM COVER OF 12 INCHES OF COMPACTED SHADING MATERIAL WILL BE REQUIRED IF, IN THE OPINION OF THE INSPECTOR, THERE IS AN EXCESSIVE AMOUNT OF ROCK AND CLODS IN THE BACKFILL. THE SHADING MATERIAL MUST BE INSTALLED AND COMPACTED AT EACH LEVEL BEFORE INSTALLING THE NEXT UTILITY. THE SHADING MATERIAL MUST BE INSTALLED BEFORE THE TRENCH IS BACKFILLED TO PREVENT DAMAGE FROM ROCKS, CLODS, ETC. GAS PIPE SHALL NEVER BE CONCRETE OR SLURRY ENCASED, AND SHALL HAVE THE PROPER BASE, SHADING, BACKFILL, AND COMPACTION.

8. COMPACTION:

   EXTREME CARE SHALL BE TAKEN TO ENSURE THAT SHADING MATERIAL IS ADEQUATELY COMPACTED BOTH UNDERNEATH AND AROUND GAS PIPE AND FITTINGS TO PREVENT EXCESSIVE STRESS AND SHEARING FORCES. HAND TAMP AROUND FITTINGS WHERE MECHANICAL COMPACTION CANNOT BE USED. COMPACTING WITH A HYDRAHAMMER OR SIMILAR EQUIPMENT SHALL NOT BE ALLOWED ON TRENCHES WHERE POLYETHYLENE PIPE HAS BEEN INSTALLED. WHEN THE SHEEP'S FOOT METHOD OF COMPACTION IS USED, A MINIMUM OF 18 INCHES OF COVER IS REQUIRED BEFORE COMPACTING. WHEEL ROLLING WITH A HEAVY VEHICLE, COMBINED WITH ADEQUATE MECHANICAL COMPACTION, IF NEEDED, IS ALLOWED FOR COMPACTING BACKFILL MATERIAL PROVIDED A MINIMUM OF 4 INCHES OF MECHANICALLY COMPACTED SHADE MATERIAL AND A MINIMUM OF 12 INCHES OF BACKFILL MATERIAL EXISTS OVER THE GAS PIPE OR ELECTRICAL CONDUIT. WHEN FLOODING OF THE TRENCH IS DONE TO CONSOLIDATE BACKFILL, CARE MUST BE TAKEN TO ENSURE THAT GAS PIPE OR ELECTRIC CONDUIT HAS NOT FLOATED FROM ITS POSITION IN THE TRENCH. COMPACTION BY THE WATER JETTING METHOD IS NOT ALLOWED. SHADING AND BACKFILL SHALL BE COMPACTED IN ACCORDANCE WITH GOVERNMENTAL AGENCIES AND SHALL HAVE A MINIMUM OF 90 PERCENT RELATIVE COMPACTION.

9. ALL BASE, SHADING, AND BACKFILL MATERIAL MUST BE APPROVED BY AN SDG&E INSPECTOR.

(E) ALL 5-INCH PRIMARY CONDUITS SHALL BE INSTALLED WITH SPACERS AND ENCASED WITH CONCRETE SLURRY (2 SACK MIX).

(F) FOREIGN UTILITIES MUST NOT BE LOCATED UNDER ANY SDG&E FACILITIES, SUCH AS HANDHOLES, TRANSFORMER PADS, ETC.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## INSTALLATION (CONT'D):

### (G) TABLE 5

| MINIMUM TRENCH WIDTH | | | |
|---|---|---|---|
| | **UTILITY** | **PIPE/CONDUIT SIZE** | **MINIMUM WIDTH (IN)** |
| GAS | SINGLE GAS-SERVICE | 1-INCH AND LESS | 6 |
| | SINGLE GAS | 2-INCH | 9 |
| | SINGLE GAS | 3 AND 4 INCHES | 12 |
| | SINGLE GAS | 6 AND 8 INCHES | 18 |
| ELECTRICAL MAIN TRENCH | ALL CONDUIT SIZES INCLUDING 2-5 INCHES | | |
| | ELECTRIC | ALL SIZES | 6 |
| | JOINT UTILITIES | ALL PERMITTED SIZES (6 AND 8-INCH GAS) | 12<br>18 |
| | MULTIPLE ELECTRIC | SPACERS AND 2-SACK CONCRETE SLURRY | 9 |
| ELECTRICAL SERVICE TRENCH | SINGLE ELECTRIC | 2-INCH CONDUIT | 6 |
| | SINGLE ELECTRIC & FOREIGN UTILITIES (EXCLUDING GAS) | 2-INCH CONDUIT | 6 |
| | ELECTRIC | ALL SIZES | 9 |
| | SINGLE ELECTRIC & FOREIGN UTILITIES (EXCLUDING GAS) | LARGER THAT 2-INCH | 12 |
| | JOINT UTILITIES | ALL PERMITTED SIZES | 12 |
| | MULTIPLE ELECTRIC | SPACERS AND 2-SACK CONCRETE SLURRY | 9 |

H. FOR A GAS OR ELECTRIC SERVICE, IF ANY OBSTRUCTION IS ENCOUNTERED (WATER PIPES, ETC.), A 2'-0" X 3'-0" HOLE MAY BE REQUIRED FOR WORKING ROOM IN THE AREA OF THE OBSTRUCTION. THIS IS TO BE DETERMINED BY AN SDG&E INSPECTOR.

(J) THE FOREIGN UTILITY (U) SPACE ALLOTMENT MUST BE A MINIMUM OF 6 INCHES BELOW THE GAS MAIN AND 12-INCH RADIAL SEPARATION FROM ALL OTHER UTILITIES MUST BE MAINTAINED (SEE FIGURES 1 AND 5). IF (U) SPACE ALLOTMENT EXCEEDS A 9-INCH HORIZONTAL MEASUREMENT, IT MUST BE PLACED DIRECTLY ABOVE THE ELECTRIC SPACE ALLOTMENTS AND SHALL NOT EXTEND PAST THE OUTER SIDES OF ELECTRIC SPACE ALLOTMENTS. (FOR INSTALLATION PURPOSES, BENCHING THE TRENCH IS NOT ALLOWED). SEE FIGURES 2, 3, & 4. IF (U) SPACE ALLOTMENT IS 9" X 9" OR SMALLER, IT IS ALLOWED AT THE SAME LEVEL AS THE ELECTRIC (SEE FIGURE 6).

(K) ALL ENCASED BURIED CONDUIT, REGARDLESS OF THE SIZE, SHALL BE CONCRETE ENCASED WITH 2 SACK CEMENT SLURRY. DIRECT BURIED CONDUIT MAY ALSO BE SLURRY ENCASED IF INCLUDED IN THE MULTIPLE ELECTRIC PACKAGE. IN A SERVICE TRENCH, ALL ENCASED BURIED CONDUIT SHALL BE ENCASED WITH CEMENT SLURRY (2 SACK). DIRECT BURIED CONDUIT MAY ALSO BE CONCRETE OR SLURRY ENCASED IF INCLUDED IN THE MULTIPLE ELECTRIC PACKAGE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## INSTALLATION (CONT'D):

### (L) TABLE 6

| MINIMUM SEPARATION MAIN TRENCH | |
|---|---|
| **UTILITY** | **HORIZONTAL SEPARATION** |
| TELCO MULTIPLE CONCRETE DUCT (CONDEX), TRANSITE, WATER, SEWER, FUEL, OIL, DIESEL, PROPANE GAS, SPRINKLER, DRAIN, LEACH LINES, STEEL GAS MAIN LARGER THAN 2", PRIVATELY OWNED UTILITIES I.E. PRIVATE TELCO, VIDEO, AUDIO, SECURITY WIRES, FIRE ALARM, STREET LIGHTING, ETC. | NOT PERMITTED IN JOINT TRENCH WITH GAS AND/OR ELECTRIC |
| WATER, SEWER, EXISTING GAS OR ELECTRIC, STORM DRAINS, STEAM, IRRIGATION PIPE, SPRINKLER PIPE LARGER THAN 4", PRIVATE TELCO TRANSITE, PROPANE GAS | 5 FEET WITH 3 FEET OF UNDISTURBED SOIL (VI) |
| SEWAGE LEACH LINES OR SEEPAGE PITS | 5 FEET FROM MAIN TRENCH FOR EACH 1-FOOT DEPTH OF MAIN TRENCH |
| IRRIGATION, SPRINKLER PIPE 4" AND LESS | 3 FEET PROVIDED DEPTH OF PIPE DOES NOT EXCEED DEPTH OF GAS OR ELECTRIC (VI) |
| FUEL OIL, GASOLINE, DIESEL | FROM GAS - 15 FEET, FROM ELECTRIC - 5 FEET WITH 3 FEET OF UNDISTURBED SOIL |

## CAUTION:

* IN CONSIDERATION FOR THE SAFETY OF THE GENERAL PUBLIC, PERSONS ENGAGED IN CONSTRUCTION, PROPERTY, AND FOR THE OPERATION AND MAINTENANCE OF SDG&E SYSTEM, PROPANE GAS LINES ARE NOT PERMITTED IN A JOINT TRENCH WITH SDG&E FACILITIES.

### TABLE 7

| MINIMUM VERTICAL CROSSING SEPARATION | |
|---|---|
| **UTILITY** | **VERTICAL (CROSSING) SEPARATION** |
| ALL WET UTILITIES, TELCO, TV, GAS, ELECT. | 6 INCHES |
| FUEL OIL, GASOLINE, DIESEL | FROM GAS, 12 INCHES<br>FROM ELECT. 6 INCHES |
| ARC-WELDABLE PIPELINES 3" AND LARGER | 18 INCHES |
| STEAM (M) | FROM GAS, POLY PIPE 5 FEET<br>FROM ELECT., 5 FEET |

(M) PLACE INSULATING BARRIER BETWEEN STEAM MAIN AND POLYETHYLENE PIPE AND/OR ELECTRIC.

N. MINIMUM SEPARATION SERVICE TRENCH

1. IN A SERVICE TRENCH, WATER, SEWER, PROPANE GAS, SPRINKLER, DRAIN, LEACH LINES, PRIVATELY OWNED UTILITIES I.E., PRIVATE TELCO, VIDEO, AUDIO, SECURITY WIRES, FIRE ALARM, STREET LIGHTING, ETC., ARE NOT PERMITTED IN THE SAME TRENCH WITH GAS OR ELECTRIC. WHEN THESE FACILITIES PARALLEL GAS OR ELECTRIC, 12 INCHES SEPARATION BETWEEN SEPARATE TRENCHES SHALL BE MAINTAINED BETWEEN THE UTILITIES WITH AT LEAST 12 INCHES OF UNDISTURBED NATIVE SOIL BETWEEN TRENCHES. PROPANE GAS SHALL ALWAYS HAVE A 5-FOOT SEPARATION. WHEN CROSSING, A 6-INCH VERTICAL SEPARATION IS REQUIRED.
2. (EXCEPTION) WHEN THERE IS NO SDG&E GAS IN THE SERVICE TRENCH, A SINGLE NATURAL GAS LINE MAY BE INSTALLED IN THE TRENCH, PROVIDED A 12-INCH RADIAL SEPARATION IS MAINTAINED. (THIS IS FOR AN INDIVIDUAL HOUSE ON A CASE BY CASE BASIS, NOT A GROUP OF HOUSES/BUILDINGS).
3. FUEL OIL, GASOLINE, AND DIESEL LINES MUST MAINTAIN A 15-FOOT SEPARATION FROM GAS PIPELINES AND A FIVE-FOOT SEPARATION WITH THREE FEET OF UNDISTURBED SOIL SEPARATION FROM ELECTRIC CONDUITS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

4. IF FIELD CONDITIONS WILL NOT PERMIT THESE SEPARATIONS, THEN APPROVAL OF REDUCED SEPARATIONS MUST COME FROM BOTH THE CUSTOMER PROJECT PLANNER AND SDG&E INSPECTOR.
5. WHEN FIELD CONDITIONS WILL NOT PERMIT STANDARD PARALLEL SEPARATIONS, A 12-INCH MINIMUM SEPARATION IS REQUIRED. PROPANE GAS SHALL ALWAYS HAVE A 5-FOOT SEPARATION.

(6) THE GAS MAIN SHALL BE THE LAST INSTALLED, SHALL BE ON THE PROPERTY SIDE OF THE TRENCH, AND SHALL HAVE A MINIMUM OF INCH PAD (AFTER COMPACTION) OF SHADING MATERIAL THE WIDTH OF THE TRENCH ABOVE ANY FOREIGN UTILITY. ANY CROSSING INVOLVING GAS SHALL MAINTAIN A MINIMUM VERTICAL SEPARATION OF 6 INCHES. A GAS SERVICE INSTALLED IN A MAIN TRENCH OR A SERVICE TRENCH ON PUBLIC PROPERTY SHALL REQUIRE THE SAME COVER AND CLEARANCES AS A GAS MAIN. A GAS SERVICE IN A TRENCH ON PRIVATE PROPERTY MAY BE INSTALLED ON THE SAME LEVEL AS FOREIGN UTILITY OR ELECTRIC, BUT SHALL NOT BE DEEPER THAN THE ELECTRIC SERVICE. SDG&E INSPECTOR IS TO DETERMINE AT WHICH LEVEL THE GAS SERVICE IS INSTALLED ON PRIVATE PROPERTY.

(7) SDG&E INSTALLED STREET LIGHT CIRCUITS, WHEN INSTALLED ALONE IN A TRENCH, SHALL BE AT A MINIMUM DEPTH OF 24 INCHES EVERYWHERE EXCEPT ON PRIVATE PROPERTY, WHERE THE MINIMUM MAY BE 18 INCHES BELOW FINAL GRADE.

(8) THE ELECTRIC PRIMARY WILL BE ON THE STREET SIDE OF THE TRENCH. THE SDG&E STREET LIGHT CIRCUITS WILL BE ON THE PROPERTY SIDE OF THE TRENCH WHENEVER POSSIBLE. FOREIGN UTILITY STREET LIGHTS (NOT SERIES) SHALL BE ON THE PROPERTY SIDE OF THE TRENCH AT THE SAME LEVEL AS SDG&E CONDUITS AND SHALL MAINTAIN A 12-INCH RADIAL SEPARATION. ALL UTILITIES SHALL MAINTAIN A 6-INCH SEPARATION WHEN CROSSING ALL SDG&E ELECTRIC. FOR SEPARATION ON THE SERVICE TRENCH, SEE TABLES 3 AND 4.

(9) MINIMUM HORIZONTAL SEPARATION FROM GAS PIPE TO ANY FOREIGN SUBSTRUCTURE (VAULTS, HANDHOLES, ETC.) SHALL BE 12 INCHES.

(10) GAS LINES MUST NOT BE LOCATED UNDER ANY STRUCTURE, SUCH AS BUILDINGS, CARPORTS, PATIOS, BREEZEWAYS, EQUIPMENT PADS, AND FACILITIES, SUCH AS SPLICE BOXES FOR ELECTRIC, CATV, TELCO, ETC. TREES OR SHRUBBERY MUST NOT BE PLANTED OVER ANY GAS PIPELINE. A THREE-FOOT SEPARATION MUST BE MAINTAINED BETWEEN THE TREE ROOT BALL AND THE GAS PIPELINE.

(11) IF AN AGENCY OR UTILITY SUCH AS THE U.S. GOVERNMENT, SAN DIEGO UNIFIED PORT DISTRICT, TELCO, CATV, ETC. REQUIRES CONCRETE ENCASEMENT, CONCRETE MAY BE SUBSTITUTED FOR THE BACKFILL. BASE & SHADING SHALL BE PER SDG&E STANDARDS. ON SDG&E CONDUITS, EITHER DIRECT BURIED OR CONCRETE ENCASED, A MINIMUM INCH COMPACTED SHADING MATERIAL SHALL BE INSTALLED OVER THE UPPERMOST DIRECT BURIED CONDUITS BEFORE THE CONCRETE BACKFILL IS INSTALLED. ALL OTHER INSTALLATIONS SHALL PROVIDE THE REQUIRED MATERIALS AS SPECIFIED IN THIS STANDARD. (O) (d) (e) (o)

(O) THE GAS MAIN, GAS SERVICE SHALL NEVER BE CONCRETE OR SLURRY ENCASED AND SHALL HAVE THE PROPER BASE, SHADING, BACKFILL, AND COMPACTION.

P. MINIMUM SEPARATION OF ANY FOREIGN UTILITY INCLUDING WATER PIPES, SEWER, ETC., FROM SDG&E SUBSTRUCTURES SHALL BE 12 INCHES. PROPANE GAS SHALL BE 5 FEET.

(Q) SDG&E FIBER OPTIC COMMUNICATION CONDUIT MUST BE INSTALLED IN ALL NEW DISTRIBUTION MAIN FEEDER TRENCHES.

(R) ELECTRIC VEHICLE CHARGER SERVICE IS PROHIBITED IN JOINT TRENCH WITH GAS LINE OR PRIMARY ELECTRIC.

(S) WARNING TAPE NEEDS TO EXTEND A MINIMUM OF 1-INCH ON BOTH SIDES OF CONDUIT PACKAGE.

## BILL OF MATERIALS: NONE

## NOTES:

I. DRAWINGS ARE NOT TO SCALE.

II. SPACE ALLOTMENTS (OTHER THAN FOREIGN UTILITY) ARE 1/2-INCH LARGER THAN THE NOMINAL SIZE OF GAS MAIN, GAS SERVICE OR ELECTRIC CONDUIT. SEE INSTALLATION NOTE J FOR FOREIGN UTILITY SPACE ALLOTMENT.

III. TYPICAL TRENCH SECTIONS ARE DESIGNED FOR INSTALLATIONS WHERE EACH OCCUPANT IS UTILIZING ENTIRE SPACE ALLOTMENT. SIZE OF SPACE ALLOTMENTS MAY BE REDUCED OR ADDITIONAL ALLOTMENTS MAY BE ADDED PROVIDED MINIMUM COVER AND CLEARANCES ARE MAINTAINED, AS LISTED IN TABLES 3 AND 4. ONLY ONE FOREIGN UTILITY SPACE ALLOTMENT FOR TELCO AND/OR CATV IS ALLOWED PER TRENCH. WIDTH AND DEPTH OF THE TRENCH MUST BE ADJUSTED ACCORDING TO SPACE ALLOTMENTS, MINIMUM CLEARANCES AND MINIMUM COVER.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |



TABLE OF CONTENTS

## NOTES (CONT'D):

IV. GAS PIPE REQUIRES A MINIMUM OF 12 INCHES RADIAL SEPARATION FROM ALL UTILITIES.

(V) ALL MINIMUM COVER DEPTHS MEASURED FROM FINAL GRADE. REDUCED DEPTHS IN NOTE (B) ARE LESSER DEPTHS THAN WHAT IS SHOWN UNDER "MINIMUM COVER".

(VI) IF FIELD CONDITIONS WILL NOT PERMIT ANY OF THESE SEPARATIONS, THEN APPROVAL OF REDUCED SEPARATIONS MUST COME FROM BOTH THE CUSTOMER PROJECT PLANNER AND SDG&E INSPECTOR. ON FIELD CONDITIONS THAT WILL NOT PERMIT STANDARD PARALLEL SEPARATIONS, A 12-INCH MINIMUM SEPARATION IS REQUIRED. PROPANE GAS SHALL ALWAYS HAVE A 5-FOOT SEPARATION.

(VII) ALL TRENCH RESURFACING SHALL BE DONE ACCORDING TO GOVERNMENTAL PERMITTING AGENCIES.

## REFERENCE:

(a) SEE UG3362 (PREVIOUS # UG3364.1) FOR UTILITY LOCATIONS IN LOCAL AND COLLECTOR STREETS.

b. SEE UG3363 (PREVIOUS # UG3364.2) FOR UTILITY LOCATIONS IN MAJOR STREETS, PRIME ARTERIALS AND EXPRESSWAYS.

c. SEE UG3364 (PREVIOUS # UG3364.3) FOR JOINT TRENCH TYPICAL LOCATION FOR UNDERGROUND CONVERSIONS.

(d) SEE UG3365 FOR IMPORTED OR NATIVE BACKFILL MATERIAL.

(e) SEE UG3366 (PREVIOUS # UG3365.2) FOR SLURRY BACKFILL MATERIAL.

(f) CONCRETE OR CONCRETE SLURRY ENCASEMENT OF ELECTRIC CONDUITS SHALL BE IN ACCORDANCE WITH UG3376.

g. SEE UG3376, UG3421, UG3425, UG3426, AND UG3427 FOR CONDUIT CONFIGURATIONS ALLOWED IN THE SERVICE TRENCH.

(h) SEE UG4620 TELECOMMUNICATIONS INSTALLATION.

i. SEE SDG&E TRENCHING AND SHORING MANUAL FOR TRENCHING AND SHORING QUESTIONS.

j. SEE UG7403.1, UG7403.2, UG7403.3, UG7403.4, UG7403.5, AND UG7403.6 [FOR INTERNAL USE ONLY].

k. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

(l) SEE UG3376 FOR OTHER CONDUIT/TRENCH CONFIGURATIONS.

(m) SEE UG3366 (PREVIOUS # UG3365.2) FOR SLURRY BACKFILL REQUIREMENTS. (LOCAL GOVERNMENTAL AGENCIES MAY REQUIRE 2 SACK MIX FOR SPECIFIC APPLICATIONS.)

(n) SEE UG3365 (PREVIOUS # UG3365.1) FOR IMPORTED OR NATIVE BACKFILL REQUIREMENTS. (LOCAL GOVERNMENTAL AGENCIES MAY REQUIRE DIFFERENT BACKFILL MATERIAL OTHER THAN NATIVE BACKFILL.)

(o) SEE UG3376 FOR CONDUIT/TRENCH CONFIGURATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | EJA | GLW | CZH | 08/16/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 11/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS TYPICAL PLACEMENT OF UTILITIES WITHIN TRENCHES FOR DISTRIBUTION AND SERVICE IN DEDICATED R/W (STREET) AND PRIVATE PROPERTY, AND PROVIDES THE MINIMUM DEPTH AND CLEARANCE THAT MUST BE MAINTAINED BETWEEN VARIOUS UTILITIES OCCUPYING THE SAME TRENCH IN ORANGE COUNTY.





**FIGURE 1**





**FIGURE 2** (h)





**FIGURE 3**





**FIGURE 4**





**FIGURE 5**





**FIGURE 6**
SERVICE TRENCH ON PRIVATE PROPERTY

**TABLE 1**

| LEGEND | |
|---|---|
| **CODE** | **DESCRIPTION** |
| P | PRIMARY ELECTRIC |
| S | SECONDARY ELECTRIC |
| ES | ELECTRIC SERVICE |
| ME | MULTIPLE ELECTRIC (P OR S OR ES, STACKED CONFIGURATION INCLUDING SPACERS AND 1-SACK CONCRETE SLURRY) |
| SL | SDG&E STREET LIGHT |
| U | FOREIGN UTILITY STREET LIGHT, TELCO, (M) (L) CATV, GAS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



UNDERGROUND DISTRIBUTION (UD) TRENCHES AND UTILITY POSITIONING - ORANGE COUNTY

UG3371.1

**ATTENTION:**

* THE FOLLOWING TABLES SHOW THE COVER FOR EACH UTILITY, THE MINIMUM SEPARATION BETWEEN SPACE ALLOTMENTS AND THE MAXIMUM SIZE FOR EACH SPACE ALLOTMENT. TO READ THE TABLES, READ ACROSS AND DOWN UNTIL THE TWO JOIN IN A SQUARE, AND THAT IS THE DISTANCE REQUIRED BETWEEN THE TWO UTILITIES. SEE TABLE 2.

** UNDER VERTICAL, 'ES & ES' JOIN AT (C) WHICH REFERS TO INSTALLATION NOTE C.

*** UNDER HORIZONTAL, 'ES & U' JOIN AT 12 INCHES WHICH WOULD BE THE DISTANCE REQUIRED FROM THE OUTER EDGE OF THE ELECTRIC SERVICE (SPACE ALLOTMENT) TO THE OUTER EDGE OF THE FOREIGN UTILITY (SPACE ALLOTMENT).

## TABLE 2

| EXAMPLE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | | VERTICAL | | | HORIZONTAL | | | |
| | | | ES | | U | | | |
| | | | ↓ | | ↓ | | | |
| ES | ELECTRIC SERVICE | → | (C) | | 12" | | | |

## TABLE 3

| MAIN TRENCH MINIMUM SEPARATION (SERVICE TRENCH PUBLIC PROPERTY) | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | VERTICAL | | | | | | HORIZONTAL | | | | | | | | |
| | | P | S | ES | SL | ME | U | P | S | ES | SL | ME | U | MIN. COVER (IV) | FACILITY SPACE ALLOTMENT (MAX.) |
| P | PRIMARY ELECTRIC (D)(F)(N)(Q)(d)(e)(f) | | | | | | | | | | | | (V) | | |
| S | SECONDARY ELECTRIC (D)(N)(d)(e)(f) | | | | | | | | | | | | | | |
| ES | ELECTRIC SERVICE (D)(N)(d)(e)(f) | | | (C) | | | 12" | | | (C) | | | 12" | | 5 1/2" X 2 1/2" |
| SL | SDG&E STREET LIGHT (D)(J)(N)(Q)(d)(e)(f) | | | | | | | | | | | | | 30" | |
| ME | MULTIPLE ELECTRIC (G)(N)(f) | | | | | | | | | | | | | | 18" X 14" (4 DUCTS) |
| U | FOREIGN UTILITY (STREET LIGHT, TELCO, CATV) (H)(L)(M)(O) | | | 12" | | | (V) | (V) | | 12" | | | (V) | | 9" X 24" HORIZONTAL OR VERTICAL |
| | GAS (L)(M) | | | | | | | | | (V) | | | | | |

## TABLE 4

| SERVICE TRENCH PRIVATE PROPERTY MINIMUM SEPARATION | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | VERTICAL | | | HORIZONTAL | | | | | |
| | | ES | ME | U | ES | ME | U | MIN. COVER (IV) | FACILITY SPACE ALLOTMENT (MAX.) | |
| ES | ELECTRIC SERVICE (D)(F)(K)(N)(d)(e)(f) | (C) | | 12" | (C) | | 12" | 24" | 5 1/2" X 5 1/2" | |
| ME | MULTIPLE ELECTRIC (G)(N)(f)(h) | | | | | | (V) | | WILL VARY DUE TO BOARD AMPACITY (h) | |
| U | FOREIGN UTILITY (STREET LIGHT, TELCO, CATV) (H)(K)(L)(M)(O) | 12" | | (V) | 12" | (V) | | | 9" X 24" HORIZONTAL OR VERTICAL | |
| | GAS (L)(M) | | | | (V) | | | | | |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

UNDERGROUND DISTRIBUTION (UD) TRENCHES AND UTILITY POSITIONING - ORANGE COUNTY

UG3371.2

TABLE OF CONTENTS

## INSTALLATION:

A. AN EFFORT SHOULD BE MADE TO KEEP THE TRENCH DEPTH LESS THAN 60 INCHES. IF A PERSON IS REQUIRED TO ENTER A TRENCH 60 INCHES OR DEEPER, IT SHALL BE SHORED, BENCHED, OR SLOPED TO PREVENT MOVEMENT OF EARTH THAT MAY ENDANGER LIFE OR PROPERTY. THE TRENCH CONFIGURATION, UTILITY POSITIONING AND ALL OTHER RELATED CONSTRUCTION MUST CONFORM TO THIS STANDARD AND THE STATE OF CALIFORNIA PUBLIC UTILITIES COMMISSION GENERAL ORDERS 128 AND 112-F, AND ANY OTHER APPROPRIATE GOVERNMENTAL AGENCY HAVING JURISDICTION OVER CONSTRUCTION. (I)

## CAUTION:

* BENCHING THE TRENCH IS FOR SAFETY REASONS ONLY AND NOT TO BE USED FOR INSTALLATION PURPOSES.

(B) THE TRENCH DEPTH IN THIS STANDARD SHALL BE FOLLOWED FOR ALL NORMAL INSTALLATIONS. IN INSTALLATIONS WHERE THE TRENCH DEPTH CANNOT BE MET, G.O. 128 REQUIRES ONE OF THE FOLLOWING:

1. STEEL
2. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 0.15 INCHES
3. A 3-INCH LAYER OF CONCRETE (2-SACK 3/8-INCH ROCK) ABOVE AND 2 INCHES ON EACH SIDE OF THE CONDUIT. REDUCED DEPTHS MUST BE APPROVED BY BOTH THE PROJECT MANAGEMENT SPECIALIST AND SDG&E INSPECTOR.

(C) ANY CONDUIT COMBINATION 5-INCH AND SMALLER, (NOT MULTIPLE ELECTRIC-ME OR SERVICE CONDUITS) ARE PERMITTED WITHOUT SEPARATION WHEN INSTALLED IN A HORIZONTAL CONFIGURATION (6-INCH MINIMUM TRENCH WIDTH, 24-INCH MAXIMUM TRENCH WIDTH). (h)

(D) BASE, SHADING, AND BACKFILL MATERIAL

1. SHADING MATERIAL FOR GAS AND/OR ELECTRIC: WHEN BOTH GAS AND ELECTRIC ARE INSTALLED IN THE SAME TRENCH, THE ELECTRIC SHADING MATERIAL (ESM) SHALL BE USED FOR SHADING ELECTRICAL CONDUITS. THE LOCAL GAS CO. SHALL SPECIFY THE MATERIAL REQUIRED FOR THEIR PORTION OF THE TRENCH.
2. SHADING MATERIAL FOR ELECTRIC TRENCH ONLY: ELECTRIC SHADING MATERIAL (ESM) SPECIFICATION. ACCEPTABLE MATERIAL FOR DIRECT BURIED (DB) CONDUIT. NATURAL SAND, MANUFACTURED SAND, DECOMPOSED GRANITE, ROCK FREE SANDY LOAM, EXISTING NATIVE MATERIAL OR COMBINATION THEREOF. AGGREGATE COMPOSITION SHALL BE CAPABLE OF PASSING THROUGH A 1/2-INCH SIEVE. GRAVELS SHALL NOT AMOUNT TO MORE THAN 50 PERCENT OF THE MIXTURE. SCREENING OR OTHER SUITABLE MEANS MAY BE REQUIRED AT THE DISCRETION OF THE SDG&E INSPECTOR TO MEET THIS (ESM) SHADING MATERIAL SPECIFICATION.
3. NOT ACCEPTABLE ARE SOILS OF HIGHLY ORGANIC CONTENT IDENTIFIED BY ODOR OR SPONGY FEEL AND HIGHLY PLASTIC (SOGGY) CLAYS, SILTS, OR METALLIC SLAG.
4. BACKFILL MATERIAL FOR GAS AND/OR ELECTRIC: THE MATERIAL USED FOR BACKFILLING THE TRENCH ABOVE THE SHADING MATERIAL AND EXTENDING UPWARD TO THE SUBGRADE SHALL BE FREE OF ROCKS OR CLODS LARGER THAN 6 INCHES IN ANY DIMENSION. THE COARSE MATERIAL SHALL BE WELL DISTRIBUTED THROUGHOUT THE FINER MATERIAL. THE AMOUNT OF ROCKS OR CLODS SHALL BE LIMITED, AND MUST BE APPROVED BY AN SDG&E INSPECTOR. THE BACKFILL MATERIAL SHALL MEET THE REQUIREMENTS OF ALL APPLICABLE CODES, ORDINANCES AND SDG&E STANDARDS AND BE FREE OF DEBRIS AND ORGANIC MATTER. 1-SACK CONCRETE SLURRY MIX IS THE PREFERRED BACKFILL MATERIAL. THE SLURRY INSTALLATION SHALL MEET THE REQUIREMENTS OF GOVERNMENTAL AGENCIES, LOCAL GAS CO., AND SDG&E STANDARDS.
5. EARTH TRENCH BOTTOM INSTALLATION FOR ELECTRIC (EB & DB CONDUIT): THE 1-INCH EARTH TRENCH BOTTOM SHALL BE STABLE WITH A UNIFORM GRADE CONTAINING NO HARD CLODS, ROCKS, ETC. THAT MAY DAMAGE THE CONDUIT. IF, IN THE OPINION OF THE SDG&E INSPECTOR, THE CONDUIT MAY BE DAMAGED, TAMPING, WETTING OR A 3-INCH BASE ELECTRIC SHADING MATERIAL (ESM) MAY BE REQUIRED.
6. SHADING INSTALLATION: A MINIMUM COVER OF 4 INCHES OF COMPACTED SHADING MATERIAL (4 INCHES AFTER COMPACTION) SHALL BE REQUIRED ABOVE ANY ELECTRICAL CONDUIT. A MINIMUM COVER OF 12 INCHES OF COMPACTED SHADING MATERIAL WILL BE REQUIRED IF, IN THE OPINION OF THE INSPECTOR, THERE IS AN EXCESSIVE AMOUNT OF ROCK AND CLODS IN THE BACKFILL. THE SHADING MATERIAL MUST BE INSTALLED AND COMPACTED AT EACH LEVEL BEFORE INSTALLING THE NEXT UTILITY. THE SHADING MATERIAL MUST BE INSTALLED BEFORE THE TRENCH IS BACKFILLED TO PREVENT DAMAGE FROM ROCKS, CLODS, ETC. GAS PIPE SHALL NEVER BE CONCRETE OR SLURRY ENCASED, AND SHALL HAVE THE PROPER BASE, SHADING, BACKFILL, AND COMPACTION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## INSTALLATION (CONT'D):

7. COMPACTION: EXTREME CARE SHALL BE TAKEN TO ENSURE THAT SHADING MATERIAL IS ADEQUATELY COMPACTED BOTH UNDERNEATH AND AROUND GAS PIPE AND FITTINGS TO PREVENT EXCESSIVE STRESS AND SHEARING FORCES. HAND TAMP AROUND FITTINGS WHERE MECHANICAL COMPACTION CANNOT BE USED. COMPACTING WITH A HYDRAHAMMER OR SIMILAR EQUIPMENT SHALL NOT BE ALLOWED ON TRENCHES WHERE POLYETHYLENE PIPE HAS BEEN INSTALLED. WHEN THE SHEEP'S FOOT METHOD OF COMPACTION IS USED, A MINIMUM OF 18 INCHES OF COVER IS REQUIRED BEFORE COMPACTING. WHEEL ROLLING WITH A HEAVY VEHICLE, COMBINED WITH ADEQUATE MECHANICAL COMPACTION, IF NEEDED, IS ALLOWED FOR COMPACTING BACKFILL MATERIAL PROVIDED A MINIMUM OF 6 INCHES OF MECHANICALLY COMPACTED SHADE MATERIAL AND A MINIMUM OF 12 INCHES OF BACKFILL MATERIAL EXISTS OVER THE GAS PIPE OR ELECTRICAL CONDUIT. WHEN FLOODING OF THE TRENCH IS DONE TO CONSOLIDATE BACKFILL, CARE MUST BE TAKEN TO ENSURE THAT GAS PIPE OR ELECTRIC CONDUIT IS NOT FLOATED FROM ITS POSITION HAS IN THE TRENCH. COMPACTION BY THE WATER JETTING METHOD IS NOT ALLOWED. SHADING AND BACKFILL SHALL BE COMPACTED IN ACCORDANCE WITH GOVERNMENTAL AGENCIES AND SHALL HAVE A MINIMUM OF 90 PERCENT RELATIVE COMPACTION.
8. ALL BASE, SHADING, AND BACKFILL MATERIAL MUST BE APPROVED BY AN SDG&E INSPECTOR.

(E) ONE OR MORE 5-INCH PRIMARY CONDUITS SHALL BE SLURRY ENCASED.

(F) **TABLE 5**

| MINIMUM TRENCH WIDTH | | | |
|---|---|---|---|
| | **UTILITY** | **CONDUIT SIZE** | **MINIMUM DEPTH (IN)** |
| ELECTRICAL MAIN TRENCH | ALL CONDUIT SIZES INCLUDING 2-5 INCHES | | -- |
| | ELECTRIC | ALL SIZES | 6 |
| | JOINT UTILITIES | ALL SIZES | 12 |
| | MULTIPLE ELECTRIC | SPACERS AND 1-SACK CONCRETE SLURRY | 9 |
| ELECTRICAL SERVICE TRENCH | SINGLE ELECTRIC | 2-INCH CONDUIT | 6 |
| | SINGLE ELECTRIC AND FOREIGN UTILITIES (EXCLUDING GAS) | 2-INCH CONDUIT | 6 |
| | ELECTRIC | ALL SIZES | 9 |
| | SINGLE ELECTRIC AND FOREIGN UTILITIES (EXCLUDING GAS) | LARGER THAN 2-INCH | 12 |
| | JOINT UTILITIES | ALL PERMITTED SIZES | 12 |
| | MULTIPLE ELECTRIC | SPACERS AND 1-SACK CONCRETE SLURRY | 9 |

1. IF ANY OBSTRUCTION IS ENCOUNTERED (WATER PIPES, ETC.), A 2-FOOT WIDE X 3-FOOT LONG HOLE MAY BE REQUIRED FOR WORKING ROOM IN THE AREA OF THE OBSTRUCTION. THIS IS TO BE DETERMINED BY AN SDG&E INSPECTOR.

(G) ALL EB CONDUIT, REGARDLESS OF THE SIZE, SHALL BE CONCRETE ENCASED WITH 1-SACK CEMENT SLURRY. DB CONDUIT MAY ALSO BE CONCRETE OR SLURRY ENCASED IF INCLUDED IN THE MULTIPLE ELECTRIC PACKAGE. IN A SERVICE TRENCH, ALL EB CONDUIT SHALL BE ENCASED WITH CEMENT 1-SACK SLURRY.

(H) **TABLE 6**

| MINIMUM SEPARATION MAIN TRENCH | |
|---|---|
| **UTILITY** | **HORIZONTAL SEPARATION** |
| TELCO MULTIPLE CONCRETE DUCT (CONDEX), TRANSITE, WATER, SEWER, FUEL, OIL, DIESEL, PROPANE GAS, SPRINKLER, DRAIN, LEACH LINES, STEEL GAS MAIN LARGER THAN 2 INCHES, PRIVATELY OWNED UTILITIES, I.E. PRIVATE TELCO VIDEO, AUDIO, SECURITY WIRES, FIRE ALARM, STREET LIGHTING ETC., STEEL GAS MAIN LARGER THAN 2 INCHES | NOT PERMITTED IN TRENCH |
| WATER, SEWER, EXISTING GAS OR ELECTRIC, STORM DRAINS, STEAM, IRRIGATION PIPE, SPRINKLER PIPE LARGER THAN 4 INCHES, PRIVATE TELCO TRANSITE, PROPANE GAS | 5 FEET WITH 3 FEET OF UNDISTURBED SOIL (H1) |
| SEWAGE LEACH LINES OR SEEPAGE PITS | 5 FEET FROM MAIN TRENCH FOR EACH 1-FOOT DEPTH OF MAIN TRENCH |
| IRRIGATION, SPRINKLER PIPE, 4 INCHES AND LESS | 3 FEET PROVIDED DEPTH OF PIPE DOES NOT EXCEED DEPTH OF ELECTRIC. (H1) |
| FUEL OIL, GASOLINE, DIESEL | 5 FEET WITH 3 FEET OF UNDISTURBED SOIL |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

## CAUTION:

* IN CONSIDERATION OF SAFETY FOR THE GENERAL PUBLIC, PERSONS ENGAGED IN CONSTRUCTION, PROPERTY AND OPERATION AND MAINTENANCE OF SDG&E SYSTEM, PROPANE GAS LINES ARE NOT PERMITTED IN A JOINT TRENCH WITH SDG&E FACILITIES.

1. IF FIELD CONDITIONS WILL NOT PERMIT ANY OF THESE SEPARATIONS, THEN APPROVAL OF REDUCED SEPARATIONS MUST COME FROM BOTH THE CUSTOMER PROJECT PLANNER AND SDG&E INSPECTOR. ON FIELD CONDITIONS THAT WILL NOT PERMIT STANDARD PARALLEL SEPARATIONS, A 12-INCH MINIMUM SEPARATION IS REQUIRED. PROPANE GAS SHALL ALWAYS HAVE A 5-FOOT SEPARATION.

### TABLE 7

| MINIMUM VERTICAL CROSSING SEPARATION | |
|---|---|
| **UTILITY** | **VERTICAL (CROSSING) SEPARATION (MIN.)** |
| ALL WET UTILITIES, TELCO, TV, GAS, ELECTRIC | 6 INCHES |
| FUEL OIL, GASOLINE, DIESEL | 6 INCHES |
| ARC-WELDABLE PIPELINES, 4-INCH AND LARGER | 18 INCHES |
| STEAM (H2) | 5 FEET |

2. PLACE INSULATING BARRIER BETWEEN STEAM MAIN AND GAS AND/OR ELECTRIC.

J. MINIMUM SEPARATION SERVICE TRENCH

1. IN A SERVICE TRENCH, WATER, SEWER, PROPANE GAS, SPRINKLER, DRAIN, LEACH LINES, PRIVATELY OWNED UTILITIES I.E. PRIVATE TELCO, VIDEO, AUDIO, SECURITY WIRES, FIRE ALARM, STREET LIGHTING ETC., ARE NOT PERMITTED IN THE SAME TRENCH WITH ELECTRIC. WHEN THESE FACILITIES PARALLEL ELECTRIC, 12 INCHES SEPARATION BETWEEN SEPARATE TRENCHES SHALL BE MAINTAINED BETWEEN THE UTILITIES WITH AT LEAST 12 INCHES OF UNDISTURBED NATIVE SOIL BETWEEN TRENCHES. PROPANE GAS SHALL ALWAYS HAVE A 5-FOOT SEPARATION. WHEN CROSSING, A 6-INCH VERTICAL SEPARATION IS REQUIRED.
2. (EXCEPTION) WHEN THERE IS NO SOUTHERN CAL. GAS IN THE SERVICE TRENCH, A SINGLE NATURAL GAS LINE MAY BE INSTALLED IN THE TRENCH PROVIDED A 12-INCH RADIAL SEPARATION IS MAINTAINED. (THIS IS FOR AN INDIVIDUAL HOUSE ON A CASE BY CASE BASIS, NOT A GROUP OF HOUSES/BUILDINGS).
3. FUEL OIL, GASOLINE, AND DIESEL LINES MUST MAINTAIN A FIVE-FOOT SEPARATION WITH THREE FEET OF UNDISTURBED SOIL SEPARATION FROM ELECTRIC CONDUITS.
4. IF FIELD CONDITIONS WILL NOT PERMIT THESE SEPARATIONS, THEN APPROVAL OF REDUCED SEPARATIONS MUST COME FROM BOTH THE CUSTOMER PROJECT PLANNER AND SDG&E INSPECTOR.
5. WHEN FIELD CONDITIONS WILL NOT PERMIT STANDARD PARALLEL SEPARATIONS, A 12-INCH MINIMUM SEPARATION IS REQUIRED. PROPANE GAS SHALL ALWAYS HAVE A 5-FOOT SEPARATION.

(K) ON CONVERSIONS A SINGLE ELECTRIC SERVICE ("ES") IN THE SERVICE TRENCH MAY BE INSTALLED WITHOUT SEPARATION FROM TELCO AND CATV.

(L) THE "SOUTHERN CAL." GAS MAIN OR GAS SERVICE SHALL NOT BE PLACED AT THE SAME LEVEL AS ELECTRIC.

(M) FOREIGN UTILITIES MUST NOT BE LOCATED UNDER ANY SDG&E ELECTRIC FACILITIES, SUCH AS HANDHOLES, TRANSFORMER PADS, ETC..

(N) IF AN AGENCY OR UTILITY SUCH AS THE U.S. GOVERNMENT, SAN DIEGO UNIFIED PORT DISTRICT, TELCO, CATV, ETC., REQUIRES CONCRETE ENCASEMENT, CONCRETE MAY BE SUBSTITUTED FOR THE BACKFILL. BASE & SHADING SHALL BE PER SDG&E STANDARDS. ON SDG&E CONDUITS, EITHER DIRECT BURIED OR CONCRETE ENCASED, A MINIMUM 6-INCH COMPACTED SHADING MATERIAL SHALL BE INSTALLED OVER THE UPPERMOST DB CONDUITS BEFORE THE CONCRETE BACKFILL IS INSTALLED. ALL OTHER INSTALLATIONS SHALL PROVIDE THE REQUIRED MATERIALS AS SPECIFIED IN THIS STANDARD, UG3365, AND UG3376.

1. THE GAS MAIN, GAS SERVICE SHALL NEVER BE CONCRETE OR SLURRY ENCASED AND SHALL HAVE THE PROPER BASE, SHADING, BACKFILL, AND COMPACTION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

## INSTALLATION (CONT'D):

(O) MINIMUM SEPARATION OF ANY FOREIGN UTILITY INCLUDING WATER PIPES, SEWER, ETC., FROM SDG&E SUBSTRUCTURES SHALL BE 12 INCHES. PROPANE GAS SHALL BE 5 FEET.

(P) SDG&E INSTALLED STREET LIGHT CIRCUITS, WHEN INSTALLED ALONE IN A TRENCH, SHALL BE AT A MINIMUM DEPTH OF 24 INCHES EVERYWHERE, EXCEPT ON PRIVATE PROPERTY, WHERE THE MINIMUM MAY BE 18 INCHES BELOW FINAL GRADE.

(Q) THE ELECTRIC PRIMARY WILL BE ON THE STREET SIDE OF THE TRENCH. THE SDG&E STREET LIGHT CIRCUITS WILL BE ON THE PROPERTY SIDE OF THE TRENCH WHENEVER POSSIBLE. ALL UTILITIES SHALL MAINTAIN A 6-INCH SEPARATION WHEN CROSSING ALL SDG&E ELECTRIC. (FOR SEPARATION ON THE SERVICE TRENCH, SEE TABLE 1 AND 2).

**BILL OF MATERIALS:** NONE

## NOTES:

I. FIGURES ARE NOT TO SCALE.

II. SPACE ALLOTMENTS (OTHER THAN FOREIGN UTILITY) ARE 1/2-INCH LARGER THAN THE NOMINAL SIZE OF ELECTRIC CONDUIT.

III. TYPICAL TRENCH SECTIONS ARE DESIGNED FOR INSTALLATIONS WHERE EACH OCCUPANT IS UTILIZING HIS ENTIRE SPACE ALLOTMENT. SIZE OF SPACE ALLOTMENT MAY BE REDUCED OR ADDITIONAL ALLOTMENTS MAY BE ADDED PROVIDING MINIMUM COVER AND CLEARANCES ARE MAINTAINED AS LISTED ON TABLE 3 AND 4. ONLY ONE FOREIGN UTILITY SPACE ALLOTMENT IS ALLOWED PER TRENCH. WIDTH AND DEPTH OF THE TRENCH MUST BE ADJUSTED ACCORDING TO SPACE ALLOTMENTS, MINIMUM CLEARANCES AND MINIMUM COVER.

(IV) ALL MINIMUM COVER DEPTHS MEASURED FROM FINAL GRADE. REDUCED DEPTHS IN NOTE (B) ARE LESSER DEPTHS THAN WHAT IS SHOWN UNDER "MINIMUM COVER".

(V) NOT ALLOWED.

## REFERENCE:

a. FOR UTILITY LOCATIONS IN LOCAL AND COLLECTOR STREETS, SEE UG3362.

b. FOR UTILITY LOCATIONS IN MAJOR STREETS, PRIME ARTERIALS AND EXPRESSWAYS, SEE UG3363.

c. FOR JOINT TRENCH TYPICAL LOCATION FOR UNDERGROUND CONVERSIONS, SEE UG3364.

(d) FOR IMPORTED OR NATIVE BACKFILL MATERIAL, SEE UG3365.

(e) FOR SLURRY BACKFILL MATERIAL, SEE UG3366.

(f) FOR TRENCH PARALLELING FOUNDATIONS, SEE UG3367.

g. FOR SAN DIEGO COUNTY JOINT TRENCH STANDARD, SEE UG3370.

(h) CONCRETE OR CONCRETE SLURRY ENCASEMENT OF ELECTRIC CONDUITS SHALL BE IN ACCORDANCE WITH UG3376.

i. FOR CONDUIT CONFIGURATIONS ALLOWED IN THE SERVICE TRENCH, SEE UG3376, UG3421, UG3425, UG3426, AND UG3427.

j. FOR TRENCHING AND SHORING QUESTIONS, SEE SDG&E TRENCHING AND SHORING MANUAL.

k. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

(l) SEE G.O. 128 AND G.O. 112.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/26/2016 | D | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| X | Indicates Latest Revision | | Completely Revised | | New Page | | Information Removed |



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

UNDERGROUND DISTRIBUTION (UD) TRENCHES AND UTILITY POSITIONING - ORANGE COUNTY

UG3371.6

**SCOPE:** THIS STANDARD LISTS THE MINIMUM CONDUIT SIZE REQUIRED FOR THE INSTALLATION OF PRIMARY AND SECONDARY CABLES.

**TABLE 1**

| CONDUIT SIZING CHART | | | | |
|---|---|---|---|---|
| CABLE TYPE | CONDUCTOR SIZE (AWG OR KCMIL) | MINIMUM CONDUIT SIZE (IN) | | |
| | | 1/C | 2-1/C | 3-1/C |
| **PRIMARY** | | | | |
| XLPECN-PEJ | 1/C #2 SOL AL | 3 | 3 (C) | 4 (D)(G) |
| XLPECN-PEJ | 3-1/C #2 SOL AL | -- | -- | 4 (G) |
| XLPECN-PEJ | #2/0 AL | -- | -- | 4 (B)(G) |
| XLPECN-PEJ | 350 AL | -- | -- | 5 (B)(F) |
| EPR-PEJ | 750 COMP AL | -- | -- | 4 (B) |
| XLPECN-PEJ | 1000 AL | -- | -- | 5 (B) |
| XLPECN-PEJ | 1000 CU | -- | -- | 5 (B) |
| **SECONDARY** | | | | |
| XLPE | 2-#8 | 1 | | (E)(c) |
| | 2-#2 & 1-#4 | 2 | | |
| | 2-#1/0 & 1-#2 | 2 | | |
| | 2-#3/0 & 1-1/0 | 2 | | |
| | 3-#3/0 & 1-1/0 | 3 | | |
| | 3-350 KCMIL & 1-#3/0 | 3 | | |
| | 2-350 & 1-#3/0 | 3 | | |
| | 3-500 KCMIL & 1-350 KCMIL | 4 | | |
| | 3-1000 KCMIL & 1-500 KCMIL | 5 | | |

TABLE OF CONTENTS

## INSTALLATION:

A. INSTALL CONDUIT AS SPECIFIED ON TABLE 1.

(B) 2/0, 350, 750 COMP, 1000 PRIMARY CABLES ARE ONLY PURCHASED IN TRIPLEX CONFIGURATION.

(C) 2-1 /C #2 SOL PECN-PEJ CABLES MAY BE PARALLELED IN A 3-INCH CONDUIT FOR SINGLE-PHASE 12KV LOAD.

(D) 3-1 /C #2 SOL PECN-PEJ CABLES MAY BE PARALLELED IN A 4-INCH CONDUIT FOR THREE-PHASE LOAD.

(E) CONDUIT FROM A RISER POLE TO THE FIRST LOCATION SHALL BE 2-INCH MINIMUM.

(F) MAY BE INSTALLED IN EXISTING 4-INCH CONDUITS.

(G) MAY BE INSTALLED IN EXISTING 3-INCH CONDUITS.

**BILL OF MATERIALS:** NONE

## NOTES:

I. IF FUTURE LOAD GROWTH REQUIRES LARGER CABLE THAN INITIAL REQUIREMENTS, SIZE CONDUIT FOR FUTURE NEEDS. PROJECT MANAGEMENT SUPERVISOR'S APPROVAL IS REQUIRED.

## REFERENCE:

a. FOR "CONDUIT SIZING CHARTS" OF CABLES NO LONGER PURCHASED, SEE FMO UG3372.

b. FOR RESIDENTIAL OR COMMERCIAL SERVICE LATERAL CONDUIT REQUIREMENTS, SEE UG3942.

(c) FOR CABLE POLE RISER INSTALLATION, SEE UG4204.

d. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | GLC | FRC | FRC | FRC | 01/24/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE CONDUIT AND FITTINGS USED TO CONSTRUCT UNDERGROUND CONDUIT SYSTEMS. CONDUIT AND FITTINGS IN THIS STANDARD SHALL BE USED IN BELOW-GROUND OR BRIDGE CELL APPLICATIONS.





**FIGURE 1**
(PVC) POLYVINYLCHLORIDE CONDUIT
CONDUIT STRAIGHT SECTIONS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**(PVC) POLYVINYLCHLORIDE CONDUIT**

I. PVC CONDUIT SHALL BE GRAY OR BLACK IN COLOR. NO OTHER COLOR IS ACCEPTABLE FOR SDG&E CONDUIT SYSTEM.

II. FOR SCHEDULE 40 AND SCHEDULE 80 ABOVE-GROUND COMPONENTS TO CONSTRUCT CABLE POLE RISERS, SEE UG4204.

III. ALL 5-INCH CONDUIT MUST BE ENCASED WITH CONCRETE SLURRY (1-SACK MIX).

IV. DB CONDUIT IS REQUIRED FOR INSTALLATIONS REQUIRING DIRECT BURIED MATERIAL, I.E. SAND, DECOMPOSED GRANITE (DG), NATIVE, ETC.

V. FOR DIRECT BURIED INSTALLATIONS, DB 60 IS REQUIRED FOR 2-INCH, 3-INCH, AND 5-INCH CONDUIT. DB 100 IS REQUIRED FOR 4-INCH CONDUIT.

VI. ALL COUPLINGS, BENDS, AND SWEEPS CLASSIFIED AS DB ARE TO BE USED WITH DB AND EB CONDUIT.

VII. DB = DIRECT BURIED CONDUIT

VIII. EB = ENCASED BURIED CONDUIT

IX. THE SHELF LIFE FOR DB CONDUIT, BENDS, AND FITTINGS EXPOSED TO SUNLIGHT IS 6 MONTHS MAXIMUM. 2-#8 FROM A RISER POLE TO THE FIRST LOCATION SHALL BE INSTALLED IN 2-INCH CONDUIT.

XI. POLYETHYLENE CONDUIT SHALL BE BLACK OR BLACK WITH THREE EQUALLY SPACED RED STRIPS. NO OTHER COLOR IS ACCEPTABLE FOR THE SDG&E CONDUIT SYSTEM.

XII. CORRUGATED POLYETHYLENE CONDUIT IS NOT ACCEPTABLE FOR THE SDG&E CONDUIT SYSTEM.

(XIII) S280384 SCH 40 PVC MAY BE USED AS A REPLACEMENT ON A TEMPORARY BASIS (DEPENDS ON SUPPLIER OF COUPLING).

(XIV) SCHEDULE 40 CONDUIT IS REQUIRED IN BRIDGE CELLS.

**TABLE 1**

| (PVC) POLYVINYLCHLORIDE CONDUIT | | | | | | |
|---|---|---|---|---|---|---|
| CONDUIT SIZE (IN) | TYPE | LENGTH 'L' (FT) | STOCK NUMBER | DESIGN UNITS | | |
| | | | | 1-SACK ENCASE W/SPACERS | PRIMARY | SEC/SERV |
| 2 | DB 60 | 20 | S249632 | IDB2-P | 1DB2-P | 1DB2-S |
| 3 | DB 60 | 20 | S249664 | IDB3-P | 1DB3-P | 1DB3-S |
| 4 | DB 100 | 20 | S249710 | IDB4-P | 1DB4-P | 1DB4-S |
| 5 | DB 60 | 20 | S249728 | 1, 2DB5SL | 1DB5-P | 1DB5-S |
| | SCH40 (XIV) | 10 | S251408 | -- | S40-5" | S40-5" |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | EJA | GLW | CZH | 05/11/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JS | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JW | 08/10/2004 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |



TABLE OF CONTENTS

## TABLE 2

| (PE) POLYETHYLENE CONDUIT | | | | |
|---|---|---|---|---|
| CONDUIT SIZE (IN) | TYPE | COIL LENGTH (FT) | STOCK NUMBER | DESIGN UNIT |
| 1 | SDR 9 | 2,000 | S249630 | 1" PE |
| 2 | SCH 40 | 2,500 | S252002 | 2" PE |
| 3 | SCH 40 | 1,000 | S252004 | 3" PE |
| 4 | SDR 15.5 | 500 | S252006 | 4" PE |
| 5 | SCH 80 | 20 LENGTHS | S252008 | 5" PE |




**FIGURE 2**
DB SWEDGE COUPLING




**FIGURE 3**
DB MOLDING COUPLING
(BOTH WITH CENTER STOPS)

## TABLE 3 (FIGURE 2 AND 3)

| CONDUIT COUPLINGS | |
|---|---|
| COUPLING CONDUIT SIZE (IN) | DB STOCK NUMBER |
| 2 (XIII) | S279872 |
| 3 | S279904 |
| 4 | S279936 |
| 5 | S280032 |




**FIGURE 4**
DB STRAIGHT COUPLING (WITHOUT CENTER STOPS, TO BE USED ONLY WHEN REPAIRING EXISTING CONDUIT SYSTEMS)

## TABLE 4 (FIGURE 4)

| CONDUIT COUPLINGS | |
|---|---|
| COUPLING CONDUIT SIZE (IN) | DB STOCK NUMBER |
| 2 | -- |
| 3 | S279920 |
| 4 | S279952 |
| 5 | S280064 |





**FIGURE 5**
CONDUIT PLUG





**FIGURE 6**
CONDUIT BELL REDUCER





**FIGURE 7**
CONDUIT END CAP

## TABLE 5 (FIGURE 5)

| CONDUIT PLUG | | |
|---|---|---|
| CONDUIT SIZE (IN) | STOCK NUMBER | DESIGN UNITS |
| 2 | S544768 | PLUG-2 |
| 3 | S544800 | PLUG-3 |
| 4 | S544704 | PLUG-4 |
| 5 | S544736 | PLUG-5 |

## TABLE 6 (FIGURE 6)

| CONDUIT BELL REDUCER | | |
|---|---|---|
| CONDUIT SIZE X TO Z (IN) | STOCK NUMBER | DESIGN UNITS |
| 3 - 2 | S573376 | RED3-2 |
| 4 - 3 | S573380 | RED4-3 |
| 5 - 4 | S573384 | RED5-4 |

## TABLE 7 (FIGURE 7)


| CONDUIT END CAP | | |
|---|---|---|
| CONDUIT SIZE (IN) | STOCK NUMBER | DESIGN UNITS |
| 2 | S203296 | CAP-02 |
| 3 | S203328 | CAP-03 |
| 4 | S203360 | CAP-04 |
| 5 | S203392 | CAP-05 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | EJA | GLW | CZH | 05/11/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JS | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JW | 08/10/2004 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |



TABLE OF CONTENTS




EXAMPLE 1
90 DEGREE ELBOW/24" RADIUS




EXAMPLE 2
22 1/2 DEGREE SWEEP/25'-0" RADIUS

**FIGURE 8**
CONDUIT BENDS

## TABLE 8

| CONDUIT BENDS | | | | | | | |
|---|---|---|---|---|---|---|---|
| NOMINAL CONDUIT SIZE (IN) | DEGREE OF CURVATURE (DEG) | RADIUS OF CURVATURE | TYPE OF CONDUIT | STOCK NUMBER | DESIGN UNITS | | |
| | | | | | CONCRETE ENCASE | PRIMARY | SEC/SERV |
| 2 | 22 1/2 | 25'-0" | DB 60 | S321808 | 1EB2-S | 1DB2PS | 1DB2SS |
| | 45 | 24" (SECONDARY ONLY) | DB 60 | S321920 | -- | -- | 1DB2S8 |
| | 45 | 36" | DB 60 | S321810 | 1EB2-8 | 1DB2-8 | -- |
| | 90 | 24" (SECONDARY ONLY) | DB 60 | S321984 | -- | -- | 1DB2SB |
| | 90 | 36" | DB 60 | S321812 | 1EB2-B | 1DB2-B | -- |
| 3 | 11 1/4 | 25'-0" | DB 60 | S321876 | 1EB3-C | 1DB3-C | 1DB3SC |
| | 22 1/2 | 25'-0" | DB 60 | S322144 | 1EB3-S | 1DB3PS | 1DB3SS |
| | 45 | 36" | DB 60 | S321878 | 1EB3-8 | 1DB3-8 | 1DB3S8 |
| | 90 | 36" | DB 60 | S322048 | 1EB3-B | 1DB3-B | 1DB3SB |
| 4 | 11 1/4 | 25'-0" | DB 100 | S321884 | 1EB4-C | 1DB4-C | 1DB3SC |
| | 22 1/2 | 25'-0" | DB 100 | S321826 | 1EB4-S | 1DB4PS | 1DB4SS |
| | 45 | 36" | DB 100 | S321942 | 1EB4-8 | 1DB4-8 | 1DB4S8 |
| | 90 | 36" | DB 100 | S322082 | 1EB4-B | 1DB4-B | 1DB4SB |
| 5 | 11 1/4 | 25'-0" | DB 60 | S321882 | 1EB5-C | 1DB4-C | 1DB5SC |
| | 22 1/2 | 25'-0" | DB 60 | S321856 | 1EB5-S | 1DB5PS | 1DB5SS |
| | 45 | 60" | SCH 80 | TBD | 1EB5-8 | 1DB5-8 | 1DB5S8 |
| | 90 | 60" | SCH 80 | TBD | 1EB5-B | 1DB5-B | 1DB5SB |

## REFERENCE:

a. FOR SPLICING OR REPAIRING 1-INCH POLYETHYLENE CONDUIT, SEE UG3383.

b. FOR CABLE POLE INSTALLATION, SEE UG4204.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | EJA | GLW | CZH | 05/11/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JS | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JW | 08/10/2004 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |

**SCOPE:** THIS STANDARD SHOWS PRACTICES WHICH ARE ESSENTIAL FOR PROPER INSTALLATION OF A CONDUIT SYSTEM.

## INSTALLATION:

### CUTTING CONDUIT/CHAMFERING

(A) A FINE-TOOTH SAW SHOULD BE USED TO CUT CONDUIT (I.E., HACKSAW FOR CONDUIT TWO INCHES OR LESS, WOODSAW FOR CONDUIT GREATER THAN TWO INCHES). THE CONDUIT MUST BE CUT STRAIGHT AND CLEANED OF BURRS. CONDUIT TRANSITIONS FROM SCHEDULE 40 OR SCHEDULE 80 EB OR DB CONDUIT SHALL BE CHAMFERED. IF CONDUITS ARE NOT CHAMFERED BY THE MANUFACTURER, THE CONDUITS MUST BE CHAMFERED IN THE FIELD WITH A KNIFE OR HALF ROUND FILE, ETC.




**FIGURE 1** (A)

B. TO ASSURE A PROPER JOINT, SDG&E AND CONTRACTORS ARE TO USE ONLY SDG&E APPROVED SOLVENT CEMENTING PVC TO PVC OR ABS TO PVC CONDUIT AS DESCRIBED IN THE BILL OF MATERIAL. MAKE CERTAIN THAT ALL FOREIGN MATTER HAS BEEN WIPED FROM BOTH THE CONDUIT AND FITTINGS. APPLY A LIBERAL AND UNIFORM COAT OF SOLVENT CEMENT TO THE DUCT END A LENGTH EQUAL TO THE DEPTH OF THE BELL OR COUPLING BEING ATTACHED. FOR MAXIMUM STRENGTH ALSO APPLY A LIGHT COAT ON THE INSIDE ON THE COUPLING OR BELLED END. PREVENT EXCESS SOLVENT CEMENT FROM BEING FORCED INTO THE FITTING AT THE INSIDE SHOULDER OF THE CONDUIT. A NATURAL BRISTLE BRUSH OR THE APPLICATOR SUPPLIED WITH THE SOLVENT CONTAINER SHOULD BE USED. PLASTIC BRISTLE BRUSHES SHOULD NOT BE USED AS THE SOLVENT WILL DISSOLVE THE BRISTLES. FOLLOW THE MANUFACTURERS INSTRUCTIONS ON THE SOLVENT CONTAINER. SOLVENT CEMENT WITH A PAST EXPIRATION DATE INDICATED ON THE CONTAINER MUST BE DISCARDED. CONTRACTORS MAY OBTAIN LARGER CONTAINERS OF SOLVENT CEMENT IF NEEDED. THE LARGER CONTAINERS HAVE DIFFERENT CATALOG NUMBERS THAN SPECIFIED ON THE BILL OF MATERIAL.

### BENDS AND SWEEPS

C. ANY JOINT INCLUDED IN A SECTION OF CONDUIT TO BE BENT IN A DITCH SHOULD BE FIRMLY STAKED FOR THE DESIRED RADIUS TO ENSURE THAT THE JOINT IS NOT DISTURBED OR DAMAGED BEFORE OR AFTER BACKFILL OR ENCASEMENT IS COMPLETED. IN CASES WHERE A PLASTIC CONNECTION IS MADE WITH THE JOINTS UNDER STRESS DUE TO MISALIGNMENT OR OTHER FACTORS, THE PLASTIC JOINT MUST BE HELD RIGID AFTER INSERTION UNTIL COMPLETELY CURED. WHERE STAKES ARE LOCATED AT THE CENTER OF A BEND OR SWEEP, CARE MUST BE EXERCISED TO PREVENT DEFORMATION OF DUCT DUE TO MOVEMENT BY CONTRACTION AND EXPANSION. STAKES TO BE REMOVED AFTER INITIAL BACKFILL IS PLACED.

D. HORIZONTAL BENDS (PRIMARY) IN THE CONDUIT SHALL BE MADE ONLY WITH LONG SWEEPS OF 25'-0" RADIUS OR LARGER WHENEVER POSSIBLE. SMALLER RADIUS SWEEPS MAY BE INSTALLED ONLY IF SPACE LIMITATIONS PROHIBIT THE USE OF THE 25'-0" RADIUS SWEEPS AND PULLING TENSIONS PERMIT (E.G. SHORT-SIDE SERVICES IN A SUBDIVISION). SHOULD FIELD CONDITIONS WARRANT A SMALLER RADIUS, APPROVAL MUST COME FROM BOTH THE CUSTOMER PROJECT PLANNER AND THE SDG&E INSPECTOR.

### EXPANSION AND CONTRACTION

E. DUE TO EXPANSION AND/OR CONTRACTION OF PLASTIC CONDUIT, BACKFILL FROM CENTER OF TRENCH BOTH WAYS OR FROM ONE TIE-IN POINT TOWARD THE OPPOSITE END OF THE TRENCH.

### TERMINATING CONDUIT, CONDUIT ENTRANCES AND CONNECTIONS

(F) ALL CONDUIT MUST BE WATERTIGHT AND MECHANICALLY SOUND AT THE SUBSTRUCTURE ENTRY POINT. CONDUIT SHALL BE TERMINATED IN SUBSTRUCTURES AS FOLLOWS:

1. CONDUIT END SHALL BE FLUSH WITH THE INTERIOR SURFACE OF SUBSTRUCTURE CONDUIT TERMINATOR.
2. USE A CONDUIT BELL REDUCER WHEN CONDUIT IS SMALLER THAN CONDUIT TERMINATOR KNOCKOUT (EXCEPT WITH 1-INCH CONDUIT). FOR 1-INCH CONDUIT, USE THE SUBSTRUCTURE ADAPTOR(S) SHOWN ON PAGE 3382.1.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 10/9/2020 | E | | | | | | |
| A | NO CHANGES - RE-AFFIRMED | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT INSTALLATION PRACTICES



UG3374.1

TABLE OF CONTENTS

## INSTALLATION (CONT'D):

3. UNLESS OTHERWISE SPECIFIED ON THE JOB PRINT, INSTALL CONDUIT USING THE BOTTOM SET OF TERMINATOR KNOCKOUTS FIRST. IF ONLY ONE CONDUIT IS REQUIRED, USE THE BOTTOM OUTSIDE (CLOSET TO WALL) KNOCKOUT.
4. WHEN CONDUITS MUST ENTER THE SUBSTRUCTURE IN ANY AREA WHERE TERMINATION KNOCKOUTS ARE NOT PROVIDED, THE SUBSTRUCTURE MUST BE CORE BORED. CORE BORING LOCATIONS WILL BE SPECIFIED BY THE CUSTOMER PROJECT PLANNER AND MUST BE APPROVED (CLOSET TO WALL) KNOCKOUT. AN EFFORT SHOULD BE MADE TO MAINTAIN 5 FEET OF STRAIGHT PRIMARY CONDUIT FOR 90 DEGREE BENDS JUST OUTSIDE ANY SUBSTRUCTURE.
5. WHEN SUBSTRUCTURE REINFORCING STEEL IS EXPOSED BY CORE BORING, IT MUST BE COATED WITH GALVANOX (STOCK NUMBER S516064) AND THEN COATED WITH COAL TAR EPOXY (STOCK NUMBER S241000) TO MOISTURE SEAL. AFTER CONDUIT IS TERMINATED IN THE SUBSTRUCTURE, SEAL THE SUBSTRUCTURE ENTRANCE WITH CEMENT GROUT.

G. TYPICAL METHODS FOR ROUTING CONDUITS INTO HANDHOLES AND MANHOLES: (VII)





**FIGURE 2**
TOP VIEW
SINGLE TRENCH





**FIGURE 3**
TOP VIEW
SEPARATE TRENCHES

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 10/9/2020 | E | | | | | | |
| A | NO CHANGES - RE-AFFIRMED | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | CATALOG NO. | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 1 | SOLVENT CEMENTS (CLEAR) | PERMALITE | 405C | -- | -- | S213232 | -- |
| | | CERTAINTEED | 85172 | -- | -- | | -- |
| | | CARLON | VC9982 | -- | -- | | -- |
| 2 | GALVANOX PAINT (F) | | -- | -- | -- | S516064 | -- |
| 3 | COAL TAR EPOXY (F) | | -- | -- | -- | S241000 | -- |

## NOTES:

I. EACH CONDUIT RUN BETWEEN SUBSTRUCTURES, PADS, CUSTOMER SERVICE, RISERS, ETC., SHALL BE ONE SIZE CONDUIT CONTINUOUSLY, I.E., NO REDUCERS ARE ALLOWED WITHIN A CONDUIT RUN EXCEPT WHERE THE CONDUIT ENTERS THE SUBSTRUCTURE OR ABOVE THE GROUND LEVEL ON A RISER POLE. IF A STUBOUT IS LARGER THAN THE CONDUIT REQUIRED, CONTINUE USING THE LARGER SIZE CONDUIT TO THE FIRST TERMINATION POINT THEN CONTINUE WITH THE SMALLER CONDUIT SIZED FOR THE CABLE. DEVIATIONS MUST BE APPROVED BY SDG&E'S CONSTRUCTION STANDARDS GROUP.

II. ROUNDNESS OF CONDUIT MUST BE MAINTAINED AT ALL TIMES.

III. DO NOT CUT SWEEPS & ELBOWS, THEY ARE NOT SIZED TO ACCEPT COUPLINGS.

IV. ALL BENDS, SWEEPS AND ELBOWS SHOWN ON JOB PRINT MUST BE INCLUDED IN CABLE PULLING CALCULATION.

V. FIELD BENDS ARE NOT ACCEPTABLE.

VI. TO AVOID CUTTING THE CONDUIT BENDS, SUBSTRUCTURES AND/OR CABLE POLES WHICH REQUIRE A 90° BEND SHALL BE LOCATED FAR ENOUGH AWAY FROM EACH OTHER TO ALLOW ROOM ENOUGH FOR THE TWO 90° BENDS. THIS WILL VARY DEPENDING ON THE SIZE OF THE 90° BEND.

(VII) IN EACH SUBSTRUCTURE AS MANY CONDUIT KNOCKOUTS MAY BE USED AS NEEDED, PROVIDING PROPER INSTALLATION IS FOLLOWED AND REQUIRED UNOBSTRUCTED SPACE IS MAINTAINED. INSTALL CONDUITS USING THE LOWER SET OF KNOCKOUTS FIRST, UNLESS OTHERWISE SPECIFIED ON JOB PRINT. IF ONLY ONE CONDUIT IS REQUIRED, USE THE BOTTOM OUTSIDE (CLOSET TO THE WALL) KNOCKOUT.

## REFERENCE:

a. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 10/9/2020 | E | | | | | | |
| A | NO CHANGES - RE-AFFIRMED | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS CONDUIT SPACERS FOR MULTI-DUCT INSTALLATION.




**FIGURE 1**
INTERMEDIATE SPACER OR BASE SPACER
USED IN BRIDGE CELLS




**FIGURE 2**
BASE SPACER




**FIGURE 3**
5-INCH VERTICAL SPACER
FOR 9-INCH WIDTH TRENCH

**TABLE 1**

| CONDUIT SPACERS | | | |
|---|---|---|---|
| **CONDUIT SIZE (IN)** | **DESCRIPTION** | **QUANTITY** | **STOCK NUMBER** |
| 5 | INTERMEDIATE SPACER | AS REQ'D | S663528 |
| 5 | 1" BASE SPACER | AS REQ'D | S663530 |
| 5 | BASE SPACER (USED IN BRIDGE CELLS) | AS REQ'D | S663008 |
| 5 | VERTICAL SPACER | AS REQ'D | S663532 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT SPACER DATA



UG3375.1

**SCOPE:** THIS STANDARD SHOWS CEMENT AND SLURRY MIXTURE. ALSO SHOWN ARE CONCRETE SLURRY ENCASED CONDUIT INSTALLATIONS.

**TABLE 1**

| DATA FOR CONDUITS WHICH ARE NORMALLY INSTALLED 2 CONDUITS WIDE AND 1 THRU 4 ROWS HIGH | | |
|---|---|---|
| NUMBER OF CONDUITS IN TRENCH | CONCRETE PER 100 FT OF TRENCH, CUBIC YARDS | |
| | 4" CONDUITS | 5" CONDUITS |
| 2 | 5.5 | 5.2 |
| 4 | 8.7 | 8.5 |
| 6 | 12.4 | 11.8 |
| 8 | 16.1 | 15.1 |

**TABLE 2**

| INGREDIENTS FOR 1 - SACK CONCRETE SLURRY MIX (PER YARD) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CEMENT FOR | AIR ENTRAINMENT (%) | SAND (LBS) | GRAVEL | | CEMENT | | MAX., TOTAL WATER PER SACK OF CEMENT (GALS/YARD) | SLUMP | |
| | | | SIZE | LBS | SACKS | LBS | | MIN. (IN) | MAX. (IN) |
| ENCASEMENT | 0-2 | 3000 ± 50 | - | - | 1 | 94 | 60 | 6 | 8 |

**TABLE 3**

| INGREDIENTS FOR 2 - SACK CONCRETE SLURRY MIX (PER YARD) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CEMENT FOR | AIR ENTRAINMENT (%) | SAND (LBS) | GRAVEL | | CEMENT | | MAX., TOTAL WATER PER SACK OF CEMENT (GALS/YARD) | SLUMP | |
| | | | SIZE | LBS | SACKS | LBS | | MIN. (IN) | MAX. (IN) |
| ENCASEMENT | 0-2 | 1600 ± 20 | 3/8 | 1600 ± 20 | 2 | 188 | 50 | 6 | 8 |

TABLE OF CONTENTS

## INSTALLATION:

**SECONDARY SERVICE TRENCH:** (a) (b) (c)

A. INSTALLATION WHERE CONCRETE SLURRY ENCASEMENT (1 SACK MIX) AND SPACERS ARE REQUIRED:

1. WHEN CONDUITS ARE IN A STACKED CONFIGURATION WITH SPACERS, ENCASED BURIED (EB) CONDUITS MUST BE ENCASED WITH 1 SACK SLURRY. DIRECT BURIED (DB) CONDUITS ARE ALSO ACCEPTABLE WHEN EXTENDED FROM A DIRECT BURIED TRENCH INTO THE STACKED CONFIGURATION.

B. INSTALLATION FOR CONCRETE SLURRY ENCASEMENT (1 SACK MIX) OR IMPORTED/NATIVE MATERIAL WITHOUT SPACERS:

1. WHEN CONDUITS ARE SIDE BY SIDE ON THE BOTTOM OF THE TRENCH (4 CONDUITS MAX.). IN THE TRANSITION AREA WHERE THE CONDUITS FROM THE BOTTOM OF THE TRENCH START TOWARD THE SURFACE (THE STRAIGHT PORTION BY THE 90 BEND), SPACERS MAY BE REQUIRED TO ALLOW THE 90 BENDS TO ENTER STRAIGHT INTO THE PAD OPENING. USE DIRECT BURIED (DB) CONDUIT WITH IMPORTED NATIVE MATERIAL. USE ENCASED BURIED (EB) CONDUITS WITH CONCRETE SLURRY ENCASEMENT (1 SACK MIX). DIRECT BURIED (DB) CONDUITS ARE ALSO ACCEPTABLE.

2. IF THE SERVICE CONDUIT EXTENDS INTO THE MAIN TRENCH WHERE STACKING IS REQUIRED, ALL CONDUITS SHALL BE INSTALLED IN ONE PACKAGE WITH SPACERS AND 1 SACK SLURRY.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 03/09/2020 | F | | | | | | |
| B | NOTES UPDATE | - | JES | JES | CZH | 05/23/2019 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |

## INSTALLATION (CONT'D):

**MAIN FEEDER TRENCH OR PRIMARY TRENCH:** (c)(d)

C. INSTALLATION WHERE CONCRETE SLURRY ENCASEMENT (1 SACK MIX) AND SPACERS ARE REQUIRED:

1. ALL 5-INCH PRIMARY CONDUITS SHALL BE INSTALLED WITH SPACERS AND ENCASED WITH CONCRETE SLURRY (1 SACK MIX).
2. WHEN CONDUITS ARE IN A STACKED CONFIGURATION WITH SPACERS, ENCASED BURIED (EB) CONDUITS MUST BE ENCASED WITH 1 SACK SLURRY.

(3) EXCAVATE TRENCH TO REQUIRED DEPTH AND WIDTH. (e)





**FIGURE 1** (C3)

(4) MULTI-SIZED CONDUIT SYSTEMS TO BE A MAXIMUM OF TWO CONDUITS WIDE AND FIVE CONDUITS HIGH (UP TO TEN SPACER POSITIONS IN ONE TRENCH). IF MORE THAN TEN POSITIONS ARE REQUIRED, A SEPARATE CONDUIT BANK SHALL BE INSTALLED IN A SEPARATE TRENCH. MAINTAIN 5 FEET SEPARATION WITH 3 FEET OF UNDISTURBED NATIVE SOIL BETWEEN TRENCHES.

(5) ASSEMBLE CONDUITS IN SPACERS ON TOP OF THE GROUND OR IN THE TRENCH. PLACE SPACERS 8 TO 10 FEET APART.





**FIGURE 2** (C5)




**FIGURE 3** (C5)

6. SPOT POUR 1 SACK OVER CONDUITS APPROXIMATELY AT 25-FOOT INTERVALS TO PREVENT CONDUITS FROM FLOATING.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 03/09/2020 | F | | | | | | |
| B | NOTES UPDATE | - | JES | JES | CZH | 05/23/2019 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT,
ENCASED MULTI-CONDUIT INSTALLATION

UG3376.2

TABLE OF CONTENTS

## INSTALLATION (CONT'D):

7. A CONCRETE ENVELOPE USING 1 SACK CONCRETE MIX (PER TABLE 2) IS TO BE POURED AROUND AND OVER THE CONDUITS. TRENCH BACKFILL MATERIAL SHALL MEET THE GOVERNING AUTHORITY'S REQUIREMENTS AND COMPANY STANDARDS.

(8) TWO OR THREE 2-INCH CONDUITS MAY BE INSTALLED IN ONE SPACER POSITION.





**FIGURE 4** (C8)

(D) MAXIMUM TWO 5-INCH CONDUITS USING CONDUIT SPACERS, ELECTRIC TRENCH ONLY:

1. ALL 5-INCH PRIMARY CONDUITS SHALL BE INSTALLED WITH SPACERS AND ENCASED WITH CONCRETE SLURRY (1 SACK MIX).
2. USE DIRECT BURIED (DB) CONDUIT EVEN THOUGH THEY ARE ENCASED IN 1-SACK CONCRETE SLURRY.





**FIGURE 5** (D)

E. NON PRIMARY FEEDER 5-INCH INSTALLATIONS WITHOUT SPACERS, ELECTRIC TRENCH ONLY, MAXIMUM OF TWO 5-INCH CONDUITS, FOR USE ON BRANCH OR LATERAL CIRCUITS ONLY. WHEN SPACER IS NOT REQUIRED:

1. ALL 5 INCH PRIMARY CONDUITS SHALL BE INSTALLED WITH SPACERS AND ENCASED WITH CONCRETE SLURRY (1 SACK MIX).
2. USE DIRECT BURIED (DB) CONDUIT EVEN THOUGH THEY ARE ENCASED IN 1 SACK CONCRETE SLURRY.
3. THE EXAMPLES SHOWN ARE TYPICAL. OTHER CONDUIT COMBINATIONS MAY BE USED PROVIDED THE TOTAL NUMBER DOES NOT EXCEED FOUR AND A REQUIRED 1 1/2-INCH MINIMUM SEPARATION BETWEEN CONDUITS AND OUTER WALL SURFACES ARE MAINTAINED. 1-INCH CONDUITS MAY BE ADDED AS NEEDED.
4. ALWAYS INSTALL 5-INCH CONDUITS ON THE OUTER SIDE OF THE TRENCH.

(5) THE EXAMPLES SHOWN MAY BE USED IN A JOINT TRENCH CONFIGURATION WITH PROPER VERTICAL SPACING.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 03/09/2020 | F | | | | | | |
| B | NOTES UPDATE | - | JES | JES | CZH | 05/23/2019 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):





**FIGURE 6** (E5)

F. CONDUITS FIVE INCHES OR LESS, CONCRETE SLURRY ENCASEMENT 1 SACK MIX OR IMPORTED/NATIVE MATERIAL.

1. ANY CONDUIT COMBINATION SMALLER THAN 5 INCHES MAY BE INSTALLED SIDE BY SIDE ON BOTTOM OF TRENCH. (6-INCH MINIMUM TRENCH WIDTH, 24-INCH MAXIMUM TRENCH WIDTH).
2. THE CONDUIT COMBINATIONS DESCRIBED MAY BE USED IN A JOINT TRENCH CONFIGURATION.
3. USE DIRECT BURIED (DB) CONDUIT WHEN THEY ARE TO BE ENCASED OR IMPORTED/NATIVE BACKFILL IS USED.
4. NARROW TRENCHES, 6 INCHES THROUGH 12 INCHES REQUIRE 1 SACK CONCRETE SLURRY OR MINIMUM 90 PERCENT COMPACTION FOR IMPORTED OR NATIVE MATERIAL.
5. SEE UG3365 AND UG3366 FOR TYPICAL PLACEMENT AND PREFERRED TRENCH MATERIAL. (f)

(6) 12 INCHES MINIMUM SLURRY COVER.

(7) 1 1/2 INCHES MINIMUM SEPARATION REQUIRED BETWEEN CONDUITS AND BETWEEN CONDUIT AND OUTER WALL SURFACES.

8. STACKING CONDUIT IS PROHIBITED WITHOUT SPACERS.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

(b) FOR CONDUIT PLACEMENT AND TRENCH CONFIGURATION, SEE UG3421, UG3425, UG3426, AND UG3427.

(c) FOR SHADING/BACKFILL REQUIREMENTS, AND TRENCH DEPTH, SEE UG3370, UG3371.

(d) FOR FEEDER CONDUIT APPLICATIONS, SEE DM5722.

(e) FOR TRENCHING REQUIREMENTS, SEE UG3370, UG3371, OR UG3376.

(f) SEE UG3365 AND UG3366.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | INSTALLATION UPDATE | EDM | EJA | GLW | CZH | 03/09/2020 | F | | | | | | |
| B | NOTES UPDATE | - | JES | JES | CZH | 05/23/2019 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | FORMATTING | EDM | JIK | - | - | 10/27/2021 |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIRED FOR INSTALLING THE CONDUIT STUB MARKER AND BALL MARKER LOCATING SYSTEM USED TO LOCATE AND SHOW THE DEPTH OF PRIMARY, SECONDARY AND SERVICE CONDUIT STUBS.





**FIGURE 1**





**FIGURE 2**
MARKER BALL








**FIGURE 3**
CONDUIT STUB MARKER





EXAMPLE 1
GAS SERVICE ONLY
(SEE TABLE 1)




EXAMPLE 2
GAS SERVICE AND CONDUIT STUBS TOGETHER
(SEE TABLE 2)





EXAMPLE 3
SINGLE CONDUIT STUB
(SEE TABLE 3)




EXAMPLE 4
JOINT UTILITY STUBS
(SEE TABLE 4)

**FIGURE 4**




**DETAIL 1** **DETAIL 2**

**TABLE 1**

| DESIGN UNITS |
|---|
| STUB-M |

**TABLE 2**

| DESIGN UNITS |
|---|
| STUB/M (UG) |
| STUB-J (GAS) |

**TABLE 3**

| DESIGN UNITS |
|---|
| STUB/M |

**TABLE 4**

| DESIGN UNITS |
|---|
| STUB/M |
| STUB-J |
| ANODE-5 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT STUB MARKER AND BALL MARKER LOCATING SYSTEM

SHEET 1 OF 2

UG3377.1

TABLE OF CONTENTS

## INSTALLATION:

(A) INSTALL CONDUIT STUB MARKERS AND BALL MARKERS ON ALL STUBS (REGARDLESS OF LENGTH), 1-FOOT MAXIMUM INWARD FROM THE END. IF MORE THAN ONE CONDUIT IS STUBBED OUT AT THE SAME LOCATION, INSTALL ONE BALL MARKER ABOVE THE CONDUIT(S) ONLY.

(B) LOOP THE STUB MARKER AROUND THE CONDUIT. IF THE MARKER IS NOT LONG ENOUGH TO SHOW ABOVE GRADE LEVEL, TAPE A SECOND MARKER TO THE FIRST MARKER.

(C) INSTALL THE PULLING TAPE INSIDE THE CONDUIT LEAVING SLACK AT THE PAD OR SUBSTRUCTURE END. AT THE SAME END, THE PULL ROPE MUST BE SECURELY ATTACHED TO EITHER A CONDUIT CAP OR TIE AND TAPE THE PULL ROPE TO THE END OF THE CONDUIT WITH GRAY TAPE.

(D) AT THE CONDUIT STUB END, TIE THE PULLING TAPE TO THE END OF THE CONDUIT AND TAPE THE END OF THE STUB OVER THE PULLING TAPE WITH GRAY TAPE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | MARKER, CONDUIT STUB (RED) | 1 | 3377 | S476302 | STUB/M |
| 2 | BALL MARKER | 1 | -- | S476492 | STUB/M AND STUB-M |
| 3 | MARKER, GAS STUB (YELLOW) | 1 | 3377/3390 | S476306 (X) | STUB-M |
| 4 | ANODE, 5 LB | 1 | -- | S109362 (X) | ANODE-5 |
| 5 | TAPE, GRAY | AS REQ'D | -- | S721120 | -- |
| 6 | PULLING AND MEASURING TAPE | AS REQ'D | -- | S721700 | -- |
| 7 | PLUG, CONDUIT | AS REQ'D | 3373 | -- | -- |
| 8 | CAP, CONDUIT END | AS REQ'D | 3373 | -- | -- |
| 9 | MARKER, GAS STUB ONLY (YELLOW) | AS REQ'D | 3377/3390 | S476306 (X) | STUB-J |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR MINIMUM CONDUIT COVER AND CONDUIT PLACEMENT, SEE UG3370.

b. FOR CONDUIT PLUG OR CONDUIT CAP STOCK NUMBERS, SEE UG3373.

c. FOR GAS STUB MARKER AND BALL MARKER LOCATING SYSTEM, SEE UG3390.

d. FOR POLICY ON MARKING GAS STUBS, SEE GAS STANDARDS D 7243, AND D 7244.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | | | | | | |

**SCOPE:** THIS SECTION EXPLAINS THE PROCESS REQUIRED TO INSTALL ELECTRIC CONDUIT IN NEW AND EXISTING BRIDGES. THIS INCLUDES SLAB, CLOSED CELL, T-SECTIONED, AND CUSTOM BRIDGES.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**DISCUSSION**

I. CONDUIT INSTALLATION DESIGN IN BRIDGES IS PROJECT SPECIFIC WORK. ALMOST EVERY BRIDGE HAS ITS OWN UNIQUE DESIGN AND CONDUIT ATTACHMENT REQUIREMENTS. DEVELOPING A STANDARD THAT COVERS CONDUIT INSTALLATION IN ALL TYPES OF BRIDGES WOULD PRODUCE A DOCUMENT CONTAINING SO MUCH INFORMATION THAT IT WOULD NOT BE PRACTICAL TO USE. THE CIVIL/STRUCTURAL ENGINEERING SECTION HAS EXPERIENCE IN DESIGNING CONDUIT SUPPORTS TO RESIST SEISMIC REQUIREMENTS AND BRIDGE CONSTRAINTS. THE CUSTOMER PROJECT PLANNER SHOULD CONTACT THE CIVIL/STRUCTURAL ENGINEERING SECTION ONCE THEY RECEIVE A BRIDGE JOB. THE CIVIL/STRUCTURAL ENGINEERING SECTION WILL PROVIDE INFORMATION COLLECTION, DESIGN, DRAWINGS, AND FIELD SUPPORT SERVICE AS REQUIRED.

**PROCESS**

II. CONTACT THE CIVIL/STRUCTURAL ENGINEERING SECTION ONCE ELECTRIC CONDUIT IS PROPOSED ON A NEW OR EXISTING BRIDGE.

CONTACT:

CIVIL/STRUCTURAL ENGINEERING MANAGER: (858) 636-6815

CIVIL/STRUCTURAL ENGINEERING OFFICE ASSISTANT: (858) 654-1615

III. A CIVIL/STRUCTURAL ENGINEER WILL BE ASSIGNED TO THE PROJECT. THE ENGINEER DEVELOP THE SCOPE OF WORK, ATTEND MEETINGS AND COMPILE BRIDGE AND SEISMIC INFORMATION. THE ENGINEER WILL ALSO PROVIDE ELECTRIC CONDUIT SUPPORT ANCHORAGE DESIGN AND DRAWINGS, BILL OF MATERIALS INCLUDING STOCK NUMBERS, DPSS ASSEMBLY UNITS (AU) CALL OUTS, AND CONSTRUCTION SUPPORT.

IV. THE CUSTOMER PROJECT PLANNER WILL RETAIN PROJECT AND JOB RESPONSIBILITY, NEGOTIATIONS, AND BE THE MAIN CONTACT WITH THE CUSTOMER. THE CUSTOMER PROJECT PLANNER WILL WORK CLOSELY WITH THE CIVIL/STRUCTURAL ENGINEER IN DESIGN COORDINATION, ATTENDING MEETINGS, AND FINALIZING THE JOB DESIGN. FINAL JOB COSTS, DPSS AU DATA ENTRY, AND COMPLETE FINAL JOB PACKAGE WILL ALSO BE PERFORMED BY THE CUSTOMER PROJECT PLANNER.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 11/29/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD DESCRIBES THE PROCEDURE FOR MANDRELING CONDUITS AND THE INSTALLATION OF PULLING AND MEASURING TAPE.





**FIGURE 1**

## INSTALLATION:

A. ALL MANDRELING MUST BE DONE IN THE PRESENCE OF QUALIFIED SDG&E PERSONNEL.

B. AFTER CONDUITS ARE INSTALLED, THEY MUST BE MANDRELED BY THE CONDUIT INSTALLER TO CHECK THE INSIDE DIAMETER AND PROVIDE A PATH FREE OF OBSTRUCTIONS.

C. IN EACH CONDUIT RUN, USE A MANDREL EQUIVALENT TO THE SIZE CONDUIT BEING MANDRELED. THE MANDREL MUST BE SIZED TO THE SMALLEST INSIDE CONDUIT DIAMETER FOR THE TOTAL LENGTH OF THE RUN.

D. IF IT IS DETERMINED THAT ONE OR MORE OF THE CONDUITS ARE PARTIALLY OR TOTALLY COLLAPSED, OR CONTAIN BURRS OR OTHER OBSTRUCTIONS, AND THE MANDREL WILL NOT PASS THROUGH AN OBSTRUCTION, THE CONDUIT MUST BE SWABBED, REPLACED OR REPAIRED AT THAT POINT BY THE INSTALLER.

E. THE PULLING TAPE SHALL BE PULLED IN BEHIND THE MANDREL. WHEN THE PULLING AND MEASURING TAPE IS INSTALLED IT SHALL BE ONE CONTINUOUS LENGTH, NEW AND FREE OF WEAR, WITHOUT KNOTS FOR THE ACCURATE MEASUREMENT FOR CONDUCTOR INSTALLATION AND THE PULLING OF CONDUCTORS OR WINCH LINES.

F. THE CONDUIT INSTALLER MUST PROVIDE 3/4-INCH PULLING AND MEASURING TAPE (S721700) IN EACH CONDUIT. THE PULLING TAPE MUST BE APPROVED BY SDG&E AND HAVE A MINIMUM AVERAGE TENSILE STRENGTH OF 2,500 LBS. PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF CONDUIT.

## BILL OF MATERIALS: NONE

## NOTES:

I. **MATERIAL DATA**

a. CABLE PULLING AND MEASURING TAPE: SDG&E APPROVED TENSILE STRENGTH 2,500 LBS, WOVEN POLYESTER HIGH STRENGTH, CONTINUOUS FILAMENT, PRE LUBRICATED 3/4-INCH WITH FOOTAGE MARKING.

## REFERENCE:

a. AVAILABLE IN SERVICE STANDARD AND GUIDE MANUAL.

b. SEE SDG&E ELECTRIC STANDARD, PRACTICE MANUAL NUMBER 217, FOR INSTALLATION OF PULLING AND MEASURING TAPE AND MANDRELING.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | NOTES UPDATE | EDM | EJA | GLW | CZH | 07/29/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT MANDRELING

SHEET 1 OF 1

UG3379.1

**SCOPE:** THIS STANDARD SHOWS THE ACCESSORIES AND PROCEDURES THAT ENABLE 1-INCH CONDUIT TO BE INSTALLED INTO 5-INCH SUBSTRUCTURE DUCT TERMINATORS.





**FIGURE 1**
STYLE A





**FIGURE 2**
STYLE B





**FIGURE 3**

## INSTALLATION:

(A) USE SOLVENT CEMENT TO CEMENT THE ADAPTOR INTO THE PREFERRED TERMINATOR KNOCKOUT.

(B) MAKE SURE THE CONDUIT ENTERS THE ADAPTOR STRAIGHT. THIS REQUIRES A MOUND OF DIRT APPROXIMATELY ONE OR TWO FEET OUTSIDE THE SUBSTRUCTURE (SEE FIGURE 3). LEAVE 24 INCHES OF THE CONDUIT EXPOSED BEYOND THE SUBSTRUCTURE TERMINATOR INSIDE THE SUBSTRUCTURE. THIS WILL ALLOW MOVEMENT OF THE CONDUIT UNTIL THE TRENCH IS BACKFILLED.

(C) AFTER THE TRENCH IS BACKFILLED, THE CONNECTION CREW SHALL INSTALL EITHER THE HEAT SHRINK SLEEVE OR TAPE WHERE THE CONDUIT AND ADAPTOR JOIN. NEXT MAKE THE FINAL CUT ON THE CONDUIT JUST BEYOND THE HEAT SHRINK SLEEVE OR TAPE AND DISREGARD THE EXCESS CONDUIT.

(D) ON SINGLE ENTRANCE ADAPTORS (STYLE A ON FIGURE 1), APPLY ONE LAYER OF AQUA-SEAL AND TWO LAYERS OF GRAY TAPE AT THE POINT WHERE THE CONDUIT ENTERS THE ADAPTOR INSIDE THE SUBSTRUCTURE.

(E) ONE ENTRANCE OF THE TRIPLE ENTRANCE ADAPTOR IS CAPPED SO IT MAY BE USED AS A TWO-WAY ADAPTOR. THE CAP MAY BE CUT OFF IF THE THIRD CONDUIT ENTRANCE IS NEEDED.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 07/25/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT SUBSTRUCTURE ADAPTORS

UG3382.1



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(F) HEAT SHRINK SLEEVES ARE REQUIRED ON DOUBLE AND TRIPLE ENTRANCE ADAPTORS (STYLE B ON FIGURE 2), INSTEAD OF THE HAND TAPED APPLICATION. BOTH METHODS DESCRIBED WILL PREVENT WATER AND OTHER DEBRIS FROM ENTERING THE SUBSTRUCTURE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | | | | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|
| | WIRE TYPE | WIRE SIZE | U-NUMBER | ADAPTER STYLE | RUNS ALLOWED | | | | |
| 1 | 2-#8 IN 1" CONDUIT | | U-10.011 | A | 1 | AS REQ'D | -- | S102052 | ADPT-1 |
| | | | | B | 2 OR 3 | | -- | S102054 | ADPT-2 |
| 2 | SEALING COMPOUND | | | | | | -- | S442976 | -- |
| 3 | TAPE, GRAY | | | | | | -- | S721120 | -- |
| 4 | SLEEVE, HEAT SHRINK, 1.5 ID X 9" EXPANDED | | | | | | -- | S778016 | -- |
| 5 | CEMENT, SOLVENT | | | | | | -- | S213232 | -- |

**NOTES:** NONE

## REFERENCE:

a. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 07/25/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONDUIT SUBSTRUCTURE ADAPTORS

UG3382.2

**SCOPE:** THIS STANDARD SETS FORTH THE PROCEDURE FOR INSTALLING A GAS SERVICE STUB LOCATING MARKER.






**FIGURE 1**
INSTALLATION




**DETAIL 1**

## INSTALLATION:

(A) ATTACH A YELLOW PLASTIC GAS MARKER TO THE END OF THE GAS SERVICE AND EXTEND ABOVE GRADE.

(B) BRING THE YELLOW TRACER WIRE UP FROM THE POLY GAS SERVICE STUB AND TAPE IT TO THE YELLOW MARKER AT GRADE LEVEL. CUT THE TRACER WIRE 2 FEET ABOVE GRADE AND COIL AROUND THE MARKER AT GRADE LEVEL. SEAL TIP OF THE TRACER WIRE WITH AQUA-SEAL AND ELECTRICAL TAPE TO PREVENT GROUNDING.

C. AN APPROVED BALL MARKER WILL BE INSTALLED AT EACH STUB.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | MARKER, GAS STUB (YELLOW) | 1 | 3377/3390 | S476306 (X) | -- |
| 2 | WIRE, TRACER, (#14 AWG 600V YELLOW) | AS REQ'D | -- | S809200 | -- |
| 3 | SEALING COMPOUND | AS REQ'D | -- | S442976 | -- |
| 4 | BALL MARKER | 1 | -- | S476492 | -- |

## NOTES:

I. THE INSTALLER SHALL FURNISH AND INSTALL ALL THE MATERIAL SHOWN IN THIS STANDARD.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE GAS STANDARDS 7241, 7244, 7344, & 7243 [FOR INTERNAL USE ONLY].

b. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3377 | EDM | JIK | - | - | 10/27/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 05/24/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GAS STUB MARKER



UG3390.1

TABLE OF CONTENTS

| PAGE | SUBJECT |
|---|---|
| 3405 | EQUIPMENT, PAD AND SUBSTRUCTURE CROSS REFERENCE |
| 3408 | PAD MOUNTED EQUIPMENT WIRE ENTRY PREVENTION |
| 3409 | RTU PAD FOR SWITCH WITH REMOTE RTU |
| 3410 | 600A - 200A TERMINATOR PAD |
| 3414 | CAPACITOR PAD |
| 3415 | SERVICE RESTORER PAD |
| 3416 | 12KV THREE-PHASE 200A TERMINATING CABINET PAD |
| 3417 | 600A TERMINATING CABINET PAD |
| 3418 | BOX PAD FOR PME-3 AND PME-5 SWITCHES |
| 3419 | BOX PAD FOR 3-WAY PAD MOUNTED SWITCH |
| 3421 | SINGLE-PHASE TRANSFORMER/UTILITY EQUIPMENT PAD |
| 3423 | BOX PAD W/ TEMPORARY COVER FOR PME 9, 10 & 11 AND 2 SIDED TRAYER SWITCHES |
| 3425 | THREE-PHASE DEADFRONT TRANSFORMER PAD INSTALLATION |
| 3426 | THREE-PHASE DEADFRONT TRANSFORMER PAD INSTALLATION |
| 3427 | THREE-PHASE DEADFRONT/LIVEFRONT TRANSFORMER PAD INSTALLATION |
| 3428 | BOX PAD FOR 4-WAY TRAYER PAD MOUNTED SWITCH |
| 3429 | BOX PAD FOR 5-WAY TRAYER PAD MOUNTED SWITCH |
| 3443 | SWITCH PADS: 3443A, 3443B, AND 3443C |
| 3478 | TRANSFORMER SOUND ENCLOSURE |
| 3479 | EQUIPMENT BARRIER PROTECTION AND CLEARANCE |
| 3480 | CLEARANCE REQUIREMENTS FOR PAD MOUNTED AND SUBSURFACE EQUIPMENT FROM ABOVE GROUND OBJECTS |
| 3481 | MINIMUM OPERATING CLEARANCE REQUIREMENTS FOR PAD MOUNTED EQUIPMENT |
| 3482 | MINIMUM OPERATING CLEARANCE REQUIREMENTS FOR SUBSURFACE EQUIPMENT |
| 3483 | MINIMUM OPERATING CLEARANCE REQUIREMENTS FOR PAD MOUNTED AND SUBSURFACE EQUIPMENT |


MAIN TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | E | | | | | | |
| A | UPDATES TO 3421 | - | KR | JS | MDJ | 07/25/2017 | D | ADDED UG3443 | EDM | ADW | GLW | CZH | 07/29/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PADS, RETAINING WALLS, CLEARANCES
TABEL OF CONTENTS

UG3401.1

| PAGE | SUBJECT |
|---|---|
| 3484 | PAD INSTALLATION FOR PAD MOUNTED EQUIPMENT, SLOPING GRADE INSTALLS, FIBERGLASS RETAINING WALLS |
| 3485 | SUBSTRUCTURE INSTALLATION ON SLOPING GRADES |
| 3486 | RETAINING WALL REQUIREMENTS AND CLEARANCES |
| 3487 | RETAINING WALL REQUIREMENTS AND SINGLE PHASE TRANSFORMER PAD LOCATIONS SHOWING CATV AND/OR TELCO LOCATIONS |
| 3488 | CLEARANCES BETWEEN SDG&E FACILITIES AND OTHER ABOVE GROUND OBJECTS |
| 3489 | MASONRY RETAINING WALLS - TYPES 1, 2, 3, 4, 5, 6 - LEVEL AND SLOPING BACKFILL |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | E | | | | | | |
| A | UPDATES TO 3421 | - | KR | JS | MDJ | 07/25/2017 | D | ADDED UG3443 | EDM | ADW | GLW | CZH | 07/29/2021 |

**SCOPE:** THIS STANDARD SHOWS A CHART CROSS REFERENCING PAD MOUNTED EQUIPMENT WITH THE PAD AND SUBSTRUCTURES USED FOR INSTALLATION. READ FROM LEFT TO RIGHT.

## TABLE 1

| EQUIPMENT PAD AND SUBSTRUCTURE CROSS REFERENCE | | | | | |
|---|---|---|---|---|---|
| **EQUIPMENT** | | **PAD** | | **HANDHOLE** | |
| **TYPE** | **STANDARD PAGE** | **TYPE** | **STANDARD PAGE** | **TYPE/ STANDARD** | **INSIDE DIMENSIONS (IN)** |
| SINGLE-PHASE FUSE PAD | 3512 | TRANSFORMER/UTILITY EQUIPMENT PAD | 3421 | 3312 | 17 X 30 |
| THREE-PHASE SWITCHING CAB FUSED | -- | | | | |
| THREE-PHASE SWITCHING CAB FUSED (FEED THRU) | 3514 | | | | |
| SINGLE-PHASE TEMINATOR | 3522 | | | | |
| THREE-PHASE LOW PROFILE CABLE TERMINATING CABINET | 3523 | THREE-PHASE LOW PROFILE TERMINATOR PAD | 3416 | 3311 | 14 X 66 X 14 |
| 60A TERMINATING CABINET (DEADFRONT) | 3582 | 600A TERMINATING CABINET PAD | 3417 | 3313 | BASE SECTION |
| PAD MOUNTED PME 3 SWITCH | 3583 | PME 3 BOX PAD | 3418 | -- | -- |
| 3-WAY PAD MOUNTED SWITCH | 3586 | BOX PAD | 3419 | -- | -- |
| PAD MOUNTED PME 9, 10 & 11 SWITCHES | 3567 | PME 9, 10 & 11 BOX PAD | 3423 | -- | -- |
| PAD MOUNTED SERVICE RESTORER OR 2-WAY SWITCH | 3575 | SERVICE RESTORER PAD | 3415 | 3313 | (1) 18" BASE SECTION |
| -- | 3711 3712 3713 | TRANSFORMER/UTILITY EQUIPMENT PAD | 3421 | -- | -- |
| -- | -- | THREE-PHASE TRANSFORMER PAD (THRU 300 KVA DEADFRONT) | 3425 | -- | -- |
| 1200 KVAR PAD MOUNT CAPACITOR | -- | CAPACITOR PAD | 3414,3415 | -- | -- |
| 600A TO 200A TERMINATOR | 3410 | TERMINATOR PAD | 3410 | 3314 | 36 X 72 |
| -- | 3751 | THREE-PHASE TRANSFORMER PAD (500-1000 KVA DEADFRONT) | 3426 | 3314 | 12" TOP SECTION (IF REQ'D) & (2) 3314 12" INTERMEDIATE EXTENSION SECTIONS (IF REQ'D) |
| | | THREE-PHASE TRANSFORMER PAD (225-2500 KVA DEADFRONT) (A) | 3427 | | |
| -- | 3755 | THREE-PHASE TRANSFORMER PAD (3750 HHR KVA DEADFRONT) | 3425 | -- | -- |

## INSTALLATION:

(A) FOR USE WHEN CONDUIT REQUIREMENTS ARE GREATER THAN THE MAXIMUM SHOWN IN UG3426.

**BILL OF MATERIALS:** NONE

## NOTES:

I. UNOBSTRUCTED READY ACCESS FOR THE UTILITIES VEHICLES AND EQUIPMENT MUST BE MAINTAINED TO INSTALL, REMOVE, OR MAINTAIN THESE FACILITIES.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGE | - | GLW | JES | CZH | 11/21/2019 | F | | | | | | |
| B | REVISION | - | RSW | VCR | - | 08/31/2000 | E | TABLE UPDATE | EDM | EJA | GLW | KRG | 09/29/2022 |
| A | REVISION | - | RSW | VCR | - | 01/01/2000 | D | FORMATTING | EDM | JIK | - | - | 11/05/2020 |

**SCOPE:** THIS STANDARD SHOWS SEALANT USED TO FILL GAPS BETWEEN CONCRETE PADS AND PAD MOUNTED EQUIPMENT TO PREVENT A PERSON FROM PASSING A WIRE OR OTHER CONDUCTING MATERIAL FROM THE THE OUTSIDE INTO A COMPARTMENT WITH EXPOSED LIVE PARTS AFTER THE EQUIPMENT IS CLOSED AND LOCKED.





**FIGURE 1**

## INSTALLATION:

A. ON ALL PAD MOUNTED TRANSFORMERS, APPLY SEALANT AROUND THE FRONT OR SILL OF THE TRANSFORMER NEXT TO CONCRETE PAD AND THE "PAD UNISTRUT" INSIDE AND OUT. THIS WILL PREVENT ANY POSSIBLE WIRE ENTRY. ON ALL OTHER PAD MOUNTED EQUIPMENT CHECK INSTALLATION USING A #18 AWG WIRE OR EQUIVALENT FOR GAPS BETWEEN EQUIPMENT BASE AND TOP OF PAD, INCLUDING EXPOSED UNISTRUT ENTRANCES. APPLY SEALANT WHERE NECESSARY TO PREVENT WIRE ENTRY. (B)

(B) USE EXTREME CAUTION WHEN CHECKING ENERGIZED EQUIPMENT AND USE INSULATING BARRIERS AS NECESSARY.

C. BEFORE APPLYING SEALANT, CAREFULLY FOLLOW INSTRUCTIONS ON THE CARTRIDGE. CLEAN SURFACE WITH SOLVENT AND APPLY SEALANT WITH A CAULKING GUN. DO NOT SEAL MANHOLE OR HANDHOLE COVERS.

D. MAINTENANCE:

REPLACE ANY SEALANT THAT MAY BE LOOSE OR BROKEN. IF NEW SEALANT WILL NOT ADHERE TO EXISTING SEALANT, REMOVE IT AND FOLLOW INSTALLATION STEP C.

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) SEALANT STOCK NUMBER S631800.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/MJC | 9/20/2013 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD-MOUNTED EQUIPMENT WIRE ENTRY PREVENTION

SHEET 1 OF 1

UG3408.1

**SCOPE:** THIS STANDARD SHOWS RTU PAD FOR S&C REMOTE. REMOTE TERMINAL UNITS.






**FIGURE 1**
ISOMETRIC VIEW




SIDEWALK

**FIGURE 1**
PLAN VIEW

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | JS | CZH | 2/18/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

RTU PAD FOR VISTA SWITCH WITH REMOTE RTU



UG3409.1

TABLE OF CONTENTS

## INSTALLATION:

A. SET PAD LEVEL TO FINAL AND INSTALL EQUIPMENT GROUND.

B. PLACE ONE OR TWO 5-INCH CONDUIT, ONE 2-INCH CONDUIT, ONE 1-INCH CONDUIT AND EQUIPMENT GROUND WITHIN PAD OPENING.

C. TERMINATE ALL CONDUITS FLUSH WITH THE TOP OF THE PAD. DO NOT CUT INTO THE CURVED PORTION OF THE ELBOWS. RADIUS OF CURVATURE IS 36-INCH MINIMUM OF 3-INCH, 5-INCH CONDUITS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | APPROVED MFG | MFG PART NUMBER | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| 1 | PAD - REMOTE TERMINAL UNIT | 108 (49KGS) | QUAZITE | PL4846WA | 1 | 3409.1 | S513428 | RTUPAD |
| 2 | EQUIPMENT GROUND | -- | -- | -- | 1 | 4510 | -- | TG-T-W |
| 3 | 5-INCH CONDUIT | -- | -- | -- | AS REQ'D | 3373.1 | S249728 | -- |
| 4 | 2-INCH CONDUIT | -- | -- | -- | 1 | | S249632 | 1DB2-S |
| 5 | 1-INCH PE | -- | -- | -- | 1 | | S249630 | 1"PE |

## NOTES:

I. THIS PAD IS NOT TO BE POURED IN PLACE.

## REFERENCE:

a. SEE UG3211.3 FOR PAD IDENTIFICATION.

b. SEE UG3370 OR UG3371 FOR TRENCH, UTILITY POSITIONING, SHADING AND BACKFILL REQUIREMENTS.

c. SEE UG3479 FOR TRANSFORMER BARRIER PROTECTION.

d. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

e. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

f. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

g. SEE UG3489 FOR RETAINING WALLS.

h. SEE UG4512 FOR EQUIPMENT GROUNDING.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | JS | CZH | 2/18/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

RTU PAD FOR VISTA SWITCH WITH REMOTE RTU

UG3409.2

**SCOPE:** THIS STANDARD SHOWS THE PAD USED WITH THE 600A TO 200A DEADFRONT TERMINATOR INSTALLED ON TOP OF AN EXISTING 3314 HANDHOLE.





**FIGURE 1**

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JS | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

600A TO 200A TERMINATOR PAD

UG3410.1

TABLE OF CONTENTS

## INSTALLATION:

A. THIS PAD IS NOT TO BE INSTALLED ON NEW CONSTRUCTION. PAD IS TO BE INSTALLED ON THE TOP OF AN EXISTING 3314 HANDHOLE. MAY ALSO BE INSTALLED ON A "B" BOX PROVIDING THE TOP SECTION HAS BEEN MODIFIED OR REPLACED WITH 3314 INTERMEDIATE SECTIONS.

B. WHEN THE EXISTING HANDHOLE TOP SECTION HAS BEEN SET TO A SLOPING GRADE, THE TOP SECTION OF HANDHOLE MUST RE-GRADED AND SET LEVEL.

C. INSTALL A THIN LAYER OF SEALANT MASTIC BETWEEN HANDHOLE TOP SECTION AND PAD.

D. APPLY LUBRICANT SUCH AS EZ-1 TO THE PENTAHEAD BOLTS WHEN SECURING THE COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. TIGHTEN DOWN BOLTS WITH A TORQUE WRENCH TO 30 FT./IBS MIN., 40FT/IBS. MAX.

(E) PAD SHOULD NOT BE INSTALLED ON EXISTING HANDHOLES LOCATED IN SIDEWALKS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 1 | TERMINATOR PAD | 1,480 MAX. | 1 | -- | S514260 | 3410 | 3410PAD |
| 2 | SEALANT, PLASTIC-MASTIC (NOT SHOWN) | -- | AS REQ'D | -- | S631872 | -- | -- |
| 3 | EXISTING 3314 HANDHOLE | -- | 1 | 3314 | -- | -- | -- |

**NOTES:** NONE

## REFERENCE:

a. SEE UG3479 FOR BARRIER PROTECTION AND CLEARANCE.

b. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

c. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

e. SEE UG3489 FOR RETAINING WALLS.

f. SEE UG3524 FOR 600A TO 200A TERMINATOR.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JS | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE PAD MOUNTED SCADA CAPACITOR PAD AND CONDUIT PLACEMENT USED WITH THE 1200 KVAR PAD MOUNTED SCADA CAPACITOR.





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 1**
TOP VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | CZH | 07/29/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/05/2020 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 06/05/2015 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |
| SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS | | | | |
| SHEET 1 OF 4 | CAPACITOR PAD | | | UG3414.1 |

TABLE OF CONTENTS

## INSTALLATION:

(A) THIS PAD MAY NOT BE POURED IN PLACE. USE PRECAST PADS ONLY.

B. 4" CONDUITS SHOULD CONNECT TO THE ORIGINATION POINT OF THE PRIMARY (HANDHOLE/MANHOLE).

(C) TERMINATE ALL CONDUIT FLUSH WITH TOP OF PAD.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CAPACITOR PAD (A) | 1,850 MAX. | 1 | -- | S514280 | CAP-PD |

**NOTES:** NONE

## REFERENCE:

a. SEE UG3211 FOR PAD IDENTIFICATION.

b. SEE UG3479 FOR BARRIER PROTECTION AND CLEARANCE.

c. SEE UG3480, UG3481, UG3482 AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

d. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

e. SEE UG3486 AND UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

f. SEE UG3489 FOR RETAINING WALLS.

g. SEE UG3821 FOR INSTALLATION REQUIREMENTS FOR PAD MOUNTED CAPACITOR.

h. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | CZH | 07/29/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/05/2020 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 06/05/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD IDENTIFIES A 3414 GENERAL USE PAD.






**FIGURE 1**
ISOMETRIC VIEW




**DETAIL 1**
SECTION A-A





**FIGURE 1**
PLAN VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | CZH | 07/29/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/05/2020 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 06/05/2015 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3414 GENERAL USE PAD
49" X 85"

UG3414.3

**TABLE 1**

| ITEM | DESCRIPTION | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|
| 1 | GENERAL USE PAD, 49" X 85" X 6" | S162520 | B-BOX1 |

**INSTALLATION:**

A. SET PAD LEVEL TO FINISH GRADE AND INSTALL EQUIPMENT GROUND.

**BILL OF MATERIALS:** NONE

**NOTES:**

I. EQUIPMENT IS NOT TO EXCEED OUTSIDE DIMENSIONS OF PAD.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | ADW | GLW | CZH | 07/29/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 11/05/2020 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 06/05/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE PAD MOUNTED SERVICE RESTORER PAD AND CONDUIT PLACEMENT USED WITH THE PAD MOUNTED SERVICE RESTORER.

**ATTENTION:**

* PAD MAY NOT BE POURED IN PLACE. USE PRECAST PADS ONLY.





**FIGURE 1**
PAD FOR EATON-COOPER SERVICE RESTORER
ISOMETRIC VIEW





**FIGURE 1**
PAD FOR EATON-COOPER SERVICE RESTORER
PROFILE VIEW





**FIGURE 1**
PAD FOR EATON-COOPER SERVICE RESTORER (I)
PREFERRED INSTALLATION
PLAN VIEW





**FIGURE 1**
3313 HANDHOLE 18" BASE SECTION
ISOMETRIC VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | F | | | | | | |
| B | TITLE BLOCK UPDATE | - | BR | BR | - | 2/24/2017 | E | FORMATTING | EDM | JIK | - | - | 11/5/2020 |
| A | REVISION | - | - | - | - | 1/1/1996 | D | DRAWING UPDATES | - | GW | JS | CZH | 6/13/2019 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

SERVICE RESTORER PAD

UG3415.1





**FIGURE 2**
PAD FOR ISG AND FUTURE SERVICE RESTORERS
PLAN VIEW





**FIGURE 2**
PAD FOR ISG AND FUTURE SERVICE RESTORERS
PROFILE VIEW





**FIGURE 3**
ALTERNATE INSTALLATION (D)(i)
PLAN VIEW

**ATTENTION:**

* DEVIATION REQUEST IS REQUIRED FOR PAD ALTERNATE INSTALLATION. (i)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | F | | | | | | |
| B | TITLE BLOCK UPDATE | - | BR | BR | - | 2/24/2017 | E | FORMATTING | EDM | JIK | - | - | 11/5/2020 |
| A | REVISION | - | - | - | - | 1/1/1996 | D | DRAWING UPDATES | - | GW | JS | CZH | 6/13/2019 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 2 OF 3

SERVICE RESTORER PAD

UG3415.2

TABLE OF CONTENTS

## INSTALLATION:

A. SET PAD LEVEL TO FINAL GRADE AND INSTALL EQUIPMENT GROUND.

B. TERMINATE CONDUITS 3 INCHES ABOVE THE BOTTOM OF THE 3313 HANDHOLE.

C. INSTALL SECONDARY CONDUIT WHEN SOURCE IS WITHIN PLUS OR MINUS 50 FEET, OTHERWISE INSTALL "N" TRANSFORMER.

(D) PLACE PAD IN THIS POSITION TO ALLOW DOOR, HOUSING CONTROL TO OPEN TOWARD THE SIDEWALK.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO |
|---|---|---|---|---|---|---|---|
| 1 | PAD, LEGACY RECLOSER, FOR EATON-COOPER RECLOSER | 1,825 MAX. | 1 | -- | S514282 | -- | 3415-B |
| 2 | BASE SECTION, 3313 HANDHOLE, 18" | 885 MAX. | 1 | 3313 | S162664 | 3313-B | |
| 3 | PAD, RESTORER, ISG/SERVICE | -- | 1 | -- | S514262 | 3415-I | -- |

## NOTES:

(I) 64" WILL NORMALLY REQUIRE A RIGHT-OF-WAY. USE ALTERNATE INSTALLATION WHEN RIGHT-OF-WAY CANNOT BE OBTAINED.

## REFERENCE:

a. SEE UG3479 FOR BARRIER PROTECTION AND CLEARANCE.

b. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

c. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

e. SEE UG3489 FOR RETAINING WALLS.

f. SEE UG3575 FOR PAD MOUNTED SERVICE RESTORER.

g. SEE UG3576 FOR INSTALLATION REQUIREMENTS FOR PAD MOUNTED SERVICE RESTORER.

h. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

(i) SEE UG3005 FOR DEVIATION REQUEST FORM AND PROCEDURE.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | F | | | | | | |
| B | TITLE BLOCK UPDATE | - | BR | BR | - | 2/24/2017 | E | FORMATTING | EDM | JIK | - | - | 11/5/2020 |
| A | REVISION | - | - | - | - | 1/1/1996 | D | DRAWING UPDATES | - | GW | JS | CZH | 6/13/2019 |

**SCOPE:** THIS STANDARD SHOWS THE PAD AND HANDHOLE USED WITH THE PAD MOUNTED 200A LOW PROFILE CABLE TERMINATING CABINET. CONDUIT PLACEMENT IS ALSO SHOWN.





**FIGURE 1**





**FIGURE 2**
PLAN VIEW

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3416 PAD & HANDHOLE INSTALLATIONS FOR PAD MOUNTED
12KV THREE-PHASE 200A TERMINATING CABINET



UG3416.1

TABLE OF CONTENTS





**FIGURE 3**
INSTALLATION LOCATION DETAIL

## INSTALLATION:

### 3416 PAD OVER 3311 HANDHOLE

A. INSTALL CONDUITS AS SHOWN.

(B) THE PAD AND HANDHOLE LOCATION IS TO BE MARKED OUT PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING PAD AND HANDHOLES REQUIRES APPROVAL FROM SERVICE PLANNING. ONCE THE LOCATION HAS BEEN ESTABLISHED, MARK OUT DIMENSIONS FOR AN EXCAVATION OF 2'-5" WIDE X 6'-9" LONG. THE DEPTH OF THE EXCAVATION IS 17 INCHES ALLOWING THE BOTTOM OF THE PAD TO SET 3" BELOW GRADE.

(C) PLACE ALL PRIMARY AND SECONDARY CONDUITS WITHIN THE HANDHOLE. TERMINATE PRIMARY AND SECONDARY CONDUITS 3 INCHES ABOVE THE BOTTOM OF HANDHOLE. DO NOT CUT INTO THE CURVED PORTION OF THE ELBOWS.

(D) **TABLE 1**

| SECONDARY CONDUIT COMBINATIONS (E) | | | |
|---|---|---|---|
| 2-INCH | 3-INCH | 4-INCH | TOTAL CONDUITS |
| -- | 5 | -- | 5 |
| 4 | 3 | -- | 7 |
| 5 | 2 | -- | 7 |
| 6 | 1 | -- | 7 |
| 7 | -- | -- | 7 |
| 1 | -- | 4 | 5 |
| -- | 1 | 4 | 5 |
| 1 | 1 | 3 | 5 |
| -- | 3 | 2 | 5 |
| -- | 4 | 1 | 5 |
| 4 | -- | 3 | 7 |
| 5 | -- | 2 | 7 |
| 6 | -- | 1 | 7 |

**TABLE 2**

| PRIMARY CONDUIT COMBINATIONS | | | |
|---|---|---|---|
| 2-INCH | 3-INCH | 4-INCH | TOTAL CONDUITS |
| -- | -- | 4 | 4 |
| 3 | -- | 3 | 6 |
| -- | 3 | 1 | 4 |

(E) MAY INCLUDE TWO ADDITIONAL ONE INCH CONDUITS FOR STREET LIGHTS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 1 | PAD SECTION, 3416 | 1,200 | 1 | 3416.1 | S514020 | 3416 | 3416PAD |
| 2 | HANDHOLE, 3311, 14" X 66" X 14" | -- | 1 | 3311 | S162660 | | |

## NOTES:

I. PAD SECTION MAY NOT BE POURED IN PLACE.

## REFERENCE:

a. SEE UG3211.3 FOR INSTALLATION OF IDENTIFICATION TAG.
b. SEE UG3479 FOR EQUIPMENT BARRIER PROTECTION.
c. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).
d. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.
e. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.
f. SEE UG3489 FOR RETAINING WALLS.
g. SEE UG3523 FOR PAD MOUNTED CABLE TERMINATING CABINET.
h. SEE UG4510 FOR PREFERRED AND ALTERNATE TRENCH GROUND WIRE.
i. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.
j. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE PAD AND HANDHOLE USED WITH THE PAD MOUNTED 600A TERMINATING CABINET. CONDUIT PLACEMENT IS ALSO SHOWN.





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 2**
3313 HANDHOLE, 18" BASE SECTION

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KN | KN | CZH | 1/10/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



600A TERMINATING CABINET PAD

UG3417.1





**FIGURE 3**
SIDE VIEW





**FIGURE 3**
PLAN VIEW

## INSTALLATION:

A. SET PAD LEVEL TO FINAL GRADE AND INSTALL EQUIPMENT GROUND.

(B) TERMINATE CONDUITS 3 INCHES ABOVE THE BOTTOM OF THE 3313 HANDHOLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 1 | PAD, 600A TERMINATING CABINET | 619 MAX. | 1 | -- | S514022 | 3417 | 3417PAD |
| 2 | HANDHOLE, 3313 BASE SECTION | 885 MAX. | 1 | 3313 | S162664 | | |

## NOTES:

I. PAD MAY NOT BE POURED IN PLACE. USE PRECAST PADS ONLY.

II. MAY INCLUDE TWO ADDITIONAL ONE INCH CONDUITS FOR STREET LIGHTS.

## REFERENCE:

a. SEE UG3479 FOR BARRIER PROTECTION AND CLEARANCE.

b. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

c. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

e. SEE UG3489 FOR RETAINING WALLS.

f. SEE UG3582 FOR INSTALLATION REQUIREMENTS FOR PAD MOUNTED 600A TERMINATING CABINET.

g. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KN | KN | CZH | 1/10/2014 | D | | | | | | |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE BOX PAD AND CONDUIT PLACEMENT FOR THE PME-3 AND PME-5 PAD MOUNTED AIR BREAK SWITCHES.





**FIGURE 1** (II)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR PME-3 AND PME-5 SWITCHES

UG3418.1





**FIGURE 2**
BOX & CONDUIT PLACEMENT
PLAN VIEW





**FIGURE 2**
BOX & CONDUIT PLACEMENT
SIDE VIEW

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR PME-3 AND PME-5 SWITCHES

UG3418.2

TABLE OF CONTENTS





**FIGURE 3**
EXCAVATION DIMENSIONS

## INSTALLATION:

### CONDUIT:

(A) INSTALL CONDUITS AND TERMINATE THEM NOT LESS THAN 3 INCHES (76mm) ABOVE THE GRAVEL BASE.

(B) DO NOT CUT THE 90 DEGREE ELBOWS ON CURVE.

(C) STUB ONE 3-INCH (76mm) CONDUIT FROM CMPT #2, 4 FEET (1,219mm) FROM THE BOTTOM FLANGE OF BOX PAD.

D. NO MORE THAN 2 CONDUITS MAY BE INSTALLED IN COMPARTMENTS 1 & 2. ONE ADDITIONAL 3-INCH (76mm) CONDUIT IS ALLOWED IN CMPT 2 FOR SCADA ANTENNA.

(E) WHEN TWO CONDUITS ARE INSTALLED IN ONE COMPARTMENT, PLACE CONDUITS SIDE BY SIDE CENTERED ON THE APPROPRIATE DIMENSION.

(F) COMPLETELY SLURRY ENCASE ALL 5-INCH 90-DEGREE BENDS TO WITHIN 7 INCHES OF THE FINISH CUT OF THE CONDUIT.

### BOX PAD:

G. THE BOX PAD LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE BOX REQUIRES APPROVAL FROM PROJECT MANAGEMENT. WHEN INSTALLING ADJACENT TO NEW OR EXISTING HANDHOLES ALLOW 17 FEET MINIMUM FROM THE CLOSEST EDGE OF HANDHOLE TO THE CENTERLINE OF THE BOX PAD.

H. MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH AND LENGTH PER DRAWING BELOW. THE WIDTH, AND LENGTH DIMENSIONS GIVEN, ALLOW AN EXTRA 12 INCHES (305mm) FOR SETTING BOX PAD.

J. ADD 4 INCHES (102mm) OF GRAVEL TO BOTTOM OF EXCAVATION AND THEN COMPACT THIS MATERIAL BY HAND OR MACHINE.

K. PLACE THE BOX PAD IN THE EXCAVATION WITH THE LONG SIDE OF THE BOX PAD PARALLEL TO AND 15 INCHES (381mm) FROM THE BACK EDGE OF THE SIDEWALK.

L. LEVEL BOX PAD.

M. SET THE TOP SURFACE OF THE BOX PAD 4 INCHES (102mm) ABOVE FINAL GRADE.

(N) BACKFILL THE OUTSIDE WITH ONE SACK SLURRY. STOP SLURRY 6 INCHES (152mm) FROM FINISH GRADE, CONTINUE TO BACKFILL WITH NATIVE SOIL TO FINISH GRADE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | BOX PAD, 70" X 44" X 32" (1,778mm X 1,118mm X 813mm) | 195 (88KG) | 1 | -- | S614040 | -- |
| 2 | GRAVEL, 3/8" - 3/4" | -- | AS REQ'D | -- | S601600 | 3428BP |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

**NOTES:**

I. LOCATE THE LINE SIDE CONDUIT OR FEED TO THE SWITCH IN COMPARTMENT 1. COMPARTMENT 1 SHALL BE LOCATED ON THE RIGHT SIDE OF BOX PAD WHEN VIEWED FROM THE SIDEWALK OR STREET SIDE OF THE BOX PAD.

(II) APPEARANCE AND DIMENSIONS MAY VARY SLIGHTLY BETWEEN MANUFACTURERS.

**REFERENCE:**

a. SEE UG3211.3 FOR INSTALLATION OF IDENTIFICATION TAG.

b. SEE UG3365.2 FOR SLURRY BACKFILL.

c. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

(e) SEE UG4510 FOR TRENCH GROUND WIRE.

f. SEE UG3583 FOR PME-3 SWITCH INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE BOX PAD FOR THE THREE-WAY PAD MOUNTED SWITCH.





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 1**
PLAN VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 9/5/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 3-WAY PAD MOUNTED SWITCH



UG3419.1





**FIGURE 2**
BOX PAD & CONDUIT PLACEMENT
PLAN VIEW





**FIGURE 2**
BOX PAD & CONDUIT PLACEMENT
SIDE VIEW

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 9/5/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 3-WAY PAD MOUNTED SWITCH

UG3419.2

TABLE OF CONTENTS





**FIGURE 3**
EXCAVATION DIMENSIONS

## INSTALLATION:

### CONDUIT:

(A) INSTALL CONDUITS AND TERMINATE THEM NOT LESS THAN 3 INCHES (76mm) ABOVE THE GRAVEL BASE.

(B) DO NOT CUT THE 90 DEGREE ELBOWS ON CURVE.

C. STUB ONE 5-INCH (127mm) CONDUIT FROM THE STREET SIDE OF WINDOW FOUR FEET FROM THE BOTTOM FLANGE OF BOX PAD.

D. INSTALL ONE CONDUIT PER SWITCH WAY. ONE ADDITIONAL CONDUIT MAY BE INSTALLED FOR SCADA POWER SOURCE.

(E) COMPLETELY SLURRY ENCASE ALL 5-INCH 90-DEGREE BENDS TO WITHIN 7 INCHES (178mm) OF THE FINISH CUT OF THE CONDUIT.

### BOX PAD:

(F) ALWAYS INSTALL BOX PAD WITH LONG SIDE PARALLEL TO STREET OR SIDEWALK WITH OPENING TO THE RIGHT.

G. ESTABLISH THE BOX PAD LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE BOX REQUIRES APPROVAL FROM PROJECT MANAGEMENT. WHEN INSTALLING ADJACENT TO NEW OR EXISTING HANDHOLES ALLOW 17 FEET MINIMUM FROM THE CLOSEST EDGE OF HANDHOLE TO THE CENTERLINE OF THE BOX PAD.

H. MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH AND LENGTH PER DRAWING BELOW. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW AN EXTRA 12 INCHES (305mm) FOR SETTING BOX PAD.

J. ADD 4 INCHES (102mm) OF GRAVEL TO BOTTOM OF EXCAVATION AND THEN COMPACT THIS MATERIAL BY HAND OR MACHINE.

K. PLACE THE BOX PAD IN THE EXCAVATION WITH THE LONG SIDE OF THE BOX PAD PARALLED TO AND AS CLOSE AS POSSIBLE TO BACK EDGE OF SIDEWALK.

L. LEVEL BOX PAD.

M. SET THE TOP SURFACE OF THE BOX PAD 4 INCHES (102mm) ABOVE FINAL GRADE.

(N) BACKFILL THE OUTSIDE WITH ONE SACK SLURRY. STOP SLURRY 6 INCHES (152mm) FROM FINISH GRADE; CONTINUE TO BACKFILL WITH NATIVE SOIL TO FINISH GRADE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | PAD, BOX, 60" X 64" X 24" (1,524mm X 1,627mm X 610mm) | 210 (95 KG) | 1 | -- | S513904 | 3419BP |
| 2 | GRAVEL, 3/8" - 3/4" | -- | AS REQ'D | -- | S601600 | -- |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 9/5/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

**NOTES:**

(I) SIZE OF INSERT IS 1/2 X 13.

**REFERENCE:**

a. SEE UG3211.3 FOR INSTALLATION OF IDENTIFICATION TAG.

b. SEE UG3365.2 FOR SLURRY BACKFILL.

c. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

(e) SEE UG4510 FOR TRENCH GROUND WIRE.

f. SEE UG3585 & UG3586 FOR SWITCH INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 9/5/2000 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 3-WAY PAD MOUNTED SWITCH

UG3419.4

**SCOPE:** THIS STANDARD SHOWS THE PAD AND INSTALLATION REQUIREMENTS FOR THE ALLOWABLE CONDUIT COMBINATIONS AND CONFIGURATIONS FOR A SINGLE-PHASE TRANSFORMER, THREE-PHASE FUSE CABINET, SINGLE-PHASE FUSE CABINET AND SINGLE-PHASE CABLE TERMINATOR. THIS ALSO INCLUDES THE 'SP2' SHORT TRANSFORMER PAD USED FOR IN-KIND REPLACEMENTS WHERE THE STANDARD UG3421 PAD WILL NOT FIT.





**FIGURE 1**
UG3421 PAD





**FIGURE 2**
UG3421 'SP2' PAD (II)





**FIGURE 3**
UG3421 'S' PAD





**FIGURE 4**
UG3421 '600A' PAD





**FIGURE 5**
UG3312 HANDHOLE (I)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | FIGURE UPDATE | - | KR | JS | MDJ | 07/25/2017 | G | FIGURE UPDATE | EDM | ADW | GLW | KRG | 10/21/2022 |
| C | FIGURE UPDATE | - | - | - | TR/JJ | 10/19/2010 | F | FORMATTING | EDM | JIK | - | - | 11/05/2020 |
| B | FIGURE UPDATE | - | - | - | TR/JJ | 12/05/2005 | E | EDITORIAL CHANGES | - | GW | JS | CZH | 09/04/2018 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 6

SINGLE-PHASE TRANSFORMER/UTILITY EQUIPMENT PAD

UG3421.1

TABLE OF CONTENTS





**FIGURE 6**
UG3711, UG3712 INSTALLATION (B)
SINGLE-PHASE TRANSFORMER
PLAN VIEW





**FIGURE 7**
UG3514 INSTALLATION (B)
THREE-PHASE FUSE CABINET
PLAN VIEW

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | FIGURE UPDATE | - | KR | JS | MDJ | 07/25/2017 | G | FIGURE UPDATE | EDM | ADW | GLW | KRG | 10/21/2022 |
| C | FIGURE UPDATE | - | - | - | TR/JJ | 10/19/2010 | F | FORMATTING | EDM | JIK | - | - | 11/05/2020 |
| B | FIGURE UPDATE | - | - | - | TR/JJ | 12/05/2005 | E | EDITORIAL CHANGES | - | GW | JS | CZH | 09/04/2018 |





**FIGURE 8**
UG3512 INSTALLATION
SINGLE-PHASE FUSE CABINET
PLAN VIEW





**FIGURE 9**
UG3522 INSTALLATION
SINGLE-PHASE CABLE TERMINATOR
PLAN VIEW

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | FIGURE UPDATE | - | KR | JS | MDJ | 07/25/2017 | G | FIGURE UPDATE | EDM | ADW | GLW | KRG | 10/21/2022 |
| C | FIGURE UPDATE | - | - | - | TR/JJ | 10/19/2010 | F | FORMATTING | EDM | JIK | - | - | 11/05/2020 |
| B | FIGURE UPDATE | - | - | - | TR/JJ | 12/05/2005 | E | EDITORIAL CHANGES | - | GW | JS | CZH | 09/04/2018 |

## INSTALLATION:

### SINGLE-PHASE TRANSFORMER

A. SET PAD LEVEL TO FINAL GRADE AND INSTALL EQUIPMENT GROUND.

(B) PLACE ALL PRIMARY AND SECONDARY CONDUITS WITHIN THE PAD OPENING AS SHOWN IN FIGURES 6 AND 7. DO NOT CUT INTO THE CURVED PORTION ON THE ELBOWS. RADIUS OF CURVATURE IS 36-INCH MINIMUM FOR 3-INCH AND 4-INCH CONDUITS. PLACE ALL CONDUIT WITH 3/0 OR LARGER CABLE TOWARDS THE REAR OF THE 12-INCH SECONDARY AREA. (C)

(C) PRIMARY CONDUITS IN RIGHT HAND CORNER SHALL HAVE 2-INCH CLEARANCE FROM FRONT AND SIDE OF PAD.

(D) THE CONDUIT CONFIGURATION REQUIREMENT BETWEEN TERMINATING POINTS LIMITS THE SECONDARY CONDUIT CONFIGURATION TO 2 WIDE X 4 DEEP OR 4 WIDE X 2 DEEP (NO ONE CONDUIT IS TO BE COMPLETELY SURROUNDED ON ALL FOUR SIDES BY OTHER CONDUITS), USING SPACERS AND 1 SACK CONCRETE SLURRY BACKFILL. CONDUITS MAY ALSO BE INSTALLED SIDE BY SIDE ON THE BOTTOM OF THE TRENCH WITHOUT SPACERS OR CONCRETE SLURRY (4 CONDUITS MAX.). IN THE TRANSITION AREA WHERE THE CONDUITS FROM THE BOTTOM OF THE TRENCH START TOWARD THE SURFACE (THE STRAIGHT PORTION BY THE 90 DEGREE BEND), SPACERS MAY BE REQUIRED TO ALLOW THE 90 DEGREE BENDS TO ENTER STRAIGHT INTO THE PAD OPENING. AT THE SURFACE POINT, THE CONDUITS MAY BE BUNDLED TOGETHER. USE SDG&E APPROVED BASE, SHADING AND BACKFILL.





**FIGURE 10** (D)

E. THE PRIMARY AND SECONDARY CONDUIT COMBINATIONS ALLOWED ARE SHOWN IN THE CHART BELOW. READ DOWN DESIRED COLUMN UNTIL THE NUMBER OF RUNS BEING INSTALLED ARE LOCATED, THEN READ ACROSS THE ROW CHECKING FOR ADDITIONAL ALLOWABLE RUNS. THE SUM OF THE COLUMNS SHALL NOT EXCEED THE TOTAL CONDUITS ALLOWED.

**TABLE 1**

| SECONDARY CONDUIT COMBINATIONS | | | |
|---|---|---|---|
| 2" (EB OR DB) | 3" (EB OR DB) | 4" (EB OR DB) | TOTAL CONDUITS ALLOWED (V) |
| -- | 6 | -- | 7 |
| 2 | 4 | -- | 7 |
| 3 | 3 | -- | 7 |
| 4 | 2 | -- | 7 |
| 7 | -- | -- | 7 |
| 1 | -- | 4 | 5 |
| -- | 1 | 4 | 5 |
| 1 | 1 | 3 | 5 |
| -- | 3 | 2 | 5 |
| -- | 4 | 1 | 5 |
| 4 | -- | 3 | 7 |
| 5 | -- | 2 | 7 |
| 6 | -- | 1 | 7 |

**TABLE 2**

| PRIMARY CONDUIT COMBINATIONS | | |
|---|---|---|
| 2" (EB OR DB) | 3" (EB OR DB) | TOTAL CONDUITS ALLOWED (VI) |
| 4 | -- | 4 |
| 2 | 2 | 4 |
| 2 | 1 | 3 |
| 1 | 2 | 3 |
| 2 | -- | 2 |
| -- | 2 | 2 |
| 1 | -- | 1 |
| -- | 1 | 1 |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | FIGURE UPDATE | - | KR | JS | MDJ | 07/25/2017 | G | FIGURE UPDATE | EDM | ADW | GLW | KRG | 10/21/2022 |
| C | FIGURE UPDATE | - | - | - | TR/JJ | 10/19/2010 | F | FORMATTING | EDM | JIK | - | - | 11/05/2020 |
| B | FIGURE UPDATE | - | - | - | TR/JJ | 12/05/2005 | E | EDITORIAL CHANGES | - | GW | JS | CZH | 09/04/2018 |

## INSTALLATION (CONT'D):

F. TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD.

(G) WHEN THE NUMBER OF REQUIRED CONDUITS IS LESS THAN THE TOTAL CONDUITS ALLOWED IN THE TABLE, INSTALL CONDUITS IN NUMBERED SEQUENCE AS SHOWN IN FIGURE 6.

H. IN SOFT SOILS, A CONCRETE BACKFILL (1-SACK MIX) 12 INCHES BEYOND THE SIDE EDGES OF THE PAD AND 12 INCHES DEEP IS REQUIRED UNDER THE TRANSFORMER PAD.

**THREE-PHASE FUSE CABINET**

J. SET PAD LEVEL TO FINAL GRADE AND INSTALL EQUIPMENT GROUND. TERMINATE CONDUITS 3 INCHES ABOVE BOTTOM OF HANDHOLE. INSTALL CONDUITS.

(K) THE MAXIMUM PRIMARY CONDUITS ALLOWED ARE ULTIMATE 4 RUNS OF 4-INCH CONDUIT AS SHOWN IN FIGURE 7.

**SINGLE-FUSE SWITCHING CABINET AND SINGLE-PHASE TERMINATOR**

(L) SET PAD LEVEL TO FINAL GRADE AND INSTALL EQUIPMENT GROUND. TERMINATE CONDUITS 3 INCHES ABOVE BOTTOM OF HANDHOLE. INSTALL CONDUITS AS SHOWN IN FIGURE 7, 8 AND 9.

1. INSTALL CONDUITS #1 AND #2 WHENEVER THERE IS JUST ONE LINE AND ONE LOAD CABLE.
2. INSTALL CONDUITS #3 AND/OR #4 FOR THE SECOND LOAD OR LINE CABLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO |
|---|---|---|---|---|---|---|---|
| 1 | PAD, SINGLE-PHASE TRANSFORMER/UTILITY EQUIPMENT PAD | 619 MAX. | 1 | -- | S514240 | 3421-1 | FC3PAD |
| 2 | HANDHOLE, BODY | 185 MAX. | 1 | 3312 | S162426 | 3312-1 | |
| 3 | PAD, TRANSFORMER, 'SP2', 38" X 38" | 505 MAX. | 1 | -- | S514242 | 3421-2 | -- |
| 4 | PAD, TRANSFORMER, '1S' | -- | 1 | -- | S514220 | 3413-0 | -- |
| 5 | PAD, TRANSFORMER, '600A' | -- | 1 | -- | S514050 | 3421CT | -- |

## NOTES:

(I) REQUIRED FOR THREE-PHASE FUSE CABINET, SINGLE-PHASE FUSE CABINET AND SINGLE-PHASE CABLE TERMINATOR.

(II) TO BE USED ONLY FOR IN-KIND REPLACEMENTS. DEVIATION REQUIRED FOR NEW INSTALLATIONS.

III. TRANSFORMER COOLING FINS MAY OVERHANG REAR OF PAD BY 6 INCHES.

IV. FIVE-INCH CONDUIT NOT ALLOWED IN THESE INSTALLATIONS.

(V) SECONDARY CONDUITS MAY INCLUDE TWO ADDITIONAL ONE-INCH CONDUITS FOR STREET LIGHTS.

(VI) ONE 4-INCH OR ONE 5-INCH PRIMARY CONDUIT IS ALLOWED WHEN THE CONDUIT IS EXTENDED FROM AN EXISTING STUBOUT.

## REFERENCE:

a. SEE UG3211 FOR PAD IDENTIFICATION.

b. SEE UG3370 OR UG3371 FOR TRENCH, UTILITY POSITIONING, SHADING AND BACKFILL REQUIREMENTS.

c. SEE UG3376 FOR CONCRETE SLURRY, SHADING AND TYPE OF CONDUIT.

d. SEE UG3479 FOR BARRIER PROTECTION AND CLEARANCE.

e. SEE UG3487 FOR SINGLE-PHASE TRANSFORMER LOCATIONS NEXT TO CATV AND/OR TELCO.

f. SEE UG3480, UG3481, UG3482 AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

g. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

h. SEE UG3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | FIGURE UPDATE | - | KR | JS | MDJ | 07/25/2017 | G | FIGURE UPDATE | EDM | ADW | GLW | KRG | 10/21/2022 |
| C | FIGURE UPDATE | - | - | - | TR/JJ | 10/19/2010 | F | FORMATTING | EDM | JIK | - | - | 11/05/2020 |
| B | FIGURE UPDATE | - | - | - | TR/JJ | 12/05/2005 | E | EDITORIAL CHANGES | - | GW | JS | CZH | 09/04/2018 |

**REFERENCE (CONT'D):**

i. SEE UG3485 AND UG3487 FOR RETAINING WALLS.

j. SEE UG3512 FOR SINGLE-PHASE LOW PROFILE FUSED SWITCHING CABINET.

k. SEE UG3522 FOR SINGLE-PHASE LOW PROFILE TERMINATOR INSTALLATION.

l. SEE UG3711, UG3712 AND UG3713 FOR TRANSFORMER INSTALLATIONS.

m. SEE UG4512 FOR EQUIPMENT GROUNDING.

n. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | FIGURE UPDATE | - | KR | JS | MDJ | 07/25/2017 | G | FIGURE UPDATE | EDM | ADW | GLW | KRG | 10/21/2022 |
| C | FIGURE UPDATE | - | - | - | TR/JJ | 10/19/2010 | F | FORMATTING | EDM | JIK | - | - | 11/05/2020 |
| B | FIGURE UPDATE | - | - | - | TR/JJ | 12/05/2005 | E | EDITORIAL CHANGES | - | GW | JS | CZH | 09/04/2018 |

**SCOPE:** THIS STANDARD SHOWS THE BOX PAD **W/TEMPORARY COVER** AND CONDUIT PLACEMENT FOR THE PAD MOUNTED PME 9, 10, 11 AIR BREAK AND 2 SIDED 4-WAY TRAYER SWITCHES.





**FIGURE 1**
TEMPORARY COVER





**FIGURE 2** (I)
BOX PAD

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 2/5/2014 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD W/ TEMPORARY COVER FOR
PME 9, 10, 11 AND 2 SIDED TRAYER SWITCHES

UG3423.1

TABLE OF CONTENTS





**FIGURE 3**
BOX & CONDUIT PLACEMENT
PLAN VIEW





**FIGURE 3**
BOX & CONDUIT PLACEMENT
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 2/5/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD W/ TEMPORARY COVER FOR
PME 9, 10, 11 AND 2 SIDED TRAYER SWITCHES

UG3423.2





**FIGURE 4**
EXCAVATION DIMENSIONS





**FIGURE 5**

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 2/5/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD W/ TEMPORARY COVER FOR
PME 9, 10, 11 AND 2 SIDED TRAYER SWITCHES

UG3423.3

## TABLE 1

| CONDUIT COMBINATIONS | | | | |
|---|---|---|---|---|
| **SWITCH TYPE** | **CMPT #1** | **CMPT #2** | **CMPT #3** | **CMPT #4** |
| PME-9 | 5" (127mm) (QTY 1) + 2" (51mm) THRU 5" (127mm) (QTY 1) TOTAL QTY = 2 | | 4" (102mm) OR 5" (127mm) (QTY 1) + 3" (76mm) FOR SCADA ANTENNA ONLY (QTY 1) TOTAL QTY = 2 | 4" (102mm) OR 5" (127mm) (QTY 2) TOTAL QTY = 2 |
| PME-10 (II) | | | 5" (127mm) (QTY 2) + 3" (76mm) FOR SCADA ANTENNA ONLY (QTY 1) TOTAL QTY = 3 | 5" (127mm) (QTY 1) + 2" (51mm) THRU 5" (127mm) (QTY 1) TOTAL QTY = 2 |
| TRAYER 2-SIDED 4-WAY (II) | | | | |
| PME-11 | | | 4" (102mm) OR 5" (127mm) (QTY 1) + 3" (76mm) FOR SCADA ANTENNA ONLY (QTY 1) TOTAL QTY = 2 | |









**FIGURE 6**
TEMPORARY 3423 PME AND TRAYER PAD COVER INSTALLATION (O)(III)(IV)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 2/5/2014 | D | | | | | | |



TABLE OF CONTENTS

## INSTALLATION:

**CONDUIT:**

(A) INSTALL CONDUITS AND TERMINATE THEM NOT LESS THAN 3 INCHES (76mm) ABOVE THE GRAVEL BASE.

(B) DO NOT CUT THE 90-DEGREE ELBOWS ON CURVE.

(C) STUB ONE 3-INCH (76mm) CONDUIT FROM CMPT #3, 4 FEET (1,219mm) FROM THE BOTTOM FLANGE OF BOX PAD FOR FUTURE SCADA ANTENNA.

D. NO MORE THAN TWO CONDUITS MAY BE INSTALLED IN COMPARTMENTS 1, 2 AND 4 FOR CABLE PULLING. NO ADDITIONAL CONDUITS MAY BE INSTALLED IN COMPARTMENTS 3.

(E) WHEN TWO CONDUITS ARE INSTALLED IN ONE COMPARTMENT, PLACE CONDUITS SIDE BY SIDE CENTERED ON THE APPROPRIATE DIMENSION.

(F) COMPLETELY SLURRY ENCASE ALL 5-INCH 90-DEGREE BENDS TO WITHIN 7 INCHES OF THE FINISH CUT OF THE CONDUIT.

**BOX PAD:**

G. ESTABLISH THE BOX PAD LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING THE BOX REQUIRES APPROVAL FROM PROJECT MANAGEMENT. WHEN INSTALLING ADJACENT TO NEW OR EXISTING HANDHOLES ALLOW 17 FEET MINIMUM FROM THE CLOSEST EDGE OF HANDHOLE TO THE CENTERLINE OF THE BOX PAD.

H. MARK OUT DIMENSIONS FOR THE EXCAVATION WIDTH AND LENGTH PER DRAWING BELOW. THE WIDTH, AND LENGTH DIMENSIONS GIVEN, ALLOW AN EXTRA 12 INCHES (305mm) FOR SETTING BOX PAD.

(J) ADD 4 INCHES (102mm) OF GRAVEL TO BOTTOM OF EXCAVATION AND THEN COMPACT THIS MATERIAL BY HAND OR MACHINE.

K. PLACE THE BOX PAD IN THE EXCAVATION WITH THE SHORTEST SIDE OF THE BOX PAD PARALLEL TO AND 15 INCHES (381mm) FROM THE BACK EDGE OF THE SIDEWALK.

(L) LEVEL BOX PAD.

M. SET THE TOP SURFACE OF THE BOX PAD 4 INCHES (102mm) ABOVE FINAL GRADE.

(N) BACKFILL THE OUTSIDE WITH ONE SACK SLURRY. STOP SLURRY 6 INCHES (152mm) FROM FINISH GRADE, CONTINUE TO BACKFILL WITH NATIVE SOIL TO FINISH GRADE.

(O) **TEMPORARY COVER INSTALLATION:**

1. TEMPORARY COVERS WILL FIT ALL 3423 BOX PADS CURRENTLY PURCHASED.
2. PLACE COVER ON PAD, CENTER/ALIGN COVER ON BOX PAD FOR DRILLING.
3. USE A 5/16-INCH DRILL BIT AND DRILL MOTOR, DRILL THROUGH COVER AND BOX PAD.
4. INSTALL 4 SELF-TAPPING BOLTS (S152716 (X)) WITH 4 WASHERS (S800160).
5. TIGHTEN BOLTS BY HAND WITH SOCKET AND RATCHET, DO NOT OVER TORQUE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | PAD, BOX, 78" X 73" X 32" (1,981mm X 1,854mm X 813mm) | 200 (91 KG) | 1 | -- | S514028 | 3423BP |
| 2 | GRAVEL, 3/8" - 3/4" | -- | AS REQ'D | -- | S601600 | -- |
| 3 | COVER, TEMPORARY, 77" X 71" X 1 1/2" (1,956mm X 1,803mm X 38mm) | 150 (68 KG) | 1 | -- | S286810 | PMECOV |
| 4 | BOLT, SIMPSON STRONGTIE, 3/8" X 4" | -- | 4 | -- | S152716 (X) | -- |
| 5 | WASHER, 3/8" | -- | 4 | -- | S800160 | -- |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 2/5/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD W/ TEMPORARY COVER FOR PME 9, 10, 11 AND 2 SIDED TRAYER SWITCHES

UG3423.5

**NOTES:**

(I) APPEARANCE AND DIMENSIONS MAY VARY SLIGHTLY BETWEEN MANUFACTURERS.

(II) WHEN ONLY THREE OF THE FOUR SWITCH POSITIONS WILL BE UTILIZED, PULL CABLES IN COMPARTMENTS 1, 2 AND 4 FIRST.

(III) ALL PARTIES INCLUDING APPLICANT INSTALLERS, CONTRACT CONSTRUCTION CREWS AND SDG&E CREWS THAT INSTALL THE PAD 3423 ARE REQUIRED TO INSTALL A TEMPORARY PAD COVER AT ALL PME 9, 10 AND 11, AND 2-SIDED TRAYER SWITCH LOCATIONS. THE ONLY EXCEPTION TO THIS STANDARD APPLICATION IS THAT THE SWITCH SHALL BE INSTALLED ON THE PAD THE SAME DAY AFTER THE PAD IS INSTALLED.

(IV) WHEN TEMPORARY COVERS ARE REMOVED, THEY SHALL BE RETURNED TO THE DISTRICT OF RECORD AND CREDITED BACK AS THE PAD COVER IS REUSABLE FOR OTHER FUTURE INSTALLATIONS.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

a. SEE UG3211.3 FOR INSTALLATION OF IDENTIFICATION TAG.

b. SEE UG3365.2 FOR SLURRY BACKFILL.

c. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

(e) SEE UG4510 FOR TRENCH GROUND WIRE.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 2/5/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD W/ TEMPORARY COVER FOR
PME 9, 10, 11 AND 2 SIDED TRAYER SWITCHES



UG3423.6

**SCOPE:** THIS STANDARD SHOWS REQUIREMENTS FOR INSTALLING A 3425 THREE-PHASE PAD FOR DEADFRONT TRANSFORMER APPLICATION THROUGH 300 KVA. ALSO FOR 3750 KVA HHR DEADFRONT BOOSTER TRANSFORMER AND PRIMARY METER CABINET.





**FIGURE 1**





**FIGURE 2**
MAXIMUM PRIMARY CONDUITS ALLOWED (B)(C)(D)(E)
TWO RUNS OF 4-INCH (EB OR DB)





**FIGURE 3**
MAXIMUM OF TWO PRIMARY CONDUITS ALLOWED FOR PRIMARY METER CABINET

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 6/9/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE DEADFRONT TRANSFORMER PAD INSTALLATION 3425

UG3425.1



TABLE OF CONTENTS

## INSTALLATION:

(A) 1-INCH EARTH IN THE BOTTOM OF THE TRENCH IS REQUIRED TO PREVENT DAMAGE FROM ROCKS, SAGS, AND POCKETS.

(B) PLACE ALL PRIMARY AND SECONDARY CONDUITS WITHIN THE PAD OPENING AS SHOWN IN FIGURES 2 & 3. TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH THE TOP OF THE PAD. DO NOT CUT INTO THE CURVED PORTION OF THE ELBOWS. RADIUS OF CURVATURE IS 36-INCH MINIMUM FOR 3-INCH, 4-INCH AND 5-INCH CONDUITS.

(C) THE CONDUIT CONFIGURATION REQUIREMENT BETWEEN TERMINATING POINTS LIMITS THE SECONDARY CONDUIT CONFIGURATION TO 2 WIDE X 3 DEEP OR 3 WIDE X 2 DEEP (NO ONE CONDUIT IS TO BE COMPLETELY SURROUNDED ON ALL FOUR SIDES BY OTHER CONDUITS), USING SPACERS AND 1 SACK CONCRETE SLURRY BACKFILL. CONDUITS MAY ALSO BE INSTALLED SIDE BY SIDE ON THE BOTTOM OF THE TRENCH WITHOUT SPACERS OR CONCRETE SLURRY (FOUR CONDUITS MAX.). IN THE TRANSITION AREA WHERE THE CONDUITS FROM THE BOTTOM OF THE TRENCH START TOWARD THE SURFACE (THE STRAIGHT PORTION BY THE 90° BEND), SPACERS MAY BE REQUIRED TO ALLOW THE 90° BENDS TO ENTER STRAIGHT INTO THE PAD OPENING. AT THE SURFACE POINT, THE CONDUITS MAY BE BUNDLED TOGETHER. USE SDG&E APPROVED BASE, SHADING AND BACKFILL.





**FIGURE 4** (C)

(D) ANY COMBINATION OF 3, 4 OR 5-INCH SECONDARY CONDUITS MAY BE USED, PROVIDED THEY DO NOT EXCEED THE TOTAL OF 6 OR THE MAXIMUM OF EACH SIZE CONDUIT AS SPECIFIED IN FIGURE 2. AN EXCEPTION WOULD BE WHEN THE TRANSFORMER FEEDS ONE CUSTOMER WITH A 2000A MAIN WHICH REQUIRES FIVE 5-INCH CONDUITS. NO FUTURE CUSTOMERS ARE ALLOWED IN THIS INSTALLATION. TWO EXTRA 1-INCH OR TWO EXTRA 2-INCH CONDUITS MAY BE ADDED TO SERVE STREET LIGHTS, RECREATION BUILDINGS, ETC.

(E) WHEN NUMBER OF REQUIRED CONDUITS IS LESS THAN THE TOTAL ALLOWABLE SHOWN IN FIGURE 2, INSTALL IN NUMBERED SEQUENCE AS SHOWN.

F. IN SOFT SOILS A CONCRETE BACKFILL (1-SACK MIX.) IS REQUIRED UNDER THE PAD, 12 INCHES BEYOND THE SIDE EDGES OF PAD AND 12 INCHES DEEP.

(G) MAXIMUM NUMBER OF CONDUITS ALLOWED FOR 200A APPLICATION IS TWO 4-INCH PRIMARY CONDUITS. NO COMBINATION OF DIFFERENT SIZE PRIMARY CONDUITS ALLOWED. NO SECONDARY CONDUITS ALLOWED.

(H) MAXIMUM NUMBER OF CONDUITS ALLOWED FOR 600A APPLICATION IS TWO 5-INCH PRIMARY CONDUITS. NO COMBINATION OF DIFFERENT SIZE PRIMARY CONDUITS ALLOWED. NO SECONDARY CONDUITS ALLOWED.

(J) PLACE PRIMARY CONDUITS WITHIN THE PAD OPENING AS SHOWN IN FIGURES 2 & 3. TERMINATE PRIMARY CONDUITS 3 INCHES ABOVE THE BOTTOM OF 3311 HANDHOLE. 3311 HANDHOLE TO BE INSTALLED WITH PRIMARY METER APPLICATIONS. DO NOT CUT THE CURVED PORTION OF CONDUIT ELBOWS. RADIUS OF CURVATURE IS 36 INCHES MINIMUM FOR 4-INCH OR 5-INCH CONDUITS.

(K) WHEN METER WILL NOT BE ATTACHED TO PRIMARY METER CABINET, INSTALL 1-INCH CONDUIT TO REMOTE METER LOCATION. 1-INCH CONDUIT NOT REQUIRED WHEN METER ATTACHED.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 6/9/2005 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO UNITS |
|---|---|---|---|---|---|---|---|
| 1 | PAD | 1,900 MAX. | AS REQ'D | -- | S513998 | 3425-3 | 3425-M |
| 2 | HANDHOLE, 3311 | -- | AS REQ'D | -- | S162660 | 3311-S | |

## NOTES:

I. TRANSFORMER COOLING FINS MAY OVERHANG REAR OF PAD BY 6 INCHES.

II. IF NUMBER OF SECONDARY CONDUITS IS GREATER THAN MAXIMUM SHOWN, USE PAD PER UG3426 OR UG3427.

III. TRANSFORMER PAD MAY NOT BE POURED IN PLACE. USE PRECAST PADS ONLY.

## REFERENCE:

a. SEE UG3211.3 FOR PAD IDENTIFICATION.

b. SEE UG3370 OR 3371 FOR TRENCH, UTILITY POSITIONING, SHADING AND BACKFILL REQUIREMENTS.

c. SEE UG3376 FOR CONCRETE SLURRY.

d. SEE UG3479 FOR TRANSFORMER BARRIER PROTECTION.

e. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

f. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

g. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3489 FOR RETAINING WALLS.

i. SEE UG3751 FOR TRANSFORMER INSTALLATION.

j. SEE UG4512 FOR EQUIPMENT GROUNDING.

k. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | CZH | 9/4/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 6/9/2005 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS REQUIREMENTS FOR INSTALLING A 3426 THREE-PHASE PAD FOR DEADFRONT TRANSFORMER APPLICATION THROUGH 1000 KVA.






**FIGURE 1**
PAD




CONFIGURATION 1
3-INCH SECONDARY CONDUITS

CONFIGURATION 2
4-INCH SECONDARY CONDUITS

CONFIGURATION 3
5-INCH SECONDARY CONDUITS

**FIGURE 2**
MAXIMUM PRIMARY CONDUITS ALLOWED (B)(C)(D)(E)(H)
TWO RUNS OF 4-INCH (EB OR DB)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1998 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE DEADFRONT TRANSFORMER PAD INSTALLATION 3426

UG3426.1



TABLE OF CONTENTS




**DETAIL 1**
TYPICAL INSTALLATION FOR
NINE 3-INCH OR NINE 4-INCH
SECONDARY CONDUITS





**FIGURE 3**
MAXIMUM PRIMARY CONDUITS ALLOWED
TWO RUNS OF 4-INCH (EB OR DB)





**FIGURE 4**
TYPICAL INSTALLATION FOR SIX 5-INCH
SECONDARY CONDUITS

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1998 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE DEADFRONT TRANSFORMER PAD INSTALLATION 3426

UG3426.2

## INSTALLATION:

(A) 1-INCH EARTH IN THE BOTTOM OF TRENCH IS REQUIRED TO PREVENT DAMAGE FROM ROCKS, SAGS AND POCKETS.

(B) PLACE ALL SECONDARY CONDUITS WITHIN THE PAD OR HANDHOLE OPENING AS SHOWN IN FIGURES 2-4. TERMINATE PRIMARY OR SECONDARY CONDUITS FLUSH WITH THE TOP OF THE PAD. WHEN A HANDHOLE IS REQUIRED FOR SECONDARY CONDUITS, TERMINATE THEM NOT LESS THAN 3 INCHES ABOVE BOTTOM OF HANDHOLE. DO NOT CUT INTO THE CURVED PORTION OF THE ELBOWS. RADIUS OF CURVATURE IS 36 INCHES MINIMUM FOR 3-INCH, 4-INCH AND 5-INCH CONDUITS.

(C) THE CONDUIT CONFIGURATION REQUIREMENT BETWEEN TERMINATING POINTS LIMITS THE SECONDARY CONDUIT CONFIGURATION TO TWO WIDE X FIVE DEEP OR FIVE WIDE X TWO DEEP (NO ONE CONDUIT IS TO BE COMPLETELY SURROUNDED ON ALL FOUR SIDES BY OTHER CONDUITS), USING SPACERS AND ONE SACK CONCRETE SLURRY BACKFILL. CONDUITS MAY ALSO BE INSTALLED SIDE BY SIDE ON THE BOTTOM OF THE TRENCH WITHOUT SPACERS OR CONCRETE SLURRY (FOUR CONDUITS MAX.). IN THE TRANSITION AREA WHERE THE CONDUITS FROM THE BOTTOM OF THE TRENCH START TOWARD THE SURFACE (THE STRAIGHT PORTION BY THE 90° BEND), SPACERS MAY BE REQUIRED TO ALLOW THE 90° BENDS TO ENTER STRAIGHT INTO THE PAD OPENING. AT THE SURFACE POINT, THE CONDUITS MAY BE BUNDLED TOGETHER. USE SDG&E APPROVED BASE, SHADING AND BACKFILL.





**FIGURE 5** (C)

(D) THE TOP AND INTERMEDIATE 3314 HANDHOLE SECTIONS MAY BE ELIMINATED WHEN INSTALLATION SERVES ONLY ONE CUSTOMER ULTIMATELY AND CONDUIT REQUIREMENTS DO NOT EXCEED WHAT IS SHOWN IN FIGURE 2 OR AS SPECIFIED IN NOTE E. IF MORE THAN FIVE 5-INCH CONDUITS ARE USED (REGARDLESS OF THE NUMBER OF CUSTOMERS), ONE TOP SECTION AND TWO INTERMEDIATE SECTIONS ARE REQUIRED.

(E) **FOR SECONDARY INSTALLATION WITHOUT A HANDHOLE (ULTIMATELY ONE CUSTOMER ONLY),** ANY COMBINATION OF 3-INCH, 4-INCH OR 5-INCH SECONDARY CONDUITS MAY BE USED PROVIDED THEY DO NOT EXCEED A TOTAL OF SIX OR THE TOTAL OF EACH SIZE CONDUIT SHOWN IN FIGURE 2. TWO EXTRA 1-INCH OR TWO EXTRA 2-INCH CONDUITS MAY BE ADDED TO SERVE STREET LIGHT, RECREATION BUILDINGS, ETC.

(F) **FOR SECONDARY INSTALLATIONS IN A HANDHOLE**, ANY COMBINATION OF 3-INCH, 4-INCH, OR 5-INCH SECONDARY CONDUITS MAY BE USED, PROVIDED THEY DO NOT EXCEED THE TOTAL OF NINE OR THE MAXIMUM OF EACH SIZE CONDUIT (SEE FIGURES 3 & 4). TWO EXTRA 1-INCH OR TWO EXTRA 2-INCH CONDUITS MAY BE ADDED TO SERVE STREET LIGHT, RECREATION BUILDINGS, ETC.

(G) WHEN THE NUMBER OF REQUIRED CONDUITS IS LESS THAN THE TOTAL SHOWN ON THE SKETCHES, INSTALL THE CONDUITS IN NUMBERED SEQUENCE AS SHOWN.

(H) IF THE INSTALLATION IS FOR A 12KV TO 4KV TRANSFORMER (HPR TYPE), DO NOT USE HANDHOLE AND TERMINATE CONDUITS FLUSH WITH TOP OF PAD.

(J) IN SOFT SOILS A CONCRETE BACKFILL (1-SACK MIX.) IS REQUIRED UNDER THE PAD, 12 INCHES BEYOND THE SIDE EDGES OF PAD AND 12 INCHES DEEP.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1998 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO UNITS |
|---|---|---|---|---|---|---|---|
| 1 | PAD | 2,430 MIN.<br>2,690 MAX. | 1 | -- | S514005 | 3426B0 | 3426B3 |
| 2 | HANDHOLE SECTION, TOP | -- | 1 | 3314 | S336210 | -- | |
| 3 | HANDHOLE SECTION, INTERMEDIATE | -- | 2 | | S336212 | -- | |
| 4 | COVER, PARKWAY | -- | 1 | | S286843 | -- | |

## NOTES:

I. TRANSFORMER COOLING FINS MAY OVERHANG REAR OF PAD BY 6 INCHES.

II. IF NUMBER OF SECONDARY CONDUITS IS GREATER THAN MAXIMUM SHOWN, USE PAD 3427. (1)

III. TRANSFORMER PAD MAY NOT BE POURED IN PLACE. USE PRECAST PADS ONLY.

## REFERENCE:

a. SEE UG3211.3 FOR PAD IDENTIFICATION.

b. SEE UG3370 OR UG3371 FOR TRENCH, UTILITY POSITIONING, SHADING AND BACKFILL REQUIREMENTS.

c. SEE UG3376 FOR CONCRETE SLURRY, SHADING AND TYPE OF CONDUIT.

d. SEE UG3479 FOR TRANSFORMER BARRIER PROTECTION.

e. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

f. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

g. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3489 FOR RETAINING WALLS.

i. SEE UG3751 FOR TRANSFORMER INSTALLATION.

j. SEE UG4512 FOR EQUIPMENT GROUNDING.

k. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

(1) SEE UG3427, THREE-PHASE TRANSFORMER PAD INSTALLATION 3427.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1998 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE DEADFRONT TRANSFORMER PAD INSTALLATION 3426

UG3426.4

**SCOPE:** THIS STANDARD SHOWS THE REQUIREMENTS FOR INSTALLING A 3427 THREE-PHASE PAD FOR DEADFRONT TRANSFORMER APPLICATION FROM 1,500 KVA THROUGH 2,500 KVA AND 3,000 KVA LIVEFRONT TRANSFORMER.

**ATTENTION:**

* DEADFRONT TRANSFORMERS BETWEEN 225 KVA & 1,000 KVA MAX. ARE TO BE USED ON THIS PAD WHENEVER THE CONDUIT REQUIREMENTS ARE GREATER THAN THE MAXIMUM SHOWN ON UG3425 OR UG3426. (I)






**FIGURE 1**
PAD




CONFIGURATION 1
3-INCH SECONDARY CONDUITS

CONFIGURATION 2
4-INCH SECONDARY CONDUITS

CONFIGURATION 3
5-INCH SECONDARY CONDUITS

**FIGURE 2**
MAXIMUM PRIMARY CONDUITS ALLOWED (B)(C)(E)(G)
TWO RUNS OF 4-INCH (EB OR DB)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

TABLE OF CONTENTS





**FIGURE 3**
MAXIMUM PRIMARY CONDUITS ALLOWED
TWO RUNS OF 4-INCH (EB OR DB)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE DEADFRONT/LIVEFRONT TRANSFORMER PAD INSTALLATION 3427

UG3427.2

## INSTALLATION:

(A) 1-INCH EARTH IN THE BOTTOM OF THE TRENCH IS REQUIRED TO PREVENT DAMAGE FROM ROCKS, SAGS OR POCKETS.

(B) PLACE ALL SECONDARY CONDUITS WITHIN THE PAD OR HANDHOLE OPENING AS SHOWN IN FIGURES 2 & 3. TERMINATE PRIMARY OR SECONDARY CONDUITS FLUSH WITH TOP OF THE PAD. WHEN A HANDHOLE IS REQUIRED FOR SECONDARY CONDUITS, TERMINATE THEM NOT LESS THAN 3 INCHES ABOVE BOTTOM OF HANDHOLE. DO NOT CUT INTO THE CURVED PORTION OF THE ELBOWS. RADIUS OF CURVATURE IS 36 INCHES MINIMUM FOR 3-INCH, 4-INCH AND 5-INCH CONDUITS.

(C) THE CONDUIT CONFIGURATION REQUIREMENT BETWEEN TERMINATING POINTS LIMITS THE SECONDARY CONDUIT CONFIGURATION TO TWO WIDE X SIX DEEP OR SIX WIDE X TWO DEEP (NO ONE CONDUIT IS TO BE COMPLETELY SURROUNDED ON ALL FOUR SIDES BY OTHER CONDUITS) USING SPACERS AND 1 SACK CONCRETE SLURRY BACKFILL. CONDUITS MAY ALSO BE INSTALLED SIDE BY SIDE ON THE BOTTOM OF THE TRENCH WITHOUT SPACERS OR CONCRETE SLURRY (FOUR CONDUITS MAX.). IN THE TRANSITION AREA WHERE THE CONDUITS FROM THE BOTTOM OF THE TRENCH START TOWARD THE SURFACE (THE STRAIGHT PORTION BY THE 90° BEND), SPACERS MAY BE REQUIRED TO ALLOW THE 90° BENDS TO ENTER STRAIGHT INTO THE PAD OPENING. AT THE SURFACE POINT, THE CONDUITS MAY BE BUNDLED TOGETHER. USE SDG&E APPROVED BASE, SHADING AND BACKFILL.





**FIGURE 4** (C)

(D) THE 3314 HANDHOLE SECTIONS ARE NOT REQUIRED WHEN INSTALLATION SERVES ONLY ONE CUSTOMER ULTIMATELY AND CONDUIT REQUIREMENTS DO NOT EXCEED THAT SHOWN IN FIGURE 2 OR AS SPECIFIED IN NOTE E. IF MORE THAN FIVE 5-INCH CONDUITS ARE USED (REGARDLESS OF THE NUMBER OF CUSTOMERS), ONE TOP SECTION AND TWO INTERMEDIATE ARE REQUIRED.

(E) **FOR SECONDARY INSTALLATIONS WITHOUT A HANDHOLE (ULTIMATELY ONE CUSTOMER ONLY)**, ANY COMBINATION OF 3-INCH, 4-INCH OR 5-INCH SECONDARY CONDUITS MAY BE USED PROVIDED THEY DO NOT EXCEED THE TOTAL OF EACH SIZE CONDUIT SHOWN IN FIGURE 2. TWO EXTRA 1-INCH OR TWO EXTRA 2-INCH CONDUITS MAY BE ADDED TO SERVE STREET LIGHT, RECREATION BUILDINGS, ETC.

(F) **FOR SECONDARY INSTALLATIONS IN A HANDHOLE**, ANY COMBINATION OF 3-INCH, 4-INCH OR 5-INCH SECONDARY CONDUITS MAY BE USED PROVIDED THEY DO NOT EXCEED THE TOTAL OF 12 OR THE MAXIMUM OF EACH SIZE CONDUIT (12-3", 12-4" OR 12-5"). TWO EXTRA 1-INCH OR TWO EXTRA 2-INCH CONDUITS MAY BE ADDED TO SERVE STREET LIGHT, RECREATION BUILDINGS, ETC.

(G) WHEN NUMBER OF REQUIRED CONDUITS IS LESS THAN TOTAL SHOWN ON SKETCHES, INSTALL CONDUITS IN NUMBERED SEQUENCE AS SHOWN.

(H) A CONCRETE BACKFILL (1-SACK MIX.) IS REQUIRED UNDER THE PAD, 12 INCHES BEYOND THE SIDE EDGES OF PAD AND 12 INCHES DEEP.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO UNITS |
|---|---|---|---|---|---|---|---|
| 1 | PAD | 4,000 MIN. 4,100 MAX. | 1 | -- | S514012 | 3427B0 | 3427B3 |
| 2 | HANDHOLE SECTION, TOP | -- | 1 | 3314 | S332610 | -- | |
| 3 | HANDHOLE SECTION, INTERMEDIATE | -- | 2 | | S336212 | -- | |
| 4 | COVER, PARKWAY | -- | 1 | | S286843 | -- | |
| 5 | BACKFILL, CONCRETE | -- | AS REQ'D | -- | -- | 3427CB | -- |

## NOTES:

I. SET TRANSFORMER ON THE PAD AS FAR TO THE LEFT AS POSSIBLE IN ORDER TO OBTAIN MAXIMUM CLEARANCE IN THE SECONDARY COMPARTMENT FOR CABLE TRAINING.

II. TRANSFORMER COOLING FINS MAY OVERHANG REAR OF PAD BY 6 INCHES.

III. PAD MAY NOT BE POURED IN PLACE. USE PRECAST PADS ONLY.

## REFERENCE:

a. SEE UG3211.3 FOR PAD IDENTIFICATION.

b. SEE UG3370 OR UG3371 FOR TRENCH, UTILITY POSITIONING, SHADING AND BACKFILL REQUIREMENTS.

c. SEE UG3376 FOR CONCRETE SLURRY, SHADING AND TYPE OF CONDUIT.

d. SEE UG3479 FOR TRANSFORMER BARRIER PROTECTION.

e. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

f. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

g. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3489 FOR RETAINING WALLS.

i. SEE UG3751 FOR TRANSFORMER INSTALLATION.

j. SEE UG4512 FOR EQUIPMENT GROUNDING.

k. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

(l) SEE UG3755 FOR CONDUIT PLACEMENT OF STEP-DOWN TRANSFORMER INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE BOX PAD 4-WAY SWITCH.





**FIGURE 1**
FIBERGLASS PAD
ISOMETRIC VIEW





**FIGURE 2**
CONCRETE PAD
ISOMETRIC VIEW

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | DRAWING UPDATE | EDM | EJA | JES | KRG | 07/14/2022 |
| A | REVISION | - | - | - | - | 12/08/2005 | D | DRAWING UPDATE | EDM | EJA | GLW | CZH | 07/29/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 4-WAY PAD MOUNTED SWITCH



UG3428.1

TABLE OF CONTENTS





**FIGURE 3**
EXCAVATION DIMENSIONS
FIBERGLASS OR CONCRETE PAD
SEE TABLE 1





**FIGURE 4**
INTERIOR LAYOUT
FIBERGLASS OR CONCRETE PAD (F) (G) (I)





**FIGURE 4**
ALTERNATE ARRANGEMENT (F) (G) (I)

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | DRAWING UPDATE | EDM | EJA | JES | KRG | 07/14/2022 |
| A | REVISION | - | - | - | - | 12/08/2005 | D | DRAWING UPDATE | EDM | EJA | GLW | CZH | 07/29/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 4-WAY PAD MOUNTED SWITCH

UG3428.2





**FIGURE 4**
FIBERGLASS OR CONCRETE PAD
SEE TABLE 1
VIEW A-A

**TABLE 1**

| BOX PAD DIMENSIONS | | | | |
|---|---|---|---|---|
| **BOX PAD MATERIAL** | **Z (IN)** | **Y (IN)** | **X (IN)** | **EXCAVATION DIMENSIONS (IN)** |
| FG | 56 | 84 | 4 | 127 X 98 |
| CONCRETE | 58 | 86 | 6 | 98 X 70 |

TABLE OF CONTENTS

## INSTALLATION:

### CONDUIT

(A) INSTALL CONDUITS AND TERMINATE THEM NO LESS THAN 3 INCHES ABOVE THE GRAVEL BASE.

(B) DO NOT CUT THE 90-DEGREE ELBOWS ON CURVE.

(C) SCADA ANTENNA CONDUIT TO BE LOCATED ON LEFT SIDE OF WINDOW. STUB ONE 3-INCH CONDUIT OUT FOUR FEET.

D. TWO CONDUITS MAY BE INSTALLED AT ONE SWITCH POSITION ONLY IF CONDUIT LENGTH EXCEEDS 50 FEET OR GOES TO A POLE SUBJECT TO FUTURE CONVERSION. THE SECOND CONDUIT MUST GO TO THE ADJACENT POSITION AT THE NEXT STRUCTURE.

(E) COMPLETELY SLURRY ENCASE ALL 5-INCH 90-DEGREE BENDS TO WITHIN 7 INCHES OF FINISH CUT OF CONDUIT.

(F) EVERY DEDICATED RUN SHALL HAVE A SPARE RUN. ALL PRIMARY WAYS SHALL BE STUBBED OUT.

### BOX PAD

(G) ALWAYS INSTALL BOX PAD WITH WINDOW SIDE PARALLEL TO STREET OR SIDEWALK.

H. ESTABLISH BOX PAD LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING BOX REQUIRES APPROVAL FROM PROJECT MANAGEMENT. WHEN INSTALLING ADJACENT TO NEW OR EXISTING HANDHOLES ALLOW 17 FEET MINIMUM FROM CLOSEST EDGE OF HANDHOLE TO CENTERLINE OF BOX PAD.

J. MARK OUT DIMENSIONS FOR EXCAVATION WIDTH AND LENGTH PER FIGURE 4. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW AN EXTRA 12 INCHES FOR SETTING BOX PAD.

K. ADD 4 INCHES OF GRAVEL TO BOTTOM OF EXCAVATION AND THEN COMPACT THIS MATERIAL BY HAND OR MACHINE.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | DRAWING UPDATE | EDM | EJA | JES | KRG | 07/14/2022 |
| A | REVISION | - | - | - | - | 12/08/2005 | D | DRAWING UPDATE | EDM | EJA | GLW | CZH | 07/29/2021 |

## INSTALLATION (CONT'D):

**BOX PAD**

L. PLACE BOX PAD IN EXCAVATION WITH WINDOW SIDE OF BOX PAD PARALLEL TO AND AS CLOSE AS POSSIBLE TO BACK EDGE OF SIDEWALK.

M. LEVEL BOX PAD.

N. SET TOP SURFACE OF BOX PAD 4 INCHES ABOVE FINAL GRADE. MAY BE SET AT 6 INCHES FOR MINOR GRADE ADJUSTMENTS TO BACK OR SIDES OF PAD.

(O) BACKFILL OUTSIDE WITH ONE SLACK SLURRY. STOP SLURRY 6 INCHES FROM FINISH GRADE; CONTINUE TO BACKFILL WITH NATIVE SOIL TO FINISH GRADE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | MANUFACTURER PART NUMBER | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | PAD, BOX, FIBERGLASS | SG845630 | 1 | -- | S514026 | 3428BP |
| | PAD, BOX, CONCRETE | -- | | -- | S514060 | 3428CB |
| 2 | GRAVEL, 3/8" - 3/4" | -- | AS REQ'D | -- | S601600 | 3428BP |
| 3 | SLURRY, 1 SLACK | -- | AS REQ'D | -- | S656400 | |
| 4 | EXCAVATION, BOX PAD (II) | -- | 1 | -- | -- | X3428 |

## NOTES:

(I) IDENTIFIES CONDUIT LOCATION FOR SWITCH WAY POSITION.

(II) THIS ITEM IS NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3211 FOR INSTALLATION OF IDENTIFICATION TAG.

b. SEE UG3366 FOR SLURRY BACKFILL.

c. SEE UG3480, UG3481, UG3482 AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3486 AND UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

(e) SEE UG4510 FOR TRENCH GROUND WIRE.

f. SEE UG3550, UG3551, UG3552, UG3553, UG3554, AND UG3555 FOR SWITCH INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | DRAWING UPDATE | EDM | EJA | JES | KRG | 07/14/2022 |
| A | REVISION | - | - | - | - | 12/08/2005 | D | DRAWING UPDATE | EDM | EJA | GLW | CZH | 07/29/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 4-WAY PAD MOUNTED SWITCH

UG3428.4

**SCOPE:** THIS STANDARD SHOWS THE BOX PAD TRAYER 5-WAY SWITCH.





**FIGURE 1**
FIBERGLASS PAD
ISOMETRIC VIEW





**FIGURE 2**
CONCRETE PAD
ISOMETRIC VIEW





**FIGURE 3**
FIBERGLASS/CONCRETE PAD F
INTERIOR LAYOUT

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JJ | 12/8/2005 | D | DRAWING UPDATE | ARC | ADW | GLW | KRG | 03/10/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

BOX PAD FOR 5-WAY TRAYER PAD MOUNTED SWITCH

UG3429.1





**FIGURE 3**
FIBERGLASS/CONCRETE PAD
INTERIOR LAYOUT
VIEW A-A





**FIGURE 4**
EXCAVATION DIMENSIONS (H)
SEE TABLE 1

**TABLE 1**

| BOX PAD DIMENSIONS | | | | | |
|---|---|---|---|---|---|
| BOX PAD MATERIAL | Z (IN) | Y (IN) | BOX PAD BASE | | EXCAVATION DIMENSIONS (IN) |
| | | | LENGTH (IN) | WIDTH (IN) | |
| FIBERGLASS | 104 | 56 | 136 | 86 | 148 X 98 |
| CONCRETE | 105 | 57 | 105 | 57 | 117 X 69 |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JJ | 12/8/2005 | D | DRAWING UPDATE | ARC | ADW | GLW | KRG | 03/10/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

BOX PAD FOR 5-WAY TRAYER PAD MOUNTED SWITCH



UG3429.2

TABLE OF CONTENTS

## INSTALLATION:

### CONDUIT

(A) INSTALL CONDUITS AND TERMINATE THEM NOT LESS THAN 3 INCHES ABOVE GRAVEL BASE.

(B) DO NOT CUT 90-DEGREE ELBOWS ON CURVE.

(C) SCADA ANTENNA CONDUIT TO BE LOCATED ON LEFT SIDE OF WINDOW. STUB ONE 3-INCH CONDUIT OUT FOUR FEET.

D. INSTALL ONE CONDUIT PER SWITCH POSITION.

(E) COMPLETELY SLURRY ENCASE ALL 5-INCH 90-DEGREE BENDS TO WITHIN 7 INCHES OF FINISH CUT OF CONDUIT.

### BOX PAD

(F) ALWAYS INSTALL BOX PAD WITH WINDOW SIDE PARALLEL TO STREET OR SIDEWALK.

G. ESTABLISH BOX PAD LOCATION PAYING PARTICULAR ATTENTION TO FOREIGN UTILITY PLACEMENTS. RELOCATING BOX REQUIRES APPROVAL FROM PROJECT MANAGEMENT. WHEN INSTALLING ADJACENT TO NEW OR EXISTING HANDHOLES ALLOW 17 FEET MINIMUM FROM CLOSEST EDGE OF HANDHOLE TO CENTERLINE OF BOX PAD.

(H) MARK OUT DIMENSIONS FOR EXCAVATION WIDTH AND LENGTH. THE WIDTH AND LENGTH DIMENSIONS GIVEN ALLOW AN EXTRA 12 INCHES FOR SETTING BOX PAD. SEE TABLE 1.

J. ADD 4 INCHES OF GRAVEL TO BOTTOM OF EXCAVATION. COMPACT THIS MATERIAL BY HAND OR MACHINE.

K. PLACE BOX PAD IN EXCAVATION WITH WINDOW SIDE OF BOX PAD PARALLEL AND AS CLOSE AS POSSIBLE TO BACK EDGE OF SIDEWALK.

L. LEVEL BOX PAD.

M. SET TOP SURFACE OF BOX PAD 4 INCHES ABOVE FINAL GRADE. MAY BE SET AT 6 INCHES FOR MINOR GRADE ADJUSTMENTS TO BACK OR SIDES OF PAD.

(N) BACKFILL OUTSIDE WITH ONE SLACK SLURRY. STOP SLURRY 6 INCHES FROM FINISH GRADE; CONTINUE TO BACKFILL WITH NATIVE SOIL TO FINISH GRADE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | MANUFACTURER | MANUFACTURER PART NUMBER | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| 1 | PAD, BOX, CONCRETE | JENSEN PRECAST | 200050852 | 4,854 | 1 | -- | S514062 | BP3429 |
| | PAD, BOX, FIBERGLASS | PROGLASS, INC | SG1045630 | -- | 1 | -- | S514036 | 3429BP |
| 2 | GRAVEL, 3/8" - 3/4" | -- | -- | -- | AS REQ'D | -- | S601600 | |
| 3 | SLURRY, 1 SLACK | -- | -- | -- | AS REQ'D | -- | S656400 | |
| 4 | EXCAVATION, BOX PAD (II) | -- | -- | -- | 1 | -- | -- | X3429 |

## NOTES:

(I) IDENTIFIES CONDUIT LOCATION FOR SWITCH WAY POSITION.

(II) THIS ITEM IS NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3211.3 FOR INSTALLATION OF IDENTIFICATION TAG.

b. SEE UG3365 FOR SLURRY BACKFILL.

c. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

(e) SEE UG4510 FOR TRENCH GROUND WIRE.

f. SEE UG3550 FOR SWITCH INSTALLATION.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JJ | 12/8/2005 | D | DRAWING UPDATE | ARC | ADW | GLW | KRG | 03/10/2023 |

**SCOPE:** THIS STANDARD IS FOR 3443A, 3443B, AND 3443C SWITCH PADS.

**ATTENTION:**

* PADS MAY ALSO BE USED FOR PAD MOUNTED TRANSFORMERS.





**FIGURE 1**
3443A





**FIGURE 2**
3443B





**FIGURE 3**
3443C

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ADW | GLW | CZH | 07/29/2021 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| | Indicates Latest Revision | Completely Revised | X New Page | Information Removed |



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SWITCH PADS
3443A, 3443B AND 3443C

UG3443.1

## INSTALLATION:

A. USE ALL FOUR LIFTING EYES WHEN MOVING PAD.

## BILL OF MATERIALS:

| ITEM | | DESCRIPTION | LID OPENING (IN) | CABLE OPENING (IN) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| 1 | A | PAD, SWITCH, 104 1/2" X 115 1/2" | 30 X 102 | 18 X 70 | AS REQ'D | SECTION 3400 | S514052 | 3443-A |
| | B | PAD, SWITCH, 104 1/2" X 115 1/2" | 30 X 102 | 18 X 60 | | | S514054 | 3443-B |
| | C | PAD, SWITCH, 104 1/2" X 115 1/2" | 30 X 102 | 18 X 95 1/2 | | | S514056 | 3443-C |

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ADW | GLW | CZH | 07/29/2021 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE DIMENSIONAL CRITERIA FOR INSTALLATION OF PAD MOUNTED TRANSFORMER SOUND ENCLOSURES. ENCLOSURES ARE TO BE USED WHEN TRANSFORMERS NOISE IS TO BE REDUCED.

## ATTENTION:

* THIS IS AN ON GRADE FACILITY ONLY.





**FIGURE 1** (I)
PLAN VIEW





**FIGURE 1** (I)
FRONT ELEVATION

## INSTALLATION:

A. CUSTOMER SHALL INSTALL, OWN, AND MAINTAIN TRANSFORMER ENCLOSURE.

B. ENCLOSURE WALLS SHALL CONSIST OF EITHER REINFORCED CONCRETE, NOT LESS THAN 6 INCHES THICK, OR REINFORCED CONCRETE BLOCK, NOT LESS THAN 8 INCHES THICK.

C. THE ENCLOSURE MUST BE DESIGNED TO MEET BUILDING CODE REQUIREMENTS. DESIGN CALCULATIONS AND DRAWINGS ARE TO BE STAMPED AND SIGNED BY A CIVIL OR STRUCTURAL ENGINEER REGISTERED IN THE STATE OF CALIFORNIA.

D. INSIDE DIMENSIONS OF ENCLOSURE TO BE BASED ON TRANSFORMER PAD SELECTION AS DESIGNATED BY SDG&E PLANNER/DESIGNER.

**TABLE 1**

| MINIMUM REQUIREMENTS FOR DEADFRONT TRANSFORMER INSTALLATIONS THROUGH 1,000KVA (E) | | | | |
|---|---|---|---|---|
| **PAD (UGS REF.)** | **Z (IN)** | **Y (IN)** | **X (IN) (J)** | **W (IN)** |
| 3421 | 94 | 72 | 90 | 52 |
| 3425 | 126 | 83 | 101 | 89 |
| 3426 | 126 | 99 | 117 | 98 |
| 3427 | 146 | 116 | 134 | 114 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(E) HEIGHT REQUIREMENTS MAY INCREASE FOR LARGER TRANSFORMER INSTALLATIONS. FUTURE LOAD ADDITIONS SHOULD BE CONSIDERED.

F. ENCLOSURE COVER TO BE PITCHED (2%) TO PROMOTE DRAINAGE TO SIDE OR REAR OF ENCLOSURE.

(G) ENCLOSURE COVER TO BE CONSTRUCTED OF STEEL OR STEEL REINFORCED CONCRETE. SOLID COVER TO BE REMOVABLE AND FITTED WITH FOUR (4) REMOVABLE LIFTING EYES. COVER WEIGHT SHALL BE STENCILED ON UNDERSIDE OF COVER.

H. ENCLOSURE COVER TO BE SECURED TO WALL STRUCTURE WITH PINS OR BOLTS TO PREVENT LATERAL MOVEMENT.

(J) WHEN OPTIONAL ENCLOSURE GATE IS PROVIDED, USE LENGTH X SHOWN ABOVE. GATE CONSTRUCTION TO PROVIDE FULL VENTILATION. GATE MUST BE A MINIMUM OF 18 INCHES IN FRONT OF TRANSFORMER PAD. GATE TO BE LATCHED WITH HASP FOR SDG&E PADLOCK.

K. MINIMUM CRANE OPERATING HEADROOM CLEARANCE IS 20 FEET ABOVE PAD. UTILITY TRUCK ACCESS TO BE WITHIN 10 FEET OF ENCLOSURE.

(L) 8" X 16" VENT OPENINGS ARE REQUIRED IN WALL, (8 INCHES FROM BASE AND 8 INCHES FROM EACH REAR CORNER). DO NOT VENT INTO BUILDINGS.

M. A MINIMUM OF 3 1/2-INCH THICK CONCRETE IS REQUIRED BETWEEN WALL AND PAD. SLOPE CONCRETE SLIGHTLY TOWARD THE FRONT IN ALL INSTALLATIONS.

N. OPEN SIDE OF ENCLOSURE REQUIRES 8'-0" CLEAR WORK AREA IN FRONT OF PAD. AVOID FACING OPEN SIDE TO ADJACENT BUILDINGS OR INACCESSIBLE AREAS.

**BILL OF MATERIALS:** NONE

## NOTES:

(I) GATE HINGE(S) SHALL NOT BE WELDED.

## REFERENCE:

a. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS FOR PAD MOUNTED AND SUBSURFACE EQUIPMENT.

b. SEE UG3484 TO SET TRANSFORMER PADS FOR NOISE CONTROL.

c. SEE DM5612 FOR TRANSFORMER NOISE CRITERIA.

d. PAD LOCATED OR POSITIONED IN RELATION TO ADJACENT BUILDINGS SHALL BE PER UG3483.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRANSFORMER SOUND ENCLOSURE



UG3478.2

**SCOPE:** THIS STANDARD IS FOR THE INSTALLATION OF SAFETY WARNING POSTS (COMPOSITE BOLLARDS) USED AS A WARNING BARRIER FOR EQUIPMENT ON PADS AND HANDHOLES.

**ATTENTION:**

* WARNING POSTS OFFER NO PHYSICAL PROTECTION. THEY ACT AS A SAFETY WARNING BARRIER ONLY AND MAY BE REPLACED WHEN SHEARED OFF OR DAMAGED.





**FIGURE 1**
REMOVABLE COMPOSITE BOLLARD





**FIGURE 2**
REMOVABLE BOLLARD COVER





**FIGURE 3**
REMOVABLE COMPOSITE BOLLARDS
AT HANDHOLE





**FIGURE 4**
REMOVABLE COMPOSITE BOLLARDS
AT EQUIPMENT PAD

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3481 | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/2000 | D | DRAWING UPDATE | EDM | ADW | GLW | FRC | 03/01/2022 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SAFETY WARNING POSTS

UG3479.1

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. SAFETY POSTS ARE TO BE USED NEAR COUNTY-MAINTAINED ROADS THAT DO NOT HAVE CONCRETE CURB BETWEEN ROADWAY AND SHOULDER.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3481 | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/2000 | D | DRAWING UPDATE | EDM | ADW | GLW | FRC | 03/01/2022 |

**SCOPE:** THIS STANDARD ILLUSTRATES BARRIER POST USAGE WHEN NEEDED TO PROTECT SDG&E FACILITIES FROM PASSENGER VEHICLES, TRUCKS, FORK LIFTS, TRAILERS OR OTHER HEAVY MOBILE ITEMS (E.G. DUMPSTERS).

**ATTENTION:**

* CALL "UNDERGROUND SERVICE ALERT" (U.S.A.) TWO WORKING DAYS BEFORE YOU DIG TO VERIFY THE LOCATION OF UNDERGROUND UTILITIES. CALL TOLL FREE: 1-800-422-4133 OR 811







**FIGURE 1**




**DETAIL 1**
NON-REMOVABLE BARRIER POST




**DETAIL 2** (D)
REMOVABLE BARRIER POST

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3481 | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/2000 | D | DRAWING UPDATE | EDM | ADW | GLW | FRC | 03/01/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## INSTALLATION:

(A) USE 4-INCH STEEL PIPE, (NOT GALVANIZED) WITH A MINIMUM WALL THICKNESS OF 3/16-INCH. THE PIPE SHALL BE PRIMED AND PAINTED WHITE.

(B) AN 8-FOOT MINIMUM CLEARANCE FROM ANY ABOVE GROUND OBJECT IS REQUIRED IN FRONT OF PAD WHERE EQUIPMENT DOOR OPENS FOR HOT STICK OPERATION.

(C) WHEN USING THE LARGER 3427 TRANSFORMER PAD OR PAD MOUNTED SWITCH PAD, ADDITIONAL BARRIERS ARE REQUIRED AS SHOWN.

(D) ALL BARRIERS REQUIRED IN FRONT OF EQUIPMENT DOORS MUST BE REMOVABLE.

(E) THE CONCRETE ENCASEMENT SHALL BE A MINIMUM OF 6 INCHES THICK IN STABLE SOIL AND 12 INCHES THICK IN SANDY OR UNSTABLE SOIL.

(F) MAY BE REDUCED TO 24 INCHES IN TIGHT AREAS.

(G) INCREASE DISTANCE AS REQUIRED FOR A THREE-PHASE TRANSFORMER WITH HANDHOLE.

(H) DRILL FOUR 1/4-INCH DIAMETER HOLES AS SHOWN TO PREVENT SUCTION.

(J) A WELDED CAP OR BLANK MAY BE USED IN LIEU OF CONCRETE CAP.

(K) DRILL AN 11/16-INCH HOLE COMPLETELY THROUGH REMOVABLE POST. THIS WILL ALLOW FOR A 5/8-INCH BOLT WHICH MAY BE USED FOR REMOVAL OF THE POST.

## BILL OF MATERIALS: NONE

## NOTES:

I. CAUTION MUST BE TAKEN WHEN INSTALLING BARRIER POSTS SO THERE IS NO CONTACT WITH UNDERGROUND UTILITIES.

II. DO NOT INSTALL TRAFFIC POSTS IF ABOVE GROUND OBJECTS EXIST WHICH PROTECT PAD MOUNTED EQUIPMENT FROM VEHICULAR TRAFFIC.

## REFERENCE:

a. SEE UG3480, UG3481, UG3482 & UG3483 FOR SPECIFIC OPERATING CLEARANCE REQUIREMENTS FOR PAD MOUNTED EQUIPMENT.

b. SEE DM5240.2-.3 FOR CRITERIA TO LOCATE PAD MOUNTED EQUIPMENT IN PUBLIC RIGHT-OF-WAY.

c. SEE DM5240.4 TO DETERMINE WHEN TO INSTALL BARRIER POSTS TO PROTECT PAD MOUNTED EQUIPMENT ALONG SIDE ROADWAYS.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3481 | EDM | JIK | - | - | 11/05/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/2000 | D | DRAWING UPDATE | EDM | ADW | GLW | FRC | 03/01/2022 |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |
| SHEET 4 OF 4 | SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS | | | UG3479.4 |
| | EQUIPMENT BARRIER PROTECTION AND CLEARANCE | | | |

**SCOPE:** THIS STANDARD SHOWS THE MINIMUM RETAINING WALL AND OPERATING CLEARANCES REQUIRED FOR PADS AND SUBSURFACE STRUCTURES.





**FIGURE 1**

**TABLE 1**

| PAD OR SUBSTRUCTURE OPERATING CLEARANCES (VI) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| PAD USAGE | | STANDARD PAGE | PAD OR STRUCTURE DIMENSIONS AND MINIMUM OPERATING WIDTH | | MINIMUM CLEARANCE DIMENSIONS (c) | | | |
| | | | Z | Y | X | W | V | U |
| RTU PAD | | 3409 | 3'-10" (1168) | 4'-0" (1219) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| THREE-PHASE CABLE TERMINATING CABINET 600A TO 200A | | 3410 | 7'-3" (2210) | 4'-9" (1461) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| THREE-PHASE CAPACITOR | | 3414 | 5'-4" (1626) | 5'-0" (1524) | 8'-0" (2438) | 8'-0" (2438) | 18" (457) | 18" (457) |
| THREE-PHASE SERVICE RESTORER | PREFERRED | 3415 | 5" (1524) | 4'-9" (1461) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| | ALTERNATIVE | | 5'-4" (1626) | 5'-0" (1524) | 4'-0" (1219) | 8'-0" (2438) | 18" (457) | 18" (457) |
| THREE-PHASE CABLE TERMINATING CABINET (200A) | | 3416 | 6'-8" (2210) | 2'-6" (762) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| THREE-PHASE CABLE TERMINATING CABINET (600A) | | 3417 | 4'-0" (1219) | 3'-10" (1168) | 8'-0" (2438) | 8'-0" (2438) | 18" (457) | 18" (457) |
| THREE-PHASE PME 3 SWITCH (600A) | | 3418 | 5'-10" (1788) | 3'-8" (1118) | 8'-0" (2438) | 8'-0" (2438) | 18" (457) | 4'-4" (1321) |
| 3-WAY VISTA BOX PAD | | 3419 | 5'-4" | 5'-1" | 3'-0" | 8'-0" | 18" | 18" |
| SINGLE-PHASE CABLE TERMINATOR (FUTURE TRANSFORMER INSTALLATIONS) | | 3421 | 3'-10" (1168) | 4'-0" (1219) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| THREE-PHASE FUSE CABINET (VERTICAL & HORIZONTAL MOUNT) | | 3421 | 4'-0" (1219) | 3'-10" (1168) | 8'-0" (457) | 8'-0" (457) | 18" (457) | 18" (2438) |
| SINGLE-PHASE FUSED SECTIONALIZING CABINET | | 3421 | 4'-0" (1219) | 3'-10" (1168) | 8'-0" (2438) | 8'-0" (2438) | 18" (457) | 18" (457) |
| SINGLE-PHASE CABLE TERMINATOR | | 3421 | 3'-10" (1168) | 4'-0" (1219) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| SINGLE-PHASE TRANSFORMER (25-167KVA) | | 3421 | 3'-10" (1168) | 4'-0" (1219) | 18" (457) | 18" (457) | 18" (457) | 8'-0" (2438) |
| PAD MOUNTED MVI FUSE CABINET | | 3421 | 3'-10" (1168) | 4'-0" (1219) | 48" (1219) | 48" (1219) | 18" (457) | 8'-0" (2438) |
| THREE-PHASE PME 9 SWITCH (600A) | | 3423 | 6'-1" (1854) | 6'-6" (1981) | 8'-0" (2438) | 8'-0" (2438) | 4'-4" (457) | 4'-4" (1321) |
| THREE-PHASE PME 10 SWITCH (600A) | | 3423 | 6'-1" (1854) | 6'-6" (1981) | 8'-0" (2438) | 8'-0" (2438) | 4'-4" (457) | 4'-4" (1321) |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | MOVED FROM 3483 | EDM | JIK | - | - | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | CZH | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

## TABLE 1 (CONT'D)

| PAD OR SUBSTRUCTURE OPERATING CLEARANCES (VI) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| PAD USAGE | STANDARD PAGE | PAD OR STRUCTURE DIMENSIONS AND MINIMUM OPERATING WIDTH | | MINIMUM CLEARANCE DIMENSIONS (c) | | | | |
| | | Z | Y | X | W | V | U | |
| THREE-PHASE PME 11 SWITCH (600A) | 3423 | 6'-1" (1854) | 6'-6" (1981) | 8'-0" (2438) | 8'-0" (2438) | 4'-4" (457) | 4'-4" (1321) | |
| THREE-PHASE AUTOMATIC TRANSFER SWITCH (600A S & C) | 3423 | 6'-1" (1854) | 6'-6" (1981) | 8'-0" (2438) | 8'-0" (2438) | 18" (457) | 6" (1829) | |
| THREE-PHASE PRIMARY METER CABINET | 3425 | 6'-6" (1981) | 4'-11" (1499) | 18" (457) | 18" (457) | 5'-0" (1524) | 8'-0" (2438) | |
| THREE-PHASE TRANSFORMER | 3425 | 6'-6" (1981) | 4'-11" (1499) | 18" (457) | 18" (457) | 2'-0" (610) | 8'-0" (2438) | |
| THREE-PHASE TRANSFORMER | 3426 | 6'-6" (1981) | 6'-3" (1905) | 18" (457) | 18" (457) | 2'-0" (610) | 8'-0" (2438) | |
| THREE-PHASE LIVEFRONT TRANSFORMER | 3427 | 8'-2" (2489) | 7'-8" (2337) | 18" (457) | 18" (457) | 2'-0" (610) | 8'-0" (2438) | |
| THREE-PHASE TRAYER SWITCH 4-WAY | 3428 | 7'-0" (2134) | 4'-8" (1422) | 4'-4" (1321) | 18" (457) | 2'-0" (610) | 8'-0" (2438) | |
| THREE-PHASE TRAYER SWITCH 5-WAY | 3429 | 8'-8" (2642) | 4'-8" (1422) | 4'-4" (1321) | 18" (457) | 2'-0" (610) | 8'-0" (2438) | |

## TABLE 2

| CABLE JUNCTION PEDESTAL (VI) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| STRUCTURE USAGE | STANDARD PAGE | PAD OR STRUCTURE DIMENSIONS AND MINIMUM OPERATING WIDTH | | MINIMUM CLEARANCE DIMENSIONS (c) | | | | |
| | | Z | Y | X | W | V | U | |
| PRIMARY | 3523 | 4'-10" (1473) | 2'-6" (762) | 18" (457) (V) | 18" (457) (V) | 18" (457) (V) | 8'-0" (2438) | |

## TABLE 3

| SUBSTRUCTURE CLEARANCES FROM ABOVE GROUND OBJECTS (VI) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| STRUCTURE USAGE | STANDARD PAGE | PAD OR STRUCTURE DIMENSIONS AND MINIMUM OPERATING WIDTH | | MINIMUM CLEARANCE DIMENSIONS (c) | | | | |
| | | Z | Y | X | W | V | U | |
| SECONDARY | 3312 | 1'-10" (559) | 2'-11" (889) | 18" (457) | 18" (457) | 18" (457) | 5'-0" (1524) | |
| SECONDARY/PRIMARY | 3313 | 2'-8" (813) | 3'-8" (1118) | 18" (457) | 18" (457) | 18" (457) | 5'-0" (1524) | |
| SECONDARY/PRIMARY | 3314 | 6'-8" (2032) | 3'-8" (1118) | 5'-0" (1524) | 5'-0" (1524) | 18" (457) | 5'-0" (1524) | |
| SECONDARY/PRIMARY | 3315 | 7'-6" (2286) | 5'-0" (1524) | 5'-0" (1524) | 5'-0" (1524) | 5'-0" (1524) (VII) | 5'-0" (1524) | |
| SECONDARY/PRIMARY | 3316 | 9'-6" (2896) | 6'-0" (1829) | 5'-0" (1524) | 5'-0" (1524) | 5'-0" (1524) (VII) | 5'-0" (1524) | |
| PRIMARY SWITCH ENCLOSURE | 3317 | 10'-0" (3048) | 8'-0" (2438) | 5'-0" (1524) | 5'-0" (1524) | 18" (457) | 18" (457) | |
| NECK SECTION, SECONDARY/PRIMARY (3325, 3326 MANHOLE) | 3332 | 10'-0" (1930) | 8'-0" (1676) | 5'-0" (1524) | 5'-0" (1524) | 18" (457) | 5'-0" (1524) | |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | MOVED FROM 3483 | EDM | JIK | - | - | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | CZH | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

**INSTALLATION:** REFER TO UG3483

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THIS STANDARD DOES NOT APPLY TO EXISTING COMMUNICATION PEDESTALS PROVIDING THEY ARE NO CLOSER THAN 4 INCHES TO THE PAD AND THEY DO NOT OBSTRUCT THE DOORS OR THE 8-FOOT WORK SPACE.

II. THIS PAGE DOES NOT APPLY TO PREFORMED RETAINING WALLS IN UG3484.3.

III. WALL MOUNTED FUSE CABINETS REQUIRE 8-FOOT MINIMUM CLEARANCE IN FRONT OF THE CABINET FOR HOT STICK OPERATION.

IV. THE OPERATING CLEARANCES DESCRIBED IN THIS STANDARD SHALL APPLY TO BUSHES, HEDGES AND OTHER LANDSCAPING MATERIALS. LOW GROUND COVER IS EXCLUDED.

(V) RETAINING WALLS ARE NOT REQUIRED WHEN THE SLOPE REMAINS 6 INCHES BELOW AND PARALLEL TO THE JOINT BETWEEN THE BASE AND COVER OF TERMINATOR. (d)

(VI) THE NUMBERS IN PARENTHESIS IN THE TABLES REPRESENT THE MILLIMETER MEASUREMENT OF THE FEET/INCHES NUMBER ABOVE IT.

(VII) 5-FOOT OPERATING CLEARANCE IS REQUIRED ONLY FOR HOT STICK OPERATION OF LOADBREAK EQUIPMENT (CABLE TAP(S) WITH LOADBREAK ELBOWS LOCATED ON THE STREET SIDE OF HANDHOLE), IF THIS LOADBREAK EQUIPMENT IS NOT PRESENT OR NO FUTURE CABLE TAPS ARE ANTICIPATED IN THIS AREA, MAINTAIN 18-INCH MINIMUM CLEARANCE.

**REFERENCE:**

a. SEE UG3487 FOR RETAINING WALL REQUIREMENTS AND ONE-PHASE TRANSFORMER PAD LOCATIONS SHOWING CATV AND/OR TELCO LOCATIONS.

b. SEE UG3488 FOR CLEARANCES BETWEEN SDG&E FACILITIES AND OTHER ABOVE GROUND OBJECTS.

(c) SEE UG3483.

(d) SEE UG3523.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | MOVED FROM 3483 | EDM | JIK | - | - | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | CZH | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


CLEARANCE REQUIREMENTS FOR PAD MOUNTED AND SUBSURFACE EQUIPMENT FROM ABOVE GROUND OBJECTS

UG3480.3


**SCOPE:** THIS STANDARD SHOWS MINIMUM OPERATING CLEARANCE REQUIREMENTS FOR PAD MOUNTED EQUIPMENT.





EXAMPLE 1




EXAMPLE 2 (I)(VII)





EXAMPLE 3





EXAMPLE 4




EXAMPLE 5




EXAMPLE 6




EXAMPLE 7

**FIGURE 1**
PAD MOUNTED EQUIPMENT HOT STICK OPERATION CLEARANCE EXAMPLES

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | MOVED FROM 3483 | EDM | JIK | - | - | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | CZH | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MINIMUM OPERATING CLEARANCE REQUIREMENTS
FOR PAD MOUNTED EQUIPMENT



UG3481.1

TABLE OF CONTENTS

**INSTALLATIONS:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) X = IN FRONT OF PAD.

II. X = 8-FOOT MIN. FOR HOT STICK OPERATION.

III. Y = SLOPE OF GRADE IN FRONT OF THE PAD NOT TO EXCEED 8-FOOT HORIZONTAL RUN TO 3-FOOT VERTICAL RISE.

IV. Z = 6-FOOT MIN. FLAT GRADE FOR HOT STICK OPERATION.

V. AN EFFORT SHOULD BE MADE TO KEEP THE X MEASUREMENT TO A FLAT GRADE. IF THIS IS NOT POSSIBLE, THE X MEASUREMENT SHALL NOT EXCEED AN 8-FOOT HORIZONTAL RUN TO 3-FOOT VERTICAL RISE.

VI. AN 8-FOOT CLEARANCE IS REQUIRED IN FRONT OF THE PADMOUNT EQUIPMENT FOR HOT STICK OPERATION. SDG&E HANDHOLES AND MANHOLES MAY OCCUPY OR BE INSTALLED WITHIN THE 8-FOOT CLEARANCE. PROVIDE A 5-FOOT CLEARANCE FROM PADS TO 3314 AND LARGER SUBSTRUCTURES.

(VII) THE SLOPE IN FRONT OF THE PAD SHALL NOT EXCEED AN 8-FOOT HORIZONTAL RUN TO 3-FOOT VERTICAL RISE.

**REFERENCE:**

a. SEE UG3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

b. SEE UG3484 FOR INSTALLATION OF PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | MOVED FROM 3483 | EDM | JIK | - | - | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | CZH | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

**SCOPE:** THIS STANDARD SHOWS MINIMUM OPERATING CLEARANCES FOR SUBSURFACE EQUIPMENT.





**FIGURE 1**
SUBSURFACE EQUIPMENT HOT STICK OPERATION CLEARANCE EXAMPLES (I)

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) Z = 5-FOOT MIN. WHEN HOT STICK OPERATION IS REQUIRED, OTHERWISE BASIC CLEARANCES APPLY. (b)

II. IF THE SUBSTRUCTURE IS NOT TO BE LOCATED IN THE STREET, AN EFFORT SHOULD BE MADE TO KEEP THE Z MEASUREMENT TO A FLAT GRADE. IF THIS IS NOT POSSIBLE, THE Z MEASUREMENT SHALL NOT EXCEED AN 8-FOOT HORIZONTAL RUN TO 3-FOOT VERTICAL RISE.

III. A 5-FOOT CLEARANCE IS REQUIRED IN FRONT OF THE SUBSTRUCTURE FOR HOT STICK OPERATION. SDG&E HANDHOLES AND MANHOLES MAY OCCUPY OR BE INSTALLED WITHIN THE 8-FOOT CLEARANCE REQUIRED IN FRONT OF SDG&E "PAD MOUNTED" EQUIPMENT. PROVIDE A 5-FOOT CLEARANCE FROM PAD TO 3314 AND LARGER SUBSTRUCTURES.

**REFERENCE:**

a. SEE UG3485 FOR INSTALLATIONS OF SUBSTRUCTURES ON SLOPING GRADES.

(b) SEE "MINIMUM OPERATING CLEARANCE REQUIREMENTS" ON UG3480, UG3481 AND UG3483.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | MOVED FROM 3483 | EDM | JIK | - | - | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | CZH | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MINIMUM OPERATING CLEARANCE REQUIREMENTS
FOR SUBSURFACE EQUIPMENT



UG3482.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS MINIMUM OPERATING CLEARANCES FOR PAD MOUNTED AND SUBSURFACE EQUIPMENT.





**FIGURE 1**

## INSTALLATION:

A. CLEARANCES SHALL BE MEASURED FROM ALL ABOVE-GROUND OBJECTS. PADS WHERE DIMENSION "U" IS LESS THAN 5 FEET FROM EDGE OF PAVEMENT OR FRONT OF CURB, AND NO ABOVE-GROUND OBJECTS TO PROTECT EQUIPMENT EXIST, SHALL HAVE BARRIER PROTECTION. (b) (h)

B. DIMENSION "V" SHALL BE THE SAME AS DIMENSION "U" WHEN CABLE TAPS ARE ON BOTH SIDES OF THE HANDHOLE. (h)

C. CLEARANCES ARE REQUIRED AT THE SIDE(S) OR END(S) OF SUBSTRUCTURES, PAD MOUNTED EQUIPMENT, ETC., WHERE HOT STICK OPERATION IS REQUIRED. SDG&E HANDHOLES AND MANHOLES MAY OCCUPY OR BE INSTALLED WITHIN THE REQUIRED CLEARANCES. PROVIDE A 5-FOOT CLEARANCE FROM PADS TO 3314 AND LARGER SUBSTRUCTURES.

D. FOR EQUIPMENT CONTAINING OIL & CAPACITORS NEXT TO COMBUSTIBLE BUILDINGS, THE "X", "W", "V" DIMENSIONS SHALL NOT BE LESS THAN 3 FEET FROM BUILDING SURFACES. FOR ALL TRANSFORMERS, DIMENSION "V" MUST BE INCREASED TO 3'-6" FOR COMBUSTIBLE BUILDING SURFACES OR 2'-6" FOR NONCOMBUSTIBLE BUILDING SURFACES ALLOWING ROOM FOR TRANSFORMER COOLING FINS IN EACH INSTALLATION. "X" & "W" DIMENSIONS MAY BE REDUCED TO 2 FEET IF BUILDING SURFACES ARE NONCOMBUSTIBLE AND NOISE CLEARANCE REQUIREMENTS ARE MET FOR TRANSFORMERS. (h) (i)

(E) **"NONCOMBUSTIBLE"** BUILDING SURFACES OR MATERIALS APPROVED BY THE UNIFORM BUILDING CODE AS HAVING A MINIMUM FIRE RATING OF ONE HOUR INCLUDE BUT ARE NOT LIMITED TO:

1. STEEL STUDDED DRYWALL, STEEL STUDDED STUCCO OR OTHER MATERIALS ON STEEL STUDS HAVING MINIMUM FIRE RATING OF ONE HOUR:
2. BRICK, CLAY, TILE, CONCRETE, IRON, STEEL AND STONE.

F. **"COMBUSTIBLE"** BUILDING SURFACES OR MATERIALS INCLUDE BUT ARE NOT LIMITED TO WOOD STUDDED STUCCO AND WOOD STUDDED DRYWALL.

G. IF ROOF OVERHANG IS 20 FEET OR LESS ABOVE TOP OF ANY PAD MOUNTED EQUIPMENT, THE MINIMUM HORIZONTAL CLEARANCE FROM END OF OVERHANG TO THE NEAREST EDGE OF THE PAD SHALL NOT BE LESS THAN 3'-6" OR 2'-6" IF THE OVERHANG IS NONCOMBUSTIBLE AND THE CLEARANCE DOES NOT CREATE A NOISE PROBLEM. IF THE ROOF OVERHANG IS MORE THAN 20 FEET, THE PAD MOUNTED EQUIPMENT MAY BE PLACED UNDER THE OVERHANG. IF IN DOUBT THAT A NOISE PROBLEM MAY DEVELOP, CONTACT DESIGN PLANNING.

H. PADS ARE PERMITTED IN THE SIDEWALKS PROVIDED THE WALK IS WIDER THAN 4 FEET NOT INCLUDING THE CURB. A 4-FOOT USEABLE WALKWAY (NOT INCLUDING THE CURB) MUST BE PROVIDED FOR WHEELCHAIR ACCESS. DO NOT INSTALL PADS IN TRAILS SUCH AS BIKE, JOGGING, WALKING, EQUESTRIAN, ETC.

J. ANY UNDERGROUND FACILITY, SUBSURFACE OR PAD MOUNTED WITH LOADBREAK CAPABILITY, E.G., CABLE TAPS IN HANDHOLES, PAD MOUNTED TRANSFORMERS AND FUSED SWITCHING CABINET, SHALL MAINTAIN A 25-FOOT RADIAL CLEARANCE FROM ANY TANK, VENT OF FILL-TUBE THAT CONTAINS FLAMMABLE LIQUIDS, GASES, VAPORS OR MIXTURES. DIESEL FUEL IS COMBUSTIBLE BUT NOT FLAMMABLE, THEREFORE DIESEL TANKS ARE ALLOWED WITHIN THE 25-FOOT RADIUS. (g)

**BILL OF MATERIALS:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | FORMATTING | EDM | EJA | GLW | CZH | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | MF/JJ | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MINIMUM OPERATING CLEARANCE REQUIREMENTS FOR PAD MOUNTED AND SUBSURFACE EQUIPMENT



UG3483.1

TABLE OF CONTENTS

**NOTES:** NONE

**REFERENCE:**

a. SEE UG3478 FOR TRANSFORMER SOUND ENCLOSURE.
b. SEE UG3479 FOR EQUIPMENT BARRIER PROTECTION AND CLEARANCE.
c. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT AND FOR SETTING TRANSFORMER PADS FOR NOISE CONTROL.
d. SEE UG3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.
e. SEE UG3489 FOR RETAINING WALLS.
f. SEE DM5612 FOR TRANSFORMER NOISE CLEARANCE REQUIREMENTS.
g. SEE SG316 FOR INSTALLING UNDERGROUND SERVICE LATERAL TO GASOLINE DISPENSING AND SERVICE STATIONS.
h. SEE UG3480 FOR RELATED FIGURE.
i. SEE G.O. 128 RULE 34.3 D.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION REASON | - | - | - | MF/JJ | 9/25/2006 | F | FORMATTING | EDM | EJA | GLW | CZH | 11/5/2020 |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1996 | E | EDITORIAL CHANGES | - | AW | JS | MF/JJ | 11/12/2019 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | D | REVISION REASON | - | - | - | TR/DW | 2/27/2013 |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF PADS USED FOR MOUNTING PAD MOUNTED EQUIPMENT.





**FIGURE 1**
PAD SET ON FLAT GRADE





**FIGURE 2**
PAD SET ON SLOPING GRADE
BEHIND SIDEWALKS

## INSTALLATION:

(A) SET PADS TO FINAL GRADE. SET 3416 PAD 6 INCHES ABOVE AND 3 INCHES BELOW FINAL GRADE.

(B) PADS ARE PERMITTED IN SIDEWALK PROVIDED THE WALK IS WIDER THAN 4 FEET NOT INCLUDING THE CURB. IN SIDEWALK OR PAVED AREAS, SET PADS 2 INCHES ABOVE PAVEMENT. SET 3440 PAD 3 INCHES ABOVE PAVEMENT. IN AREAS WHERE THERE IS LIMITED SPACE AND 4 FEET CANNOT BE OBTAINED, PAD MAY BE SET FLUSH WITH THE WALK IN ORDER TO OBTAIN THE REQUIRED 4-FOOT DISTANCE. THIS IS PROVIDED IT IS APPROVED BY GOVERNMENTAL (PERMITTING AGENCIES) AND IT IS NOT A LOW AREA WHERE WATER MAY DRAIN OR COLLECT.

(C) FOR PADS ON SLOPING GRADES BEHIND SIDEWALKS IN PAVED OR UNPAVED AREAS, SET UP TO HALF OF THE PAD BELOW GRADE ON THE HIGH SIDE OF THE SLOPE (DO NOT EXCEED HALF THE PAD). ON THE LOW SIDE OF THE SLOPE SET THE PAD TO THE FINAL GRADE (SEE FIGURE 2).

(D) SET TRANSFORMER PADS FOR NOISE CONTROL AS FOLLOWS.

1. FOR TRANSFORMER PADS WITHIN A PAVED AREA, LEAVE 6 INCHES OF EARTH BENEATH PAD AND INSTALL FELT EXPANSION JOINT AROUND SIDES OF PAD, OR INSTALL FELT EXPANSION JOINT BENEATH AND AROUND SIDES OF PAD.
2. TRANSFORMER PADS LOCATED OVER AN UNDERGROUND PARKING AREA OF A BUILDING MUST BE PLACED BETWEEN WALLS AND NOT OVER BEARING WALLS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD (h) | 1 | -- | REFER TO WORK ORDER | -- |

**NOTES:** NONE

## REFERENCE:

a. SEE UG3211.3 FOR EQUIPMENT PAD IDENTIFICATION.

b. SEE UG3478 FOR TRANSFORMER SOUND ENCLOSURE.

c. SEE UG3479 FOR EQUIPMENT BARRIER PROTECTION.

d. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

(e) SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE (CONT'D):**

(f) SEE UG3489 FOR RETAINING WALL REQUIREMENTS.

g. SEE UG4510 FOR PREFERRED AND ALTERNATE TRENCH GROUND WIRE INSTALLATION.

(h) SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

i. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIRED TO SET EQUIPMENT PAD ON SLOPING GRADES.





**FIGURE 1**





**FIGURE 2**





**FIGURE 3**





**FIGURE 4**





**FIGURE 5**





**FIGURE 6**





**FIGURE 7**





**FIGURE 8**

## INSTALLATION:

A. ALIGN PAD TO FINAL GRADE.

(B) INSTALL CONCRETE BLOCK AS REQUIRED.

(C) FOR 600A THREE-PHASE PAD MOUNTED SWITCH, SLURRY BACKFILL (1 SACK SAND SLURRY) 22 INCHES DEEP AROUND THE 3423 PAD BOX.

(D) INSTALL PREFORMED PLASTIC RETAINING WALLS AS REQUIRED.

(E) SLOPE OF GRADE IN FRONT OF THE PAD NOT TO EXCEED 8-FOOT HORIZONTAL RUN TO 3-FOOT VERTICAL RISE.

(F) BUTT THE FRONT OF THE PAD AGAINST THE WALL.

**BILL OF MATERIALS:** NONE

## NOTES:

I. AN 8-FOOT CLEARANCE IS REQUIRED IN FRONT OF THE PADMOUNT EQUIPMENT FOR HOT STICK OPERATION. COMPANY HANDHOLES AND MANHOLES MAY OCCUPY OR BE INSTALLED WITHIN THE 8-FOOT CLEARANCE. PROVIDE A 5-FOOT CLEARANCE FROM PADS TO 3314 AND LARGER SUBSTRUCTURES.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD INSTALLATION FOR PAD MOUNTED EQUIPMENT
SLOPING GRADES



UG3484.3

TABLE OF CONTENTS

**REFERENCE:**

a. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

b. SEE UG3484 FOR INSTALLATION OF PAD MOUNTED EQUIPMENT.

c. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD INSTALLATION FOR PAD MOUNTED EQUIPMENT
SLOPING GRADES

**SCOPE:** THIS STANDARD SHOWS THE PREFORMED PLASTIC RETAINING WALL USED TO PROTECT PAD MOUNTED EQUIPMENT AGAINST CORROSION FROM SOIL CONTACT ON SLOPE.





**FIGURE 1**
SIDE ELEVATION





**FIGURE 1**
ISOMETRIC VIEW






**FIGURE 2**
TYPICAL INSTALLATION




**DETAIL 1**

**TABLE 1** (II)

| WALL USAGE | | |
|---|---|---|
| **PAD STD** | **PAD USAGE** | **EQUIPMENT STD OR SECTION** |
| 3421 | 1 PHASE TRANSFORMER/UTILITY EQUIPMENT PAD | 3700 |

## INSTALLATION:

A. SET THE PAD. EXCAVATE AROUND THE PAD AREA ALLOWING ROOM FOR THE WALL. EXCAVATION SHALL BE LEVEL ALLOWING AN EXTRA 7 INCHES OUTSIDE THE WALL FOR BACKFILL AND TAMPING.

B. THE BOTTOM PORTION OF THE EXCAVATION SHALL START 2 INCHES BELOW GROUND LEVEL AND CONTINUE INTO THE SLOPING BANK.

(C) SET THE WALL. FILL AND TAMP THE BACKFILL. THE PREFERRED INSTALLATION IS TO BUTT THE 4 1/4-INCH PORTION AGAINST THE SIDEWALK AS SHOWN IN DETAIL A. IF THIS IS NOT POSSIBLE, POUR CONCRETE BETWEEN THE PAD AND SIDEWALK. IN RURAL AREAS WITHOUT SIDEWALKS, CONCRETE IS NOT REQUIRED IN FRONT OF THE PAD AND WALL.

D. CONCRETE OR ASPHALT IS REQUIRED BETWEEN THE WALL AND THE PAD AND SHALL BE A MINIMUM OF 3 1/2 INCHES THICK. SLOPE THE CONCRETE OR ASPHALT SLIGHTLY TOWARD THE FRONT IN ALL INSTALLATIONS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | COLOR | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 1 | WALL, RETAINING, PLASTIC | 90 | GOLDEN BROWN (SANDSTONE) | AS REQ'D | -- | S413496 | RW-PRE |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |



TABLE OF CONTENTS

**NOTES:**

I. WALL SHALL BE USED ON SLOPING GRADES WHERE A RETAINING WALL OF 14 INCHES OR LESS IS REQUIRED. MAXIMUM SLOPE OF RETAINED EARTH: 4 TO 1 (HORIZONTAL RUN TO VERTICAL RISE).

(II) THIS TYPE WALL TO BE USED ONLY IN INSTALLATIONS PER TABLE 1.

**REFERENCE:**

a. SEE UG3484 FOR INSTALLATION OF PAD MOUNTED EQUIPMENT.

b. SEE UG3486 FOR CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

c. SEE UG3489 FOR MASONRY RETAINING WALL.

d. SEE UG4512 FOR EQUIPMENT GROUNDING.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD INSTALLATION FOR PAD MOUNTED EQUIPMENT
FIBERGLASS RETAINING WALLS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND MATERIAL REQUIRED TO SET SUBSTRUCTURES ON SLOPING GRADES.





**FIGURE 1**
SUBSURFACE TRANSFORMER ENCLOSURE
(FIELD MAINTENANCE ONLY)
3399.401 AND 3399.404





**FIGURE 2**
NO CONCRETE FILL REQ'D
HANDHOLES 3312, 3313





**FIGURE 3**
MULTI-SECTION HANDHOLES
3399.101, 3314, 3315, 3316





**FIGURE 4**
MANHOLES - 36" OPENING
(FIELD MAINTENANCE ONLY)
3399.201, 3399.202, 3399.306, 3399.307





**FIGURE 5**
MANHOLES - 48" OPENING
3325, 3326, 3399.203, 3399.205, 3399.305

## INSTALLATION:

A. ALIGN TOP SECTION TO FINAL GRADE. POUR CONCRETE (4-SACK MIX WITH 3/8" PEA GRAVEL OR AS REQUIRED BY CITY OR COUNTY CODES).

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (SUBSTRUCTURE PLACEMENT).

b. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

c. SEE UG3489 FOR RETAINING WALLS WHERE BANKS OR EXCESSIVE SLOPES EXIST.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

SUBSTRUCTURE INSTALLATION ON SLOPING GRADES

UG3485.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS WHEN RETAINING WALLS ARE REQUIRED AND MINIMUM CLEARANCE REQUIREMENTS FROM PAD MOUNTED AND/OR SUBSURFACE EQUIPMENT FROM REVERSE SUBGRADE RETAINING WALLS.





**FIGURE 1**
WHEN RETAINING WALLS ARE REQUIRED (A)





**FIGURE 2**
MINIMUM CLEARANCE REQUIREMENTS FROM PAD MOUNTED AND/OR SUBSURFACE EQUIPMENT TO REVERSE SUBGRADE RETAINING WALLS

## INSTALLATION:

(A) WALLS ARE REQUIRED WHEN SLOPE COMES WITHIN THREE FEET OF A FLAT GRADE ADJACENT TO A PAD OR SUBSTRUCTURE. THE FLAT GRADE IS ESTABLISHED FROM THE TOP OF A PAD. SEE FIGURE 1.

B. SDG&E WILL DETERMINE WHEN WALLS ARE REQUIRED IF THEY ARE NOT INCLUDED ON THE JOB PRINT.

(C) MINIMUM OPERATING CLEARANCE REQUIREMENTS SHALL PREVAIL WHEN HOT STICK OPERATION OF LOADBREAK EQUIPMENT IS REQUIRED. (a)

(D) WALLS ARE REQUIRED WHEN SLOPE COMES WITHIN TWO FEET OF A FLAT GRADE ADJACENT TO A PAD OR SUBSTRUCTURE. THE FLAT GRADE IS ESTABLISHED FROM THE BOTTOM OF A PAD.

E. A MINIMUM OF 90% COMPACTION IS REQUIRED UNDER THE PAD AREA AND THE TWO-FOOT FLAT GRADE AREA ADJACENT TO THE PAD AND/OR SUBSTRUCTURE.

(F) SAFETY FENCING SHALL BE INSTALLED WHEN REQUIRED BY CITY OR COUNTY CODES.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

RETAINING WALL REQUIREMENTS AND CLEARANCES



UG3486.1

TABLE OF CONTENTS

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THIS STANDARD DOES NOT APPLY TO THE PREFORMED PLASTIC RETAINING WALL SHOWN ON UG3484.

**REFERENCE:**

(a) SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENT (SUBSTRUCTURE PLACEMENT).

b. SEE UG3484 AND UG3489 FOR RETAINING WALLS.

c. SEE UG3423 FOR SWITCH PAD CLEARANCE REQUIREMENTS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS SINGLE-PHASE TRANSFORMER PAD LOCATIONS ADJACENT TO CATV AND/TELCO AND RETAINING WALLS FOR SINGLE-PHASE TRANSFORMERS.





**FIGURE 1**

## INSTALLATION:

(A) THE CONCRETE AREA SHALL BE A MINIMUM OF 3 1/2 INCHES THICK. SLOPE THE CONCRETE TOWARD THE FRONT OR SIDEWALK.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. SEE UG3480, UG3481, UG3482 & UG3483 FOR PAD CLEARANCE REQUIREMENTS WITHOUT CATV AND/OR TELCO.

b. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

c. SEE UG3489 FOR RETAINING WALLS.

d. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

e. SEE UG3488 CLEARANCES BETWEEN SDG&E FACILITIES AND OTHER ABOVE GROUND OBJECTS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3486 | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1998 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

RETAINING WALL REQUIREMENTS AND SINGLE-PHASE TRANSFORMER PAD LOCATIONS SHOWING CATV AND/OR TELCO LOCATIONS



UG3487.1

TABLE OF CONTENTS

**SCOPE:** THE PURPOSE OF THIS DRAWING IS TO ILLUSTRATE THE REQUIRED CLEARANCES FROM ABOVE GROUND OBJECTS AND MINIMUM HOT STICK CLEARANCE.





**FIGURE 1**





**FIGURE 2**

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3486 | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 11/16/2006 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CLEARANCES BETWEEN SDG&E FACILITIES
AND OTHER ABOVE GROUND OBJECTS



UG3488.1

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WET UTILITIES INCLUDING FIRE HYDRANTS, STAND PIPES, ABOVE GROUND WATER METERS, BACK FLOW VALVES AND OTHER ABOVE GROUND WET UTILITY EQUIPMENT SHALL BE A MINIMUM 5 FEET FROM PAD MOUNTED SDG&E FACILITIES AND 8 FEET FOR THE WORK SPACE.

**REFERENCE:**

a. SEE UG3487 FOR RETAINING WALL REQUIREMENTS AND SINGLE-PHASE PAD LOCATIONS SHOWING CATV FOR TELCO LOCATIONS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3486 | EDM | JIK | - | - | 11/5/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 11/16/2006 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CLEARANCES BETWEEN SDG&E FACILITIES AND OTHER ABOVE GROUND OBJECTS

UG3488.2

**SCOPE:** THIS STANDARD SHOWS RETAINING WALLS FOR LEVEL BACKFILL TO PROTECT PAD MOUNTED AND SUBSURFACE EQUIPMENT.

**ATTENTION:**

* SEE FIGURE 14 FOR STEPPED WALL FOOTING DETAILS.

** SEE SHEET 9-10 FOR ADDITIONAL NOTES AND DETAILS.





**FIGURE 1**
C-1 TYPICAL SECTION
5'-4" MAX.





**FIGURE 2**
C-1 TYPICAL SECTION
OVER 5'-4"

## TABLE 1 (C-1)

| DIMENSIONS AND REINFORCING STEEL | | | | | | | |
|---|---|---|---|---|---|---|---|
| WALL HEIGHT | FOUNDATION DEPTH | FOUNDATION HEIGHT | REBAR | | | FOUNDATION KEY | |
| | Z (MIN.) | Y (MIN.) | X | W | V | U (IN) | T (IN) |
| 1'-4" | 2'-4" | 8" | #4 @ 32" | -- | 4-#4 | 8 | 8 |
| 2'-0" | 2'-4" | 8" | #4 @ 32" | -- | 4-#4 | 8 | 8 |
| 2'-8" | 2'-4" | 8" | #4 @ 32" | -- | 4-#4 | 8 | 8 |
| 3'-4" | 2'-4" | 8" | #4 @ 32" | -- | 4-#4 | 8 | 8 |
| 4'-0" | 3'-6" | 10" | #4 @ 16" | -- | 5-#4 | 8 | 8 |
| 4'-8" | 3'-6" | 10" | #4 @ 16" | -- | 5-#4 | 8 | 8 |
| 5'-4" | 3'-6" | 10" | #4 @ 16" | -- | 5-#4 | 8 | 8 |
| 6'-0" | 5'-4" | 1'-0" | #4 @ 16" | #6 @ 16" | 6-#4 | 12 | 12 |
| 6'-8" | 5'-4" | 1'-0" | #4 @ 16" | #6 @ 16" | 6-#4 | 12 | 12 |
| 7'-4" | 5'-4" | 1'-0" | #4 @ 16" | #6 @ 16" | 6-#4 | 12 | 12 |
| 8'-0" | 5'-4" | 1'-0" | #4 @ 16" | #6 @ 16" | 6-#4 | 12 | 12 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MASONRY RETAINING WALLS
TYPE 1 - LEVEL BACKFILL

UG3489.1

TABLE OF CONTENTS





**FIGURE 3**
C-2 TYPICAL SECTION
3'-8" MAX.





**FIGURE 4**
C-2 TYPICAL SECTION
OVER 3'-8"

## TABLE 2 (C-2)

| DIMENSIONS AND REINFORCING STEEL | | | | | | | |
|---|---|---|---|---|---|---|---|
| WALL HEIGHT | FOUNDATION DEPTH | FOUNDATION HEIGHT | REBAR | | | FOUNDATION KEY | |
| | Z (MIN.) | Y (MIN.) | X | W | V | U (IN) | T (IN) |
| 1'-4" | 3'-9" | 10" | -- | #4 @ 16" | 3-#4 | 12 | 12 |
| 2'-0" | 3'-9" | 10" | -- | #4 @ 16" | 3-#4 | 12 | 12 |
| 2'-8" | 3'-9" | 10" | -- | #4 @ 16" | 3-#4 | 12 | 12 |
| 3'-4" | 3'-9" | 10" | -- | #4 @ 16" | 3-#4 | 12 | 12 |
| 4'-0" | 5'-0" | 10" | #4 @ 16" | #6 @ 16" | 5-#4 | 12 | 20 |
| 4'-8" | 5'-0" | 10" | #4 @ 16" | #6 @ 16" | 5-#4 | 12 | 20 |
| 5'-4" | 5'-0" | 10" | #4 @ 16" | #6 @ 16" | 5-#4 | 12 | 20 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS





**FIGURE 5**
C-3 TYPICAL SECTION
5'-4" MAX.





**FIGURE 6**
C-3 TYPICAL SECTION
OVER 5'-4"

## TABLE 3 (C-3)

| DIMENSIONS AND REINFORCING STEEL | | | | | | |
|---|---|---|---|---|---|---|
| WALL HEIGHT | FOUNDATION DEPTH | FOUNDATION HEIGHT | REBAR | | | |
| | Z (MIN.) | Y (MIN.) | X | W | V | U |
| 1'-4" | 2'-4" | 8" | #4 @ 32" | -- | #4 @ 32" | 5-#4 |
| 2'-0" | 2'-4" | 8" | #4 @ 32" | -- | #4 @ 32" | 5-#4 |
| 2'-8" | 2'-4" | 8" | #4 @ 32" | -- | #4 @ 32" | 5-#4 |
| 3'-4" | 2'-4" | 8" | #4 @ 32" | -- | #4 @ 32" | 5-#4 |
| 4'-0" | 3'-2" | 10" | #4 @ 16" | -- | #4 @ 16" | 6-#4 |
| 4'-8" | 3'-2" | 10" | #4 @ 16" | -- | #4 @ 16" | 6-#4 |
| 5'-4" | 3'-2" | 10" | #4 @ 16" | -- | #4 @ 16" | 6-#4 |
| 6'-0" | 4'-9" | 1'-0" | #4 @ 16" | #6 @ 16" | #6 @ 16" | 7-#4 |
| 6'-8" | 4'-9" | 1'-0" | #4 @ 16" | #6 @ 16" | #6 @ 16" | 7-#4 |
| 7'-4" | 4'-9" | 1'-0" | #4 @ 16" | #6 @ 16" | #6 @ 16" | 7-#4 |
| 8'-0" | 4'-9" | 1'-0" | #4 @ 16" | #6 @ 16" | #6 @ 16" | 7-#4 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |





**FIGURE 7**
C-4 TYPICAL SECTION
3'-8" MAX.





**FIGURE 8**
C-4 TYPICAL SECTION
OVER 3'-8"

## TABLE 4 (C-4)

| DIMENSIONS AND REINFORCING STEEL | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| WALL HEIGHT | FOUNDATION DEPTH | FOUNDATION HEIGHT | REBAR | | | | FOUNDATION KEY | |
| | Z (MIN.) | Y (MIN.) | X | W | V | U | T (IN) | S (IN) |
| 1'-4" | 3'-0" | 8" | #4 @ 16" | -- | #6 @ 16" | 6-#4 | 12 | 12 |
| 2'-0" | 3'-0" | 8" | #4 @ 16" | -- | #6 @ 16" | 6-#4 | 12 | 12 |
| 2'-8" | 3'-0" | 8" | #4 @ 16" | -- | #6 @ 16" | 6-#4 | 12 | 12 |
| 3'-4" | 3'-0" | 8" | #4 @ 16" | -- | #6 @ 16" | 6-#4 | 12 | 12 |
| 4'-0" | 4'-0" | 10" | #4 @ 16" | #6 @ 16" | #6 @ 8" | 8-#4 | 12 | 12 |
| 4'-8" | 4'-0" | 10" | #4 @ 16" | #6 @ 16" | #6 @ 8" | 8-#4 | 12 | 12 |
| 5'-4" | 4'-0" | 10" | #4 @ 16" | #6 @ 16" | #6 @ 8" | 8-#4 | 12 | 12 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |





**FIGURE 9**
C-5 TYPICAL SECTION
5'-4" MAX.





**FIGURE 10**
C-5 TYPICAL SECTION
OVER 5'-4"

## TABLE 5 (C-5)

| DIMENSIONS AND REINFORCING STEEL | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| WALL HEIGHT | FOUNDATION DEPTH Z (MIN.) | FOUNDATION HEIGHT Y (MIN.) | X | W | REBAR V | REBAR U | REBAR T | REBAR S | FOUNDATION KEY R (IN) | FOUNDATION KEY Q (IN) |
| 1'-4" | 2'-1" | 8" | 9" | 8 1/2" | #4 @ 32" | -- | #4 @ 32" | 5-#4 | 8 | 8 |
| 2'-0" | 2'-1" | 8" | 9" | 8 1/2" | #4 @ 32" | -- | #4 @ 32" | 5-#4 | 8 | 8 |
| 2'-8" | 2'-1" | 8" | 9" | 8 1/2" | #4 @ 32" | -- | #4 @ 32" | 5-#4 | 8 | 8 |
| 3'-4" | 2'-1" | 8" | 9" | 8 1/2" | #4 @ 32" | -- | #4 @ 32" | 5-#4 | 8 | 8 |
| 4'-0" | 3'-1" | 10" | 1'-2" | 1'-1/2" | #4 @ 16" | -- | #4 @ 16" | 5-#4 | 8 | 8 |
| 4'-8" | 3'-1" | 10" | 1'-2" | 1'-1/2" | #4 @ 16" | -- | #4 @ 16" | 5-#4 | 8 | 8 |
| 5'-4" | 3'-1" | 10" | 1'-2" | 1'-1/2" | #4 @ 16" | -- | #4 @ 16" | 5-#4 | 8 | 8 |
| 6'-0" | 4'-3" | 1'-0" | 1'-5" | 1'-7 1/2" | #4 @ 16" | #7 @ 16" | #4 @ 16" | 6-#4 | 12 | 12 |
| 6'-8" | 4'-3" | 1'-0" | 1'-5" | 1'-7 1/2" | #4 @ 16" | #7 @ 16" | #4 @ 16" | 6-#4 | 12 | 12 |
| 7'-4" | 4'-3" | 1'-0" | 1'-5" | 1'-7 1/2" | #4 @ 16" | #7 @ 16" | #4 @ 16" | 6-#4 | 12 | 12 |
| 8'-0" | 4'-3" | 1'-0" | 1'-5" | 1'-7 1/2" | #4 @ 16" | #7 @ 16" | #4 @ 16" | 6-#4 | 12 | 12 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS





**FIGURE 11**
C-6 TYPICAL SECTION
3'-8" MAX.





**FIGURE 12**
C-6 TYPICAL SECTION
OVER 3'-8"

## TABLE 6 (C-6)

| DIMENSIONS AND REINFORCING STEEL | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| WALL HEIGHT | FOUNDATION DEPTH | FOUNDATION HEIGHT | REBAR | | | | FOUNDATION KEY | |
| | Z (MIN.) | Y (MIN.) | X | W | V | U | T (IN) | S (IN) |
| 1'-4" | 2'-9" | 8" | -- | #4 @ 16" | #5 @ 16" | 5-#4 | 12 | 8 |
| 2'-0" | 2'-9" | 8" | -- | #4 @ 16" | #5 @ 16" | 5-#4 | 12 | 8 |
| 2'-8" | 2'-9" | 8" | -- | #4 @ 16" | #5 @ 16" | 5-#4 | 12 | 8 |
| 3'-4" | 2'-9" | 8" | -- | #4 @ 16" | #5 @ 16" | 5-#4 | 12 | 8 |
| 4'-0" | 3'-10" | 10" | #4 @ 16" | #6 @ 16" | #5 @ 16" | 5-#4 | 12 | 12 |
| 4'-8" | 3'-10" | 10" | #4 @ 16" | #6 @ 16" | #5 @ 16" | 5-#4 | 12 | 12 |
| 5'-4" | 3'-10" | 10" | #4 @ 16" | #6 @ 16" | #5 @ 16" | 5-#4 | 12 | 12 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed





**FIGURE 13**
PLAN VIEW





**FIGURE 13** V
ELEVATION VIEW

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MASONRY RETAINING WALLS
TYPE 6 - SLOPING BACKFILL



UG3489.7

TABLE OF CONTENTS





**FIGURE 14**
TYPICAL SECTION





**FIGURE 14**
CAP DETAIL





**FIGURE 14**
KEY DETAIL

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MASONRY RETAINING WALLS
DETAILS



UG3489.8

TABLE OF CONTENTS

**INSTALLATION:**

A. FILL ALL BLOCK CELLS WITH GROUT.

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THIS STANDARD WAS DEVELOPED BASED ON THE SAN DIEGO REGIONAL STANDARD DRAWINGS.

II. ALL MASONRY WALLS SHALL BE CONSTRUCTED WITH CAP, KEY AND DRAINAGE DETAILS AS SHOWN HEREON.

III. 4-INCH DIAMETER DRAIN MAY BE FORMED BY PLACING A BLOCK ON ITS SIDE.

(IV) WALL HEIGHTS AND FOOTING TYPES VARY DEPENDING ON SELECTED RETAINING WALL TYPE AND SITE CONDITIONS.

(V) HORIZONTAL REINFORCEMENT NOT SHOWN.

VI. WALLS ARE TO BE USED ONLY FOR THE LOADING CONDITIONS SHOWN FOR EACH TYPE WALL. THE DESIGN HEIGHTS ARE MEASURED FROM THE TOP OF THE FOUNDATION, NOT FROM FINISHED GRADE AND ARE NOT TO BE EXCEEDED WHEN USING THESE STANDARD DESIGNS. WALLS NOT MEETING THE SPECIFICATIONS IN THIS STANDARD ARE TO BE DESIGNED BY CIVIL/STRUCTURAL ENGINEERING FOR THE SPECIFIC CONDITIONS REQUIRED.

VII. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN ADEQUATE ERECTION, SHORING AND BRACING AS REQUIRED FOR STABILITY OF ALL WALLS AND EMBANKMENTS DURING ALL PHASES OF CONSTRUCTION.

VIII. BEFORE COMMENCING ANY EXCAVATIONS, THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES, VALVE BOXES, VAULTS OR ANY OTHER UNDERGROUND OBSTRUCTIONS, AND NOT PERFORM ANY WORK THAT WILL INTERFERE WITH THEIR SERVICE. NOTIFY SDG&E OF ANY OBSTRUCTIONS FOUND THAT INTERFERE WITH CONSTRUCTION.

IX. TO INSURE PROPER BONDING BETWEEN THE FOOTING AND WALL, A MORTAR KEY SHALL BE FORMED BY EMBEDDING A FLAT 2x4 FLUSH WITH AND AT THE TOP OF THE FRESHLY POURED FOOTING. THE 2x4 SHOULD BE REMOVED AFTER THE CONCRETE HAS STARTED TO HARDEN (APPROXIMATELY 1 HOUR).

XI. WALL DRAINS SHALL BE PROVIDED AS SHOWN IN THIS STANDARD.

XII. NO BACKFILL MATERIAL SHALL BE PLACED AGAINST MASONRY RETAINING WALLS UNTIL GROUT HAS REACHED DESIGN STRENGTH OR UNTIL GROUT HAS CURED FOR A MINIMUM OF 28 DAYS AND BUILDING DEPARTMENT INSPECTION IS COMPLETE. COMPACTION OF BACKFILL MATERIAL BY JETTING OR PONDING WITH WATER WILL NOT BE PERMITTED. EACH LAYER OF BACKFILL SHALL BE MOISTENED AND THOROUGHLY TAMPED, ROLLED OR OTHERWISE COMPACTED UNTIL THE RELATIVE COMPACTING IS NOT LESS THAN 90%.

XIII. SAFETY FENCING SHALL BE INSTALLED AT THE TOP OF THE WALL AS REQUIRED BY THE AGENCY.

XIV. **REINFORCED CONCRETE:**

a. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 2,000 PSI, MAXIMUM 4-INCH SLUMP (MAX. SLUMP OF 8-INCH PERMITTED WITH ADDITION OF APPROVED PLASTICIZER) AND MAXIMUM 1-INCH AGGREGATE. MAXIMUM WATER/CEMENT RATIO TO BE 0.45. CEMENT SHALL CONFORM TO 'TYPE II MODIFIED' AS DEFINED BY THE MOST CURRENT EDITION OF CALTRANS STANDARD SPECIFICATIONS.

b. ALL REINFORCING STEEL SHALL BE WELL-SECURED IN POSITION PRIOR TO PLACING CONCRETE.

c. BOTTOMS OF FOUNDATIONS SHALL BE CLEANED OF LOOSE MATERIAL AND DAMPENED PRIOR TO PLACING CONCRETE IN FOOTINGS.

d. CONSTRUCTION JOINTS ARE TO BE USED ONLY WHERE SHOWN ON THE APPROVED PLANS. ADDITIONAL JOINTS PROPOSED BY THE CONTRACTOR MUST BE APPROVED BY SDG&E PRIOR TO START OF CONSTRUCTION. THE SURFACE OF ALL CONSTRUCTION JOINTS SHALL BE CLEANED AND ROUGHENED BY REMOVING THE ENTIRE SURFACE AND EXPOSING CLEAN AGGREGATE SOLIDLY EMBEDDED IN MORTAR PRIOR TO PLACING NEW CONCRETE. SURFACE AT JOINTS SHALL BE ROUGHENED TO 1/4-INCH MINIMUM AMPLITUDE.

e. ALL CONCRETE SHALL BE MIXED, DELIVERED, PLACED AND CURED PER THE LATEST EDITION OF ACI 301. MECHANICAL VIBRATORS SHALL BE USED.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MASONRY RETAINING WALLS
GENERAL NOTES

## NOTES (CONT'D):

XV. **CONCRETE BLOCK MASONRY:**

a. CONCRETE MASONRY UNITS SHALL BE TYPE I MEDIUM WEIGHT UNITS IN CONFORMANCE WITH ASTM C90 (f'm = 1,500 PSI).

b. MORTAR SHALL BE TYPE S IN CONFORMANCE WITH ASTM C270 WITH AN ULTIMATE COMPRESSIVE STRENGTH OF 1,800 PSI.

c. GROUT SHALL HAVE AN ULTIMATE COMPRESSIVE STRENGTH OF 2,000 PSI.

d. ALL CELLS SHALL BE SOLID GROUTED AND CONSOLIDATED WITH A MECHANICAL VIBRATOR.

e. WHEN GROUTING IS STOPPED FOR ONE HOUR OR LONGER, HORIZONTAL CONSTRUCTION JOINTS SHALL BE FORMED BY STOPPING THE GROUT POUR 1 1/2-INCH BELOW THE TOP OF THE UPPERMOST UNIT.

f. APPLY CLEAR WATER REPELLANT SEALER TO ALL EXPOSED SURFACES AFTER REQUIRED MOISTURE CONTENT IS REACHED, IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS (5-YEAR GUARANTEE).

XVI. **REINFORCING STEEL:**

a. REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60.

b. BAR LAP SPLICE LENGTHS SHALL BE 48 BAR DIAMETERS MINIMUM.

c. FOOTING DOWELS SHALL MATCH VERTICAL REINFORCING IN SIZE, GRADE AND SPACING UNLESS OTHERWISE NOTED.

d. ALL DETAILING, FABRICATION AND ERECTION OF REINFORCING STEEL SHALL CONFORM TO THE LATEST EDITION OF ACI 315, DETAILS AND DETAILING OF CONCRETE REINFORCING.

e. MINIMUM CONCRETE COVER FOR REINFORCING STEEL SHALL BE AS FOLLOWS UNLESS SHOWN OTHERWISE ON DRAWINGS:

**TABLE 7**

| MINIMUM REBAR CONCRETE COVER | |
|---|---|
| **TYPE** | **DIMENSION (IN)** |
| CONCRETE CAST AGAINST EARTH | 3 |
| ALL OTHER | 2 |

XVII. **INSPECTIONS:** CALL THE GOVERNING JURISDICTION FOR INSPECTIONS AS FOLLOWS:

a. WHEN THE FOOTING HAS BEEN FORMED AND CLEANED, WITH STEEL TIED SECURELY IN FINAL POSITION AND READY FOR CONCRETE PLACEMENT.

b. WHERE CLEANOUT HOLES ARE NOT PROVIDED, AFTER BLOCK HAS BEEN LAID UP TO A HEIGHT OF 4 FEET OR FULL HEIGHT FOR WALLS UP TO 5 FEET, WITH STEEL IN PLACE, AND BEFORE THE GROUT IS POURED.

c. WHERE CLEANOUT HOLES ARE NOT PROVIDED, AFTER FIRST LIFT IS PROPERLY GROUTED, BLOCK HAS BEEN LAID UP TO TOP OF WALL, STEEL TIED SECURELY IN PLACE, AND BEFORE UPPER LIFT IS GROUTED.

d. WHERE CLEANOUT HOLES ARE PROVIDED, AFTER BLOCK HAS BEEN LAID UP TO TOP OF WALL, WITH STEEL TIED SECURELY IN PLACE, AND BEFORE GROUTING.

e. AFTER GROUTING IS COMPLETE, WALL DRAINAGE IS IN PLACE, AND BEFORE EARTH BACKFILL IS PLACED.

f. FINAL INSPECTION WHEN ALL WORK HAS BEEN COMPLETED.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG3487 | EDM | JIK | - | - | 11/5/2020 | E | | | | | | |
| A | TITLE BLOCK UPDATE | - | B | BR | - | 3/8/2017 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MASONRY RETAINING WALLS
GENERAL NOTES

UG3489.10

# 3500 - PAD/WALL MOUNTED SECTIONALIZING EQUIPMENT

# 3500 - PAD/WALL MOUNTED SECTIONALIZING EQUIPMENT

| PAGE | SUBJECT |
|---|---|
| | **FUSE CABINETS** |
| 3511 | PAD MOUNTED AIRBREAK PME-5 FUSED SWITCH CABINET, 12KV, 200A, THREE-PHASE |
| 3512 | SINGLE-PHASE, LOW PROFILE FUSED SWITCHING CABINET - 6,930V |
| 3514 | THREE-PHASE FUSE CABINET WITH HORIZONTAL MOUNTED FUSES - 12KV WITH FEED THRU CAPABILITY |
| 3515 | THREE-PHASE FUSE CABINET WITH VERTICAL MOUNTED FUSE AND FUSE BYPASS - 12KV WITH FEED THRU CAPABILITY |
| 3516 | THREE-PHASE WALL MOUNTED FUSE CABINET - 12KV, 200A |
| | **TERMINATING CABINETS** |
| 3517 | 200A LIVEFRONT TO DEADFRONT TERMINATING CABINET |
| 3518 | 600A LIVEFRONT TO DEADFRONT TERMINATING CABINET |
| 3522 | SINGLE-PHASE, LOW PROFILE CABLE TERMINATING CABINET - 6,930V |
| 3523 | THREE-PHASE LOW PROFILE CABLE TERMINATING CABINET, 12KV, 200A |
| 3524 | THREE-PHASE LOW PROFILE CABLE TERMINATING CABINET, 12KV, 200A/600A |
| | **SWITCH CABINETS** |
| 3550 | PAD MOUNTED SWITCH GEAR |
| 3551 | 4-WAY MANUAL |
| 3552 | 4-WAY SCADA |
| 3553 | 4-WAY SCADA HIGH SPEED TRIP COIL |
| 3554 | 2 SIDED 4-WAY SCADA |
| 3555 | 5-WAY SCADA |
| 3560 | INNOVATIVE SWITCH GEAR |
| 3567 | PAD MOUNTED AIRBREAK PME 9, 10 AND 11 SECTIONALIZING SWITCH, 12KV, 600A, THREE-PHASE |
| 3568 | INSTALLATION OF PAD MOUNTED AIRBREAK PME 9, 10 AND 11 SECTIONALIZING SWITCH, 12KV, 600A, THREE-PHASE |


MAIN TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | H | UG3525 MOVED TO FMO | EDM | EJA | GLW | KRG | 09/07/2022 |
| D | UPDATES TO 3522 | - | JS | JS | MDJ | 06/27/2017 | G | FORMATTING | EDM | JIK | - | - | 05/17/2021 |
| C | UPDATES TO 3523 | - | JS | TR | MDJ | 08/11/2016 | F | ADDED 3517 & 3518 | - | GW | JS | CZH | 11/01/2018 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED SECTIONALIZING EQUIPMENT
TABLE OF CONTENTS

| PAGE | SUBJECT |
|---|---|
| 3580 | PAD MOUNTED MVI SWITCH ENCLOSURE |
| 3583 | PAD MOUNTED AIRBREAK PME-3 SECTIONALIZING SWITCH CABINET, 12KV, 600A |
| 3584 | INSTALLATION OF PAD MOUNTED AIRBREAK PME-3 SECTIONALIZING SWITCH CABINET, 12KV, 600A |
| 3585 | PAD MOUNTED 3-WAY 600A SF-6 GAS SWITCH CABINET (VISTA) |
| 3586 | INSTALLATION OF PAD MOUNTED 3-WAY 600A SF-6 GAS SWITCH CABINET (VISTA) |
| 3588 | INSTALLATION OF PAD MOUNTED AIRBREAK PME-5 FUSED SWITCH CABINET, 12KV, 200A |
| | **SERVICE RESTORERS** |
| 3590 | PAD MOUNTED SERVICE RESTORER - 12KV, 600A, THREE-PHASE |
| 3591 | INSTALLATION OF PAD MOUNTED SERVICE RESTORER - 12KV, 600A, AND 3313 HANDHOLE |


MAIN TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | H | UG3525 MOVED TO FMO | EDM | EJA | GLW | KRG | 09/07/2022 |
| D | UPDATES TO 3522 | - | JS | JS | MDJ | 06/27/2017 | G | FORMATTING | EDM | JIK | - | - | 05/17/2021 |
| C | UPDATES TO 3523 | - | JS | TR | MDJ | 08/11/2016 | F | ADDED 3517 & 3518 | - | GW | JS | CZH | 11/01/2018 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED SECTIONALIZING EQUIPMENT
TABLE OF CONTENTS

UG3501.2

**SCOPE:** THIS STANDARD SHOWS INSTALLATION FOR THE PME-5 FUSE CABINET. APPROVED APPLICATIONS OF THIS STANDARD INCLUDE FEEDER TAPS FOR CERTAIN LOCAL DISTRIBUTION LOADS, AND FIELD MAINTENANCE JOBS REPLACING OLDER PMH-5 (LIVEFRONT) CABINETS.

**ATTENTION:**

* THIS DEVICE DOES NOT QUALIFY AS A SWITCH, FOR THE PURPOSES OF FEEDER CIRCUIT DESIGN CRITERIA. NOTE THAT ALL TERMINATIONS ON THE PME-5 USE 200A CONNECTORS. FUSING HARDWARE FOR THE PME-5 IS COMMON TO THE PME-9 AND PME-11, AND CAN ACCOMMODATE X-LIMITER CLF, OR SM-4 EXPULSION FUSING, WITH THE REQUIRED MODIFICATIONS.





**FIGURE 1** (I)
SIDE VIEW
EXPOSED





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
COMPARTMENT 1
END VIEW





**FIGURE 3**
COMPARTMENT 2
END VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3587 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED AIRBREAK PME-5 FUSED SWITCH CABINET
12KV, 200A, THREE-PHASE

UG3511.1






**FIGURE 4**
PME-5
CONNECTION DIAGRAM

**UG MAP SYMBOL**




PME-5

## TABLE 1

| SWITCH PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | BAR, GROUND |
| 2 | WELL, BUSHING, 200A |
| 3 | NAME PLATE, (ON OUTSIDE OF DOOR) |
| 4 | PLATE, GROUNDING |
| 5 | BUS, 200A |
| 6 | TABS, LIFTING (III) |
| 7 | SWITCH, MINI-RUPTER, 200A |
| 8 | SWITCH OPERATOR, (SCADA ONLY) |
| 9 | LOCKING PROVISION, PENTAHEAD LATCH |
| 10 | WINDOW, VIEWING, LEXAN SWITCH (II) |

## TABLE 2

| ELECTRIC RATINGS | |
|---|---|
| VOLTAGE | 14.4KV |
| B.I.L. | 95KV |
| CURRENT, CONDITIONS | 200A |
| LOADMAKE AND LOADBREAK | 200A |
| MOMENTARY AND FAULT CLOSE (RMS, ASYMMETRICAL) | 22,400A |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 14,000A |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) WEIGHT: 1,100 LBS MAX.

(II) NOT SHOWN IN FIGURES.

(III) REMOVE AFTER INSTALLATION AND REPLACE BOLTS, STORE INSIDE CABINET.

**REFERENCE:**

a. SEE UG3214 FOR SWITCH IDENTIFICATION.

b. SEE UG3418 FOR BOX PAD INSTALLATION FOR PAD MOUNTED, 600A, 12KV SWITCH.

c. SEE UG3588 FOR SWITCH INSTALLATION.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3587 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS PAD MOUNTED SINGLE-PHASE FUSED SWITCHING CABINET AND INSTALLATION REQUIREMENTS FOR FUSING SINGLE-PHASE LOAD IN UNDERGROUND SYSTEM.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
FRONT VIEW
EXPOSED






**FIGURE 2**
PLAN VIEW
EXPOSED




EXAMPLE 1
STANDARD

EXAMPLE 2
REVERSED

**FIGURE 3**

**TABLE 1**

| RATINGS | |
|---|---|
| FUSE (KV) | 8.3 |
| AMPERES | 200 |
| KV-BIL | 95 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 5/17/2021 | E | | | | | | |
| A | NO CHANGES-REAFFIRMED | - | JC | TR | MDJ | 9/17/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

SINGLE-PHASE, LOW PROFILE FUSED SWITCHING CABINET - 6,930V

UG3512.1






**FIGURE 4**




**DETAIL 1**

## INSTALLATION:

A. THIS INSTALLATION IS LIMITED TO A MAXIMUM OF THREE SINGLE-PHASE, #2 AL PRIMARY CABLES.

B. SET PAD AND HANDHOLE, INSTALL EQUIPMENT GROUND.

(C) TERMINATE CONDUITS AS SHOWN AND SEAL CONDUITS WITH SEALING COMPOUND.

(D) BASE OF CABINET SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(E) KEYLESS LOCKS TO BE ATTACHED TO LATCHING MECHANISM ON FUSE CABINET AND PENTAHEAD BOLTS TO BE THREADED IN COMPLETELY.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABINET, LOW PROFILE, FUSED | 1 | - | S190438 | FC-1PH |
| 2 | TRANSFORMER/UTILITY, SINGLE-PHASE | 1 | 3421 | S514240 | FC3PAD |
| 3 | HANDHOLE | 1 | 3312 | S162426 | 3312-0 |
| 4 | WIRE, GROUND, TRENCH (m) | AS REQ'D | 4510 | - | - |
| 5 | ELBOW, LOADBREAK, 14.4K, 200A | AS REQ'D | 4190-4191 | - | - |
| 6 | RECEPTACLE, INSULATING (II) | AS REQ'D | 4195 | S204304 | - |
| 7 | LOCK, KEYLESS (E) (II) | 2 | - | S468010 | - |
| 8 | FUSE | 1 | 4311-4314 | - | - |
| 9 | NUT, CLAMPING CHANNEL W/SPRING, 1/2" | 2 | - | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 2 1/2" | 2 | - | S616352 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 2 | - | S799488 | - |
| 12 | WASHER, LOCK, BRONZE, 1/2" | 2 | - | S796416 | - |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 5/17/2021 | E | | | | | | |
| A | NO CHANGES-REAFFIRMED | - | JC | TR | MDJ | 9/17/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SINGLE-PHASE, LOW PROFILE FUSED SWITCHING CABINET - 6,930V

UG3512.2

TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 13 | SEALING COMPOUND (C) | AS REQ'D | - | S442976 | - |
| 14 | TAGS, IDENTIFICATION, CABLE | AS REQ'D | 3202 | - | - |

## NOTES:

(I) FUSE CABINET COMES WITH 5/8" X 1" SLOT IN CENTER OF UNISTRUT FRAME (TYP).

(II) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3202 FOR CABLE IDENTIFICATION.

b. SEE UG3211, UG3212 (PREVIOUS # UG3211.1-.4) FOR STRUCTURE/EQUIPMENT IDENTIFICATION.

c. SEE UG3221 FOR HIGH VOLTAGE DECAL.

d. SEE UG3408 FOR WIRE ENTRY PREVENTION.

e. SEE UG3421 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.

f. SEE UG3479 FOR BARRIER PROTECTION.

g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

h. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

i. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

j. SEE UG3489 FOR RETAINING WALLS.

(k) SEE UG4108 FOR SEALING JACKETED CABLE.

l. SEE UG4302, UG4311, AND UG4312 FOR FUSING.

(m) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

n. SEE UG4512 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(o) SEE UG4512 FOR GROUNDING EQUIPMENT.

p. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

(q) SEE UG4520-UG4521 (PREVIOUS # UG4520.1-.9) FOR GROUNDING PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 5/17/2021 | E | | | | | | |
| A | NO CHANGES-REAFFIRMED | - | JC | TR | MDJ | 9/17/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SINGLE-PHASE, LOW PROFILE FUSED SWITCHING CABINET - 6,930V

UG3512.3

**SCOPE:** THIS STANDARD SHOWS PAD MOUNTED THREE-PHASE FUSE CABINET WITH HORIZONTAL MOUNTED FUSES WITH FEED THRU CAPABILITY AND INSTALLATION REQUIREMENTS USED FOR FUSING WYE AND DELTA LOADS IN UNDERGROUND SYSTEM.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
FRONT VIEW
EXPOSED




**FIGURE 1**
REAR VIEW





**FIGURE 1**
SIDE VIEW
EXPOSED

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 5/17/2021 | E | | | | | | |
| A | NO CHANGES-REAFFIRMED | - | JC | TR | - | 6/3/2015 | D | | | | | | |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE, FUSE CABINET WITH
HORIZONTAL MOUNTED FUSES - 12KV
WITH FEED THRU CAPABILITY


UG3514.1




**DETAIL 1**
HOLD-DOWN ASSEMBLY (TYP.)

**UG MAP SYMBOL**




FUSE CABINET

**FIGURE 2**

## INSTALLATION:

A. THIS INSTALLATION IS LIMITED TO A MAXIMUM OF FOUR THREE-PHASE, 2/0 AL CABLES AND SMALLER.

B. SET PAD AND HANDHOLE, INSTALL EQUIPMENT GROUND.

(C) TERMINATE CONDUITS AS SHOWN AND SEAL CONDUITS WITH SEALING COMPOUND.

(D) BASE OF CABINET SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(E) INSTALL SIX FEED-THRU INSERTS.

(F) INSTALL SINGLE BARREL FUSE ALL THE WAY BACK IN DOUBLE BARREL FUSE CLIPS NEAREST THE INSULATOR.

(G) KEYLESS LOCKS TO BE ATTACHED TO LATCHING MECHANISM ON FUSE CABINET AND PENTAHEAD BOLTS TO BE THREADED IN COMPLETELY.

(H) PREFERRED CONDUIT INSTALLATION IS LINE IN ON LEFT LOAD OUT ON RIGHT.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 5/17/2021 | E | | | | | | |
| A | NO CHANGES-REAFFIRMED | - | JC | TR | - | 6/3/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE, FUSE CABINET WITH
HORIZONTAL MOUNTED FUSES - 12KV
WITH FEED THRU CAPABILITY



UG3514.2

TABLE OF CONTENTS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABINET, FUSE, THREE-PHASE, HORIZ. MOUNT (G) | 1 | - | S190454 | FC3PFT |
| 2 | PAD WITH BOX, TRANSFORMER/UTILITY EQUIPMENT, SINGLE-PHASE | 1 | 3421 | S514240 | FC3PAD |
| 3 | HANDHOLE, 17" X 30" | 1 | 3312 | S162426 | - |
| 4 | WIRE, GROUND, TRENCH (m) | AS REQ'D | 4510 | - | - |
| 5 | ELBOW, LOADBREAK, 14.4KV 200A | AS REQ'D | 4190 - 4191 | - | - |
| 6 | RECEPTACLE, INSULATING (I) | AS REQ'D | 4195 | S204304 | - |
| 7 | LOCKS, KEYLESS (G)(I) | 2 | - | S468010 | - |
| 8 | FUSE (F)(I) | 3 | 4311 - 4314 | - | - |
| 9 | NUT, STUD, 1/2" X 1 3/8" | 2 | - | S507000 | - |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 2 | - | S799488 | - |
| 11 | HOLD DOWN (SUPPLIED WITH CABINET) | 2 | - | - | - |
| 12 | COMPOUND, SEALING (C)(I) | AS REQ'D | - | S442976 | - |
| 13 | TAGS, IDENTIFICATION, CABLE (C) | AS REQ'D | 3202 | - | - |
| 14 | BUSHING, FEED-THRU LOADBREAK (NOT SUPPLIED WITH CABINET) (E) | 6 | 4195 | S544678 | FEED-1 |
| 15 | NUT, STANDARD HEX, STAINLESS STEEL (I) | 2 | - | S505536 | - |

## NOTES:

(I) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3202 FOR CABLE IDENTIFICATION.
b. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION.
c. SEE UG3221 FOR HIGH VOLTAGE DECAL.
d. SEE UG3408 FOR WIRE ENTRY PREVENTION.
e. SEE UG3421 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.
f. SEE UG3479 FOR BARRIER PROTECTION.
g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).
h. SEE UG3484 FOR INSTALLATION OF PAD MOUNTED EQUIPMENT.
i. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.
j. SEE UG3489 FOR RETAINING WALLS.
k. SEE UG4108 FOR SEALING JACKETED CABLE.
l. SEE UG4302, UG4311, AND UG4312 FOR FUSING.
(m) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.
n. SEE UG4512 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.
(o) SEE UG4512 FOR GROUNDING EQUIPMENT.
(p) SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.
(q) SEE UG4520 AND UG4521 (PREVIOUS # UG4520.1-.9) FOR GROUNDING PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 5/17/2021 | E | | | | | | |
| A | NO CHANGES-REAFFIRMED | - | JC | TR | - | 6/3/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS PAD MOUNTED THREE-PHASE FUSE CABINET WITH VERTICAL MOUNTED FUSES AND FUSE BYPASS WITH FEED THRU CAPABILITY AND INSTALLATION REQUIREMENTS USED FOR FUSING WYE AND DELTA LOADS IN UNDERGROUND SYSTEM.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
FRONT VIEW
EXPOSED





**FIGURE 1**
REAR VIEW
EXPOSED





**FIGURE 1**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 12/8/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE, FUSE CABINET WITH
VERTICAL MOUNTED FUSE AND FUSE BYPASS - 12KV
WITH FEED THRU CAPABILITY



UG3515.1







**FIGURE 2**




**DETAIL 1**
HOLD-DOWN ASSEMBLY (TYP.)

**UG MAP SYMBOL**




## INSTALLATION:

A. THIS INSTALLATION IS LIMITED TO A MAXIMUM OF FOUR THREE-PHASE, 2/0 AL CABLES AND SMALLER.

B. SET PAD AND HANDHOLE, INSTALL EQUIPMENT GROUND.

(C) TERMINATE CONDUITS AS SHOWN AND SEAL CONDUITS WITH SEALING COMPOUND.

(D) BASE OF CABINET SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(E) INSTALL SIX FEED-THRU INSERTS.

(F) INSTALL SINGLE BARREL FUSE ALL THE WAY BACK IN DOUBLE BARREL FUSE CLIPS NEAREST THE INSULATOR.

(G) KEYLESS LOCKS TO BE ATTACHED TO LATCHING MECHANISM ON FUSE CABINET AND PENTAHEAD BOLTS TO BE THREADED IN COMPLETELY.

(H) PREFERRED CONDUIT INSTALLATION IS LINE IN ON LEFT LOAD OUT ON RIGHT.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABINET, FUSE, THREE-PHASE, VERTICAL MOUNT (G) | 1 | - | S190452 | FC3PBP |
| 2 | PAD WITH BOX, TRANSFORMER/UTILITY EQUIPMENT, SINGLE-PHASE | 1 | 3421 | S514240 | FC3PAD |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 12/8/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE, FUSE CABINET WITH
VERTICAL MOUNTED FUSE AND FUSE BYPASS - 12KV
WITH FEED THRU CAPABILITY



UG3515.2

TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 3 | HANDHOLE, 17" X 30" | 1 | 3312 | S162426 | - |
| 4 | WIRE, GROUND, TRENCH (m) | AS REQ'D | 4510 | - | - |
| 5 | ELBOW, LOADBREAK, 14.4KV 200A | AS REQ'D | 4190 - 4191 | - | - |
| 6 | RECEPTACLE, INSULATING (II) | AS REQ'D | 4195 | S204304 | - |
| 7 | LOCKS, KEYLESS (G) (II) | 2 | - | S468010 | - |
| 8 | FUSE (F) (II) | 3 | 4311 - 4314 | - | - |
| 9 | NUT, STUD, 1/2" X 1 3/8" | 2 | - | S507000 | - |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 2 | - | S799488 | - |
| 11 | HOLD DOWN (SUPPLIED WITH CABINET) | - | - | - | - |
| 12 | COMPOUND, SEALING (C) (II) | AS REQ'D | - | S442976 | - |
| 13 | TAGS, IDENTIFICATION, CABLE (C) | AS REQ'D | 3202 | - | - |
| 14 | BUSHING, FEED-THRU LOADBREAK (NOT SUPPLIED WITH CABINET) (E) | 6 | 4195 | S544678 | FEED-1 |
| 15 | NUT, STANDARD HEX, STAINLESS STEEL (II) | 2 | - | S505536 | - |

## NOTES:

(I) HOTSTICK OPERABLE KNIFE BLADE SWITCH FOR FUSE BYPASS AND 200A LOOP OPERATIONS.

(II) NOT SHOWN ON FIGURES.

III. CHECK KNIFE BLADES IN OPEN POSITION BEFORE ENERGIZING CABINET.

## REFERENCE:

a. SEE UG3202 FOR CABLE IDENTIFICATION.

b. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION.

c. SEE UG3221 FOR HIGH VOLTAGE DECAL.

d. SEE UG3408 FOR WIRE ENTRY PREVENTION.

e. SEE UG3421 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.

f. SEE UG3479 FOR BARRIER PROTECTION.

g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

h. SEE UG3484 FOR INSTALLATION OF PAD MOUNTED EQUIPMENT.

i. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

j. SEE UG3489 FOR RETAINING WALLS.

k. SEE UG4108 FOR SEALING JACKETED CABLE.

l. SEE UG4302, UG4311, AND UG4312 FOR FUSING.

(m) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

n. SEE UG4512 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(o) SEE UG4512 FOR GROUNDING EQUIPMENT.

(p) SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

(q) SEE UG4520 AND UG4521 (PREVIOUS # UG4520.1-.9) FOR GROUNDING PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 12/8/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE, FUSE CABINET WITH
VERTICAL MOUNTED FUSE AND FUSE BYPASS - 12KV
WITH FEED THRU CAPABILITY

UG3515.3

**SCOPE:** THIS STANDARD SHOWS A 12KV, 200A WALL MOUNTED FUSE CABINET USED FOR FUSING IN TRANSFORMER VAULTS.





**FIGURE 1**
FRONT





**FIGURE 1**
FRONT SECTION





**FIGURE 1**
SIDE SECTION

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3580 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 7/29/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE WALL MOUNTED FUSE CABINET
12KV, 200A




UG3516.1

**TABLE 1**

| ELECTRIC RATING | |
|---|---|
| VOLTAGE | 15KV |
| B.I.L. | 110KV |
| MAX FUSE SIZE | 200A |

**UG MAP SYMBOL**




WALL MOUNTED
FUSE CABINET

## INSTALLATION:

A. BUSHING WELLS WILL ACCEPT BUSHING PLUGS (S544676) OR FEED-THRU INSERTS (S544678) FOR LOADBREAK CAPABILITY.

B. INSTALL FEED-THRU INSERTS ON LOAD SIDE OF ALL CABINETS.

(C) CABINET DOOR HANDLE DOES NOT REQUIRE A PADLOCK.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CABINET, FUSE, WALL MOUNTED, THREE-PHASE | 380 | 1 | -- | S190446 | FC-VLT |
| 2 | BUS, COPPER | -- | 1 | -- | | |
| 3 | BUSHING | -- | 1 | -- | | |
| 4 | BARRIER | -- | 1 | -- | | |
| 5 | BARRIER, REMOVABLE | -- | 1 | -- | | |
| 6 | GROUNDING POSITION | -- | 1 | -- | | |
| 7 | BUSHING WELL | -- | 1 | -- | | |
| 8 | PARKING STAND | -- | 1 | -- | | |
| 9 | BRACKET, MOUNTING | -- | 1 | -- | | |
| 10 | CABINET DOOR HANDLE AND PENTAHEAD BOLT PROVISION (C) | -- | 1 | -- | | |
| 11 | TABS, LIFTING | -- | 1 | -- | | |
| 12 | DECAL, MR OUCH | -- | 1 | -- | | |
| 13 | NAMEPLATE (ON INSIDE OF DOOR) (II) | -- | 1 | -- | | |
| 14 | FUSE, CURRENT LIMITING, 150A (II) (c) | -- | 1 | -- | S363687 | -- |

## NOTES:

I. WALL MOUNTED FUSE CABINET (S190444) IS DELIVERED FROM THE SUPPLIER WITH ALL THE PARTS LISTED IN THE BILL OF MATERIALS EXCEPT FUSES.

(II) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE TRANSFORMER VAULTS SPECIFICATIONS BOOK FOR INSTALLATION LOCATION.

b. SEE UG3480, UG3481, UG3482, AND UG3483 FOR CLEARANCE IN FRONT OF CABINET.

(c) SEE UG4302 FOR FUSE APPLICATION GUIDE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3580 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 7/29/2014 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE ASSEMBLY OF A 200A CABINET PLATE.




**FIGURE 1**
200A CABINET PLATE ASSEMBLY
ISOMETRIC VIEW





**FIGURE 1**
200A CABINET PLATE ASSEMBLY
TOP VIEW





**FIGURE 1**
200A CABINET PLATE ASSEMBLY
FRONT VIEW





**FIGURE 1**
200A CABINET PLATE ASSEMBLY
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 03/20/2020 | E | BILL OF MATERIALS UPDATE | ARC | MBL | JAS | KRG | 11/03/2022 |
| A | ORIGINAL | - | GLW | JES | CZH | 10/01/2018 | D | BILL OF MATERIALS UPDATE | EDM | ADW | GLW | KRG | 05/31/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

200A LIVEFRONT TO DEADFRONT TERMINATING CABINET

UG3517.1





**FIGURE 2**
200A FRONT VIEW




**FIGURE 3**
PLATE PHOTO





**FIGURE 4**
4-WAY DEADFRONT

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 03/20/2020 | E | BILL OF MATERIALS UPDATE | ARC | MBL | JAS | KRG | 11/03/2022 |
| A | ORIGINAL | - | GLW | JES | CZH | 10/01/2018 | D | BILL OF MATERIALS UPDATE | EDM | ADW | GLW | KRG | 05/31/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

200A LIVEFRONT TO DEADFRONT TERMINATING CABINET

UG3517.2

## INSTALLATION:

A. INSTALL #2, 2/0 OR 2SOL ELBOWS DEPENDING ON THE WIRE BEING INSTALLED.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PLATE, CABINET, 200A | 1 | -- | S168400 | BRK200A |
| 2 | 4 WAY DEADFRONT TERMINATION ASSEMBLY | AS REQ'D | 4179 | S718338 | TAP4NB |
| 3 | 3421 PAD | 1 | -- | S514240 | UG3421-1 |
| 4 | 3312 HANDHOLE (CONCRETE OR PVC BOX) (LEAVE LID IN YARD) | 1 | -- | S162424 | 3312-0 |
| 5 | CABINET, MVI/MVS, MULTI USE | 1 | 3580 | S190490 | DMV-12 |
| 6 | ASSEMBLY, BOLT, 2" | AS REQ'D | -- | S148800 | -- |
| 7 | ELBOWS AND WIRE, 200A | AS REQ'D | -- | -- | -- |
| 8 | WIRE, BARE COPPER 4/0 STR, SOFT DRAWN (IV) | AS REQ'D | -- | S812764 | 4/0-SD |
| 9 | RECEPTACLE, INSULATION, 200A (IV) | AS REQ'D | 4179-4180 | S204304 | INSREC |
| 10 | WIRE, BARE COPPER, #2, 7 STRANDED, SOFT DRAWN (IV) | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 11 | WIRE, #2 AU, U12.043 (IV) | AS REQ'D | 4002 | S197656 | RJN3/2 |
| 12 | WIRE, 2/0 AU, U12.061 (IV) | AS REQ'D | 4002 | S197648 | RJN2/0 |
| 13 | ELBOW, 200A, #2 (IV) | AS REQ'D | 4180 | S443838 | LBE-2A |
| 14 | ELBOW, 200A, 2/0 (IV) | AS REQ'D | 4180 | S443840 | LBE2/0 |

## NOTES:

I. WHEN REMOVING ANY LIVEFRONT EQUIPMENT AND INSTALLING THE NEW TERMINATOR CONVERSION CABINET REMOVE THE UNJACKETED CABLE AND INSTALL NEW JACKETED CABLE. DO NOT SPLICE UNJACKETED CABLE.

II. MAKE SURE WHEN MAKING UP THE NEW CABLE THAT THE CABLE IS MADE LONG ENOUGH TO BE INSTALLED ON THE STAND-OFF POSITION IN CASE OF DE-ENERGIZING THE CABLE BECAUSE OF TROUBLE USE THE 600/200A TERMINATOR PAD IF THE WIRE DOESN'T LINE UP IN THE 200A PAD.

III. TERMINATE THE CABLE WITH ENOUGH SLACK TO REACH THE STANDOFF POSITIONS ABOVE THE 4 WAYS.

(IV) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 03/20/2020 | E | BILL OF MATERIALS UPDATE | ARC | MBL | JAS | KRG | 11/03/2022 |
| A | ORIGINAL | - | GLW | JES | CZH | 10/01/2018 | D | BILL OF MATERIALS UPDATE | EDM | ADW | GLW | KRG | 05/31/2022 |

**SCOPE:** THIS STANDARD SHOWS THE ASSEMBLY OF A 600A CABINET PLATE.





**FIGURE 1**
600A CABINET PLATE ASSEMBLY

TABLE OF CONTENTS




**FIGURE 2**
600A AND 200A
COMBINATION





**FIGURE 2**
WITH LOAD TRACKER
FAULT INDICATORS



**FIGURE 2**
WITHOUT LOAD TRACKER
FAULT INDICATORS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | EJA | GLW | CZH | 11/12/2019 | E | EDITORIAL CHANGES | EDM | EJA | JAS | KRG | 04/11/2023 |
| A | ORIGINAL | - | GLW | JES | CZH | 10/01/2018 | D | EDITORIAL CHANGES | EDM | ADW | GLW | FRC | 02/14/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

600A LIVEFRONT TO DEADFRONT TERMINATING CABINET

UG3518.1





**FIGURE 3**
600A FRONT VIEW (V)

## INSTALLATION:

(A) INSTALL 200A REDUCING TAP WELLS FOR GROUNDING OR 200A CABLE WELLS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PLATE, CABINET, 304 STAINLESS STEEL, 600A | 1 | -- | S168402 | -- |
| 2 | TAP WELL, REDUCING, 200A (TAP PLUG, ELBOW) (III) | AS REQ'D | 4181 | S547328 | -- |
| 3 | 3421-600A PAD | 1 | -- | S514042 | UG3421-2 |
| 4 | HANDHOLE, CONCRETE, 3312 (OR LARGER) (C) | 1 | -- | S162476 | 3312-0 |
| 5 | ELBOW TEE BODY, 15KV, 600A W/ CAPACITIVE TEST POINT | 6 EACH | -- | S326578 | ELBO-T |
| 6 | ASSEMBLY, BOLT, 2" | AS REQ'D | -- | S148800 | -- |
| 7 | 200A ELBOWS AND WIRE (III) | AS REQ'D | -- | -- | -- |
| 8 | EXTENSION BUSHING, 600A W/ LOAD TAP PLUG | AS REQ'D | -- | S336198 | EXLRTP |
| 9 | RECEPTACLE, INSULATION, 200A | AS REQ'D | 4179-4180 | S204304 | INSREC |
| 10 | WIRE, BARE COPPER, #2, 7 STR., SOFT DRAWN | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 11 | WIRE, BARE COPPER, 4/0, STR., SOFT DRAWN | AS REQ'D | -- | S812764 | 4/0-SD |
| 12 | JUNCTION BAR, 600A CLEER, 15KV, LOADBREAK - SQUARE | 3 | 4198 | S439872 | CCL-SQ |
| 13 | CABINET, MVI/MVS, MULTI USE | 1 | 3580 | S190490 | DMV12 |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | EJA | GLW | CZH | 11/12/2019 | E | EDITORIAL CHANGES | EDM | EJA | JAS | KRG | 04/11/2023 |
| A | ORIGINAL | - | GLW | JES | CZH | 10/01/2018 | D | EDITORIAL CHANGES | EDM | ADW | GLW | FRC | 02/14/2022 |

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 14 | WIRE, #2 AU, U12.043 | AS REQ'D | 4004 | S197656 | RJN3/2 |
| 15 | WIRE, 2/0 AU, U12.061 | AS REQ'D | 4004 | S197648 | RJN2/0 |
| 16 | WIRE, 1000MCM | AS REQ'D | 4004 | S197654 | RJ1000 |
| 17 | ELBOW, 200A, #2 | AS REQ'D | 4180 | S443838 | LBE-2A |
| 18 | ELBOW, 200A, 2/0 | AS REQ'D | 4180 | S443840 | LBE2/0 |
| 19 | INDICATOR, FAULT, LOAD TRACKER (FI) (III)(V) | AS REQ'D | 4360 | S423714 | -- |

## NOTES:

I. WHEN REMOVING ANY LIVEFRONT EQUIPMENT AND INSTALLING THE NEW TERMINATOR CONVERSION CABINET REMOVE THE UNJACKETED CABLE AND INSTALL NEW JACKETED CABLE. DO NOT SPLICE EXISTING 600A CABLE.

II. MAKE SURE WHEN MAKING UP THE NEW CABLE THAT THE CABLE IS MADE LONG ENOUGH TO BE INSTALLED ON THE STAND-OFF POSITION IN CASE OF DE-ENERGIZING THE CABLE BECAUSE OF TROUBLE USE THE 600A/200A TERMINATOR PAD IF THE WIRE DOESN'T LINE UP IN THE 200A PAD.

(III) NOT SHOWN ON FIGURES.

IV. WHEN PIGGY BACKING OFF OF THE 600A TEE BODIES, USE DOUBLE ENDED CONNECTION PLUG. (S544832)

(V) LOAD TRACKER FAULT INDICATOR (FI) IS REQUIRED ON ALL 600A CLEER CONNECTOR INSTALLATIONS.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR ELBOWS AND TEE BODIES, SEE UG4183, TABLES 4 AND 5.

b. SEE UG4002 WHEN EXISTING 3-INCH CONDUIT IS ALREADY IN SERVICE.

(c) SEE SECTION 3300: SUBSTRUCTURES.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | FIGURE UPDATE | - | EJA | GLW | CZH | 11/12/2019 | E | EDITORIAL CHANGES | EDM | EJA | JAS | KRG | 04/11/2023 |
| A | ORIGINAL | - | GLW | JES | CZH | 10/01/2018 | D | EDITORIAL CHANGES | EDM | ADW | GLW | FRC | 02/14/2022 |

**SCOPE:** THIS STANDARD SHOWS THE PAD MOUNTED, SINGLE-PHASE, LOW PROFILE CABLE TERMINATING CABINET INSTALLATION REQUIREMENTS USED WHEN #2 CABLE IS TERMINATED OR PLANNED TO BE TERMINATED.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
SIDE VIEW





**FIGURE 1**
FRONT VIEW
EXPOSED

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | JS | TR | MDJ | 11/28/2016 | F | FORMATTING | EDM | JIK | - | - | 5/17/2021 |
| B | NO CHANGES-REAFFIRMED | - | JC | TR | JS/MDJ | 09/30/2015 | E | EDITORIAL CHANGES | - | SL | JES | CZH | 10/18/2019 |
| A | EDITORIAL CHANGES | - | JC | IL | MDJ | 02/28/2015 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 06/26/2017 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SINGLE-PHASE, LOW PROFILE CABLE TERMINATING CABINET, 6,930V

UG3522.1

TABLE OF CONTENTS






**FIGURE 2**
CABLE TAP INSTALLATION
W/3421 PAD




**DETAIL 1**
HOLD DOWN ASSEMBLY
TYPICAL BOTH SIDES

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | JS | TR | MDJ | 11/28/2016 | F | FORMATTING | EDM | JIK | - | - | 5/17/2021 |
| B | NO CHANGES-REAFFIRMED | - | JC | TR | JS/MDJ | 09/30/2015 | E | EDITORIAL CHANGES | - | SL | JES | CZH | 10/18/2019 |
| A | EDITORIAL CHANGES | - | JC | IL | MDJ | 02/28/2015 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 06/26/2017 |

## INSTALLATION:

(A) THIS INSTALLATION IS LIMITED TO A MAXIMUM OF 4 SINGLE-PHASE #2 AL PRIMARY CABLES WITH ONE 3 OR 4 WAY CABLE TAP.
(B) SET PAD AND HANDHOLE, INSTALL EQUIPMENT GROUND.
(C) TERMINATE CONDUITS AS SHOWN AND SEAL CONDUITS WITH SEALING COMPOUND.
(D) KEYLESS LOCK TO BE ATTACHED TO LATCHING MECHANISM ON CABINET AND PENTAHEAD BOLT TO BE THREADED IN COMPLETELY.
(E) FOR FIELD MAINTENANCE INSTALLS USE S732966/TERM-1.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABINET, LOW PROFILE CABLE TERMINATOR, SINGLE-PHASE (E) | 1 | 3522 | S190430 | SWTERM |
| 2 | PAD, TRANSFORMER/UTLITY EQUIPMENT, SINGLE-PHASE | 1 | 3421 | S514240 | FC3PAD |
| 3 | HANDHOLE | 1 | 3312 | S162426 | - |
| 4 | EQUIPMENT, PAD GROUNDING (m) | 1 | 4512 | - | - |
| 5 | RECEPTACLE, INSULATING (II) | AS REQ'D | 4180 | S204304 | - |
| 6 | ELBOW, LOADBREAK, 14.4KV 200A<br>ELBOW, LOADBREAK, FUSED 6930, 200A | AS REQ'D | 4190-4191 | - | - |
| 7 | LOCK, KEYLESS (D) (II) | 1 | - | S468010 | - |
| 8 | TAGS, IDENTIFICATION, CABLE | AS REQ'D | 3202 | - | - |
| 9 | CABLE TAP, 4-WAY | AS REQ'D | 4180 | - | TAP-4W |
| | CABLE TAP, 3-WAY | | | | TAP-3W |
| | PLUG, STAND-OFF | | | | S/OPLG |
| | BUSHING, FEED-THRU | | | | FEED-B |
| 10 | NUT, CLAMPING CHANNEL W/SPRING, 1/2" | 2 | - | S503520 | - |
| 11 | COMPOUND, SEALING (C) | AS REQ'D | - | S442976 | - |
| 12 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 2 1/2" | 2 | - | S616352 | - |
| 13 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 2 | - | S799488 | - |
| 14 | WASHER, LOCK, BRONZE, 1/2" | 2 | - | S796416 | - |

TABLE OF CONTENTS

## NOTES:

(I) TERMINATOR COMES WITH 5/8" X 1" SLOT IN CENTER OF FRAME UNISTRUT (TYPICAL BOTH SIDES)
(II) NOT SHOWN IN FIGURES.

## REFERENCE:

a. SEE UG3202 FOR CABLE IDENTIFICATION.
b. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION.
c. SEE UG3221 FOR HIGH VOLTAGE DECAL.
(d) SEE UG3408 FOR WIRE ENTRY PREVENTION.
e. SEE UG3421 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.
f. SEE UG3479 FOR BARRIER PROTECTION.
g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | JS | TR | MDJ | 11/28/2016 | F | FORMATTING | EDM | JIK | - | - | 5/17/2021 |
| B | NO CHANGES-REAFFIRMED | - | JC | TR | JS/MDJ | 09/30/2015 | E | EDITORIAL CHANGES | - | SL | JES | CZH | 10/18/2019 |
| A | EDITORIAL CHANGES | - | JC | IL | MDJ | 02/28/2015 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 06/26/2017 |

## REFERENCE (CONT'D):

h. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

i. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

j. SEE UG3489 FOR RETAINING WALLS.

k. SEE UG3605 AND UG3660 FOR SINGLE-PHASE SUBSURFACE SECTIONALIZING.

(l) SEE UG4108 FOR SEALING JACKETED CABLE.

(m) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

n. SEE UG4512 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(o) SEE UG4512 FOR EQUIPMENT GROUNDING.

p. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

(q) SEE UG4520 AND UG4521 (PREVIOUS # UG4520) FOR GROUNDING PAD MOUNTED EQUIPMENT.

r. SEE UG3675 FOR SINGLE PHASE MVI INSTALLATION.

s. SEE UG4191 FOR FUSED ELBOW INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | JS | TR | MDJ | 11/28/2016 | F | FORMATTING | EDM | JIK | - | - | 5/17/2021 |
| B | NO CHANGES-REAFFIRMED | - | JC | TR | JS/MDJ | 09/30/2015 | E | EDITORIAL CHANGES | - | SL | JES | CZH | 10/18/2019 |
| A | EDITORIAL CHANGES | - | JC | IL | MDJ | 02/28/2015 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 06/26/2017 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SINGLE-PHASE, LOW PROFILE CABLE TERMINATING CABINET, 6,930V

UG3522.4

**SCOPE:** THIS STANDARD SHOWS THE PAD MOUNTED, THREE-PHASE, LOW PROFILE, DEADFRONT, METAL TERMINATING CABINET.





**FIGURE 1** (V)
FRONT VIEW





**FIGURE 1**
ISOMETRIC VIEW






**FIGURE 1**
SIDE VIEW

**TABLE 1**

| RATINGS | |
|---|---|
| KV-BIL | 95 |
| AMPERES | 200 |
| WEIGHT (LBS) | 290 MAX. |

**UG MAP SYMBOL**




200A TERMINATING CABINET

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | EDM | RSL | JES | CZH | 12/12/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 05/17/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 08/11/2016 | D | | | | | | |






**FIGURE 2**
CABLE TAP INSTALLATION W/ 3416 PAD (VI)
FRONT VIEW




**DETAIL 1**
HOLD-DOWN ASSEMBLY
TYPICAL BOTH SIDES OF EQUIPMENT PAD

## INSTALLATION:

(A) SEAL CONDUITS WITH SEALING COMPOUND.
(B) BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT POSSIBLE WIRE ENTRY.
(C) FUSED ELBOWS 1 PER CABLE TAP.
(D) KEYLESS LOCK TO BE ATTACHED TO LATCHING MECHANISM ON CABINET AND PENTAHEAD BOLT TO BE THREADED IN COMPLETELY.
(E) CABLE TAP PLATES SUPPLIED WITH CABINET ARE ADJUSTABLE & REMOVABLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO UNITS |
|---|---|---|---|---|---|---|
| 1 | CABINET, THREE-PHASE TERMINATING | 1 | -- | S732974 | CT-CAB | -- |
| 2 | PAD, 3416 | 1 | 3416 | S514020 | PAD1 | 3416PAD |
| 3 | HANDHOLE, 3311, 14" X 66" X 14" | 1 | 3311 | S162660 | PAD2 | |
| 4 | WIRE, TRENCH GROUND (i) | AS REQ'D | 4510 | -- | -- | -- |
| 5 | ELBOW, LOADBREAK, 14.4KV, 200A (C) | AS REQ'D | 4191 | -- | -- | -- |
| 6 | RECEPTACLE, INSULATING | AS REQ'D | 4195 | S204304 | INSREC | -- |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | EDM | RSL | JES | CZH | 12/12/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 05/17/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 08/11/2016 | D | | | | | | |



TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO UNITS |
|---|---|---|---|---|---|---|
| 7 | CABLE TAP, 4 WAY ONLY, (WITHOUT BRACKET) | 3 | 4195 | -- | -- | -- |
| 8 | NUT, CLAMPING CHANNEL, W/ SPRING, 1/2" | 4 | -- | S505520 | -- | -- |
| 9 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 4 | -- | S616192 | -- | -- |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 4 | -- | S799488 | -- | -- |
| 11 | HOLD DOWN (SUPPLIED WITH CABINET) | 4 | -- | - | -- | -- |
| 12 | SEALING COMPOUND (A) | AS REQ'D | -- | S442976 | -- | -- |
| 13 | LOCK, KEYLESS (D) | 1 | -- | S468010 | -- | -- |
| 14 | TAG, CABLE IDENTIFICATION | AS REQ'D | 3202 | -- | -- | -- |

## NOTES:

I. THE PAD MOUNTED TERMINATOR IS DESIGNED FOR 2/0 AND SMALLER 15KV CABLES.

II. THIS TERMINATOR MAY ALSO REPLACE LIVEFRONT TERMINATORS, IF SPACE IS AVAILABLE.

III. THIS TERMINATOR AND PAD SHOULD BE LOCATED IN AREAS THAT ARE FLAT AND CONCRETED, SUCH AS AREAS NEXT TO SIDEWALKS AND STREETS, THAT PROVIDE ADEQUATE WORK SPACE AND LIVE-LINE TOOL OPERATION SPACE.

IV. SECONDARY CABLES MAY BE TERMINATED IN THIS TERMINATING FACILITY BY DEVIATION ONLY.

(V) CABLE TAP PLATES ARE SUPPLIED WITH CABINET.

(VI) PAD MOUNTED INSTALLATION WHEN TERMINATING 2/0 AND SMALLER CABLE.

## REFERENCE:

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

b. SEE UG3408 FOR WIRE ENTRY PREVENTION AND MOISTURE ENTRY.

(c) SEE UG3416 FOR PAD AND HANDHOLE INSTALLATION.

d. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

e. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

f. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

g. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3489 FOR RETAINING WALLS.

(i) SEE UG4510 FOR STANDARD AND ALTERNATE TRENCH GROUND WIRE.

(j) SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

(k) SEE UG4520-UG4521 FOR GROUNDING PAD MOUNTED EQUIPMENT.

(l) SEE UG4525 FOR GROUNDING CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS

m. SEE UG3202 FOR CABLE IDENTIFICATION.

n. SEE UG3203 FOR PULLING AND MEASURING TAPE, CONDUIT, AND CONDUIT KNOCKOUT IDENTIFICATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | EDM | RSL | JES | CZH | 12/12/2021 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 05/17/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 08/11/2016 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE LOW PROFILE CABLE TERMINATING CABINET
12KV, 200A

UG3523.3

**SCOPE:** THIS STANDARD SHOWS THE 600A/200A PAD MOUNTED LOW PROFILE TERMINATING CABINET (FOR FIELD MAINTENANCE).






**FIGURE 1**
FRONT VIEW

**TABLE 1**

| RATINGS | |
|---|---|
| KV-BIL | 95 |
| AMPERES | 600 |
| WEIGHT | 290 LBS MAX. |

**UG MAP SYMBOL**








**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 1**
SIDE VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 4/11/2012 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE LOW PROFILE CABLE
TERMINATING CABINET 12KV, 600A/200A



UG3524.1

TABLE OF CONTENTS

TABLE OF CONTENTS





**FIGURE 2**
FRONT VIEW
600A/200A JUNCTION & CABLE INSTALLATION
WITH 3410 NEW PAD





**FIGURE 3**
HOLD-DOWN ASSEMBLY DETAIL
TYPICAL BOTH SIDES OF EQUIPMENT PAD

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 4/11/2012 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE LOW PROFILE CABLE
TERMINATING CABINET 12KV, 600A/200A

UG3524.2

## INSTALLATION:

(A) SEAL CONDUITS WITH SEALING COMPOUND.

(B) BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT POSSIBLE WIRE ENTRY.

(C) FUSED ELBOWS AND SECONDARIES ARE ACCEPTABLE.

(D) KEYLESS LOCK TO BE ATTACHED TO LATCHING MECHANISM ON CABINET AND PENTAHEAD BOLT TO BE THREADED IN COMPLETELY.

(E) JUNCTION SUPPORT PLATES SUPPLIED WITH CABINET ARE REMOVABLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABINET, THREE-PHASE CABLE TERMINATING | 1 | 3524 | S732944 | MT-CAB |
| 2 | PAD, 3410 | 1 | 3410 | S514260 | 3410 |
| 3 | HANDHOLE, EXISTING | 1 | - | - | - |
| 4 | JUNCTION, 600A/200A | 3 | 4186 | S439860 | JUN6/2 |
| 5 | ELBOW, LOADBREAK, 14.4KV, 200A (A) | AS REQ'D | 4191 | - | - |
| 6 | RECEPTABLE, INSULATING | AS REQ'D | 4195 | S204304 | INSREC |
| 7 | TEE, ELBOW | AS REQ'D | - | S326578 | ELBO-T |
| 8 | NUT, CLAMPING CHANNEL, W/SPRING, 1/2" | 4 | - | S505520 | - |
| 9 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 4 | - | S616192 | - |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 4 | - | S799488 | - |
| 11 | HOLD DOWN (SUPPLIED WITH CABINET) | 4 | - | - | - |
| 12 | SEALING COMPOUND (A) (I) | AS REQ'D | - | S442976 | - |
| 13 | KEYLESS LOCK (D) (I) | 1 | - | S468010 | - |
| 14 | CABLE IDENTIFICATION TAGS | AS REQ'D | 3202 | - | - |
| 15 | ADAPTER, FOR CABLE ARMS | AS REQ'D | 4177/4178 | S102016 | - |
| 16 | CABLE ARMS, 2, 3 OR 4 POSITIONS | AS REQ'D | 4177/4178 | - | - |
| 17 | CABLE INSULATORS | AS REQ'D | 4177/4178 | S430592 | - |
| 18 | HANGER, FOR CABLE ARMS | AS REQ'D | 4177/4178 | S564480 | - |
| 19 | HANGER, 30" | 2 | - | S503520 | - |

## NOTES:

(I) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

b. SEE UG3408 FOR WIRE ENTRY PREVENTION.

c. SEE UG3410 FOR PAD INSTALLATION.

d. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

e. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

f. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

g. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3489 FOR RETAINING WALLS.

(i) SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

(j) SEE UG4520 AND UG4521 (PREVIOUS # UG4520) FOR GROUNDING PAD MOUNTED EQUIPMENT.

(k) SEE UG4525 FOR GROUNDING CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 4/11/2012 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE LOW PROFILE CABLE TERMINATING CABINET 12KV, 600A/200A

UG3524.3

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD COVERS PAD MOUNTED 600A, 15KV THREE-PHASE LIQUID INSULATED VACUUM SWITCH GEAR WITH VISIBLE DISCONNECTS.

**ATTENTION:**

* DUE TO DIVERSE ENVIRONMENTAL CONDITIONS, THE SWITCH GEAR IS CONSTRUCTED OF STAINLESS STEEL. THE LIQUID INSULATION IS NOT SUBJECTED TO ARC CONTAMINATION DURING SWITCHING AND WILL NOT REQUIRE TESTING.

**TABLE 1**

| ELECTRICAL RATINGS | |
|---|---|
| VOLTAGE | 15.5KV |
| CURRENT, CONTINUES | 600A |
| B.I.L | 95KV |
| MAXIMUM INTERRUPTING CURRENT VFI | 12.5KA - (SYMMETRICAL) |
| MOMENTARY MAKE AND LATCH | 20KA - (ASYMMETRICAL) |
| B.I.L. ACROSS OPEN VFI | 125KV |

**TABLE 2**

| SWITCH INFORMATION | | |
|---|---|---|
| **TYPE OF SWITCH** | **STOCK NUMBER** | **DESIGN UNITS** |
| 4-WAY MANUAL SWITCH | S709052 | 4WAYTM |
| 4-WAY SCADA SWITCH | S704732 | 4WAYTS |
| 5-WAY SCADA SWITCH | S704734 | 5WAYTS |
| 4-WAY SCADA SWITCH 2-SIDED | S704736 | 4WTPES |
| 4-WAY SCADA SWITCH HSTC | S704738 | 4WTFTS |

TABLE OF CONTENTS

**TABLE 3**

| SWITCH GEAR INTERNAL DESIGNATION LOCATIONS | |
|---|---|
| **DESIGNATION** | **LOCATION** |
| L | LEFT |
| S | 4TH POSITION |
| T | TAP |
| R | RIGHT |






**FIGURE 1**
4-WAY MANUAL CONNECTION DIAGRAM
(SEE TABLE 3)

**UG MAP SYMBOL**




© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | REFERENCE UPDATE | EDM | JIK | JES | CZH | 07/28/2021 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | EDITORIAL CHANGES | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |






**FIGURE 2**
4-WAY SCADA CONNECTION DIAGRAM

**UG MAP SYMBOL**









**FIGURE 3**
5-WAY SCADA CONNECTION DIAGRAM

**UG MAP SYMBOL**








**FIGURE 4**
4-WAY 2 SIDED SCADA CONNECTION DIAGRAM

**UG MAP SYMBOL**





TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | REFERENCE UPDATE | EDM | JIK | JES | CZH | 07/28/2021 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | EDITORIAL CHANGES | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

TABLE OF CONTENTS






**FIGURE 5**




**DETAIL 1**
HOLD DOWN
(USE STAINLESS STEEL TIE DOWNS PROVIDED)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | REFERENCE UPDATE | EDM | JIK | JES | CZH | 07/28/2021 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | EDITORIAL CHANGES | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

## INSTALLATION:

(A) SEAL ALL CONDUITS WITH SEALING COMPOUND.

(B) SET THE SWITCH ON THE BOX PAD. USING A 1/2 INCH DRILL BIT, DRILL THROUGH THE EXISTING HOLES IN THE SILL FLANGE AND THROUGH THE BOX PAD. BOLT DOWN AS SHOWN IN DETAIL 1.

(C) BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT POSSIBLE WIRE ENTRY.

(D) SECURE THE SWITCH DOORS AND THE SWITCH OPERATING HANDLE COVERS WITH LEVEL 3 LOCKS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 4-WAY MANUAL (IX) | 1 | -- | -- | -- |
| | 4-WAY SCADA (IX) | 1 | -- | -- | -- |
| 2 | 5-WAY SCADA (IX) | 1 | -- | -- | -- |
| 3 | 4-WAY SCADA, 2 SIDED (SEE 3423 BOX PAD) (IX) | 1 | -- | -- | -- |
| 4 | BOX PAD | 1 | 3428/3429/3423 | AS REQ'D | AS REQ'D |
| 5 | CONNECTORS, 12KV 600/200A (IX) | AS REQ'D | 4186 | -- | -- |
| 6 | PADLOCK | 2 | -- | S514848 | 4WTFTS |
| 7 | SCADA ANTENNA INSTALLATION | -- | 4640 | -- | -- |
| 8 | CONNECTOR POST, 1/0 (IX) | 5 | -- | S262560 | SPCONN |
| 9 | WIRE, COPPER, 4/0 (IX) | AS REQ'D | 4520.8, .9 | S812764 | 4/0-SD |
| 10 | WIRE, BARE COPPER, #2 7 STR. SOFT-DRAWN | 1 | 4510 | S812818 (X) | TG-E-W |
| 11 | SEALING COMPOUND (IX) | AS REQ'D | 3948.1 | S442976 | SEAL-6 |
| 12 | SWITCH POSITION TAGGING | -- | 3212.2 | -- | -- |
| 13 | EYE BOLT, STAINLESS STEEL, 6" X 1/2" | 1 | -- | S150582 | -- |
| 14 | BRACKET, ANGLE, STAINLESS STEEL, 2" X 3" | 2 | -- | S166072 | -- |
| 15 | BOLT, TIE DOWN, STAINLESS STEEL, 3 1/2" X 1/2" (B) | 4 | -- | S148804 | -- |
| 16 | WASHER, STANDARD FLAT BRONZE, 1/2" | 8 | -- | S799488 | -- |
| 17 | WASHER, LOCK SPRING | 4 | -- | S796416 | -- |
| 18 | CABLE IDENTIFICATION TAGS (IX) | AS REQ'D | 3202.3 | -- | -- |
| 19 | ANCHOR, CONCRETE, STAINLESS STEEL, 1/2" X 3 3/4" (VIII) | 4 | -- | S107654 | CNCANC |
| 20 | INTEGRATED REMOTE TERMINAL (SCADA ONLY) | 1 | -- | -- | -- |

## NOTES:

### APPLICATION:

I. THE FOOTPRINT OF THE SWITCH AND UP FRONT WORK SPACE WILL ALLOW IT TO BE INSTALLED ON THE W SERIES SWITCH FACILITIES INCLUDING 3440, 3441 PADS ON HAND HOLES AND THE TROUGH STYLE SWITCH PADS. IT MAY BE USED WHEN LIMITED RIGHT-OF-WAY ISSUES EXIST FOR CONVERSIONS AND WHERE THERE IS LIMITED SPACE FOR NEW CONSTRUCTION.

II. FOR NEW CONSTRUCTION, THE WAY POSITION MARKED T (THIRD POSITION FROM THE LEFT) SHALL BE USED AS THE OPEN TIE FOR ALL SWITCHES. WHEN REPLACING EXISTING SWITCHES, THE TIE POSITIONS ARE ESTABLISHED AND CONNECTED AS DESIGNED TO AVOID MAJOR RE-CABLING. CONNECT AS BUILT.

III. THE USE OF FUSED ELBOWS WILL BE LIMITED TO ONE FUSED ELBOW ONLY ON THE RIGHT OR LEFT SIDE SWITCH WAY POSITION. NO DEVIATION WILL BE GRANTED FOR MORE THAN ONE FUSED ELBOW IN SWITCH CABINET.

IV. TAPPING THE BACK OF 600A TEES FOR 200A DISTRIBUTION WILL BE LIMITED TO SWITCH CHANGE OUTS WITH EXISTING 200A TAPS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | REFERENCE UPDATE | EDM | JIK | JES | CZH | 07/28/2021 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | EDITORIAL CHANGES | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |



TABLE OF CONTENTS

## NOTES (CONT'D):

V. ROUTINE REPLACEMENT OF EXISTING 4-WAY PADMOUNT SWITCHES IS LIMITED TO THE 'W' TYPE CONFIGURATIONS ABOVE 3315 & 3316 HH'S AND THE 'D' TYPE CONFIGURATIONS ABOVE 3311 HH'S.

VI. ANOTHER 'D' CONFIGURATION CONSISTS OF SUBSURFACE SWITCHES MOUNTED ABOVE 3315 HH'S. THESE DO NOT LEND THEMSELVES TO SIMPLE REPLACEMENT OF THE SWITCH. THESE INSTALLATIONS ARE COMMONLY CALLED 'I-BEAM' OR 'RAIL' SWITCHES. A DEVIATION REQUEST IS REQUIRED WHEN ATTEMPTING TO REPLACE THESE WITH A PADMOUNT STYLE SWITCH.

VII. FOR NEW CONSTRUCTION AND CONVERSIONS THIS SWITCH SHOULD NOT BE USED TO TAP FEEDER CABLES. TAPS ON THE BACK OF 600A TEES IMPEDE GROUNDING AND LIMIT USE OF SWITCH POSITIONS DURING ROUTINE SWITCHING PROCEDURES AND OUTAGE SITUATIONS. TAP FEEDER SEGMENTS BETWEEN SWITCH POSITIONS USING 600A TERMINATORS OR TAP THE SWITCH POSITION WITH DISTRIBUTION CABLE ONLY.

(VIII) USE WHEN MOUNTING ON CONCRETE PAD.

(IX) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) SEE UG3202 FOR CABLE IDENTIFICATION.

b. SEE UG3211 FOR ATTACHING STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

c. SEE UG3221 FOR HIGH VOLTAGE DECAL.

d. SEE UG3408 FOR WIRE ENTRY PREVENTION.

e. SEE UG3428 & UG3429 FOR BOX PAD AND CONDUIT PLACEMENT.

f. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

g. SEE UG3480, UG3481, UG3482 & UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

h. SEE UG3486 & UG3487 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

i. SEE UG3489 FOR RETAINING WALLS.

j. SEE UG3212.3 & 4 FOR PAD MOUNTED SWITCH IDENTIFICATION.

k. SEE UG4355 FOR FAULT INDICATOR INSTALLATION.

l. SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE TRENCH GROUND WIRE).

m. SEE UG4520 FOR EQUIPMENT GROUNDING.

n. SEE UG4525 FOR GROUNDING PREMOLDED CONNECTORS.

o. SEE UG4521 (PREVIOUS # UG4520.8-.9) FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

(p) SEE UG4642 FOR SCADA INSTALLATION.

(q) SEE UG4181 FOR 600A/200A CONNECTIONS.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | REFERENCE UPDATE | EDM | JIK | JES | CZH | 07/28/2021 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | EDITORIAL CHANGES | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

**SCOPE:** THIS STANDARD ILLUSTRATES A 4-WAY MANUAL SWITCH.





**FIGURE 1**
FRONT VIEW
SEE TABLE 1





**FIGURE 1**
SIDE VIEW
SEE TABLE 1





**FIGURE 2**
FRONT VIEW
CABINET REMOVED
SEE TABLE 1

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

4-WAY MANUAL

UG3551.1

TABLE OF CONTENTS

## TABLE 1

| PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | WINDOW, FAULT INDICATOR |
| 2 | EYE, LIFTING |
| 3 | CABINET, SCADA |
| 4 | HANDLE, CABINET, PAD LOCKABLE |
| 5 | FUSE, POWER TRANSFORMER DRY WELL, 8.3KV, 3A CL |
| 6 | NAMEPLATE |
| 7 | ACTUATOR, DC LINEAR, 24V |
| 8 | PLUG, OIL FILL |
| 9 | INDICATOR, FAULT TRIP |
| 10 | NUTS, EQUIPMENT GROUND, 1/2" |
| 11 | BUSHING/CONNECTOR, 600A |
| 12 | DISCONNECT, VISIBLE, WINDOW VIEW TRI-PHASE |
| 13 | PARKING STAND |
| 14 | PROVISION FOR ROPE OPERATION |
| 15 | HANDLE, TRI-PHASE VISIBLE DISCONNECT OPERATOR |
| 16 | HANDLE, VACUUM SWITCH OPERATING |
| 17 | BOLT, PENTA, PAD LOCKABLE |
| 18 | LIQUID LEVEL GAUGE, 901A |
| 19 | ANTENNA CONNECTION, SCADA |
| 20 | DECAL: "PULL TO CLOSE MANUALLY" |
| 21 | HANDLE, HIGH SPEED TRIP CLOSE MANUAL |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WEIGHT: 4,350 LBS.

**REFERENCE:**

a. FOR ADDITIONAL INFORMATION, SEE UG3550.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

**SCOPE:** THIS STANDARD ILLUSTRATES A 4-WAY SCADA SWITCH.





**FIGURE 1**
FRONT VIEW
SEE TABLE 1





**FIGURE 1**
SIDE VIEW
SEE TABLE 1





**FIGURE 1**
FRONT VIEW
CABINET REMOVED
SEE TABLE 1

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed

SHEET 1 OF 2

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

4-WAY SCADA

UG3552.1

TABLE OF CONTENTS

TABLE OF CONTENTS

## TABLE 1

| PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | WINDOW, FAULT INDICATOR |
| 2 | EYE, LIFTING |
| 3 | CABINET, SCADA |
| 4 | HANDLE, CABINET, PAD LOCKABLE |
| 5 | FUSE, POWER TRANSFORMER DRY WELL, 8.3KV, 3A CL |
| 6 | NAMEPLATE |
| 7 | ACTUATOR, DC LINEAR, 24V |
| 8 | PLUG, OIL FILL |
| 9 | INDICATOR, FAULT TRIP |
| 10 | NUTS, EQUIPMENT GROUND, 1/2" |
| 11 | BUSHING/CONNECTOR, 600A |
| 12 | DISCONNECT, VISIBLE, WINDOW VIEW TRI-PHASE |
| 13 | PARKING STAND |
| 14 | PROVISION FOR ROPE OPERATION |
| 15 | HANDLE, TRI-PHASE VISIBLE DISCONNECT OPERATOR |
| 16 | HANDLE, VACUUM SWITCH OPERATING |
| 17 | BOLT, PENTA, PAD LOCKABLE |
| 18 | LIQUID LEVEL GAUGE, 901A |
| 19 | ANTENNA CONNECTION, SCADA |
| 20 | DECAL: "PULL TO CLOSE MANUALLY" |
| 21 | HANDLE, HIGH SPEED TRIP CLOSE MANUAL |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WEIGHT: 5,535 LBS.

**REFERENCE:**

a. FOR ADDITIONAL INFORMATION, SEE UG3550.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

**SCOPE:** THIS STANDARD ILLUSTRATES A 4-WAY SCADA HIGH SPEED TRIP COIL SWITCH.

**CAUTION:**

* THE 4-WAY SCADA HIGH SPEED TRIP COIL SWITCH IS ONLY TO BE USED FOR RENEWABLE ENERGY/ALTERNATIVE RESOURCES SUCH AS BATTERY STORAGE FACILITIES.






**FIGURE 1**
4-WAY SCADA HIGH SPEED TRIP COIL
CONNECTION DIAGRAM








**FIGURE 2**
FRONT VIEW
CABINET REMOVED
SEE TABLE 1

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

4-WAY SCADA
HIGH SPEED TRIP COIL

UG3553.1

TABLE OF CONTENTS

TABLE OF CONTENTS

## TABLE 1

| PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | WINDOW, FAULT INDICATOR |
| 2 | EYE, LIFTING |
| 3 | CABINET, SCADA |
| 4 | HANDLE, CABINET, PAD LOCKABLE |
| 5 | FUSE, POWER TRANSFORMER DRY WELL, 8.3KV, 3A CL |
| 6 | NAMEPLATE |
| 7 | ACTUATOR, DC LINEAR, 24V |
| 8 | PLUG, OIL FILL |
| 9 | INDICATOR, FAULT TRIP |
| 10 | NUTS, EQUIPMENT GROUND, 1/2" |
| 11 | BUSHING/CONNECTOR, 600A |
| 12 | DISCONNECT, VISIBLE, WINDOW VIEW TRI-PHASE |
| 13 | PARKING STAND |
| 14 | PROVISION FOR ROPE OPERATION |
| 15 | HANDLE, TRI-PHASE VISIBLE DISCONNECT OPERATOR |
| 16 | HANDLE, VACUUM SWITCH OPERATING |
| 17 | BOLT, PENTA, PAD LOCKABLE |
| 18 | LIQUID LEVEL GAUGE, 901A |
| 19 | ANTENNA CONNECTION, SCADA |
| 20 | DECAL: "PULL TO CLOSE MANUALLY" |
| 21 | HANDLE, HIGH SPEED TRIP CLOSE MANUAL |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WEIGHT: 5,535 LBS.

II. ENCLOSURE DIMENSIONS ARE THE SAME AS THE 4-WAY SCADA SWITCH. (a)

(III) WAY THREE CONTAINS A HIGH SPEED CLOSE COIL THAT CAN BE OPERATED VIA THE 487E RELAY OR THE MANUAL CLOSE HANDLE.

**REFERENCE:**

(a) SEE UG3552.

b. FOR ADDITIONAL INFORMATION, SEE UG3550.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

**SCOPE:** THIS STANDARD ILLUSTRATES A 2-SIDED 4-WAY SCADA SWITCH.





**FIGURE 1**
FRONT VIEW
CABINET REMOVED
SEE TABLE 1





**FIGURE 1**
SIDE VIEW
SEE TABLE 1





**FIGURE 1**
REAR VIEW
CABINET REMOVED
SEE TABLE 1

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



2 SIDED 4-WAY SCADA

UG3554.1

TABLE OF CONTENTS

## TABLE 1

| PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | WINDOW, FAULT INDICATOR |
| 2 | EYE, LIFTING |
| 3 | CABINET, SCADA |
| 4 | HANDLE, CABINET, PAD LOCKABLE |
| 5 | FUSE, POWER TRANSFORMER DRY WELL, 8.3KV, 3A CL |
| 6 | NAMEPLATE |
| 7 | ACTUATOR, DC LINEAR, 24V |
| 8 | PLUG, OIL FILL |
| 9 | INDICATOR, FAULT TRIP |
| 10 | NUTS, EQUIPMENT GROUND, 1/2" |
| 11 | BUSHING/CONNECTOR, 600A |
| 12 | DISCONNECT, VISIBLE, WINDOW VIEW TRI-PHASE |
| 13 | PARKING STAND |
| 14 | PROVISION FOR ROPE OPERATION |
| 15 | HANDLE, TRI-PHASE VISIBLE DISCONNECT OPERATOR |
| 16 | HANDLE, VACUUM SWITCH OPERATING |
| 17 | BOLT, PENTA, PAD LOCKABLE |
| 18 | LIQUID LEVEL GAUGE, 901A |
| 19 | ANTENNA CONNECTION, SCADA |
| 20 | DECAL: "PULL TO CLOSE MANUALLY" |
| 21 | HANDLE, HIGH SPEED TRIP CLOSE MANUAL |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WEIGHT: 5,545 LBS.

**REFERENCE:**

a. FOR ADDITIONAL INFORMATION, SEE UG3550.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | TABLE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | EJA | GLW | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

**SCOPE:** THIS STANDARD ILLUSTRATES A 5-WAY SCADA SWITCH.





**FIGURE 1**
FRONT VIEW
SEE TABLE 1





**FIGURE 1**
SIDE VIEW
SEE TABLE 1





**FIGURE 1**
FRONT VIEW
CABINET REMOVED
SEE TABLE 1

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | SCOPE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



5-WAY SCADA

UG3555.1

## TABLE 1

| PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | WINDOW, FAULT INDICATOR |
| 2 | EYE, LIFTING |
| 3 | CABINET, SCADA |
| 4 | HANDLE, CABINET, PAD LOCKABLE |
| 5 | FUSE, POWER TRANSFORMER DRY WELL, 8.3KV, 3A CL |
| 6 | NAMEPLATE |
| 7 | ACTUATOR, DC LINEAR, 24V |
| 8 | PLUG, OIL FILL |
| 9 | INDICATOR, FAULT TRIP |
| 10 | NUTS, EQUIPMENT GROUND, 1/2" |
| 11 | BUSHING/CONNECTOR, 600A |
| 12 | DISCONNECT, VISIBLE, WINDOW VIEW TRI-PHASE |
| 13 | PARKING STAND |
| 14 | PROVISION FOR ROPE OPERATION |
| 15 | HANDLE, TRI-PHASE VISIBLE DISCONNECT OPERATOR |
| 16 | HANDLE, VACUUM SWITCH OPERATING |
| 17 | BOLT, PENTA, PAD LOCKABLE |
| 18 | LIQUID LEVEL GAUGE, 901A |
| 19 | ANTENNA CONNECTION, SCADA |
| 20 | DECAL: "PULL TO CLOSE MANUALLY" |
| 21 | HANDLE, HIGH SPEED TRIP CLOSE MANUAL |

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. WEIGHT: 6,450 LBS.

**REFERENCE:**

a. FOR ADDITIONAL INFORMATION, SEE UG3550.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | TABLE UPDATE | - | JBH | TR | MDJ | 08/05/2016 | H | SCOPE UPDATE | EDM | ADW | GLW | KRG | 06/29/2022 |
| D | REVISION | - | - | - | RR/DW | 06/25/2014 | G | MOVED FROM UG3550 | EDM | JIK | JES | CZH | 05/16/2021 |
| C | REVISION | - | - | - | RR/DW | 02/07/2014 | F | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 |

**SCOPE:** THIS STANDARD COVERS PAD & WALL MOUNTED (200 & 600 AMP) INNOVATIVE SWITCH GEARS, 15KV THREE PHASE SOLID-DIELECTRIC-IN-AIR, AND COMES AS A VACUUM LOAD-BREAK SWITCH, AS WELL AS A VACUUM FAULT INTERRUPTER WITH VISIBLE DISCONNECTS. DUE TO DIVERSE ENVIRONMENTAL CONDITIONS THE SWITCH GEAR IS CONSTRUCTED OF STAINLESS STEEL AND POWDER COATED.

## ATTENTION:

* SINGLE SIDED SWITCHES, NEVER LIFT THE PALLET BY THE PADMOUNT ENCLOSURE. THE BOLTS HOLDING THE ENCLOSURE TO THE PALLET WILL NOT SUPPORT THE WEIGHT OF THE SWITCH TANK AND STAND INSIDE.

** THIS WARNING DOES NOT APPLY TO THE FOUR WAY, TWO SIDED SWITCH AS THE TANK AND CABINET ARE ASSEMBLED TOGETHER BY THE MANUFACTURER.

*** ISG SWITCHES ARE RATED FOR 12KV USAGE. FOR A 4KV RATED SWITCH REMOVE THE 12KV PT AND INSTALL A 4KV PT. CONTACT KEARNY SCADA CREW FOR JOINT MEET TO COMPLETE.

**TABLE 1**

| INNOVATIVE SWITCH GEAR ELECTRICAL RATINGS | | |
|---|---|---|
| | **SCADA** | **MANUAL** |
| VOLTAGE | 15.5KV/4KV | 25KV |
| CURRENT, CONTINUOUS | 600 AMP/200 AMP | |
| B.I.L. | 95KV | |
| MAXIMUM INTERRUPTING CURRENT VACCUM FAULT INTERRUPTER | 12.5KA (SYMMETRICAL)<br>20KA (ASYMMETRICAL) AT 32.5 KA PEAK CURRENT | |
| MOMENTARY MAKE AND LATCH | 12.5KA (SYMMETRICAL)<br>20KA (ASYMMETRICAL) AT 32.5 KA PEAK CURRENT | |
| B.I.L. ACROSS OPEN VACUUM FAULT INTERRUPTER | 125KV | |

## INSTALLATION:

SEE SHEET 3560.40

*IF VIEWING AS AN ELECTRONIC PDF* **CLICK HERE** *TO JUMP TO "INSTALLATIONS".*

## NOTES:

SEE SHEET 3560.49

*IF VIEWING AS AN ELECTRONIC PDF* **CLICK HERE** *TO JUMP TO "NOTES".*

## REFERENCE:

SEE SHEET 3560.50

*IF VIEWING AS AN ELECTRONIC PDF* **CLICK HERE** *TO JUMP TO "REFERENCES".*

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 3560.3 | IN/OUT WALL MOUNT MANUAL 200AMP |
| 3560.6 | IN/OUT WALL MOUNT MANUAL 600AMP |
| 3560.9 | IN/OUT SINGLE SIDED MANUAL 200AMP |
| 3560.12 | IN/OUT SINGLE SIDED SCADA 200AMP |
| 3560.15 | IN/OUT SINGLE SIDED MANUAL 600AMP |
| 3560.18 | IN/OUT SINGLE SIDED SCADA 600AMP |
| 3560.21 | 4-WAY SINGLE SIDED MANUAL 600AMP |
| 3560.24 | 4-WAY SINGLE SIDED SCADA 600AMP |
| 3560.27 | 5-WAY SINGLE SIDED SCADA 600AMP |
| 3560.30 | 6-WAY SINGLE SIDED SCADA 600AMP |
| 3560.33 | PAD, BOX (USED WITH 6-WAY SINGLE SIDED) |
| 3560.34 | 4-WAY DOUBLE SIDED MANUAL 600AMP |
| 3560.37 | 4-WAY DOUBLE SIDED SCADA 600AMP |
| 3560.40 | INSTALLATION |
| 3560.49 | NOTES |
| 3560.50 | REFERENCE |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT
TABLE OF CONTENTS

## IN/OUT WALL MOUNT 200A MANUAL/ NON-SCADA

**ATTENTION:**

CURRENTLY ALLOWED TO BE INSTALLED IN MANHOLES AND VAULTS





**FIGURE 1**
FRONT VIEW





**FIGURE 2**
SIDE VIEW




**FIGURE 3**
ISOMETRIC VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |





**FIGURE 1**
IN/OUT WALL MOUNT 200A MANUAL
CONNECTION DIAGRAM





**FIGURE 2**
MAP SYMBOL





**FIGURE 3**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| S201022-007 SWITCH TANK | 420 LBS |
| MOTOR OPERATOR | 35 LBS |
| PENDANT | 20 LBS |
| RELAY | 30 LBS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## IN/OUT WALL MOUNT 200A MANUAL/ NON-SCADA

### BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | IN/OUT WALL MOUNT 200A MANUAL (ISG) | 1 | - | S190460 | IS2WFM |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 6 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 7 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 8 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 9 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 11 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 12 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 13 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 14 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 15 | PADLOCK | AS REQ. | - | S514848 | - |
| 16 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 17 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 18 | HEADER BOARDS (INCLUDES TIME TO I & R) | AS REQ. | - | - | H-BRDS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## IN/OUT WALL MOUNT 600A MANUAL/ NON-SCADA

**ATTENTION:**

CURRENTLY ALLOWED TO BE INSTALLED IN MANHOLES AND VAULTS





**FIGURE 1**
FRONT VIEW





**FIGURE 2**
SIDE VIEW




**FIGURE 3**
ISOMETRIC VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision | X | Completely Revised | New Page | Information Removed





**FIGURE 1**
IN/OUT WALL MOUNT 600A MANUAL
CONNECTION DIAGRAM





**FIGURE 2**
MAP SYMBOL





**FIGURE 3**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| S201066-007 SWITCH TANK | 420 LBS |
| MOTOR OPERATOR | 35 LBS |
| PENDANT | 20 LBS |
| RELAY | 20 LBS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## IN/OUT WALL MOUNT 600A MANUAL/ NON-SCADA

### BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | IN/OUT WALL MOUNT 600A MANUAL (ISG) | 1 | - | S704750 | 1S2W6M |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | PADLOCK | AS REQ. | - | S514848 | - |
| 17 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 18 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 19 | HEADER BOARDS (INCLUDES TIME TO I & R) | AS REQ. | - | - | H-BRDS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## IN/OUT SINGLE SIDED PADMOUNT 200A MANUAL/ NON-SCADA





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
TOP VIEW





**FIGURE 3**
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.9

# IN/OUT SINGLE SIDED PADMOUNT 200A MANUAL/ NON-SCADA





**FIGURE 1**
IN/OUT SINGLE SIDED PADMOUNT 200A
MANUAL CONNECTION DIAGRAM





**FIGURE 2**
MAP SYMBOL





**FIGURE 3**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS201022-108 SWITCH TANK | 480 LBS |
| ENCLOSURE | 550 LBS |
| MOTOR OPERATOR | 35 LBS |
| PENDANT | 20 LBS |
| RELAY | 20 LBS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision | X | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

# IN/OUT SINGLE SIDED PADMOUNT 200A MANUAL/ NON-SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | IN/OUT SINGLE SIDED PADMOUNT 200A MANUAL (ISG) | 1 | - | S190462 | IS2PF2 |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, #2/7 COPPER GROUND | 1 | 4510 | S812818 | TG-E-W |
| 6 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 7 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 8 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 9 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 11 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 12 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 13 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 14 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 15 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 16 | PADLOCK | AS REQ. | - | S514848 | - |
| 17 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 18 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 19 | 3312 SECONDARY HANDHOLE | AS REQ. | - | S162426 | 3312-0 |
| 20 | CONCRETE PAD WITH 3312, SINGLE OR THREE PHASE | AS REQ. | - | S514240 | FC3PAD |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.11

## IN/OUT SINGLE SIDED PADMOUNT 200A SCADA





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
TOP VIEW





**FIGURE 1**
FRONT VIEW- DOOR HIDDEN

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# IN/OUT SINGLE SIDED PADMOUNT 200A SCADA





**FIGURE 1**
IN/OUT SINGLE SIDED PADMOUNT 200A
SCADA CONNECTION DIAGRAM





**FIGURE 2**
MAP SYMBOL





**FIGURE 3**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS201022-108 SWITCH TANK | 480 LBS |
| ENCLOSURE | 550 LBS |
| POTENTIAL TRANSFORMER | 125 LBS |
| MOTOR OPERATOR | 35 LBS |
| AUTOMATION CONTROL CABINET | 400 LBS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision [X] Completely Revised [ ] New Page [ ] Information Removed

# IN/OUT SINGLE SIDED PADMOUNT 200A SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | IN/OUT SINGLE SIDED PADMOUNT 200A SCADA (ISG) | 1 | - | S190464 | ISG21S |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, #2/7 COPPER GROUND | 1 | 4510 | S812818 | TG-E-W |
| 6 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 7 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 8 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 9 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 11 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 12 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 13 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 14 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 15 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 16 | PADLOCK | AS REQ. | - | S514848 | - |
| 17 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 18 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 19 | 3112 SECONDARY HANDHOLE | AS REQ. | - | S162426 | 3312-0 |
| 20 | CONCRETE PAD WITH 3312, SINGLE OR THREE PHASE | AS REQ. | - | S514240 | FC3PAD |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## IN/OUT SINGLE SIDED PADMOUNT 600A MANUAL/ NON-SCADA





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
TOP VIEW





**FIGURE 3**
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

## IN/OUT SINGLE SIDED PADMOUNT 600A MANUAL/ NON-SCADA





**FIGURE 1**
IN/OUT SINGLE SIDED PADMOUNT 600A MANUAL
CONNECTION DIAGRAM





**FIGURE 2**
MAP SYMBOL





**FIGURE 3**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS201066-101 SWITCH TANK | 480 LBS |
| ENCLOSURE | 715 LBS |
| MOTOR OPERATOR | 35 LBS |
| RELAY | 20 LBS |
| PENDANT | 20 LBS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision | X | Completely Revised | | New Page | | Information Removed

# IN/OUT SINGLE SIDED PADMOUNT 600A MANUAL/ NON-SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | IN/OUT SINGLE SIDED PADMOUNT 600A MANUAL (ISG) | 1 | - | S704804 | IS6PFM |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 20 | 3312 SECONDARY HANDHOLE | 1 | 3312 | S286750<br>S162424<br>S596750 | 3312SH<br>3312CB<br>3312RR |
| 22 | CONCRETE PAD | AS REQ. | 3414 | S514280 | CAP-PD |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## IN/OUT SINGLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
TOP VIEW





**FIGURE 3**
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.18

# IN/OUT SINGLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
IN/OUT SINGLE SIDED PADMOUNT 600A SCADA
CONNECTION DIAGRAM





**FIGURE 2**
MAP SYMBOL





**FIGURE 3**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS201066-101 SWITCH TANK | 480 LBS |
| ENCLOSURE | 715 LBS |
| MOTOR OPERATOR | 35 LBS |
| POTENTIAL TRANSFORMER | 125 LBS |
| AUTOMATION CONTROL CABINET | 400 LBS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# IN/OUT SINGLE SIDED PADMOUNT 600A SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | IN/OUT SINGLE SIDED PADMOUNT 600A SCADA (ISG) | 1 | - | S704800 | ISG61S |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 20 | CONCRETE PADMOUNT | AS REQ. | 3414 | S514280 | CAP-PD |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

## 4-WAY SINGLE SIDED PADMOUNT 600A MANUAL/ NON-SCADA





**FIGURE 1**
TOP VIEW





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
FRONT VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.21

TABLE OF CONTENTS

# 4-WAY SINGLE SIDED PADMOUNT 600A MANUAL/ NON-SCADA





**FIGURE 1**
4-WAY SINGLE SIDED PADMOUNT 600A MANUAL
CONNECTION DIAGRAM





**FIGURE 3**
MAP SYMBOL





**FIGURE 2**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS40406666-101 SWITCH TANK | 1,420 LBS |
| MOTOR OPERATORS | 35 LBS EACH |
| STAND | 160 LBS |
| ENCLOSURE | 915 LBS |
| J-BOX | 10 LBS |
| PENDANT | 20 LBS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

# 4-WAY SINGLE SIDED PADMOUNT 600A MANUAL/ NON-SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 4-WAY SINGLE SIDED PADMOUNT 600A MANUAL (ISG) | 1 | - | S709054 | ISG4WM |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 20 | 3440 & 3441 CONCRETE SKIRT (CONCRETE SKIRT REQUIRED FOR RETROFIT.) | 1 | 3560.38 | S248205 | CC-WLK |
| 21 | FIBERGLASS PADMOUNT | AS REQ. | 3428 | S514026 S601600 S656400 | 3428BP X3428 |
| 22 | CONCRETE PADMOUNT | AS REQ. | 3441 | - | - |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## 4-WAY SINGLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
TOP VIEW





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
FRONT VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.24

TABLE OF CONTENTS

# 4-WAY SINGLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
4-WAY SINGLE SIDED PADMOUNT 600A SCADA
CONNECTION DIAGRAM





**FIGURE 3**
MAP SYMBOL





**FIGURE 2**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS40406666-101 SWITCH TANK | 1,420 LBS |
| MOTOR OPERATORS | 35 LBS EACH |
| STAND | 160 LBS |
| POTENTIAL TRANSFORMER | 130 LBS EACH |
| ENCLOSURE | 915 LBS |
| CONTROL CABINET | 500 LBS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

# 4-WAY SINGLE SIDED PADMOUNT 600A SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 4-WAY SINGLE SIDED PADMOUNT 600A SCADA (ISG) | 1 | - | S704724 | ISG4WS |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 20 | 3440 & 3441 CONCRETE SKIRT (CONCRETE SKIRT REQUIRED FOR RETROFIT.) | 1 | 3560.38 | S248205 | CC-WLK |
| 21 | FIBERGLASS PADMOUNT | AS REQ. | 3428 | S514026 S601600 S656400 | 3428BP X3428 |
| 22 | CONCRETE PADMOUNT | AS REQ. | 3441 | - | - |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## 5-WAY SINGLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
TOP VIEW





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
FRONT VIEW
DOORS REMOVED

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# 5-WAY SINGLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
5-WAY SINGLE SIDED PADMOUNT 600A SCADA
CONNECTION DIAGRAM





**FIGURE 3**
MAP SYMBOL





**FIGURE 2**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS505066666-101 SWITCH TANK | 1,600 LBS |
| MOTOR OPERATORS | 35 LBS EACH |
| STAND | 170 LBS |
| POTENTIAL TRANSFORMERS | 130 LBS EACH |
| ENCLOSURE | 1,055 LBS |
| CONTROL CABINET | 500 LBS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# 5-WAY SINGLE SIDED PADMOUNT 600A SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 5-WAY SINGLE SIDED PADMOUNT 600A SCADA | 1 | - | S704728 | ISG5WS |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 20 | 3440 & 3441 CONCRETE SKIRT | 1 | 3560.38 | S248205 | CC-WLK |
| 21 | FIBERGLASS PADMOUNT | AS REQ. | 3429.3 | - | - |
| 22 | CONCRETE PADMOUNT | AS REQ. | 3441 | - | - |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.29

## 6-WAY SINGLE SIDED PADMOUNT 600A SCADA

**ATTENTION:**

6-WAY ISG SWITCHGEAR: WAYS 1-5 ARE FAULT INTERRUPTING CAPABLE.WAY 6 WILL ONLY BE USED AS A SWITCH OR TIE POSITION.





**FIGURE 1**
TOP VIEW





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
FRONT VIEW


TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision | X | Completely Revised | New Page | Information Removed

# 6-WAY SINGLE SIDED PADMOUNT 600A SCADA








**FIGURE 1**
6-WAY SINGLE SIDED PADMOUNT 600A SCADA
CONNECTION DIAGRAM

INNOVATIVE SWITCHGEAR SOLUTIONS INC.™
FAULT INTERRUPTER/SWITCH
PATENT PENDING

| | |
|---|---|
| MAXIMUM VOLTAGE | 15.5 KV |
| CONTINUOUS CURRENT | 600 AMPS |
| INTERRUPTING CURRENT (SYM.) | 12.5 KA |
| INTERRUPTING CURRENT (ASYM.) | 20.0 KA |
| PEAK CURRENT | 32.5 KA |
| FAULT CLOSE (SYM.) | 12.5 KA |
| IMPULSE WITHSTAND VOLTAGE | 95 BIL |
| POWER FREQUENCY | 60 HZ |

CURRENT TRANSFORMER RATIO

600:5 RATIO

INTERNAL VOLTAGE SENSORS

RATED 12470/7200:120

INNOVATIVE SWITCHGEAR SOLUTIONS, INC

ISGYYXXXX

____/20YY

**FIGURE 2**
MANUFACTURER LABEL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| PS6150666666-102 SWITCH TANK | 2,040 LBS |
| STAND | 240 LBS |
| MOTOR OPERATORS | 35 LBS EACH |
| POTENTIAL TRANSFORMERS | 105 LBS EACH |
| ENCLOSURE | 1,215 LBS |
| AUTOMATION CONTROL CABINET | 500 LBS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

# 6-WAY SINGLE SIDED PADMOUNT 600A SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 6-WAY SINGLE SIDED PADMOUNT 600A SCADA | 1 | - | S704810 | ISG6WS |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3<br>3679.2 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL<br>2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | SEALANT, CAULKING | 1 | 3408 | S631800 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 20 | FIBERGLASS BOX PAD | AS REQ. | 3560.28 | S514032 | ISG6WY |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## 6-WAY SINGLE SIDED PADMOUNT SWITCHGEAR

**ATTENTION:**

SPECIALTY PAD FOR 6-WAY ISG ONLY





**FIGURE 1**
TOP VIEW





**FIGURE 2**
FRONT VIEW





**FIGURE 3**
SIDE VIEW





**FIGURE 4**
ISOMETRIC VIEW

**TABLE 1**

| 6-WAY SPECIALTY PAD | |
|---|---|
| **STOCK CODE** | **AU** |
| S514032 | ISG6WY |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# 4-WAY DOUBLE SIDED PADMOUNT 600A MANUAL/NON-SCADA





**FIGURE 1**
FRONT VIEW
DOORS REMOVED





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
REAR VIEW
DOORS REMOVED

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# 4-WAY DOUBLE SIDED PADMOUNT 600A MANUAL/NON-SCADA





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 3**
MAP SYMBOL





**FIGURE 4**
4-WAY DOUBLE SIDED PADMOUNT 600A
MANUAL CONNECTION DIAGRAM

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| P40406666-101 SWITCH TANK | 1,740 LBS |
| MOTOR OPERATORS | 35 LBS EACH |
| ENCLOSURE | 950 LBS |
| J-BOX | 10 LBS |
| PENDANT | 25 LBS |





**FIGURE 2**
MANUFACTURER LABEL

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

# 4-WAY DOUBLE SIDED PADMOUNT 600A MANUAL/NON-SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 4-WAY DOUBLE SIDED PADMOUNT 600A MANUAL/NON-SCADA | 1 | - | S704742 | IS4P6M |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | FIBERGLASS BOX PAD | AS REQ. | 3423.3 | S514028 | 3423BP |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed

## 4-WAY DOUBLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
FRONT VIEW
DOORS REMOVED





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
REAR VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X | Completely Revised | New Page | Information Removed

# 4-WAY DOUBLE SIDED PADMOUNT 600A SCADA





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 3**
MAP SYMBOL

**TABLE 1**

| APPROXIMATE SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT** |
| P40406666-101 SWITCH TANK | 1,740 LBS |
| MOTOR OPERATORS | 35 LBS EACH |
| POTENTIAL TRANSFORMERS | 130 LBS EACH |
| ENCLOSURE | 950 LBS |
| CONTROL CABINET | 500 LBS |






**FIGURE 4**
4-WAY DOUBLE SIDED PADMOUNT 600A SCADA
CONNECTION DIAGRAM

INNOVATIVE SWITCHGEAR SOLUTIONS INC.
FAULT INTERRUPTER/SWITCH
PATENT PENDING

| | |
|---|---|
| MAXIMUM VOLTAGE | 15.5 KV |
| CONTINUOUS CURRENT | 600 AMPS |
| INTERRUPTING CURRENT (SYM.) | 12.5 KA |
| INTERRUPTING CURRENT (ASYM.) | 20.0 KA |
| PEAK CURRENT | 32.5 KA |
| FAULT CLOSE (SYM.) | 12.5 KA |
| IMPULSE WITHSTAND VOLTAGE | 95 BIL |
| POWER FREQUENCY | 60 HZ |




CAT# P40406666-101 | WEIGHT 1740 LBS

CURRENT TRANSFORMER RATIO

600:5 RATIO

INNOVATIVE SWITCHGEAR SOLUTIONS, INC

ISGYYXXXX

____/20YY

INTERNAL VOLTAGE SENSORS

RATED 12470/7200:120

**FIGURE 2**
MANUFACTURER LABEL

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision | X | Completely Revised | New Page | Information Removed

# 4-WAY DOUBLE SIDED PADMOUNT 600A SCADA

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 4-WAY DOUBLE SIDED PADMOUNT 600A SCADA | 1 | - | S704726 | ISG42P |
| 2 | 12KV, 600/200 AMP CONNECTIONS | AS REQ. | 4181.19 | - | - |
| 3 | ELBOW, FUSED, 2 SOLID, 30 AMP (FUSE INCLUDED) | AS REQ. | 4191 | S321680 | CFE2SL |
| 4 | 1/0 CONNECTOR POST | 5 | - | S262560 | - |
| 5 | WIRE, 4/0 COPPER | AS REQ. | 4520.8 | S812764 | 4/0-SD |
| 6 | WIRE, #2 COPPER GROUND TRENCH | 1 | 4510 | S812816 | TG-E-W |
| 7 | BOLT, EYE, STAINLESS STEEL | AS REQ. | - | S150528 | - |
| 8 | CONNECTOR, SERVICE POST | 4 | 3711.3 | S262560 | SPCONN |
| 9 | NUT, CLAMPING CHANNEL | AS REQ. | | S503520 | - |
| 10 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | AS REQ. | | S616192 | - |
| 11 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ. | | S799488 | - |
| 12 | WASHER, SPRING, LOCK | AS REQ. | | S796416 | - |
| 13 | BOLT, 3-1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | - | S148804 | - |
| 14 | BRACKET, ANGLE, STAINLESS STEEL 2" X 3" | AS REQ. | 4520.8 | S166072 | - |
| 15 | ANCHOR, 1/2" X 3-3/4" MOUNTING ON CONCRETE PAD | AS REQ. | - | S107654 | - |
| 16 | 5/8" X 14" MACHINE BOLT | AS REQ. | 392.1 | S154880 | - |
| 17 | PADLOCK | AS REQ. | - | S514848 | - |
| 18 | CABLE, #2 AWG, SOLID 1/C | AS REQ. | 4003.1 | S197600 | - |
| 19 | FIBERGLASS BOX PAD | AS REQ. | 3423.3 | S514028 | 3423BP |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

Indicates Latest Revision X Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

## INSTALLATION:

A. FOR SINGLE PADMOUNT APPLICATIONS, THE SWITH TANK IS SHIPPED INSIDE THE ENCLOSURE ON ITS BACK WITH THE BUSHINGS FACING UP. THE SWITCH STAND AND ANY OPTIONAL ITEMS TO COMPLETE THE PACKAGE WILL BE SHIPPED INSIDE THE PADMOUNT ENCLOSURE. SEE FIGURE 1.



**FIGURE 1**

B. FOUR INTERNAL AND TWO EXTERNAL BOLTS SECURE THE ENCLOSURE TO THE PALLET. REMOVE THESE BOLTS TO LIFT THE ENCLOSURE FROM THE PALLET. THE DOORS MAY BE OPENED OR REMOVED TO HELP GUIDE THE ENCLOSURE OVER THE EQUIPMENT. SEE FIGURE 2 AND 3.



**FIGURE 2**



**FIGURE 3**

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

## INSTALLATION (CON'T):

C. THREE LIFTING PROVISIONS ARE PROVIDED ON BOTH ENDS OF THE SWITCH TANK. THESE LIFTING PROVISIONS ROTATE 360 DEGREES. SEE FIGURE 4 AND 5.



**FIGURE 4**



**FIGURE 5**

D. MOTOR OPERATOR LINKAGE REQUIRES 20-INCHES OF SPACE IN THE OPEN POSITION TO NOT IMPACT THE PADMOUNT ENCLOSURE DOORS. LEAVE 21 ½ INCHES FROM THE FACE OF THE SWITCH TO THE PADMOUNT ENCLOSURE DOORS. SEE FIGURE 6.





**FIGURE 6**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

**INSTALLATION (CON'T):**

E. **MOTOR OPERATORS AND LINKAGES ARE MATED TO THE SWITCH AND IDENTIFIED AT THE MANUFACTURING PLANT.** MOUNT MOTOR OPERATORS WITH CORRESPONDING WAYS AFTER THE CABLE HAS BEEN LANDED AND PRIOR TO MOUNTING THE ENCLOSURE. SEE FIGURE 7 AND 8.




**FIGURE 7**





**FIGURE 8**

F. INNOVATIVE SWITCH GEAR HAS A UNIQUE FEATURE ALLOWING THE ENCLOSURE TO BE REMOVED WHILE THE SWITCH REMAINS INTACT. THIS WILL BETTER FACILITATE IN WIRE PULLING AND SWITCH MAKE-UP. SWITCH STAND AND ENCLOSURE MUST BE SECURED TO THE PAD AND GROUNDED INDIVIDUALLY.

G. ON NON-SCADA UNITS, ONCE THE ENCLOSURE IS SECURE, ATTACH THE CABLES FROM THE JUNCTION BOX TO THE MOTOR OPERATORS. EACH CABLE IS DESIGNATED AND MARKED WITH A WAY POSITION. SEE FIGURE 9.




**FIGURE 9**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

**INSTALLATION (CON'T):**

H. THE POLYCARBONATE VIEWING WINDOWS FOR THE CLOSED/OPEN VACUUM CONTACT SEMAPHORE ARE COVERED AT THE FACTORY WITH GREEN ULTRAVIOLET PROTECTIVE TAPE. REMOVE THE TAPE UPON COMPLETION OF INSTALLATION. IF THE TAPE IS INADVERTENTLY REMOVED PRIOR TO INSTALLATION, PLEASE COVER THE LENSES OR APPLY ULTRAVIOLET PROTECTIVE TAPE TO KEEP THE WINDOWS FROM YELLOWING. SEE FIGURE 10.





**FIGURE 10**

J. THE ONE OPERATING HANDLE OPENS THE VACUUM INTERRUPTS FIRST SO THAT THE ELECTRICAL INTERRUPTION IS ALWAYS PERFORMED WITHIN THE VACUUM INTERRUPTS AND THEN THE VISIBLE OPEN ISOLATION POINT (VOIP) SWITCH OPENS.


K. FOR PADMOUNT VVIEW OF THE CONTACTS:

1. FOR SINGLE SIDE PADMOUNT, VAULTMOUNT, AND SUBMERSIBLE, THE VIEW OF THE OPEN CONTACTS IS FROM THE TOP OF THE MECHANISM. SEE FIGURES 11 AND 12 BELOW.




VISIBLE OPEN SHAFT "CLOSED"

**FIGURE 11**




VISIBLE OPEN SHAFT "OPEN", ISOLATED AND VISIBLE

**FIGURE 12**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

**INSTALLATION (CON'T):**

2. FOR DOUBLE SIDE PADMOUNT APPLICATIONS, THE VIEW OF THE OPEN CONTACTS IS FROM THE SIDE OF THE MECHANISM, SEE FIGURES 13 AND 14.



VISIBLE OPEN SHAFT
"OPEN"

**FIGURE 13**



VISIBLE CLOSED SHAFT
"CLOSED"

**FIGURE 14**

L. PENDANT CONTROLLERS ARE PROVIDED TO POWER AND CONTROL ALL THE MOTOR OPERATORS FROM OUTSIDE THE ENCLOSURE. THESE PORTABLE CONTROLLERS ARE DESIGNED TO PROVIDE FIELD PERSONNEL THE ABILITY TO PLUG INTO A JUNCTION BOX TO DETERMINE STATUS OF ALL THE MOTORS AND TO CONTROL MULTIPLE MOTOR OPERATORS LOCALLY WITH EXTERNAL 120V AC POWER PLUGGED INTO THE PENDANT CONTROL. CAUTION: THE "CONTROL HEALTHY" LIGHT WILL ONLY LIGHT WHEN THE TOGGLE SWITCH IS TURNED ON AN WHEN CONNECTED TO A "PURE SINE WAVE" SOURCE OF 120V AC POWER. SQUARE SINE WAVE OR MODIFIED SINE WAVE INVERTERS WILL NOT POWER THIS DEVICE AND MAY DAMAGE THE CONTROL. SEE FIGURE 15.





**FIGURE 15**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

## INSTALLATION (CON'T):

M. PENDANT CONTROLLER MUST BE CONNECTED TO THE JUNCTION BOX PICTURED BELOW TO OPERATE MOTOR OPERATORS. JUNCTION BOX CONNECTIONS ARE SEVEN-PIN AND 12-PIN, SO THEY CANNOT BE INSTALLED INCORRECTLY. SEE FIGURE 16.





**FIGURE 16**

N. WITH THE ABILITY TO REMOTELY OPERATE THE MOTOR OPERATIONS ON THE SWITCH. THE ACTUATOR ARMS SHALL NOT BE LOCKED.

## SCADA UNITS

O. ALL SOURCE AND TIE POSITIONS SHALL BE PHASE IDENTIFIED WITH THE AP30. THE SWITCH SHALL BE MARKED FOR "A", "B" AND "C" PHASES.

P. THERE ARE TWO REDUNDANT POTENTIAL TRANSFORMERS (PTs) THAT ARE CONNECTED PHASE TO GROUND. PTs TO BE CONNECT ON THE SOURCE SIDE AND TIE POSITION OF THE SWITCH (IF NO TIE EXISTS ON SWITCH, CHOOSE POSITION WITH DOWNSTREAM TIE SWITCH). IF APPLICABLE, ON THE CENTER PHASE POSITION. PHASE CONNECTION TO THE P.T. IS TO BE MADE WITH A FUSED ELBOW AS THE P.T. DOES NOT HAVE ITS OWN PROTECTION. GROUND ELBOW TO BE STRIPPED AND CONNECTED TO A COPPER TAIL AND THEN HARD TAPPED TO THE GROUND RING BUS. SEE FIGURE 17 AND 18.




**FIGURE 17**





**FIGURE 18**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

## INSTALLATION (CON'T):

Q. WHEN INSTALLING THE PTs, WE MUST BOND ALL OF THE BASE PLATES OF H2 AND H1 TO GROUND SOURCE/RING BUS. FAILURE TO DO SO WILL RESULT IN THE RING BUS HAVING HIGH VOLTAGE CAPABILITY AND COULD RESULT IN UNFAVORABLE CONSEQUENCES. (ALL RED ARROWS ARE POINTING TO BONDS)





FIGURE 19



FIGURE 20



FIGURE 21

R. WARNING: VOLTAGE SENSORS ARE TO BE GROUNDED PRIOR TO ENERGIZING. VOLTAGE SENSOR ARE TO BE CONNECTED TO THE TIE POSITION OF THE SWITCH. IF APPLICABLE USING A FEED THRU DEVICE ON THE P.T. WILL ALLOW FOR THE VOLTAGE SENSOR AND P.T. TO BE CONNECTED TO THE SAME SWITCH POSITION. SEE FIGURE 22.





**FIGURE 22**

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

## INSTALLATION (CON'T):





**FIGURE 23**

S. PRIOR TO ENERGIZING, CHECK TO MAKE SURE MOTOR OPERATOR ACTUATOR ARMS CAN FUNCTION UNOBSTRUCTED. P.T. ELBOWS SHALL BE PLACED ON THE CENTER PHASE POSITION OF THE SWITCH. FAULT INDICATORS SHALL BE POSITIONED AWAY FROM THE TRAVEL OF THE MOTOR OPERATOR ACTUATOR ARMS. SEE FIGURE 24 AND 25.





**FIGURE 24**




**FIGURE 25**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION (CON'T):

### PAD MOUNT OPTIONS

T. SET THE SWITCH ON THE BOX PAD. USING A 1/2 INCH DRILL BIT, DRILL THROUGH THE EXISTING HOLES IN THE SILL FLANGE AND THROUGH THE BOX PAD. BOLT DOWN AS SHOWN IN HOLD DOWN DETAIL. SEE FIGURE 26.

HOLD DOWN DETAILS
(USE STAINLESS STEEL
TIE DOWNS PROVIDED)





**FIGURE 26**

U. THE FOOTPRINT OF THE INNOVATIVE SWITCH AND UP FRONT WORK SPACE WILL ALLOW IT TO BE INSTALLED ON THE "W" SERIES SWITCH FACILITIES INCLUDING 3440, 3441 PADS ON HAND HOLES AND THE TROUGH STYLE SWITCH PADS WITH A MODIFICATION. IT MAY BE USED WHEN LIMITED RIGHT OF WAY ISSUES MAY EXIST FOR CONVERSIONS AND LIMITED SPACE FOR NEW CONSTRUCTION. INNOVATIVE SWITCH INSTALLS ON EXISTING "W" PADS MAY NEED TO HAVE THE SKIRT EXTENDED TO ACCEPT THE LARGER SWITCH FOOT PRINT. SEE FIGURE 27, 28 AND 29.



**FIGURE 27**





**FIGURE 28**
TOP VIEW

**FIGURE 29**
SIDE VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.48

TABLE OF CONTENTS

RETURN TO FIRST PAGE

**NOTES:**

I. WHEN REPLACING EXISTING SWITCHES, THE TIE POSITIONS ARE ESTABLISHED AND CONNECTED AS DESIGNED TO AVOID MAJOR RE-CABLING, CONNECT AS-BUILT. NEW INSTALLATIONS WILL FOLLOW THE DESIGN MANUAL.

II. INNOVATIVE SWITCHGEAR'S PRODUCTS DO NOT CONTAIN ANY OIL OR SF6 GAS FOR THE ELECTRICAL ARC INTERRUPTION OR FOR COMPONENT INSULATION. INNOVATIVE SWITCHGEAR CONTAINS ONLY MECHANISMS, INSULATED BUS WORK AND DRY AIR. DO NOT REMOVE THE PRESSURE TEST PLUG ON THIS VESSEL. EACH UNIT HAS BEEN PRESSURE TESTED AND PERMANENTLY FACTORY SEALED. THE SWITCH TANK IS FILLED WITH THREE TO FIVE POUNDS OF DRY AIR TO KEEP THE STRUCTURAL INTEGRITY OF THE TANK AT SEA LEVEL.

III. THE USE OF FUSED ELBOWS WILL BE FOR THE ADDITION OF POTENTIAL TRANSFORMERS FOR SCADA APPLICATIONS AND LIMITED TO TWO FUSED ELBOW ONLY ONE PER SWITCH WAY POSITION. NO DEVIATION WILL BE GRANTED FOR MORE THAN TWO FUSED ELBOWS IN THE INNOVATIVE SWITCH CABINET. THE 30A FUSED ELBOW (S321680) AND 10 FEET OF #2 CABLE (197600) WILL BE MADE BY LINE CREWS (KEARNY MAY ALSO AS NEEDED) TO INSTALL SCADA INSTALLATIONS. PT PLACEMENT WILL BE DETERMINED BY KEARNY (FOR DOUBLE-SIDED UNITS, THE PTS MAY BE PLACED ON THE OPPOSITE SIDE SO THAT THE PTS ARE ALWAYS ON THE SAME SIDE OF THE BUSHINGS REQUIRING FUSED ELBOWS).

IV. TAPPING THE BACK OF 600 AMP TEES FOR 200 AMP DISTRIBUTION WILL BE LIMITED TO SWITCH CHANGE OUTS WITH EXISTING 200 AMP TAPS.

V. FOR NEW CONSTRUCTION AND CONVERSIONS THIS INNOVATE SWITCH SHOULD NOT BE USED TO TAP FEEDER CABLES. TAPS ON THE BACK OF 600 AMP TEES IMPEDE GROUNDING AND LIMIT USE OF SWITCH POSITIONS DURING ROUTING SWITCHING PROCEDURES AND OUTAGE SITUATIONS. TAP FEEDER SEGMENTS BETWEEN SWITCH POSITIONS USING 600 AMP TERMINATORS OR TAP THE SWITCH POSITION WITH DISTRIBUTION CABLE ONLY.

VI. ROUTINE REPLACEMENT OF EXISTING 4 WAY PADMOUNT SWITCHES IS LIMITED TO THE 'W' TYPE CONFIGURATIONS ABOVE 3315 & 3316 HAND HOLES AND THE 'D' TYPE CONFIGURATIONS ABOVE 3311 HAND HOLES. FOR “W” INSTALLED EQUIPMENT, 12” DEPTH SKIRT IS REQUIRED ALONG REAR OF PAD.

VII. ANOTHER 'D' CONFIGURATION CONSISTS OF SUBSURFACE SWITCHES MOUNTED ABOVE 3315 HAND HOLES. THESE DO NOT LEND THEMSELVES TO SIMPLE REPLACEMENT OF THE SWITCH. THESE INSTALLATIONS ARE COMMONLY CALLED "I -BEAM" OR "RAIL" SWITCHES. A DEVIATION REQUEST OS REQUIRED WHEN ATTEMPTING TO REPLACE THESE WITH A PADMOUNT STYLE SWITCH.

VIII. ALL ISG MANUAL SWITCHES ARE “SCADA-READY (CAPABLE OF BEING RETROFITTED TO SCADA)” AND POTENTIALLY FAULT INTERRUPTING USING OTHER CONTROLLERS/RELAYS.

IX. IF INSTALLING ON 3440/3441 PAD, PLEASE REFER TO THE 12" EXTENSION FIGURES 16A-C.

XI. ALL MANUAL SWITCHES CAN BE USED ON 12 AND 4 KV APPLICATIONS

XII. FOR THE 4 WAY DOUBLE SIDED SWITCH APPLICATIONS FOR REPLACEMENT OF PME-9 AND PME-11 SWITCHES, THE ISG UNITS HAVE 600A BUSHINGS ON AL POSITIONS.

XIII. ISG MANUAL SWITCHES REFER TO MOTORIZED OPERATORS INSTALLED AND CAN BE OPERATED WITH THE LEVER VIA HOOKSTICK. ISG SCADA REFERS TO THE CONTROLLER WITH THE FAULT INTERRUPTING AND COMMUNICATIVE FEATURES TO INCLUDE MOTOR OPERATORS. ISG NON-SCADA REFERS TO MANUAL SWITCHES, BUT MAY BE RETROFITTED TO INCLUDE NON-COMMUNICATIVE RELAYS/CONTROLLERS.

XIV. REGARDING THE 6 WAY ISG SWITCHGEAR: WAYS 1-5 ARE FAULT INTERRUPTING CAPABLE. WAY 6 WILL ONLY BE USED AS A SWITCH OR TIE POSITION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INNOVATIVE SWTICHGEAR PAD AND WALL-MOUNT

UG3560.49

**REFERENCE:**

a. CABLE IDENTIFICATION, SEE UNDERGROUND STANDARD 3202.

b. ATTACHING STRUCTURE/EQUIPMENT IDENTIFICATION TAG, SEE UNDERGROUND STANDARD 3211.

c. HIGH VOLTAGE DECAL, SEE UNDERGROUND STANDARD 3221.

d. WIRE ENTRY PREVENTION, SEE UNDERGROUND STANDARD 3408.

e. BOX PAD AND CONDUIT PLACEMENT, SEE UNDERGROUND STANDARD 3428/3429.

f. BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC, SEE UNDERGROUND STANDARD 3481.

g. MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UNDERGROUND STANDARD 3483.

h. RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UNDERGROUND STANDARD 3486.

i. RETAINING WALLS, SEE UNDERGROUND STANDARD 3487.

j. PAD-MOUNTED SWITCH IDENTIFICATION, SEE UNDERGROUND STANDARD 3212.2.

k. FAULT INDICATOR INSTALLATION, SEE UNDERGROUND STANDARD 4355.

l. (PREFERRED 1) AND (ALTERNATE TRENCH GROUND WIRE), SEE UNDERGROUND STANDARD 4510.

m. EQUIPMENT GROUNDING, SEE UNDERGROUND STANDARD 4520.

n. GROUNDING PREMOLDED CONNECTORS, SEE UNDERGROUND STANDARD 4525.

o. NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM, SEE UNDERGROUND STANDARD 4520.8 & 4520.9.

p. SCADA INSTALLATION, SEE UNDERGROUND STANDARD 4640.4 & 4640.5.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | EDITORIAL CHANGES | PEI | NTB | FRC | CZH | 11/23/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | - | NB | JS | CZH | 11/01/2020 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS A TYPICAL 12KV, 600 AMP AIRBREAK PME-9, 10 & 11 SECTIONALIZING SWITCH.





**FIGURE 1**
PME-9





**FIGURE 2**
PME-10 & PME-11

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | GLC | EJA | EJA | KRG | 11/09/2022 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD-MOUNTED AIRBREAK PME-9, 10 & 11
SECTIONALIZING SWITCH 12KV, 600 AMP, THREE-PHASE



UG3567.1

TABLE OF CONTENTS





**FIGURE 3**
VIEW OF COMPARTMENT 1 & 2

**TABLE 1**

| MAXIMUM WEIGHT FOR SCADA EQUIPPED SWITCHES | |
|---|---|
| **SWITCH** | **WEIGHT** |
| PME-9 | 2420 LBS. (1098 KG) |
| PME-10 | 2475 LBS. (1123 KG) |
| PME-11 | 2525 LBS. (1145 KG) |





**FIGURE 4**
VIEW OF COMPARTMENT 3 & 4







© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | GLC | EJA | EJA | KRG | 11/09/2022 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |



TABLE OF CONTENTS

| EQUIPMENT RATINGS: | |
|---|---|
| VOLTAGE | 14.4 |
| B.I.L. | 95 |
| CURRENT, CONDITIONS (GANG OPERATED) | 600 AMP |
| LOADMAKE AND LOADBREAK (GANG OPERATED) | 600 AMP |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 14,000 AMP |

| | | | |
|---|---|---|---|
| CONNECTION DIAGRAM |  |  |  |
| SWITCH TYPE | PME-9 | PME-10 | PME-11 |
| MAP SYMBOLS |  |  |  |

## TABLE 2

| ITEM | DESCRIPTION |
|---|---|
| 1 | FOLDING SWITCH OPERATING HANDLE |
| 2 | LEXAN VIEWING WINDOW (600 AMP SWITCH) |
| 3 | 600 AMP STUD BUSHING |
| 4 | GROUND ROD (FOR PERSONAL GROUNDS ONLY) |
| 5 | GROUND RODS & CABLE GUIDES FOR FUSES |
| 6 | INTERLOCK TO REQUIRE REMOVAL OF THE LBE ACCESS TO FUSE |
| 7 | LIFTING TABS (REMOVE AFTER INSTALLATION AND REPLACE BOLTS, STORE INSIDE CABINET) |
| 8 | 200 AMP BUSHING WELLS |
| 9 | LEXAN VIEWING WINDOW (BLOWN FUSE INDICATOR) |
| 10 | FAULT INDICATOR MOUNTING BRACKET |
| 11 | FUSE COMPARTMENT |
| 12 | LOW VOLTAGE COMPARTMENT (SCADA ONLY) |
| 13 | SWITCH OPERATOR (SCADA ONLY) |
| 14 | TRANSFUSER DOOR |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | GLC | EJA | EJA | KRG | 11/09/2022 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SHEET 3 OF 4

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD-MOUNTED AIRBREAK PME-9, 10 & 11
SECTIONALIZING SWITCH 12KV, 600 AMP, THREE-PHASE

UG3567.3

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. PAD-MOUNTED SWITCH (STOCK NUMBERS PME-9 #S708970, PME-10 #S708972 AND PME-11 #S708974) ARE DELIVERED FROM THE SUPPLIER WITH ALL THE PARTS LISTED EXCEPT FOR FUSES AND 200A LOAD BREAK BUSHING INSERTS.

**REFERENCE:**

a. SEE STANDARD 3212.2 FOR SWITCH IDENTIFICATION.

b. SEE STANDARD 3423 FOR BOX PAD AND CONDUIT PLACEMENT.

c. SEE STANDARD 3568 FOR SWITCH INSTALLATION.

(d) SEE STANDARD 4302 FOR FUSE APPLICATION GUIDE.

e. SEE STANDARD 4355.3 FOR FAULT INDICATOR INSTALLATION.

(f) SEE DESIGN STANDARD 6113 FOR AUTOMATIC FAULT INDICATOR APPLICATION.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | GLC | EJA | EJA | KRG | 11/09/2022 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD-MOUNTED AIRBREAK PME-9, 10 & 11
SECTIONALIZING SWITCH 12KV, 600 AMP, THREE-PHASE

UG3567.4

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION FOR PAD MOUNTED, 12KV, 600A, AIR BREAK, PME 9, 10 AND 11 SECTIONALIZING SWITCH CABINET.








**FIGURE 1**




**DETAIL 1** (II)
SCADA ONLY




**DETAIL 2**

**FIGURE 2**
VIEW OF COMPARTMENT 3 AND 4

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED AIR BREAK PME 9, 10 AND 11 SECTIONALIZING SWITCH CABINET, 12KV, 600A, THREE-PHASE

UG3568.1



TABLE OF CONTENTS





**FIGURE 3**
HOLD-DOWN DETAIL AND RING BUSS SUPPORT

## INSTALLATION:

(A) SEAL CONDUITS WITH SEALING COMPOUND.

(B) SET THE SWITCH ON THE BOX PAD. USING A 1/2-INCH DRILL BIT, DRILL THROUGH THE EXISTING HOLES IN THE SILL FLANGE AND THROUGH THE BOX PAD. BOLT DOWN AS SHOWN IN HOLD DOWN DETAIL.

C. BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT POSSIBLE WIRE ENTRY.

D. INSTALL RING BUSS SO THAT IT DOES NOT INTERFERE WITH TRANSFUSER DOORS.

E. SECURE THE SWITCH DOORS AND THE SWITCH OPERATING HANDLE COVERS WITH PME LOCKS.

(F) INSTALL CURRENT LIMITING OR SML-4Z FUSES PER FUSE REQUEST.

G. FOR THE PME-10 ONLY. WHEN ONLY THREE OF THE FOUR SWITCH POSITION WILL BE UTILIZED, PULL CABLES IN COMPARTMENTS 1, 2 AND 4 FIRST.

H. SOURCE TRANSFER SWITCHES REQUIRE A SPECIAL FACILITIES AGREEMENT. CONTACT DISTRIBUTION STANDARDS FOR ADDITIONAL INFORMATION.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BOX PAD FOR PME 9, 10, 11 | 1 | 3423 | S514028 | 3423BP |
| 2 | PADLOCK, PME (III) | 6 | - | S514862 | - |
| 3 | WIRE, THW, 4/0 | AS REQ'D | 4530 | S808224 | - |
| 4 | SWITCH, MANUAL, PME 9 | AS REQ'D | 3568 | S708970 | PME-09 |
| | SWITCH, SCADA, PME 9 | | | S708978 | PME-9S |
| | TRANSFER, SOURCE, PME 9 | | - | - | - |
| 5 | SWITCH, MANUAL, PME 10 | AS REQ'D | 3568 | S708972 | PME-10 |
| | SWITCH, SCADA, PME 10 | | | S708981 | PME-10S |
| 6 | SWITCH, MANUAL, PME 11 | AS REQ'D | 3568 | S708974 | PME-11 |
| | SWITCH, SCADA, PME 11 | | | S708976 | PME-11S |
| 7 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 4 | - | S616192 | - |
| 8 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 8 | - | S799488 | - |
| 9 | WASHER, LOCK SPRING | 4 | - | S796416 | - |
| 10 | TAGS, CABLE IDENTIFICATION | AS REQ'D | - | - | - |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 11 | AUTOMATIC FAULT INDICATOR | AS REQ'D | 4355 | - | - |
| 12 | BUSHING PLUG | AS REQ'D | 4179-4180 | S544676 | BSHPLG |
| 13 | 12KV, 200A LOADBREAK AND 600A CONNECTORS | AS REQ'D | 4181 | - | - |
| 14 | WIRE, TRENCH GROUND | 1 | 4510 | - | TG-E-W |
| 15 | GROUNDING ROD, BY MANUFACTURER | - | - | - | - |
| 16 | DECALS (III) | AS REQ'D | 3213-3218 | - | - |
| 17 | NUT, HEX, BRONZE, 1/2" | 4 | - | S506112 | - |
| 18 | GASKET, BY MANUFACTURER | - | - | - | - |
| 19 | NUT, CLAMPING CHANNEL (III) | 4 | - | S506112 | - |
| 20 | CONNECTOR, COMPRESSION | AS REQ'D | | - | - |
| 21 | FUSE, CURRENT LIMITING, 140A X-LIMITER | AS REQ'D | 4312 | S365730 | XL-140 |
| 22 | CABLE GUIDE, BY MANUFACTURER | - | - | - | - |
| 23 | SEALING COMPOUND | AS REQ'D | - | S442976 | - |
| 24 | KIT CONVERSION CL TO SME-4Z FOR PME | 1 | - | S442944 | CL-SM4- |
| 25 | BRACKET, STAINLESS STEEL, 2" X 3" | 4 | - | S166072 | - |

## NOTES:

I. INSTALL SWITCH WITH SWITCH OPERATING HANDLE DOORS OR MOTOR OPERATORS FACING THE STREET WITH COMPARTMENTS 1 AND 2 ON THE RIGHT WHEN FACING THE SWITCH.

(II) CURRENT SENSORS TO BE INSTALLED BY SCADA CREW.

(III) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3202 FOR CABLE IDENTIFICATION.

b. SEE UG3211 FOR ATTACHING STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

c. SEE UG3221 FOR HIGH VOLTAGE DECAL.

d. SEE UG3408 FOR WIRE ENTRY PREVENTION.

e. SEE UG3423 FOR BOX PAD AND CONDUIT PLACEMENT.

f. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

h. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

i. SEE UG3511 FOR RETAINING WALLS.

j. SEE UG4302 FOR FUSE APPLICATION GUIDE.

(k) SEE UG4355 FOR FAULT INDICATOR INSTALLATION.

(l) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE TRENCH GROUND WIRE).

(m) SEE UG4520 AND UG4521 (PREVIOUS # UG4520) FOR EQUIPMENT GROUNDING.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

**REFERENCE (CONT'D):**

n. SEE UG4525 FOR GROUNDING PREMOLDED CONNECTORS.

o. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

p. SEE DM6113 FOR AUTOMATIC FAULT INDICATOR APPLICATION.

(q) SEE UG4310 FOR CONVERSION KIT FOR CURRENT LIMITING TO SML-4Z FUSE HOLDERS.

(r) SEE UG4520, UG4521 (PREVIOUS # UG4520) AND UG4530 FOR GROUNDING.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED AIR BREAK PME 9, 10 AND 11 SECTIONALIZING SWITCH CABINET, 12KV, 600A, THREE-PHASE

UG3568.4

**SCOPE:** THIS STANDARD COVERS THE USE OF THE ELASTIMOLD 200/200A MOLDED VACUUM INTERRUPTER HOUSED IN THE DURHAM MVI ENCLOSURE; IT CAN REPLACE A STANDARD FUSE CABINET ON A 3421 EQUIPMENT PAD.



**FIGURE 1** (I)





**FIGURE 2**
FRONT VIEW





**FIGURE 2**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3516 | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 07/12/2011 | D | BILL OF MATERIALS UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED MVI SWITCH ENCLOSURE



UG3580.1






**FIGURE 3**

| UG MAP SYMBOL |
|---|
| 168-531<br>D103541<br><br>MVI FUSE CABINET |





**FIGURE 4**

TABLE OF CONTENTS

## INSTALLATION:

A. THIS INSTALLATION IS LIMITED TO ONE THREE-PHASE RUN IN AND OUT; THE MVI WILL NOT ACCOMMODATE FEED THRU BUSHINGS.

B. PREFERRED CONDUIT PLACEMENT AND CABLE CONNECTION IS LINE ON THE LEFT AND LOAD ON THE RIGHT FACING THE SWITCH.

C. MVI MUST BE PRE-PROGRAMMED FOR EACH FACILITY LOCATION BY KEARNY BEFORE THE UNIT IS INSTALLED AND ENERGIZED.

D. CABINET HAS 4 LIFTING 1/2 X 13 THREAD INSERTS FOR LIFTING BOLTS WHEN INSTALLING THE CABINET AND MVI.

E. INSTALLING THE MVI IN THE DURHAM PAD MOUNTING CABINET: UN-BOLT AND REMOVE THE LID OF THE CABINET AND UN-PIN SWITCH HANDLE FOR EASY INSTALLATION. BOLT MVI IN THE FAR LEFT BOLT HOLES, WITH THE SWITCH HANDLE FACING THE SIDE SWITCHING DOOR. (SWITCH HANDLE MAY REQUIRE BENDING UP ONE-INCH TO CLEAR SIDE DOOR HARDWARE).

(F) 6 BUSHING PLUGS REQUIRE BONDING TO THE MVI SWITCH; THE MVI MUST BE GROUNDED TO THE CABINET AND THE TRENCH GROUNDS. CONCENTRIC NEUTRALS SHALL BE CONNECTED TO THE TRENCH GROUND, CABINET AND MVI.

G. ADDITIONAL TAGGING OF FACILITY NUMBERS ON INSIDE OF DOOR AND CIRCUIT SWITCH NUMBER ON THE MVI SWITCH.

H. SIDE AND FRONT DOOR SHALL BE LOCKED WITH KEYLESS LOCKS.

J. USE THE 4-WAY ADJUSTABLE JUNCTION TAP FOR STANDOFF GROUNDING (S305712).

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3516 | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 07/12/2011 | D | BILL OF MATERIALS UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABINET, ENCLOSURE, FOR MVI/MVS | 1 | -- | S190490 | DMV12 |
| 2 | MVI, 3-Ø 200A LINE, 200A LOAD | 1 | -- | S708410 | S23PFI |
| 3 | PAD\W-BOX, TRANSFORMER\UTILITY EQUIPMENT, SINGLE-PHASE | 1 | 3421 | S514240 | FC3PAD |
| 4 | HANDHOLE, 17" X 30" | 1 | 3312 | S162426 | TERM3F |
| 5 | WIRE, GROUND, TRENCH, COPPER, #2 | AS REQ'D | 4510 | -- | -- |
| 6 | ELBOW, LOADBREAK, 14.4KV, 200A | AS REQ'D | 4190 - 4191 | -- | -- |
| 7 | PLUG, BUSHING (F) | 6 | 4180 | S544676 | BSHPLG |
| 8 | LOCKS, KEYLESS (II) | 2 | -- | S468010 | -- |
| 9 | NUT, STUD, 1/2" X 1 3/8" (II) | 2 | -- | S507000 (X) | -- |
| 10 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" (II) | 2 | -- | S799488 | -- |
| 11 | HOLD DOWN (SUPPLIED WITH CABINET) (II) | 2 | -- | -- | -- |
| 12 | SEALING COMPOUND (II) | AS REQ'D | -- | S442976 | -- |
| 13 | TAGS, IDENTIFICATION, CABLE | AS REQ'D | 3202 | -- | -- |
| 14 | TAGS, IDENTIFICATION, SWITCH | AS REQ'D | -- | -- | -- |
| 15 | NUT, STANDARD HEX, STAINLESS STEEL (II) | 2 | -- | S505536 | -- |

## NOTES:

(I) THIS APPLICATION OFFERS THE ABILITY TO PROGRAM AN INTERRUPTION CURRENT CURVE AND A THREE-PHASE SWITCH FOR HIGHER LOAD AND RELIABILITY ISSUES OF EXISTING FACILITIES. THE THREE-PHASE SWITCH WILL ALSO REDUCE THE POSSIBILITY OF FERRO-RESONANCE DURING SERVICE RESTORATION.

(II) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR CABLE IDENTIFICATION, SEE UG3202.
b. FOR STRUCTURE/EQUIPMENT IDENTIFICATION, SEE UG3211.
c. FOR HIGH VOLTAGE DECAL, SEE UG3221.
d. FOR WIRE ENTRY PREVENTION, SEE UG3408.
e. FOR RETAINING WALLS, SEE UG3489.
f. FOR SEALING JACKETED CABLE, SEE UG4108.
g. FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE, SEE UG4510.
h. FOR EQUIPMENT GROUNDING, SEE UG4512.
i. FOR GROUNDING PAD MOUNTED EQUIPMENT, SEE UG4520 AND UG4521.
j. FOR GROUNDING HARDWARE AND CONNECTIONS, SEE UG4505.
k. FOR MVI SPECIFICATIONS, SEE UG3675.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3516 | EDM | JIK | - | - | 05/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 07/12/2011 | D | BILL OF MATERIALS UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |

**SCOPE:** THIS STANDARD SHOWS A 12KV, 600A AIR BREAK PME 3 SECTIONALIZING SWITCH CABINET.





**FIGURE 1** (I)
SIDE VIEW





**FIGURE 1**
SIDE VIEW





**FIGURE 1**
COMPARTMENT 1
END VIEW





**FIGURE 1**
COMPARTMENT 2
END VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


PAD MOUNTED AIR BREAK PME 3 SECTIONALIZING SWITCH CABINET
12KV, 600A



UG3583.1

## TABLE 1

| ELECTRIC RATINGS | |
|---|---|
| VOLTAGE | 14.4KV |
| B.I.L. | 95KV |
| CURRENT, CONDITIONS | 600A |
| LOADMAKE AND LOADBREAK | 600A |
| MOMENTARY AND FAULT CLOSE (RMS, ASYMMETRICAL) | 22,400A |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 14,000A |




**UG MAP SYMBOL**





**FIGURE 2**
PME 3
CONNECTION DIAGRAM

| SWITCH PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | BAR, GROUND |
| 2 | BUSHING, 600A |
| 3 | PLATE, NAME (ON OUTSIDE OF DOOR) |
| 4 | PLATE, GROUNDING |
| 5 | BUS, 600A |
| 6 | TABS, LIFTING (II) |
| 7 | SWITCH, 600A MINI-RUPTER |
| 8 | OPERATOR, SWITCH (SCADA ONLY) |
| 9 | PROVISION, PENTAHEAD LATCH LOCKING |
| 10 | COMPARTMENT, LOW VOLTAGE (SCADA ONLY) |
| 11 | WINDOW, LEXAN SWITCH VIEWING |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |



TABLE OF CONTENTS

**NOTES:**

(I) WEIGHT: 1,040 LBS MAX.

(II) REMOVE AFTER INSTALLATION, REPLACE BOLTS AND STORE INSIDE CABINET.

**REFERENCE:**

a. SEE UG3214 FOR SWITCH IDENTIFICATION.

b. SEE UG3418 FOR BOX PAD INSTALLATION FOR PAD MOUNTED 600A, 12KV SWITCH.

c. SEE UG3584 FOR SWITCH INSTALLATION.

d. SEE UG4355 FOR FAULT INDICATOR INSTALLATION.

e. SEE DM6113 FOR AUTOMATIC FAULT INDICATOR APPLICATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED AIR BREAK PME 3 SECTIONALIZING SWITCH CABINET
12KV, 600A

UG3583.3

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION FOR PAD MOUNTED AIR BREAK 12KV, 600A PME 3 SECTIONALIZING SWITCH CABINET.




**DETAIL 1**
CURRENT SENSORS TO BE INSTALLED BY SCADA CREW, SCADA ONLY




**FIGURE 1**
COMPARTMENT 1
END VIEW





**FIGURE 2**
COMPARTMENT 2
END VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED AIRBREAK PME 3
SECTIONALIZING SWITCH CABINET, 12KV, 600A



UG3584.1





**FIGURE 3**
HOLD-DOWN DETAIL AND RING BUSS SUPPORT

## INSTALLATION:

(A) SEAL CONDUITS WITH SEALING COMPOUND.

(B) BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT WIRE ENTRY.

C. SECURE ALL OF THE SWITCH DOORS WITH PENTAHEAD BOLTS AND SCHLAGE PME SERIES LOCKS.

(D) SUPERVISORY OR ANTENNA CABLE AS REQUIRED FOR SCADA.

(E) DO NOT CONNECT CONCENTRIC TO GROUND BAR.

(F) CURRENT SENSORS TO BE INSTALLED BY SCADA CREW.

(G) INSTALL CONDUITS SO THAT THE FEED IS CONNECTED TO THE SWITCH IN COMPARTMENT 1. COMPARTMENT 1 SHALL BE ON THE RIGHT SIDE AS ONE FACES THE CABINET FROM THE STREET OR SIDEWALK.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BOX PAD, FOR PME 3, AIR BREAK SWITCH | 1 | 3418 | S514040 | 3418BP |
| 2 | PADLOCK (I)(G) | AS REQ'D | - | S514848 | PME-3C |
| 3 | WIRE, THW 4/0 (D) | AS REQ'D | 4530 | S808224 | THW4/0 |
| 4 | SWITCH, PME 3, MANUAL | AS REQ'D | 3584 | S708968 | PME-03 |
| | SWITCH, PME 3, SCADA | AS REQ'D | 3584 | S708980 | PME-3S |
| 5 | GROUND BAR | AS REQ'D | - | - | - |
| 6 | IDENTIFICATION TAGS | AS REQ'D | 3202/3213-3218 | - | - |
| 7 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 4 | - | S616192 | - |
| 8 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 8 | - | S799488 | - |
| 9 | SPRING, WASHER LOCK | 4 | - | S796416 | - |
| 10 | SEALING COMPOUND | AS REQ'D | - | S442976 | - |
| 11 | CONNECTORS, 12KV, CAMLINK OPERABLE, 600A | AS REQ'D | 4187 | - | C-LINK |
| 12 | CURRENT SENSORS (SCADA ONLY) | - | - | - | - |
| 13 | WIRE, TRENCH GROUND | AS REQ'D | 4510 | - | TG-T-W |
| 14 | SWITCH OPERATOR (SCADA ONLY) | - | - | - | - |
| 15 | RTU (SCADA ONLY) | - | - | - | - |
| 16 | BRACKET, STAINLESS STEEL, 2" X 3" | 4 | - | S166072 | - |
| 17 | NUT, 1/2" HEX BRONZE | 4 | - | S506112 | - |
| 18 | GASKET (BY MANUFACTURER) | - | - | - | - |
| 19 | CONNECTOR, COMPRESSION (I) | AS REQ'D | - | - | - |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |

**NOTES:**

(I) NOT SHOWN OF FIGURES.

**REFERENCE:**

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

b. SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218 FOR SWITCH IDENTIFICATION.

c. SEE UG3408 FOR WIRE ENTRY PREVENTION AND MOISTURE ENTRY.

(d) SEE UG3418 FOR BOX PAD INSTALLATION.

e. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

f. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

g. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

h. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

i. SEE UG3489 FOR RETAINING WALLS.

j. SEE UG3583 FOR PAD MOUNTED PME 3 SECTIONALIZING SWITCH.

k. SEE UG4108 FOR INSTRUCTIONS TO SEAL JACKETED CABLE.

(l) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE TRENCH GROUND WIRE).

m. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

n. SEE UG4520 AND UG4521 (PREVIOUS # UG4520.1-.9) FOR GROUNDING PAD MOUNTED EQUIPMENT.

o. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

p. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

q. SEE UG4187 FOR CAM-LINK CONNECTION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED AIRBREAK PME 3 SECTIONALIZING SWITCH CABINET, 12KV, 600A

UG3584.3

**SCOPE:** THIS STANDARD SHOWS THE PAD MOUNTED 3-WAY 12KV 600A SF-6 GAS SWITCH CABINET.





**FIGURE 1**
ISOMETRIC VIEW

**TABLE 1**

| EQUIPMENT | WEIGHT (LBS) |
|---|---|
| MANUAL SWITCH | 825 |
| SCADA SWITCH | 1050 |
| ENCLOSURE | 370 |





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED 3-WAY 600A SF-6 GAS SWITCH CABINET (VISTA)

UG3585.1





**FIGURE 2**
CONNECTION DIAGRAM

**UG MAP SYMBOL**




3-WAY SWITCH

## TABLE 2

| ELECTRIC RATING | |
|---|---|
| VOLTAGE | 14.4KV |
| B.I.L. | 95KV |
| CURRENT, CONDITIONS | 600A |
| LOADMAKE AND LOADBREAK | 600A |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 12,500A |

## TABLE 3

| SWITCH STOCK NUMBER | | |
|---|---|---|
| **600A** | **STOCK NUMBER** | **DESIGN UNIT** |
| (STAINLESS STEEL) | S709046 | 3WAY-V |
| SCADA 3-WAY | S704698 | 3WAYVS |

## TABLE 4

| GAS SWITCH PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | ENCLOSURE, PAD MOUNTED |
| 2 | PANEL, REMOVABLE |
| 3 | SIGN, WARNING |
| 4 | NAME PLATE |
| 5 | LOCKING MECHANISM, PENTAHEAD BOLT |
| 6 | LIFT-UP ROOF, HINGED |
| 7 | TAB, RETRACTABLE LIFTING |
| 8 | BUSHING, 600A |
| 9 | TANK, SUBMERSIBLE, STAINLESS STEEL, SF-6, INSULATED |
| 10 | WINDOWS, FAULT INDICATOR (I) |
| 11 | MOTOR OPERATOR, "SCADA ONLY" |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) NOT SHOWN ON FIGURES.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION FOR PAD MOUNTED 3-WAY 600A SF-6 GAS SWITCH CABINET (VISTA).





**FIGURE 1**
**FRONT VIEW**





**FIGURE 1**
**SIDE VIEW**

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |





**FIGURE 2** (II)
HOLD DOWN DETAIL

## INSTALLATION:

A. THE SWITCH AND ENCLOSURE ARE SHIPPED ON ONE PALLET BUT ARE TWO SEPARATE ITEMS.

B. DO NOT ATTEMPT TO LIFT THE SWITCH AND SWITCH ENCLOSURE AT ONE TIME, DAMAGE WILL OCCUR TO THE ENCLOSURE LIFTING DEVICES.

(C) DO NOT REMOVE THE GALVANIZED REAR SWITCH MOUNTING BRACKET SUPPLIED BY THE MANUFACTURER.

D. MOUNT SWITCH TO PAD USING 1/2" X 1 1/2" BRONZE CAP SCREWS.

(E) SEAL CONDUIT WITH SEALING COMPOUND.

F. LOADBREAK ELBOWS SHALL NOT BE LANDED ON THE BACK OF THE 600A TEES EXCEPT FOR 1 LOADBREAK ELBOW FOR A SINGLE-PHASE TRANSFORMER (6930). THREE LOADBREAK ELBOWS MAY BE INSTALLED WHEN CONNECTED TO SWITCH WITH NO 600A TEES.

G. SCADA INSTALLATIONS REQUIRE AN ADDITIONAL PAD FOR THE RTU. AN ADDITIONAL 120V SOURCE MUST BE PROVIDED TO THE RTU.

(H) SCADA SWITCHES INCLUDE THE RTU AND CABLES, CONTROL CABLES ARE 45 FEET IN LENGTH. RTU PAD SHALL BE NO MORE THAN 30 FEET FROM SWITCH.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | SWITCH, 3-WAY, 600A | 1 | 3585 | S709046<br>S704698 | 3WAY-V |
| | SWITCH, SCADA, 3-WAY, 600A (H) | 1 | | | 3WAYVS |
| 2 | ENCLOSURE, PAD MOUNT | 1 | | | - |
| 3 | BOX PAD | 1 | 3419 | S513904 | 3419BP |
| 4 | CONNECTORS, 12KV, 600/200A | AS REQ'D | - | - | - |
| 5 | PADLOCK (C) | 2 | - | S514848 | 4WTFTS |
| 6 | ENCLOSURE, GROUND PAD | - | - | - | - |
| 7 | SWITCH, GROUND PAD | - | - | - | - |
| 8 | RING BUSS, 4/0 COPPER | - | - | - | - |
| 9 | GROUND, TRENCH, COPPER, #2 | 1 | 4510 | - | TG-E-Q |
| 10 | SEALING COMPOUND | AS REQ'D | 3948 | S442976 | - |
| 11 | GASKET, BY MANUFACTURER | - | - | - | - |
| 12 | INSERT, 1/2" X 13, BY PAD MANUFACTURER | - | - | - | - |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 13 | HOLD DOWN, BY MANUFACTURER | - | - | - | - |
| 14 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 6 | - | S616192 | - |
| 15 | WASHER, STANDARD FLAT, BRONZE, 1/2" (III) | 6 | - | S799488 | - |
| 16 | WASHER, LOCK SPRING (III) | 6 | - | S796416 | - |
| 17 | TAGS, CABLE IDENTIFICATION | AS REQ'D | 3202 | - | - |
| 18 | BRACKET, REAR SWITCH MOUNTING | 2 | - | - | - |
| 19 | MOTOR OPERATOR, "SCADA ONLY" | 3 | 3586 | - | - |

## NOTES:

I. SCADA SWITCH REQUIRES SEPARATE PAD MOUNTED RTU AND EXTERNAL 120V POWER SOURCE.

(II) 1/2 X 13 THREADED INSERTS INSTALLED IN 3419 PAD.

(III) NOT SHOWN ON FIGURES.

## REFERENCE:

(a) SEE UG3202 FOR CABLE IDENTIFICATION.

b. SEE UG3211 FOR ATTACHING STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

c. SEE UG3221 FOR HIGH VOLTAGE DECAL.

(d) SEE UG3408 FOR WIRE ENTRY PREVENTION.

e. SEE UG3419 FOR BOX PAD AND CONDUIT PLACEMENT.

f. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

h. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

i. SEE UG3489 FOR RETAINING WALLS.

j. SEE UG3409 RTU PAD.

k. SEE UG4355 FOR FAULT INDICATOR INSTALLATION.

l. SEE UG4510 FOR PREFERRED I AND ALTERNATE TRENCH GROUND WIRE.

m. SEE UG4520 AND UG4521 (PREVIOUS # UG4520) FOR EQUIPMENT GROUNDING.

n. SEE UG4525 FOR GROUNDING PREMOLDED CONNECTORS.

o. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

p. SEE DM6113 FOR AUTOMATIC FAULT INDICATOR APPLICATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 3/1/2002 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION FOR PAD MOUNTED AIRBREAK 12KV, 200A, PME-5 FUSED SWITCH CABINET.





**FIGURE 1**
COMPARTMENT 1
END VIEW





**FIGURE 2**
COMPARTMENT 2
END VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 10/28/2008 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED AIRBREAK PME-5 FUSED SWITCH CABINET
12KV, 200A



UG3588.1





**FIGURE 3**
HOLD-DOWN DETAIL AND RING BUSS SUPPORT

## INSTALLATION:

(A) SEAL CONDUITS WITH SEALING COMPOUND.

(B) BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT WIRE ENTRY.

C. SECURE ALL OF THE SWITCH DOORS WITH PENTAHEAD BOLTS AND 30 SERIES LOCKS.

(D) DO NOT CONNECT CONCENTRIC TO GROUND BAR.

(E) INSTALL CONDUITS SO THAT THE FEED IS CONNECTED TO THE SWITCH IN COMPARTMENT 1. COMPARTMENT 1 SHALL BE ON THE RIGHT SIDE AS ONE FACES THE CABINET FROM THE STREET OR SIDEWALK.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BOX PAD, FOR PME 3, AIR BREAK SWITCH | 1 | 3418 | S514040 | 3418BP |
| 2 | PADLOCK (I) | AS REQ'D | - | S514848 | 4WTFTS |
| 3 | WIRE, 4/0 THW (D) | AS REQ'D | 4530 | S808224 | THW4/0 |
| 4 | SWITCH, PME-5 | AS REQ'D | 3511 | S708969 | PME-05 |
| 5 | GROUND BAR | AS REQ'D | - | - | - |
| 6 | TAGS, IDENTIFICATION | AS REQ'D | 3202/3213-3218 | - | - |
| 7 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 4 | - | S616192 | - |
| 8 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 8 | - | S799488 | - |
| 9 | WASHER, LOCK SPRING | 4 | - | S796416 | - |
| 10 | SEALING COMPOUND | AS REQ'D | - | S442976 | - |
| 11 | WIRE, TRENCH GROUND | AS REQ'D | 4510 | - | TG-E-W |
| 12 | BRACKET, STAINLESS STEEL, 2" X 3" | 4 | - | S166072 | - |
| 13 | NUT, HEX, BRONZE, 1/2" | 4 | - | S506112 | - |
| 14 | GASKET, BY MANUFACTURER | - | - | - | - |
| 15 | CONNECTOR, COMPRESSION | AS REQ'D | - | - | - |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 10/28/2008 | D | | | | | | |

**NOTES:**

(I) NOT SHOWN OF FIGURES.

**REFERENCE:**

(a) SEE UG4310 FOR SM-4 FUSE CONVERSION.

b. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

c. SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218 FOR SWITCH IDENTIFICATION.

d. SEE UG3408 FOR WIRE ENTRY PREVENTION AND MOISTURE ENTRY.

(e) SEE UG3418 FOR BOX PAD INSTALLATION.

f. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

g. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

h. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

i. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM SUBGRADE RETAINING WALLS.

j. SEE UG3489 FOR RETAINING WALLS.

k. SEE UG3511 FOR PAD MOUNTED, PME-5, 200A, FUSED SWITCH.

l. SEE UG4108 FOR INSTRUCTIONS TO SEAL JACKETED CABLE.

m. SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE TRENCH GROUND WIRE).

n. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

o. SEE UG4520 AND UG4521 (PREVIOUS # UG4520) FOR GROUNDING PAD MOUNTED EQUIPMENT.

p. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

q. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 10/28/2008 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED AIRBREAK PME-5 FUSED SWITCH CABINET 12KV, 200A

UG3588.3

**SCOPE:** THIS STANDARD SHOWS A 12KV, 600A SERVICE RESTORER USED FOR PAD MOUNTED APPLICATIONS.





**FIGURE 1** (IV)
FRONT VIEW
TANK ONLY
SEE TABLE 1





**FIGURE 1**
SIDE VIEW






**FIGURE 1**
TOP VIEW
SEE TABLE 1




**DETAIL 1**

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3575 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1994 | D | | | | | | |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

PAD MOUNTED SERVICE RESTORER
12KV, 600A, THREE-PHASE



UG3590.1








**FIGURE 2**
CONNECTION DIAGRAM

## TABLE 1

| SERVICE RESTORER PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | HANDLE, CLOSE ENABLE & MANUAL TRIP |
| 2 | FLAG, CONTACT POSITION |
| 3 | COUNTER, MECHANICAL OPERATIONS |
| 4 | INFORMATION PLATE |
| 5 | DIAGRAM, NAME PLATE & CONNECTION |
| 6 | MANUAL CLOSE TOOL, DE-ENERGIZED RECLOSER |
| 7 | CONNECTOR, "ME" CONTROL |
| 8 | INDICATOR, OIL LEVEL |
| 9 | BRACKET, STAND-OFF |
| 10 | BUSHING |
| 11 | OIL DRAIN VALVE |
| 12 | GROUNDING LUG |
| 13 | CONTROL CABINET |

## TABLE 2

| ELECTRIC RATINGS | |
|---|---|
| VOLTAGE | 15.5KV |
| B.I.L. | 125KV |
| CURRENT, CONTINUOUS | 560A |
| MAX INTERRUPTING RATING (SYMMETRICAL) | 12,000A |
| MOMENTARY AND FAULT CLOSE (RMS, ASYMMETRICAL) | 20,000A |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 12,000A |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. PAD MOUNTED SERVICE RESTORER (S572112) IS DELIVERED FROM THE SUPPLIER WITH ALL THE PARTS LISTED IN TABLE 1.

II. SWITCH IS DELIVERED WITH OIL.

III. SWITCH NUMBERS ARE TO BE ISSUED BY THE ENGINEERING CLERK IN THE DISTRIBUTION FACILITIES INFORMATION SECTION.

IV WEIGHT: 1,520 LBS.

**REFERENCE:**

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION.

b. SEE UG3415 FOR PAD AND HANDHOLE INSTALLATION.

c. SEE UG3591 FOR SERVICE RESTORER INSTALLATION.

d. SEE DM6114 FOR SERVICE RESTORER APPLICATION.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3575 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/1994 | D | | | | | | |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION FOR PAD MOUNTED 12KV, 600A SERVICE RESTORER OVER A 3313 HANDHOLE WITH CAM-LINK CONNECTORS.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
SIDE VIEW





**FIGURE 2**
HOLD-DOWN ASSEMBLY DETAIL
TYPICAL BOTH SIDES OF EQUIPMENT PAD

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3576 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED SERVICE RESTORER
12KV, 600A AND 3313 HANDHOLE

UG3591.1

## INSTALLATION:

(A) THE ONLY 200A CABLE ALLOWED WILL BE SINGLE-PHASE TAPPED OFF THE TEES ON THE LINE SIDE, FUSED ELBOWS ARE ACCEPTABLE.

B. LINE SIDE, FUSED ELBOWS ARE ACCEPTABLE.

(C) AN ANTENNA MAY BE REQUIRED IF SUPERVISORY CABLE IS NOT AVAILABLE.

(D) SEAL CONDUITS WITH SEALING COMPOUND.

(E) BASE OF CABINET SHALL BE CAULKED TO PREVENT WIRE ENTRY.

(F) LOCK THE SWITCH DOOR WITH A SCHLAGE ELEC SERIES LOCK.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD, SERVICE RESTORER | 1 | 3415 | S514282 | 3415-B |
| 2 | HANDHOLE, 3313 BASE SECTION | 1 | 3313 | S162664 | |
| 3 | EQUIPMENT, GROUNDING FOR SERVICE RESTORER (k) | 1 | 4520 | - | - |
| 4 | SERVICE RESTORER | 1 | 3590 | S572112 | RESTOR |
| 5 | TAGS, IDENTIFICATION | AS REQ'D | 3202/3213-3218 | - | - |
| 6 | NUT, CLAMPING CHANNEL | 2 | - | S503520 | - |
| 7 | SCREW, HEX HEAD CARP, BRONZE, 1/2" X 1 1/2" | 2 | - | S616192 | - |
| 8 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 2 | - | S799488 | - |
| 9 | HOLD DOWN (SUPPLIED WITH CABINET) | 2 | - | - | - |
| 10 | CONNECTORS, 12KV, 600A, CAM-LINK OPERABLE (i)(l) | 6 | 4187 | S270240 | C-LINK |
| 11 | SEALING COMPOUND (D) | AS REQ'D | - | S442976 | - |
| 12 | PADLOCK, SCHLAGE ELEC SERIES (IV)(F) | 1 | - | S514848 | 4WTFTS |
| 13 | LINK, VISIBLE (IV) | 3 | 4187 | S270242 | V-LINK |

## NOTES:

I. ALL 200A CONNECTORS ON THE SERVICE RESTORER MUST BE LOADBREAK.

II. 120V AC SECONDARY MUST BE BROUGHT UP TO THE SERVICE RESTORER FOR CONTROL POWER. THE ACTUAL LOAD FOR THE CONTROL IS MINIMAL. USE THE UG STREETLIGHT NOMOGRAPH, DM5431 TO SIZE CONTROL POWER SECONDARY USING THE LOWEST POWER LEVEL SHOWN ON LINE "A". LIMIT TOTAL VOLTAGE DROP FROM THE TRANSFORMER STATION TO LESS THAN 4 PERCENT.

III. IF SECONDARY IS NOT AVAILABLE INSTALL AN "N" 1.5KVA TRANSFORMER INSIDE THE SERVICE RESTORER AIR CABINET.

(IV) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

b. SEE UG3415 FOR PAD AND HANDHOLE INSTALLATION.

c. SEE UG3479 FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC.

d. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

e. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

f. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE.

g. SEE UG3489 FOR RETAINING WALLS.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3576 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

**REFERENCE (CONT'D):**

h. SEE UG3590 FOR PAD MOUNTED SERVICE RESTORER.
(i) SEE UG4187 FOR CAM-LINK OPERABLE 600A CONNECTOR.
(j) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE TRENCH GROUND WIRE).
(k) SEE UG4520 AND UG4521 (PREVIOUS # UG4520) FOR GROUNDING PAD MOUNTED EQUIPMENT.
(l) SEE UG4525 FOR GROUNDING CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.
(m) SEE UG4645, UG4646, AND UG4647 FOR SCADA POLE AND ANTENNA.
n. SEE UG3709 FOR THE N 1.5KVA (6930/120V) DRY TYPE TRANSFORMER.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3576 | EDM | JIK | - | - | 5/17/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 7/1/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 1/1/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 3 OF 3

INSTALLATION OF PAD MOUNTED SERVICE RESTORER
12KV, 600A AND 3313 HANDHOLE

UG3591.3

# 3600 - SUBSURFACE SECTIONALIZING EQUIPMENT

# 3600 - SUBSURFACE SECTIONALIZING EQUIPMENT

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 3605 | SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET |
| 3644 | EQUIPMENT INSTALLATIONS IN SUBSTRUCTURES |
| 3645 | UNOBSTRUCTED SPACE |
| 3646 | CABLE AND CONNECTOR PLACEMENT |
| 3647 | EQUIPMENT DIMENSIONS AND PLACEMENT |
| 3648 | EQUIPMENT ASSEMBLIES |
| 3649 | EQUIPMENT COMBINATION GUIDELINES (INCLUDING WALK IN VAULTS) |
| 3660 | SECTIONALIZING HANDHOLE - 200A, 6.9KV SINGLE-PHASE |
| 3669 | 600A SUBSURFACE/SURFACE OPERABLE 4-WAY SF-6 GAS SWITCH (VISTA) |
| 3670 | 600A 6-WAY SF-6 GAS SWITCH (VISTA) WITH THREE FAULT INTERRUPTERS |
| 3671 | INSTALLATION OF SUBSURFACE/SURFACE OPERABLE SWITCH IN A 3317 HANDHOLE |
| 3672 | G & W G-RAM 4-WAY GAS SWITCH WITH GROUNDING POSITIONS |
| 3675 | SUBSURFACE APPLICATION OF ELASTIMOLD VACUUM SWITCH/INTERRUPTER |
| 3677 | TRAYER VAULT-MOUNTED SWITCH GEAR |
| 3678 | TRAYER 3-WAY SUBMERSIBLE LIQUID INSULATED VACUUM SWITCHGEAR |
| 3679 | TRAYER 4-WAY GROUNDED VACUUM SWITCH |
| 3680 | INNOVATIVE SWITCH GEAR SUBMERSIBLE AND VAULT MOUNT |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | ADDED 3680 | - | DG | JS | CZH | 05/01/2018 | E | | | | | | |
| A | ADDED 3679 | - | DS | TR | MDJ | 05/13/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

SUBSURFACE SECTIONALIZING EQUIPMENT
TABLE OF CONTENTS

UG3601.1

**SCOPE:** THIS STANDARD SHOWS THE REFERENCE SHEET ON SUBSTRUCTURE USE AND LIMITATIONS.

## TABLE 1

| STRUCTURE USE AND LIMITATIONS | | | |
|---|---|---|---|
| **SUBSTRUCTURE** | **DIMENSIONS** | **TYPE** | **MAJOR USE OF LIMITATION** |
| 3309.1 | 36" X 24 1/4" X 18" | SINGLE-PHASE HANDHOLE | ALLOWS FOR A MAX OF 3 CONNECTORS WITH 8 TERMINAL POSITIONS EACH. THE 8 RUNS SHALL NOT EXCEED ONE RUN 500 KCMIL, 3 RUNS 350 KCMIL, 2 RUNS 3/0 AND ONE STREET LIGHT RUN. |
| 3309.2 | 36" X 24 1/4" X 26" | SINGLE-PHASE HANDHOLE | ALLOWS FOR A MAX OF 3 CONNECTORS WITH 7 TERMINAL POSITIONS EACH. THE 7 RUNS SHALL NOT EXCEED 2 RUNS 500 KCMIL, 2 RUNS 350 KCMIL, 2 RUNS 3/0 AND ONE STREET LIGHT RUN. |
| 3309.2 | 36" X 24 1/4" X 26" | THREE-PHASE HANDHOLE | ALLOWS FOR A MAX OF 4 CONNECTORS WITH 7 TERMINAL POSITIONS EACH. THIS SHALL NOT EXCEED 5 RUNS THREE-PHASE CONSISTING OF ONE RUN 350 KCMIL AND 4 RUNS 3/0 AND ONE STREET LIGHT RUN. |
| 3311 | 14" X 66" X 14" | HANDHOLE | FOR PRIMARY AND SECONDARY CABLE TRAINING BETWEEN TWO SINGLE-PHASE PADMOUNT TRANSFORMERS CONNECTED IN AN OPEN DELTA BANK. |
| 3311 | 14" X 108" X 14" | HANDHOLE | FOR PRIMARY AND SECONDARY CABLE TRAINING BETWEEN THREE SINGLE-PHASE PADMOUNT TRANSFORMERS FOR CLOSED DELTA BANK, WHEN HKR TRANSFORMER CANNOT BE USED. |
| 3312 | 17" X 30" X 12" | HANDHOLE-1 BODY SECONDARY AND UNDER PAD | MAY BE USED FOR REPLACEMENT OF EXISTING FACILITIES. ALL EQUIPMENT FACILITIES REQUIRING 30" X 17" BOX UNDER PAD MOUNTED EQUIPMENT. |
| 3313 | 24" X 36" X 24" | HANDHOLE SECONDARY | ALLOWS A MAXIMUM OF FOUR RUNS OF 350 KCMIL SINGLE-PHASE OR THREE-PHASE PLUS SERVICES SMALLER THAN 350, OR A MAXIMUM OF THREE RUNS OF 500 KCMIL SINGLE-PHASE OR THREE-PHASE. NO PRIMARY AND SECONDARY ALLOWED TOGETHER. NO 1000 KCMIL ALLOWED. |
| 3313 | 24" X 36" X 24" | HANDHOLE PRIMARY | ALLOWS SINGLE-PHASE (6.9KV OR 12KV) PRIMARY CABLE DEADBREAK CONNECTIONS FOR TWO RUNS (200A TEE CONNECTOR WITH DEADBREAK ELBOWS ONLY, NOT A STRAIGHT SPLICE) OR ONE 3-WAY CABLE TAP AND LOADBREAK ELBOWS WITH THREE CABLE RUNS MAXIMUM. #2 SOLID IS THE MAXIMUM CABLE ON EACH INSTALLATION. NO FUSED ELBOWS OR 4-WAY CABLE TAPS ALLOWED. NO SECONDARY ALLOWED. |
| 3314 | 36" X 6" X 48" | HANDHOLE PRIMARY & SECONDARY | FOR THREE-PHASE #2/0 OR SMALLER PRIMARY CABLE PLUS SECONDARIES (500 KCMIL MAX). AN UNOBSTRUCTED SPACE OF 18" X 42" MUST BE MAINTAINED.<br>EXAMPLE:<br>A MAXIMUM INSTALLATION WOULD BE THREE 4-WAY CABLE TAPS WITH LOADBREAK ELBOWS ON ONE WALL AND TWO RUNS OF 3/C - 2/0 ON OPPOSITE WALL. ONE OF THESE RUNS CAN HAVE THREE STRAIGHT SPLICES (UG3646, FIGURE 1). THIS WOULD NOT ALLOW ANY SECONDARIES, FUSED OR ELBOWS. TO OBTAIN REQUIRED UNOBSTRUCTED SPACE, THE 3/C - 2/0 SPLICES AND STRAIGHT RUN MUST BE RACKED ON THE SMALL CABLE HOOKS, SEE UG4178. (a)(b)(d) |
| 3315 | 4'-0" X 6'-6"X 6'-7" | HANDHOLE PRIMARY & SECONDARY | FOR ALL SIZES OF PRIMARY AND UP TO 500 KCMIL SECONDARY CABLES MAX. AN UNOBSTRUCTED SPACE OF 18" X 48" MUST BE MAINTAINED.<br>EXAMPLE:<br>MAXIMUM INSTALLATION CONSISTS OF 3-350 KCMIL OR LARGER ELBOW TEE SPLICED THREE-PHASE PRIMARY CIRCUITS ON OPPOSITE WALLS, EACH ONE TAPPED WITH ONE THREE-PHASE DISTRIBUTION RUN. THE THREE TEE COMBINATION SHALL ONLY BE USED TO FEED A SWITCHED TIE POSITION. |
| 3316 | 5'-0" X 8'-6" X 7'-0" | HANDHOLE PRIMARY & SECONDARY | FOR ALL SIZES OF PRIMARY AND UP TO 500 KCMIL SECONDARY CABLES MAX. AN UNOBSTRUCTED SPACE OF 22" X 72" MUST BE MAINTAINED.<br>EXAMPLE:<br>MAXIMUM INSTALLATION CONSISTS OF 3-350 KCMIL OR LARGER ELBOW TEE SPLICED THREE-PHASE PRIMARY CIRCUITS ON OPPOSITE WALLS, EACH ONE TAPPED WITH ONE THREE-PHASE DISTRIBUTION RUN. IN THE SAME HANDHOLE, 6-200A TEES WITH 12 DEADBREAK ELBOWS OR 600V CONNECTORS ON OPPOSITE WALLS. THE THREE TEE COMBINATION SHALL ONLY BE USED TO FEED A SWITCHED TIE POSITION. |
| 3317 (SWITCH ENCLOSURE) | 6'-0" X 8'-0" X 7'-0" | HANDHOLE PRIMARY & SECONDARY | FOR ALL SIZES OF PRIMARY CABLE CONNECTED TO SWITCH. SECONDARY CABLE IS LIMITED TO A FEED TO SUMP PUMP AND/OR SCADA. AN UNOBSTRUCTED SPACE OF 36" X 70" MUST BE MAINTAINED. NO CABLE MAY PASS THROUGH OR BE SPLICED IN STRUCTURE. |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 03/01/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUBSTRUCTURE USE AND LIMITATIONS REFERENCE SHEET

UG3605.1

## TABLE 1 (CONT'D)

| STRUCTURE USE AND LIMITATIONS | | | |
|---|---|---|---|
| **SUBSTRUCTURE** | **DIMENSIONS** | **TYPE** | **MAJOR USE OF LIMITATION** |
| 3325 | 8'-0" X 14'-0" X 9'-6" | MANHOLE PRIMARY & SECONDARY | FOR ALL SIZES OF PRIMARY AND UP TO 500 KCMIL SECONDARY CABLES MAX. AN UNOBSTRUCTED SPACE OF 36" X 10" FOR 14-FOOT MANHOLE OR 36" X 16' FOR 20-FOOT MANHOLE MUST BE MAINTAINED. EXAMPLE: MAXIMUM INSTALLATION CONSISTS OF ONE 4-WAY SWITCH IN A 14-FOOT LONG MANHOLE AND TWO 4-WAY SWITCHES IN A 20-FOOT LONG MANHOLE. A 20-FOOT LONG MANHOLE IS THE MAXIMUM ALLOWABLE SIZE. NO CABLE TAPS ALLOWED. ALWAYS MAINTAIN AN UNOBSTRUCTED SPACE, AS MENTIONED ABOVE, TO ALLOW ACCESSIBILITY TO CABLE, EQUIPMENT, AND CONDUIT. (b)(c) |
| 3326 | 8'-0" X 20'-0" X 9'-6" | | |

## INSTALLATION:

A. TO AVOID CUTTING THE CONDUIT BENDS, SUBSTRUCTURES AND/OR CABLE POLES WHICH REQUIRE A 90 DEGREE BEND SHALL BE LOCATED FAR ENOUGH AWAY FROM EACH OTHER TO ALLOW ROOM ENOUGH FOR THE TWO 90 DEGREE BENDS. THIS WILL VARY DEPENDING ON THE SIZE OF THE 90 DEGREE BEND.

B. IN EACH SUBSTRUCTURE, AS MANY CONDUIT KNOCKOUTS MAY BE USED AS NEEDED, PROVIDING PROPER INSTALLATION IS FOLLOWED AND REQUIRED UNOBSTRUCTED SPACE IS MAINTAINED. INSTALL CONDUITS USING THE LOWER SET OF KNOCKOUTS FIRST, UNLESS OTHERWISE SPECIFIED ON JOB PRINT. IF ONLY ONE CONDUIT IS REQUIRED, USE THE BOTTOM OUTSIDE (CLOSEST TO THE WALL) KNOCKOUT.

(C) **ONE RUN**: CABLE IN CONDUIT RUNNING FROM ONE LOCATION TO ANOTHER LOCATION.





**FIGURE 1** (C)
EXAMPLE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) SEE UG4178.
(b) FOR EQUIPMENT COMBINATION GUIDELINES, SEE UG3649.
(c) FOR MINIMUM BENDING RADII, SEE UG4008.
(d) SEE UG3646.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 03/01/2002 | D | | | | | | |

**SCOPE:** THIS STANDARD DESCRIBES THE SPACE LIMITATIONS AND PROPER CABLE AND EQUIPMENT INSTALLATION STANDARDS IN SUBSTRUCTURES.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**THERE ARE FIVE STANDARDS PERTAINING TO THE PROPER INSTALLATION OF EQUIPMENT IN SUBSTRUCTURES:**

I. **UNOBSTRUCTED SPACE - UG3645**
   a. UNOBSTRUCTED SPACE REQUIREMENTS FOR EACH SUBSTRUCTURE.

II. **CABLE AND CONDUIT PLACEMENT - UG3646**
   a. PROPER CABLE AND CONDUIT INSTALLATION.

III. **EQUIPMENT DIMENSIONS AND PLACEMENT - UG3647**
   a. PROPER INSTALLATION AND APPLICATION OF CABLE RACKING.

IV. **EQUIPMENT ASSEMBLIES - UG3648**
   a. THE COMMON EQUIPMENT ASSEMBLIES ILLUSTRATED AND DIMENSIONED FOR EASE OF DESIGN AND INSTALLATION IN SUBSTRUCTURES.

V. **EQUIPMENT COMBINATION GUIDELINES - UG3649**
   a. THIS STANDARD PRESENTS ILLUSTRATIONS OF THE MOST COMMON EQUIPMENT CONFIGURATIONS THAT ARE ALLOWED OR NOT ALLOWED IN VARIOUS SUBSTRUCTURES.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | DRH | 03/15/1982 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |
| SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS | | | | |
| SHEET 1 OF 1 | EQUIPMENT INSTALLATIONS IN SUBSTRUCTURES | | | UG3644.1 |

**SCOPE:** THIS STANDARD SHOWS THE MINIMUM UNOBSTRUCTED SPACE REQUIRED INSIDE A SUBSTRUCTURE TO ALLOW PERSONNEL TO PERFORM WORK SAFELY AND FREE FROM ANY OBSTRUCTIONS.





**FIGURE 1**
UNOBSTRUCTED SPACE




**FIGURE 2**
CORRECT UNOBSTRUCTED SPACE
END VIEW




**FIGURE 2**
CORRECT UNOBSTRUCTED SPACE
PLAN VIEW




**FIGURE 3**
INCORRECT UNOBSTRUCTED SPACE
END VIEW




**FIGURE 3**
INCORRECT UNOBSTRUCTED SPACE
PLAN VIEW

**TABLE 1**

| UNOBSTRUCTED SPACE REQUIREMENTS | |
|---|---|
| **SUBSTRUCTURE** | **UNOBSTRUCTED SPACE** |
| 3314 | 18" X 42" |
| 3315 | 18" X 48" |
| 3316 | 22" X 72" |
| 3316 AND SUBSURFACE/SURFACE OPERABLE SWITCH | 20" X 60" |
| 3325 (14'-0" LONG) | 36" X 10'-0" |
| 3326 (20'-0" LONG) | 36" X 16'-0" |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. AN UNOBSTRUCTED SPACE MUST BE MAINTAINED IN EACH SUBSTRUCTURE TO ALLOW PERSONNEL TO SAFELY ENTER OR EXIT THE SUBSTRUCTURE AND PERFORM WORK.

II. AN UNOBSTRUCTED SPACE SHOULD BE IN THE CENTER OF A SUBSTRUCTURE WHENEVER POSSIBLE.

III. THE UNOBSTRUCTED SPACE MAY BE REDUCED DURING CONSTRUCTION FOR PULLING, TRAINING AND TERMINATING CABLES, ETC., BUT NO PORTION OF THE FINAL UNOBSTRUCTED SPACE MAY BE REDUCED BY CABLES, CABLE RACKS, ETC.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

UNOBSTRUCTED SPACE

UG3645.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS CABLE PLACEMENT IN 3314 AND 3315 SUBSTRUCTURES TO ASSURE PROPER CABLE TRAINING.

**ATTENTION:**

* CABLE PULLED STRAIGHT THROUGH MUST ENTER AND EXIT THE SAME CONDUIT POSITION ON OPPOSITE ENDS. (m)





**FIGURE 1**
3314 HANDHOLE
PLAN VIEW





**FIGURE 2**
SECTION VIEW
3314 HANDHOLE

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



CABLE AND CONNECTOR PLACEMENT

UG3646.1

TABLE OF CONTENTS





**FIGURE 3**
3315 HANDHOLE
PLAN VIEW





**FIGURE 3**
VIEW A-A
TYPICAL BOTH ENDS





**FIGURE 4**
3315 HANDHOLE
CABLE TAP AND 600A "T" COMBINATION
PLAN VIEW





**FIGURE 4**
VIEW A-A
TYPICAL BOTH ENDS

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed





**FIGURE 5**
3315 HANDHOLE
CABLE TAP AND 600A "T" COMBINATION
SECTION VIEW





**FIGURE 5**
VIEW A-A
TYPICAL BOTH ENDS





**FIGURE 6**
3315 HANDHOLE
CABLE TAP COMBINATION - WALL OPPOSITE 600A TEES
SECTION VIEW

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed





**FIGURE 7**
3315 HANDHOLE
SECTION VIEW

**FIGURE 7**
VIEW A-A
TYPICAL BOTH ENDS





**FIGURE 8**
3314, 3315 & 3316 HANDHOLES
CABLE TAP ANGLE
SIDE VIEW

**ATTENTION:**


* BEFORE DESIGNING THE INSTALLATION OF HANDHOLES, IT IS IMPORTANT TO FIRST DETERMINE ON WHICH SIDE THE CABLE TAPS WILL BE PLACED, THEN INSTALL THE OTHER CABLES ACCORDINGLY. DO NOT INSTALL CABLE TAPS ON HANDHOLE ENDS. (m)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |



TABLE OF CONTENTS




**DETAIL 1**
3314, 3315 & 3316 HANDHOLES
TEE BRACKET ANGLE & INSTALLATION MEASUREMENTS
FRONT VIEW

## ATTENTION:

* THIS ILLUSTRATION APPLIES TP 2-WAY OR 3-WAY 600A TEE COMBINATION. MAY BE INSTALLED AT EITHER END.

## INSTALLATION:

(A) LEAVE AN UNOBSTRUCTED SPACE FREE OF CABLE INTRUSION BY CABLING AROUND WALLS. UNUSED CONDUITS MUST BE ACCESSIBLE FOR FUTURE CABLES. LEAVE ADEQUATE SPACE FOR BLOWING PULL ROPES IN CONDUITS AND/OR CABLE PULLING.

(B) AS TAP POSITIONS ARE USED, REDUCE QUANTITY OF ITEM 15 ACCORDINGLY.

C. NOTE ORIENTATION OF ELBOW TEES AND CABLE LOOPS TO ALLOW FOR CABLE EXPANSION TO PREVENT DAMAGE.

(D) LOADBREAK ELBOWS SHOULD ALWAYS BE POSITIONED VERTICALLY TO ALLOW FOR MAXIMUM ELECTRICAL GROUND CLEARANCE TO ADJACENT ELBOWS WHEN SWITCHING ENERGIZED. CABLES BE INSERTED STRAIGHT INTO ELBOWS SO AS NOT TO ALLOW BENDING OF ELBOW ENTRANCE. ELBOWS SHOULD BE INSTALLED AT APPROXIMATELY 40 DEGREE ANGLE.

(E) 350, 750 OR 1000 KCMIL CABLES TO BE TERMINATED WITH 600A TEE CONNECTORS SHALL BE ON THE WALL OPPOSITE ANY CABLE TAPS. THIS CABLE SHALL BE IN THE BOTTOM OUTSIDE CONDUIT ENTERING AND LEAVING AND SHALL BE RACKED OR TERMINATED ON THE SAME WALL OF THE CONDUIT BANK THAT THE CABLE ENTERS AND LEAVES (POSITION 1). USE POSITIONS 3 AND 4 FOR SMALLER CABLES (SEE FIGURES 4 AND 5).

(F) 350, 750 AND 1000 KCMIL PRIMARY OR CABLES PULLED STRAIGHT THROUGH WITHOUT ANY TERMINATIONS SHALL BE PULLED IN THE BOTTOM CONDUITS (POSITION 1 AND 2) AND SHALL BE RACKED ON THE SAME WALL OF THE DUCT BANK THAT THE CABLE ENTERS AND LEAVES. (DO NOT INSTALL ON THE SAME SIDE AS 600A TEES).

(G) #2 OR 2/0 PRIMARY CABLES OR SECONDARY (500 KCMIL MAX.) MAY BE PULLED IN ANY CONDUIT NOT USED FOR LARGER CABLES AS DESCRIBED IN INSTALLATION NOTES 'E' AND 'F'. IF CONDUITS ARE NOT BEING USED AS DESCRIBED IN THESE NOTES, LEAVE THEM EMPTY FOR FUTURE LARGER SIZED CABLES UNLESS THERE IS NO POSSIBLE FUTURE LOAD. (E) (F)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



CABLE AND CONNECTOR PLACEMENT

UG3646.5

TABLE OF CONTENTS

## INSTALLATION (CONT'D.):

H. DO NOT USE UNISTRUT FOR MOUNTING CABLE TAPS.

(J) DO NOT INSTALL EQUIPMENT ON 12-INCH TOP SECTION OF HANDHOLES AS THIS SECTION IS USED FOR FINAL GRADE ADJUSTMENTS.

K. FOR MAINTENANCE OR TROUBLE SITUATIONS THAT INVOLVE CABLE WITH FIBER OPTIC CABLE IN THE SAME CONDUIT, CUT THE FIBER IN THE CLEAR AND ALWAYS REINSTALL NEW POWER CABLE WITH MAXCELL SLEEVE AND FIBER OPTIC. (n)

1. MAXCELL SLEEVE SHALL HAVE TWENTY FEET OF SLACK BEYOND THE CONDUIT.

L. IF A CONDUIT HAS FIBER OPTIC CABLE ALREADY INSTALLED AND IS NEEDED FOR UG CABLE, INSTALL NEW CABLE WITH MAXCELL SLEEVE AND FIBER OPTIC.

M. FIBER OPTIC CABLE WILL BE INSTALLED BY SDG&E CREWS.

N. TELECOMMUNICATION CREWS TO MAKE FIBER OPTIC CABLE TERMINATIONS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | TEE BRACKET, INSULATORS INCLUDED (f) | 1 | 4177/4178 | S166675 | T/BRKT |
| 2 | HANGER, 15" | AS REQ'D | 4177/4178 | S564512 | - |
| 3 | CABLE HOOK, 2 1/2" | AS REQ'D | 4177/4178 | S415110 | - |
| 4 | INSULATOR, CABLE | AS REQ'D | 4177/4178 | S430592 | - |
| 5 | ADAPTER, CABLE ARM | AS REQ'D | 4177/4178 | S102016 | - |
| 6 | ARM, CABLE, 3-WAY | AS REQ'D | 4177/4178 | S110528 | - |
| 7 | CONNECTOR ASSEMBLY, 200/600A | AS REQ'D | 4181 | - | - |
| 8 | TAG, DO NOT OPERATE ENERGIZED | 3 | 3232 | S547966 | - |
| 9 | CABLE TAP, 12KV, 3-WAY OR 4-WAY | 3 | 4195 | - | - |
| 10 | CABLE, #2 OR #2/0 PECN | AS REQ'D | 4003 | - | - |
| 11 | ELBOW, LOADBREAK, 12KV | AS REQ'D | 4190 | - | - |
| 12 | CAP, INSULTING RECEPTACLE | AS REQ'D | 4195 | S204304 | INSREC |
| 13 | TAGS, CABLE IDENTIFICATION | AS REQ'D | 3202 | - | - |
| 14 | ELBOW, DEADBREAK, 12KV | AS REQ'D | 4196 | - | - |
| 15 | ARM. CABLE, 4-WAY (B) | AS REQ'D | 4177/4178 | S110560 | - |
| 16 | STRAP, TIE (f) | AS REQ'D | 4177/4178 | S738440 | - |
| 17 | INSULATOR, UNISTRUT (REPLACEMENT ITEM) | AS REQ'D | 4177/4178 | S430560 | - |
| 18 | CABLE, FIBER OPTIC | AS REQ'D | 4600 | - | - |

## NOTES: NONE

## REFERENCE:

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION.

b. SEE UG3374 FOR CONDUIT TERMINATION.

c. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

e. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

**REFERENCE (CONT'D):**

(f) SEE UG3489 FOR RETAINING WALLS.

(g) SEE UG4174 AND UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART.

(h) SEE UG4177 AND 4178 FOR TEE BRACKET AND STAND OFF BAR.

(i) SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

(j) SEE UG4540 FOR GROUNDING SUBSTRUCTURES AND EQUIPMENT.

k. SEE UG4550 FOR GROUNDING TELCO CONDUCTOR IN HANDHOLES.

l. SEE DM5721 FOR CONDUIT POSITION WITHIN SUBSTRUCTURES.

(m) SEE UG3647 FOR PLACEMENT OF CABLE TAPS.

(n) CONTACT STEVEN HUNDLEY, PROJ. MGR - 111
EMAIL: SHUNDLEY@SDGE.COM
WORK PHONE: 619.676.7790
CELL: 619.929.8705

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

**SCOPE:** THIS STANDARD SHOWS CABLE PLACEMENT IN 3316 STRUCTURES TO ENSURE PROPER CABLE TRAINING.





**FIGURE 1**
3316 HANDHOLE
600A "T" COMBINATION
PLAN VIEW

**FIGURE 1**
VIEW A-A
TYPICAL BOTH ENDS





**FIGURE 2**
3316 HANDHOLE
600A "T" COMBINATION
SECTION VIEW

**FIGURE 2**
VIEW A-A
TYPICAL BOTH ENDS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 8 OF 12

CABLE AND CONNECTOR PLACEMENT

UG3646.8

TABLE OF CONTENTS





**FIGURE 3**
VIEW A-A
TYPICAL BOTH ENDS

6-200A TEES W/12
DEADBREAK ELBOWS OR
600V CONNECTOR

**FIGURE 3**
3316 HANDHOLE
600A "T" COMBINATION
PLAN VIEW





**FIGURE 4**
3316 HANDHOLE
600A "T" COMBINATION
SECTION VIEW

**FIGURE 4**
VIEW A-A
TYPICAL BOTH ENDS

**ATTENTION:**

* CABLE PULLED STRAIGHT THROUGH MUST ENTER AND EXIT CONDUIT POSITIONS ON OPPOSITE ENDS.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 9 OF 12

CABLE AND CONNECTOR PLACEMENT

UG3646.9

TABLE OF CONTENTS






**FIGURE 5**
3314, 3315 & 3316 HANDHOLES
CABLE TAP ANGLE
SIDE VIEW

**ATTENTION:**

* BEFORE DESIGNING THE INSTALLATION OF HANDHOLES, IT IS IMPORTANT TO FIRST DETERMINE ON WHICH SIDE THE CABLE TAPS WILL BE PLACED, THEN INSTALL THE OTHER CABLES ACCORDINGLY. DO NOT INSTALL CABLE TAPS ON HANDHOLE ENDS. (1)




**DETAIL 1**
3314, 3315 & 3316 HANDHOLES
TEE BRACKET ANGLE & INSTALLATION MEASUREMENTS
FRONT VIEW

**ATTENTION:**

* THIS ILLUSTRATION APPLIES TP 2-WAY OR 3-WAY 600A TEE COMBINATION. (MAY BE INSTALLED AT EITHER END.)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

## INSTALLATION:

(A) LEAVE AN UNOBSTRUCTED SPACE FREE OF CABLE INTRUSION BY CABLING AROUND WALLS. UNUSED CONDUITS MUST BE ACCESSIBLE FOR FUTURE CABLES. LEAVE ADEQUATE SPACE FOR BLOWING PULL ROPES IN CONDUITS AND/OR CABLE PULLING.

(B) NOTE ORIENTATION OF ELBOW TEES AND CABLE LOOPS TO ALLOW FOR CABLE EXPANSION AND TO PREVENT DAMAGE.

(C) THE CABLES TERMINATED ON THE TEE BRACKET SHALL BE RACKED OR TERMINATED ON THE SAME WALL OF THE CONDUIT BANK THAT THE CABLE ENTERS AND LEAVES (POSITION 1 & 2).

(D) USE POSITION #4 FOR SPARE FEEDER CONDUIT.

(E) #2 OR 2/0 PRIMARY CABLES MAY BE PULLED IN ANY CONDUIT NOT USED FOR LARGER CABLES AS DESCRIBED IN INSTALLATION NOTES "C" AND "D". IF CONDUITS ARE NOT BEING USED AS DESCRIBED IN THESE NOTES, LEAVE THEM EMPTY FOR FUTURE LARGER SIZED CABLES UNLESS THERE IS NO POSSIBLE FUTURE LOAD. (C)(D)

(F) DO NOT INSTALL EQUIPMENT ON TOP SECTION OF HANDHOLES AS THIS IS USED FOR FINAL GRADE ADJUSTMENT.

G. FOR MAINTENANCE OR TROUBLE SITUATIONS THAT INVOLVE FIBER OPTIC CABLES, ALWAYS REINSTALL FIBER OPTIC. IF A CONDUIT HAS FIBER OPTIC CABLES ALREADY INSTALLED AND IS NEEDED FOR UG CABLE, INSTALL FIBER OPTIC CABLES WITH NEW CABLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | TEE BRACKET | 1 | 4177/4178 | S166675 | - |
| 2 | CLAMP, GROUND ROD (I) | 2 | - | S230018 (X) | - |
| 3 | WIRE, BARE COPPER, #2 (I) | AS REQ'D | - | S812818 (X) | - |
| 4 | WIRE, BARE COPPER, #1/0 (I) | AS REQ'D | - | S812752 | - |
| 5 | INSULATOR, CABLE | AS REQ'D | 4177/4178 | S430592 | - |
| 6 | ADAPTOR, CABLE ARM | AS REQ'D | 4177/4178 | S102016 | - |
| 7 | ARM, CABLE, 3-WAY | AS REQ'D | 4177/4178 | S110528 | - |
| 8 | ELBOW, LOADBREAK, 12KV | AS REQ'D | 4190 | - | - |
| 9 | CONNECTOR ASSEMBLY, 200/600A | AS REQ'D | 4181 | - | - |
| 10 | TAG, DO NOT OPERATE ENERGIZED (I) | 12 | 3232 | S647966 | - |
| 11 | TAGS, CABLE IDENTIFICATION | AS REQ'D | 3202 | - | - |
| 12 | ELBOW, DEADBREAK, 12KV | AS REQ'D | 4196 | - | - |
| 13 | ARM, CABLE, 4-WAY | AS REQ'D | 4177/4178 | S110560 | - |
| 14 | TIE STRAP | AS REQ'D | 4177/4178 | S738440 | - |
| 15 | CABLE, FIBER OPTIC | AS REQ'D | 4600 | - | - |

## NOTES:

(I) NOT SHOWN ON FIGURES

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION.

b. SEE UG3374 FOR CONDUIT TERMINATION.

c. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS.

d. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

e. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

f. SEE UG3489 FOR RETAINING WALLS.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

**REFERENCE (CONT'D):**

g. SEE UG4174 AND UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART.

(h) SEE UG4177 AND UG4178 FOR TEE BRACKET AND STAND OFF BAR.

(i) SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

(j) SEE UG4540 FOR GROUNDING SUBSTRUCTURES AND EQUIPMENT.

k. SEE UG4550 FOR GROUNDING TELCO CONDUCTOR IN HANDHOLES.

(l) SEE UG3647 FOR CABLE TAPS.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | ADW | JES | CZH | 07/13/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1994 | D | BILL OF MATERIALS UPDATE | EDM | EJA | GLW | FRC | 01/24/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CABLE AND CONNECTOR PLACEMENT

UG3646.12

**SCOPE:** THIS STANDARD SHOWS CABLE TAP PLACEMENT AND DIMENSIONAL AREA NEEDED TO INSTALL COMPONENTS SO THAT AN UNOBSTRUCTED SPACE IN THE MIDDLE OF THE SUBSTRUCTURE IS PROVIDED IN A 3314, 3315 OR 3316 HANDHOLE.





**FIGURE 1**



**FIGURE 2**





**FIGURE 3**

CABLE RACKING

**FIGURE 4**

## INSTALLATION:

A. USE FIGURES 1-4 TO DETERMINE THE WALL ON WHICH TO INSTALL CABLE TAPS IN A 3314, 3315 OR 3316 HANDHOLE. IF FIELD CONDITIONS DO NOT ALLOW A 5 FOOT MINIMUM CLEARANCE FOR HOT STICK OPERATION OF THE CABLE TAPS, CABLE TAPS MAY BE LOCATED ON THE OPPOSITE WALL TO OBTAIN THE 5 FOOT MINIMUM CLEARANCE. THIS SHOULD BE DONE IN THE DESIGN STAGE OF THE JOB.

(B) DO NOT INSTALL CABLE TAPS ON UNISTRUT IN SUBSTRUCTURE.

C. ON CABLE HANGERS WITH CABLE HOOKS, LEAVE ONE HOLE OPEN BETWEEN EACH HOOK.

## TABLE 1

**CABLE TAP & ELBOW DISTANCES BETWEEN WALL AND OUTER PORTION OF CABLE RADIUS (X)**











| DESCRIPTION | DISTANCE "A" (MAXIMUM FROM WALL) | DRAWING |
|---|---|---|
| LOADBREAK ELBOW ON A CABLE TAP | 1'-2" |   |
| LOADBREAK ELBOW ON STANDOFF PLUG (THIS IS A PERMANENT INSTALLATION FOR THE LOOP SYSTEM) | 1'-5" |   |
| FUSED ELBOW ON CABLE TAP | 1'-5" |   |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | EJA | GLW | CZH | 07/27/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1989 | D | | | | | | |

## TABLE 2

| DISTANCES REQUIRED FROM FACE OF WALL AND MAXIMUM CABLE SIZE | | | |
|---|---|---|---|
| **DESCRIPTION** | **DISTANCE "A" (MAXIMUM FROM WALL)** | **DRAWING** | **MAXIMUM CABLING** |
| SMALL CABLE HOOK & HANGER<br>HOOK STOCK NUMBER S415432 (X)<br>HANGER STOCK NUMBERS:<br>12" HANGER S677288 (X)<br>24" HANGER S677290 (X)<br>36" HANGER S677292 (X) | 4" |  | SECONDARY<br>3-500 & 1-350 KCMIL<br><br>PRIMARY<br>1/C-ALL SIZES OR 3-1/C-2/0<br>(ALL 200 AMP CONNECTORS WILL FIT IN THIS HOOK) |
| LARGE CABLE HOOK & HANGER<br>HOOK STOCK NUMBER S610948 (X)<br>HANGER STOCK NUMBERS:<br>12" HANGER S677288 (X)<br>24" HANGER S677290 (X)<br>36" HANGER S677292 (X) | 6" |  | SECONDARY<br>3-1000 & 1-500 KCMIL<br><br>PRIMARY<br>3-1/C-350 KCMIL,<br>750 KCMIL<br>AND 1000 KCMIL |
| 2-WAY CABLE ARM & HANGER<br>ARM STOCK NUMBER S110564 (X)<br>HANGER AS NEEDED | 7 1/2" |  | PRIMARY & SECONDARY<br>1/C, 3-1/C OR 4-1/C<br>ALL SIZES |
| 3-WAY CABLE ARM & HANGER<br>ARM STOCK NUMBER S110570 (X)<br>HANGER AS NEEDED | 9 3/4" |  | PRIMARY & SECONDARY<br>1/C, 3-1/C OR 4-1/C<br>ALL SIZES |
| 4-WAY CABLE ARM & HANGER<br>ARM STOCK NUMBER S110576 (X)<br>HANGER AS NEEDED | 1'-0 1/4" |  | PRIMARY & SECONDARY<br>1/C, 3-1/C OR 4-1/C<br>ALL SIZES |
| ADAPTOR FOR CABLE ARMS AS NEEDED<br>STOCK NUMBERS<br>14" S110582 (X)<br>20" S110590 (X) | 1'-3 7/8"<br>1'-9 1/2" |  | PRIMARY & SECONDARY<br>1/C, 3-1/C OR 4-1/C<br>ALL SIZES |
| TEE BRACKET<br>STOCK NUMBER S166675 | 1'-3" |  | PRIMARY<br>3-1/C-350 KCMIL,<br>750 KCMIL<br>AND 1000 KCMIL |

**BILL OF MATERIALS:** NONE

**NOTES:**

I. EACH NOTCH IN THE CABLE ARM WILL ALLOW EITHER 1/C, 3-1/C OR 4-1/C CABLES.

II. DO NOT INSTALL EQUIPMENT ON TOP SECTION OF HANDHOLES AS THIS SECTION IS USED FOR FINAL GRADE ADJUSTMENTS.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

a. FOR CABLE HANGERS AND ACCESSORIES, SEE STANDARD 4178.

b. FOR TEE BRACKET AND STAND OFF BAR, SEE STANDARD 4178.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | EJA | GLW | CZH | 07/27/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1989 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS COMMON EQUIPMENT ASSEMBLIES USED IN SUBSTRUCTURE CONSTRUCTION.





**FIGURE 1**
3315 & 3316 HANDHOLE OR (A)
MANHOLE INSTALLATIONS
SIDE VIEW





**FIGURE 1**
3315 & 3316 HANDHOLE OR (A)
MANHOLE INSTALLATIONS
FRONT VIEW





**FIGURE 2**
3314 HANDHOLE INSTALLATION (B)
SIDE VIEW





**FIGURE 2**
3314 HANDHOLE INSTALLATION (B)
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1987 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

EQUIPMENT ASSEMBLIES

UG3648.1





**FIGURE 3**
3315 & 3316 HANDHOLE OR (C)
MANHOLE INSTALLATIONS
SIDE VIEW





**FIGURE 3**
3315 & 3316 HANDHOLE OR (C)
MANHOLE INSTALLATIONS
FRONT VIEW





**FIGURE 4**
3314 HANDHOLE INSTALLATION (D)
SIDE VIEW





**FIGURE 4**
3314 HANDHOLE INSTALLATION (D)
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1987 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## INSTALLATION:

### EQUIPMENT ASSEMBLIES

(A) 3315 & 3316 HANDHOLE OR MANHOLE INSTALLATIONS: 3-1/C CABLE WITH 200A SPLICES INSTALLED ON ADAPTORS AND 3-WAY CABLE ARMS. HANGERS (S677288 (X) AND S110564 (X)) MAY BE USED WHEN MORE THAN ONE LEVEL OF CABLE IS REQUIRED.

(B) 3314 HANDHOLE INSTALLATION: THIS INSTALLATION IS NORMALLY USED IN A 3314 TO OBTAIN UNOBSTRUCTED SPACE. 3-1/C CABLE WITH 200A SPLICES INSTALLED ON HANGERS AND SMALL CABLE HOOKS. (S677292 (X) AND S415432 (X)). (a)

(C) 3315 & 3316 HANDHOLE OR MANHOLE INSTALLATIONS: 3-1/C CABLE WITH 200A TEES AND DEADBREAK ELBOWS INSTALLED ON ADAPTORS AND 3-WAY CABLE ARMS. HANGERS (S677288 (X) AND S110564 (X)) MAY BE USED WHEN MORE THAN ONE LEVEL OF CABLE IS REQUIRED. FIBER CABLE ARM'S MAY BE TRIMMED TO FIT BETWEEN DEADBREAK CONNECTORS. (a)

(D) 3314 HANDHOLE INSTALLATION: THIS INSTALLATION IS NORMALLY USED IN A 3314 TO OBTAIN UNOBSTRUCTED SPACE. 1Ø WYE (I.E. 6.9KV) CABLE WITH 200A TEES AND DEADBREAK ELBOWS INSTALLED ON HANGERS AND SMALL CABLE HOOKS (S415432 (X)). TRIM AS NEEDED.

**BILL OF MATERIALS:** NONE

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) SEE UG4177 AND UG4178.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1987 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

EQUIPMENT ASSEMBLIES

UG3648.3

**SCOPE:** THIS STANDARD SHOWS THE MAXIMUM EQUIPMENT COMBINATIONS THAT CAN BE UTILIZED IN A 3314, 3315, 3316 OR 3324 SUBSTRUCTURE.

**ATTENTION:**

* FIND THE COMBINATION THAT REPRESENTS THE INSTALLATION, THEN CHECK THE LEGEND FOR COINCIDING SYMBOL AND REFERENCE TO THE EQUIPMENT ASSEMBLY OR CABLE HANGER STANDARDS PAGE.

** ONLY INSTALL THE THREE TEE COMBINATIONS SHOWN IN THESE STANDARDS TO FEED A SWITCHED TIE POSITION.

**TABLE 1**












| LEGEND | | | | | |
|---|---|---|---|---|---|
| **SIZE** | **PLAN VIEW** | **FRONT VIEW** | **SIDE VIEW** | **DESCRIPTION** | **STANDARD PAGE** |
| 200A |  | -- | -- | LOADBREAK CABLE TAP | 4195 |
| |  |  |  | DEADBREAK ELBOW TEE | 4196 |
| |  |  |  | DEABREAK ELBOW TEE | |
| 600A |  |  |  | 600A EXTENSION SPLICE | 4185 |
| |  |  |  | 600A TEES WITH LOADBREAK ELBOW OR 200A RECEPTACLES, ALSO WITH OR WITHOUT DEADBREAK ELBOWS IN A HANDHOLE | 4182 |
| |  |  |  | 600A TEES WITH LOADBREAK ELBOWS OR 200A INSULATING RECEPTACLES, ALSO WITHOUT DEADBREAK ELBOWS IN A HANDHOLE | |
| |  |  |  | 600A TEES WITH OR WITHOUT DEADBREAK ELBOWS IN A MANHOLE | |
| |  |  |  | | |
| |  |  |  | | |
| |  |  |  | | |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

## TABLE 1 (CONT'D)

| LEGEND | | | | | |
|---|---|---|---|---|---|
| **SIZE** | **PLAN VIEW** | **FRONT VIEW** | **SIDE VIEW** | **DESCRIPTION** | **STANDARD PAGE** |
| 200A & 600A | OR | | | SECONDARY OR PRIMARY CABLE PULLED STRAIGHT THROUGH WITHOUT ANY SPLICES | -- |
| 600V | | | -- | 600V SECONDARY CONNECTOR | 4175 |
| -- | -- | -- | | ADAPTER AND 2, 3, OR 4 WAY CABLE ARMS | 4177/4178 |
| | -- | -- | | HANGER AND 2, 3, OR 4 WAY CABLE ARMS | |
| | -- | -- | | HANGER AND SMALL CABLE HOOK | |
| | -- | -- | | HANGER AND LARGE CABLE HOOK | |
| | -- | | | TEE BRACKET | |
| | -- | | -- | STAND OFF BAR | |
| | | -- | -- | PADMOUNTED SWITCH AREA | 3560 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

**INSTALLATION:**

A. THE ALLOWED INSTALLATIONS SHOWN ARE TYPICAL. OTHER CONFIGURATIONS MAY BE DESIGNED PROVIDED EQUIPMENT LIMITATIONS AND THE UNOBSTRUCTED SPACE REQUIREMENT IS PROVIDED TO ALLOW PERSONNEL TO PERFORM WORK SAFELY AND ALLOW ACCESS INTO THE HANDHOLE AND TO THE CONDUITS.

B. #2 OR 2/0 PRIMARY CABLES OR SECONDARY (500 KCMIL MAX.) MAY BE PULLED IN ANY CONDUIT NOT USED FOR LARGER CABLES.

C. CABLE PULLED STRAIGHT THROUGH SHOULD BE PULLED INTO BOTTOM CONDUITS WHEN CONDUITS ARE AVAILABLE AND MUST ENTER AND EXIT THE SAME CONDUIT POSITIONS ON OPPOSITE ENDS OF THE SUBSTRUCTURE.


D. THE "NOT ALLOWED" EQUIPMENT COMBINATION GUIDELINES SHOWN ARE DUE TO:

1. NOT ENOUGH ROOM TO ALLOW PROPER CABLE BENDING RADIUS
2. NOT ENOUGH "UNOBSTRUCTED SPACE" OR "CLEAR PERSONNEL ACCESS OPENING"
3. TOO MANY CABLES TO ALLOW PROPER CABLE TRAINING
4. MORE CABLES THAN CABLE KNOCKOUTS PROVIDED


E. DRAWINGS ARE NOT TO SCALE.

(F) IN THE 3314, 3315 AND 3316, DO NOT INSTALL CABLE TAPS ON THE HANDHOLE ENDS.


(1) ONLY USE SIDE WALLS WHEN THERE ARE NO END KNOCKOUTS AVAILABLE OR THERE IS NOT ENOUGH ROOM TO INSTALL A 90 DEGREE BEND OR SWEEP.




CONFIGURATION 1



CONFIGURATION 2



CONFIGURATION 2
SIDE VIEW

**FIGURE 1** (F)(F1)
3314
ALLOWED
FOR THREE-PHASE 2/0 AND SMALLER PRIMARY CABLES AND
UP TO 500 KCMIL SECONDARY CABLES MAXIMUM.
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


EQUIPMENT COMBINATION GUIDELINES

UG3649.3


TABLE OF CONTENTS

**INSTALLATION (CONT'D):**


(G) WHEN A FUSED ELBOW OR LOADBREAK ELBOW ON STAND OFF PLUG (INSTALLATION FOR LOOP SYSTEM) IS INSTALLED ON THE CENTER CABLE TAP, NO OTHER CABLE OR CONNECTORS WILL BE ALLOWED ON THE OPPOSITE WALL FROM THE CENTER CABLE TAP DUE TO THE LACK OF SPACE.





CONFIGURATION 1
ALLOWED





CONFIGURATION 2
ALLOWED




CONFIGURATION 2
SIDE VIEW




CONFIGURATION 3
SIDE VIEW





CONFIGURATION 3
WITH OR WITHOUT SECONDARY





CONFIGURATION 4
ALLOWED



CONFIGURATION 4
SIDE VIEW



CONFIGURATION 5
NOT ALLOWED



CONFIGURATION 6
NOT ALLOWED
4 OR MORE CABLE TAPS
WITH OR WITHOUT SPLICE


**FIGURE 2** (G)
3314
FOR THREE-PHASE 2/0 AND SMALLER PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |



TABLE OF CONTENTS





CONFIGURATION 1 ALLOWED

CONFIGURATION 2 ALLOWED

CONFIGURATION 2 SIDE VIEW


CONFIGURATION 1 SIDE VIEW




CONFIGURATION 3 NOT ALLOWED

CONFIGURATION 4 NOT ALLOWED WITH OR WITHOUT SPLICES

**FIGURE 3** (G)
3314
FOR THREE-PHASE 2/0 AND SMALLER PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW







**FIGURE 5**
TEE BRACKET SN/166675 AU T/BRKT

**FIGURE 4** (G)
3314
FOR THREE-PHASE 750 AND SMALLER PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
ONLY FOR EXISTING HANDHOLES WITH 750 KCMIL MAXIMUM INSTALLED ON A TEE BRACKET
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |





**FIGURE 6** (G)
3315
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed





**FIGURE 7** (G)
3315
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS






**FIGURE 8** (G)
3315
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |





CONFIGURATION 1
SIDE VIEW

CONFIGURATION 1

CONFIGURATION 2

CONFIGURATION 2
SIDE VIEW




CONFIGURATION 3
SIDE VIEW

CONFIGURATION 3

CONFIGURATION 4

CONFIGURATION 4
SIDE VIEW




CONFIGURATION 5
SIDE VIEW

CONFIGURATION 5

CONFIGURATION 6

CONFIGURATION 6
SIDE VIEW

**FIGURE 9** (G)
3315
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

TABLE OF CONTENTS


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed




CONFIGURATION 1
SIDE VIEW





CONFIGURATION 1
ALLOWED





CONFIGURATION 2 (F1)
ALLOWED




CONFIGURATION 3
NOT ALLOWED



CONFIGURATION 4
NOT ALLOWED




CONFIGURATION 5
NO FUSED ELBOWS
NOT ALLOWED




CONFIGURATION 6
NOT ALLOWED

**FIGURE 10** (G)
3315
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed




TABLE OF CONTENTS




CONFIGURATION 1



CONFIGURATION 2




CONFIGURATION 3




CONFIGURATION 4

**FIGURE 11**
3315
NOT ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 11 OF 22

EQUIPMENT COMBINATION GUIDELINES

UG3649.11


TABLE OF CONTENTS

## INSTALLATION (CONT'D):


(H) ONLY 3 CABLE TAPS ALLOWED ON EITHER WALL WHEN HANDHOLE REQUIRES A TRAFFIC COVER. TAPS MUST BE GROUPED TOGETHER AND CENTERED ON THE WALL.

J. WHEN ONLY ONE SET OF 600A TEES ARE INSTALLED, USE THE BOTTOM OUTSIDE CONDUIT CLOSEST TO THE WALL.


(K) THERE IS NO LIMITATION TO THE NUMBER OF FUSED ELBOWS ALLOWED IN 3316 HANDHOLES.




CONFIGURATION 1





CONFIGURATION 2



CONFIGURATION 2
SIDE VIEW




CONFIGURATION 3



CONFIGURATION 3
SIDE VIEW

**FIGURE 12** (H)(K)
3316
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




TABLE OF CONTENTS

## INSTALLATION (CONT'D):


(L) ONLY 3 CABLE TAPS ALLOWED ON EITHER WALL WHEN HANDHOLE REQUIRES A TRAFFIC COVER. TAPS MUST BE GROUPED TOGETHER AND CENTERED ON THE WALL.

M. WHEN ONLY ONE SET OF 600A TEES ARE INSTALLED, USE THE BOTTOM OUTSIDE CONDUIT CLOSEST TO THE WALL.


(N) #2 OR 2/0 PRIMARY CABLES OR SECONDARY (500 KCMIL MAX.) MAY BE PULLED IN ANY CONDUIT NOT USED FOR LARGER CABLES.




CONFIGURATION 1
SIDE VIEW





CONFIGURATION 1




CONFIGURATION 2
SIDE VIEW





CONFIGURATION 2




CONFIGURATION 2
SIDE VIEW



CONFIGURATION 3
SIDE VIEW




CONFIGURATION 3



CONFIGURATION 3
SIDE VIEW

**FIGURE 13** (L)(N)
3316
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

TABLE OF CONTENTS


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |


## INSTALLATION (CONT'D):

(O) ONLY 3 CABLE TAPS ALLOWED ON EITHER WALL WHEN HANDHOLE REQUIRES A TRAFFIC COVER. TAPS MUST BE GROUPED TOGETHER AND CENTERED ON THE WALL.


(P) WHEN ONLY TWO SETS OF 600A TEES ARE REQUIRED, INSTALL THEM ON ONE WALL. LEAVE THE OPPOSITE WALL OPEN FOR FUTURE CONSTRUCTION.





CONFIGURATION 1 (O)




CONFIGURATION 1
SIDE VIEW





CONFIGURATION 2




CONFIGURATION 2
SIDE VIEW







CONFIGURATION 2
SIDE VIEW





CONFIGURATION 3





CONFIGURATION 3
SIDE VIEW





CONFIGURATION 3
SIDE VIEW

**FIGURE 14** (P)
3316
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |



TABLE OF CONTENTS





**FIGURE 15** (P)
3316
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




TABLE OF CONTENTS







CONFIGURATION 1
SIDE VIEW





CONFIGURATION 1




CONFIGURATION 1
SIDE VIEW






CONFIGURATION 2
SIDE VIEW




CONFIGURATION 2




CONFIGURATION 3 (F1)

**FIGURE 16** (P)
3316
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 16 OF 22

EQUIPMENT COMBINATION GUIDELINES

UG3649.16


TABLE OF CONTENTS





CONFIGURATION 1
SIDE VIEW

CONFIGURATION 1

CONFIGURATION 1
SIDE VIEW




CONFIGURATION 2




CONFIGURATION 3

**FIGURE 17** (P)
3316
NOT ALLOWED
PLAN VIEW

TABLE OF CONTENTS


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS


PROPERTY SIDE




CONFIGURATION 1




CONFIGURATION 2





CONFIGURATION 3

**FIGURE 18** (P)(a)
3317
WITH SUBSURFACE/SURFACE OPERABLE SWITCH FOR ALL SIZES PRIMARY.
NO SECONDARY OTHER THAN SUMP PUMP AND/OR SCADA FEED
PLAN VIEW


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed




CONFIGURATION 1




CONFIGURATION 2




CONFIGURATION 3

**FIGURE 19** (P)
3317
NOT ALLOWED
WITH SUBSURFACE/SURFACE OPERABLE SWITCH FOR ALL SIZES PRIMARY.
NO SECONDARY OTHER THAN SUMP PUMP AND/OR SCADA FEED
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(Q) WHEN CABLE ENTERS THE MANHOLE AND MAKES AN IMMEDIATE 90 DEGREE BEND AS SHOWN IN FIGURE 20, IT MUST BE UNTRIPLEXED AND INSTALLED IN THE THREE OUTSIDE POSITIONS NEAREST THE END OF A 4-WAY STEP (SEE DETAIL 1).






**FIGURE 20** (Q)
3325/3326
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM.
THE PREFERRED INSTALLATION FOR SECONDARY CABLE & CONNECTIONS IS IN A HANDHOLE, USE A 3312 OR 3313 AND BYPASS THE MANHOLE IF POSSIBLE
PLAN VIEW



**DETAIL 1**
UNTRIPLEXED CABLE
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

## INSTALLATION (CONT'D):


R. CABLES PULLED STRAIGHT THROUGH THE MANHOLE MAY BE POSITIONED ADJACENT TO THE SPLICED CABLES.

(S) ONLY USE A 20-FOOT MANHOLE WHEN TWO 4-WAY SWITCHES ARE REQUIRED.

1. 14-FOOT: 6 SETS OF STRAIGHT SPLICES OR 600A TEES (3 ON EACH WALL).
2. 20-FOOT: 10 SETS OF STRAIGHT SPLICES OR 600A TEES (5 ON EACH WALL).




CONFIGURATION 1




CONFIGURATION 2

**FIGURE 21** (S)
3325/3326
ALLOWED
FOR ALL SIZES OF PRIMARY CABLES AND UP TO 500 KCMIL SECONDARY CABLES MAXIMUM
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

T. THE 6 WAY SWITCH SCADA AND FAULT INTERRUPTERS IS THE PREFERRED SWITCH FOR VAULTS.

(U) FOUR AND SIX WAY VISTA SWITCHES MAY BE INSTALLED IN DRY VAULTS WITHOUT A DEVIATION REQUEST.





**FIGURE 22**
TYPICAL 4-WAY MANUAL OR SCADA SWITCH (U)
FRONT VIEW





**FIGURE 23**
WALK-IN VAULTS
TYPICAL 6-WAY SCADA SWITCH (U)
PLAN VIEW

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) FOR PREFERRED CONDUITS, SEE UG3671.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | - | EJA | GLW | CZH | 11/09/2020 | F | | | | | | |
| B | EDITIORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 12/28/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

**SCOPE:** TO PROVIDE A SUBSURFACE TERMINATING POINT WITH 3-WAY CABLE TAP, FOR SINGLE-PHASE 6.9KV SUPPLY AND BRANCH LOADS. FOR ALTERNATE INSTALLATION, SEE PAD MOUNTED UG3522.






**FIGURE 1**




**DETAIL 1**





**FIGURE 2**
TYPICAL INSTALLATION




**FIGURE 3**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

SECTIONALIZING HANDHOLE 200A, 6.9KV SINGLE PHASE

UG3660.1

TABLE OF CONTENTS

## INSTALLATION:

(A) **FOUR WAY RACKS, AND FUSED ELBOWS ARE NOT ALLOWED.**

(B) ELBOWS SHALL ALWAYS BE TRAINED VERTICALLY TO ALLOW FOR MAXIMUM ELECTRICAL GROUND CLEARANCE TO ADJACENT ELBOWS WHEN SWITCHING ENERGIZED. (f)

C. NO SECONDARY ALLOWED WITH THIS INSTALLATION.

(D) WHEN TAP POSITION IS UNUSED, INSTALL INSULATING RECEPTACLE.

(E) APPLY SILICONE GREASE TO THE PENTAHEAD BOLTS WHEN SECURING THE COVERS TO REDUCE REMOVAL OR INSTALLATION DIFFICULTIES. (h)

(F) CABLE TAP ANGLE SHALL BE ADJUSTED (45 DEGREES UP FROM HORIZONTAL ON FLAT TERRAIN) TO ALLOW FOR STRAIGHT INSERTION OF ELBOW INTO BUSHING WITH HOT STICK.

(G) IF RIGHT OF WAY OR OBSTRUCTIONS CAUSE A PROBLEM, THE HANDHOLE MAY BE TURNED TO WHERE THE LONG SIDE OF THE HANDHOLE PARALLELS THE SIDEWALK OR PROPERTY LINE. IF THE HANDHOLE HOUSES A CABLE TAP, THE HANDHOLE IS NOT TO BE TURNED AND THE TYPICAL PLAN VIEW OUTLINED IN THIS STANDARD MUST BE FOLLOWED (CABLE TAP IS MOUNTED ON THE END OF THE 5-FOOT CLEARANCE FOR HOT STICK OPERATION WOULD BE ON THE SIDEWALK SIDE).

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | HANDHOLE, 24" X 36" | 1 | 3313 | -- | 3313PC |
| 2 | GROUNDING EQUIPMENT (c)(d) | AS REQ'D | 4540 | -- | -- |
| 3 | CABLE TAP, 12KV, 3-WAY | 1 | -- | S718312 | TAP-3W |
| 4 | ELBOW, LOADBREAK 12KV AND/OR INSULATING RECEPTACLE | AS REQ'D | 4180/4190/4191/4195 | -- | -- |
| 5 | TAGS, CABLE IDENTIFICATION | AS REQ'D | 3202 | -- | -- |
| 6 | ANCHOR BOLT, CONCRETE | 2 | -- | S107654 | CNCANC |
| 7 | STRUCTURE IDENTIFICATION | 1 | 3211 | -- | -- |
| 8 | AQUA-SEAL OR EQUIVALENT | AS REQ'D | -- | S442996 | -- |
| 9 | EPOXY | AS REQ'D | -- | S213244 | -- |

## NOTES:

I. BEFORE BEGINNING THE INSTALLATION, STUDY ANY KIT INSTRUCTION AND FOLLOW THE DIMENSIONS ON INSTALLATION DRAWING.

II. CUT CONDUIT, INSTALL AQUA SEAL AROUND CABLE AND CONDUIT, SET HANDHOLE, INSTALL GROUND GRID AND COMPACT SOIL TO 90 PERCENT AROUND BOX AREA. (e)

III. INSTALL CABLE RACK AND TRAIN CABLES TO MAKE SURE THAT YOU HAVE 6 INCHES OF STRAIGHT CABLE WHERE IT ENTERS THE ELBOWS. ALSO HAVE AT LEAST 10 TIMES THE CABLE DIAMETER AS MINIMUM BENDING RADIUS.

IV. INSTALL ELBOWS ON CABLES AND SEAT EACH ONE ONTO THE RACK WITH A HOT STICK. MAKE SURE THERE IS A LIGHT COATING OF SILICONE INSIDE THE ELBOW AND ALSO ON THE RACK BUSHING PER MANUFACTURER'S INSTRUCTIONS. (f)

V. REMOVE EACH CAPACITIVE TEST CAP, LUBE CAP AND TEST POINT WITH A LIGHT COATING OF SILICONE GREASE, INSTALL CAP AND ROTATE 5 TIMES CLOCKWISE. LUBING WILL ALLOW EASIER REMOVAL OF THE CAP AND PREVENT CORROSION OF THE TEST POINT.

VI. INSTALL CABLE TAGS AND STRUCTURE IDENTIFICATION. (g)

VII. INSTALL CONCENTRIC NEUTRAL GROUNDS AS SHOWN ON SKETCH LEAVING ENOUGH SLACK TO OPERATE ELBOW.

VIII. BOLT DOWN LID WITH 1/2-INCH PENTAHEAD BOLTS AFTER APPLYING INHIBITOR ON THREADS OF EACH BOLT. (h)

IX. INSTALL STRUCTURE IDENTIFICATION TAG WITH EPOXY. (g)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE:**

a. FOR PAD MOUNTED SINGLE-PHASE SECTIONALIZING, SEE UG3522.

b. FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART, SEE UG4174 AND UG4176.

(c) FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE, SEE UG4510.

(d) FOR GROUNDING SUBSTRUCTURES AND EQUIPMENT WHEN DIFFERENT PARTIES ARE RESPONSIBLE FOR THE CONDUIT AND PAD INSTALLATION, SEE UG4540.

(e) FOR SETTING TO FINAL GRADE IF SLOPED, SEE UG3305.

(f) SEE UG4190-UG4191.

(g) SEE UG3211, UG3202, AND G.O. 128, 35.1.

(h) SEE G.O. 128, 32.7.

(i) FOR 1-INCH BASE, SEE UG3370 OR UG3371.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | - | 01/01/1996 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |





SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


SECTIONALIZING HANDHOLE 200A, 6.9KV SINGLE PHASE

UG3660.3

**SCOPE:** THIS STANDARD SHOWS A SUBSURFACE/SURFACE OPERABLE 600A (VISTA) SF-6 GAS SWITCH.




**DETAIL 1**

**FIGURE 1**
SEE TABLES 3 & 4

**TABLE 1**

| ELECTRICAL RATINGS | |
|---|---|
| VOLTAGE | 15.5KV |
| BIL | 95KV |
| CURRENT, CONTINUOUS | 600A |
| LOADMAKE AND LOADBREAK | 600A |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 12,500A |

**TABLE 2**

| SF-6 GAS SWITCH | | | |
|---|---|---|---|
| 600A | | STOCK NUMBER | DESIGN UNITS |
| 4-WAY | STEEL | S708998 | 4WY-V |
| | STAINLESS | S704700 | 4WY-SV |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3670 | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REFERENCES UPDATE | - | DG | TR | MDJ | 06/01/2016 | E | | | | | | |
| A | DRAWING UPDATE | - | DG | TR | MDJ | 05/31/2016 | D | | | | | | |




**FIGURE 2**
4-WAY ONE LINE DIAGRAM

**TABLE 3**

| SWITCH PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | OPERATING PANEL AND CONNECTION DIAGRAM |
| 2 | SF-6 FILL VALVE |
| 3 | GROUND LUG |
| 4 | NAME PLATE |
| 5 | PRESSURE GAUGE (UNDERWINDOW) |
| 6 | PRESSURE RELIEF VALVE |
| 7 | 600A BUSHING ASSEMBLY |
| 8 | MOUNTING ANGLES |
| 9 | OPERATING MECHANISMS |
| 10 | MOTOR OPERATORS (SCADA ONLY) |

**TABLE 4**

| SF-6 GAS SWITCH | |
|---|---|
| **ITEM** | **WEIGHT (LBS)** |
| MANUAL | 1,100 |
| SCADA | 1,300 |

TABLE OF CONTENTS

## INSTALLATION:

A. 4-WAY VISTA SWITCH SHALL BE INSTALLED WITH THE OPERATING MECHANISMS UP FOR THE 3317. BOLT THE SWITCH TO THE SUPPORTS SUPPLIED WITH THE 3317 HANDHOLE. FOR VAULT INSTALLATION USE 54-INCH STAINLESS STEEL LEGS (S457180). BOLT SWITCH TO THE WALL USING THE 24-INCH BRACKET SUPPLIED WITH LEG KIT.

**BILL OF MATERIALS:** NONE

## NOTES:

I. PRESSURE GAUGE IS LOCATED UNDER THE LEFT HAND SIDE WINDOW. IT IS TEMPERATURE AND ALTITUDE COMPENSATED.

II. SWITCHES ARE DELIVERED FROM THE SUPPLIERS WITH ALL THE PARTS LISTED IN THE PARTS LIST.

III. OPERATION SELECTOR PREVENTS INADVERTENT OPERATION FROM THE CLOSED POSITION DIRECTLY TO THE GROUND POSITION AND VICE VERSA.

IV. THE SWITCHES SHALL BE USED WITH POLYETHYLENE CABLES AND 600A ELBOW TEES.

## REFERENCE:

a. FOR SWITCH IDENTIFICATION, SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218.

b. FOR EQUIPMENT COMBINATION GUIDELINES FOR SWITCHES IN MANHOLES, SEE UG3649.

c. FOR SWITCH INSTALLATION IN A 3317 HANDHOLE, SEE UG3671.

d. FOR SWITCH CONNECTIONS, SEE UG4181.

e. FOR SWITCH APPLICATION, SEE DM6111.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG3670 | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REFERENCES UPDATE | - | DG | TR | MDJ | 06/01/2016 | E | | | | | | |
| A | DRAWING UPDATE | - | DG | TR | MDJ | 05/31/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS A VISTA 6-WAY SWITCH (3-600A SWITCHES W/3-600A FAULT INTERRUPTERS). FOR DRY VAULT INSTALLATION ONLY. NO DEVIATION REQUEST REQUIRED.





**FIGURE 1**
WEIGHT: 1,700 LBS

## TABLE 1

| ELECTRICAL RATINGS | |
|---|---|
| VOLTAGE | 15.5KV |
| BIL | 95KV |
| CURRENT, CONTINUOUS | 600A |
| LOADMAKE AND LOADBREAK | 600A |
| MOMENTARY AND FAULT CLOSE (RMS, SYMMETRICAL) | 16,000A |
| FAULT INTERRUPTER (LOAD DROPPING) | 600A |




**FIGURE 2**
6-WAY ONE LINE DIAGRAM

## TABLE 2

| SF-6 GAS SWITCH | | |
|---|---|---|
| **600A** | **STOCK NUMBER** | **DESIGN UNITS** |
| 6-WAY (STAINLESS STEEL) | S708986 | 633-V |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REFERENCES UPDATE | - | DG | TR | MDJ | 06/01/2016 | E | | | | | | |
| A | DRAWING UPDATE | - | DG | TR | MDJ | 05/31/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

600A 6-WAY SF-6 GAS SWITCH (VISTA)
W/3 - FAULT INTERRUPTERS



UG3670.1

TABLE OF CONTENTS

## TABLE 3

| SWITCH PARTS LIST | | | |
|---|---|---|---|
| ITEM | DESCRIPTION | ITEM | DESCRIPTION |
| 1 | OPERATING PANEL AND CONNECTION DIAGRAM | 7 | 600A BUSHING ASSEMBLY |
| 2 | SF-6 FILL VALVE | 8 | OPERATING MECHANISMS |
| 3 | GROUND LUG | 9 | MOTOR OPERATORS |
| 4 | NAME PLATE | 10 | OVER CURRENT CONTROLS |
| 5 | PRESSURE GAUGE (UNDERWINDOW) | 11 | CONTROL CABLE SUPPORT |
| 6 | PRESSURE RELIEF VALVE | -- | -- |

## INSTALLATION:

A. THE 6-WAY SWITCH SHALL BE INSTALLED ON 54-INCH LEGS AND BOLTED TO THE WALL WITH THE 24-INCH STAND-OFF BRACKET SUPPLIED WITH THE SWITCH LEG KIT. ATTACH THE BRACKETS TO THE SWITCH USING THE TOP LEG BOLTS (S457180).

B. A SWITCH LEG KIT IS INCLUDED IN THE 6-WAY VISTA SWITCH AU. FOR A 4-WAY SWITCH INSTALLED IN A VAULT THE SWITCH LEGS MUST BE ORDERED SEPARATELY (S457180 VS-LEG).

C. LOADBREAK ELBOWS SHALL NOT BE CONNECTED TO THE BACK OF THE 600A TEES. 200A LOADBREAK ELBOWS MAY BE CONNECTED TO THE FAULT INTERRUPTERS PROVIDING THERE ARE NO 600A CONNECTORS AT THAT POSITION.

D. SCADA RTU AND ALL CONTROL CABLES ARE INCLUDED WITH SWITCH. CONTROL CABLES ARE 50 FEET LONG.

**BILL OF MATERIALS:** NONE

## NOTES:

I. PRESSURE GAUGE IS LOCATED UNDER THE LEFT HAND SIDE WINDOW. IT IS TEMPERATURE AND ALTITUDE COMPENSATED.

II. SWITCHES ARE DELIVERED FROM THE SUPPLIERS WITH ALL THE PARTS LISTED IN THE PARTS LIST.

III. OPERATION SELECTOR PREVENTS INADVERTENT OPERATION FROM THE CLOSED POSITION DIRECTLY TO THE GROUND POSITION AND VICE VERSA.

IV. THE SWITCHES SHALL BE USED WITH POLYETHYLENE CABLES AND 600A ELBOW TEES.

## REFERENCE:

a. FOR SWITCH IDENTIFICATION, SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218.

b. FOR EQUIPMENT COMBINATION GUIDELINES FOR SWITCHES IN MANHOLES, SEE UG3649.

c. FOR 4-WAY SWITCH INSTALLATION IN A 3317 HANDHOLE, SEE UG3671.

d. FOR SWITCH CONNECTIONS, SEE UG4181.

e. FOR SWITCH APPLICATION, SEE DM6111.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REFERENCES UPDATE | - | DG | TR | MDJ | 06/01/2016 | E | | | | | | |
| A | DRAWING UPDATE | - | DG | TR | MDJ | 05/31/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE TYPICAL INSTALLATION OF A SUBSURFACE/SURFACE OPERABLE SWITCH IN A 3317 HANDHOLE.





**FIGURE 1**
INSIDE OF HANDHOLE
PREFERRED DUCTS





**FIGURE 2**
SIDE VIEW






**FIGURE 3**
INSIDE OF HANDHOLE
PREFERRED DUCTS




**DETAIL 1**





**FIGURE 4**





**FIGURE 5**
INSIDE OF HANDHOLE





**FIGURE 2**
TOP VIEW





**FIGURE 6**
INSIDE OF HANDHOLE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REVISION | - | - | - | RW/VCR | 01/12/2001 | E | | | | | | |
| A | REVISION | - | - | - | RW/VCR | 10/23/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

INSTALLATION OF SUBSURFACE/SURFACE OPERABLE SWITCH IN A 3317 HANDHOLE

UG3671.1

TABLE OF CONTENTS

## INSTALLATION:

(A) MBS-6 MOUNTING BRACKETS SHALL BE BOLTED TO THE TOP OF THE CABLE SUPPORT BRACKET.

B. BOLT THE SWITCH TO THE SWITCH SUPPORT ANGLES.

C. NO SECONDARY ALLOWED IN THIS INSTALLATION OTHER THAN THE FEED TO THE SUMP PUMP OR SCADA.

D. 200A CABLES SHALL BE PULLED IN UPPER CONDUITS (3 AND 4).

E. DO NOT PIGGYBACK 600A TEES (ONE ON TOP OF THE OTHER) AT ANY TIME ON THE SWITCH BUSHINGS.

F. INSTALL SWITCH IDENTIFICATION NUMBER AND CABLE I.D. AS SHOWN IN UG3200.

(G) LOWER STEEL GRATING IS REMOVABLE FOR CABLE PULLING.

H. LOADBREAK ELBOWS SHALL NOT BE LANDED ON THE BACK OF THE 600A TEES EXCEPT FOR 1 LOADBREAK ELBOW FOR A SINGLE-PHASE TRANSFORMER (6930). THREE LOADBREAK ELBOWS MAY BE INSTALLED WHEN CONNECTED TO SWITCH WITH NO 600A TEES.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | HANDHOLE, 6'-0" X 8'-0" | 1 | 3317 | S334430 | 3317SE |
| 2 | SWITCH, 12KV, SUBSURFACE/SURFACE, OPERABLE | 1 | 3669/3670 | S708998 | 4WY-V |
| 3 | BRACKET, MOUNTING MBS-6 | AS REQ'D | -- | S165530 | -- |
| 4 | GRATING, UPPER STEEL | 1 | -- | -- | -- |
| 5 | GRATING, LOWER STEEL | 1 | -- | -- | -- |
| 6 | GROUND CONNECTION | -- | -- | -- | -- |
| 7 | SWITCH SUPPORT | -- | -- | -- | -- |
| 8 | PULLING IRONS | -- | -- | -- | -- |
| 9 | INDICATORS, AUTOMATIC FAULT (II) | AS REQ'D | 4352 | -- | -- |
| 10 | ANCHOR, CONCRETE, STAINLESS STEEL (II) | AS REQ'D | -- | -- | -- |
| 11 | PADLOCK, SCHLAGE ELECTRIC SERIES | 8 | -- | S514848 | -- |
| 12 | CONNECTOR, COMPRESSION | AS REQ'D | 4174/4176 | -- | -- |
| 13 | DECALS | AS REQ'D | 3213-3218 | -- | -- |

## NOTES:

I. OTHER CONFIGURATIONS MAY BE DESIGNED PROVIDED CABLES DO NOT CROSS FROM ONE SIDE OF THE STRUCTURE TO THE OTHER.

(II) NOT SHOWN ON FIGURES.

## REFERENCE:

a. FOR SUBSURFACE SWITCH, SEE UG3669 AND UG3670.

b. FOR INSTALLING SWITCH IDENTIFICATION NUMBERS, SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218.

c. FOR INSTALLING CABLE I.D. TAGS, SEE UG3202.

d. FOR CONDUIT INSTALLATION PRACTICES, SEE UG3374.

e. FOR SUMP PUMP INSTALLATION, SEE UG3660.

f. FOR 12KV 200A AND 600A CONNECTOR ASSEMBLIES, SEE UG4181.

g. FOR NEUTRAL AND GROUND WIRE DIAGRAM, SEE UG4530.

h. FOR GROUNDING STRUCTURES AND EQUIPMENT, SEE UG4540.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REVISION | - | - | - | RW/VCR | 01/12/2001 | E | | | | | | |
| A | REVISION | - | - | - | RW/VCR | 10/23/2000 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE (CONT'D):**

i. FOR SWITCH APPLICATION, SEE DM6111.

j. FOR AUTOMATIC FAULT INDICATOR APPLICATION, SEE DM6113.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | REVISION | - | - | - | RW/VCR | 01/12/2001 | E | | | | | | |
| A | REVISION | - | - | - | RW/VCR | 10/23/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF SUBSURFACE/SURFACE OPERABLE SWITCH IN A 3317 HANDHOLE

UG3671.3

**SCOPE:** THIS STANDARD SHOWS THE G&W G-RAM SUB SURFACE STAINLESS STEEL GAS INSULATED 4-WAY SWITCH. EACH SWITCH WAY POSITION CAN BE GROUNDED INDEPENDENTLY.

**ATTENTION:**

* THE G-RAM IS THE REPLACEMENT FOR BOTH GAS AND OIL SWITCHES WHEN THEY CANNOT BE PAD MOUNTED.






**FIGURE 1**




**DETAIL 1**





**FIGURE 2**
CONNECTION DIAGRAM

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JJ | 05/20/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

G & W G-RAM 4-WAY GAS SWITCH WITH GROUNDING POSITIONS



UG3672.1

## TABLE 1

| PARTS LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | PRESSURE GAUGE |
| 2 | FILL VALVE |
| 3 | PROVISION FOR LOW PRESSURE WARNING |
| 4 | SF6 TEMPERATURE AND PRESSURE CHART |
| 5 | NAME PLATE AND ONE LINE DIAGRAM |
| 6 | OPERATING SHAFT AND LOCKING ASSY. |
| 7 | CONTACT POSITION VIEWING WINDOW |
| 8 | 600A BUSHING CONNECTION |
| 9 | OPERATING HANDLE |
| 10 | EQUIPMENT GROUNDING POINTS |
| 11 | EQUIPMENT LIFTING POINTS |
| 12 | SUPPORT LEGS |

## TABLE 2

| SWITCH ELECTRICAL RATING | |
|---|---|
| **DESCRIPTION** | **RATING** |
| VOLTAGE | 15.5KV |
| BIL | 110KV |
| CURRENT, CONTINUOUS | 600A |
| LOAD MAKE, LOADBREAK CURRENT | 600A |
| NOT FAULT CLOSE RATED | -- |

## INSTALLATION:

A. THE G-RAM 4-WAY SWITCH IS FOR INSTALLATION IN 3324, 3325, 3326 MANHOLES. SMALLER MANHOLES WILL REQUIRE A DEVIATION REQUEST.

B. FOR SUB-SURFACE INSTALLATION THE G-RAM 4-WAY SWITCH SHALL BE BOLTED TO THE WALL WITH STAINLESS STEEL ANGLE BRACKETS AND SUPPORTED WITH (4) 54-INCH STAINLESS STEEL LEGS (S457168), 8 5/8-INCH BOLTS X 3 1/2-INCH STAINLESS STEEL BOLTS (S156750) AND 1/2-INCH WASHERS STAINLESS STEEL.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 4-WAY, 600A, STAINLESS STEEL | 1 | -- | S708780 | GR-RAM |
| | PADLOCK, SCHLAGE ELECTRIC SERIES | 8 | -- | S514848 | |
| 2 | DECALS | AS REQ'D | 3213-3218 | -- | -- |
| 3 | CONNECTOR, COMPRESSION | AS REQ'D | 4174/4176 | -- | -- |
| 4 | FAULT INDICATORS | AS REQ'D | 4352 | -- | -- |
| 5 | SUPPORT LEGS | 4 | -- | S457168 | SWL-54 |
| 6 | CONNECTORS, 600A, 600A/200A OR 200A | AS REQ'D | 4181 | -- | AS NEEDED |

## NOTES:

I. PLACE SWITCH ON OPPOSITE SIDE OF MANHOLE OPENING.

II. THE OPERATION SELECTOR PREVENTS INADVERTENT OPERATION FROM THE CLOSED POSITION TO THE OPEN POSITION AND OPEN TO GROUND POSITION.

III. THE G-RAM IS A MANUALLY OPERATED SWITCH AND NOT SCADA ADAPTABLE.

IV. REMOTE SWITCHING OPERATIONS USING THE 1/2 RATCHET FROM THE REMOTE SWITCH OPERATIONS KIT, REQUIRES REMOTE ADAPTER S327-48R, THIS TOOL IS AVAILABLE FROM ELECTRIC DISTRIBUTION STANDARDS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JJ | 05/20/2005 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE:**

a. FOR SWITCH IDENTIFICATION, SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218.

b. FOR NEUTRAL AND GROUNDING WIRE DIAGRAM, SEE UG4530.

c. FOR CONNECTOR ASSEMBLIES, SEE UG4181.

d. FOR EQUIPMENT COMBINATION GUIDELINES, SEE UG3649.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/JJ | 05/20/2005 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| SHEET 3 OF 3 | X Indicates Latest Revision | Completely Revised | New Page | Information Removed |
| | SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS | | | |
| | G & W G-RAM 4-WAY GAS SWITCH WITH GROUNDING POSITIONS | | | UG3672.3 |

**SCOPE:** THIS STANDARD COVERS THE ELASTIMOLD® MOLDED VACUUM SWITCH (MVS) AND INTERRUPTER (MVI).




**FIGURE 1**
THREE-PHASE
MOLDED VACUUM SWITCH (MVS)
APPROX. 135 LB.





**FIGURE 2**
SINGLE-PHASE
MOLDED VACUUM SWITCH (MVS)
APPROX. 30 LB.



**FIGURES 1 & 2**
MOLDED VACUUM SWITCH (MVS)
SIDE VIEW




**FIGURE 3**
THREE-PHASE
MOLDED VACUUM INTERRUPTER (MVI)
APPROX. 145 LB.





**FIGURE 4**
SINGLE-PHASE
MOLDED VACUUM INTERRUPTER (MVI)
APPROX. 45 LB.



**FIGURES 3 & 4**
MOLDED VACUUM INTERRUPTER (MVI)
SIDE VIEW

## TABLE 1

| ELASTIMOLD MVS AND MVI ELECTRICAL RATINGS | |
|---|---|
| CONTINUOUS CURRENT | 200A |
| BASIC INSULATION LEVEL (BIL) | 95kV |
| VOLTAGE CLASS | 15.5kV |
| ASYMMETRICAL MOMENTARY AND 3 OPERATION FAULT CLOSE | 20kA |
| SYMMETRICAL 1 SECOND FAULTING RATING | 12.5kA |
| CAPACITOR OR CABLE CHARGING INTERRUPTING | 40A |
| AMBIENT TEMPERATURE RANGE | -30°C TO + 40°C |

## TABLE 2

| MVS AND MVI STOCK NUMBERS | | | |
|---|---|---|---|
| DESCRIPTION | | STOCK NUMBER | DESIGN UNITS |
| MVS, 1-0, 200A LINE, 200A LOAD | | S708400 | S21P |
| MVI, 1-0, 200A LINE, 200A LOAD | (I) | S708402 | S21PFI |
| MVS, 3-0, 200A LINE, 200A LOAD | | S708412 | S23P |
| MVI, 3-0, 200A LINE, 200A LOAD | (I) | S708410 | S23PFI |
| MVS, 3-0, 600A LINE, 200A LOAD | | S708414 | S63P |
| MVI, 3-0, 600A LINE, 200A LOAD | (I) | S708416 | S63PFI |
| MVI, 3-0, 600A LINE, 600A LOAD | (I) | S708418 | S66PFI |

## TABLE 3






| MVS AND MVI MAP SYMBOLS | |
|---|---|
| SWITCH TYPE | MAP SYMBOL |
| MVS |  |
| |  |
| MV1 |   |
| |  |
| |  |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | TABLE UPDATE | EDM | EJA | GLW | CZH | 07/04/2021 | E | | | | | | |
| A | REVISION | - | - | - | WT/MC | 05/10/2010 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUBSURFACE APPLICATION OF ELASTIMOLD
MOLDED VACUUM SWITCH/INTERRUPTER



UG3675.1

## INSTALLATION:

A. **MVS** (MOLDED VACUUM SWITCH) - A SINGLE-PHASE OR THREE-PHASE SOLID DIELECTRIC VACUUM SWITCH CAPABLE OF MAKING, CARRYING, AND INTERRUPTING LOAD CURRENT UP TO 200A AT 15.5KV. THE SWITCH IS INSULATED IN EPDM RUBBER AND REQUIRES NO MAINTENANCE.

B. **MVI** (MOLDED VACUUM INTERRUPTER) - A SINGLE-PHASE OR THREE-PHASE SOLID DIELECTRIC VACUUM SWITCH CAPABLE OF MAKING AND CARRYING LOAD CURRENT UP TO 200A AT 15.5KV, AND AUTOMATICALLY INTERRUPTING FAULT CURRENT UP TO 12.5KA. THESE UNITS ARE SELF POWERED AND INCLUDE CURRENT SENSING AND ELECTRONIC CONTROLS TO PROVIDE OVER-CURRENT PROTECTION. THE SWITCH IS INSULATED IN EPDM RUBBER AND REQUIRES NO MAINTENANCE. A FUSING REQUEST MUST BE SUBMITTED TO ELECTRIC DISTRIBUTION PLANNING WHO WILL THEN FORWARD THE REQUEST TO THE FUSING COORDINATION GROUP FOR A TRIP SELECTION OF LESS THAN 200A. SYSTEM PROTECTION WILL REVIEW FOR A TRIP SELECTION OF 200A OR ABOVE. ONLY STOCKED AT KEARNY.

## ATTENTION:

* PRIOR TO INSTALLATION, THE MVI MUST BE PROGRAMMED BY A QUALIFIED KEARNY SCADA TECHNICIAN. CONTACT THE KEARNY CONSTRUCTION SUPERVISOR TO PICK-UP OR HAVE THE DEVICE DELIVERED.

C. THE MVS/MVI SERIES SWITCHES MAY BE APPLIED IN SUBMERSIBLE APPLICATIONS. THEY ARE FOR WALK IN VAULTS AND MANHOLES THAT HAVE WORK SPACE TO STAND-OFF THE LOAD-SIDE ELBOWS, AND HOOK STICK OR REMOTE RIGGING ABILITY TO OPERATE THE SWITCH FROM OUTSIDE THE STRUCTURE. CAN BE INSTALLED IN HANDHOLES AS LONG AS THE SWITCH CAN BE OPEN/CLOSED FROM OUTSIDE THE STRUCTURE, AND THE ELBOWS CAN BE REMOVED USING A SHOTGUN.

D. REMOTE RIGGING INSTALLATION: WHEN MVI AND MVS SWITCHES ARE INSTALLED AND REQUIRE REMOTE RIGGING, SEE UG3675.3 FOR REMOTE RIGGING POINT INSTALLATION.

## CAUTION:

* OPERATING THE LOAD-SIDE, LOAD-BREAK ELBOWS IS A DE-ENERGIZED OPERATION ONLY WHEN THE SWITCH IS OPEN AND TESTED DE-ENERGIZED ON THAT SIDE.

E. **DIMENSIONS** - THE THREE-PHASE SWITCH (MVS OR MVI) REQUIRES A MINIMUM OF 24" X 30" TO MOUNT ON A WALL OR FLOOR THE SINGLE-PHASE SWITCH (MVS OR MVI) REQUIRES A MINIMUM OF 26" X 8". **A MINIMUM OF 8FT CLEAR WORKING SPACE IS REQUIRED IN FRONT OF THE SWITCH ELBOWS.**

F. SUB-SURFACE INSTALLATION FOR WALK IN VAULTS AND MANHOLES. CAN BE APPLIED AT 12KV OR 4KV.

G. CAN BE INSTALLED IN HANDHOLES AS LONG AS THE SWITCH CAN BE OPEN/CLOSED FROM OUTSIDE STRUCTURE, AND THE ELBOWS CAN BE REMOVED USING A SHOTGUN. REQUIRED WORKING SPACE DIMENSIONS MUST BE RESPECTED.

H. SWITCH CAN BE MOUNTED ON THE FLOOR OR WALL, HORIZONTAL OR VERTICAL USING HILTI 1/2 INCH DRIVE IN STUDS.

J. PROVISIONS MUST BE PROVIDED FOR REMOTE RIGGING (ROPE OPERATION) IF THE SWITCH CANNOT BE OPERATED USING A HOOK STICK FROM OUTSIDE THE STRUCTURE. SEE UG3675.3

K. ALL BUSHING PLUGS MUST BE BONDED TO THE SWITCH BODY GROUND.

L. FOR GROUNDING INSTRUCTIONS SEE UG4530.2.

M. LOCK SWITCH HANDLE WHEN IN FINAL POSITION (OPEN OR CLOSED). USE NON-FERROUS LOCK STOCK # S468010.

**BILL OF MATERIALS:** NONE

## NOTES:

(I) STOCKED AT KEARNY ONLY.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | TABLE UPDATE | EDM | EJA | GLW | CZH | 07/04/2021 | E | | | | | | |
| A | REVISION | - | - | - | WT/MC | 05/10/2010 | D | | | | | | |

**SCOPE:** REMOTE RIGGING HARDWARE INSTALLATION FOR MVI AND MVS SWITCHES.




**FIGURE 1**
REMOTE RIGGING
ARRANGEMENTS (EXAMPLE)
FRONT VIEW







**FIGURE 1**
REMOTE RIGGING
ARRANGEMENTS (EXAMPLE)
SIDE VIEW




**DETAIL 1**




**DETAIL 2**

## INSTALLATION:

A. APPLY EYE BOLTS AS NEEDED TO OPEN AND CLOSE MVI AND MVS SWITCHES FOR REMOTE OPERATION WITH ROPE.

B. ADDITIONAL POINTS MAY BE ADDED WITH L BRACKETS FOR ROPE RIGGING TO THE SURFACE OPENING OR DOOR ACCESS.

C. SEE THE DRIVE IN ANCHOR INSTALLATION IN CONSTRUCTION STANDARD 4178.4, REQUIRES 5/8 INCH CONCRETE DRILL AND DRIVE IN ANCHOR SETTING TOOL S746758. THE STAINLESS STEEL EYE BOLT WILL THREAD INTO THE ANCHOR.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | DROP IN ANCHOR STAINLESS STEEL | AS REQ'D | 4178.4 | S108864 (X) | -- |
| 2 | EYE BOLT, 1 1/2" X 1/2", STAINLESS STEEL | AS REQ'D | 4505 | S152722 (X) | -- |
| 3 | WASHER, 1/2", STAINLESS STEEL | AS REQ'D | 4505 | S799680 | -- |
| 4 | L BRACKET, STAINLESS STEEL, 2" X 3" | AS REQ'D | 4505 | S166072 | -- |
| 5 | ANCHOR, CONCRETE, STAINLESS STEEL, 1/2" X 3 1/2" | AS REQ'D | 4505 | S107654 | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | TABLE UPDATE | EDM | EJA | GLW | CZH | 07/04/2021 | E | | | | | | |
| A | REVISION | - | - | - | WT/MC | 05/10/2010 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUBSURFACE APPLICATION OF ELASTIMOLD
MOLDED VACUUM SWITCH/INTERRUPTER

UG3675.3

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS A TILT MOUNT ADAPTER FOR SINGLE-PHASE MVI AND MVS.




**FIGURE 1**
ISOMETRIC VIEW




**FIGURE 2**
SIDE VIEWS

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BRACKET SINGLE-PHASE MVI/MVS | 2 | - | S164636 | TMA-EM |
| 2 | ANC 1/2" X 3 1/2" STAINLESS STEEL | 4 | - | S107654 | CNCANC |

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | TABLE UPDATE | EDM | EJA | GLW | CZH | 07/04/2021 | E | | | | | | |
| A | REVISION | - | - | - | WT/MC | 05/10/2010 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SUBSURFACE APPLICATION OF ELASTIMOLD
MOLDED VACUUM SWITCH/INTERRUPTER



UG3675.4

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD COVERS TRAYER ENGINEERING'S VAULT MOUNTED 600A, 15KV THREE-PHASE LIQUID INSULATED VACUUM SWITCH GEAR WITH VISIBLE DISCONNECTS. DUE TO DIVERSE ENVIRONMENTAL CONDITIONS THE SWITCH GEAR IS CONSTRUCTED OF STAINLESS STEEL. THE LIQUID INSULATION IS NOT SUBJECTED TO ARC CONTAMINATION DURING SWITCHING AND WILL NOT REQUIRE TESTING.

**ATTENTION:**

* THE TRAYER VAULT MOUNT SWITCH MAY BE INSTALLED IN THE WALK IN VAULT APPLICATION FOR ALL NEW CONSTRUCTION AS NEEDED FOR BOTH MANUAL AND SCADA FACILITIES.





**FIGURE 1**
4-WAY MANUAL
CONNECTION DIAGRAM (II)
SEE TABLE 2

**UG MAP SYMBOL**






**TABLE 1**

| ELECTRICAL RATINGS | |
|---|---|
| VOLTAGE | 15.5KV |
| CURRENT, CONTINUOUS | 600A |
| B.I.L. | 95KV |
| MAXIMUM INTERRUPTING CURRENT VFI | 16KA - SYMMETRICAL |
| MOMENTARY MAKE AND LATCH | 20KA - ASYMMETRICAL |
| B.I.L. ACROSS OPEN VFI | 125KV |

**TABLE 2**

| INTERNAL TRAYER DESIGNATION | |
|---|---|
| **SYMBOL** | **DEFINITION** |
| L | LEFT |
| S | 4TH POSITION |
| T | TAP |
| R | RIGHT |




**UG MAP SYMBOL**






**FIGURE 2**
4-WAY SCADA VAULT-MOUNT
CONNECTION DIAGRAM
SEE TABLE 2

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |








**FIGURE 3**
5-WAY SCADA VAULT-MOUNT
CONNECTION DIAGRAM
SEE TABLE 2





**FIGURE 4**
4-WAY MANUAL
FRONT VIEW
SEE TABLE 3





**FIGURE 4**
4-WAY MANUAL
SIDE VIEW
SEE TABLE 3

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |




**FIGURE 5**
LINEAR ACTUATOR (III)



**FIGURE 6**
4-WAY MANUAL WITH (III)
LINEAR ACTUATOR





**FIGURE 7**
4-WAY SCADA
FRONT VIEW
SEE TABLE 3





**FIGURE 7**
4-WAY SCADA
SIDE VIEW
SEE TABLE 3

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

TABLE OF CONTENTS





**FIGURE 8**
5-WAY SCADA
FRONT VIEW
SEE TABLE 3





**FIGURE 8**
5-WAY SCADA
SIDE VIEW
SEE TABLE 3



**FIGURE 9**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |

## TABLE 3

| TRAYER SWITCH DETAILS | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | FAULT INDICATOR WINDOW |
| 2 | LIFTING EYE |
| 3 | SCADA CABINET |
| 4 | CABINET HANDLE, PAD LOCKABLE |
| 5 | POWER TRANSFORMER DRY WELL FUSE, 8.3KV, 3A CL |
| 6 | NAME PLATE |
| 7 | 24V DC LINEAR ACTUATOR |
| 8 | OIL FILL PLUG |
| 9 | FAULT TRIP INDICATOR |
| 10 | EQUIPMENT GROUND NUTS, 1/2" |
| 11 | 600A BUSHING/CONNECTOR |
| 12 | WINDOW VIEW TRI-PHASE VISIBLE DISCONNECT |
| 13 | PARKING STAND |
| 14 | PROVISION FOR ROPE OPERATION |
| 15 | TRI PHASE VISIBLE DISCONNECT OPERATOR HANDLE |
| 16 | VACUUM SWITCH OPERATING HANDLE |
| 17 | WALL MOUNTING BRACKET |
| 18 | LIQUID LEVEL GAUGE, TRAYER 901A |
| 19 | ANTENNA CONNECTION, SCADA |
| 20 | SWITCH BASE |
| 21 | FLOOR ATTACHMENTS |

TABLE OF CONTENTS

## INSTALLATION:

A. ALL CONDUITS THAT ENTER FROM THE OUTSIDE SHALL BE SEALED WITH DUCT PLUGS. CONDUITS SHALL ALSO BE SEALED FROM FACILITIES THAT TRANSITION TO THE VAULT. CONDUITS WITH CABLE SHALL BE SEALED WITH THE TYCO RAYFLATE SYSTEM. (j) (k)

B. SWITCHES MUST BE ATTACHED TO THE FLOOR AND THE WALL. THE WALL ANCHOR MOUNT BRACKETS ARE ADJUSTABLE FOR CABLE TRAINING AND CABLE TRANSITION BEHIND THE SWITCH IF NECESSARY.

C. THE DRILLING PATTERN ON THE SWITCH STAND MATCHES THE UNDERGROUND DEVICES PLASTIC CABLE RACKS FOR ATTACHMENT OF CABLE HOOKS AND ARMS.

D. EACH 4-WAY MANUAL TRAYER SWITCH COMES WITH A MOTOR ACTUATOR FOR REMOTE SWITCHING. THE UNIT MAY BE MOVED TO ANY POSITION FOR REMOTE SWITCHING OPERATIONS. IT MAY BE POWERED BY THE INTERNAL 120V SOURCE OF THE VAULT OR A GENERATOR FOR EXTENDED OUTAGES.

E. THE 4/0 GROUND MAY RING THE SWITCH STAND JUST BELOW THE SWITCH USING THE 2-INCH X 3-INCH STAINLESS STEEL (L) BRACKETS AND 1/2-INCH X 6-INCH PULLING AND 1 1/2-INCH X 1/2-INCH STAINLESS STEEL SHOULDER BOLT. THE STAND HAS MULTIPLE 1/2-INCH HOLES ON ALL SIDES FOR ATTACHMENT POINTS. THE 4/0 RING GROUND MUST BE ATTACHED TO THE VAULT GROUND SYSTEM. (h)

F. THE SCADA RTU CABINET MUST HAVE A MINIMUM OF 48 INCHES FROM THE WALL FOR WORK SPACE. THE STANDARD 8-FOOT WORK SPACE MUST BE MAINTAINED IN FRONT OF THE SWITCH FOR LIVE LINE TOOL OPERATIONS. (b)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

G. SEE UG3214 FOR TAGGING OF THE WAY POSITIONS ON THE FACE OF THE SWITCH.

H. LOCKS: ALL MANUAL SWITCHES SHALL BE LOCKED, SCADA SWITCH POSITIONS THAT ARE NOT OCCUPIED SHALL BE LOCKED. LOCKS SHALL BE AVAILABLE FOR THE LOCK OUT AND TAGGING FOR ALL D.S.O. OPERATIONS.

J. THE USE OF FUSED ELBOWS WILL BE LIMITED TO ONE FUSED ELBOW ONLY ON THE RIGHT OR LEFT SIDE SWITCH WAY POSITION. NO DEVIATION WILL BE GRANTED FOR MORE THAN ONE FUSE ELBOW IN THE TRAYER SWITCH.

K. TAPPING THE BACK OF 600A TEES FOR 200A DISTRIBUTION WILL BE LIMITED TO SWITCH CHANGE OUTS WITH EXISTING 200A TAPS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | 4-WAY MANUAL | 2,845 | 1 | -- | S704730 | 4WYTMV |
| | 4-WAY SCADA | 5,320 | 1 | -- | S704712 | 4WYTSV |
| | 5-WAY SCADA | 6,170 | 1 | -- | S704714 | 5WYTSV |
| 2 | ANCHOR, WALL (V) | -- | 4 | -- | SUPPLIED WITH SWITCH | |
| 3 | CONNECTORS, 12KV, 600/200A (V) | -- | AS REQ'D | 4186 | -- | -- |
| 4 | PADLOCK (V) | -- | AS REQ'D | -- | S514848 | -- |
| 5 | ANCHOR, CONCRETE, STAINLESS STEEL (V) | -- | 12 | 4177/4178 | S107654 | CNCANC |
| 6 | POST, CONNECTOR, 1/0 (V) | -- | 5 | -- | S262560 | USPCON |
| 7 | WIRE, 4/0, COPPER (V) | -- | AS REQ'D | 4521 | S812764 | 4/0-SD |
| 8 | GROUND, TRENCH, 4/0, COPPER (V) | -- | AS REQ'D | 4510 | S812818 (X) | TG-E-W |
| 9 | SEALING COMPOUND (V) | -- | AS REQ'D | 3948 | S442976 | SEAL-6 |
| 10 | TAG, SWITCH POSITION (V) | -- | -- | 3214 | -- | -- |
| 11 | EYE BOLT, 6" X 1/2", STAINLESS (V) | -- | 2 | -- | S150582 | -- |
| 12 | BRACKET, ANGLE, STAINLESS STEEL, 2" X 3" (V) | -- | 4 | 4505 | S166072 | -- |
| 13 | EYE BOLT, STAINLESS STEEL, 1 1/2" X 1/2" (V) | -- | 2 | -- | S152722 (X) | -- |
| 14 | WASHER, STANDARD FLAT, BRONZE, 1/2" (V) | -- | 8 | -- | S799488 | -- |
| 15 | WASHER, LOCK SPRING (V) | -- | 4 | -- | S796416 | -- |
| 16 | CABLE IDENTIFICATION (V) | -- | AS REQ'D | 3202 | -- | -- |

## NOTES:

I. WHEN PLANNING AND DESIGNING EXISTING WALK IN VAULTS FOR RETROFITTING NEW SWITCHES OR TRANSFORMERS SOME OF THE SMALLER VAULTS WILL REQUIRE MEASURING THE OPENINGS THAT EQUIPMENT IS DELIVERED THROUGH AND THE PLACEMENT OF EQUIPMENT FOR OPERATION AS SOME EQUIPMENT MAY NOT FIT OLDER FACILITIES.

(II) THE WAY POSITION MARKED T (THE 3RD POSITION FROM THE LEFT) SHALL BE THE OPEN TIE POSITION FOR ALL TRAYER SWITCHES

(III) EACH 4-WAY MANUAL SWITCH COMES WITH A 120V PIN-IN MOVABLE LINEAR ACTUATOR. IT MAY BE PLUGGED IN AT THE VAULT OR GENERATOR.

(IV) WHEN A TRAYER SCADA SWITCH IS FIRST ENERGIZED, THE SWITCH POSITIONS MUST BE MANUALLY OPERATED UNTIL THE KEARNY CREW INSTALLS ALL SCADA EQUIPMENT AND PROGRAMS THE SWITCH. THIS WILL REQUIRE THE CREW OPERATOR TO:

1. REMOVE THE YELLOW CONTROL CORD FROM THE LINEAR ACTUATOR
2. UN-PIN THE LINEAR ACTUATOR FROM THE VACUUM SWITCH HANDLE
3. DE-COUPLE THE LINEAR ACTUATOR FROM THE VACUUM SWITCH HANDLE
4. (4) REVERSE THE DIRECTION OF THE LINEAR ACTUATOR BY UN-PINNING AND RE-PINNING AT IT'S HINGE POINT (REFER TO FIGURE 10).

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |

**NOTES (CONT'D):**




**FIGURE 10** (V4)

5. TRAYER VAULT MOUNT SCADA SWITCHES COME WITH A REMOTE WAY POSITION PLUG-IN HAND HELD OPERATOR, WHEN THE UNIT IS PLACED ON LOCAL CONTROL FOR VAULT OPERATIONS IF REQUESTED BY THE SWITCHING CENTER DSO. IT CAN BE FOUND IN THE LOW VOLTAGE CONTROL CABINET DOOR. CONTROL POWER MUST BE AVAILABLE FOR THIS TO WORK, OTHERWISE SWITCHING MUST BE DONE MANUALLY.

(V) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

a. FOR CABLE IDENTIFICATION, SEE UG3202.

(b) FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

c. FOR PAD MOUNTED SWITCH IDENTIFICATION, SEE UG3214.

d. FOR FAULT INDICATOR INSTALLATION, SEE UG4355.

e. FOR (STANDARD) AND (ALTERNATE TRENCH GROUND WIRE), SEE UG4510.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE (CONT'D):**

f. FOR EQUIPMENT GROUNDING, SEE UG4520 AND UG4521.
g. FOR GROUNDING PREMOLDED CONNECTORS, SEE UG4525.
(h) FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM, SEE UG4521.
i. FOR SCADA INSTALLATION, SEE UG4640.
(j) FOR ELEVATION OF CUSTOMER FACILITIES PREVENTING WATER ENTRY, SEE UG3960.
(k) SEE UG3948.
l. FOR 600/200A CONNECTION APPLICATION, SEE UG4181.
m. SEE UG3214.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRAYER VAULT-MOUNTED SWITCH GEAR

UG3677.8

**SCOPE:** THIS STANDARD COVERS THE TRAYER 3-WAY MANUAL SUBMERSIBLE SWITCH, IT MAY BE INSTALLED IN SUB-SURFACE LOCATIONS, WALK-IN VAULTS, MANHOLES AND ANY STRUCTURE WITH LIMITED SPACE ISSUES.

**ATTENTION:**

* SOME APPLICATIONS WILL REQUIRE A DEVIATION FOR INSTALLATION. THIS SWITCH MAY BE MOUNTED IN A VERTICAL POSITION. THIS SWITCH SHOULD FIT IN STRUCTURES IN THE FMO3399 WITH THE 36-INCH OR LARGER ROUND OPENINGS IN SOME LOCATIONS. IT MAY BE REQUIRED TO REMOVE THE TOP SECTION TO GET TO THE 36-INCH OPENING.





**FIGURE 1** (I)
PLAN VIEW





**FIGURE 1**
SIDE VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 03/18/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRAYER 3-WAY SUBMERSIBLE LIQUID INSULATED VACUUM SWITCHGEAR

UG3678.1

TABLE OF CONTENTS





**FIGURE 2**
WIRING DIAGRAM

**UG MAP SYMBOL**



3-WAY TRAYER
MANUAL

## INSTALLATION:

A. **FOR 36-INCH OPENING:** REMOVE THE STAND OFF BUSHING BAND AND PUSH THE SUPPORTS IN FOR PREPARATION TO LOWER SWITCH INTO STRUCTURE.

B. SWITCH **SHALL ONLY** BE LIFTED USING SPECIFIED MANUFACTURER'S LIFT POINTS.

C. IT IS REQUIRED THAT THE UNIT BE BOLTED TO THE FLOOR OF THE STRUCTURE. IF USING THE MOUNTING BRACKET SWITCH MUST BE BOLTED TO THE BRACKET AND BRACKET BOLTED TO THE FLOOR.

D. USE ONLY EQUIPMENT GROUND POINTS SPECIFIED IN THE STANDARD.

E. THE SWITCH COMES WITH (6) 200A STAND OFF POSITIONS, LOOSEN THE NUT AND BOLT AND ADJUST THE STAND OFF BRACKETS AS NEEDED, RE-TIGHTEN THE BOLT AND NUT ON THE SUPPORT BAND.

F. EACH VISUAL OPEN HAS A COVER TO KEEP THE VIEW PORT CLEAN, IT CAN ONLY BE REMOVED WHEN THE SWITCH IS IN THE OPEN POSITION.

G. THE SWITCH HAS RIGGING POINTS FOR REMOTE OPERATION, THESE CAN ALSO BE APPLIED TO THE WALLS, FLOOR AND CEILING AS NEEDED. (j)

H. BUSHING PLUGS MAY BE APPLIED ON THE BACK OF THE TEE'S FOR EACH WAY POSITION FOR TESTING AND GROUNDING AS NEEDED. CHECK WORK SPACE FOR LIVE LINE TOOL OPERATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 03/18/2014 | D | | | | | | |

## INSTALLATION (CONT'D):

### (J) 3316/3317 APPLICATION OF SUBMERSIBLE TRAYER SWITCH

1. REQUIRES DEVIATION FOR THIS INSTALLATION.
2. THIS INSTALLATION HAS OPERATION LIMITATIONS AND MUST BE DE-ENERGIZED TO WORK ON.
3. NO OTHER CABLE OR EQUIPMENT MAY BE INSTALLED IN THIS STRUCTURE.
4. WHEN BOX IS SET SUMP SHOULD BE OPEN NOT COVERED BY SWITCH.
5. CONDUITS SHOULD USE TOP KNOCK OUTS FOR BETTER CABLE TRAINING.






**FIGURE 3** (J)
TOP VIEW




**DETAIL 1**




**FIGURE 4** (J)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 03/18/2014 | D | | | | | | |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(K) TRAYER 3-WAY IN A MANHOLE.

1. THE BUSHINGS SHOULD ALWAYS FACE THE WALL FOR CLEAR CABLE TRAINING AND SWITCH OPERATIONS.
2. THE SWITCH SHALL BE LOCATED 12 INCHES TO 18 INCHES OFF THE WALL TO ALLOW OTHER CABLE RUN CLEARANCES BEHIND THE SWITCH.
3. THE SWITCH SHALL BE BOLTED TO THE FLOOR USING THE EXTENSION BRACKETS ON THE BOTTOM.
4. SWITCH WAY POSITION 2 BUSHINGS SHALL HAVE THE 12-INCH TEE EXTENSIONS APPLIED TO PROVIDE CABLE SEPARATION AND CLEAR ACCESS TO THE TEE'S FOR GROUNDING OPERATIONS IF REQUIRED. THE TEE EXTENSION ALLOWS THE WAY POSITION 2 CABLES TO BE RACKED AT A HIGH LEVEL.
5. USE THE UNDERGROUND DEVICES FIBER CABLE STEPS AND HOOKS TO SECURE THE CABLE.





**FIGURE 5** (K)
TOP VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 03/18/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRAYER 3-WAY SUBMERSIBLE LIQUID INSULATED VACUUM SWITCHGEAR

UG3678.4

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 3-WAY TRAYER MANUAL | 1 | -- | S708570 | 3WAYTM |
| 2 | DEVICES, UG, CABLE RACKS (II) | AS REQ'D | 4178 | -- | -- |
| 3 | ADJUSTABLE STAND OFF PARKING | 6 | -- | -- | -- |
| 4 | CONNECTION, GROUND POINT (II) | -- | 4540/4505 | -- | -- |
| 5 | MOUNTING RAILS, PULL OUT BOLT DOWN TO FLOOR | 4 | 4177/4178 | S107654 | CNCANC |
| 6 | WINDOW, VISIBLE DISCONNECT VIEW | -- | -- | -- | -- |
| 7 | SWITCH HANDLE (II) | -- | -- | -- | -- |
| 8 | GROUND HARDWIRE (II) | AS REQ'D | 4505 | -- | -- |
| 9 | SOFT DRAWN COPPER, 4/0 (II) | AS REQ'D | -- | S812764 | 4/0-SD |
| 10 | GROUND, MOUNTING BRACKET (II) | -- | -- | -- | -- |
| 11 | INDICATOR, LIQUID LEVEL (II) | -- | -- | -- | -- |
| 12 | BRACKETS, LIFT POINT (II) | 3 | -- | -- | -- |
| 13 | PROVISIONS, FOR ROPE OPERATIONS | 6 | -- | -- | -- |
| 14 | HANDHOLE, 3316, TRAFFIC (II) | 1 | 3316 | S400312 | 3316TC |
| 15 | HANDHOLE, 3317, PARKWAY (II) | 1 | 3317 | S334430 | 3317SE |
| 16 | BUSHING EXTENSION (II) | 3 | 4181 | S336704 | BUSH-X |
| 17 | PLUG, ELBOW TAP (II) | 6 | 4181 | S547328 | BTP650 |
| 18 | CABLE ADAPTER (II) | 6 | 4181 | -- | -- |
| 19 | CONNECTOR LUG (II) | 6 | 4181 | -- | -- |
| 20 | ELBOW TEE (II) | 6 | 4181 | S326578 | BLBO-T |
| 21 | BOLT, BRONZE EYE (II) | 6 | 4505 | S471232 | TL1/0 |
| 22 | GROUND, SPLIT BOLT STUD (II) | 6 | 4505 | S262560 | USPCON |
| 23 | SCHLAGE, PAD LOCK (II) | 3 | -- | S514848 | 4WTFTS |
| 24 | FAULT INDICATOR (II) | AS REQ'D | 4352 | -- | -- |
| 25 | BUSS, STRUCTURE GROUND RING (II) | AS REQ'D | 4540 | S812818 (X) | GOWIRE |

TABLE OF CONTENTS

## NOTES:

(I) **OPERATION DESCRIPTION**

a. 600A
b. 3-WAY MANUAL OPERATION, WITH VISIBLE OPEN ON EACH POSITION
c. 14.4KV VOLTAGE
d. 14,300 SYM AMPS MOMENTARY
e. 20,000 ASY MAKE AND LATCH
f. WEIGHT: 1,245 LBS
g. STAINLESS STEEL
h. APPROX. LIQUID VOLUME: 112 GALLONS
i. NON PCB MINERAL OIL LIQUID INSULATION

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 03/18/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRAYER 3-WAY SUBMERSIBLE LIQUID INSULATED VACUUM SWITCHGEAR

UG3678.5

**NOTES (CONT'D):**

(II) NOT SHOWN IN FIGURES.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

a. FOR SWITCH IDENTIFICATION, SEE UG3215.

b. FOR EQUIPMENT COMBINATION GUIDELINES FOR SWITCHES IN MANHOLES, SEE UG3649.

c. FOR WIRE INFORMATION, SEE UG4003.

d. FOR SEALING JACKETED CABLE, SEE UG4108.

e. FOR SWITCH CONNECTIONS, SEE UG4181.

f. FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION, SEE UG4512.

g. FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM, SEE UG4521.

h. FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS, SEE UG4525.

i. FOR SWITCH APPLICATION, SEE DM6111.

(j) FOR RIGHTING, SEE UG3675.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | AW | JS | CZH | 07/01/2018 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 03/18/2014 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRAYER 3-WAY SUBMERSIBLE LIQUID INSULATED VACUUM SWITCHGEAR

UG3678.6

**SCOPE:** THIS STANDARD SHOWS THE TRAYER SUBSURFACE STAINLESS STEEL LIQUID INSULATED VACUUM 4-WAY SWITCH. EACH WAY POSITION CAN BE GROUNDED INDEPENDENTLY.

**ATTENTION:**

* THE TRAYER SUBSURFACE IS THE REPLACEMENT FOR BOTH GAS AND OIL SWITCHES WHEN THEY CANNOT BE PAD MOUNTED.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
SIDE VIEW






**FIGURE 2**
ONE LINE DIAGRAM
SEE TABLE 1

**UG MAP SYMBOL**



4-WAY MANUAL TRAYER

**TABLE 1**

| INTERNAL TRAYER DESIGNATION | |
|---|---|
| **SYMBOL** | **DESIGNATION** |
| L | LEFT |
| S | 4TH POSITION |
| T | TAP |
| R | RIGHT |

**TABLE 2**

| SWITCH OPERATION DESCRIPTION | |
|---|---|
| **DESCRIPTION** | **RATING** |
| VOLTAGE | 25KV |
| B.I.L. | 125KV |
| CURRENT, CONTINUOUS | 600A |
| LOAD MAKE, LOAD BREAK CURRENT | 600A |
| MOMENTARY MAKE AND LATCH | 20KA - ASY |
| WEIGHT | 2,445LBS |

**TABLE 3**

| SWITCH PARTS LIST | | | | | |
|---|---|---|---|---|---|
| **ITEM** | **DESCRIPTION** | **QTY** | **ITEM** | **DESCRIPTION** | **QTY** |
| 1 | VIEW WINDOW FOR VISIBLE DISCONNECT | -- | 9 | LIQUID LEVEL GAUGE | -- |
| 2 | HEAVY LIFTING EYE | 4 | 10 | EQUIPMENT GROUNDING POINT | -- |
| 3 | DECAL FOR LOW OIL | -- | 11 | 600A BUSHING CONNECTION | -- |
| 4 | TRI-PHASE VISIBLE DISCONNECT OPERATING HANDLE | -- | 12 | ADJUSTABLE WALL ANCHOR | 4 |
| 5 | OIL DRAIN PLUG | -- | 13 | SUPPORT STAND | -- |
| 6 | SDG&E NAME PLATE | -- | 14 | PROVISION FOR ROPE OPERATOR | 12 |
| 7 | INTERLOCKING MECHANISM | -- | 15 | VACUUM SWITCH OPERATING HANDLE | -- |
| 8 | OIL FILL PLUG | -- | 16 | HEAVY LIFTING EYE BOTTOM MOUNT | 2 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | TR | MDJ | 05/13/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRAYER 4-WAY GROUNDED VACUUM SWITCH



UG3679.1

TABLE OF CONTENTS

## INSTALLATION:

A. THE TRAYER 4-WAY SWITCH IS FOR INSTALLATION IN 3324, 3325, & 3326 MANHOLES. SMALLER MANHOLES WILL REQUIRE A DEVIATION REQUEST.

B. FOR SUB-SURFACE INSTALLATION THE TRAYER 4-WAY SWITCH SHALL BE BOLTED TO THE WALL WITH STAINLESS STEEL ANGLE BRACKETS AND SUPPORTED WITH 24-INCH STAINLESS STEEL STAND PROVIDED, 8-5/8-INCH BOLTS X 3-1/2-INCH STAINLESS STEEL BOLTS (S156750) AND 1/2-INCH WASHERS, STAINLESS STEEL.

C. STAND MUST BE REMOVED FROM SWITCH AND LOWERED INTO PLACE INSIDE STRUCTURE. SWITCH SHALL THEN BE LOWERED INTO STRUCTURE AND PLACED ON TOP OF STAND AND REASSEMBLED USING PROVIDED HARDWARE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | 600A 4-WAY STAINLESS STEEL | 1 | -- | S704740 | 4WTMSS |
| | MASTERLOCK 3 LONG SHANK | AS REQ'D | -- | S514914 | |
| 2 | DECALS | AS REQ'D | 3212-3218 | -- | -- |
| 3 | CONNECTOR, COMPRESSION (VIII) | AS REQ'D | 4174/4176 | -- | -- |
| 4 | FAULT INDICATORS (VIII) | AS REQ'D | 4352 | -- | -- |
| 5 | CONNECTORS, 600A, 600A/200A OR 200A (VIII) | AS REQ'D | 4181 | -- | AS NEEDED |

## NOTES:

I. WHEN REMOVING TANK FROM STAND, ENSURE TO HAVE BLOCKS/SUPPORTS UNDER THE FRONT END OF THE SWITCH TO PREVENT TANK FROM BEING FLUSH WITH THE GROUND. WITHOUT BLOCKS/SUPPORTS, DAMAGE WILL OCCUR TO THE DISCONNECT SWITCH HANDLES.

II. PLACE SWITCH ON OPPOSITE SIDE OF MANHOLE OPENING.

III. THE OPERATION SELECTOR PREVENTS INADVERTENT OPERATION FROM THE CLOSED POSITION TO THE OPEN POSITION AND OPEN TO GROUND POSITION.

IV. SWITCH IS DESIGNED TO BE OPERATED REMOTELY FOR SINGLE SWITCH OPERATIONS. THIS SWITCH IS NOT TO BE OPERATED MULTIPLE TIMES IN SHORT DURATIONS WHICH COULD RESULT IN DAMAGE TO THE GEARING.

V. THE TRAYER IS A MANUALLY OPERATED SWITCH AND NOT SCADA ADAPTABLE.

VI. PERFORM REMOTE SWITCHING OPERATIONS USING THE TRAYER MANUAL SWITCH BAG AND BLOCKS KIT. THIS TOOL IS AVAILABLE AT EACH ELECTRIC DISTRIBUTION DISTRICT.

VII. FOR NEW CONSTRUCTION AND CONVERSIONS, THIS TRAYER SWITCH SHOULD NOT BE USED TO TAP FEEDER CABLES. TAPS ON THE BACK OF 600A TEES IMPEDE GROUNDING AND LIMIT USE OF SWITCH POSITIONS DURING ROUTINE SWITCHING PROCEDURES AND OUTAGE SITUATIONS. TAP FEEDER SEGMENTS BETWEEN SWITCH POSITIONS USING 600A TERMINATORS OR TAP THE SWITCH POSITION WITH DISTRIBUTION CABLE ONLY.

(VIII) NOT SHOWN ON FIGURES.

## REFERENCE:

a. FOR SWITCH IDENTIFICATION, SEE UG3215.

b. FOR NEUTRAL AND GROUNDING WIRE DIAGRAM, SEE UG4530.

c. FOR CONNECTOR ASSEMBLIES, SEE UG4181.

d. FOR EQUIPMENT COMBINATION GUIDELINES, SEE UG3649.

e. FOR REMOTE SWITCHING PROCEDURES, SEE ESP221.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 04/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | TR | MDJ | 05/13/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD COVERS INNOVATIVE SWITCHGEAR'S SUBMERSIBLE AND VAULT MOUNT 600A, 15KV THREE-PHASE SOLID-DIELECTRIC-IN-AIR, AND COMES AS A VACUUM LOADBREAK SWITCH, AS WELL AS A VACUUM FAULT INTERRUPTER WITH VISIBLE DISCONNECTS. DUE TO DIVERSE ENVIRONMENTAL CONDITIONS THE SWITCHGEAR IS CONSTRUCTED OF STAINLESS STEEL AND POWDER COATED.

**ATTENTION:**

* THIS IS AN INITIAL CONSTRUCTION STANDARD RELEASE. AS SWITCHES ARE INSTALLED, MORE DETAILS WILL BE UPDATED FOR EACH TYPE OF SWITCH BELOW. PLEASE COORDINATE WITH EDE FOR INQUIRIES.

**TABLE 1**

| INNOVATIVE SWITCHGEAR ELECTRICAL RATINGS | | |
|---|---|---|
| | **SCADA** | **MANUAL** |
| **VOLTAGE** | 15.5KV/4KV | 25KV |
| **CURRENT, CONTINUOUS** | 600A/200A | -- |
| **B.I.L.** | 95KV | -- |
| **MAXIMUM INTERRUPTING CURRENT VACUUM FAULT INTERRUPTER** | 12.5KA (SYMMETRICAL) | -- |
| | 20KA (ASYMMETRICAL) AT 32.5KA PEAK CURRENT | -- |
| **MOMENTARY MAKE AND LATCH** | 12.5KA (SYMMETRICAL) | -- |
| | 20KA (ASYMMETRICAL) AT 32.5KA PEAK CURRENT | -- |
| **B.I.L. ACROSS OPEN VACUUM FAULT INTERRUPTER** | 125KV | -- |



© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 1**
TWO-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA
SEE TABLE 2


**TABLE 2**

| TWO-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA PACKAGE | | |
|---|---|---|
| **DESCRIPTION** | **QUANTITY** | **APPROX. SYSTEM WEIGHT (LBS)** |
| S201066-008 SWITCH TANK | 1 | 420 |
| CT SHORTING PLUG | 1 | -- |
| MOTOR OPERATOR WITH HANDLE LINKAGE | 1 | 35 EACH |
| JUNCTION CONTROL BOX | 1 | -- |
| PENDANT CONTROL | 1 | -- |
| 50-FOOT CABLES | 2 | -- |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

| INNOVATIVE SWITCHGEAR SOLUTIONS INC. ™<br>FAULT INTERRUPTER/SWITCH<br>PATENT PENDING | |
|---|---|
| MAXIMUM VOLTAGE | 25 KV |
| CONTINUOUS CURRENT | 600 AMPS |
| INTERRUPTING CURRENT (SYM.) | 12.5 KA |
| INTERRUPTING CURRENT (ASYM.) | 20.0 KA |
| PEAK CURRENT | 32.5 KA |
| FAULT CLOSE (SYM.) | 12.5 KA |
| IMPULSE WITHSTAND VOLTAGE | 125 BIL |
| POWER FREQUENCY | 60 HZ |




| CAT# S201066-008 | WEIGHT 420 LBS |
|---|---|

CURRENT TRANSFORMER RATIOS

200 AMP BUSHINGS = 200:5 RATIO

600 AMP BUSHINGS = 600:5 RATIO

INNOVATIVE SWITCHGEAR SOLUTIONS, INC

ISGYYXXXX

____/20YY

**FIGURE 2**
TWO-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA
SEE TABLE 2








**FIGURE 3**
TWO-WAY SUBMERSIBLE 600A MANUAL
CONNECTION DIAGRAM

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |










**FIGURE 4**
THREE-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA
SEE TABLE 3

**TABLE 3**

| THREE-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 620 |






**FIGURE 5**
THREE-WAY SUBMERSIBLE 600A MANUAL
CONNECTION DIAGRAM

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |








**FIGURE 6**
THREE-WAY SUBMERSIBLE STAND
ISO VIEW







**FIGURE 6**
THREE-WAY SUBMERSIBLE STAND




**DETAIL 1**




**DETAIL 2**

## BILL OF MATERIALS (FIGURE 6):

| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | STAND SET, QUAD CHANNEL, ADJUSTABLE, SIDE MOUNT, OCTAGONAL 3-WAY | 160 | 1 | -- | SS-10003 | -- |
| 2 | BRACKET, 3-WAY NO VO, TO WALL | 10 | 1 | -- | SMP-10693 | -- |
| 3 | LIFTING EYE, BOLT ON 1/2" NUT | -- | 4 | -- | SMP-10263 | -- |
| 4 | WASHER, FLAT, 18-8, 1/2" SAE, MMC# 96659A110 | -- | 10 | -- | PP-10218 | -- |
| 5 | WASHER, LOCK, 18-8 SS, 1/2" SIZE, .87"OD, .12" MIN THICK, MMC#92146A033 OR EQUIV | -- | 10 | -- | PP-10097 | -- |
| 6 | SCREW, HC, 1/2"-13, 3/4"L, SILICON BRONZE, ALLIED BOLT#14136 | -- | 10 | -- | PP-10402 | -- |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 7**
FOUR-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA
SEE TABLE 4

**TABLE 4**

| FOUR-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA PACKAGE | | |
|---|---|---|
| **DESCRIPTION** | **QUANTITY** | **APPROX. SYSTEM WEIGHT (LBS)** |
| S40406666-008 SWITCHGEAR | 1 | -- |
| MOTOR OPERATORS | 4 | -- |
| PENDANT CONTROL | 1 | -- |
| JUNCTION BOX | 1 | -- |
| CT SHORTING PLUGS | 4 | -- |
| SWITCH TANK | -- | 1,200 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 8**
FOUR-WAY SUBMERSIBLE 600A MANUAL/NON-SCADA
SEE TABLE 4





**FIGURE 9**
FOUR-WAY SUBMERSIBLE 600A MANUAL
CONNECTION DIAGRAM

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 10**
FOUR-WAY SUBMERSIBLE 600A SCADA 12KV W/ PEDESTAL
SEE TABLE 5

**TABLE 5**

| FOUR-WAY SUBMERSIBLE 600A SCADA 12KV W/ PEDESTAL PACKAGE APPROX. SYSTEMS WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 1,200 |
| MOTOR OPERATORS | 35 EACH |
| LIFTING BRACKETS | 2 EACH |
| POTENTIAL TRANSFORMERS WITH CRADLE | 145 EACH |
| CONTROL CABINET WITH PEDESTAL | 585 |





**FIGURE 11**
FOUR-WAY SUBMERSIBLE 600A SCADA
CONNECTION DIAGRAM

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 12**
FOUR-WAY SUBMERSIBLE 600A SCADA 12KV W/ PEDESTAL
SEE TABLE 6





**FIGURE 13**
FOUR-WAY SUBMERSIBLE 600A SCADA 12KV W/ PEDESTAL
SEE TABLE 6

**TABLE 6**

| FOUR-WAY SUBMERSIBLE 600A SCADA 12KV W/ PEDESTAL APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 420 |
| MOTOR OPERATOR | 35 EACH |





**FIGURE 14**
FOUR-WAY SUBMERSIBLE 600A SCADA 12KV W/ PEDESTAL
SEE TABLE 6

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 15**
FOUR-WAY SUBMERSIBLE STAND (MANUAL & SCADA)







**FIGURE 15**
FOUR-WAY SUBMERSIBLE STAND (MANUAL & SCADA)
ISO VIEW




**DETAIL 3**





**DETAIL 4**


## BILL OF MATERIALS (FIGURE 15):


| ITEM | DESCRIPTION | WEIGHT (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | ASSY, STAND, 4-WAY , SUB, 304 S/S, FOR S40406666-_0_ | 105 | 1 | -- | SMA-20188 | -- |
| 2 | BRACKET, LIFTING, WALL MOUNT | 2 EACH | 4 | -- | SMP-10887 | -- |
| 3 | BRACKET, WALL ATTACHMENT | 5 EACH | 2 | -- | SMP-10888 | -- |
| 4 | WASHER, FLAT, 18-8, 1/2" SAE, MMC# 96659A110 | -- | 18 | -- | PP-10218 | -- |
| 5 | WASHER, LOCK, 18-8 SS, 1/2" SIZE, .87"OD, .12" MIN THICK, MMC#92146A033 OR EQUIV | -- | 18 | -- | PP-10097 | -- |
| 6 | SCREW, HEX CAP, 1/2-13, 1 1/4"L, SILICON BRONZE | -- | 14 | -- | PP-10400 | -- |
| 7 | SCREW, HC 18-8, 1/2-13 X 1 1/4" MMC#92240A714 | -- | 4 | -- | PP-10215 | -- |
| 8 | NUT, 1/2-13, SILICON BRONZE, FASTENAL #74967 | -- | 4 | -- | PP-10366 | -- |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |










**FIGURE 16**
FOUR-WAY VAULT MOUNT 600A MANUAL/NON-SCADA
SEE TABLES 7 AND 8

**TABLE 7**

| FOUR-WAY VAULT MOUNT 600A MANUAL/NON-SCADA APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 1,420 |
| STAND AND BRACKETS | 195 |
| MOTOR OPERATORS | 35 EACH |

**TABLE 8**

| VOLTAGE RATING | |
|---|---|
| **ITEM** | **VOLTAGE** |
| INTERNAL VS | 12.47/7.2KV LINE TO GROUND |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 17**
FOUR-WAY VAULT MOUNT 600A MANUAL/NON-SCADA
CONNECTION DIAGRAM





**FIGURE 18**
FOUR-WAY VAULT MOUNT 600A MANUAL/NON-SCADA
SEE TABLES 7 AND 8

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 19**
FOUR-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 9 AND 10

**TABLE 9**

| FOUR-WAY VAULT MOUNT 600A SCADA 12KV APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 1,420 |
| STAND AND BRACKETS | 195 |
| MOTOR OPERATORS | 35 EACH |
| CONTROL CABINET | 500 |
| POTENTIAL TRANSFORMERS | 130 EACH |

**TABLE 10**

| VOLTAGE RATING | |
|---|---|
| **ITEM** | **VOLTAGE** |
| PT | 12.47/7.2KV LINE TO GROUND |
| INTERNAL VS | 12.47/7.2KV LINE TO GROUND EXTERNAL |
| EXTERNAL VS | 12.47/7.2KV LINE TO GROUND |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |







**FIGURE 20**
FOUR-WAY VAULT MOUNT 600A SCADA 12KV
CONNECTION DIAGRAM



CONTROL CABINET WITH
WALL MOUNTING PROVISION

**FIGURE 21**
FOUR-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 9 AND 10



POTENTIAL TRANSFORMER
WITH WALL MOUNTING
PROVISION (2)

**FIGURE 22**
FOUR-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 9 AND 10





**FIGURE 23**
FOUR-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 9 AND 10

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 24**
FIVE-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 11 AND 12

**TABLE 11**

| FIVE-WAY VAULT MOUNT 600A SCADA 12KV APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 1,750 |
| STAND AND BRACKETS | 240 |
| MOTOR OPERATORS | 35 EACH |
| CONTROL CABINET | 500 |
| POTENTIAL TRANSFORMERS | 130 EACH |

**TABLE 12**

| VOLTAGE RATING | |
|---|---|
| **ITEM** | **VOLTAGE** |
| PT | 12.47/7.2KV LINE TO GROUND |
| INTERNAL VS | |
| EXTERNAL VS | |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |






**FIGURE 25**
FIVE-WAY VAULT MOUNT 600A SCADA 12KV
CONNECTION DIAGRAM



CONTROL CABINET WITH WALL
MOUNTING PROVISION (2)

**FIGURE 26**
FIVE-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 13 AND 14

**TABLE 13**

| FIVE-WAY VAULT MOUNT 600A SCADA 12KV APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 1,420 |
| STAND AND BRACKETS | 195 |
| MOTOR OPERATORS | 35 EACH |
| CONTROL CABINET | 500 |
| POTENTIAL TRANSFORMERS | 130 EACH |






**TABLE 14**

| VOLTAGE RATING | |
|---|---|
| **ITEM** | **VOLTAGE** |
| PT | 12.47/7.2KV LINE TO GROUND |
| INTERNAL VS | 12.47/7.2KV LINE TO GROUND EXTERNAL |
| EXTERNAL VS | 12.47/7.2KV LINE TO GROUND |



POTENTIAL TRANSFORMER
WITH WALL MOUNTING
PROVISION (2)

**FIGURE 27**
FIVE-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 13 AND 14

**FIGURE 28**
FOUR-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 13 AND 14

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |





**FIGURE 29**
SIX-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 15 AND 16

**TABLE 15**

| SIX-WAY VAULT MOUNT 600A SCADA 12KV APPROX. SYSTEM WEIGHTS | |
|---|---|
| **DESCRIPTION** | **WEIGHT (LBS)** |
| SWITCH TANK | 2,040 |
| STAND AND BRACKETS | 325 |
| MOTOR OPERATORS | 35 EACH |
| AUTOMATION CONTROL CABINET | 500 |
| POTENTIAL TRANSFORMERS WITH CRADLE | 145 EACH |

**TABLE 16**

| VOLTAGE RATING | |
|---|---|
| **ITEM** | **VOLTAGE** |
| PT | 12.47/7.2KV LINE TO GROUND |
| INTERNAL VS | |
| EXTERNAL VS | |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |






**FIGURE 30**
SIX-WAY VAULT MOUNT 600A SCADA 12KV




| CAT# V6150666666-102 | WEIGHT 2040 LBS |
|---|---|

INNOVATIVE SWITCHGEAR SOLUTIONS INC.™
FAULT INTERRUPTER/SWITCH
PATENT PENDING

| | |
|---|---|
| MAXIMUM VOLTAGE | 15.5 KV |
| CONTINUOUS CURRENT | 600 AMPS |
| INTERRUPTING CURRENT (SYM.) | 12.5 KA |
| INTERRUPTING CURRENT (ASYM.) | 20.0 KA |
| PEAK CURRENT | 32.5 KA |
| FAULT CLOSE (SYM.) | 12.5 KA |
| IMPULSE WITHSTAND VOLTAGE | 95 BIL |
| POWER FREQUENCY | 60 HZ |

CURRENT TRANSFORMER RATIO

600:5 RATIO

INNOVATIVE SWITCHGEAR SOLUTIONS, INC

ISGYYXXXX

____/20YY

INTERNAL VOLTAGE SENSORS

RATED 12470/7200:120





**FIGURE 31**
SIX-WAY VAULT MOUNT 600A SCADA 12KV





**FIGURE 32**
SIX-WAY VAULT MOUNT 600A SCADA 12KV
CONNECTION DIAGRAM
SEE TABLES 15 AND 16

**FIGURE 33**
SIX-WAY VAULT MOUNT 600A SCADA 12KV
SEE TABLES 15 AND 16


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**ATTENTION:**

* CURRENTLY UNDER EVALUATION, DO NOT USE WITHOUT APPROVAL FROM EDE.








**FIGURE 34**
SCHNEIDER P116 5A RELAY

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION:

**PAD APPLICATIONS USED AS REFERENCE UNTIL UNITS ARE INSTALLED.**

(A) FOR SINGLE PADMOUNT APPLICATIONS, THE SWITCH TANK IS SHIPPED INSIDE THE ENCLOSURE ON ITS BACK WITH THE BUSHINGS FACING UP. THE SWITCH STAND AND ANY OPTIONAL ITEMS TO COMPLETE THE PACKAGE WILL BE SHIPPED INSIDE THE PADMOUNT ENCLOSURE. SEE FIGURE 35.



**FIGURE 35** (A)

(B) FOR INTERNAL AND TWO EXTERNAL BOLTS SECURE THE ENCLOSURE TO THE PALLET. REMOVE THESE BOLTS TO LIFT THE ENCLOSURE FROM THE PALLET. THE DOORS MAY BE OPENED OR REMOVED TO HELP GUIDE THE ENCLOSURE OVER THE EQUIPMENT. SEE FIGURE 36 AND 37.



**FIGURE 36** (B)



**FIGURE 37** (B)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

(C) THREE LIFTING PROVISIONS ARE PROVIDED ON BOTH ENDS OF THE SWITCH TANK. THESE LIFTING PROVISIONS ROTATE 360 DEGREES. SEE FIGURE 38 AND 39.



**FIGURE 38** (C)



**FIGURE 39** (C)

(D) MOTOR OPERATOR LINKAGE REQUIRES 20 INCHES OF SPACE IN THE OPEN POSITION TO NOT IMPACT THE PADMOUNT ENCLOSURE DOORS. LEAVE 21 1/2 INCHES FROM THE FACE OF THE SWITCH TO THE PADMOUNT ENCLOSURE DOORS. SEE FIGURE 40.





**FIGURE 40** (D)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

(E) MOTOR OPERATORS AND LINKAGES ARE MATED TO THE SWITCH AND IDENTIFIED AT THE MANUFACTURING PLANT. MOUNT MOTOR OPERATORS WITH CORRESPONDING WAYS AFTER THE CABLE HAS BEEN LANDED AND PRIOR TO MOUNTING THE ENCLOSURE. SEE FIGURE 41 AND 42.





**FIGURE 41** (E)





**FIGURE 42** (E)

F. INNOVATIVE SWITCHGEAR HAS A UNIQUE FEATURE ALLOWING THE ENCLOSURE TO BE REMOVED WHILE THE SWITCH REMAINS INTACT. THIS WILL BETTER FACILITATE IN WIRE PULLING AND SWITCH MAKE-UP. SWITCH STAND AND ENCLOSURE MUST BE SECURED TO THE PAD AND GROUNDED INDIVIDUALLY.

(G) ON NON-SCADA UNITS, ONCE THE ENCLOSURE IS SECURE, ATTACH THE CABLES FROM THE JUNCTION BOX TO THE MOTOR OPERATORS. EACH CABLE IS DESIGNATED AND MARKED WITH A WAY POSITION. SEE FIGURE 43.




**FIGURE 43** (G)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

(H) THE POLYCARBONATE VIEWING WINDOWS FOR THE CLOSED/OPEN VACUUM CONTACT SEMAPHORE ARE COVERED AT THE FACTORY WITH GREEN ULTRAVIOLET PROTECTIVE TAPE. REMOVE THE TAPE UPON COMPLETION OF INSTALLATION. IF THE TAPE IS INADVERTENTLY REMOVED PRIOR TO INSTALLATION, PLEASE COVER THE LENSES OR APPLY ULTRAVIOLET PROTECTIVE TAPE TO KEEP THE WINDOWS FROM YELLOWING. SEE FIGURE 44.




**FIGURE 44** (H)

J. THE ONE OPERATING HANDLE OPENS THE VACUUM INTERRUPTS FIRST SO THAT THE ELECTRICAL INTERRUPTION IS ALWAYS PERFORMED WITHIN THE VACUUM INTERRUPTS AND THE THE VISIBLE OPEN ISOLATION POINT (VOIP) SWITCH OPENS.



© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

K. FOR VIEW OF THE CONTACTS:

(1) FOR SINGLE SIDE PADMOUNT, VAULT MOUNT, AND SUBMERSIBLE, THE VIEW OF THE OPEN CONTACTS IS FROM THE TOP OF THE MECHANISM. SEE FIGURES 45 AND 46 BELOW.





**FIGURE 45**
VISIBLE OPEN SHAFT (K1)
"CLOSED"





**FIGURE 46**
VISIBLE OPEN SHAFT "OPEN", (K1)
ISOLATED AND VISIBLE

(2) FOR DOUBLE SIDE PADMOUNT APPLICATIONS, THE VIEW OF THE OPEN CONTACTS IS FROM THE SIDE OF THE MECHANISM, SEE FIGURES 47 AND 48.




**FIGURE 47**
VISIBLE OPEN SHAFT (K2)
"OPEN"




**FIGURE 48**
VISIBLE CLOSED SHAFT (K2)
"CLOSED"

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## INSTALLATION (CONT'D):

(L) PENDANT CONTROLLERS ARE PROVIDED TO POWER AND CONTROL ALL THE MOTOR OPERATORS FROM OUTSIDE THE ENCLOSURE. THESE PORTABLE CONTROLLERS ARE DESIGNED TO PROVIDE FIELD PERSONNEL THE ABILITY TO PLUG INTO A JUNCTION BOX TO DETERMINE STATUS OF ALL THE MOTORS AND TO CONTROL MULTIPLE MOTOR OPERATORS LOCALLY WITH EXTERNAL 120V AC POWER PLUGGED INTO THE PENDANT CONTROL. SEE FIGURE 49.

## CAUTION:

* THE "CONTROL HEALTHY" LIGHT WILL ONLY LIGHT WHEN THE TOGGLE SWITCH IS TURNED ON AND WHEN CONNECTED TO A "PURE SINCE WAVE" SOURCE OF 120V AC POWER. SQUARE SINE WAVE OR MODIFIED SINE WAVE INVERTERS WILL NOT POWER THIS DEVICE AND MAY DAMAGE THE CONTROL.




**FIGURE 49** (L)

(M) PENDANT CONTROLLER MUST BE CONNECTED TO THE JUNCTION BOX PICTURED BELOW TO OPERATE MOTOR OPERATORS. JUNCTION BOX CONNECTIONS ARE SEVEN-PIN AND 12-PIN, SO THEY CANNOT BE INSTALLED INCORRECTLY. SEE FIGURE 50.





**FIGURE 50** (M)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

N. WITH THE ABILITY TO REMOTELY OPERATE THE MOTOR OPERATIONS ON THE SWITCH. THE ACTUATOR ARMS SHALL NOT BE LOCKED.

**SCADA UNITS**

O. ALL SOURCE AND TIE POSITIONS SHALL BE PHASE IDENTIFIED WITH THE AP30. THE SWITCH SHALL BE MARKED FOR "A", "B" AND "C" PHASES.

(P) THERE ARE TWO REDUNDANT POTENTIAL TRANSFORMERS (PTS) THAT ARE CONNECTED PHASE TO GROUND. PTS TO BE CONNECT ON THE SOURCE SIDE AND TIE POSITION OF THE SWITCH (IF NO TIE EXISTS ON SWITCH, CHOOSE POSITION WITH DOWNSTREAM TIE SWITCH). IF APPLICABLE, ON THE CENTER PHASE POSITION. PHASE CONNECTION TO THE P.T. IS TO BE MADE WITH A FUSED ELBOW AS THE P.T. DOES NOT HAVE ITS OWN PROTECTION. GROUND ELBOW TO BE STRIPPED AND CONNECTED TO A COPPER TAIL AND THEN HARD TAPPED TO THE GROUND RING BUS. SEE FIGURE 51 AND 52.




**FIGURE 51** (P)




**FIGURE 52** (P)

(Q) WHEN INSTALLING THE PTS, WE MUST BOND ALL OF THE BASE PLATES OF H2 AND H1 TO GROUND SOURCE/RING BUS. FAILURE TO DO SO WILL RESULT IN THE RING BUS HAVING HIGH VOLTAGE CAPABILITY AND COULD RESULT IN UNFAVORABLE CONSEQUENCES.





**FIGURE 53** (Q)




**FIGURE 54** (Q)




**FIGURE 55** (Q)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

## ATTENTION:

* VOLTAGE SENSORS ARE TO BE GROUNDED PRIOR TO ENERGIZING.

(R) VOLTAGE SENSOR ARE TO BE CONNECTED TO THE TIE POSITION OF THE SWITCH. IF APPLICABLE USING A FEED THRU DEVICE ON THE P.T. WILL ALLOW FOR THE VOLTAGE SENSOR AND P.T. TO BE CONNECTED TO THE SAME SWITCH POSITION. SEE FIGURE 56.





**FIGURE 56** (R)






**FIGURE 57** (R)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## INSTALLATION (CONT'D):

(S) PRIOR TO ENERGIZING, CHECK TO MAKE SURE MOTOR OPERATOR ACTUATOR ARMS CAN FUNCTION UNOBSTRUCTED. P.T. ELBOWS SHALL BE PLACED ON THE CENTER PHASE POSITION OF THE SWITCH. FAULT INDICATORS SHALL BE POSITIONED AWAY FROM THE TRAVEL OF THE MOTOR OPERATOR ACTUATOR ARMS. SEE FIGURE 58 AND 59.



P.T. ELBOW SHALL BE PLACED ON THE CENTER PHASE TO ALLOW THE MOTOR ACTUATOR THE NECESSARY CLEARANCE TO OPERATE





**FIGURE 58** (S)

**FIGURE 59** (S)

### PADMOUNT OPTIONS

(T) SET THE SWITCH ON THE BOX PAD. USING A 1/2-INCH DRILL BIT, DRILL THROUGH THE EXISTING HOLES IN THE SILL FLANGE AND THROUGH THE BOX PAD. BOLT DOWN AS SHOWN IN HOLD DOWN DETAIL. SEE DETAIL 5.




**DETAIL 5** (T)
HOLD DOWN DETAILS
(USE STAINLESS STEEL TIE DOWNS PROVIDED)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | TWO-WAY SUBMERSIBLE, 600A MANUAL/NON-SCADA | 1 | -- | S704752 | IS2S6M |
| | THREE-WAY SUBMERSIBLE, 600A MANUAL/NON-SCADA | | | S704754 | IS3S6M |
| | STAND, THREE-WAY SUBMERSIBLE | | | S677220 | IS3SDM |
| | FOUR-WAY SUBMERSIBLE, 600A MANUAL/NON-SCADA | | | S704756 | IS4S6M |
| | FOUR-WAY SUBMERSIBLE, 600A SCADA, 12KV W/ PEDESTAL | | | S704816 | IS4S6S |
| | STAND, FOUR-WAY SUBMERSIBLE (MANUAL & SCADA) | | | S677222 | IS4SDM |
| | FOUR-WAY VAULT MOUNT, 600A MANUAL/NON-SCADA | | | S704758 | IS4V6M |
| | FOUR-WAY VAULT MOUNT, 600A SCADA, 12KV | | | S709302 | IS4V6S |
| | FIVE-WAY VAULT MOUNT, 600A SCADA, 12KV | | | S704760 | IS5V6S |
| | SIX-WAY VAULT MOUNT, 600A SCADA, 12KV | | | S704762 | IS6V6S |
| | SCHNEIDER P116 5A RELAY (WALL-MOUNT)(SEE FIGURE 34) | | | S588400 | SCR5S |
| 2 | MANHOLES | AS REQ'D | 3325-3327 | -- | -- |
| | DRY VAULTS | AS REQ'D | -- | -- | -- |
| | HANDHOLES | AS REQ'D | 3314-3317 | -- | -- |
| 3 | CABLE, #2 AWG, SOLID 1/C" | AS REQ'D | 4003 | S197600 | -- |
| 4 | CONNECTIONS, 12KV, 600/200A | AS REQ'D | 4181 | -- | -- |
| 5 | ELBOW, FUSED, 2 SOLID, 30A (FUSE INCLUDED) | AS REQ'D | 4191 | S321680 | CFE2SL |
| 6 | CONNECTOR POST, 1/0 | 5 | -- | S262560 | -- |
| 7 | WIRE, 4/0 COPPER | AS REQ'D | 4521 | S812764 | 4/0-SD |
| 8 | WIRE, #2 COPPER, GROUND TRENCH | 1 | 4510 | S812818 (X) | TG-E-W |
| 9 | BOLT, EYE, STAINLESS STEEL | AS REQ'D | -- | S150528 | -- |
| 10 | CONNECTOR, SERVICE POST | AS REQ'D | 3711 | S262560 | SPCONN |
| 11 | NUT, CLAMPING CHANNEL | AS REQ'D | | S503520 | -- |
| 12 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | AS REQ'D | | S616192 | -- |
| 13 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | AS REQ'D | | S799488 | -- |
| 14 | WASHER, SPRING, LOCK | AS REQ'D | | S796416 | -- |
| 15 | BOLT, 3 1/2" X 1/2" STAINLESS STEEL, TIE DOWN | 4 | -- | S148804 | -- |
| 16 | BRACKET, ANGLE, STAINLESS STEEL, 2" X 3" | AS REQ'D | 4505 | S166072 | -- |
| 17 | ANCHOR, 1/2" X 3 3/4" MOUNTING ON CONCRETE PAD | AS REQ'D | -- | S107654 | -- |
| 18 | SEALING COMPOUND | AS REQ'D | 3948 | S442976 | -- |
| 19 | PADLOCK | AS REQ'D | -- | S514848 | -- |
| 20 | SWITCH POSITION TAGGING | -- | 3215 | -- | -- |
| 21 | CABLE IDENTIFICATION | AS REQ'D | 3202 | -- | -- |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**NOTES:**

I. WHEN REPLACING EXISTING SWITCHES, THE TIE POSITIONS ARE ESTABLISHED AND CONNECTED AS DESIGNED TO AVOID MAJOR RE-CABLING, CONNECT AS-BUILT. NEW INSTALLATIONS WILL FOLLOW THE DESIGN MANUAL.

II. INNOVATIVE SWITCHGEAR'S PRODUCTS DO NOT CONTAIN ANY OIL OR SF6 GAS FOR THE ELECTRICAL ARC INTERRUPTION OR FOR COMPONENT INSULATION. INNOVATIVE SWITCHGEAR CONTAINS ONLY MECHANISMS, INSULATED BUS WORK AND DRY AIR. DO NOT REMOVE THE PRESSURE TEST PLUG ON THIS VESSEL. EACH UNIT HAS BEEN PRESSURE TESTED AND PERMANENTLY FACTORY SEALED. THE SWITCH TANK IS FILLED WITH THREE TO FIVE POUNDS OF DRY AIR TO KEEP THE STRUCTURAL INTEGRITY OF THE TANK AT SEA LEVEL.

III. THE USE OF FUSED ELBOWS WILL BE FOR THE ADDITION OF POTENTIAL TRANSFORMERS FOR SCADA APPLICATIONS AND LIMITED TO TWO FUSED ELBOW ONLY ONE PER SWITCH WAY POSITION. NO DEVIATION WILL BE GRANTED FOR MORE THAN TWO FUSED ELBOWS IN THE INNOVATIVE SWITCH CABINET. THE 30A FUSED ELBOW (S321680) AND 10 FEET/LENGTH FROM PT TO OPENING OF SUBSTRUCTURE OF #2 CABLE (S197600) WILL BE MADE IN HOUSE BY LINE CREW (OR BY KEARNY AS NECESSARY) TO INSTALL SCADA INSTALLATIONS.

IV. TAPPING THE BACK OF 600A TEES FOR 200A DISTRIBUTION WILL BE LIMITED TO SWITCH CHANGE OUTS WITH EXISTING 200A TAPS.

V. FOR NEW CONSTRUCTION AND CONVERSIONS THIS INNOVATE SWITCH SHOULD NOT BE USED TO TAP FEEDER CABLES. TAPS ON THE BACK OF 600A TEES IMPEDE GROUNDING AND LIMIT USE OF SWITCH POSITIONS DURING ROUTING SWITCHING PROCEDURES AND OUTAGE SITUATIONS. TAP FEEDER SEGMENTS BETWEEN SWITCH POSITIONS USING 600A TERMINATORS OR TAP THE SWITCH POSITION WITH DISTRIBUTION CABLE ONLY.

VI. ALL ISG MANUAL SWITCHES ARE "SCADA-READY (CAPABLE OF BEING RETROFITTED TO SCADA)" AND POTENTIALLY FAULT INTERRUPTING USING OTHER CONTROLLERS/RELAYS.

VII. ALL MANUAL SWITCHES CAN BE USED ON 12KV AND 4KV APPLICATIONS.

VIII. ISG MANUAL SWITCHES REFER TO MOTORIZED OPERATORS INSTALLED AND CAN BE OPERATED WITH THE LEVER VIA HOOKSTICK. ISG SCADA REFERS TO THE CONTROLLER WITH THE FAULT INTERRUPTING AND COMMUNICATIVE FEATURES TO INCLUDE MOTOR OPERATORS. ISG NON-SCADA REFERS TO MANUAL SWITCHES, BUT CAPABLE OF RETROFITTING WITH NON-COMMUNICATIVE RELAYS/CONTROLLERS.

IX. REGARDING THE 6 WAY ISG SWITCHGEAR; WAYS 1-5 ARE FAULT INTERRUPTING CAPABLE. WAY 6 WILL ONLY BE USED AS A SWITCH OR TIE POSITION.

(X) THIS ITEM IS EXEMPT.

XI. THE 3 AND 4 WAY SUBMERSIBLE SWITCHES CAN BE INSTALLED ON THEIR BACKS SO THAT THE BUSHINGS ARE POINTED VERTICALLY. THE STANDS AVAILABLE ARE OPTIONAL AND ALLOW FOR A HORIZONTALLY MOUNTED SWITCH/BUSHING CONFIGURATION TO BE USED AS NEEDED.

XII. FOR EASE OF OPERATION AND STATUS OF AN ISG SUBMERSIBLE SWITCH, THE PENDANT CONTROLLER IN A MANHOLE SHOULD BE INSTALLED NEAR THE TOP PORTION (ROOF) OF THE MANHOLE.

a. PREFERRED METHOD WILL BE ATTACHED TO THE BOTTOM SIDE OF THE TOP SECTION NEAR THE LID. THIS WILL ALLOW FOR EASY ACCESS TO THE PENDANT CONTROLLER WITHOUT REMOVING THE TOP SECTION AND IF NECESSARY, WAITING FOR FLOODED STRUCTURES TO BE PUMPED.

b. ALTERNATIVE METHOD WILL BE ATTACHED ON THE TOP SIDE OF THE MANHOLE, JUST OUTSIDE OF THE TOP SECTION PORTION. THIS WILL ALLOW FOR ANOTHER METHOD OF EASIER ACCESS TO THE PENDANT CONTROLLER WITHOUT WAITING FOR FLOODED STRUCTURES TO BE PUMPED.

XIII. RESTRICTIONS/LIMITATIONS

a. ALL SUBMERSIBLE SWITCHGEAR WILL BE LIMITED TO MANHOLES CURRENTLY.

b. VAULT MOUNTED SWITCHGEAR ARE LIMITED TO DRY TYPE VAULTS ONLY.

XIV. ALL SWITCH PAGES WITH PARENTHESIS "()" AROUND A NUMBER REFLECT THE QUANTITY OF THE IDENTIFIED EQUIPMENT FROM THE MANUFACTURER. THERE ARE ALSO INTERNAL "BILL OF MATERIALS" WITHIN SOME OF THE SPECIFIC SWITCH TYPES REFERENCING FROM THE MANUFACTURER.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## NOTES (CONT'D):

XV. FOR SUBMERSIBLE SWITCHES, DO NOT ASSEMBLE THE STAND TO THE SWITCH UNTIL AFTER INSTALLATION WITHIN THE SUBSTRUCTURE.

XVI. OLDER MANHOLES MAY NOT HAVE THE 4'-0" X 5'-0" OPENING THAT IS INTENDED FOR MOST SUBMERSIBLE APPLICATIONS (4 AND 5-WAY). PLEASE CONTACT EDE CONSTRUCTION STANDARDS ADMINISTRATORS TO DETERMINE MANHOLE TOP SECTION REPLACEMENT.

XVII. FOR SUBMERSIBLE SWITCHES WITHIN SUBSTRUCTURES (MANHOLES AND HANDHOLES), THE PENDANT CONTROLLER SHOULD BE MOUNTED NEAR THE OPENING OF THE SUBSTRUCTURE. LOCKS WILL NOT BE REQUIRED ON SUBMERSIBLE SWITCH POSITIONS SO THAT USE OF THE PENDANT CONTROLLER CAN BE DONE FOR SECTIONALIZING/ISOLATING CAPABILITIES.

## REFERENCE:

a. FOR CABLE IDENTIFICATION, SEE UG3202.

b. FOR ATTACHING STRUCTURE/EQUIPMENT IDENTIFICATION TAG, SEE UG3211.

c. FOR HIGH VOLTAGE DECAL, SEE UG3221.

d. FOR WIRE ENTRY PREVENTION, SEE UG3408.

e. FOR BARRIERS IF THE SWITCH IS SUBJECT TO VEHICULAR TRAFFIC, SEE UG3479.

f. FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482, AND UG3483.

g. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS, SEE UG3486, UG3487, AND UG3488.

h. FOR RETAINING WALLS, SEE UG3489.

i. FOR FAULT INDICATOR INSTALLATION, SEE UG4355.

j. FOR (PREFERRED 1) AND (ALTERNATE TRENCH GROUND WIRE), SEE UG4510.

k. FOR EQUIPMENT GROUNDING, SEE UG4520 AND UG4521.

l. FOR GROUNDING PREMOLDED CONNECTORS, SEE UG4525.

m. FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM, SEE UG4521.

n. FOR SCADA INSTALLATION, SEE UG4641.



© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 12/28/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | EPI | NTB | FRC | CZH | 01/31/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | DG | JS | CZH | 05/03/2018 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

| PAGE(S) | SUBJECT |
|---|---|
| 3702.1 | TRANSFORMER PREFIXES, VOLTAGE DESCRIPTIONS |
| 3702.2 | TRANSFORMER PREFIXES, PAD-MOUNTED, DEAD FRONT/SINGLE-PHASE |
| 3702.3 | TRANSFORMER PREFIXES, SUBSURFACE/SINGLE-PHASE |
| 3702.4 | STAINLESS STEEL TRANSFORMER PREFIXES, PAD-MOUNTED, DEAD FRONT/THREE-PHASE |
| 3702.5 | STAINLESS STEEL TRANSFORMER PREFIXES, PAD-MOUNTED, LIVE FRONT/THREE-PHASE |
| 3703 | DISTRIBUTION TRANSFORMER APPLICATIONS |
| 3704 | "BAY-O-NET" FUSE OPERATING INSTRUCTIONS FOR THREE-PHASE AND SINGLE-PHASE DEAD FRONT, PAD-MOUNTED TRANSFORMERS |
| 3706 | ALLOWABLE LOAD CURRENT SINGLE-PHASE AND THREE-PHASE COMMERCIAL TRANSFORMERS |
| 3706.1 | ALLOWABLE LOAD CURRENT SINGLE-PHASE AND THREE-PHASE RESIDENTIAL TRANSFORMERS |
| 3706.2 | TRANSFORMER LOADING GUIDE FOR THREE-PHASE STATIONS WITH SINGLE-PHASE TRANSFORMERS |
| 3708 | SINGLE-PHASE, TYPE "XD", 480V TO 120V, WALL MOUNTED TRANSFORMER INSTALLATION |
| 3709 | SINGLE-PHASE TYPE "N" 6930 TO 120V 1.5 KVA |
| 3711.1 & .2 | SINGLE-PHASE, 6930 VOLT, TYPE "SDS", LOW PROFILE PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3711.3 & .4 | SINGLE-PHASE, 6930 VOLT, TYPE "NTS" LOW PROFILE PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3712 | SINGLE-PHASE, 12KV, TYPE "HDS", "HTS" OR "HJS" DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3713 | 2 SINGLE-PHASE, TYPE "HDS" OR "HTS" DEAD FRONT, PAD-MOUNTED TRANSFORMERS FOR OPEN DELTA BANK INSTALLATION |
| 3714 | 3 SINGLE-PHASE, TYPE "HDS" OR "HTS", DEAD FRONT PAD-MOUNTED TRANSFORMERS FOR CLOSED DELTA BANK INSTALLATION |
| 3715 | TWO SINGLE-PHASE, Y TYPE SDS DEAD FRONT PAD-MOUNT TRANSFORMERS FOR OPEN DELTA BANK INSTALLATION<br>THREE SINGLE-PHASE, Y TYPE SDS DEAD FRONT PAD-MOUNT TRANSFORMERS FOR CLOSED DELTA BANK INSTALLATION |
| 3751 | THREE-PHASE 12KV, TYPE "HZS", "HBS", "PZS", "HMS", "HNS", OR "HKS" RADIAL/LOOP, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3752 | THREE-PHASE, 12KV, TYPE "HNS" RADIAL, DEAD FRONT PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3753 | THREE-PHASE STEP-DOWN TYPE "HPS", RADIAL DEAD FRONT PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3755 | THREE-PHASE STEP-DOWN, TYPE "HPB", RADIAL/LOOP, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3756 | THREE-PHASE 12KV, TYPE "HYS" RADIAL, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3757 | THREE-PHASE 12KV, TYPE 75KVA "HBSC" COMPACT RADIAL, DEAD FRONT, PAD MOUNTED TRANSFORMER INSTALLATION |
| 3760 | GROUND FAULT DETECTION TRANSFORMER (NGD) |
| 3770 | SINGLE-PHASE, 6930 VOLT, TYPE "NCS" PAD-MOUNTED TRANSFORMER INSTALLATION |
| 3771 | SINGLE-PHASE, 12000 VOLT, TYPE "HCS" PAD-MOUNTED TRANSFORMER INSTALLATION |

MAIN TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | ADDITION OF 3757 | - | KR | JS | MDJ | 03/31/2017 | F | EDITORIAL CHANGES | PEI | VMV | FRC | CZH | 08/27/2020 |
| B | ADDITION OF 3756 | - | KR | JS | MDJ | 03/13/2017 | E | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 |
| A | ORIGINAL ISSUE | - | JS | TR | MDJ | 06/10/2016 | D | ADDITION OF 3702.1 | - | KR | JS | MDJ | 10/27/2017 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRANSFORMERS
TABLE OF CONTENTS

UG3701.1

**SCOPE:** THIS STANDARD IDENTIFIES SINGLE-PHASE AND THREE-PHASE TRANSFORMERS BY PREFIX.

**ATTENTION:**

* DATA ON THIS PAGE WAS PREPARED TO AID IN UNDERSTANDING THE VOLTAGE RATINGS USED IN THE FOLLOWING "TRANSFORMER PREFIXES" STANDARDS PAGES.

**DEFINITIONS:**

**SINGLE PHASE AND THREE PHASE TRANSFORMERS HAVE HIGH VOLTAGE RATINGS AS FOLLOWS:**

- **4160GRDY/2400:** INDICATES A WINDING OF 2,400V SUITABLE FOR LINE-TO-LINE CONNECTION ON A 2,400V SYSTEM OR LINE-TO-NEUTRAL CONNECTION ON A 4,160V 4-WIRE WYE SYSTEM.
- **12000GRDY/6930:** INDICATES A WINDING OF 6,930V SUITABLE FOR LINE-TO-NEUTRAL CONNECTION ONLY ON A 12KV EFFECTIVELY GROUNDED SYSTEM.
- **2400:** INDICATES A WINDING OF 2,400V SUITABLE FOR LINE-TO-LINE CONNECTION ON A 2,400V DELTA SYSTEM.
- **4160:** INDICATES A WINDING OF 4,160V SUITABLE FOR A LINE-TO-LINE CONNECTION ON A 4,160V WYE SYSTEM.
- **12000:** INDICATES A WINDING OF 12KV SUITABLE FOR A LINE-TO-LINE CONNECTION ON A 12KV DELTA SYSTEM.

**SINGLE PHASE TRANSFORMERS HAVE LOW VOLTAGE RATINGS AS FOLLOWS:**

- **120/240:** INDICATES A SECONDARY WINDING SUITABLE FOR 240V SERIES OPERATION, THREE-WIRE OPERATION OR FOR 120V TWO-WIRE, MULTIPLE OPERATION.
- **480/240:** INDICATES A SECONDARY WINDING SUITABLE FOR 480V SERIES OPERATION, THREE-WIRE OPERATION, BUT NOT FOR 240V TWO-WIRE, MULTIPLE OPERATION.
- **240/120:** INDICATES A SECONDARY WINDING SUITABLE FOR 240V SERIES OPERATION OR THREE-WIRE OPERATION, BUT NOT FOR 120V TWO-WIRE, MULTIPLE OPERATION.

**THREE PHASE TRANSFORMERS HAVE LOW VOLTAGE RATINGS AS FOLLOWS:**

- **240/120:** INDICATES A SECONDARY WINDING SUITABLE FOR 240V SERIES OPERATION OR THREE-WIRE OPERATION, BUT NOT FOR 120V TWO-WIRE, MULTIPLE OPERATION.
- **208Y/120:** THIS INDICATES THE TRANSFORMER IS SUITABLE FOR FOUR-WIRE OPERATION ON 120/208Y VOLTS SYSTEM ONLY.
- **480Y/277:** THIS INDICATES THAT THE TRANSFORMER IS SUITABLE FOR FOUR-WIRE OPERATION ON A 277/480Y VOLT SYSTEM OR THREE-WIRE OPERATION ON A 480V SYSTEM.
- **4160Y/2400:** THIS INDICATES THAT THE TRANSFORMER IS SUITABLE FOR FOUR-WIRE OPERATION ON A 2,400/4,160Y VOLT SYSTEM OR THREE-WIRE OPERATION ON A 4,160V SYSTEM.
- **12470GRDY/6930:** THIS INDICATES THAT THE TRANSFORMER IS SUITABLE FOR FOUR WIRE OPERATION ON A 7,200/ 12,470Y VOLT SYSTEM OR THREE-WIRE OPERATION ON A 12.47KVSYSTEM.
- **480:** THIS INDICATES THAT THE TRANSFORMER IS SUITABLE FOR THREE-WIRE DELTA OPERATION AT ITS RATED VOLTAGE.
- **240X480:** INDICATES A WINDING SUITABLE FOR THREE-WIRE SERIES OPERATION AT 480V DELTA OR FOR THREE-WIRE PARALLEL OPERATION AT 240V DELTA BUT NOT FOR BOTH VOLTAGES SIMULTANEOUSLY.
- **2400/4160Y/2400:** INDICATES A WINDING SUITABLE FOR THREE-WIRE DELTA OPERATION AT 2,400V OR FOUR-WIRE OPERATION ON A 4,160V WYE SYSTEM WITH FULLY INSULATED NEUTRAL AVAILABLE.
- **2400/4160GRDY/2400:** INDICATES A WINDING HAVING REDUCED INSULATION FOR WYE CONNECTION ON A 4,160V SYSTEM WITH THE TRANSFORMER NEUTRAL GROUNDED, OR FOR DELTA CONNECTIONS ON A 2,400V SYSTEM.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 10/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | PS | JS | MDJ | 01/25/2017 | E | EDITORIAL CHANGES | EDM | RSL | GLW | CZH | 08/24/2021 |
| A | ORIGINAL ISSUE | - | - | PEA | ROJ | 01/01/1986 | D | EDITORIAL CHANGES | - | KR | JS | MDJ | 01/25/2018 |

**SCOPE:** THIS STANDARD IDENTIFIES PREFIXES FOR SINGLE-PHASE, PAD MOUNTED DEADFRONT AND SUBSURFACE TRANSFORMERS.

## TABLE 1

**TRANSFORMER PREFIXES**

| PREFIX | VOLTAGE | | DESCRIPTION | KVA | TAPS | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| | PRIMARY | SECONDARY | | | | | |
| XD | 240/480 | 120/240 | SINGLE-PHASE SECONDARY DRY TYPE - WALL MOUNTED | 2 | -- | S757888 (F) | XD-002 |
| | | | | 3 | -- | S757920 (F) | XD-003 |
| WDS | 2400 DELTA Δ | 240/120 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (b) | 25 | (A) | S755210 | WDS-25 |
| | | | | 50 | | S755212 | WDS-50 |
| | | | | 75 | | S755214 | WDS-75 |
| SDS (C) | 4160 GRDY/2400 X 12000 GRDY/6930 | 240/120 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (D)(b) | 25 | -- | S761520 | SDS-25 |
| | | | | 50 | -- | S761522 | SDS-50 |
| | | | | 75 | -- | S761524 | SDS-75 |
| N | 12000 GRDY/6930 | 120 | SINGLE-PHASE SECONDARY DRY TYPE - WALL MOUNTED | 1.5 | -- | S757880 (F) | N-1.5 |
| NCS (C) | 12000 GRDY/6930 | 240/120 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (b) | 25 | | S750312 | NCS-25 |
| | | | | 50 | | S750350 | NCS-50 |
| | | | | 100 | | S750352 | NCS100 |
| NTS (C) | 12000 GRDY/6930 | 240/120 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (b) | 25 | (A) | S764230 | NTS-25 |
| | | | | 50 | | S764232 | NTS-50 |
| | | | | 75 | | S764234 | NTS-75 |
| | | | | 100 | | S764236 | NTS100 |
| NGD | 12000 GRDY/6930 | 0 | CURRENT LIMITING | 1.0 | -- | S758302 (F) | NGD-10 |
| HCS | 12000 | 240/120 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (b) | 25 | | S751300 | HCS-25 |
| | | | | 50 | | S751302 | HCS-50 |
| | | | | 100 | | S751304 | HCS100 |
| | | | | 167 | | S751306 | HCS167 |
| HTS (C) | 12000 | 240/120 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (b) | 25 | (A) | S765106 | HTS25 |
| | | | | 50 | | S761108 | HTS50 |
| | | | | 75 | | S765108 | HTS75 |
| | | | | 100 | | S765110 | HTS100 |
| | | | | 167 | | S761110 | HTS167 |
| | | | | 250 | | S765104 | HTS250 |
| HJS | 12000 | 480/240 | BAY-O-NET FUSE ASSEMBLY WITH ISOLATION LINK STAINLESS STEEL (b) | 25 | -- | S760262 | HJS-25 |
| | | | | 50 | -- | S760264 | HJS-50 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 10/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | PS | JS | MDJ | 01/25/2017 | E | EDITORIAL CHANGES | EDM | RSL | GLW | CZH | 08/24/2021 |
| A | ORIGINAL ISSUE | - | - | PEA | ROJ | 01/01/1986 | D | EDITORIAL CHANGES | - | KR | JS | MDJ | 01/25/2018 |

## ATTENTION:

* DEVIATION REQUEST IS REQUIRED FOR HST INSTALLATIONS. (C)

### TABLE 2

| SINGLE-PHASE SUBSURFACE | | | | | | | |
|---|---|---|---|---|---|---|---|
| PREFIX | VOLTAGE | | DESCRIPTION | KVA | TAPS | STOCK NUMBER | DESIGN UNITS |
| | PRIMARY | SECONDARY | | | | | |
| HST (B)(E) | 12000 | 208Y/120<br>120/240 | CURRENT-LIMITING FUSES OR SUBMERSIBLE BAY-O-NET FUSE W/ ISOLATION LINK STAINLESS STEEL | 25 | (A) | S764213 | HST-25 |
| | | | | 50 | | S764215 | HST-50 |
| | | | | 100 | | S764219 | HST100 |

## INSTALLATION:

(A) TWO 2 1/2 PERCENT TAPS ABOVE AND BELOW.

(B) THE HST TRANSFORMERS COME WITH FOUR SECONDARY TERMINALS (WIRES) WHICH ALLOW EXTERNAL WIRING FOR 240/120 OR 208Y/120V.

(C) HTS, HJS, HCS, NCS, WDS SINGLE-PHASE TRANSFORMERS ARE FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING PLUGS OR FEED-THRU INSERTS (SEE UG3712, UG3713, UG3751 AND UG3755). BUSHINGS PLUGS OR FEED-THRU INSERTS ARE NOT SUPPLIED WITH TRANSFORMER. NTS IS SUPPLIED WITH ONE INSERT PRE-INSTALLED, AND SDS IS SUPPLIED WITH TWO INSERTS PRE-INSTALLED.

(D) BAY-O-NET FUSES MUST BE RESIZED WHEN TRANSFORMER IS CUT FROM 4 TO 12KV.

(E) REQUIRES DEVIATION.

(F) SPECIAL ORDER (MAY REQUIRE 20 WEEKS LEAD TIME TO RECEIVE ITEMS).

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. FOR SINGLE AND THREE-PHASE POLE MOUNTED, STREETLIGHT AND SUBSTATION TRANSFORMERS, SEE OVERHEAD STANDARDS BOOK.

b. FOR FUSING, SEE UG4311, UG4312, UG4313, AND UG4314.

(C) FOR DEVIATION REQUEST FORM AND PROCEDURE, SEE UG3005.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 10/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | PS | JS | MDJ | 01/25/2017 | E | EDITORIAL CHANGES | EDM | RSL | GLW | CZH | 08/24/2021 |
| A | ORIGINAL ISSUE | - | - | PEA | ROJ | 01/01/1986 | D | EDITORIAL CHANGES | - | KR | JS | MDJ | 01/25/2018 |

**SCOPE:** THIS STANDARD IDENTIFIES TRANSFORMER PREFIXES FOR THREE-PHASE, PAD MOUNTED DEADFRONT AND PAD MOUNTED LIVEFRONT.

## TABLE 1

**THREE-PHASE PAD MOUNTED STAINLESS STEEL DEAD FRONT**

| PREFIX | VOLTAGE | | DESCRIPTION | | KVA | TAPS | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| | PRIMARY | SECONDARY | | | | | | |
| PZS (C) | 4160X12000 | 208Y/120 THREE-PHASE 4 WIRE | RADIAL/LOOP PROTECTIVE LINKS, BAY-O-NET FUSES (D)(b) | D.E.W.L. | 75 | -- | S761347 | PZS-75 |
| | | | | | 150 | -- | S761300 | PZS150 |
| | | | | FAULT SENSING | 300 | -- | S765096 | PZS300 |
| | | | | | 500 | -- | S761332 (F) | PZS500 |
| PXS (C) | 4160X12000 | 240x480 THREE-PHASE 3 WIRE | D.E.W.L. BAY-O-NET FUSES AND PROTECTIVE LINKS, RADIAL/LOOP (D)(b)(II) | | 75 | -- | S764252 | PXS-75 |
| | | | | | 225 | -- | S764260 | PXS225 |
| HBSC | 12000 | 208Y/120 THREE-PHASE 4 WIRE | RADIAL ONLY, COMPACT, BAY-O-NET FUSES | | 75 | A | S765102 | HBSC75 |
| HBS (C) | | | D.E.W.L. BAY-O-NET FUSES AND PROTECTIVE LINKS, RADIAL/LOOP (b) | | 75 | | S761360 | HBS-75 |
| | | | | | 150 | | S761362 | HBS150 |
| | | | | | 300 | | S761320 | HBS300 |
| | | | | | 500 | | S761326 | HBS500 |
| | | | | | 750 | | S761334 | HBS750 |
| | | | | | 1,000 | | S761282 | HBS1.0 |
| | | | | | 1,500 | | S761288 | HBS1.5 |
| HKS (C) | 12000 | 240/120 THREE-PHASE 4 WIRE | D.E.W.L. BAY-O-NET FUSES AND PROTECTIVE LINKS, RADIAL/LOOP (b) | | 75 | -- | S761340 | HKS-75 |
| | | | | | 225 | -- | S761306 | HKS225 |
| HNS (C) | 12000 | 480Y/277 THREE-PHASE 3 OR 4 WIRE | RADIAL/LOOP PROTECTIVE LINKS, BAY-O-NET FUSES | D.E.W.L. | 150 | A | S761354 | HNS150 |
| | | | | | 300 | | S761356 | HNS300 |
| | | | | | 500 | | S761328 | HNS500 |
| | | | | FAULT SENSING | 750 | | S761336 | HNS750 |
| | | | | | 1,000 | | S761284 | HNS1.0 |
| | | | (b) | HIGH AMPERE | 1,500 | | S761290 | HNS1.5 |
| | | | RADIAL/LOOP PROTECTIVE LINKS, HIGH AMPERE BAY-O-NET FUSES | | 2,000 | | S761302 | HNS2.0 |
| | | | | | 2,500 | | S761314 | HNS2.5 |
| HPS (C) | 12000 | 2400/4160Y/ 2400 OR 2400/4160GRDY/ 2400 3 OR 4 WIRE | RADIAL/LOOP PROTECTIVE LINKS BAY-O-NET FUSES (b) | D.E.W.L. | 225 | | S761310 | HPS225 |
| | | | | | 500 | | S761330 | HPS500 |
| | | | | FAULT SENSING | 750 | | S761338 | HPS750 |
| | | | | | 1,000 | | S761286 | HPS1.0 |
| | | | | HIGH AMPERE | 1,500 | | S761292 | HPS1.5 |
| | | | | | 2,000 | | S761304 | HPS2.0 |
| | | | | | 2,500 | | S761316 | HPS2.5 |
| HHS | 12000GRDY/ 6930 | 12470GRDY/7200 | THREE-PHASE AUTO TRANSFORMER, RADIAL (BOOSTER) 600A DEADBREAK PRIMARY AND SECONDARY BUSHINGS | | 3,750 | -- | S761324 | HS3750 |
| HYS (C)(III) | 12000GRDY/ 6930 | 480 THREE-PHASE 3 WIRE | BAY-O-NET FUSES AND CL FUSES, RADIAL ONLY (b) | | 300 | A | S765130 (E) | HYS30 |
| | | | | | 1,000 | | S765132 (E) | HYS100 |
| | | | | | 2,000 | | S765134 (E) | HYS200 |
| | | | | | 3,000 | | S765120 (E) | HYS300 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 10/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | PS | JS | MDJ | 01/25/2017 | E | EDITORIAL CHANGES | EDM | RSL | GLW | CZH | 08/24/2021 |
| A | ORIGINAL ISSUE | - | - | PEA | ROJ | 01/01/1986 | D | EDITORIAL CHANGES | - | KR | JS | MDJ | 01/25/2018 |

## TABLE 2

| THREE-PHASE PAD MOUNTED STAINLESS STEEL - LIVEFRONT | | | | | | | |
|---|---|---|---|---|---|---|---|
| PREFIX | VOLTAGE | | DESCRIPTION | KVA | TAPS | STOCK NUMBER | DESIGN UNITS |
| | PRIMARY | SECONDARY | | | | | |
| HLS (B) | 12000 | 480Y/277 THREE-PHASE 3 OR 4 WIRE | EXTERNALLY FUSED | 3,000 | (A) | S761318 | HLS3.0 |

## INSTALLATION:

(A) TWO 2 1/2 PERCENT TAPS ABOVE AND BELOW.

(B) OLDER STYLE TRANSFORMERS MAY HAVE BOTH UPPER AND LOWER PLATES NEXT TO THE FUSES FOR THE PURPOSE OF TERMINATING CABLES. CABLES SHOULD NOT BE TERMINATED ON THE LOWER PLATES. LOWER PLATES HAVE BEEN REMOVED ON NEWER STYLE TRANSFORMERS.





**FIGURE 1**
XFMRS CONNECTED WITH LOOP FEED
SM-4 FUSE IS FOR TRANSFORMER FUSING ONLY AND (B) NOT FOR "LOOP" LOAD

(C) PZS, PXS, HBS, HKS, HNS, HPS, HYS THREE-PHASE TRANSFORMERS ARE FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING PLUGS OR FEED-THRU INSERTS (SEE STANDARDS UG3712, UG3713, UG3751, UG3755, AND UG3756). BUSHING PLUGS OR FEED-THRU INSERTS ARE NOT SUPPLIED WITH TRANSFORMER.

(D) BAY-O-NET FUSES MUST BE RESIZED WHEN TRANSFORMER IS CUT FROM 4 TO 12KV.

(E) SPECIAL ORDER (MAY REQUIRE 20 WEEKS LEAD TIME TO RECEIVE ITEMS).

(F) REQUIRES DEVIATION.

**BILL OF MATERIALS:** NONE

## NOTES:

I. D.E.W.L. IS DEFINED AS "DUAL ELEMENT WEAKLINK".

(II) THE PXS PAD MOUNTED TRANSFORMER IS A 3-PHASE, 480V, THREE WIRE DELTA SERVICE APPLICATION. THIS WILL COVER CONVERSIONS OF OLDER THREE WIRE, 480V CLOSED DELTA SERVICES TO PAD MOUNTED FACILITIES. IF THE CUSTOMER HAS A CORNER GROUND, THEY MUST COORDINATE WITH SDG&E TO IDENTIFY CORRECT CORNER GROUND APPLICATION.

(III) TO BE USED ONLY FOR BATTERY PROJECTS WHEN HO BUSHING IS REQUIRED.

## REFERENCE:

a. FOR SINGLE AND THREE-PHASE POLE MOUNTED, STREETLIGHT AND SUBSTATION TRANSFORMERS, SEE OVERHEAD STANDARDS BOOK.

b. FOR FUSING, SEE UG4311, UG4312, UG4313, AND UG4314.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 10/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | PS | JS | MDJ | 01/25/2017 | E | EDITORIAL CHANGES | EDM | RSL | GLW | CZH | 08/24/2021 |
| A | ORIGINAL ISSUE | - | - | PEA | ROJ | 01/01/1986 | D | EDITORIAL CHANGES | - | KR | JS | MDJ | 01/25/2018 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD IS A GUIDE FOR SELECTING TRANSFORMER(S), BY PREFIX, FOR REPLACEMENT OF EXISTING UNITS IN FIELD, AND DETERMINING THOSE THAT ARE OBSOLETE.

## TABLE 1

| SINGLE-PHASE INSTALLATIONS (PADMOUNT) | | | | |
|---|---|---|---|---|
| VOLTAGE | | EXISTING FIELD UNITS | REPLACEMENT UNITS (C) | NOT TO BE USED OR REORDERED |
| PRIMARY | SECONDARY | | | |
| 240/480 | 120/240 | XD | XD | -- |
| 2,400 | 240/120 | SDD, SDS, SID, WDD, WEP, WEQ | SDS | SDD, SID, WDD, WEQ |
| 6,930 | 240/120 | NDD, NDL, NDP, NDS, NEP, NSD, NSL, SDD, SDS, SID, WDD | NTS, NCS (B) | NDD, NDL, NDP, NEP, NSD, NSL, SDD, SID, WDD, NDS |
| 6,930 W/SECONDARY TAPS | 240/120 W/SECONDARY TAPS | NEP, NTD, NTP, NTQ, NTS | NTS, NCS (B) | NTD, NTP, NTQ, NEP |
| 12,000 | 240/120 | HDD, HDL, HDS, HEP, HSL, HP, HQ | HTS, HCS | HDD, HDL, HP, HSL, HQ, HEP |
| 12,000 W/SECONDARY TAPS | 240/120 W/SECONDARY TAPS | HEP, HEQ, HP, HTD, HTL, HTS | HTS, HCS | HEQ, HP, HTD, HTL, HEP |
| 12,000 | 480/240 | HJD, HJL, HJP, HJS | HJS | HJD, HJL, HJP |
| **SINGLE-PHASE INSTALLATIONS (SUBSURFACE)** | | | | |
| 2,400 | 240/120 | WS, WSV, WUS | WUS | WSV, WS |
| 6,930 | 240/120 | NES | NES (B) | -- |
| 12,000 | 120/240 | HSS | HST (E) | HSS |
| 12,000 W/SECONDARY TAPS | 120/240 W/SECONDARY TAPS | HST | HST (E) | -- |
| **THREE-PHASE INSTALLATIONS (PADMOUNT)** | | | | |
| 4,160 | 208Y/120 | PZB, PZR, PZS, WGP, WZP, WZR | PZS | PZB, PZR, WGP, WZP, WZR |
| 4,160 | 240X480 (A) | WXP, PXB | PXS | WXP, PXB |
| 12,000 | 208Y/120 | HAB, HAL, HAP, HAQ, HBP, HBS, HGP, HHP, HZB, HZL, HZP, HZQ, HZR, HZS | HBS | HAB, HAL, HAP, HAQ, HBP, HGP, HHP, HZB, HZL, HZP, HZQ, HZR, HZS |
| 12,000 | 240/120 | HKB, HKR, HKS | HKS | HKB, HKR |
| | | 1Ø BANK: HDD, HDL, HDS, HEP, HSL, HP, HQ, HTD | 1Ø BANK: HTS | 1Ø BANK: HDD, HDL, HSL, HP, HQ, HTD, HDS, HEP |
| 12,000 | 480/240 | HDP, HFP | 1Ø BANK: HJS | HDP, HFP |
| 12,000 | 240X480 (A) | HLP, HXP WIRED 240V | HKS 240/120 | HLP, HXP |
| | | HLP, HXP WIRED 480V | HNS 480/277 | HLP, HXP, HMS |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | AW | JS | CZH | 07/03/2018 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JS | MDJ | 09/28/2017 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JS | TR | MDJ | 05/23/2016 | D | INFORMATION MOVED TO FMO | EDM | EJA | GLW | CZH | 06/14/2021 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DISTRIBUTION TRANSFORMER APPLICATIONS

UG3703.1

## TABLE 1 (CONT'D)

| THREE-PHASE INSTALLATIONS (PADMOUNT) (CONT'D) | | | | |
|---|---|---|---|---|
| VOLTAGE | | EXISTING FIELD UNITS | REPLACEMENT UNITS | NOT TO BE USED OR REORDERED |
| PRIMARY | SECONDARY | | | |
| 12,000 | 480Y/277 | HMB, HML, HMP, HMS, HNB, HNL, HNR, HNS, HUP | HNS | HMB, HML, HMP, HMS, HNB, HNL, HNR, HUP |
| 12,000 | 4,160Y/2,400 | HOP, HPB, HPR, HPP, HPS, HSV | HPS | HOP, HPB, HPP, HPR, HSV |
| 12,000 | 12,470Y/7,200 | HHR, HSV, HHS | HHS (D) | HHR, HSV |
| **THREE-PHASE INSTALLATIONS (SUBSURFACE)** | | | | |
| 12,000 | 208Y/120 | HAS | HAS (D) | 1Ø BANK: HSS |
| | | 1Ø BANK: HSS, HST | 1Ø BANK: HST (E) | |
| 12,000 | 240/120 | 1Ø BANK: HSS, HST | 1Ø BANK: HST (E) | 1Ø BANK: HSS |

## INSTALLATION:

(A) 240X480 INDICATES A WINDING SUITABLE FOR THREE-WIRE SERIES OPERATION AT 480V DELTA OR FOR THREE-WIRE PARALLEL OPERATION AT 240V DELTA BUT NOT FOR BOTH VOLTAGES SIMULTANEOUSLY.

(B) 6,930V 'N' TYPE SINGLE-PHASE TRANSFORMERS, WITH SECONDARY TAPS, CAN BE USED TO REPLACE 7,200V 'Y' TYPE SINGLE-PHASE TRANSFORMERS ON 7,200V SYSTEMS. WE STILL HAVE A FEW 7,200V BRANCH LINES IN THE SYSTEM. 7,200V SYSTEMS CAN BE IDENTIFIED BY THE UPSTREAM BOOSTER STATION. BOOSTER STATIONS ARE CODED WITH A 'B' SUFFIX, I.E. 275-472B. 'Y' TYPE 7,200V TRANSFORMERS (YEP, YDP, ETC.) WERE THE PREFERRED TRANSFORMER FOR 7,200V SYSTEMS. HOWEVER, WE NO LONGER STOCK, OR INSTALL, 'Y' TYPE SINGLE-PHASE TRANSFORMERS. WHEN REPLACING SINGLE-PHASE 'Y' TRANSFORMERS FIRST DETERMINE IF YOU'RE ON A 7,200V SYSTEM OR A 6,930V SYSTEM. IF YOU'RE ON A 7,200V SYSTEM, INSTALL AN 'N' TYPE TRANSFORMER WITH SECONDARY TAPS (NTS, NCS). THE FIELD CREW CAN TAP DOWN THE SECONDARY VOLTAGE, AS NEEDED, TO COMPENSATE FOR ANY SECONDARY VOLTAGE BOOST. IF YOU'RE ON A 6,930V SYSTEM (NO BOOSTER STATION) REPLACE A 'Y' TRANSFORMER WITH AN 'N' TYPE TRANSFORMER (NTS) - SECONDARY TAPS ARE NOT NEEDED.

(C) WHEN REPLACING LIVEFRONT TRANSFORMERS EVERY EFFORT SHOULD BE MADE TO UPGRADE TO DEADFRONT. EACH SITUATION SHOULD BE EVALUATED INDEPENDENTLY. WHEN IN DOUBT CONTACT YOUR LOCAL ELECTRIC CONSTRUCTION SUPERVISOR (ECS) IN THE DISTRICT. THE ECS WILL LET YOU KNOW IF CONVERTING IS FEASIBLE AND TELL YOU PRECISELY WHAT ADDITIONAL AND/OR SPECIAL MATERIAL WILL BE NEEDED.

(D) SPECIAL ORDER ITEM: CONTACT STANDARDS FOR INFORMATION AND LEAD TIMES. TRANSFORMER TABLES FOR THESE UNITS CAN BE FOUND IN THE UG FIELD MAINTENANCE ONLY MANUAL.

(E) DEVIATION REQUIRED TO INSTALL THIS TRANSFORMER.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | AW | JS | CZH | 07/03/2018 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JS | MDJ | 09/28/2017 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JS | TR | MDJ | 05/23/2016 | D | INFORMATION MOVED TO FMO | EDM | EJA | GLW | CZH | 06/14/2021 |


PURPOSE:

OVERLOAD AND FAULT PROTECTION FOR THREE-PHASE AND SINGLE-PHASE DEADFRONT PAD-MOUNTED TRANSFORMERS.

FOR USE WITH:


4KV AND 12KV - THREE-PHASE AND SINGLE-PHASE RADIAL OR LOOP FEED DEADFRONT PAD-MOUNTED TRANSFORMERS THROUGH 2500 KVA.

FOR BAYONET FUSE OPERATION: SEE ELECTRIC STANDARD PRACTICE 213 AND 214.



**NOTE:** OPERATE VENT BEFORE OPERATING BAYONET FUSES.

1. ATTACH UNIVERSAL HOT STICK TOOL, OR HOOK STICK TO FUSE HANDLE EYE - STAND TO ONE SIDE - UNLOCK HANDLE.



2. PUSH DOWN AND ROTATE THE HANDLE 90° IN THE TUBE. DURING THIS PROCEDURE INTERNAL TANK PRESSURE ESCAPES AND INSIDE AND OUTSIDE PRESSURES ARE EQUALIZED. THE 90° ROTATION OF THE FUSE HOLDER BREAKS ANY ADHESION BETWEEN THE SEAL GASKET AND THE OUTER TUBE ASSEMBLY.

TABLE OF CONTENTS

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | EDITORIAL CHANGES | AW | JS | CZH | 7/3/2018 | E | | | | | |
| A | REVISION | | | TR/JW | 7/8/2004 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

"BAY-O-NET" FUSE OPERATING INSTRUCTIONS FOR THREE-PHASE AND SINGLE-PHASE DEADFRONT PADMOUNTED TRANSFORMERS

UG3704.1

DE-ENERGIZED PADMOUNTED TRANSFORMERS:


CONTINUED FROM PAGE 3704.01



3. PULL OUT THE FUSE HOLDER THREE INCHES AND STOP! WAIT A FEW SECONDS FOR THE OIL TO DRAIN INTO THE TANK. THE INNER FUSE HOLDER ASSEMBLY CAN NOW BE REMOVED WITHOUT DRIPPING EXCESS OIL BY KEEPING THE FUSE HOLDER RUBBING AGAINST THE TOP OF THE CUTOUT, AS SHOWN, AND EXTRACTING IT VERY SLOWLY. THE TOTAL LENGTH OF THE INNER FUSE HOLDER ASSEMBLY, INCLUDING FUSE CARTRIDGE, IS FOURTEEN INCHES.

BAY-O-NET FUSE REPLACEMENT (ALL STEPS MUST BE DONE IN THE SEQUENCE DESCRIBED BELOW)

1. UNSCREW FUSE CARTRIDGE FROM INNER FUSE HOLDER.
2. UNSCREW FUSE CARTRIDGE CAP.
3. REMOVE FUSE LINK (IT MAY BE NECESSARY TO STRAIGHTEN THE TULIP TIP END THAT WAS BENT BY THE FUSE CARTRIDGE CAP BEFORE FUSE LINK CAN BE REMOVED FROM FUSE CARTRIDGE).
4. INSPECT FUSE CARTRIDGE BORE TO MAKE SURE IT IS CLEAR.
5. INSERT NEW FUSE LINK INTO CARTRIDGE FROM EITHER END.
6. TIGHTEN FUSE CARTRIDGE ONTO INNER FUSE HOLDER WITH TULIP TIP AT OPPOSITE END OF INNER FUSE HOLDER.
7. SCREW CARTRIDGE CAP INTO OTHER END OF CARTRIDGE (IMPORTANT THAT THIS STEP BE LAST).
8. WHEN THE INNER FUSE HOLDER ASSEMBLY IS INSERTED AS FAR AS POSSIBLE, PUSH DOWN, AND ROTATE THE LOCKING HANDLE, HOOKING IT OVER THE SHOULDER OF THE OUTER TUBE ASSEMBLY. WHEN HANDLE IS IN LOCKED POSITION, MAKE SURE THE STAINLESS STEEL COVER WASHER IS SEATED AGAINST THE SHOULDER OF THE OUTER TUBE ASSEMBLY.




SEE STANDARDS PAGE 4311.5 FOR FUSE SIZE AND STOCK NUMBER.

REPLACEMENT FUSE HOLDER, FUSE CARTRIDGE AND FUSE CARTRIDGE CAP

| STOCK NUMBER |
|---|
| 412685 |

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | EDITORIAL CHANGES | AW | JS | CZH | 7/3/2018 | E | | | | | |
| A | REVISION | | | TR/JW | 7/8/2004 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

"BAY-O-NET" FUSE OPERATING INSTRUCTIONS FOR THREE-PHASE AND SINGLE-PHASE DEADFRONT PADMOUNTED TRANSFORMERS

UG3704.2

TABLE OF CONTENTS

HIGH AMPERE BAY-O-NET FUSES




| STOCK NUMBER | |
|---|---|
| 100 AMP | 366140 |
| 125 AMP | 366142 |

HIGH AMPERE BAY-O-NET FUSE CARTRIDGE REPLACEMENT PROCEDURE FOLLOW THE STEPS IN THE SEQUENCE LISTED BELOW:

1. UNSCREW THE FUSE CARTRIDGE FROM INNER FUSE HOLDER.
2. DISCARD THE FUSE CARTRIDGE. DO NOT ATTEMPT TO REPLACE THE FUSE IN THE CARTRIDGE.
3. TIGHTEN A NEW FUSE CARTRIDGE ONTO THE INNER FUSE HOLDER.
4. PLACE IT INTO THE "BAY-O-NET" OUTER TUBE ASSEMBLY AND SLAM HOME.
5. WHEN THE INNER FUSE HOLDER ASSEMBLY IS INSERTED AS FAR AS POSSIBLE, PUSH DOWN, AND ROTATE THE LOCKING HANDLE, HOOKING IT OVER THE SHOULDER OF THE OUTER TUBE ASSEMBLY. WHEN HANDLE IS IN LOCKED POSITION, MAKE SURE THE STAINLESS STEEL COVER WASHER IS SEATED AGAINST THE SHOULDER OF THE OUTER TUBE ASSEMBLY.

TABLE OF CONTENTS

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | EDITORIAL CHANGES | AW | JS | CZH | 7/3/2018 | E | | | | | |
| A | REVISION | | | TR/JW | 7/8/2004 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

"BAY-O-NET" FUSE OPERATING INSTRUCTIONS FOR THREE-PHASE AND SINGLE-PHASE DEADFRONT PADMOUNTED TRANSFORMERS

UG3704.3

**SCOPE:** THIS STANDARD LISTS THE ALLOWABLE LOAD CURRENT IN AMPERES FOR SINGLE-PHASE AND THREE-PHASE COMMERCIAL TRANSFORMERS. IF TRANSFORMER LOAD EXCEEDS VALUE SHOWN IN TABLE, REPLACE THE TRANSFORMER.

## SINGLE-PHASE TRANSFORMERS

| KVA RATING | COMMERCIAL ALLOWABLE LOAD CURRENT (IN AMPERES) AT THE LINE-TO-LINE VOLTAGES LISTED BELOW | | | |
|---|---|---|---|---|
| | 240V | 480V | 2400V | 4160V |
| 10 | 61 | 31 | 6 | 4 |
| 15 | 92 | 46 | 9 | 5 |
| 25 | 153 | 77 | 15 | 9 |
| 37.5 | 230 | 115 | 23 | 13 |
| 50 | 306 | 153 | 31 | 18 |
| 75 | 459 | 230 | 46 | 27 |
| 100 | 613 | 306 | 61 | 35 |
| 167 | 1,023 | 511 | 102 | 59 |

## THREE-PHASE TRANSFORMERS

| KVA RATING | COMMERCIAL ALLOWABLE LOAD CURRENT (IN AMPERES) AT THE LINE-TO-LINE VOLTAGES LISTED BELOW | | | | |
|---|---|---|---|---|---|
| | 208V | 240V | 480V | 2400V | 4160V |
| 45 | 184 | 159 | 80 | 16 | 9 |
| 75 | 306 | 265 | 133 | 27 | 15 |
| 112.5 | 459 | 398 | 199 | 40 | 23 |
| 150 | 612 | 530 | 265 | 53 | 35 |
| 225 | 918 | 796 | 398 | 80 | 52 |
| 300 | 1,224 | 1,061 | 530 | 106 | 61 |
| 500 | 2,040 | 1,768 | 884 | 177 | 102 |
| 750 | 3,060 | 2,652 | 1,326 | 265 | 153 |
| 1,000 | 4,080 | 3,536 | 1,768 | 354 | 204 |
| 1,500 | 6,120 | 5,304 | 2,652 | 530 | 306 |
| 2,000 | 8,161 | 7,073 | 3,536 | 707 | 466 |
| 2,500 | 10,201 | 8,841 | 4,420 | 884 | 510 |
| 3,000 | 12,241 | 10,609 | 6,062 | 1,061 | 612 |

TABLE OF CONTENTS

**NOTES:**

I. LOAD VALUES IN THE TABLE ABOVE DO NOT CONSIDER VOLTAGE PROBLEMS THAT MAY OCCUR AT THOSE VALUES. VOLTAGE PROBLEMS SHOULD BE REFERRED TO THE C & O ENGINEER.

LOAD VALUES BASED ON ANSI/IEEE C57.91-1981

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | EDITORIAL CHANGES | AW | JS | CZH | 7/3/2018 | E | | | | | |
| A | REVISION | | | | 1/1/1996 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

ALLOWABLE LOAD CURRENT SINGLE-PHASE AND THREE-PHASE COMMERCIAL TRANSFORMERS

UG3706.1

**SCOPE:** THIS STANDARD PROVIDES THE DIVISION OF SINGLE-PHASE LOAD CURRENT OF A THREE-PHASE STATION WHEN IT IS COMPOSED OF SINGLE-PHASE PAD-MOUNT TRANSFORMERS.

## A: CLOSED-DELTA BANKS

| SINGLE-PHASE LOAD CURRENT IN EACH TRANSFORMER OF AN UG DELTA-DELTA BANK | | | |
|---|---|---|---|
| SIZE OF TRANSFORMERS IN BANK (KVA) | | % OF SINGLE-PHASE CURRENT | |
| 1 | 2&3 | 1 | 2&3 |
| 15 | 15 | 67 | 33 |
| 25 | 15 | 78 | 22 |
| 50 | 15 | 87 | 13 |
| 75 | 15 | 91 | 9 |
| 100 | 15 | 93 | 7 |
| 25 | 25 | 67 | 33 |
| 50 | 25 | 79 | 21 |
| 75 | 25 | 86 | 14 |
| 100 | 25 | 88 | 12 |
| 50 | 50 | 67 | 33 |
| 75 | 50 | 76 | 24 |
| 100 | 50 | 79 | 21 |
| 75 | 75 | 67 | 33 |
| 100 | 75 | 71 | 29 |
| 100 | 100 | 67 | 33 |

## B: OPEN-DELTA BANKS

SINCE BOTH TRANSFORMERS CARRY THE THREE-PHASE LOAD, AND ONE CARRIES THE SINGLE-PHASE LOAD IN ADDITION, THE LATTER TRANSFORMER MUST BE THE LARGER UNIT. IT MUST CARRY THE VECTORIAL SUM OF THE SINGLE-PHASE LOAD PLUS 58 PERCENT OF THE THREE-PHASE LOAD. FOR EXAMPLE, IF IT IS DESIRED TO CARRY A SINGLE-PHASE LOAD OF 30 KVA AND A THREE-PHASE LOAD OF 12 KVA, WITH THE SAME POWER FACTOR, THE TRANSFORMER LOADS CAN BE DETERMINED AS FOLLOWS:

| | LARGE TRANSFORMER LOAD | SMALL TRANSFORMER LOAD |
|---|---|---|
| SINGLE-PHASE LOAD | 30 KVA | - |
| THREE-PHASE LOAD (0.58 X 12) | 7 | 7 |
| TOTAL LOAD | 37 KVA | 7 KVA |

**NOTES:**

II. FOR A MORE COMPLETE DESCRIPTION OF THE DIVISION OF CURRENTS IN A THREE-PHASE STATION, CONSULT OVERHEAD STANDARD 1105.

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | EDITORIAL CHANGES | AW | JS | CZH | 7/3/2018 | E | | | | | |
| A | REVISION | | | | 1/1/1996 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD


SHEET 2 OF 2

TRANSFORMER LOADING GUIDE FOR THREE-PHASE STATIONS WITH SINGLE-PHASE TRANSFORMERS

UG3706.2

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE METHOD OF INSTALLING AN 'XD' DRY TYPE TRANSFORMER IN THE 480V SECONDARY COMPARTMENT OF A PAD–MOUNTED, THREE–PHASE TRANSFORMER.




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | | QUANTITY 2KVA | QUANTITY 3KVA | CONSTR. STD. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|---|---|
| 1 | TRANSFORMER, 'XD', DRY TYPE | | 1 | – | 3702 | 757888 | XD–002 |
| | | | – | 1 | | 757920 | XD–003 |
| 2 | KIT, CONNECTOR, FUSED | | 2 | 2 | – | 443392 | – |
| 3 | FUSE, MIDGET TYPE, SINGLE ELEMENT, 500 VOLT | 5 AMP | 2 | – | – | 368170 | – |
| | | 7 AMP | – | 2 | – | 368172 | – |
| 4 | BOLT, CARRIAGE, 5/16" X 1 1/2" (C) | | 4 | 4 | – | 149664 | – |
| 5 | NUT, HEX, 5/16", 1 ROUND AND 1 LOCK WASHER | | 4 | 4 | – | 506688 | – |
| 6 | WIRE, #8, 600V, AL INSULATED | | 6' | 6' | 4002 | 196176 | – |
| 7 | SECONDARY CONNECTIONS | | 2 | 2 | 4168, 4171 | – | – |
| 8 | CONNECTOR, COMPRESSION (SIZE AS REQ'D) | | AS REQ'D | | 4172 | – | – |
| 9 | WIRE, BARE STRANDED CU, #2 (D) | | AS REQ'D | | – | 812816 | – |

**INSTALLATION:**

A. USE THIS CONSTRUCTION TO AVOID SETTING AN ADDITIONAL TRANSFORMER FOR SMALL 240/120V METERED OR UNMETERED LOADS. DO NOT EXCEED THE NAME PLATE RATING OF TRANSFORMER.

(B) MOUNT 'XD' TRANSFORMER TO ENCLOSURE WALL IN UPPER SECONDARY COMPARTMENT SO AS NOT TO CROWD SECONDARY TERMINALS OR CONDUCTORS. MAINTAIN 1–1/2 INCH MINIMUM CLEARANCE FROM 'XD' TRANSFORMER TO 480V SECONDARY TERMINALS.

(C) TO MOUNT 'XD' TRANSFORMER, DRILL FOUR 3/8 INCH HOLES IN OUTSIDE CABINET WALL. APPLY RUST INHIBITOR AND SAME COLOR PAINT AS TRANSFORMER CABINET ON ALL HOLES DRILLED IN CABINET. FOR TAMPER RESISTANCE, INSTALL CARRIAGE BOLTS WITH HEADS ON OUTSIDE OF TRANSFORMER CABINET WALL.

(D) GROUND 'XD' TRANSFORMER CASE TO PAD GROUND WIRE IF GROUND LUG IS PROVIDED INSIDE 'XD' TRANSFORMER ACCESS PLATE.

©1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC STANDARDS


3708

SINGLE–PHASE, TYPE 'XD', 480V TO 240/120V, WALL MOUNTED TRANSFORMER INSTALLATION


REVISION DATE 1–1–98 APPD BMT / CMK

TABLE OF CONTENTS


**SCOPE:** THIS STANDARD SHOWS THE N–1.5 KVA TRANSFORMER AND THE METHODS OF INSTALLATION FOR CONTROL POWER IN AN EQUIPMENT CABINET.





PAD–MOUNTED SWITCH




1.5 KVA "N" TRANSFORMER




PAD–MOUNTED SERVICE RESTORER




UNDERGROUND OPERATING MAP SYMBOL

**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | QUANTITY | CONSTR. STD OR PAGE NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | TRANSFORMER "N" DRY TYPE | 1 | 3502 | 757880 | N–1.5 |
| 2 | BUSHING PLUG 200A LB (INCLUDED IN AU) | 1 | 4180 | 544676 | – |
| 3 | FUSED ELBOW LOADBREAK #2 AL | 1 | 4191.3 | 443850 | FE–2AL |
| 4 | ELBOW LOADBREAK #2 AL | 1 | 4191.1 | 443838 | LBE–2A |
| 5 | WHIP CABLE AL PECN–PEJ 1/C #2 | 10 FT. | 4002.2 | 197600 | WIP–#2 |
| 6 | CONNECTOR, COMPRESSION SIZE AS REQUIRED | AS REQ'D | 4172 | – | – |
| 7 | WIRE, BARE STRANDED CU, #2 | AS REQ'D | – | 812816 | – |
| 8 | ANCHOR, CONCRETE STAINLESS STEEL, 1/4" X 2–1/4" | 4 | – | 107660 | – |

**INSTALLATION:**

A. THE N–1.5 TRANSFORMER IS NOT TO BE INSTALLED IN A MANHOLE OR HANDHOLE.

B. USE THIS TRANSFORMER TO AVOID SETTING AN ADDITIONAL PAD–MOUNT TRANSFORMER FOR SMALL 120V NON–REVENUE LOADS.

C. "N" TRANSFORMERS HAVE NO INTERNAL PROTECTION, THE FEED POINT SHOULD INCLUDE A 30 AMP FUSED ELBOW.

D. WHEN INSTALLING THE "N" TRANSFORMER ON THE PAD INSIDE OF A PAD–MOUNTED SERVICE RESTORER, PLACE ONE OR TWO EXTRA 1/4 INCH ROUND WASHERS ON THE ANCHOR BOLTS BEFORE INSTALLING THE CONCRETE PAD AND THE TRANSFORMER.

E. GROUND THE "N" TRANSFORMER CASE TO THE EQUIPMENT AND CABLE GROUND SYSTEM.

F. INSTALL "N" TRANSFORMER ON LINE SIDE OF PMSR.


©1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|

| REVISION | SDG&E ELECTRIC STANDARDS | |
|---|---|---|
| DATE 3–1–02<br>APPD | SINGLE–PHASE TYPE "N"<br>6930 TO 120V 1.5 KVA | 3709 |

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION THAT SHALL BE USED FOR INSTALLING SINGLE-PHASE, DUAL VOLTAGE LOW PROFILE PAD-MOUNT TRANSFORMER TYPES "SDS".




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | KVA | TAPS | QUANTITY | CONST STD OR PG NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, SINGLE-PHASE | - | - | 1 | 3421 | S514240 | |
| 2 | TRENCH GROUND WIRE (W) | - | - | AS REQ'D | 4510 | - | |
| 3 | TRANSFORMER, (SDS) | - | - | 1 | 3702.2 | - | |
| | | 25 | - | - | - | S761520 | SDS-25 |
| | | 50 | - | - | - | S761522 | SDS-50 |
| | | 75 | - | - | - | S761524 | SDS-75 |
| 4 | HOLD DOWN DEVICE - (SUPPLIED WITH CABINET) | - | - | 2 | - | - | |
| 5 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND W/BUSHING PLUG) (C) | - | - | 2 | 4191 | - | |
| | | | | 2 | 4192.1 | S544676 | |
| 6 | CONCENTRIC NEUTRAL TAILS | - | - | 2 | - | - | |
| 7 | CONNECTOR, COMPRESSION | - | - | AS REQ'D | 4172 | - | |
| 8 | KEYLESS LOCK, (NOT SHOWN ABOVE) (H) | - | - | 1 | - | S468010 | |
| 9 | CABLE IDENTIFICATION TAGS | - | - | AS REQ'D | 3202 | - | |
| 10 | SECONDARY CONNECTIONS (D) | - | - | AS REQ'D | 4167 | - | |
| 11 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | - | - | 1 | - | - | |
| 12 | SEALING COMPOUND | - | - | AS REQ'D | - | S442976 | |
| 13 | SERVICE POST CONNECTOR | - | - | 2 | - | S262560 | |
| 14 | 3312 BOX USE AS NEEDED | - | - | AS REQ'D | 3312 | S162462 | |
| 15 | BAY-O-NET FUSE SEE FUSE TABLE 4311.5 | - | - | AS REQ'D | 4311.5 | | |
| 16 | DUAL VOLTAGE SWITCH | | | | | | |
| 17 | PRESSURE RELIEF VALVE | | | | | | |
| 18 | OIL LEVEL PLUG | | | | | | |
| 19 | DIAGRAM NAME PLATE | | | | | | |
| 20 | BAR CODE STOCK NUMBER PLATE | | | | | | |

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | EDITORIAL CHANGES | | TR | DW | 9/26/2013 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

SINGLE-PHASE, DUAL VOLTAGE SDS
4160GRDY/2400 X 12000GRDY/6930
LOW PROFILE PAD-MOUNT TRANSFORMER INSTALLATION

UG3711.1

TABLE OF CONTENTS

## INSTALLATION:

(A) THIS INSTALLATION IS LIMITED TO 2 SINGLE-PHASE #2 PRIMARY CABLES, ONE IN AND ONE OUT.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6.).

(C) WHEN INSTALLATION IS AT END OF CIRCUIT, CHANGE QUANTITY TO ONE ELBOW (STANDARD 4191 AND ONE ONE RECEPTACLE (STOCK NUMBER S204304).

(D) SET SCREW CONNECTORS ARE NOT PROVIDED WITH TRANSFORMER, SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER.

(F) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (STANDARD 3408).

(H) KEYLESS LOCK (ITEM 8) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AND PENTAHEAD BOLT THREADED IN COMPLETELY.

(I) WHEN CHANGING SDS FROM 2.4KV TO 6.9KV FOLLOW BAY-O-NET FUSE CHART LISTED:

| SDS | 2.4KV | 6.9KV |
|---|---|---|
| 25KVA | 15 AMP | 6 AMP |
| 50KVA | 40 AMP | 12 AMP |
| 75KVA | 50 AMP | 15 AMP |

SERIES/MULTIPLE PRIMARY TRANSFORMERS ARE SUPPLIED WITH 2.4KV FUSE.

## REFERENCE:

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(N) SEE STANDARD 3421 FOR PAD AND CONDUIT PLACEMENT.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S. SEE STANDARD 3487 FOR RETAINING WALL.

T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

U. SEE STANDARD 3703 FOR TRANSFORMER APPLICATIONS.

(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(W) SEE STANDARD 4510 FOR (PREFERRED I ) AND (ALTERNATE) TRENCH GROUND WIRE.

X. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II ) EQUIPMENT GROUNDING INSTALLATION.

(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PADMOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | EDITORIAL CHANGES | | TR | DW | 9/26/2013 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

SINGLE-PHASE, DUAL VOLTAGE SDS
4160GRDY/2400 X 12000GRDY/6930
LOW PROFILE PAD-MOUNT TRANSFORMER INSTALLATION

UG3711.2

**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION THAT SHALL BE USED FOR INSTALLING SINGLE-PHASE, 6930 VOLT LOW PROFILE PAD-MOUNT TRANSFORMERS TYPE "NTS", WITH VOLTAGE TAP CHANGER.




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | KVA | TAPS | QUANTITY | CONST STD. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER SINGLE-PHASE | - | - | 1 | 3421 | S514240 | 3421-1 |
| 2 | TRENCH GROUND WIRE (V) | - | - | AS REQ'D | 4510 | - | - |
| 3 | TRANSFORMER, (NTS) (G)(F) | - | - | 1 | 3702.2 | - | - |
| | | 25 | (B) | - | - | S764230 | NTS-25 |
| | | 50 | (B) | - | - | S764232 | NTS-50 |
| | | 75 | (B) | - | - | S764234 | NTS-75 |
| | | 100 | (B) | - | - | S764236 | NTS100 |
| 4 | SEALING COMPOUND (B)(U) | - | - | AS REQ'D | - | S442976 | - |
| 5 | CAP, INSULATING RECEPTACLE (H) | - | - | AS REQ'D | 4192 | S204304 | INSREC |
| 6 | FEED-THRU INSERT (H)(G)(F) | - | - | 1 | 4192 | S544678 | FEED-I |
| 7 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) (H) | - | - | 3 | 4191 | - | - |
| 8 | CONCENTRIC NEUTRAL TAILS | - | - | AS REQ'D | 4172.1 | - | - |
| 9 | CONNECTOR, COMPRESSION | - | - | AS REQ'D | 4172 | - | - |
| 10 | KEYLESS LOCK, (NOT SHOWN ABOVE) (A) | - | - | 1 | - | S468010 | - |
| 11 | CABLE IDENTIFICATION TAGS | - | - | AS REQ'D | 3202 | - | - |
| 12 | CONNECTIONS, SECONDARY (D) | - | - | AS REQ'D | 4167 | - | - |
| 13 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | - | - | 1 | - | - | - |
| 14 | HOLD DOWN DEVICE (SUPPLIED WITH TRANSFORMER) | - | - | 2 | - | - | - |
| 15 | NUT, CLAMPING CHANNEL | - | - | 2 | - | S503520 | - |

TABLE OF CONTENTS

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | EDITORIAL CHANGES | | TR | DW | 9/26/2013 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

SINGLE-PHASE, 6930 VOLT, TYPE "NTS"
LOW PROFILE PAD-MOUNT TRANSFORMER INSTALLATION

UG3711.3

## BILL OF MATERIAL: (CON'T)

| ITEM | DESCRIPTION | KVA | TAPS | QUANTITY | CONST STD. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|---|---|
| 16 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | - | - | 2 | - | S616192 | - |
| 17 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | - | - | 2 | - | S799488 | - |
| 18 | SERVICE POST CONNECTOR | - | - | 2 | - | S262560 | - |
| 19 | BUSHING PLUG | - | - | 1 | 4192 | S544676 | BSHPLG |
| 20 | BAY-O-NET FUSE SEE FUSE TABLE 4311.5 | - | - | AS REQ'D | 4311.5 | - | - |
| 21 | NO LOAD TAP CHANGER | - | - | 1 | - | - | - |
| 22 | PRESSURE RELIEF VALVE | - | - | 1 | - | - | - |
| 23 | OIL LEVEL PLUG | - | - | 1 | - | - | - |
| 24 | DIAGRAM NAME PLATE | - | - | 1 | - | - | - |
| 25 | BAR CODE STOCK NUMBER PLATE | - | - | 1 | - | - | - |

## INSTALLATION:

(A) KEYLESS LOCK, ITEM 10, TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AND PENTAHEAD BOLT THREADED IN COMPLETELY.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND OR EQUIVALENT. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(C) BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (STANDARD 3408).

(D) SET SCREW CONNECTORS ARE NOT PROVIDED WITH TRANSFORMER. SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER.

(F) THIS INSTALLATION ALLOWS UP TO THREE SINGLE-PHASE PRIMARY CABLES. THE "NTS" TRANSFORMER IS FITTED WITH ONE BUSHING WELL ON BUSHING "HIA" AND ONE INTEGRAL BUSHING ON BUSHING "HIB". A FEED-THRU INSERT IS REQUIRED ON BUSHING "HIA", ITEM 6 IN THE BILL OF MATERIAL.

(G) INSTALL THE LINE AND LOAD CABLES ON THE FEED THRU BUSHING "HIA". INSTALL THE TAP CABLE 0N THE INTEGRAL BUSHING "HIB". THE TAP CABLE MAY FEED UP TO THREE TRANSFORMERS MAXIMUM.

(H) REDUCE LOADBREAK ELBOW QUANTITY AND INSTALL INSULATING RECEPTACLE IF ALL THREE CABLES ARE NOT INSTALLED SIMULTANEOUSLY.

(I) INSTALL A BUSHING PLUG ON "HIA" BUSHING WELL WHEN THE TRANSFORMER USES ONE PRIMARY LINE CABLE IN AND ONE PRIMARY LOAD CABLE OUT.

TABLE OF CONTENTS

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | EDITORIAL CHANGES | | TR | DW | 9/26/2013 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

SINGLE-PHASE, 6930 VOLT, TYPE "NTS"
LOW PROFILE PAD-MOUNT TRANSFORMER INSTALLATION

UG3711.4

**REFERENCE:**

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(N) SEE STANDARD 3421 FOR PAD AND CONDUIT REQUIREMENTS.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALL.

S. SEE STANDARD 3487 FOR RETAINING WALLS.

(T) SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

(U) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(V) SEE STANDARD 4510 FOR (PREFERRED I ) AND (ALTERNATE) TRENCH GROUND WIRE.

W. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II ) EQUIPMENT GROUNDING INSTALLATION.

(X) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Y. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | EDITORIAL CHANGES | | TR | DW | 9/26/2013 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

SINGLE-PHASE, 6930 VOLT, TYPE "NTS"
LOW PROFILE PAD-MOUNT TRANSFORMER INSTALLATION



UG3711.5

**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION THAT SHALL BE USED FOR INSTALLING SINGLE–PHASE, 12KV, DEAD FRONT, PAD–MOUNT TRANSFORMER, TYPES "HDS", "HJS", "HTS".




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | QUANTITY | CONST STD OR PG NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, SINGLE–PHASE | 1 | 3421 | 514240 | 3421–1 |
| 2 | TRENCH GROUND WIRE (V) | AS REQ'D | 4510 | – | – |
| 3 | TRANSFORMER, (HDL, HTL, HJD OR HSL) (G) (F) | 1 | 3702 | – | – |
| 4 | SEALING COMPOUND (B) (4) | AS REQ'D | – | 442976 | – |
| 5 | BUSHING PLUG (RADIAL FEED) (F) | AS REQ'D | 4192 | 544676 | BSHPLG |
| 6 | FEED–THRU INSERT (LOOP FEED) (F) | AS REQ'D | 4192 | 544678 | FEED–I |
| 7 | ELBOW, LOADBREAK, 12KV (WITH WHITE–BLACK–WHITE BAND) | AS REQ'D | 4191 | – | – |
| 8 | CONCENTRIC NEUTRAL TAILS | AS REQ'D | – | – | – |
| 9 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | – | – |
| 10 | KEYLESS LOCK, (NOT SHOWN ABOVE) (A) | 1 | – | 468010 | – |
| 11 | CABLE IDENTIFICATION TAGS | AS REQ'D | 3202 | – | – |
| 12 | CONNECTIONS, SECONDARY (D) | AS REQ'D | 4167 | – | – |
| 13 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | 1 | – | – | – |
| 14 | HOLD DOWN DEVICE – (SUPPLIED WITH TRANSFORMER) | 2 | – | – | – |
| 15 | NUT, CLAMPING CHANNEL | 2 | – | 503520 | – |
| 16 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1–1/2" | 2 | – | 616192 | – |
| 17 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 2 | – | 799488 | – |
| 18 | SERVICE POST CONNECTOR | 2 | – | 262560 | – |
| 19 | BAY–O–NET FUSES | 2 | – | – | – |

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|

| | SDG&E ELECTRIC STANDARDS | REVISION |
|---|---|---|
| 3712.1 | SINGLE–PHASE, 12KV, TYPE "HDS", "HJS", "HTS" DEAD FRONT PAD–MOUNT TRANSFORMER INSTALLATION | DATE 5–24–04 APPD BJT/VCK |

TABLE OF CONTENTS

**INSTALLATION:**

(A) KEYLESS LOCK (ITEM 10) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AND PENTAHEAD BOLT THREADED IN COMPLETELY.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(C) BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (STANDARD 3408).

(D) SET SCREW CONNECTORS ARE NOT PROVIDED WITH TRANSFORMER, SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER.

(F) THESE INSTALLATIONS USE EITHER TWO OR FOUR SINGLE-PHASE #2 PRIMARY CABLES. THE TRANSFORMERS ARE FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS. FOR THE RADIAL FEED APPLICATION, TWO BUSHING PLUGS ARE REQUIRED, ITEM 5 IN THE BILL OF MATERIAL. FOR THE LOOP FEED APPLICATION, FEED-THRU INSERTS ARE REQUIRED, ITEM 6 IN THE BILL OF MATERIAL.

**REFERENCE:**

I. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

J. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

K. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

L. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(M) SEE STANDARD 3421 FOR PAD AND CONDUIT REQUIREMENTS.

N. SEE STANDARD 3481 FOR BARRIER PROTECTION.

O. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

P. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

Q. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

R. SEE STANDARD 3487 FOR RETAINING WALLS.

S. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

T. SEE STANDARD 3703 FOR TRANSFORMER APPLICATIONS.

(U) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(V) SEE STANDARD 4510 FOR (PREFERRED I ) AND (ALTERNATE) TRENCH GROUND WIRE.

W. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II ) EQUIPMENT GROUNDING INSTALLATION.

(X) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Y. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PADMOUNTED EQUIPMENT.

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION THAT SHALL BE USED FOR INSTALLING TWO SINGLE-PHASE, DEADFRONT TYPE "HDS", OR "HTS" TRANSFORMERS FOR AN OPEN DELTA BANK THREE-PHASE INSTALLATION.





**FIGURE 1**





**FIGURE 2**
PRIMARY TERMINAL CONNECTIONS





**FIGURE 3**
SECONDARY TERMINAL CONNECTIONS

## INSTALLATION:

(A) KEYLESS LOCK TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMERS AND PENTAHEAD BOLTS THREADED IN COMPLETELY.

(B) **TERMINATE PRIMARY AND SECONDARY CONDUITS AS SHOWN ON FIGURES 1-3.**

(C) INSERT ITEM 3 (FLOOR PLATE) PRIOR TO SETTING PADS.

(D) BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY. (d)

(E) **ON THE POWER TRANSFORMER, REMOVE SECONDARY GROUND STRAP, MAKE SURE GROUND STRAP IS ATTACHED TO THE TANK ON THE LIGHTING TRANSFORMER.**

(F) THIS INSTALLATION USES THREE-PHASE #2 OR #2/0 PRIMARY CABLES. THE "HDS" AND "HTS" TRANSFORMERS ARE FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | HANDHOLE, 14" X 66" X 14" | 1 | 3311 | S162660 | -- |
| 2 | PAD, TRANSFORMER | 2 | 3421 | S514240 | 3421-1 |
| 3 | PLATE, FLOOR, 3/8", GALV., 12" X 24" | 1 | -- | MACHINE SHOP | -- |
| 4 | WIRE, TRENCH GROUND (l) | AS REQ'D | 4510 | -- | -- |
| 5 | TRANSFORMERS, (HDL, HTL OR HSL) (F) | 2 | 3702 | -- | -- |
| 6 | FUSE, BAY-O-NET | 2 | -- | -- | -- |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REFERENCE UPDATE | EDM | EJA | GLW | KRG | 10/21/2022 | F | | | | | | |
| B | REVISION | - | - | - | RSW/VCR | 05/27/2004 | E | | | | | | |
| A | REVISION | - | - | - | RSW/VCR | 03/01/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TWO SINGLE-PHASE, TYPE "HDS", OR "HTS" DEADFRONT PADMOUNT TRANFORMERS FOR OPEN DELTA BANK INSTALLATION



UG3713.1

TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 7 | BUSHING PLUG | 3 | 4195 | S544676 | BSHPLG |
| 8 | INSERT, FEED-THRU | 1 | 4195 | S544678 | FEED-I |
| 9 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | AS REQ'D | 4190/4191 | -- | -- |
| 10 | TAILS, CONCENTRIC NEUTRAL | AS REQ'D | 4176 | -- | -- |
| 11 | CONNECTOR, COMPRESSION | AS REQ'D | 4174/4176 | -- | -- |
| 12 | KEYLESS LOCK (A)(I) | 2 | -- | S468010 | -- |
| 13 | CABLE IDENTIFICATION | AS REQ'D | 3202 | -- | -- |
| 14 | CONNECTIONS, SLIP-FIT | AS REQ'D | 4167/4168 | S269990 | -- |
| 15 | NEUTRAL GROUND STRAP (ON TRANSFORMER) (E) | 2 | -- | -- | -- |
| 16 | HOLD DOWN DEVICE (SUPPLIED WITH TRANSFORMER) | 4 | -- | -- | -- |
| 17 | NUT, CLAMPING CHANNEL | 4 | -- | S503520 | -- |
| 18 | CONNECTOR, SERVICE POST | 4 | -- | S262560 | -- |

## NOTES:

(I) NOT SHOWN ON FIGURES

## REFERENCE:

a. SEE UG3202 FOR CABLE IDENTIFICATION.

b. SEE UG3213, UG3214, UG3215, UG3216, UG3217, AND UG3218 (PREVIOUS # UG3212) FOR TRANSFORMER IDENTIFICATION.

(c) SEE UG3365 AND UG3366 (PREVIOUS # UG3365) FOR SLURRY BACKFILL.

(d) SEE UG3408.

e. SEE UG3479 FOR TRANSFORMER BARRIER PROTECTION.

f. SEE UG3480, UG3481, UG3482, AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

g. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

h. SEE UG3486, UG3487, AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

i. SEE UG3489 FOR RETAINING WALLS.

j. SEE UG3702 FOR TRANSFORMER RATING AND SIZE. SEE THE WORK ORDER FOR TRANSFORMER PREFIXES.

(k) SEE UG3948 FOR SEALING SERVICE LATERAL CONDUITS.

(l) SEE UG4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

m. SEE UG4512 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(n) SEE UG4512 FOR EQUIPMENT GROUNDING.

o. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REFERENCE UPDATE | EDM | EJA | GLW | KRG | 10/21/2022 | F | | | | | | |
| B | REVISION | - | - | - | RSW/VCR | 05/27/2004 | E | | | | | | |
| A | REVISION | - | - | - | RSW/VCR | 03/01/2002 | D | | | | | | |




X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


TWO SINGLE-PHASE, TYPE "HDS", OR "HTS" DEADFRONT PADMOUNT TRANFORMERS FOR OPEN DELTA BANK INSTALLATION

UG3713.2


**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION THAT SHALL BE USED FOR INSTALLING THREE SINGLE-PHASE, DEAD FRONT TYPE "HDS" OR "HTS" TRANSFORMERS FOR A CLOSED DELTA BANK THREE-PHASE INSTALLATION.




**PRIMARY INSTALLATION**




**SECONDARY INSTALLATION**




©1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| X Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|

| 3714.1 | SDG&E ELECTRIC STANDARDS<br>THREE SINGLE-PHASE, TYPE "HDS" OR "HTS" DEAD FRONT PAD-MOUNT TRANSFORMERS FOR CLOSED DELTA BANK INSTALLATION | REVISION<br>DATE 5-28-04<br>APPD |
|---|---|---|

TABLE OF CONTENTS

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD. OR PAGE NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | HANDHOLE, 14" X 108" X 14" | 1 | 3311 | 162662 | - |
| 2 | PAD, TRANSFORMER | 3 | 3421 | 514240 | 3421-1 |
| 3 | PLATE, FLOOR, 3/8" GALV, 12" X 24" | 2 | - | MACHINE SHOP | - |
| 4 | TRENCH GROUND WIRE (Y) | AS REQ'D | 4510 | - | - |
| 5 | TRANSFORMERS, (HDL, HTL OR HSL) (H) | 3 | 3702 | - | - |
| 6 | SEALING COMPOUND (B) (X) | AS REQ'D | - | 442976 | - |
| 7 | BUSHING PLUG | 3 | 4192 | 544676 | BSHPLG |
| 8 | FEED-THRU INSERT | 3 | 4192 | 544678 | FEED-I |
| 9 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | 9 | 4191 | - | - |
| 10 | CONCENTRIC NEUTRAL TAILS | AS REQ'D | - | - | - |
| 11 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | - | - |
| 12 | KEYLESS LOCK (NOT SHOWN ABOVE) (A) | 3 | - | 468101 | - |
| 13 | CABLE IDENTIFICATION | AS REQ'D | 3202 | - | - |
| 14 | CONNECTIONS, SECONDARY (F) | AS REQ'D | 4167 | - | - |
| 15 | NEUTRAL GROUND STRAP (SUPPLIED WITH TRANSFORMER) (G) | 3 | - | - | - |
| 16 | HOLD DOWN DEVICE (SUPPLIED WITH TRANSFORMER) | 6 | - | - | - |
| 17 | NUT, CLAMPING CHANNEL | 6 | - | 503520 | - |
| 18 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | 6 | - | 616192 | - |
| 19 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 6 | - | 799488 | - |
| 20 | SERVICE POST CONNECTOR | 6 | - | 262560 | - |
| 21 | BAY-O-NET FUSE | 2 | - | - | - |

## INSTALLATION:

(A) KEYLESS LOCK, ITEM 12, TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMERS AND PENTAHEAD BOLTS THREADED IN COMPLETELY.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS AS SHOWN ON PAGE 3714.1. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND OR EQUIVALENT. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(C) INSERT ITEM 3 (FLOOR PLATES), PRIOR TO SETTING PADS.

(D) BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (SEE STANDARD 3408).

(F) SLIP-FIT CONNECTORS ARE NOT PROVIDED WITH TRANSFORMERS, SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN ALL CONNECTIONS ARE TIGHT BEFORE ENERGIZED TRANSFORMER.

(G) ON THE POWER TRANSFORMERS, REMOVE SECONDARY GROUND STRAPS, MAKE SURE GROUND STRAP IS ATTACHED TO THE TANK ON THE LIGHTING TRANSFORMER.

(H) THIS INSTALLATION USES THREE-PHASE #2 OR #2/0 PRIMARY CABLES. THE "HDL", "HTL", "HDS AND HTS" TRANSFORMERS ARE FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS.

(I) MAKE SURE THE INSIDE WINDOW OPENING ON THE LEFT POWER TRANSFORMER IS STRAIGHT IN LINE WITH THE INSIDE OF THE HANDHOLE OPENING TO ALLOW ROOM FOR CABLE PULLING & TRAINING.

**REFERENCE:**

M. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

N. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

(O) SEE STANDARD 3365 FOR SLURRY BACKFILL.

(P) SEE STANDARD 3421 FOR PAD AND CONDUIT REQUIREMENTS.

Q. SEE STANDARD 3481 FOR TRANSFORMER BARRIER PROTECTION.

R. SEE STANDARD 3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

S. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

T. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

U. SEE STANDARD 3487 FOR RETAINING WALLS.

V. SEE STANDARD 3702 FOR TRANSFORMER RATING AND SIZE. SEE THE WORK ORDER FOR TRANSFORMER PREFIXES.

W. SEE STANDARD 3703 FOR TRANSFORMER APPLICATIONS.

(X) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(Y) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

Z. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(AA) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

B.B. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.

© 1998 - 2010 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

Indicates Latest Revision | Completely Revised | New Page | Information Removed

REVISION
DATE 3-1-02
APPD


SDG&E ELECTRIC STANDARDS

THREE SINGLE-PHASE, TYPE "HDS" OR HTS"
DEAD FRONT PAD-MOUNT TRANSFORMERS FOR
CLOSED DELTA BANK INSTALLATION


3714.2

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE SDS TRANSFORMER FOR THREE–PHASE INSTALLATION.




## SDS OPEN Y OPEN DELTA XFMR ADDITIVE POLARITY




© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| Indicates Latest Revision | Completely Revised | X New Page | Information Removed |
|---|---|---|---|

| 3715.1 | SDG&E ELECTRIC STANDARDS<br>TWO SINGLE-PHASE, Y TYPE SDS DEAD FRONT PAD-MOUNT TRANSFORMERS FOR OPEN DELTA BANK INSTALLATION | REVISION<br>DATE 3-18-05<br>APPD TR / JJ |
|---|---|---|

TABLE OF CONTENTS

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD OR PG NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | HANDHOLE, 14" X 66" X 14" | 1 | 3311 | 162660 | - |
| 2 | PAD TRANSFORMER | 2 | 3421 | 514240 | 3421-1 |
| 3 | PLATE, FLOOR, 3/8" GALV, 12" X 24" | 1 | - | MACHINE SHOP | - |
| 4 | TRENCH GROUND WIRE (X) | AS REQ'D | 4510 | - | - |
| 5 | TRANSFORMERS, (SDS) (H) | 2 | 3702.2 | - | - |
| 6 | SEALING COMPOUND (B) (W) | AS REQ'D | - | 442976 | - |
| 7 | BUSHING PLUG | 2 | 4192 | 544676 | BSHPLG |
| 8 | INSULATING CAP | 2 | 4192 | 204304 | - |
| 9 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | 2 | 4191 | - | - |
| 10 | CONCENTRIC NEUTRAL TAILS | AS REQ'D | 4172.1 | - | - |
| 11 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | - | - |
| 12 | KEYLESS LOCK, (NOT SHOWN ABOVE) (A) | 2 | - | 468010 | - |
| 13 | CABLE IDENTIFICATION | AS REQ'D | 3202 | - | - |
| 14 | CONNECTIONS, SECONDARY (F) | AS REQ'D | 4167 | - | - |
| 15 | NEUTRAL GROUND STRAP (ON TRANSFORMER) (G) | 2 | - | - | - |
| 16 | HOLD DOWN DEVICE - (SUPPLIED WITH TRANSFORMER) | 4 | - | - | - |
| 17 | NUT, CLAMPING CHANNEL | 4 | - | 503520 | - |
| 18 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | 4 | - | 616192 | - |
| 19 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 4 | - | 799488 | - |
| 20 | SERVICE POST CONNECTOR | 4 | - | 262560 | - |
| 21 | BAY-0-NET FUSE | 2 | - | - | - |

## INSTALLATION:

(A) KEYLESS LOCK, ITEM 12, TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMERS AND PENTAHEAD BOLTS THREADED IN COMPLETELY.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS AS SHOWN ON PAGE 3713.1. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND OR EQUIVALENT. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(C) INSERT ITEM 3 (FLOOR PLATE), PRIOR TO SETTING PADS.

(D) BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (SEE STANDARD 3408).

(F) SLIP-FIT CONNECTORS ARE NOT PROVIDED WITH TRANSFORMERS. SEE STANDARD 4167 FOR INSTALLATIONS AND STOCK NUMBERS. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER.

(G) ON THE POWER TRANSFORMER, REMOVE SECONDARY GROUND STRAP, NO Z BAR IS REQUIRED. MAKE SURE GROUND STRAP IS ATTACHED TO THE TANK ON THE LIGHTING TRANSFORMER.

(H) THIS INSTALLATION USES TWO-PHASE #2 OR #2/0 PRIMARY CABLES.

(I) CHECK TRANSFORMER NAME PLATE FOR POLARITY.

(J) CHECK HIGH VOLTAGE SWITCH FOR CORRECT SYSTEM VOLTAGE.

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

**REFERENCE:**

M. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

N. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

(O) SEE STANDARD 3365 FOR SLURRY BACKFILL.

(P) SEE STANDARD 3421 FOR PAD AND CONDUIT REQUIREMENTS.

Q. SEE STANDARD 3481 FOR TRANSFORMER BARRIER PROTECTION.

R. SEE STANDARD 3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

S. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

T. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

U. SEE STANDARD 3487 FOR RETAINING WALLS.

V. SEE STANDARD 3702 FOR TRANSFORMER RATING AND SIZE. SEE THE WORK ORDER FOR TRANSFORMER PREFIXES.

(W) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(X) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.


Y. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(Z) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.


TABLE OF CONTENTS

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION THAT SHALL BE USED FOR INSTALLING THREE SINGLE-PHASE, DEAD FRONT Y TYPE SDS TRANSFORMERS FOR A CLOSED DELTA BANK THREE-PHASE INSTALLATION.




**PRIMARY INSTALLATION**




**SECONDARY INSTALLATION**




**SDS Y CLOSED DELTA ADDITIVE POLARITY**

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |

| | | |
|---|---|---|
| REVISION<br>DATE 2-24-05<br>APPD TR / JJ | SDG&E ELECTRIC STANDARDS<br>THREE SINGLE-PHASE, Y TYPE SDS<br>DEAD FRONT PAD-MOUNT TRANSFORMERS FOR<br>CLOSED DELTA BANK INSTALLATION | 3715.4 |

TABLE OF CONTENTS

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD. OR PAGE NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | HANDHOLE, 14" X 108" X 14" | 1 | 3311 | 162662 | - |
| 2 | PAD, TRANSFORMER | 3 | 3421 | 514240 | 3421-1 |
| 3 | PLATE, FLOOR, 3/8" GALV, 12" X 24" | 2 | - | MACHINE SHOP | - |
| 4 | TRENCH GROUND WIRE (Y) | AS REQ'D | 4510 | - | - |
| 5 | TRANSFORMERS, SDS (H) | 3 | 3702 | - | - |
| 6 | SEALING COMPOUND (B) (X) | AS REQ'D | - | 442976 | - |
| 7 | BUSHING PLUG | 3 | 4192 | 544676 | BSHPLG |
| 8 | CAP INSULATING | 3 | 4192 | 204304 | FEED-I |
| 9 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | 3 | 4191 | - | - |
| 10 | CONCENTRIC NEUTRAL TAILS | AS REQ'D | - | - | - |
| 11 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | - | - |
| 12 | KEYLESS LOCK (NOT SHOWN ABOVE) (A) | 3 | - | 468101 | - |
| 13 | CABLE IDENTIFICATION | AS REQ'D | 3202 | - | - |
| 14 | CONNECTIONS, SECONDARY (F) | AS REQ'D | 4167 | - | - |
| 15 | NEUTRAL GROUND STRAP (SUPPLIED WITH TRANSFORMER) (G) | 3 | - | - | - |
| 16 | HOLD DOWN DEVICE (SUPPLIED WITH TRANSFORMER) | 6 | - | - | - |
| 17 | NUT, CLAMPING CHANNEL | 6 | - | 503520 | - |
| 18 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1-1/2" | 6 | - | 616192 | - |
| 19 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | 6 | - | 799488 | - |
| 20 | SERVICE POST CONNECTOR | 6 | - | 262560 | - |
| 21 | BAY-O-NET FUSE | 3 | - | - | - |

## INSTALLATION:

(A) KEYLESS LOCK, ITEM 12, TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMERS AND PENTAHEAD BOLTS THREADED IN COMPLETELY.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS AS SHOWN ON PAGE 3714.1. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND OR EQUIVALENT. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(C) INSERT ITEM 3 (FLOOR PLATES), PRIOR TO SETTING PADS.

(D) BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (SEE STANDARD 3408).

(F) SLIP-FIT CONNECTORS ARE NOT PROVIDED WITH TRANSFORMERS, SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN ALL CONNECTIONS ARE TIGHT BEFORE ENERGIZED TRANSFORMER.

(G) ON THE POWER TRANSFORMERS, REMOVE SECONDARY GROUND STRAPS, NO Z BAR IS REQUIRED. MAKE SURE GROUND STRAP IS ATTACHED TO THE TANK ON THE LIGHTING TRANSFORMER.

(H) THIS INSTALLATION USES THREE-PHASE #2 OR #2/0 PRIMARY CABLES.

(I) MAKE SURE THE INSIDE WINDOW OPENING ON THE LEFT POWER TRANSFORMER IS STRAIGHT IN LINE WITH THE INSIDE OF THE HANDHOLE OPENING TO ALLOW ROOM FOR CABLE PULLING & TRAINING.

(J) CHECK TRANSFORMER NAME PLATE FOR POLARITY.

(K) CHECK HIGH VOLTAGE SWITCH FOR CORRECT SYSTEM VOLTAGE.

© 1998 - 2014 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.



TABLE OF CONTENTS

**REFERENCE:**

M. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

N. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

(O) SEE STANDARD 3365 FOR SLURRY BACKFILL.

(P) SEE STANDARD 3421 FOR PAD AND CONDUIT REQUIREMENTS.

Q. SEE STANDARD 3481 FOR TRANSFORMER BARRIER PROTECTION.

R. SEE STANDARD 3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS.

S. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

T. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

U. SEE STANDARD 3487 FOR RETAINING WALLS.

V. SEE STANDARD 3702 FOR TRANSFORMER RATING AND SIZE. SEE THE WORK ORDER FOR TRANSFORMER PREFIXES.

W. SEE STANDARD 3703 FOR TRANSFORMER APPLICATIONS.

(X) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.


(Y) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

Z. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

**SCOPE:** THIS STANDARD SHOWS THE CONNECTION USED FOR INSTALLING THREE–PHASE, 12KV RADIAL/LOOP FEED DEAD FRONT PAD–MOUNTED TRANSFORMERS.




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | QUANTITY | CONST STD. OR PG NO | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, THREE–PHASE | 1 | 3425,3426,3427 | – | – |
| 2 | TRENCH GROUND WIRE (W) | AS REQ'D | 4510 | – | – |
| 3 | TRANSFORMER, (THRU 1500 KVA) (F) | 1 | 3702 | – | – |
| 4 | HOLD DOWN DEVICE – (SUPPLIED WITH CABINET) | 2 | – | – | – |
| 5 | BUSHING PLUG (RADIAL FEED) (A) | 3 | 4192 | 544676 | BSHPLG |
| 6 | FEED–THRU INSERT (LOOP FEED) (A) | 3 | 4192 | 544678 | FEED–I |
| 7 | ELBOW, LOADBREAK, 12KV (WITH WHITE–BLACK–WHITE BAND) | AS REQ'D | 4191 | – | – |
| 8 | CONCENTRIC NEUTRAL TAILS | – | 4172.1 | – | – |
| 9 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | – | – |
| 10 | KEYLESS LOCK, (NOT SHOWN ABOVE) (G) | 1 | – | 468010 | – |
| 11 | CABLE IDENTIFICATION TAGS | AS REQ'D | 3202 | – | – |
| 12 | SECONDARY CONNECTIONS | AS REQ'D | 4168, 4171 | – | – |
| 13 | FUSE, "BAY–O–NET" (U) | 3 | 4311 | – | – |
| 14 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | 1 | – | – | – |
| 15 | SEALING COMPOUND (B)(V) | AS REQ'D | – | 442976 | – |
| 16 | SERVICE POST CONNECTOR | 2 | – | 262560 | – |

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| X Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|

| 3751.1 | SDG&E ELECTRIC STANDARDS<br>THREE–PHASE 12KV, TYPE "HZS", "HBS", "PZS", "HMS", "HNS", OR "HKS" RADIAL/LOOP, DEAD FRONT, PAD–MOUNTED TRANSFORMER INSTALLATION | REVISION<br>DATE 5–10–05<br>APPD MF / JJ |
|---|---|---|

TABLE OF CONTENTS

**INSTALLATION:**

(A) THIS INSTALLATION USES FROM 3 TO 6 SINGLE-PHASE CONDUCTOR #2 OR 2/0 PRIMARY CABLES. THE TRANSFORMER IS FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS. FOR THE RADIAL APPLICATION, THREE BUSHING PLUGS ARE REQUIRED, ITEM 5 IN THE BILL OF MATERIAL. FOR THE LOOP FEED APPLICATION, THREE FEED-THRU INSERTS ARE REQUIRED, ITEM 6 IN THE BILL OF MATERIAL.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O 128 RULE 31.6).

(C) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(F) TRANSFORMER RATING AND SIZE PER WORK ORDER.

(G) KEYLESS LOCK (ITEM 10) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AFTER PENTAHEAD BOLT IS THREADED IN COMPLETELY.

(H) WHEN CHANGING PZS FROM 4KV TO 12KV FOLLOW BAY-O-NET FUSE CHART LISTED:

| PZS | 4KV | 12KV |
|---|---|---|
| 75KVA | 25 AMP | 6 AMP |
| 150KVA | 30 AMP | 12 AMP |
| 500KVA | 100 AMP | 40 AMP |

SERIES/MULTIPLE PRIMARY TRANSFORMERS ARE SUPPLIED WITH 4160 VOLT FUSE.

**REFERENCE:**

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(N) SEE STANDARD 3425, 3426 OR 3427 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S. SEE STANDARD 3487 FOR RETAINING WALLS.

T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

(U) SEE STANDARD 3704 FOR "BAY-O-NET" FUSE OPERATING INSTRUCTIONS.

(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(W) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

X. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE CONNECTION USED FOR INSTALLING THREE-PHASE, 12KV RADIAL FEED DEAD FRONT PAD-MOUNTED TRANSFORMER.





**FIGURE 1**

## INSTALLATION:

(A) THIS INSTALLATION USES THREE-PHASE PRIMARY CABLE IN EITHER RADIAL OR LOOP CONFIGURATION. THE TRANSFORMER IS FITTED WITH 3 BUSHINGS WELLS. INSTALL BUSHING PLUGS FOR RADIAL OR FEED-THRU INSERTS FOR LOOP CONFIGURATION.

(B) TERMINATE PRIMARY CONDUIT FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(C) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(D) TRANSFORMER RATING AND SIZE PER WORK ORDER.

(E) KEYLESS LOCK (ITEM 10) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AFTER PENTAHEAD BOLT IS THREADED IN COMPLETELY.

© 1998 - 2019 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | FIGURE UPDATE | ADW | JES | CZH | 11/11/2019 | E | | | | | |
| A | TABLE UPDATE | - | - | JJ/MF | 10/05/2005 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE 12KV, TYPE "HNS"
RADIAL, DEAD FRONT,
PAD-MOUNTED TRANSFORMER INSTALLATION



UG3752.1

TABLE OF CONTENTS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, THREE-PHASE | 1 | 3427 | - | - |
| 2 | TRENCH GROUND WIRE (n) | AS REQ'D | 4510 | - | - |
| 3 | TRANSFORMER, (500-2,500 KVA) (D) | 1 | 3702 | - | - |
| 4 | HOLD DOWN DEVICE - (SUPPLIED WITH CABINET0 | 2 | - | - | - |
| 5 | BUSHING PLUG (RADIAL FEED) | AS REQ'D | 4192.1 | S544676 | BSHPLG |
| 6 | FEED-THRU INSERT (LOOP FEED) | AS REQ'D | 4192.1 | S544678 | FEED-I |
| 7 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | AS REQ'D | 4191 | - | - |
| 8 | CONCENTRIC NEUTRAL TAILS | - | 4172.1 | - | - |
| 9 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | - | - |
| 10 | KEYLESS LOCK, (NOT SHOWN ABOVE) (E) | 1 | - | S468010 | - |
| 11 | CABLE IDENTIFICATION TAGS | AS REQ'D | 3202 | - | - |
| 12 | SECONDARY CONNECTIONS | AS REQ'D | 4168, 4171 | - | - |
| 13 | FUSE, "BAY-O-NET" (l) | 3 | 4311 | - | - |
| 14 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | 1 | - | - | - |
| 15 | SEALING COMPOUND (B)(m) | AS REQ'D | - | S442976 | - |
| 16 | SERVICE POST CONNECTOR | 2 | - | S262560 | - |

**NOTES:** NONE

## REFERENCE:

a. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.
b. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.
c. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.
d. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.
(e) SEE STANDARD 3425, 3426 OR 3427 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.
f. SEE STANDARD 3481 FOR BARRIER PROTECTION.
g. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).
h. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.
i. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.
j. SEE STANDARD 3487 FOR RETAINING WALLS.
k. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.
(l) SEE STANDARD 3704 FOR "BAY-O-NET" FUSE OPERATING INSTRUCTIONS.
(m) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.
(n) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.
o. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.
(p) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.
q. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.

© 1998 - 2019 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | FIGURE UPDATE | ADW | JES | CZH | 11/11/2019 | E | | | | | |
| A | TABLE UPDATE | - | - | JJ/MF | 10/05/2005 | D | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE 12KV, TYPE "HNS"
RADIAL, DEAD FRONT,
PAD-MOUNTED TRANSFORMER INSTALLATION




UG3752.2

TABLE OF CONTENTS


**SCOPE:** THIS STANDARD SHOWS THE METHOD OF INSTALLATING A THREE-PHASE, STEP-DOWN TYPE "HPS" RADIAL/LOOP FEED DEAD FRONT PAD-MOUNTED TRANSFORMER.

**225 KVA**




**SCOPE:** THIS STANDARD SHOWS THE METHOD OF INSTALLATING A THREE-PHASE, STEP-DOWN TYPE "HPS" RADIAL/LOOP FEED DEAD FRONT PAD-MOUNTED TRANSFORMER.

**500-2500 KVA**




© 1998 - 2012 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| | X | Indicates Latest Revision | | Completely Revised | | New Page | | Information Removed |

| | | |
|---|---|---|
| 3753.1 | SDG&E ELECTRIC STANDARDS<br>THREE-PHASE STEP-DOWN, TYPE "HPS", RADIAL, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION | REVISION<br>DATE 11-8-2011<br>APPD TR/MJC |

TABLE OF CONTENTS

**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | QUANTITY | | | STANDARD OR STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|---|
| | | PRIMARY | SECONDARY | | | |
| | | | 200A | 600A | | |
| 1 | PAD, TRANSFORMER, THREE-PHASE | 1 | – | – | 3427 | – |
| 2 | TRENCH GROUND WIRE (W) | AS REQ'D | – | – | 4510 | – |
| 3a | TRANSFORMER, 225 KVA (H) (F) | 1 | – | – | 3702 | – |
| 3b | TRANSFORMER, 500-2500 KVA (B) (F) | 1 | – | – | 3702 | – |
| 4 | NUT, CLAMPING CHANEL | 2 | – | – | 503520 | – |
| 5 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 2 | – | – | 616192 | – |
| 6 | WASHER, FLAT, ROUND, BRONZE, 1/2" | 2 | – | – | 799488 | – |
| 7 | FUSE, "BAY-O-NET" (SUPPLIED WITH TRANSFORMER) (U) | 3 | – | – | 4311 | – |
| 8 | KEYLESS LOCK (NOT SHOWN) (G) | 1 | – | – | 468010 | – |
| 9 | BUSHING WELL & BUSHING (RADIAL ONLY) (A) | 3 | – | – | – | – |
| 10 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) (A) (B) RADIAL FEED | 3 | 3 | AS REQ'D | 4191 | – |
| 11 | CABLE IDENTIFICATION TAGS | AS REQ'D | | | 3202 | – |
| 12 | CONCENTRIC NEUTRAL TAILS (OR EQUIVALENT WIRE SIZE) | – | – | – | 4172.1 | – |
| 13 | CONNECTOR, COMPRESSION (SIZE AS REQ'D) | AS REQ'D | | | 4172.2 | – |
| 14 | SERVICE POST CONNECTOR (AND 1/2" STAINLESS STEEL SPRING WASHER AS REQ'D) | 1 | – | – | 262560 | – |
| | | – | 1 | 1 | 262656 | – |
| 15 | ELBOW, TEE, 600A (B) | – | – | AS REQ'D | 326578 | ELBO-T |
| 16 | BUSHING EXTENSION (B) | – | – | AS REQ'D | 336204 | BUSH-X |
| 17 | 600/200 AMP REDUCING TAP WELL (B) | – | – | 3 | 719600 | REDTAP |
| 18 | LOADBREAK BUSHING PLUG (B) | – | – | 3 | 544676 | BSHPLG |
| 19 | 200 AMP INSULATING RECEPTICAL (A) (B) | AS REQ'D | – | AS REQ'D | 204304 | INSREC |
| 20 | CONDUCTOR CONNECTOR (B) 350 AL | – | – | AS REQ'D | 258698 | SPD350 |
| | 750 AL | – | – | AS REQ'D | 258704 | SPD750 |
| | 1000 AL | – | – | AS REQ'D | 258702 | SP1000 |
| 21 | CABLE ADAPTER (B) 350 AL | – | – | AS REQ'D | 102027 | ADP350 |
| | 750 AL | – | – | AS REQ'D | 102034 | APD750 |
| | 1000 AL | – | – | AS REQ'D | 102050 | AD1MIL |
| 22 | WIRE, BARE STRANDED COPPER, #2 | AS REQ'D | | | 812816 | GDWIRE |
| 23 | SEALING COMPOUND (C) (V) | AS REQ'D | | | 442976 | – |

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

REVISION
DATE 5-11-05
APPD MF / JJ

SDG&E ELECTRIC STANDARDS

THREE-PHASE STEP-DOWN, TYPE "HPS", RADIAL, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION

3753.2

TABLE OF CONTENTS

**INSTALLATION:**

(A) PRIMARY SIDE OF TRANSFORMER USES 3 CONDUCTOR #2 OR 2/0 PRIMARY CABLES. THE TRANSFORMER IS FITTED WITH BUSHING WELLS AND BUSHING INSERTS. THIS TRANSFORMER IS TO BE USED IN RADIAL APPLICATIONS ONLY.

(B) 500 THRU 2500 KVA TRANSFORMER HAVE 600 AMP DEADBREAK BUSHINGS ON THE SECONDARY SIDE. THESE BUSHINGS WILL ACCEPT EITHER 600 OR 200 AMP CONNECTIONS, DEPENDING ON ON THE SIZE OF CABLE BEING INSTALLED.

(C) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(D) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(F) TRANSFORMER RATING AND SIZE PER WORK ORDER.

(G) KEYLESS LOCK (ITEM 8) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AFTER PENTAHEAD BOLT IS THREADED IN COMPLETELY. PENTAHEAD BOLTS MAY NOT BE AVAILABLE ON SOME RE-FURBISHED TRANSFORMERS.

H. 225 KVA TRANSFORMERS HAVE 200 AMP LOAD BREAK BUSHINGS ON THE SECONDARY SIDE. THESE BUSHINGS ACCEPT LOAD BREAK ELBOWS APPROPRIATE FOR THE SIZE OF CABLE BEING INSTALLED.

**REFERENCE:**

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(N) SEE STANDARD 3425 OR 3426 FOR PAD AND CONDUIT PLACEMENT.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S. SEE STANDARD 3487 FOR RETAINING WALLS.

T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

(U) SEE STANDARD 3704 FOR HIGH AMPERE "BAY-O-NET" FUSE OPERATING INSTRUCTIONS.

(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(W) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

X. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.


© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |
|---|---|---|---|---|---|---|---|

| | SDG&E ELECTRIC STANDARDS | |
|---|---|---|
| 3753.3 | THREE-PHASE STEPDOWN, TYPE "HPS", RADIAL, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION | REVISION<br>DATE 5-11-05<br>APPD MF / JJ |

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE METHOD OF INSTALLATING A THREE–PHASE, STEP–DOWN TYPE "HPB" RADIAL/LOOP FEED DEAD FRONT PAD–MOUNTED TRANSFORMER.




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | | QUANTITY PRIMARY | QUANTITY SECONDARY 200A | QUANTITY SECONDARY 600A | STANDARD OR STOCK NUMBER |
|---|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, THREE–PHASE | | 1 | – | – | 3425, 3426 |
| 2 | TRENCH GROUND WIRE (W) | | AS REQ'D | – | – | 4510 |
| 3 | TRANSFORMER, INCLUDING HOLDDOWN DEVICE (F) | | 1 | – | – | 3702 |
| 4 | NUT, CLAMPING CHANEL | | 2 | – | – | 503520 |
| 5 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | | 2 | – | – | 616192 |
| 6 | WASHER, FLAT, ROUND, BRONZE, 1/2" | | 2 | – | – | 799488 |
| 7 | FUSE, "BAY–O–NET" (SUPPLIED WITH TRANSFORMER) (U) | | 3 | – | – | 4311 |
| 8 | KEYLESS LOCK (NOT SHOWN) (G) | | 1 | – | – | 468010 |
| 9 | FEED–THRU INSERT (RADIAL OR LOOP FEED) (A) | | 3 | – | – | 544678 |
| 10 | ELBOW, LOADBREAK, 12KV (WITH WHITE–BLACK–WHITE BAND) (A B) | RADIAL FEED | 3 | 3 | AS REQ'D | 4191 |
| | | LOOP FEED | 6 | 3 | AS REQ'D | |
| 11 | CABLE IDENTIFICATION TAGS | | AS REQ'D | | | 3202 |
| 12 | CONCENTRIC NEUTRAL TAILS (OR EQUIVALENT WIRE SIZE) | | – | – | – | 4172.1 |
| 13 | CONNECTOR, COMPRESSION (SIZE AS REQ'D) | | AS REQ'D | | | 4172.2 |
| 14 | SERVICE POST CONNECTOR (AND 1/2" STAINLESS STEEL SPRING WASHER AS REQ'D) | | 1 | – | – | 262560 |
| | | | – | 1 | 1 | 262656 |

© 1998 - 2012 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|

| 3755.1 | SDG&E ELECTRIC STANDARDS<br>THREE–PHASE STEP–DOWN, TYPE "HPB", RADIAL/LOOP, DEAD FRONT, PAD–MOUNTED TRANSFORMER INSTALLATION | REVISION<br>DATE 11–8–2011<br>APPD TR/MJC |
|---|---|---|

TABLE OF CONTENTS

**BILL OF MATERIAL:** (CONT'D)

| ITEM | DESCRIPTION | | QUANTITY PRIMARY | QUANTITY SECONDARY 200A | QUANTITY SECONDARY 600A | STANDARD OR STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|---|---|
| 15 | ELBOW, TEE, 600A (B) | | – | – | AS REQ'D | 326578 | ELBO–T |
| 16 | BUSHING EXTENSION (B) | | – | – | AS REQ'D | 336204 | BUSH–X |
| 17 | 600/200 AMP REDUCING TAP WELL (B) | | – | – | 3 | 719600 | REDTAP |
| 18 | LOADBREAK BUSHING PLUG (B) | | – | – | 3 | 544676 | BSHPLG |
| 19 | 200 AMP INSULATING RECEPTICAL (A)(B) | | AS REQ'D | – | AS REQ'D | 204304 | INSREC |
| 20 | CONDUCTOR CONNECTOR (B) | 350 AL | – | – | AS REQ'D | 258698 | SPD350 |
| | | 750 AL | – | – | AS REQ'D | 258704 | SPD750 |
| | | 1000 AL | – | – | AS REQ'D | 258702 | SP1000 |
| 21 | CABLE ADAPTER (B) | 350 AL | – | – | AS REQ'D | 102027 | ADP350 |
| | | 750 AL | – | – | AS REQ'D | 102034 | APD750 |
| | | 1000 AL | – | – | AS REQ'D | 102050 | AD1MIL |
| 22 | WIRE, BARE STRANDED COPPER, #2 | | AS REQ'D | | | 812816 | GDWIRE |
| 23 | SEALING COMPOUND (C)(V) | | AS REQ'D | | | 442976 | – |

**INSTALLATION:**

(A) PRIMARY SIDE OF TRANSFORMER USES FROM 3 TO 6 SINGLE CONDUCTOR #2 OR 2/0 PRIMARY CABLES. THE TRANSFORMER IF FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS. FOR THE RADIAL OR LOOP FEED APPLICATION, THREE FEED–THRU INSERTS ARE REQUIRED. FOR RADIAL APPLICATION USE 200 AMP INSULATING RECEPTACLES ON SPARE POSITIONS.

(B) SECONDARY SIDE OF TRANSFORMER HAVE 600 AMP BUSHINGS ON TRANSFORMERS RATED 500 KVA AND ABOVE. THE 600 AMP BUSHINGS MAY REQUIRE EITHER 200 OR 600 AMP CONNECTIONS DEPENDING ON LOAD REQUIREMENTS. THE 200 AMP CONNECTIONS INSTALLED ON 600 AMP BUSHINGS REQUIRE BUSHING EXTENSIONS, REDUCING TAP WELLS, LOADBREAK BUSHING PLUGS AND LOADBREAK ELBOWS. THE 600 AMP CONNECTIONS REQUIRE 600 AMP TEES, REDUCING TAP WELLS, LOADBREAK BUSHING PLUGS AND INSULATING RECEPTACLES. TRANSFORMERS RATED LESS THAN 500 KVA HAVE 200 AMP LOADBREAK BUSHINGS. THESE INSTALLATIONS REQUIRE 200 AMP LOADBREAK ELBOWS. 200 AMP BUSHING PARKING STANDS ARE PROVIDED ON ALL TRANSFORMERS.

(C) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6).

(D) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(F) TRANSFORMER RATING AND SIZE PER WORK ORDER.

(G) KEYLESS LOCK (ITEM 8) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AFTER PENTAHEAD BOLT IS THREADED IN COMPLETELY. PENTAHEAD BOLTS MAY NOT BE AVAILABLE ON SOME RE–FURBISHED TRANSFORMERS.

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.



TABLE OF CONTENTS

**REFERENCE:**

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(N) SEE STANDARD 3425 OR 3426 FOR PAD AND CONDUIT PLACEMENT.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S. SEE STANDARD 3487 FOR RETAINING WALLS.

T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

(U) SEE STANDARD 3704 FOR "BAY-O-NET" FUSE OPERATING INSTRUCTIONS.

(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(W) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

X. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.


TABLE OF CONTENTS

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|---|

| | SDG&E ELECTRIC STANDARDS | REVISION |
|---|---|---|
| 3755.3 | THREE-PHASE STEPDOWN, TYPE "HPB", RADIAL/LOOP, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION | DATE 1-1-91<br>APPD JLB/RDG |

**SCOPE:** THIS STANDARD SHOWS THE CONNECTION USED FOR INSTALLING THREE-PHASE, 12KV RADIAL DEAD FRONT PAD-MOUNTED TRANSFORMERS, TYPE "HYS".




INSTALLATION:

(A) THIS INSTALLATION USES FROM 3 TO 6 SINGLE-PHASE CONDUCTOR #2 OR 2/0 PRIMARY CABLES. THE TRANSFORMER IS FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS. FOR THE RADIAL APPLICATION, THREE BUSHING PLUGS ARE REQUIRED, ITEM 5 IN THE BILL OF MATERIAL. FOR THE LOOP FEED APPLICATION, THREE FEED-THRU INSERTS ARE REQUIRED, ITEM 6 IN THE BILL OF MATERIAL.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O 128 RULE 31.6).

(C) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(D) TRANSFORMER RATING AND SIZE PER WORK ORDER.

(E) KEYLESS LOCK (ITEM 10) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AFTER PENTAHEAD BOLT IS THREADED IN COMPLETELY.

(F) PARTIAL RANGE CURRENT LIMITING FUSES ARE UNDER OIL IN THE TANK IN LIEU OF ISOLATION SEE TABLE BELOW FOR SIZES. KEARNY TO RE-FUSE AT THE KEARNY SHOP.

| KVA | AMPS | PART NUMBER | STOCK NUMBER |
|---|---|---|---|
| 300 | 65 | HTSS242065 | S365770 |
| 1000 | 150 | HTSS242150 | S365774 |
| 2000 | 250 | (2) HTSS242125 | S365772 |

(H) DO NOT OPEN PRIMARY GROUND WHILE TRANSFORMER IS ENERGIZED.

© 1998 - 2016 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | ORIGINAL ISSUE | PS | JS | MDJ | 3/13/2017 | D | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

THREE-PHASE 12KV, TYPE "HYS" RADIAL, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION



UG 3756.1

TABLE OF CONTENTS

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD. OR PAGE NO | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, THREE-PHASE | 1 | 3425,3426,3427 | -- | -- |
| 2 | TRENCH GROUND WIRE (W) | AS REQ'D | 4510 | -- | -- |
| 3 | TRANSFORMER (D) | 1 | 3702 | -- | -- |
| 4 | HOLD DOWN DEVICE - (SUPPLIED WITH CABINET) | 2 | -- | -- | -- |
| 5 | BUSHING PLUG (RADIAL FEED) (A) | 3 | 4192 | 544678 | FEED-I |
| 7 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | AS REQ'D | 4191 | -- | -- |
| 8 | CONCENTRIC NEUTRAL TAILS | -- | 4172.1 | -- | -- |
| 9 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | -- | -- |
| 10 | KEYLESS LOCK, (NOT SHOWN ABOVE) (E) | 1 | -- | 468010 | -- |
| 11 | CABLE IDENTIFICATION TAGS | AS REQ'D | 3202 | -- | -- |
| 12 | SECONDARY CONNECTIONS | AS REQ'D | 4168, 4171 | -- | -- |
| 13 | FUSE, "BAY-O-NET" (U) | 3 | 4311 | -- | -- |
| 14 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | 1 | -- | -- | -- |
| 15 | SEALING COMPOUND (B) (V) | AS REQ'D | -- | 442976 | -- |
| 16 | SERVICE POST CONNECTOR | 2 | -- | 262560 | -- |

## REFERENCE:

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.
K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.
I. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.
M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.
(N) SEE STANDARD 3425. 3426 OR 3427 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.
O. SEE STANDARD 3481 FOR BARRIER PROTECTION.
P. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).
Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.
R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.
S. SEE STANDARD 3487 FOR RETAINING WALLS.
T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.
(U) SEE STANDARD 3704 FOR "BAY-O-NET" FUSE OPERATING INSTRUCTIONS.
(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.
(W) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.
X. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.
(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.
Z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2016 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | ORIGINAL ISSUE | PS | JS | MDJ | 3/13/2017 | D | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARD

THREE-PHASE 12KV, TYPE "HYS" RADIAL, DEAD FRONT, PAD-MOUNTED TRANSFORMER INSTALLATION



UG 3756.2

**SCOPE:** THIS STANDARD SHOWS THE CONNECTION USED FOR INSTALLING A THREE-PHASE, 75 KVA HBSC "COMPACT" 12KV RADIAL FEED DEAD FRONT PAD-MOUNTED TRANSFORMER.




## INSTALLATION:

(A) THIS INSTALLATION USES FROM 3 TO 6 SINGLE-PHASE CONDUCTOR #2 OR 2/0 PRIMARY CABLES. THE TRANSFORMER IS FITTED WITH BUSHING WELLS THAT REQUIRE SEPARATELY INSTALLED BUSHING INSERTS. FOR THE RADIAL APPLICATION, THREE BUSHING PLUGS ARE REQUIRED, ITEM 5 IN THE BILL OF MATERIAL.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O 128 RULE 31.6).

(C) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(D) KEYLESS LOCK (ITEM 10) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AFTER PENTAHEAD BOLT IS THREADED IN COMPLETELY.

(E) THIS TRANSFORMER IS INSTALLED ON A 3421 SINGLE PHASE PAD.

TABLE OF CONTENTS

© 1998 - 2016 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | ORIGINAL ISSUE | KR | JS | MDJ | 3/31/2017 | D | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

THREE-PHASE 12KV, TYPE 75KVA "HBSC" COMPACT RADIAL, DEAD FRONT, PAD MOUNTED TRANSFORMER INSTALLATION

UG 3757.1

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD. OR PG NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, SINGLE-PHASE | 1 | 3421 | S514240 | 3421-1 |
| 2 | TRANSFORMER GROUND WIRE (w) | AS REQ'D | 4510 | -- | -- |
| 3 | TRANSFORMER (75kVA) | 1 | 3702 | S765102 | HBSC75 |
| 4 | HOLD DOWN DEVICE - (SUPPLIED WITH CABINET) | 2 | -- | -- | -- |
| 5 | BUSHING PLUG (RADIAL FEED) (A) | 3 | 4192 | S544676 | BSHPLG |
| 7 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) | AS REQ'D | 4191 | -- | -- |
| 8 | CONCENTRIC NEUTRAL TAILS | -- | 4172.1 | -- | -- |
| 9 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | -- | -- |
| 10 | KEYLESS LOCK, (NOT SHOWN ABOVE) (g) | 1 | -- | S468010 | -- |
| 11 | CABLE IDENTIFICATION TAGS | AS REQ'D | 3202 | -- | -- |
| 12 | SECONDARY CONNECTIONS | AS REQ'D | 4168, 4171 | -- | -- |
| 13 | FUSE, "BAY-O-NET" (u) | 3 | 4311 | -- | -- |
| 14 | NEUTRAL GROUND STRAP (ON TRANSFORMER) | 1 | -- | -- | -- |
| 15 | SEALING COMPOUND (B)(v) | AS REQ'D | -- | S442976 | -- |
| 16 | SERVICE POST CONNECTOR | 2 | -- | S262560 | -- |

## REFERENCE:

j. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

k. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

l. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

m. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

(n) SEE STANDARD 3421 FOR PAD, HANDHOLE AND CONDUIT PLACEMENT.

o. SEE STANDARD 3481 FOR BARRIER PROTECTION.

p. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

r. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

s. SEE STANDARD 3487 FOR RETAINING WALLS.

t. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

(u) SEE STANDARD 3704 FOR "BAY-O-NET" FUSE OPERATING INSTRUCTIONS.

(v) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(w) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

x. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

(y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.

TABLE OF CONTENTS

© 1998 - 2016 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | BY | DSGN | APPV | DATE | REV | CHANGE | BY | DSGN | APPV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | F | | | | | |
| B | | | | | | E | | | | | |
| A | ORIGINAL ISSUE | KR | JS | MDJ | 3/31/2017 | D | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

SHEET 2 OF 2


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

THREE-PHASE 12KV, TYPE 75KVA "HBSC" COMPACT RADIAL, DEAD FRONT, PAD MOUNTED TRANSFORMER INSTALLATION

UG 3757.2

**SCOPE:** THIS STANDARD SHOWS THE NGD TRANSFORMER. THIS TRANSFORMER SHALL BE USED WHEN THE CUSTOMER REQUIRES GROUND FAULT INFORMATION.

**NOTE:** THIS TRANSFORMER PROVIDES NO USABLE VOLTAGE.





© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | Indicates Latest Revision | Completely Revised | New Page | Information Removed |
|---|---|---|---|---|

| | | |
|---|---|---|
| 3760.1 | SDG&E ELECTRIC STANDARDS<br>GROUND FAULT DETECTION TRANSFORMER (NGD) | REVISION<br>DATE 3-1-02<br>APPD |

TABLE OF CONTENTS

WIRING DIAGRAM




**BILL OF MATERIAL:**

| ITEM | DESCRIPTION | QUANTITY | CONSTR. STD OR PAGE NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | TRANSFORMER | 1 | 3760.1 | S758302 | NGD–01 |
| 2 | EQUIPMENT PAD | 1 | 3421.3 | S51420 | FC3PAD |
| 3 | HANDHOLE 17430 | 1 | 3312 | S16426 | – |
| 4 | ELBOW LOADBREAK | 3 | 4191 | – | – |
| 5 | TRENCH GROUND | 1 | 4510.1 | – | TG–TW |
| 6 | CABLE IDENTIFICATION TAG | AS REQ'D | 3202 | – | – |
| 7 | POTENTIAL TRANSFORMER | 3 | – | – | – |
| 8 | CURRENT LIMITING FUSE | | | | – |
| 9 | SECONDARY CONDUIT | 1 | – | – | – |
| 10 | SECONDARY COMPARTMENT | 1 | – | – | – |
| 11 | DICCONNECT SWITCH | 1 | – | – | – |
| 12 | FUSE HOLDER | | – | – | – |
| 13 | FUSE 10 AMP | 1 | – | S363968 | – |
| 14 | SECONDARY TERMINATION | 1 | – | – | – |
| 15 | SERVICE POST CONNECTOR | 1 | – | S262656 | – |
| 16 | CUSTOM CONDUIT | 1 | – | – | – |
| 17 | KEYLESS LOCK | 2 | – | S468010 | – |
| 18 | SEALING COMPOUND | AS REQ'D | | S442976 | – |
| 19 | SERVICE CONDUCTORS | AS REQ'D | BY CUSTOMER | – | – |

© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

Indicates Latest Revision | Completely Revised | New Page | Information Removed

REVISION
DATE 3–1–02
APPD

SDG&E ELECTRIC STANDARDS

GROUND FAULT DETECTION
TRANSFORMER (NGD)

3760.2

**INSTALLATION:**

(A) PRIMARY SIDE OF TRANSFORMER USES 3 CONDUCTOR #2 PRIMARY CABLES. THE TRANSFORMER IS FITTED WITH BUSHING WELLS AND BUSHING INSERTS. THIS TRANSFORMER IS TO BE USED IN RADIAL APPLICATIONS ONLY.

(B) SECONDARY CONNECTIONS ARE MADE IN THE SECONDARY COMPARTMENT ACCESSED FROM THE SIDE OF THE TRANSFORMER. REFER TO THE WIRING DIAGRAM.

(C) TERMINATE PRIMARY AND SECONDARY CONDUITS 3 INCHES ABOVE THE BOTTOM OF THE 3312. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND.

(D) THE TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(E) SECURE THE TRANSFORMER WITH PENTAHEAD BOLTS AND KEYLESS LOCKS AS NECESSARY.

NOTE: GROUND THE CUSTOMERS GROUND CONDUCTOR (GREEN WIRE) TO THE SERVICE POST CONNECTOR IN THE PRIMARY COMPARTMENT.

WARNING: NEVER OPERATE THE DISCONNECT SWITCH IN THE SECONDARY COMPARTMENT WITHOUT CONTACTING THE CUSTOMER FIRST.

**REFERENCE:**

J. SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

N. SEE STANDARD 3421 FOR PAD, HANDHOLE PLACEMENT.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S. SEE STANDARD 3487 FOR RETAINING WALLS.

T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

(U) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(V) SEE STANDARD 4510 FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE.

(W) SEE STANDARD PAGE 4512.1 FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION.

X. SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

(Y) SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PAD-MOUNTED EQUIPMENT.


© 1998 - 2005 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.





TABLE OF CONTENTS

**SCOPE:** THIS TRANSFORMER SHOULD BE RESTRICTED TO THE REPLACEMENT OF EXISTING LIVE-FRONT TRANSFORMERS WITH MORE THAN TWO PHASES OR MORE THAN TWO CONDUCTORS PER PHASE PASSING THROUGH. A DEVIATION IS REQUIRED FOR ALL OTHER INSTALLATIONS. SOME APPLICATIONS MAY REQUIRE A 3523 TERMINATOR TO BE INSTALLED.

THIS STANDARD SHOWS SOME TYPICAL CONFIGURATIONS USING THE NCS TRANSFORMER AND THE ELASTIMOLD ADJUSTABLE JUNCTION TAPS.






ACTUAL FIELD INSTALLATION OF SKETCH IN THE DEPICTION ON THE LEFT.

© 1998 - 2010 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |
|---|---|---|---|---|---|---|---|

| REVISION | SDG&E ELECTRIC STANDARDS | |
|---|---|---|
| DATE 11-18-08<br>APPD TR / MC | SINGLE-PHASE, 6930 VOLT, TYPE "NCS"<br>PAD-MOUNT TRANSFORMER INSTALLATION | 3770.1 |

TABLE OF CONTENTS

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD OR PG NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, SINGLE-PHASE | 1 | 3421 | 514240 | 3421.1 |
| 2 | TRENCH GROUND WIRE (W) | AS REQ'D | 4510 | -- | |
| 3 | TRANSFORMER, (NCS) | 1 | 3702 | S750312 | NCS-25 |
| | | | | S750350 | NCS-50 |
| | | | | S750352 | NCS-100 |
| 4 | HOLD DOWN DEVICE - (SUPPLIED WITH CABINET) | 2 | -- | -- | |
| 5 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) (C) | AS REQ'D | 4191 | -- | |
| 6 | CONCENTRIC NEUTRAL TAILS | AS REQ'D | -- | -- | |
| 7 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | -- | |
| 8 | KEYLESS LOCK, (NOT SHOWN ABOVE) (H) | 1 | -- | 468010 | |
| 9 | CABLE IDENTIFICATION TAGS (J) | AS REQ'D | 3202 | -- | |
| 10 | SECONDARY CONNECTIONS (D) | AS REQ'D | 4167 | -- | |
| 11 | NEUTRAL GROUND STRAP (SUPPLIED WITH TRANSFORMER) | 1 | -- | -- | |
| 12 | CONDUIT SEALING SYSTEM (B) | AS REQ'D | -- | 442976 | |
| 13 | SERVICE POST CONNECTOR | 4 | -- | 262560 | |
| 14 | VOLTAGE TAP CHANGER SWITCH | 1 | -- | -- | |
| 15 | BAYONET FUSE | 1 | -- | -- | |
| 16 | GROUND WIRE | AS REQ'D | -- | -- | |
| 17 | FEED-THRU INSERT BUSHING | 1 | 4192 | 544678 | FEED-I |
| 18 | 2-WAY ADJUSTABLE JUNCTION TAP | AS REQ'D | -- | 182002 | 2WYAFT |
| 19 | 3-WAY ADJUSTABLE JUNCTION TAP | AS REQ'D | -- | 305710 | 3WYAFT |
| 20 | 4-WAY ADJUSTABLE JUNCTION TAP | AS REQ'D | -- | 305712 | 4WYAFT |
| 21 | CAP, INSULATING RECEPTACLE (I) | AS REQ'D | 3202 | 204304 | INSREC |
| 22 | 3312 HANHOLE | AS REQ'D | 3421.1, .2 | 162462 | FC3PAD |
| 23 | | 1 | | | |
| 24 | | 1 | | | |
| 25 | | 1 | | | |

## NOTES:

1. EXISTING CABLES CAN BE SPLICED TO FACILITATE THE LOADBREAK ELBOWS FOR THIS INSTALLATION.
2. REPLACE EXISTING PAD, IF EXISTING PAD IS NOT CURRENT 44" X 46" 3421 PAD.
3. INSTALL A 3312 HANDHOLE TO FACILITATE CABLE TRAINING IF NEEDED, LOWER CONDUITS AS NEEDED FOR CABLE TRAINING.

© 1998 - 2010 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.



TABLE OF CONTENTS

## INSTALLATION:

(A) MAXIMUM NUMBER OF PRIMARY CABLES SHOULD NOT EXCEED 8 CONDUCTORS.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH EITHER CONDUIT BREAK-OUT BOOTS OR RAYFLATE. INFLATABLE DUCT SEAL PACKAGE AS DESCRIBED IN 3948. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6.).

(C) PROVIDE AS MANY LOADBREAK ELBOWS AS REQUIRED TO TERMINATE ALL PRIMARY CONNECTORS.

(D) SET SCREW CONNECTORS ARE NOT PROVIDED WITH TRANSFORMER, SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER.

(F) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (STANDARD 3408).

(H) KEYLESS LOCK (ITEM 8) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AND PENTAHEAD BOLT THREADED IN COMPLETELY.

(I) REDUCE LOADBREAK ELBOW QUANTITY AND INSTALL INSULATING RECEPTACLE IF CABLES ARE NOT INSTALLED SIMULTANEOUSLY.

## REFERENCE:

(J) SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

N SEE STANDARD 3421 FOR PAD AND CONDUIT PLACEMENT.

O SEE STANDARD 3481 FOR BARRIER PROTECTION.

P SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S SEE STANDARD 3487 FOR RETAINING WALL.

T SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

U SEE STANDARD 3703 FOR TRANSFORMER APPLICATIONS.

(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(W) SEE STANDARD 4510 FOR (PREFERRED I ) AND (ALTERNATE) TRENCH GROUND WIRE.

X SEE STANDARD PAGE 4512.1 FOR (PREFERRED II ) EQUIPMENT GROUNDING INSTALLATION.

(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Z SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PADMOUNTED EQUIPMENT.

TABLE OF CONTENTS


© 1998 - 2008 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |
|---|---|---|---|---|---|---|---|

| REVISION<br>DATE 11-6-08<br>APPD TR / MC | SDG&E ELECTRIC STANDARDS<br>SINGLE-PHASE, 6930 VOLT, TYPE "NCS"<br>PAD-MOUNT TRANSFORMER INSTALLATION | 3770.3 |
|---|---|---|

**SCOPE:** THIS TRANSFORMER SHOULD BE RESTRICTED TO THE REPLACEMENT OF EXISTING LIVE-FRONT TRANSFORMERS WITH MORE THAN TWO PHASES OR MORE THAN TWO CONDUCTORS PER PHASE PASSING THROUGH. A DEVIATION IS REQUIRED FOR ALL OTHER INSTALLATIONS. SOME APPLICATIONS MAY REQUIRE A 3523 TERMINATOR TO BE INSTALLED.

THIS STANDARD SHOWS SOME TYPICAL CONFIGURATIONS USING THE HCS TRANSFORMER AND THE ELASTIMOLD ADJUSTABLE JUNCTION TAPS.




1. No-load Tap changer
2. Stock number plate
3. Secondary stud bushings
4. Tank ground strap
5. Bayonet fuses
6. Bushing wells H1A, H1B and H2A, H2B
7. Standoff support brackets
8. Diagram Nameplate
9. Pressure Relief Valve
10. Fill plug
11. Compartment lift tab and penta bolt and lock provision
12. Ground nut points
13. 3421 pad
14. 3312 handhole
15. Transformer tie down unistrut stud, 1/2" nut & washer




ACTUAL FIELD INSTALLATION OF SKETCH IN THE DEPICTION ON THE TOP.

© 1998 - 2013 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |
|---|---|---|---|---|---|---|---|

| REVISION DATE 9-25-2013 APPD TR / DW | SDG&E ELECTRIC STANDARDS<br>SINGLE-PHASE DELTA, 12000 VOLT, TYPE "HCS" PAD-MOUNT TRANSFORMER INSTALLATION | 3771.1 |
|---|---|---|

TABLE OF CONTENTS

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | CONST STD OR PG NO. | STOCK NUMBER | ASSEMBLY UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, SINGLE-PHASE | 1 | 3421 | S514240 | 3421.1 |
| 2 | TRENCH GROUND WIRE (W) | AS REQ'D | 4510 | -- | |
| 3 | TRANSFORMER, (HCS) | 1 | 3702 & 3771 | S751300 | HCS-25 |
| | | | | S751302 | HCS-50 |
| | | | | S751304 | HCS100 |
| | | | | S751306 | HCS167 |
| 4 | HOLD DOWN DEVICE - (SUPPLIED WITH CABINET) | 2 | -- | -- | |
| 5 | ELBOW, LOADBREAK, 12KV (WITH WHITE-BLACK-WHITE BAND) (C) | AS REQ'D | 4191 | -- | |
| 6 | CONCENTRIC NEUTRAL TAILS | AS REQ'D | -- | -- | |
| 7 | CONNECTOR, COMPRESSION | AS REQ'D | 4172 | -- | |
| 8 | KEYLESS LOCK, (NOT SHOWN ABOVE) (H) | 1 | -- | S468010 | |
| 9 | CABLE IDENTIFICATION TAGS (J) | AS REQ'D | 3202 | -- | |
| 10 | SECONDARY CONNECTIONS (D) | AS REQ'D | 4167 | -- | |
| 11 | NEUTRAL GROUND STRAP (SUPPLIED WITH TRANSFORMER) | 1 | -- | -- | |
| 12 | CONDUIT SEALING SYSTEM (B) | AS REQ'D | -- | S442976 | |
| 13 | SERVICE POST CONNECTOR | 3 | -- | S262560 | |
| 14 | NO-LOAD TAP CHANGER | 1 | -- | -- | |
| 15 | BAYONET FUSE SEE STD. 4311.5 | AS REQ'D | 4311.5 | -- | |
| 16 | GROUND WIRE | AS REQ'D | -- | -- | |
| 17 | FEED-THRU INSERT BUSHING | AS REQ'D | 4192 | S544678 | FEED-I |
| 18 | 2-WAY ADJUSTABLE JUNCTION TAP | AS REQ'D | -- | S182002 | 2WYAFT |
| 19 | 3-WAY ADJUSTABLE JUNCTION TAP | AS REQ'D | -- | S305710 | 3WYAFT |
| 20 | BUSHING PLUG | AS REQ'D | 4192 | S544676 | BSHPL6 |
| 21 | CAP, INSULATING RECEPTACLE (I) | AS REQ'D | 3202 | S204304 | INSREC |
| 22 | 3312 HANHOLE | AS REQ'D | 3421.1, .2 | S162462 | FC3PAD |
| 23 | | 1 | | | |
| 24 | | 1 | | | |
| 25 | | 1 | | | |

**NOTES:**

1. EXISTING CABLES CAN BE SPLICED TO FACILITATE THE LOADBREAK ELBOWS FOR THIS INSTALLATION.
2. REPLACE EXISTING PAD, IF EXISTING PAD IS NOT CURRENT 44" X 46" 3421 PAD.
3. INSTALL A 3312 HANDHOLE TO FACILITATE CABLE TRAINING IF NEEDED, LOWER CONDUITS AS NEEDED FOR CABLE TRAINING.

© 1998 - 2013 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| Indicates Latest Revision | Completely Revised | X | New Page | Information Removed |
|---|---|---|---|---|

| | SDG&E ELECTRIC STANDARDS | REVISION |
|---|---|---|
| 3771.2 | SINGLE-PHASE DELTA, 12000 VOLT, TYPE "HCS" PAD-MOUNT TRANSFORMER INSTALLATION | DATE 9-25-2013<br>APPD TR / DW |

TABLE OF CONTENTS

**INSTALLATION:**

(A) MAXIMUM NUMBER OF PRIMARY CABLES SHOULD NOT EXCEED 9 CONDUCTORS.

(B) TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH EITHER CONDUIT BREAK-OUT BOOTS OR RAYFLATE. INFLATABLE DUCT SEAL PACKAGE AS DESCRIBED IN 3948. SEAL SERVICE LATERAL CONDUITS PER STANDARD 3948 (G.O. 128 RULE 31.6.).

(C) PROVIDE AS MANY LOADBREAK ELBOWS AS REQUIRED TO TERMINATE ALL PRIMARY CONNECTORS.

(D) SET SCREW CONNECTORS ARE NOT PROVIDED WITH TRANSFORMER, SEE STANDARD 4167 FOR INSTALLATION AND STOCK NUMBERS. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER.

(F) TRANSFORMER SHALL BE SOLIDLY SECURED TO PAD TO PREVENT UNAUTHORIZED MOVEMENT OR ENTRY. THE BASE SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY (STANDARD 3408).

(H) KEYLESS LOCK (ITEM 8) TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AND PENTAHEAD BOLT THREADED IN COMPLETELY.

(I) REDUCE LOADBREAK ELBOW QUANTITY AND INSTALL INSULATING RECEPTACLE IF CABLES ARE NOT INSTALLED SIMULTANEOUSLY.

**REFERENCE:**

(J) SEE STANDARD 3202 FOR CABLE IDENTIFICATION.

K. SEE STANDARD 3212 FOR TRANSFORMER IDENTIFICATION.

L. SEE STANDARD 3221 FOR HIGH VOLTAGE DECAL.

M. SEE STANDARD 3408 FOR WIRE ENTRY PREVENTION.

N. SEE STANDARD 3421 FOR PAD AND CONDUIT PLACEMENT.

O. SEE STANDARD 3481 FOR BARRIER PROTECTION.

P. SEE STANDARD 3483 FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT).

Q. SEE STANDARD 3484 FOR PAD INSTALLATION OF PAD-MOUNTED EQUIPMENT.

R. SEE STANDARD 3486 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

S. SEE STANDARD 3487 FOR RETAINING WALL.

T. SEE STANDARD 3702 FOR TRANSFORMER PREFIXES.

U. SEE STANDARD 3703 FOR TRANSFORMER APPLICATIONS.

(V) SEE STANDARD 3948 FOR SEALING SERVICE LATERAL CONDUITS.

(W) SEE STANDARD 4510 FOR (PREFERRED I ) AND (ALTERNATE) TRENCH GROUND WIRE.

X. SEE STANDARD PAGE 4512.1 FOR (PREFERRED II ) EQUIPMENT GROUNDING INSTALLATION.

(Y) SEE STANDARD 4512.2 FOR EQUIPMENT GROUNDING.

Z. SEE STANDARD 4514 FOR GROUNDING TELCO CONDUCTOR IN PADMOUNTED EQUIPMENT.

© 1998 - 2013 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| Indicates Latest Revision | Completely Revised | X | New Page | Information Removed |
|---|---|---|---|---|

| REVISION<br>DATE 9-18-2013<br>APPD TR / DW | SDG&E ELECTRIC STANDARDS<br>SINGLE-PHASE DELTA, 12000 VOLT, TYPE "HCS" PAD-MOUNT TRANSFORMER INSTALLATION | 3771.3 |
|---|---|---|

TABLE OF CONTENTS

| PAGE | SUBJECT |
|---|---|
| 3815 | INSTALLATION OF SCADA 4KV PAD MOUNTED CAPACITOR |
| 3821 | INSTALLATION OF SCADA 600 & 1200 KVAR PAD MOUNTED CAPACITOR |

MAIN TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JK | JS | CZH | 5/18/2018 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CAPACITORS
TABLE OF CONTENTS

UG3801.1

**SCOPE:** THIS STANDARD SHOWS THE EQUIPMENT AND INSTALLATION REQUIREMENTS FOR THE PAD MOUNTED 4KV CAPACITOR, WITH SCADA, 150 & 300 KVAR.





**FIGURE 1** (VI)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



INSTALLATION OF SCADA
4KV PAD MOUNTED CAPACITOR

UG3815.1

TABLE OF CONTENTS

## INSTALLATION:

A. CHECK AND TIGHTEN ALL CONNECTIONS ON CAPACITOR BEFORE INSTALLATION.

B. INSTALL PAD TO FINAL GRADE.

(C) WHEN A SYSTEM NEUTRAL OR GROUNDING BANK NEUTRAL IS PRESENT, FOR UNDERGROUND OR CABLE POLE APPLICATIONS, THE CONCENTRIC NEUTRALS SHALL BE CONNECTED TO THE NEUTRAL. (d) (e)

(D) TERMINATE CONDUIT 3 INCHES ABOVE GROUND LEVEL IN BOX.

(E) SCADA CONTROL AND RADIO; INSTALLED BY KEARNY CREWS.

(F) BASE OF CABINET SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(G) REMOVE LIFTING EYES AND STORE INSIDE THE CABINET ON THE CONTROL SIDE. IF EYES ARE NOT REMOVED, THEY MAY ENCROACH ON PRIVATE PROPERTY RIGHT-OF-WAY OR CAUSE HAZARD TO THE PUBLIC.

(H) WHEN OPERATING CAPACITOR CONTROL SWITCH, REMOVE THE PIN IN THE DOOR ASSEMBLY SO IT WILL OPEN AT 180 DEGREE ANGLE (ALLOWING OPERATION OF THE SWITCH WITHOUT STANDING IN FRONT OF THE CAPACITOR).

(J) THE 3426 PAD MAY BE SUBSTITUTED FOR THE 3414 PAD IF RIGHT-OF-WAY PERMITS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CAPACITOR, SCADA, PAD MOUNTED | 150KVAR | 1 | -- | S206236 | CAP415 |
| | | 300KVAR | 1 | -- | S206240 | CAP430 |
| 2 | PAD, CAPACITOR (IF NEW) | (J) | 1 | -- | S514280 | CAP-PD |
| 3 | BOX, 3312 | (VII) | 1 | 3312 | S162426 | 3312-0 |
| 4 | CONTROL, CAPACITOR, SCADA (PROGRAMMABLE) | (E) | 1 | -- | S274880 | SEL-UC |
| 5 | LOCKS, KEYLESS | (IX) | 2 | -- | S468010 | -- |
| 6 | CONNECTOR, COMPRESSION, COPPER | | 3 | 4174 | S257760 | -- |
| 7 | NUT, CLAMPING CHANNEL | | 2 | -- | S503520 | -- |
| 8 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | | 2 | -- | S616192 | -- |
| 9 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | | 2 | -- | S799488 | -- |
| 10 | EYES, LIFTING, (REMOVABLE) | (G) | 2 | -- | -- | -- |
| 11 | CONNECTOR, SERVICE POST | | 1 | -- | S262560 | -- |
| 12 | NUT, STANDARD HEX, BRONZE, 1/2" | | 1 | -- | S506112 | -- |
| 13 | HOLD DOWN (SUPPLIED WITH CABINET) | | 2 | -- | -- | -- |
| 14 | PIPE, POLYETHYLENE, 1" | | AS REQ'D | -- | S249630 | 1"PE |
| | PIPE, PVC, 3" | | | -- | -- | -- |
| 15 | CONDUIT, 3" | (VIII) | 1 | 3373 | S322048 | 1DB3-B |
| 16 | ANTENNA, SCADA | (IX) (E) | -- | 4645 | S109570 | ANTENA |
| 17 | ADAPTER, ANTENNA | (IX) (E) | 1 | 4645 | S102017 | -- |
| 18 | CABLE, COAX | (E) | AS REQ'D | -- | S191906 | CABANT |
| 19 | CONNECTS, COAX CABLE | (IX) (E) | AS REQ'D | -- | S254170 | CABCON |
| 20 | RADIO, MDS | (IX) (E) | 1 | 4642 | S749500 | MDSRAD |
| 21 | RADIO, MDS, SPREAD SPECT. | (IX) (E) | 1 | 4642 | S749504 | SPREAD |
| 22 | ELBOW, LOADBREAK (IF NEW) | | 3 | 4190 | -- | -- |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**NOTES:**

I. ALL NEW PAD MOUNTED CAPACITORS PURCHASED AFTER 5/14/12 WILL BE SCADA ENABLED UNITS, EQUIPPED WITH THREE VACUUM SWITCHES, LINE VOLTAGE SENSORS AND A NEUTRAL VOLTAGE SENSOR. THE CONTROL UNIT REQUIRES AN ANTENNA. ALL UNITS SHALL HAVE THE SUFFIX "CW" TO THE STATION ID AS ALL WILL BE SCADA/SWITCHED PAD MOUNTED CAPACITOR STATIONS. THE INSTALLATION OF THE 3312 HAND HOLE UNDER THE PAD SHALL BE REQUIRED FOR ALL NEW CONSTRUCTION OF SCADA CAPACITORS.

II. THE LOADBREAK ELBOWS ARE LOCATED ON THE SIDE OF THE CAPACITOR CABINET WITH THE SIGN "CONTROL INSIDE" ON THE DOOR.

III. PHASE IDENTIFICATION MUST BE MARKED USING THE AP 20 OR 30 AT ALL LOCATIONS. POSITION 1 SHALL BE CONNECTED TO A PHASE, POSITION 2 SHALL BE CONNECTED TO B PHASE AND POSITION 3 MUST BE CONNECTED TO C PHASE.

(IV) DECAL: "DANGER HIGH VOLTAGE"

(V) DECAL: "CAUTION-NEUTRAL BUSHING NOT GROUNDED WAIT 5 MINUTES AFTER OPENING CAPACITOR SWITCHES BEFORE OPERATING LOADBREAK ELBOWS"

(VI) SWEEP TO CLEAR SIDE FOR PLACEMENT OF ANTENNA POLE TO 50'-0" MAXIMUM.

(VII) LOCATED UNDER PAD (REQUIRED FOR NEW CONSTRUCTION).

(VIII) FOR STUB ONLY INSTALLATION OR ALTERNATIVE LOCATION (IF APPLICABLE).

(IX) NOT SHOWN ON FIGURES.

**REFERENCE:**

(a) SEE UG3373.

(b) SEE UG4645.

(c) SEE UG3821.

(d) FOR TRENCH GROUNDING, SEE UG4510.

(e) FOR CABLE POLE GROUNDING, SEE OH1002.

(f) FOR (PREFERRED) AND (ALTERNATE) TRENCH GROUND WIRE, SEE UG4510.

(g) FOR EQUIPMENT GROUNDING INSTALLATION, SEE UG4512.

(h) FOR EQUIPMENT GROUNDING, SEE UG4512.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**SCOPE:** SHOWS SCADA CAPACITOR INTERIOR AND LOCATION OF EQUIPMENT IN THE UNIT. LINE SENSORS, NEUTRAL SENSOR, X-LIMITER FUSES, VACUUM SWITCHES, CONTROL, CONTROL WIRING HARNESS, 120V POTENTIAL TRANSFORMER AND 50 & 100KVAR CAPACITOR CELLS.





**FIGURE 1**
TOP VIEW
(SEE TABLE 1)





**FIGURE 2**
REAR VIEW
(SEE TABLE 1)





**FIGURE 3**
SIDE VIEW
(SEE TABLE 1)

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |





**FIGURE 4**
CAPACITOR DIAGRAM

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**TABLE 1**

| CAPACITOR PARTS LIST | | | | | |
|---|---|---|---|---|---|
| **ITEM** | **DESCRIPTION** | | **QUANTITY** | **STANDARD PAGE** | **STOCK NUMBER** |
| 1 | TRANSFORMER, (P.T.), 2,400/4,160 Y | | 1 | -- | -- |
| 2 | FUSE, CURRENT-LIMITING, 0.5A, 14.4KV - GE TYPE J-1 | | 1 | -- | S366456 |
| 3 | FUSE, COMBINED TECHNOLOGIES | 150KVAR, 30A | 3 | -- | -- |
| | | 300KVAR, 60A | 3 | -- | -- |
| 4 | CELLS, CAPACITOR, 2,400V | 50KVAR | 3 | -- | -- |
| | | 100KVAR | 3 | -- | -- |
| 5 | INSULATOR, POST, 110KV BIL | | 9 | -- | -- |
| 6 | SWITCH, VACUUM, CAPACITOR, 15KV, 200A | | 3 | -- | S708420 |
| 7 | PLUG, BUSHING, 14.4KV, 200A | | 3 | 4195 | S544676 |
| 8 | HARNESS, WIRING, VACUUM SWITCH/P.T. | | 1 | -- | -- |
| 9 | HARNESS, WIRING, VOLTAGE/NEUTRAL SENSOR | | 1 | -- | -- |
| 10 | BARRIER, ACRYLIC, CLEAR, 1/4" (REMOVABLE) | | 4 | -- | -- |
| 11 | ROD, COPPER, 3/8", 9" LONG | III | 1 | -- | -- |
| 12 | SENSOR, LINE VOLTAGE | | 3 | -- | -- |
| 13 | SENSOR, NEUTRAL VOLTAGE | | 1 | -- | -- |
| 14 | CONTROL | III | 1 | -- | -- |
| 15 | WIRE, COPPER, #2 STR. | III | -- | -- | -- |
| 16 | NUTS, GROUND, 1/2" - 13 | III | 3 | -- | -- |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**NOTES:**

I. PAD MOUNTED SCADA CAPACITOR 150KVAR (S206236) AND 300KVAR (S206240) ARE DELIVERED FROM THE SUPPLIER WITH ALL THE PARTS LISTED IN THE PART LIST, INCLUDING FUSES, EXCEPT CONTROL AND RADIO.

II. VACUUM SWITCH CAN BE OPENED MANUALLY OR ELECTRICALLY. VACUUM SWITCH CAN ONLY BE CLOSED ELECTRICALLY.

(III) NOT SHOWN ON FIGURES.

**REFERENCE:**

a. FOR THE INSTALLATION INSTRUCTIONS, SEE UG3821.

b. FOR FUSING, SEE UG4302 AND UG4309.

c. FOR CONNECTING CAPACITOR TO SYSTEM, SEE DM5811.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**SCOPE:** THIS STANDARD SHOWS THE PAD INSTALLATION, UNDER PAD BOX AND WORK SPACE.





**FIGURE 1**
PAD INSTALLATION





**FIGURE 2**
PAD





**FIGURE 3**
WORK SPACE

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) SEE UG4645.

(b) SEE UG4510.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**SCOPE:** THIS STANDARD SHOWS THE PAD AND ANTENNA POLE PLACEMENT AND CLEARANCES.





**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) USE PVC OR POLYETHYLENE CONDUIT.

II. ANTENNA POLE SHALL BE LOCATED AS SHOWN (NON-CABLE POLE INSTALLATION ONLY).

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**SCOPE:** THIS PAGE COVERS CAPACITOR POLE TO PAD MOUNT DESIGN OPTION FOR USE IN THE HRFA. ALL AVIAN PROTECTION REQUIRED SHALL BE INSTALLED AS NEEDED.





**TABLE 1**

| ITEM | DESCRIPTION | STOCK NUMBER |
|---|---|---|
| 1 | U12.0.61, 2/0 PEJ TR XLPE | S197606 |
| 2 | -- | S206232 |

**FIGURE 1** k

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 9 OF 10

INSTALLATION OF SCADA PAD MOUNTED 4KV CAPACITOR FOR HRFA APPLICATIONS

UG3815.9

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) IF ADDING ADDITIONAL POLE, INSTALL STEEL. IF WOOD POLE IS IN GOOD CONDITION IT MAY USED.

(II) CLAMP TOP OPTIONAL IF STRANDED CONDUCTOR.

(III) WEDGE TAP STIRRUPS REQUIRED.

**REFERENCE:**

a. FOR TAGGING PAD, SEE UG3211.

b. FOR WIRE ENTRY PREVENTION, SEE UG3408.

c. FOR CAPACITOR PAD AND CONDUIT PLACEMENT, SEE UG3414.

d. FOR EQUIPMENT BARRIER PROTECTION AND CLEARANCE, SEE UG3479.

e. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENT, SEE UG3480, UG3481, UG3482 & UG3483.

(f) FOR PAD MOUNTED CAPACITOR, SEE UG3821.

g. FOR FUSING, INCLUDING LEGACY DESIGNS, SEE UG4302 AND UG4309.

h. FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT, SEE UG4514.

i. FOR CONNECTING CAPACITOR TO SYSTEM, SEE DM5811.

j. FOR SCADA PROJECT CHECKLIST, SEE DM6115.

(k) FOR CABLE POLE STANDARD, SEE OH1440.

(l) SEE OH1002.

(m) SEE UG4510.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/DW | 5/29/2014 | F | | | | | | |
| B | REVISION | - | - | - | TR/DW | 5/28/2014 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 4/29/2014 | D | FORMATTING | EDM | JIK | - | - | 06/18/2021 |

**SCOPE:** THIS STANDARD SHOWS THE EQUIPMENT AND INSTALLATION REQUIREMENTS FOR THE PAD MOUNTED 600 AND 1200KVAR 12KV CAPACITOR, WITH SCADA.





**FIGURE 1** (VI)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 10

INSTALLATION OF SCADA
600 & 1200 KVAR 12KV PAD MOUNTED CAPACITOR

UG3821.1

TABLE OF CONTENTS

## INSTALLATION:

A. CHECK AND TIGHTEN ALL CONNECTIONS ON CAPACITOR BEFORE INSTALLATION.

B. INSTALL PAD TO FINAL GRADE.

(C) WHEN A SYSTEM NEUTRAL OR GROUNDING BANK NEUTRAL IS PRESENT, FOR UNDERGROUND OR CABLE POLE APPLICATIONS, THE CONCENTRIC NEUTRALS SHALL BE CONNECTED TO THE NEUTRAL. (d) (e)

(D) TERMINATE CONDUIT 3 INCHES ABOVE GROUND LEVEL IN BOX.

(E) SCADA CONTROL AND RADIO; INSTALLED BY KEARNY CREWS.

(F) BASE OF CABINET SHALL BE CAULKED WHEN NECESSARY TO PREVENT WIRE ENTRY.

(G) REMOVE LIFTING EYES AND STORE INSIDE THE CABINET ON THE CONTROL SIDE. IF EYES ARE NOT REMOVED, THEY MAY ENCROACH ON PRIVATE PROPERTY RIGHT-OF-WAY OR CAUSE HAZARD TO THE PUBLIC.

(H) WHEN OPERATING CAPACITOR CONTROL SWITCH, REMOVE THE PIN IN THE DOOR ASSEMBLY SO IT WILL OPEN AT 180 DEGREE ANGLE (ALLOWING OPERATION OF THE SWITCH WITHOUT STANDING IN FRONT OF THE CAPACITOR).

(J) THE 3426 PAD MAY BE SUBSTITUTED FOR THE 3414 PAD IF RIGHT-OF-WAY PERMITS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CAPACITOR, SCADA, 1,200KVAR PAD MOUNTED | 600KVAR | 1 | -- | S206226 | CAP-4SD |
| | | 1,200KVAR | 1 | -- | S206224 | CAP-SD |
| 2 | PAD, CAPACITOR (IF NEW) | (J) | 1 | -- | S514280 | CAP-PD |
| 3 | BOX, 3312 | (VII) | 1 | 3312 | S162430 | 3312-0 |
| 4 | CONTROL, CAPACITOR, SCADA (PROGRAMMABLE) | (E) | 1 | -- | S274880 | SEL-UC |
| 5 | LOCKS, KEYLESS | (IX) | 2 | -- | S468010 | -- |
| 6 | CONNECTOR, COMPRESSION, COPPER | | 3 | 4174 | S257760 | -- |
| 7 | NUT, CLAMPING, FOR SHALLOW CHANNEL | | 2 | -- | S503520 | -- |
| 8 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | | 2 | -- | S616192 | -- |
| 9 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | | 2 | -- | S799488 | -- |
| 10 | EYES, LIFTING, (REMOVABLE) | (G) | 2 | -- | -- | -- |
| 11 | CONNECTOR, SERVICE POST | | 1 | -- | S262560 | -- |
| 12 | NUT, STANDARD HEX, BRONZE, 1/2" | | 1 | -- | S506112 | -- |
| 13 | HOLD DOWN (SUPPLIED WITH CABINET) | | 2 | -- | -- | -- |
| 14 | PIPE, POLYETHYLENE, 1" | | AS REQ'D | -- | S249630 | 1"PE |
| | PVC, 3" | | | -- | -- | -- |
| 15 | ELBOW, 3", 90 DEGREE | (VIII) | 1 | 3373 | S322048 | 1DB3-B |
| 16 | ANTENNA, SCADA | (E) (IX) | -- | 4645 | S109570 | ANTENA |
| 17 | ADAPTER, ANTENNA | (E) (IX) | 1 | 4645 | S102017 | -- |
| 18 | CABLE, COAX | (E) | AS REQ'D | -- | S191906 | CABANT |
| 19 | CONNECTS, COAX CABLE | (E) (IX) | AS REQ'D | -- | S254170 | CABCON |
| 20 | RADIO, MDS | (E) (IX) | 1 | 4642 | S749500 | MDSRAD |
| 21 | RADIO, MDS, SPREAD SPECTRUM | (E) (IX) | 1 | 4642 | S749504 | SPREAD |
| 22 | CT'S, UG T BODY, LYNDSEY 600A, WITH 100'-0" LEADS | (IX) | 3 | -- | -- | -- |
| 23 | ELBOW, LOADBREAK, 2/0 (IF NEW) | | 3 | 4190 | S443480 | LBE2/0 |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

**NOTES:**

I. PHASE IDENTIFICATION MUST BE MARKED USING THE AP 20 OR 30 AT ALL LOCATIONS. POSITION 1 SHALL BE CONNECTED TO A PHASE, POSITION 2 SHALL BE CONNECTED TO B PHASE AND POSITION 3 MUST BE CONNECTED TO C PHASE.

II. ALL NEW PAD MOUNTED CAPACITORS PURCHASED AFTER 5/14/12 WILL BE SCADA ENABLED UNITS, EQUIPPED WITH THREE VACUUM SWITCHES, LINE VOLTAGE SENSORS AND A NEUTRAL VOLTAGE SENSOR. THE CONTROL UNIT REQUIRES AN ANTENNA. ALL UNITS SHALL HAVE THE SUFFIX "CW" TO THE STATION ID AS ALL WILL BE SCADA/SWITCHED PAD MOUNTED CAPACITOR STATIONS. THE INSTALLATION OF THE 3312 HAND HOLE UNDER THE PAD SHALL BE REQUIRED FOR ALL NEW CONSTRUCTION OF SCADA CAPACITORS.

III. THE LOADBREAK ELBOWS ARE LOCATED ON THE SIDE OF THE CAPACITOR CABINET WITH THE SIGN "CONTROL INSIDE" ON THE DOOR.

(IV) DECAL: "DANGER HIGH VOLTAGE"

(V) DECAL: "CAUTION-NEUTRAL BUSHING NOT GROUNDED WAIT 5 MINUTES AFTER OPENING CAPACITOR SWITCHES BEFORE OPERATING LOADBREAK ELBOWS"

(VI) SWEEP TO CLEAR SIDE FOR PLACEMENT OF ANTENNA POLE TO 50'-0" MAXIMUM.

(VII) LOCATED UNDER PAD (REQUIRED FOR NEW CONSTRUCTION).

(VIII) FOR STUB ONLY INSTALLATION OR ALTERNATIVE LOCATION (IF APPLICABLE).

(IX) NOT SHOWN ON FIGURES.

**REFERENCE:**

(a) FOR CONDUIT AND CONDUIT FITTINGS, SEE UG3373.

(b) FOR ANTENNA POLE W/ ANTENNA, SEE UG4645.

(c) FOR EQUIPMENT GROUNDING, SEE UG4512.

(d) FOR TRENCH GROUNDING, SEE UG4510.

(e) FOR CABLE POLE GROUNDING, SEE OH1002.

(f) FOR (PREFERRED) AND (ALTERNATE) TRENCH GROUND WIRE, SEE UG4510.

(g) FOR EQUIPMENT GROUNDING INSTALLATION, SEE UG4512.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF SCADA
600 & 1200 KVAR 12KV PAD MOUNTED CAPACITOR

UG3821.3

**SCOPE:** SHOWS SCADA CAPACITOR INTERIOR AND LOCATION OF EQUIPMENT IN THE UNIT. LINE SENSORS, NEUTRAL SENSOR, X-LIMITER FUSES, VACUUM SWITCHES, CONTROL, CONTROL WIRING HARNESS, 120V POTENTIAL TRANSFORMER AND 400KVAR CAPACITOR CELLS.





**FIGURE 1**
SCADA CAPACITOR INTERIOR
TOP VIEW
(SEE TABLE 1)





**FIGURE 2**
SCADA CAPACITOR INTERIOR
REAR VIEW
(SEE TABLE 1)





**FIGURE 3**
SCADA CAPACITOR INTERIOR
SIDE VIEW
(SEE TABLE 1)

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |





**FIGURE 4** (I)
CAPACITOR DIAGRAM

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**TABLE 1**

| CAPACITOR PARTS LIST | | | | | |
|---|---|---|---|---|---|
| **ITEM** | **DESCRIPTION** | | **QUANTITY** | **STANDARD PAGE** | **STOCK NUMBER** |
| 1 | TRANSFORMER, (P.T.), 12KV/120V | | 1 | 4309 | S762714 |
| 2 | FUSE, POWER, 0.5E A, 15.5KV, SIZE B, TYPE J-1 | | 2 | -- | S366456 |
| 3 | FUSE, COMBINED TECHNOLOGIES, 15.5KV, TYPE X-LIMITER (CURRENT LIMITING) | 80A | 3 | 4309 | S365695 |
| | | 40A | 3 | 4309 | -- |
| 4 | CAPACITOR, 400KVAR, 7,200V, SINGLE-PHASE | | 3 | -- | S207348 |
| 5 | INSULATOR, POST, 110KV BIL | | 9 | 4309 | -- |
| 6 | SWITCH, VACUUM, CAPACITOR, 15KV, 200A | | 3 | -- | S708420 |
| 7 | PLUG, BUSHING, 14.4KV, 200A | | 3 | 4195 | S544676 |
| 8 | HARNESS, WIRING, VACUUM SWITCH/P.T. | | 1 | -- | -- |
| 9 | HARNESS, WIRING, VOLTAGE/NEUTRAL SENSOR | | 1 | -- | -- |
| 10 | BARRIER, ACRYLIC, CLEAR, 1/4" (REMOVABLE) | | 4 | -- | -- |
| 11 | ROD, COPPER, 3/8", 9" LONG | (III) | 1 | -- | -- |
| 12 | SENSOR, LINE VOLTAGE | | 3 | -- | -- |
| 13 | SENSOR, NEUTRAL VOLTAGE | | 1 | -- | -- |
| 14 | CONTROL | (III) | 1 | -- | -- |
| 15 | WIRE, COPPER, #2 STR. | (III) | -- | -- | -- |
| 16 | NUTS, GROUND, 1/2" - 13 | (III) | 3 | -- | -- |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

**NOTES:**

(I) PAD MOUNTED SCADA CAPACITOR (S206224) IS DELIVERED FROM THE SUPPLIER WITH ALL THE PARTS LISTED IN TABLE 1, INCLUDING FUSES, EXCEPT CONTROL AND RADIO.

(II) VACUUM SWITCH CAN BE OPENED MANUALLY OR ELECTRICALLY. VACUUM SWITCH CAN ONLY BE CLOSED ELECTRICALLY.

(III) NOT SHOWN ON FIGURES.

**REFERENCE:**

a. FOR FUSING, SEE UG4302 AND UG4309.

b. FOR CONNECTING CAPACITOR TO SYSTEM, SEE DM5811.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

**SCOPE:** THIS STANDARD SHOWS THE PAD INSTALLATION, UNDER PAD BOX AND WORK SPACE.





**FIGURE 1**
PAD INSTALLATION





**FIGURE 2**
PAD





**FIGURE 3**
WORK SPACE

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) SEE UG4645.

(b) SEE UG4510.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE PAD AND ANTENNA POLE PLACEMENT AND CLEARANCES.





**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) USE PVC OR POLYETHYLENE CONDUIT.

(II) ANTENNA POLE SHALL BE LOCATED AS SHOWN (NON-CABLE POLE INSTALLATION ONLY).

**REFERENCE:** NONE

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF SCADA
600 & 1200 KVAR 12KV PAD MOUNTED CAPACITOR,
PAD AND ANTENNA POLE

UG3821.8

TABLE OF CONTENTS

**SCOPE:** THIS PAGE COVERS CAPACITOR POLE TO PADMOUNT DESIGN OPTION FOR FTZ/HRFA. ALL AVIAN PROTECTION REQUIRED SHALL BE INSTALLED AS NEEDED.





**TABLE 1**

| ITEM | DESCRIPTION | STOCK NUMBER |
|---|---|---|
| 1 | U12.0.61, 2/0 PEJ TR XLPE | S197648 |
| 2 | -- | S206224 |

**FIGURE 1** II k

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) WEDGE TAP STIRRUPS REQUIRED.

(II) IF ADDING ADDITIONAL POLE, INSTALL STEEL. IF WOOD POLE IS IN GOOD CONDITION IT MAY USED.

**REFERENCE:**

a. FOR TAGGING PAD, SEE UG3211.

b. FOR WIRE ENTRY PREVENTION, SEE UG3408.

c. FOR CAPACITOR PAD AND CONDUIT PLACEMENT, SEE UG3414.

d. FOR EQUIPMENT BARRIER PROTECTION AND CLEARANCE, SEE UG3479.

e. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS, SEE UG3480, UG3481, UG3482 AND UG3483.

(f) SEE UG4510.

g. FOR FUSING, INCLUDING LEGACY DESIGNS, SEE UG4302 AND UG4309.

h. FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT, SEE UG4514.

i. FOR CONNECTING CAPACITOR TO SYSTEM, SEE DM5811.

j. FOR SCADA PROJECT CHECKLIST, SEE DM6115.3.

(k) FOR CABLE POLE STANDARD, SEE OH1440.

(l) SEE OH1002.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JC | TR | MDJ | 09/23/2015 | E | BILL OF MATERIALS UPDATE | EDM | RSL | JES | KRG | 05/31/2022 |
| A | REVISED | - | - | TR | DW | 06/12/2014 | D | NOTES UPDATE | EDM | EJA | GLW | CZH | 10/01/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF SCADA PAD MOUNTED
600 & 1200 KVAR 12KV CAPACITOR FOR HFA APPLICATIONS

UG3821.10

| PAGE | SUBJECT |
|---|---|
| | **GENERAL** |
| 3903 | CATHODIC PROTECTION STATION - UNDERGROUND INSTALLATION |
| 3904 | SECONDARY TEST PROCEDURE |
| | **SERVICES** |
| 3941 | RESIDENTIAL RISER AND CONDUIT |
| 3942 | UNDERGROUND ELECTRIC SERVICE LATERAL - CUSTOMER INSTALLED CONDUIT, RESIDENTIAL OR COMMERCIAL |
| 3944 | UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE), MATERIAL REQUIREMENTS |
| 3948 | SEALING SERVICE LATERAL CONDUIT, INSTRUCTIONS |
| 3950 | FIELD HEATING SERVICE LATERAL CONDUITS |
| 3960 | ELEVATION OF CUSTOMER FACILITIES PREVENTING WATER ENTRY |

MAIN TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | - | LSM/JDJ | 03/30/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SECONDARIES, SERVICES
TABLE OF CONTENTS



UG3901.1

**SCOPE:** THIS STANDARD SHOWS THE PLACEMENT AND INSTALLATION OF AN SDG&E UNDERGROUND CATHODIC PROTECTION STATION.





**FIGURE 1**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | RW | ROG | 01/01/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CATHODIC PROTECTION STATION - UNDERGROUND INSTALLATION



UG3903.1

TABLE OF CONTENTS

**INSTALLATION:**

A. PLACE PEDESTAL AS INDICATED IN LOCATION PLAN ABOVE AND AS CLOSE AS PRACTICAL. NO CLOSER THAN 2 FEET TO EDGE OF PADMOUNT TRANSFORMER PAD.

(B) THE CONCRETE BASE SHALL BE READYCRETE OR EQUIPMENT. THE TOP OF CONCRETE SHALL BE AT GRADE LEVEL (NOT ABOVE GRADE). THE DEPTH OF THE CONCRETE MAY VARY.

C. GROUND 120V NEUTRAL TO GROUND LUG IN BOTTOM OF RECTIFIER ENCLOSURE.

(D) USE CONDUIT AS REQUIRED, NO LARGER THAN 2 INCHES.

(E) ROD AND WIRE DEPTH SHALL BE 6 INCHES MINIMUM UNDER CONCRETE OR FINISHED GRADE, 12 INCHES FOR OPEN GROUND AND 18 INCHES MINIMUM IN AREAS SUBJECT TO PLOWING.

F. PRIME AND PAINT INSTALLATION TO MATCH TRANSFORMER.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | RW | ROG | 01/01/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CATHODIC PROTECTION STATION - UNDERGROUND INSTALLATION

UG3903.2

**SCOPE:** THIS STANDARD DESCRIBES THE PROCEDURE TO CONNECT SECONDARY CONDUCTORS TO AN ENERGIZED SOURCE.

**INSTALLATION:**

**THE FOLLOWING METHOD SHALL BE USED WHEN CONNECTING SECONDARY CONDUCTORS TO AN ENERGIZED SOURCE.**

A. INSPECT CONDITION OF CONDUCTORS ON LOAD END. ENSURE NO LOAD CONDITION AND PROPER INSTALLATION. NEUTRAL SHALL BE GROUNDED ON LOAD END.

B. APPLY CONNECTOR TERMINALS TO CONDUCTORS THAT ARE TO BE ENERGIZED.

C. WITH USE OF VOLTAGE TESTER (M & S 733600), CHECK POTENTIAL FROM ENERGIZED SOURCE TO ALL SECONDARY CONDUCTORS TO BE ENERGIZED.

   CORRECT METER READS:

   1. ENERGIZED SOURCE TO ALL P.S. LEGS, ZERO "0" VOLTAGE READS.
   2. ENERGIZED SOURCE TO NEUTRAL CONDUCTOR, RATED PHASE TO GROUND VOLTAGE, E.G. 120V, 240V, 277V.

D. AFTER CORRECT TEST READS ARE ATTAINED, CONNECT SECONDARY IN FOLLOWING MANNER:

   1. CONNECT SECONDARY NEUTRAL.
   2. CONNECT ONE P.S. LEG.
   3. TEST EACH REMAINING P.S. LEG TO CORRESPONDING ENERGIZED TERMINAL FOR ZERO "0" VOLTAGE READS BEFORE CONNECTING CONDUCTOR TO THAT TERMINAL.

E. AFTER ABOVE STEPS ARE COMPLETED, TEST FOR CORRECT VOLTAGE AT LOAD END OF SECONDARY CONDUCTORS.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | JWK | - | - | 01/01/1991 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

SECONDARY TEST PROCEDURE

UG3904.1

**SCOPE:** THIS STANDARD SHOWS 2-INCH CONDUIT TERMINATION AT CUSTOMERS CONDUIT RISER.





**FIGURE 1**
TYPICAL ELEVATION





**FIGURE 2**
TYPICAL PLAN





**FIGURE 3**
PLAN

## INSTALLATION:

A. VERIFY METER AND SERVICE LOCATION WITH SDG&E BEFORE INSTALLATION.

(B) ONE OF THE FOLLOWING IS REQUIRED DOWN TO 18-INCH DEPTH ON PRIVATE PROPERTY: (f)

1. STEEL CONDUIT.
2. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF .15 INCHES.
3. AT LEAST A 3-INCH LAYER OF CONCRETE ABOVE AND 2 INCHES ON EACH SIDE OF CONDUIT.

(C) WHEN TRENCH IS BUTTED UP AGAINST BUILDING, END OF TRENCH SHALL BE EXCAVATED AT A ONE-TO-ONE SLOPE IF UNDERMINING IS SUSPECTED AT BUILDING.

(D) 90 DEGREE BEND MUST BE INSTALLED DEEP ENOUGH TO CONNECT TO CONDUIT ON BOTTOM OF TRENCH.

(E) TYPE AND SCHEDULE OF CONDUIT AS PER BUILDING INSPECTORS REQUIREMENTS. FLEX CONDUIT IS NOT PERMITTED.

(F) SIZE AND NUMBER OF CONDUIT RUNS TO BE DESIGNATED BY SDG&E.

(G) CONDUIT MANUFACTURER MUST BE SDG&E APPROVED.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | - | LSM/MPB | 12/10/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

RESIDENTIAL RISER AND CONDUIT

SHEET 1 OF 2

UG3941.1

TABLE OF CONTENTS

**BILL OF MATERIALS:** NONE

**NOTES:**

I. A STRAIGHT PIECE OF 2-INCH CONDUIT AND A 90 DEGREE 24-INCH MINIMUM RADIUS IS REQUIRED.

(II) POINT CONDUIT STUB IN DIRECTION OF SUPPLY SOURCE NORMALLY AT 45 DEGREE ANGLE FROM OUTER FACE OF BUILDING WALL.

**REFERENCE:**

a. SEE UG3367 FOR TRENCH PARALLELING FOUNDATIONS.

(b) SEE UG3370 OR UG3371 FOR TRENCH DEPTHS, SHADING AND BACKFILL REQUIREMENTS.

(c) SEE UG3942 FOR MINIMUM BENDING RADIUS.

d. SEE UG3948 FOR SEALING CONDUITS.

e. SEE UG3950 FOR FIELD HEATING SERVICE LATERAL CONDUITS.

(f) SEE G.O. 128 RULE 33.4D.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | - | LSM/MPB | 12/10/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

RESIDENTIAL RISER AND CONDUIT



UG3941.2

**SCOPE:** THIS STANDARD SHOWS CUSTOMER INSTALLED CONDUIT FOR A RESIDENTIAL OR COMMERCIAL SERVICE LATERAL.





**FIGURE 1**
(REFER TO TABLE 3)

## TABLE 1

| CUSTOMER INSTALLED SERVICE RISER BEND AND SERVICE LATERAL CONDUIT SIZE FOR 3 OR 4-WIRE RUN | | | | |
|---|---|---|---|---|
| CUSTOMER INSTALLED SERVICE EQUIPMENT OR BUS AMPACITY (AMPS) (I) | QTY. | RESIDENTIAL & MULTI-FAMILY (IN) (II) | QTY. | COMMERCIAL & INDUSTRIAL (IN) (II) |
| 0-200 (VI) | 1 | 3 (C) | 1 | 3 (C) |
| 201-400 1 Ø | 1 | 3 (III) | 1 | 3 |
| 201-400 3 Ø | 1 | 4 | 1 | 4 |
| 401-800 | 2 | 4 (k) (V) | 2 | 4 |
| 801-1,200 | 3 | 4 | 3 | 5 |
| 1,201-1,600 | 3 | 4 | 4 | 5 |
| 1,601-2,000 | 4 | 4 | 5 | 5 |
| 2,001-2,500 | 5 | 4 | 6 | 5 |
| 2,501-3,000 | 4 | 5 | 7 | 5 |
| 3,001-3,500 | 5 | 5 | 8 | 5 |
| 3,501-4,000 | 7 | 5 | 10 | 5 |

## TABLE 2

| BENDING RADIUS | |
|---|---|
| CONDUIT RISER BEND SIZE (IN) (C) | MINIMUM BEND RADIUS (IN) (6) (7) |
| 2 | 24 |
| 3 | 36 |
| 4 | 36 |
| 5 | 36 |

## TABLE 3

| ITEM | DESCRIPTION | RESPONSIBLE PARTY |
|---|---|---|
| 1 | SOURCE: MANHOLE, HANDHOLE OR PADMOUNT TRANSFORMER | SDG&E UNDERGROUND DISTRIBUTION SYSTEM |
| 2 | SERVICE LATERAL CONDUCTORS AND CONNECTORS FROM SDG&E UNDERGROUND DISTRIBUTION SYSTEM, ITEM 1, TO CUSTOMER'S SERVICE TERMINATING FACILITY, ITEM 8. SDG&E WILL MAKE CONNECTIONS. | SDG&E WILL FURNISH, INSTALL, OWN AND MAINTAIN - (SUBJECT TO INSTALLATION CHARGES CONSULT SDG&E PLANNER) |
| 3 | A CLEAR ROUTE ON ANY PROPERTY, THAT IS CLEAR OF OBSTRUCTIONS WHICH WOULD INHIBIT CONSTRUCTION OF SERVICE FACILITIES. SERVICE LATERAL CONDUIT FROM SOURCE (ITEM 1) TO TERMINATING FACILITY (ITEM 8). CONDUIT SIZE SHALL BE BASED ON AMPERE CAPACITY OF BUS OR SERVICE EQUIPMENT, WHICHEVER IS GREATER AND DISTANCE FROM TRANSFORMER TO TERMINATING FACILITY (ITEM 8). CONDUIT MATERIAL FROM ITEM 1 TO ITEM 8 SHALL BE APPROVED NONMETALLIC CONDUIT. (I) BETWEEN ITEM 6 AND ITEM 8 CONDUIT INSTALLER MUST PROVIDE 3/4-INCH PULLING AND MEASURING TAPE IN EACH CONDUIT. PULLING TAPE MUST BE APPROVED BY SDG&E AND HAVE A MINIMUM AVERAGE TENSILE STRENGTH OF 2,500 LBS, AND BE WOVEN POLYESTER HIGH STRENGTH, CONTINUOUS FILAMENT, PRE-LUBRICATED WITH FOOTAGE MARKING. PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF CONDUIT. PULLING TAPE SHALL BE PULLED BEHIND MANDREL. WHEN PULLING AND MEASURING TAPE IS INSTALLED IT SHALL BE ONE CONTINUOUS LENGTH WITHOUT KNOTS FOR ACCURATE MEASUREMENT FOR CONDUCTOR INSTALLATION AND PULLING OF CONDUCTORS OR WINCH LINES. LEAVE AT LEAST 2 FEET BEYOND EACH END OF CONDUIT RUN. FLEX CONDUIT IS NOT PERMITTED. (O) | CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISON | - | - | TR/BRB | MJC | 05/19/2011 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

UNDERGROUND ELECTRIC SERVICE LATERAL
CUSTOMER INSTALLED CONDUIT, RESIDENTIAL OR COMMERCIAL



UG3942.1

TABLE OF CONTENTS

## TABLE 3 (CONT'D)

| ITEM | DESCRIPTION | RESPONSIBLE PARTY |
|---|---|---|
| 4 | TRENCH, BACKFILL, PAVEMENT REPAIR, AND STRUCTURES SHALL BE IN ACCORDANCE WITH SDG&E AND LOCAL GOVERNMENTAL AUTHORITY REQUIREMENTS. CUSTOMER TO OBTAIN EXCAVATION PERMIT FOR TRENCHING IN STREET RIGHT-OF-WAY AS REQUIRED BY LOCAL GOVERNMENTAL AUTHORITY. SDG&E INSPECTION IS REQUIRED PRIOR TO BACKFILLING TRENCH. | CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE |
| 5 | ADAPTER COUPLINGS FOR CONNECTING BENDS TO STRAIGHT CONDUIT. | |
| 6 | CONDUIT RISER BEND. | |
| 7 | SIZE AND NUMBER OF CONDUIT RUNS TO BE DESIGNATED BY SDG&E. | |
| 8 | SERVICE TERMINATING ENCLOSURE. (m) | |
| 9 | TYPE AND SCHEDULE OF CONDUIT ON OR WITHIN A BUILDING OR STRUCTURE TO BE INSTALLED PER BUILDING INSPECTORS REQUIREMENTS AND MUST BE LISTED AND LABELED. NORMALLY SCHEDULE 40 PVC IS ALLOWED INSIDE A BUILDING WALL AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH APPROPRIATE INSPECTION AUTHORITY. FLEX CONDUIT IS NOT PERMITTED. | |
| 10 | CONDUIT MANUFACTURER MUST BE SDG&E APPROVED. | |

## INSTALLATION:

A. CONTACT PROJECT MANAGEMENT AT NEAREST SDG&E REGIONAL OFFICE FOR A SERVICE AND METER LOCATION PRIOR TO START OF CONSTRUCTION.

B. SERVICE LATERAL CONDUIT SPECIFIED IN CONDUIT TABLE IS LIMITED TO 150-FOOT MAXIMUM LENGTH, WITH NOT MORE THAN 3-90 DEGREE HORIZONTAL OR VERTICAL BENDS OR 270 DEGREES TOTAL DEFLECTION THROUGH SERVICE RUN. PLANNER AND ELECTRIC CONSTRUCTION APPROVAL IS REQUIRED IF LIMITATIONS ARE EXCEEDED. (n)

(C) A 3-WIRE, 100A SINGLE-PHASE MAIN CAN BE SERVED BY A 2-INCH CONDUIT. A 3-WIRE 200A OR LESS, SINGLE-PHASE MAIN FOR TEMPORARY CONSTRUCTION POWER CAN BE SERVED BY A 2-INCH CONDUIT. (o)

D. ENGINEERS AND ARCHITECTS PROPOSALS FOR ALL SWITCHBOARDS 1,000A OR LARGER, SHALL BE SUBMITTED TO THE NEAREST PROJECT MANAGEMENT OFFICE FOR STUDY AND APPROVAL BY SDG&E'S DISTRIBUTION PLANNING AND SERVICE STANDARDS SECTIONS.

E. MAINTENANCE OF CUSTOMER'S SERVICE LATERAL CONDUITS OUTSIDE BUILDING WALL WILL BE UNDERTAKEN BY SDG&E UNDER EMERGENCY CONDITIONS AND MAY BE DONE AT CUSTOMER'S EXPENSE. CONSULT NEAREST SDG&E REGIONAL OFFICE. (p)

(F) CONDUITS SHALL BE SEALED. (q)

(G) 24-INCH MINIMUM COVER OVER CONDUIT IS REQUIRED FOR ALL NORMAL INSTALLATIONS ON PRIVATE PROPERTY AND 30-INCH MINIMUM COVER IN RIGHT-OF-WAY OR PUBLIC PROPERTY. IN ALL INSTALLATIONS WHERE MINIMUM COVER CANNOT BE MET THE FOLLOWING CAN BE USED: (r)

1. STEEL CONDUIT.
2. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 0.15 INCHES.
3. AT LEAST A 3-INCH LAYER OF CONCRETE ABOVE AND 2 INCHES ON EACH SIDE OF CONDUIT. REDUCED DEPTHS MUST BE APPROVED BY CUSTOMER PROJECT PLANNER AND SDG&E INSPECTOR.

(H) TRENCH MUST HAVE EVEN SLOPING GRADE TO ALLOW ROOM FOR A 90 DEGREE BEND INTO BOTTOM OF ANY CUSTOMER OWNED OR SDG&E FACILITY. DO NOT CUT BENDS. TRENCH DEPTH IS TO BE DETERMINED AT "PRE-CONSTRUCTION MEETING".

(J) WHEN TRENCHING TO AN EXISTING FACILITY, APPLICANT/CONTRACTOR SHALL COMPLETE TRENCH AND INSTALLATION OF CONDUIT UP TO EXISTING FACILITY UNLESS IT IS DETERMINED BY AN AUTHORIZED SDG&E EMPLOYEE THAT SUCH AN INSTALLATION PERFORMED BY APPLICANT/CONTRACTOR WOULD EXPOSE WORKERS TO OR CREATE A HAZARD. IN THIS CASE, SDG&E WOULD PERFORM TRENCHING AS INDICATED ON WORK ORDER. DIGGING UNDER PAD MOUNTED EQUIPMENT AND INSTALLATION OF CONDUIT INTO PAD MOUNTED EQUIPMENT WILL ALWAYS BE THE RESPONSIBILITY OF SDG&E.

L. SERVICE CONDUIT WILL ONLY BE ALLOWED UNDERNEATH BUILDING BEING SERVED BY CABLE IN CONDUIT. NO CONDUIT IS ALLOWED UNDER ONE BUILDING TO SERVE ANOTHER BUILDING.

**BILL OF MATERIALS:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISON | - | - | TR/BRB | MJC | 05/19/2011 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

UNDERGROUND ELECTRIC SERVICE LATERAL
CUSTOMER INSTALLED CONDUIT, RESIDENTIAL OR COMMERCIAL

UG3942.2

TABLE OF CONTENTS

**NOTES:**

(I) AMPACITY RANGE BASED ON 75 DEGREE C ALUMINUM WIRE.

(II) THESE ARE MINIMUM REQUIREMENTS. CONDUIT REQUIREMENTS MAY INCREASE WITH DIFFERENT ESTIMATED DEMANDS AND LENGTH OF SERVICE, DUE TO VOLTAGE DROP AND/OR FLICKER. FUTURE LOADS SHOULD ALSO BE CONSIDERED.

(III) INCLUDES 300A RESIDENTIAL SERVICE EQUIPMENT.

(IV) IF CUSTOMER INSTALLS A HANDHOLE, THE LID SHALL BE MARKED "SDG&E". (k)

(V) 2, 3-INCH CONDUITS MINIMUM FOR MULTI-FAMILY 600A SERVICES.

(VI) 225A RESIDENTIAL.

(VII) DEPTH OF TRENCH IS DETERMINED BY TYPE OF SUBSTRUCTURE AT SOURCE. VERIFY WITH SDG&E INSPECTOR PRIOR TO EXCAVATION.

(VIII) INSTALL CONDUIT ON EVEN SLOPING GRADE FROM CONDUIT RISER BEND TO SDG&E SOURCE.

**REFERENCE:**

a. SEE UG3367 FOR TRENCH PARALLELING FOUNDATIONS.

b. SEE UG3372 FOR CONDUIT SIZING.

c. SEE UG3373 FOR SDG&E CONDUIT FITTINGS.

d. SEE UG3376 FOR CONCRETE SLURRY REQUIREMENTS.

e. SEE UG3421, UG3425, UG3426, AND UG3427 FOR CONDUIT PLACEMENT.

f. SEE UG3941 FOR RESIDENTIAL RISER AND CONDUIT.

g. SEE UG3944 FOR MATERIAL REQUIREMENTS OF AN U.G. SERVICE FROM O.H. FACILITIES.

h. SEE UG3948 FOR SEALING CONDUITS.

i. SEE OH1404UG4204 FOR CABLE POLE CONDUIT REQUIREMENTS.

j. SEE UG3950 FOR FIELD HEATING SERVICE LATERAL CONDUIT.

(k) SEE SG707 FOR SPECIAL APPLICATIONS.

(l) IN ACCORDANCE WITH UG3373.

(m) SEE SG703, SG704, SG705, SG706, SG707, AND SG708.

(n) IF GREATER THAN 150 FEET, REFER TO UG4005, UG4006, AND UG4007.

(o) ITEM 3 SHALL BE SAME SIZE AND TYPE MATERIAL STOCKED BY SDG&E AS SHOWN ON UG3373.

(p) REPLACEMENT OR ENLARGEMENT OF SERVICE LATERAL CONDUITS DUE TO RELOCATION OR INCREASED LOAD WILL BE ACCOMPLISHED BY CUSTOMER UNDER PROVISIONS ON SG305.

(q) SEE UG3948 (G.O. 128, RULE 31.6).

(r) SEE G.O. 128.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISON | - | - | TR/BRB | MJC | 05/19/2011 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

UNDERGROUND ELECTRIC SERVICE LATERAL
CUSTOMER INSTALLED CONDUIT, RESIDENTIAL OR COMMERCIAL

UG3942.3

**SCOPE:** THIS STANDARD SHOWS WHO PROVIDES, INSTALLS, OWNS AND MAINTAINS MATERIAL AND LABOR REQUIRED FOR A SINGLE LOW VOLTAGE SERVICE FED FROM OVERHEAD FACILITIES.

**ATTENTION:**

* CONTACT THE SDG&E INSPECTOR FOR INSTRUCTIONS ON TRENCHING NEAR THE POLE.

** SDG&E INSPECTION IS REQUIRED PRIOR TO BACKFILLING TRENCH.





**FIGURE 1**

**TABLE 1**

| ITEM | DESCRIPTION | RESPONSIBLE PARTY |
|---|---|---|
| 1 | SOURCE POLE AS DESIGNATED BY SDG&E PLANNER. | SDG&E OVERHEAD DISTRIBUTION SYSTEM |
| 2 | SERVICE LATERAL CONDUCTOR AND CONNECTORS. SDG&E TO FURNISH MATERIAL AT CUSTOMERS EXPENSE INSTALL, OWN AND MAINTAIN. | SDG&E TO FURNISH, INSTALL, OWN AND MAINTAIN - SUBJECT TO INSTALLATION CHARGES CONSULT SDG&E PLANNER |
| 3 | PVC CONDUIT SCHEDULE 40. | CUSTOMER TO PROVIDE, SDG&E TO INSTALL, OWN AND MAINTAIN |
| 4 | PVC CONDUIT SCHEDULE 80. | |
| 5 | PVC CONDUIT BEND. THE LARGER RADIUS AT THE POLE IS NECESSARY TO ALLOW FOR VERTICAL CABLE PULLING TENSION. SEE TABLE 2. | CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE |
| 6 | A CLEAR ROUTE ON ANY PRIVATE PROPERTY, THAT IS CLEAR OF OBSTRUCTIONS WHICH WOULD INHIBIT THE CONSTRUCTION OF SERVICE FACILITIES. SERVICE LATERAL CONDUIT FROM SOURCE (ITEM 1) TO TERMINATING FACILITY (ITEM 11). CONDUIT SIZE SHALL BE BASED ON AMPERE CAPACITY OF BUS OR SERVICE EQUIPMENT, WHICHEVER IS GREATER AND DISTANCE FROM TRANSFORMER TO TERMINATING FACILITY (ITEM 11). | |
| 7 | SECONDARY HANDHOLE. VERIFY IF REQUIRED WITH SDG&E PLANNER. IF HANDHOLE IS REQUIRED, THE LID SHALL BE MARKED "SDG&E". | |
| 8 | TRENCH, BACKFILL, PAVEMENT REPAIR AND PROTECTIVE STRUCTURES SHALL BE IN ACCORDANCE WITH SDG&E AND LOCAL GOVERNMENTAL AUTHORITY REQUIREMENTS. CUSTOMER TO OBTAIN EXCAVATION PERMIT FOR TRENCHING IN STREET RIGHT-OF-WAY AS REQUIRED BY LOCAL GOVERNMENTAL AUTHORITY. | |
| 9 | ITEMS 3, 4, 5, & 6 SHALL BE NONMETALLIC FROM ITEM 5 AND ITEM 9. THE CONDUIT INSTALLER MUST PROVIDE A 3/4-INCH PULLING AND MEASURING TAPE IN EACH CONDUIT. THE PULLING TAPE MUST BE APPROVED BY SDG&E AND HAVE A MINIMUM AVERAGE TENSILE STRENGTH OF 2,500 LBS, AND BE WOVEN POLYESTER HIGH STRENGTH, CONTINUOUS FILAMENT, PRE-LUBRICATED WITH FOOTAGE MARKING. PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF THE CONDUIT. THE PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF THE CONDUIT. THE PULLING TAPE SHALL BE PULLED IN BEHIND THE MANDREL. WHEN THE PULLING AND MEASURING TAPE IS INSTALLED IT SHALL BE ONE CONTINUOUS LENGTH WITHOUT KNOTS FOR THE ACCURATE MEASUREMENT FOR CONDUCTOR INSTALLATION AND THE PULLING OF CONDUCTORS OR WINCH LINES. LEAVE AT LEAST 2 FEET BEYOND EACH END OF CONDUIT RUN. FLEX CONDUIT IS NOT PERMITTED. (j) | |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | TR | MJC | 06/28/2011 | E | | | | | | |
| A | REVISION | - | - | PSW | ROG | 03/06/2003 | D | | | | | | |

## TABLE 1 (CONT'D)

| ITEM | DESCRIPTION | RESPONSIBLE PARTY |
|---|---|---|
| 10 | CONDUIT RISER BEND. (k) | CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE |
| 11 | SERVICE TERMINATING ENCLOSURE. (l) | |
| 12 | TYPE AND SCHEDULE OF CONDUIT ON OR WITHIN THE BUILDING TO BE INSTALLED PER BUILDING INSPECTORS REQUIREMENTS AND MUST BE LISTED AND LABELED. NORMALLY SCHEDULE 40 PVC IS ALLOWED INSIDE A BUILDING WALL AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH APPROPRIATE BUILDING INSPECTOR. FLEX CONDUIT IS NOT PERMITTED. | |
| 13 | CONDUIT MANUFACTURER MUST BE SDG&E APPROVED. | |

## TABLE 2

| SCHEDULE 80 PVC CONDUIT MINIMUM RADIUS OF BEND | |
|---|---|
| PIPE SIZE (IN) | RADIUS (IN) |
| 3 | 36 |
| 4 | 48 |
| 5 | 48 |

## INSTALLATION:

(A) A 24-INCH MINIMUM COVER OVER THE CONDUIT SHALL BE FOLLOWED FOR ALL NORMAL INSTALLATIONS ON PRIVATE PROPERTY, 30-INCH MINIMUM COVER IN RIGHT-OF-WAY OR PUBLIC PROPERTY. ONE OF THE FOLLOWING IS REQUIRED IN ALL INSTALLATIONS WHERE THE MINIMUM COVER CANNOT BE MET: (m) (n)

1. STEEL
2. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 0.15 INCHES.
3. A 3-INCH LAYER OF CONCRETE (2 SACK 3/8" ROCK) ABOVE AND 2 INCHES ON EACH SIDE OF THE CONDUIT. REDUCED DEPTHS MUST BE APPROVED BY BOTH THE CUSTOMER PROJECT PLANNER AND SDG&E INSPECTOR.

(B) THE TRENCH MUST HAVE AN EVEN SLOPING GRADE TO ALLOW FOR A 90 DEGREE BEND INTO THE BOTTOM OF ANY CUSTOMER OWNED OR SDG&E FACILITY, **DO NOT CUT BENDS.** THE TRENCH DEPTH IS TO BE DETERMINED AT THE "PRECONSTRUCTION MEETING".

(C) WHEN TRENCHING TO AN EXISTING FACILITY, THE APPLICANT/CONTRACTOR SHALL COMPLETE THE TRENCH AND INSTALLATION OF CONDUIT UP TO THE EXISTING FACILITY UNLESS IT IS DETERMINED BY ANY AUTHORIZED SDG&E EMPLOYEE THAT SUCH AN INSTALLATION PERFORMED BY THE APPLICANT/CONTRACTOR WOULD EXPOSE WORKERS TO OR CREATE A HAZARD. IN THIS CASE, SDG&E WOULD PERFORM TRENCHING AS INDICATED ON WORK ORDER. DIGGING UNDER ENERGIZED PAD MOUNTED EQUIPMENT AND INSTALLATION OF CONDUIT INTO ENERGIZED PAD MOUNTED EQUIPMENT WILL ALWAYS BE THE RESPONSIBILITY OF SDG&E.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG3367 FOR TRENCH PARALLELING FOUNDATIONS.
b. SEE UG3373 FOR SDG&E CONDUIT AND FITTINGS.
c. SEE UG3376 FOR CONCRETE SLURRY REQUIREMENTS.
d. SEE UG3421, UG3425, UG3426 AND UG3427 FOR CONDUIT PLACEMENT.
e. SEE UG3941 FOR RESIDENTIAL RISER AND CONDUIT.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | TR | MJC | 06/28/2011 | E | | | | | | |
| A | REVISION | - | - | PSW | ROG | 03/06/2003 | D | | | | | | |



TABLE OF CONTENTS

**REFERENCE (CONT'D):**

f. SEE UG3942 FOR MATERIAL REQUIREMENTS OF AN U.G. SERVICE FROM U.G. FACILITIES.
g. SEE UG3948 FOR SEALING CONDUITS.
h. SEE OH1404UG4204 FOR CABLE POLE CONDUIT REQUIREMENTS.
i. SEE UG3950 FOR FIELD HEATING SERVICE LATERAL CONDUITS.
(j) SEE UG3373 AND UG4204.
(k) MINIMUM BENDING RADIUS PER SG305.
(l) SEE SG703, SG704, SG705, SG706, SG707, AND SG708.
(m) SEE UG3370.
(n) SEE G.O. 128 FOR REQUIREMENTS.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | TR | MJC | 06/28/2011 | E | | | | | | |
| A | REVISION | - | - | PSW | ROG | 03/06/2003 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDREGROUND CONSTRUCTION STANDARDS

UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE), MATERIAL REQUIREMENTS

**SCOPE:** THIS STANDARD SHOWS INSTALLATION AND MATERIAL REQUIREMENTS FOR SEALING SERVICE LATERAL CONDUITS.

**ATTENTION:**

* DO NOT USE SEALANT AFTER EXPIRATION DATE.





**FIGURE 1**
INSTALLATION DRAWING (a)
CONDUIT SEALANT AND PACKING FOAM

**INSTALLATION:**

**SEALING COMPOUND:**

A. BEFORE APPLYING SEALING COMPOUND THE INSIDE AND OUTSIDE SHOULD BE AS CLEAN AND DRY AS POSSIBLE. DRY OUT ANY WATER WITH COMPRESSOR, RAGS, HAND PUMP, ETC.

B. IN CONDUITS WHERE CABLES ARE PRESENT, WRAP A STRIP OF SEALING COMPOUND AROUND CONDUIT WHERE CABLES ENTER. OVERLAP SEALING COMPOUND ENDS 1/4-INCH AND PRESS EDGES FIRMLY TOGETHER.

C. IN CONDUITS THAT ARE EMPTY (FOR FUTURE CABLE PULLING) AND WATER MAY OCCUR, SECURE PULL ROPE AND INSTALL SEALING COMPOUND AND GRAY TAPE SECURELY TO PREVENT WATER ENTRY. SEAL AT SUBSTRUCTURE END OF CONDUIT.

**CONDUIT SEALANT AND PACKING FOAM:**

D. BEFORE INSTALLATION OF SEALANT AND FOAM, CABLES SHOULD SHOULD BE TERMINATED IF POSSIBLE TO AVOID ANY MOVEMENT THAT MAY CAUSE CRACKING OF SEALANT AND SUBSEQUENT WATER LEAKAGE.

E. ON EXISTING 3/4-INCH SIDA AND 1-INCH CONDUIT, SKIP INSTALLATION F, G, AND H. PACKING FOAM IS NOT REQUIRED, SEALANT WILL EXPAND ENOUGH TO MAKE A GOOD SEAL.

(F) WRAP PACKING FOAM AROUND CABLES AT THE CONDUIT ENTRANCE AS SHOWN IN FIGURE 1. USE AS MANY FOAM STRIPS AS NEEDED TO ASSURE THERE ARE NO GAPS BETWEEN FOAM, CABLES, AND CONDUIT.

(G) WITH A BLUNT OBJECT, PUSH PACKING FOAM BACK INSIDE CONDUIT 3 INCHES.

(H) WRAP ANOTHER LAYER OF PACKING FOAM AROUND CABLES AT CONDUIT ENTRANCE THE SAME WAY AS FIRST LAYER. THIS FORMS A VOID INSIDE CONDUIT THAT WILL BE FILLED WITH SEALANT.

J. CONDUIT IS NOW READY FOR INSTALLATION OF CONDUIT SEALANT. CAREFULLY READ INSTRUCTIONS ON SEALANT PACKAGE BEFORE USING. SAFETY GLASSES AND PROTECTIVE GLOVES SHALL BE WORN DURING INSTALLATION OF SEALANT.

**CAUTION:**

* AS NOTED ON SEALANT PACKAGE, CARTRIDGE WILL DEVELOP INTERNAL PRESSURE AFTER MIXING. THIS OCCURS IN 20-30 SECONDS AT WHICH POINT SEALANT BEGINS EXPANDING SO WORK QUICKLY WHEN SCREWING ON NOZZLE TO CARTRIDGE.

** DO NOT LEAVE ANY UNUSED SEALANT INSIDE OF CARTRIDGE. CONTENTS MAY STILL BE UNDER PRESSURE AND COULD RUPTURE CARTRIDGE.

(K) AFTER SEALANT IS MIXED AND NOZZLE IS ATTACHED, PUSH NOZZLE OF CARTRIDGE THROUGH TOP LAYER OF PACKING FOAM AND DEPRESS PLUNGER TO FORCE MIXED SEALANT FROM CARTRIDGE. LEAVE CARTRIDGE AND NOZZLE IN CONDUIT A FEW MINUTES TO ASSURE ALL SEALANT HAS EVACUATED TUBE.

L. REMOVE NOZZLE OF CARTRIDGE AND ALLOW SEALANT TO CURE. AFTER SEALANT HAS CURED, CHECK AROUND EDGE OF TOP LAYER OF PACKING FOAM TO SEE IF SEALANT HAS PROPERLY EXPANDED AND SEALED CONDUIT.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JJ | 11/16/2006 | F | | | | | | |
| B | REVISION | - | - | TR | JJ | 01/26/2006 | E | | | | | | |
| A | REVISION | - | - | PSW/JLB | ROG | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

## INSTALLATION (CONT'D):

### MAINTENANCE:

M. IF CABLE IS TO BE REPLACED, SEALANT CAN BE REMOVED BY CHIPPING OUT OF CONDUIT WITH A LONG SCREWDRIVER OR OTHER BLUNT OBJECT.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | SEALANT, CONDUIT, SEMCO PR-821, (2 OZ) | AS REQ'D | -- | S631892 | SEAL-2 |
| 2 | SEALANT, CONDUIT, SEMCO PR-821, (6 OZ) | AS REQ'D | -- | S631890 | SEAL-6 |
| 3 | FOAM, POLYURETHANE PACKING | AS REQ'D | -- | S511680 | -- |
| 4 | COMPOUND, SEALING | AS REQ'D | -- | S442976 | -- |
| 5 | TAPE, GRAY | AS REQ'D | -- | S721120 | -- |
| 6 | GLASSES, SAFETY | AS REQ'D | -- | S383800 | -- |
| 7 | GLOVES, DISPOSABLE | AS REQ'D | -- | S385300 | -- |

## NOTES:

I. CONDUIT SEALANT IS A TWO PART POLYURETHANE WHICH WHEN EXPANDS TO 8 TIMES ITS LIQUID STATE TO FORM A DENSE, TOUGH FOAM. FOAM CURES TO 60 PERCENT OF IT'S FULL STRENGTH IN 8-10 MINUTES AND TO FULL STRENGTH IN 12 HOURS.

II. CONDUIT SEALANT MAY ALSO BE USED ON SECONDARY AND JACKETED PRIMARY CABLES WHERE THERE MAY BE A WATER PROBLEM.

III. WHENEVER A PAD OR SUBSTRUCTURE IS HIGHER IN ELEVATION THAN ELECTRIC VAULTS, BASEMENTS, ETC., CONDUITS MUST BE SEALED WHETHER THEY ARE PRIMARY, SECONDARY, OR SERVICE LATERALS.

IV. A HANDHOLE SHALL BE INSTALLED AT BASE OF METER PANEL FOR CONDITIONS DESCRIBED BELOW. (Vd)

V. SEAL CONDUITS WITH MATERIAL AS SPECIFIED BY THE FOLLOWING CRITERIA.

a. USE CONDUIT SEALANT AND PACKING FOAM WHEN FIELD CONDITIONS INDICATE THAT WATER MAY ENTER SERVICE LATERAL CONDUIT (WITH CABLE) AT CABLE ENTRANCE AND SUBSEQUENTLY INTO CUSTOMER'S SERVICE PANEL.

b. USE SEALING COMPOUND ON SERVICE LATERAL CONDUIT (WITH CABLE) WHERE NO WATER ENTRY PROBLEMS ARE SUSPECTED. CONDUIT(S) SHALL BE SEALED ONLY AT SUBSTRUCTURE OR TRANSFORMER BY CONNECTION CREW.

c. USE SEALING COMPOUND AND GRAY TAPE WHEN FIELD CONDITIONS INDICATE THAT WATER MAY ENTER SERVICE THE SERVICE LATERAL CONDUIT (WITHOUT CABLE) AT CONDUIT ENTRANCE AND SUBSEQUENTLY INTO CUSTOMER'S SERVICE PANEL.

(d) **EXAMPLE:** THE SERVICE PANEL IS AT AN APPRECIABLY LOWER ELEVATION THAN THE SUBSTRUCTURE OR TRANSFORMER. CONDUIT(S) SHALL BE SEALED IN HANDHOLE AT BASE OF SERVICE PANEL, IN THE SERVICE PANEL AND AT THE SOURCE SUBSTRUCTURE OR TRANSFORMER BY THE CONNECTION CREW.

e. USE THE SEALING COMPOUND AND GRAY TAPE ON SERVICE LATERAL CONDUIT (WITHOUT CABLE) WHERE NO WATER PROBLEMS ARE SUSPECTED. CONDUIT(S) SHALL BE SEALED ONLY AT SUBSTRUCTURE OR TRANSFORMER BY THE CONNECTION CREW.

VI. SHELF LIFE/EXPIRATION DATE: SHELF LIFE IS 12 MONTHS WHEN STORED IN ORIGINAL AND UNOPENED CONTAINERS BELOW 80 DEGREES F. PROLONGED STORAGE AT TEMPERATURES ABOVE 100 DEGREES F MAY ALTER EXPANSION RATIO OF THE FOAM.

## REFERENCE:

(a) SEE G.O. 128, RULE 31.6 ON SEALING SERVICE LATERALS.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JJ | 11/16/2006 | F | | | | | | |
| B | REVISION | - | - | TR | JJ | 01/26/2006 | E | | | | | | |
| A | REVISION | - | - | PSW/JLB | ROG | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

**SCOPE:** THIS STANDARD COVERS CONDUIT SEALING WITH TYCO RAYFLATE AND CONDUCTOR BREAKOUT BOOTS. THE APPLICATION OF THESE PRODUCTS IS DESIGNED TO PREVENT WATER ENTRY INTO CUSTOMER AND SDG&E FACILITIES, WHEN SDG&E SERVICE POINT IS A HIGHER ELEVATION THAN CUSTOMERS SERVICE POINT OF ENTRY.




**FIGURE 1**

**TABLE 1**

| TYCO NUMBER | CONDUIT SIZE (IN) | CONDUCTOR NUMBER | CONDUCTOR SIZE | STOCK NUMBER |
|---|---|---|---|---|
| CBR-3-3-A | 2 AND 3 | 3 | NO. 2 TO 350 | S160650 |
| CBR-4-3-A | 3 AND 4 | 4 | NO. 3/0 TO 350 | S160652 |
| CBR-4-4-A | 4 | 4 | NO. 350 TO 500 | S160654 |
| CBR-4-4-A | 5 | 4 | NO. 750, 1000 | S160654 |

## INSTALLATION:

A. SELECT SIZE OF CBR TO SEAL CABLE AND CONDUIT.

B. ONCE CABLE IS INSTALLED, CLEAN CABLE AND CONDUIT SURFACES.

C. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION.

## ATTENTION:

* APPLY HEAT SLOW AND EVENLY TO PREVENT DISTORTION OF CONDUIT.

**BILL OF MATERIALS:** NONE

## NOTES:

**CABLE BREAKOUTS (CBR):**

I. CABLE BREAKOUT BOOTS ARE DESIGNED TO KEEP WATER OUT ONLY AND SHOULD ALWAYS BE USED AT HIGHER ELEVATION IN TRANSFORMERS AND SECONDARY HANDHOLES.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JJ | 11/16/2006 | F | | | | | | |
| B | REVISION | - | - | TR | JJ | 01/26/2006 | E | | | | | | |
| A | REVISION | - | - | PSW/JLB | ROG | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

**SCOPE:** THE RAYFLATE DUCT SEALING SYSTEM HAS BEEN DESIGNED FOR USE IN CONJUNCTION WITH PLASTIC, CONCRETE OR STEEL DUCTS WITH SINGLE OR MULTIPLE CONDUCTORS. THE RDSS SEALING SYSTEM SHOULD PREVENT WATER ENTRY INTO CUSTOMER VAULTS, METER ROOMS, MANHOLES, AND HANDHOLES. THE RAYFLATE BLADDER IS A FLEXIBLE METALLIC LAMINATED HIGH TEMPERATURE SEALANT.




**FIGURE 1**




**FIGURE 2**




**FIGURE 3**




**TABLE 1**

| CONDUIT SIZE, WITH 1 CONDUCTOR (IN) | RAYFLATE DUCT SEAL | STOCK NUMBER | ADD-CLIP FOR MULTIPLE CONDUCTORS | STOCK NUMBER |
|---|---|---|---|---|
| 2 | RDSS-60 | S632070 | RDSS-CLIP-75 | S477542 |
| 3 | RDSS-75 | S632072 | RDSS-CLIP-75 | S477542 |
| 4 | RDSS-100 | S632074 | RDSS-CLIP-100 | S477544 |
| 5 | RDSS-125 | S632076 | RDSS-CLIP-125 | S477546 |
| CO2 CARTRIDGE | E7515-0160 | S209412 | - | - |

## INSTALLATION:

A. FOLLOW MANUFACTURER'S INSTRUCTION FOR INSTALLATION OF RDSS BLADDER.

B. CLEAN ALL SURFACES OF CABLE AND CONDUITS TO BE SEALED.

C. SEALING SYSTEM CAN SEAL SINGLE CONDUCTOR UNJACKETED CONCENTRIC OR JACKETED CABLE, DUPLEX, TRIPLEX, AND QUAD CONDUCTORS, PRIMARY AND SECONDARY.

D. FOR MULTIPLE CONDUCTORS USE THE CORRECT RDSS-CLIP TO SEAL BETWEEN CONDUCTORS TO MAKE A POSITIVE SEAL WHEN APPLYING RDSS INFLATABLE BLADDER. SEE TABLE 1.

E. RDSS-IT-16 INFLATION TOOL IS USED TO INFLATE BLADDER. TOOL IS POWERED BY A CO2 CARTRIDGE. BLADDER IS INFLATED TO 45 PSI IN GREEN ZONE ON GAUGE. CO2 REPLACEMENT IS S209412.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JJ | 11/16/2006 | F | | | | | | |
| B | REVISION | - | - | TR | JJ | 01/26/2006 | E | | | | | | |
| A | REVISION | - | - | PSW/JLB | ROG | 01/01/1996 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SEALING SERVICE LATERAL CONDUIT, INSTRUCTIONS

UG3948.4

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD PROVIDES THE REQUIREMENTS AND CONDITIONS ALLOWING FIELD HEATING OF SERVICE LATERAL CONDUITS INSTALLED ABOVE GRADE ONLY.





**FIGURE 1**
VERTICAL OFFSET
SIDE VIEW





**FIGURE 2**
HORIZONTAL OFFSET
FRONT VIEW

## INSTALLATION:

(A) ONLY MANUFACTURER'S RECOGNIZED FIELD CONDUIT HEATING EQUIPMENT SHALL BE USED. DEGRADATION OF THE CONDUIT'S SHAPE, WRINKLES, DISCOLORATION, BURN MARKS, OR PAINT IS NOT ALLOWED. SDG&E'S INSPECTOR WILL DETERMINE IF THE HEATED CONDUIT IS ACCEPTABLE.

(B) 45 DEGREES MAXIMUM ALLOWABLE DEFLECTION ON RISER. THE DEFLECTION IN RISER IS INCLUDED IN THE MAXIMUM 270 DEGREE TOTAL DEFLECTION IN THE SERVICE LATERAL CONDUIT RUN.

(C) WHEN CONVERTING AN EXISTING SERVICE TO UNDERGROUND, MANDREL NEW CONDUIT TO THE TOP OF THE ELBOW EXTENDING TO GRADE PRIOR TO CONNECTING THE RISER CONDUIT. ALLOW ENOUGH PULL ROPE TO EXTEND THROUGH RISER, WITH A MINIMUM 12-INCH TAIL TO BE LEFT IN THE TERMINATING ENCLOSURE.

(D) NEW SERVICES REQUIRE MANDRELING OF ALL NEW CONDUIT, INCLUDING THE CONDUIT RISER.

**BILL OF MATERIALS:** NONE

## NOTES:

I. THIS STANDARD PROVIDES A MEANS TO AVOID EXCAVATING INTO AN EXISTING BUILDING FOOTING WHEN CONVERTING EXISTING OVERHEAD SERVICES TO UNDERGROUND (SEE FIGURE 1). IT ALSO APPLIES TO EXISTING OR NEW SERVICES WHEN A HORIZONTAL OFFSET IS REQUIRED DUE TO FIELD CONDITIONS (SEE FIGURE 2).

II. THIS STANDARD IS NOT INTENDED TO CORRECT POOR WORKMANSHIP. CARE SHOULD BE TAKEN TO INSTALL SERVICE EQUIPMENT IN A MANNER ALLOWING THE SERVICE LATERAL CONDUIT RISER TO EXIT THE GROUND AND RUN STRAIGHT UP INTO THE TERMINATING ENCLOSURE EXCEPT WHERE PRE-EXISTING FIELD CONDITIONS EXIST.

(III) THIS STANDARD APPLIES TO 2-INCH, 3-INCH, AND 4-INCH CONDUIT SIZES ONLY.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | - | LSM/MPB | 12/21/2002 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FIELD HEATING SERVICE LATERAL CONDUITS



UG3950.1

TABLE OF CONTENTS

**SCOPE:** THE STANDARD COVERS THE ELEVATION OF CUSTOMER PRIMARY AND SECONDARY SERVICE LATERALS WHEN THEY ARE LOWER THAN THAT OF THE SDG&E FACILITY THAT SERVES THEM AND PREVENTING WATER ENTRY.




**FIGURE 1** (A)




**FIGURE 2** (I)




**FIGURE 3** (C)





**FIGURE 4** (D)




**FIGURE 5** (II) (F)





**FIGURE 6** (F)





**FIGURE 7** (F)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 03/30/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

ELEVATION OF CUSTOMER FACILITIES
PREVENTING WATER ENTRY

UG3960.1

TABLE OF CONTENTS

## INSTALLATION:

(A) **RESIDENTIAL AND LIGHT COMMERCIAL:** WHEN ELEVATION OF SDG&E FACILITY SERVING CUSTOMER PANEL IS GREATER THAN 10 FEET ABOVE, AN ADDITIONAL SECONDARY HANDHOLE SHALL BE INSTALLED AS CLOSE AS POSSIBLE TO CUSTOMER PANEL AND SERVICE LATERAL TO CUSTOMER PANEL IS TO BE SEALED. THIS WILL PREVENT WATER ENTRY DUE TO WATER HEAD PRESSURE IN CONDUIT CREATED BY ELEVATION OF HIGHER FACILITY. (a)

B. **EXTERIOR WALL FLUSH, SEMIFLUSH OR SURFACE MOUNTED SERVICE EQUIPMENT:** WHEN ELEVATION CHANGE IS GREATER THAN 10 FEET AND WATER ENTRY IS AN ISSUE A SAFETY OVER FLOW FITTING MAY BE INSTALLED IN CUSTOMER RISER BELOW PANEL. (I) (b)

(C) **LARGER THREE-PHASE CUSTOMERS USING CABLE:** WHEN ELEVATION CHANGE IS GREATER THAN 10 FEET OR PANEL IS LOCATED IN CUSTOMER SUB-STRUCTURE, A SECONDARY OUTDOOR PULL SECTION OR TERMINATOR MAY BE LOCATED NEXT TO POINT OF ELEVATION TRANSITION TO PREVENT WATER ENTRY.

(D) **TRANSFORMER WITH BUS DUCT:** IF TRANSFORMER IS WITH 3 FEET OF BUILDING STRUCTURE, USE WEATHER PROOF BUS DUCT TO MAKE A TRANSITION THROUGH WALL AND DOWN IN TO SUB-STRUCTURE TO PREVENT WATER ENTRY.

E. TO PREVENT WATER ENTRY, WHEN CONDUIT IS INSTALLED ALL JOINTS SHALL BE FULLY GLUED 360 DEGREES FOR STRENGTH AND A WATER TIGHT SEAL. CONDUITS SHALL BE PROTECTED DURING BACK FILLING WITH SOIL TO PREVENT ROCK DAMAGE, CRUSHING/COMPRESSING, CRACKING, KINKING OR PULLING OUT OF THE FORMS AND STRUCTURES. CEMENT SLURRY CONDUITS SHALL HAVE DUCT SEPARATORS AND BE SECURED IN TRENCH TO PREVENT CONDUIT PACKAGE FROM FLOATING DURING THE BACK FILL PROCESS THAT CAN DAMAGE THE CONDUIT AND CREATE POTENTIAL FUTURE LEAKS.

(F) WHEN WATER TABLE RISES, WE KNOW WATER WILL MIGRATE IN TRENCHES AND DISTURBED SOIL. LARGE BUILDING WITH SURROUNDING DISTURBED SOIL. WILL ALLOW WATER TO ACCUMULATE AROUND SUB-STRUCTURE AND ANY COLD/CASTING JOINT, CRACKS, SAW CUTS, OR PVC CONDUIT TRANSITION THROUGH CEMENT, WILL CAUSE LEAKS. (H) (J) (K)

G. UNOCCUPIED CONDUITS TRANSITIONING FROM ONE SUB-STRUCTURE TO ANOTHER MAY BE PLUGGED AT BOTH ENDS WITH EXPANDABLE DUCT PLUGS. CONDUITS WITH CONDUCTORS CAN USE THE TYCO SEALING SYSTEM. (c)

(H) NOTE CONDUIT SEPARATION, THIS ALLOWS A HIGH QUALITY POLYMER SEALANT TO BE APPLIED 360 DEGREES AROUND CONDUIT ON OUTSIDE OF FOUNDATION.

(J) AFTER CONDUIT IS SEALED WATER PROOF MASTIC SEALANT IS APPLIED TO CONCRETE AND AREA AROUND CONDUIT TO PREVENT WATER ENTRY.

(K) DURING PROCESS OF BUILDING FORMS FOR FOUNDATION, INSIDE THE AREA THE CONDUIT TRANSITIONS THROUGH, APPLY A ONE-INCH THICK AND ONE-INCH WIDE LAYER OF SEALANT MASTIC AROUND CONDUIT IN CENTER OF FORM BEFORE CONCRETE IS POURED.

TABLE OF CONTENTS

## BILL OF MATERIALS: NONE

## NOTES:

(I) THIS INSTALLATION IS FOR EXTERIOR WALL MOUNTED PANEL USE ONLY. IT IS INSTALLER'S RESPONSIBILITY TO FOLLOW ALL APPLICABLE STATE AND LOCAL ELECTRICAL CODES.

(II) WHEN PVC CONDUIT TRANSITION THROUGH CONCRETE, THE SMOOTH SURFACE OF THE PVC AND CONCRETE CAN CREATE A COLD JOINT AND THE HYDRAULIC ACTION AND PRESSURE OF WATER AROUND A FOUNDATION CAN LEAK.

## REFERENCE:

(a) SEE UG3605, FIGURE 1 FOR CORRECT BOX SIZE.

(b) SEE SG304 FOR INSTALLATION INSTRUCTIONS.

(c) SEE UG3948 FOR APPLICATION AND INSTALLATION INSTRUCTIONS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 03/30/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

ELEVATION OF CUSTOMER FACILITIES PREVENTING WATER ENTRY

UG3960.2

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 4002 | 600V ALUMINUM CABLE SIZES |
| 4003 | 600V COPPER CABLE SIZES |
| 4004 | 12KV CABLE SIZES |
| 4005 | CABLE PULLING TENSIONS, PRIMARY AND SECONDARY |
| 4006 | CABLE PULLING GRIPS, PRIMARY AND SECONDARY |
| 4007 | CABLE PULLING EYES, PRIMARY |
| 4008 | MINIMUM BENDING RADIUS FOR U.G. ALUMINUM/COPPER CABLES |
| 4010 | CABLE PULLING COMPOUND |
| 4011 | CABLE TAIL LENGTH REQUIREMENTS |
| 4012 | CABLE AMPACITIES |


© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | UG4009 REMOVED | EDM | EJA | GLW | KRG | 05/31/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | TR | MJC | 09/02/2010 | D | | | | | | |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

CABLES
TABLE OF CONTENTS

UG4001.1

**SCOPE:** THIS STANDARD LISTS LOW VOLTAGE ALUMINUM CABLES.

## TABLE 1

| 600V ALUMINUM CROSS-LINKED POLYETHYLENE | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| WIRE SIZE | CONDUIT MIN. SIZE (IN) | REEL FOOTAGE | REEL CODE | | | REEL MAT'L | STOCK NUMBER | U-NUMBER REFERENCE | SECONDARY WORK | | SERVICE WORK | |
| | | | FD (IN) | IT (IN) | DD (IN) | | | | DESIGN UNITS | SAP CU | DESIGN UNITS | SAP CU |
| 2-#8 (B) (b) (f) | 3 | 2,000 | 30 | 18 | 10 | WOOD | S196176 | U-10.011 | U/2-#8 | U/2-#8 | U/2-#8 | U/2-#8SV |
| 2-#2<br>1-#4 | 3 | 2,000 | 35 | 28 | 18 | COIL | S197504 | U-10.02 | U1P-#2 | U1P-#2 | U1P-#2 | U1P-#2SV |
| 2-1/0<br>1-#2 | 3 | 2,000 | 40 | 28 | 18 | COIL | S197472 | U-10.04 | U1P1/0 | U1P1/0 | U1P1/0 | U1P1/0SV |
| 2-3/0<br>1-1/0 | 3 | 1,300 | 40 | 28 | 18 | COIL | S197536 | U-10.06 | U1P3/0 | U1P3/0 | U1P3/0 | U1P3/0SV |
| 3-3/0<br>1-1/0 | 3 | 2,000 | 58 | 32 | 21 | WOOD | S197592 | U-10.06 | U3P3/0 | U3P3/0 | U3P3/0 | U3P3/0SV |
| 2-350KCMIL<br>1-3/0 | 3 | 1,200 | 58 | 32 | 24 | WOOD | S197568 | U-10.08 | U1P350 | U1P350 | U1P350 | U1P350SV |
| 3-350KCMIL<br>1-3/0 | 3 | 1,000 | 58 | 32 | 28 | WOOD | S197594 | U-10.082 | U3P350 | U3P350 | U3P350 | U3P350SV |
| 2-500KCMIL (A)<br>1-350KCMIL | 3 | 2,000 | 84 | 45 | 42 | STEEL | S197450 | U-10.09 | U1P500 | U1P500 | U1P500 | U1P500 |
| 3-500KCMIL<br>1-350KCMIL | 4 | 2,000 | 84 | 45 | 42 | STEEL | S197596 | U-10.092 | U3P500 | U3P500 | U3P500 | U3P500SV |
| 3-1000KCMIL<br>1-750KCMIL | 5 | 1,000 | 84 | 36 | 42 | STEEL | S197598 | U-10.095 | 3P1000 | 3P1000 | 3P1000 | 3P1000 |

## TABLE 2

| ABBREVIATIONS | | |
|---|---|---|
| TOPIC | ABBREVIATION | DEFINITION |
| | KCMIL | THOUSAND CIRCULAR MILLS |
| REEL CODE | FD | FLANGE DIAMETER |
| | IT | INSIDE TRAVERSE WIDTH |
| | DD | DRUM DIAMETER |

## INSTALLATION:

(A) 2-500 KCMIL AND 1-350 KCMIL REQUIRE 3-INCH CONDUIT MIN.

(B) 2-#8 WIRE USED FOR STREET LIGHTING SHALL BE INSTALLED IN 1-INCH POLYETHYLENE (PE) CONDUIT. 2-#8 WIRE FROM A RISER POLE TO THE FIRST LOCATION SHALL BE INSTALLED IN 2-INCH CONDUIT.

C. CABLE ENDS SHALL BE SEALED WITH SEALING COMPOUND AND VINYL PLASTIC TAPE TO PREVENT MOISTURE ENTRY.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. FOR SDG&E CONDUIT AND CONDUIT FITTINGS, SEE UG3373.

(b) FOR SPLICING OR REPAIRING FLEXIBLE CONDUIT, SEE UG3383.

c. FOR SERVICE LATERAL CONDUIT REQUIREMENTS, SEE UG3942.

d. FOR CABLE POLE CONDUIT REQUIREMENTS, SEE OH1404UG4204.

e. FOR CABLE PULLING LIMITATIONS, SEE UG4005.

(f) FOR CABLE POLE RISER INSTALLATION, SEE OH1404UG4204.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | DW | 02/24/2014 | F | | | | | | |
| B | REVISION | - | - | KN | DW | 01/22/2014 | E | EDITORIAL CHANGES | GLC | FRC | FRC | FRC | 02/15/2022 |
| A | REVISION | - | - | TR | MJC | 09/10/2010 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD LISTS LOW VOLTAGE COPPER CABLES.

**ATTENTION:**

* THIS CABLE IS NOT TO BE USED IN NEW INSTALLATIONS OR WHEN A CUSTOMER INCREASES THEIR PANEL SIZE AND THE ALUMINUM CABLE REQUIRED TO SERVE THE PANEL WILL NOT FIT IN EXISTING CONDUIT. AVAILABILITY OF THIS CABLE DOES NOT ELIMINATE THE REQUIREMENT FOR A CONDUIT UPGRADE TO MEET REQUIREMENTS OF THE NEW PANEL. THIS CABLE IS ONLY TO BE USED TO REPLACE EXISTING ALUMINUM CABLE IN SIDA CONDUITS WHEN LARGER ALUMINUM CABLE IS REQUIRED TO CORRECT SDG&E LOW VOLTAGE PROBLEMS AND THE LARGER CABLE WILL NOT FIT IN EXISTING CONDUITS.

**TABLE 1**

| 600V COMPACT COPPER CROSS-LINKED POLYETHYLENE | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| WIRE SIZE | CONDUIT MIN. SIZE (IN) | REEL FOOTAGE | REEL CODE | | | REEL MAT'L | WEIGHT (LBS/1,000 FT) | STOCK NUMBER | AMPACITY (AMPS) | U-NUMBER REFERENCE | DESIGN UNITS |
| | | | FD (IN) | IT (IN) | DD (IN) | | | | | | |
| 2-1/0 | 1 1/4 SIDA | 2,000 | 45 | 28 | 21 | WOOD | S870 | S197510 | 170 | - | TCU1/0 |
| 1-#2 | | | | | | | | | | | |
| 2-250 | 2 SIDA | 1,000 | 48 | 28 | 24 | WOOD | S2240 | S197512 | 315 | - | TCU250 |
| 1-#4/0 | | | | | | | | | | | |

**TABLE 2**

| ABBREVIATIONS | | |
|---|---|---|
| TOPIC | ABBREVIATION | DEFINITION |
| | KCMIL | THOUSAND CIRCULAR MILLS |
| REEL CODE | FD | FLANGE DIAMETER |
| | IT | INSIDE TRAVERSE WIDTH |
| | DD | DRUM DIAMETER |

**INSTALLATION:**

A. CABLE ENDS SHALL BE SEALED WITH SEALING COMPOUND AND VINYL PLASTIC TAPE TO PREVENT MOISTURE ENTRY.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. FOR SDG&E CONDUIT AND CONDUIT FITTINGS, SEE UG3373.

b. FOR SPLICING OR REPAIRING FLEXIBLE CONDUIT, SEE UG3383.

c. FOR SERVICE LATERAL CONDUIT REQUIREMENTS, SEE UG3942.

d. FOR CABLE POLE RISER INSTALLATION, SEE OH1404UG4204.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | DW | 02/24/2014 | F | | | | | | |
| B | REVISION | - | - | KN | DW | 01/22/2014 | E | | | | | | |
| A | REVISION | - | - | TR | MJC | 09/10/2010 | D | MOVED FROM UG4002 | EDM | JIK | - | - | 09/16/2021 |

**SCOPE:** THIS STANDARD LISTS HIGH VOLTAGE CABLES.

## TABLE 1

| ALUMINUM | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| WIRE SIZE | CONDUIT MIN. SIZE (IN) | REEL FOOTAGE | REEL CODE | | | REEL MAT'L | STOCK NUMBER | DESIGN UNITS | U-NUMBER REFERENCE |
| | | | FD (IN) | IT (IN) | DD (IN) | | | | |
| 1/C #2 SOL TRXLPECN-PEJ | 3 | 4,300 | 58 | 32 | 28 | WOOD | S197644 | RJN1#2 | U-12.041 |
| 2-1/C #2 SOL TRXLPECN-PEJ | 3 | 2,150 | 58 | 32 | 28 | WOOD | S197646 | RJN2#2 | U-12.042 |
| 3-1/C #2 SOL TRXLPECN-PEJ (C) | 4 | 2,000 | 84 | 45 | 42 | STEEL | S197656 | RJN3/2 | U-12.043 |
| 3-1/C 2/0 STR TRXLPECN-PEJ (C) | 4 | 2,000 | 84 | 45 | 42 | STEEL | S197648 | RJN2/0 | U-12.061 |
| 3-1/C 350 KCMIL STR TRXLPECN-PEJ (B) | 5 | 600 (A)<br>1,200 | 90 | 45 | 42 | STEEL | S197650 | RJN350 | U-12.08 |
| 3-1/C 750 KCMIL COMP EAM-PEJ | 4 | 1,200 | 96 | 45 | 42 | STEEL | S197640 | RCPJ750 | U-13.1 |
| 3-1/C 1000 KCMIL STR TRXLPECN-PEJ | 5 | 600 (A)<br>1,100 | 96 | 60 | 42 | STEEL | S197654 | RJ1000 | U-12.096 |
| **COPPER** | | | | | | | | | |
| 3-1/C 750 KCMIL COMP EAM-PEJ | 4 | 1,100 | 96 | 45 | 42 | STEEL | S197642 | RCPC750 | U-13.2 |
| 3-1/C 1000 KCMIL STR TRXLPECN-PEJ | 5 | 780 | 96 | 60 | 42 | STEEL | S197652 | R1000CU | U-13.5 |

## TABLE 2

| BARE COPPER | | | | | |
|---|---|---|---|---|---|
| WIRE SIZE | FT PER LBS | WEIGHT (LBS/1,000 FT) | STOCK NUMBER | DESIGN UNITS | U/M |
| #2, 7 STR SOFT DRAWN | 4.7 | 212 | S812818 (X) | GDWIRE | LBS |
| 1/0 STR SOFT DRAWN | 3 | 333 | S812852 | - | LBS |
| 4/0 STR SOFT DRAWN | 1 | 1,000 | S812764 | - | LBS |

## TABLE 3

| ABBREVIATIONS | | |
|---|---|---|
| TOPIC | ABBREVIATION | DEFINITION |
| | 1/C | ONE CONDUCTOR |
| | 3/C | THREE CONDUCTOR |
| | TRXLPECN-PEJ | TREE RETARDANT CROSS-LINKED POLYETHYLENE INSULATION, CONCENTRIC NEUTRAL, POLYETHYLENE JACKET |
| | EAM-PEJ | ETHYLENE ALKENE COPOLYMER INSULATION, FLAT STRAP NEUTRAL, POLYETHYLENE JACKET |
| | SOL | SOLID |
| | STR | STRANDED |
| | COMP | COMPACT STRANDED |
| | KCMIL | THOUSAND CIRCULAR MILLS |
| | U/M | UNIT OF MEASURE |
| REEL CODE | FD | FLANGE DIAMETER |
| | IT | INSIDE TRAVERSE WIDTH |
| | DD | DRUM DIAMETER |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | DW | 02/24/2014 | F | | | | | | |
| B | REVISION | - | - | KN | DW | 01/22/2014 | E | TABLE UPDATE | EDM | RSL | JAS | KRG | 10/21/2022 |
| A | REVISION | - | - | TR | MJC | 09/10/2010 | D | MOVED FROM UG4002 | EDM | JIK | - | - | 09/16/2021 |

**INSTALLATION:**

(A) FOR SPECIAL PURCHASE ONLY.

(B) MAY BE INSTALLED IN EXISTING 4-INCH CONDUITS. (d)

(C) MAY BE INSTALLED IN EXISTING 3-INCH CONDUITS. WHEN 2/0 CABLE IS PULLED INTO EXISTING 3-INCH CONDUITS. REMOVE CABLE JACKET WHERE CABLE PULLING GRIP IS INSTALLED (APPROX. 3 FEET). (d)

D. THESE CABLES TO BE INSTALLED THREE IN PARALLEL ONLY.

**BILL OF MATERIALS:** NONE

**NOTES:**

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

a. FOR CABLES NO LONGER PURCHASED, SEE FMO UG4099 (FIELD MAINTENANCE ONLY).

b. FOR CABLE PULLING LIMITATIONS, SEE UG4005.

c. FOR CABLE END SEALS, SEE UG4109.

(d) SEE UG3372.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | DW | 02/24/2014 | F | | | | | | |
| B | REVISION | - | - | KN | DW | 01/22/2014 | E | TABLE UPDATE | EDM | RSL | JAS | KRG | 10/21/2022 |
| A | REVISION | - | - | TR | MJC | 09/10/2010 | D | MOVED FROM UG4002 | EDM | JIK | - | - | 09/16/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV CABLE SIZES

UG4004.2

**SCOPE:** THIS STANDARD SHOWS MAXIMUM CABLE PULLING TENSIONS AND CONDUCTOR CHARACTERISTICS.

## TABLE 1

**MAXIMUM PULLING TENSIONS UNDERGROUND ELECTRICAL CABLES**

| CONDUCTOR SIZE (AWG/KCMIL) | CABLE TYPE | CONDUCTOR TYPE | STOCK NUMBER | WEIGHT (LBS/1,000 FT) | MAX. TENSION (LBS) (A) | | AREA PHASE CONDUCTOR (CIRC MIL) |
|---|---|---|---|---|---|---|---|
| | | | | | GRIP | EYE (B) | |
| **PRIMARY CABLES** | | | | | | | |
| 1/C #2 SOL | XLPECN-PEJ | AL | S197600 | 440 | 530 | -- | 66,360 |
| 2 - 1/C #2 SOL | XLPECN-PEJ | | S197602 | 880 | 1,000 | -- | 66,360 |
| 3 - 1/C #2 SOL | XLPECN-PEJ | | S197622 | 1,220 | 1,000 | -- | 66,360 |
| 3 - 1/C 2/0 | XLPECN-PEJ | | S197606 | 1,670 | 1,000 | -- | 133,100 |
| 3 - 1/C 350 | XLPECN-PEJ | | S197608 | 3,335 | 1,000 | 5,600 | 350,000 |
| 3 - 1/C 750 COMP | EPR-PEJ | | S195010 | 4,600 | 1,000 | 7,000 | 750,000 |
| 1/C 1000 | XLPECN-PEJ | | S197628 | 2,140 | -- | 7,000 | 1,000,000 |
| 3 - 1/C 1000 | XLPECN-PEJ | | S197618 | 7,320 | 1,000 | 7,000 | 1,000,000 |
| 3 - 1/C 750 COMP | EPR-PEJ | CU | S195028 | 9,640 | 1,000 | 7,000 | 750,000 |
| 3 - 1/C 1000 | XLPECN-PEJ | | S197610 | 13,600 | 1,000 | 7,000 | 1,000,000 |
| **SECONDARY CABLES** | | | | | | | |
| 2 - #8 | XLPE | AL | S196176 | 69 | 364 | -- | 16,510 |
| 2 - #2 & 1 - #4 | XLPE | | S197504 | 256 | 1,000 | -- | 66,360 |
| 2 - 1/0 & 1 - #2 | XLPE | | S197472 | 395 | 1,000 | -- | 105,600 |
| 2 - 3/0 & 1 - 1/0 | XLPE | | S197536 | 588 | 1,000 | -- | 167,800 |
| 3 - 3/0 & 1 - 1/0 | XLPE | | S197592 | 810 | 1,000 | -- | 167,800 |
| 2 - 350 & 1 - 3/0 | XLPE | | S197568 | 1,090 | 1,000 | -- | 350,000 |
| 3 - 350 & 1 - 3/0 | XLPE | | S197594 | 1,520 | 1,000 | -- | 350,000 |
| 2 - 500 & 1 - 350 | XLPE | | S197450 | 1,621 | 1,000 | -- | 500,000 |
| 3 - 500 & 1 - 350 | XLPE | | S197596 | 2,215 | 1,000 | -- | 500,000 |
| 3 - 1000 & 1 - 750 | XLPE | | S197598 | 4,300 | 1,000 | -- | 1,000,000 |
| 2 - 1/0 & 1 - #2 | XLPE | CU | S197510 | 870 | 1,000 | -- | 105,600 |
| 2 - 250 & 1 - 4/0 | XLPE | | S197512 | 2,240 | 1,000 | -- | 250,000 |

TABLE OF CONTENTS

## INSTALLATION:

(A) WHEN CALCULATING PULLING TENSION, DO NOT EXCEED MAXIMUM TENSION LIMITS.

(B) CABLE PULLING EYES ARE ONLY AVAILABLE FOR 350, 750, AND 1000 KCMIL ALUMINUM (XLPE-PEJ) AND 750 AND 1000 KCMIL COPPER (XLPE-PEJ) PRIMARY CABLES. ALL OTHER CABLES SHALL BE LIMITED TO GRIP TENSION SPECIFIED.

C. THE MAXIMUM PULLING TENSION OF THE PULLING EQUIPMENT IS 7,000 LBS.

D. SINGLE CONDUCTOR 1000 KCMIL AL CABLES ARE TO BE INSTALLED THREE IN PARALLEL ONLY USING NON-CRIMP PULLING EYES AND WIRE BRIDLE.

E. MAXIMUM COMBINED WORKING LOAD FOR WIRE BRIDLE FOR ATTACHING THREE-PHASE SINGLE CONDUCTOR PULLING EYES IS 9,000 LBS.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

**SCOPE:** THIS STANDARD DESCRIBES THE METHOD TO BE USED WHEN CALCULATING PRIMARY CABLE PULLING TENSIONS USING A SET OF FORMULAS MANUALLY.

## ATTENTION:

* FOR ALL CALCULATIONS, THE COEFFICIENT OF FRICTION SHOULD BE .70 AND THE USE OF CABLE PULLING LUBRICANT IS REQUIRED FOR JACKETED CABLE.

## DEFINITIONS:

- **CABLE PULLING TENSION:** THE FORCE REQUIRED (IN POUNDS) TO PULL A CABLE THROUGH A CONDUIT. MAXIMUM CABLE TENSIONS HAVE BEEN SET TO PROTECT THE CABLE FROM DAMAGE DUE TO EXCESSIVE PULLING FORCE.
- **CABLE SIDEWALL PRESSURE (SWBP):** THE PRESSURE EXERTED BY THE CABLE ON THE SIDEWALL OF THE CONDUIT WHEN GOING THROUGH ITS BENDS. THIS PRESSURE IS CAUSED BY THE TENSION AND WEIGHT OF THE CABLE WHICH TENDS TO FORCE IT AGAINST THE CONDUIT WALL. THIS SWBP CAN BE ESTIMATED USING THE TENSION IN CABLE AT BEND EXIT, DIVIDED BY THE INSIDE RADIUS OF BEND (FT).

## INSTALLATION:

A. THE NOMINAL (CENTERLINE) RADIUS OF THE BEND MAY BE USED TO CALCULATE SIDEWALL BEARING PRESSURE.

**TABLE 1**

| MAXIMUM ALLOWABLE SIDEWALL BEARING PRESSURE | | |
|---|---|---|
| **CONDUITS** | **CABLE** | **LBS/FT** |
| CONCRETE ENCASED | JACKETED | 1,250 |
| CONCRETE ENCASED | UNJACKETED | 750 |
| DIRECT BURIED | -- | 300 |

B. SEE SHEET 1 TABLE 1 FOR MAXIMUM TENSION WHEN PULLING CABLES USE CASKET GRIP.


C. SEE SHEET 1 TABLE 1 FOR MAXIMUM TENSION WHEN PULLING CABLES USING PULLING EYE.

**PULLING TENSION CALCULATIONS**

(D) THE INTENT OF THE FOLLOWING EQUATIONS IS TO HELP DETERMINE TENSIONS FOR A TYPICAL CABLE INSTALLATION. IN ORDER TO USE THESE FORMULAS, THE CABLE PULL SHOULD BE DIVIDED INTO SPECIFIC SECTIONS. PLEASE TAKE NOTE THAT THE TENSION OBTAINED WHEN PULLING IN ONE DIRECTION OFTEN DIFFERS FROM THE TENSION OBTAINED WHEN PULLING IN THE OPPOSITE DIRECTION, THIS IS DUE TO THE SLOPE OF THE PULL AND THE LOCATION OF THE BENDS.


(1) ANGLE THETA (DEG) MEASURED FROM HORIZONTAL AXIS.

(2) THE VALUE OF K (THE CURVE CONSTANT) IS DETERMINED BY THE ANGLE, IN DEGREES, OF THE CURVE SECTION. E.G. $T_2 = T_1 K$





$T_2 = T_1 + L\ W\ C$

EQUATION 1
STRAIGHT SECTION
CASE 1: HORIZONTAL





$T_2 = T_1 + L\ W\ [SIN\ \theta\ + COS\ \theta]$

EQUATION 2 (D1)
STRAIGHT SECTION
CASE 2: INCLINE UPWARD




$T_2 = T_1 + L\ W\ [SIN\ \theta\ - COS\ \theta]$

EQUATION 3 (D1)
STRAIGHT SECTION
CASE 3: INCLINE DOWNWARD




$T_{OUT} = T_{IN}\ K,$

EQUATION 3 (D2)
CURVE SECTION

**FIGURE 1** (D) (E)
TYPICAL CABLE INSTALLATION TENSION EQUATIONS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

## INSTALLATION (CONT'D):

(E) THE COMPLETE PULLING EQUATIONS ARE MORE COMPLEX THAN THOSE ON SHEET 2 AND INCLUDE WEIGHT CORRECTION FACTORS FOR STRAIGHT AND INCLINED PULLS. USE OF THESE EQUATIONS IS TOO TIME CONSUMING FOR EVERY PULL. IF MORE COMPLEX CALCULATION IS NEEDED, USE THE INTELLICADD PROGRAM FOR CABLE PULLING. THIS PROGRAM MAKES FAST AND CONVENIENT CALCULATIONS ON A PC. (D)

1. INITIAL TENSION: ASSUME 50 LBS REEL TENSION AT THE BEGINNING OF ALL PULLS, E.G. BOTTOM OF FIRST ELBOW OF PADMOUNT EQUIPMENT OR FEED-IN POINT OF SUBSTRUCTURES.

### TABLE 2

| LEGEND | |
|---|---|
| **VARIABLE AND FUNCTION** | **DESCRIPTION** |
| T | PULLING TENSION AT A POINT "X" (T = TENSION AT POINT NUMBER 1) |
| L | LENGTH OF STRAIGHT SECTION "X" (L = LENGTH OF STRAIGHT SECTION NUMBER 1) |
| W | WEIGHT OF CABLE IN LBS FOOT (LBS/FT) SHEET 1 TABLE 1 LISTS CABLE WEIGHT IN LBS/1,000 FT TO FIND LBS/FT DIVIDE BY 1,000, E.G. W (1/C #2 SOL XLPECN-PEJ AL) = $\frac{440}{1,000}$ = .44 LBS/FT) |
| C | .70 (COEFFICIENT OF FRICTION) |
| $\theta$ | GREEK ALPHABET LETTER USED TO IDENTIFY OR NAME AN ANGLE. PRONOUNCED "THETA". |
| K | CURVE CONSTANT |
| SIN | ABBREVIATION FOR SINE, A TRIGONOMETRY RATIO RELATED TO ANGLES. (SIN $\theta$ = *SINE OF THE ANGLE THETA)* |
| COS | ABBREVIATION FOR COSINE, A TRIGONOMETRY RATIO RELATED TO ANGLES. (COS $\theta$ = *COSINE OF THE ANGLE THETA)* |

### TABLE 3

| CURVE CONSTANTS TABLE | | |
|---|---|---|
| ***θ ANGLE (DEG)*** | **SIN *θ*** | **COS *θ*** |
| 2 | .035 | .999 |
| 3 | .052 | .999 |
| 4 | .070 | .998 |
| 5 | .087 | .996 |
| 6 | .105 | .995 |
| 7 | .129 | .993 |
| 8 | .139 | .990 |
| 9 | .156 | .988 |
| 10 | .174 | .985 |
| 11 | .191 | .982 |
| 12 | .208 | .978 |
| 13 | .225 | .974 |
| 14 | .242 | .970 |
| 15 | .259 | .966 |

### TABLE 4

| CURVE CONSTANTS TABLE | |
|---|---|
| **ANGLE (DEG)** | **K VALUE** |
| 11.25 | 1.05 |
| 22.5 | 1.10 |
| 33.75 | 1.16 |
| 45 | 1.22 |
| 56.25 | 1.28 |
| 67.5 | 1.34 |
| 78.75 | 1.41 |
| 90 | 1.48 |

F. DO NOT EXCEED MAXIMUM LIMITS FOR PULLING EYE OR GRIP, OR SIDEWALL PRESSURE WHEN CALCULATING PULLING TENSION ON SHEET 1.

G. SIDEWALL PRESSURE IS CALCULATED AT THE EXIT OF THE BEND.

H. TO OBTAIN LOWEST TENSION, USE AS FEW CURVED SECTIONS AS POSSIBLE WITH MAXIMUM POSSIBLE RADIUS OF CURVATURE.

J. PULLING TENSIONS SHALL BE CALCULATED FOR PULLING FROM EACH END OF THE CONDUIT RUN. THE CUSTOMER PROJECT PLANNER SHALL SPECIFY THE DIRECTION OF PULL, NOT TO EXCEED THE CABLE OR CONDUIT LIMITS. THE DIRECTION USUALLY RESULTING IN THE MINIMUM TENSION IS WHEN FEED-IN END IS NEAREST THE CURED SECTIONS. **ASSUME CABLE WILL BE PULLED UP THE CABLE POLE WHEN CONDUIT RISER IS USED.**

K. FOR PRIMARY OR SECONDARY CABLE WHERE PULLING TENSIONS ARE CALCULATED FOR BOTH DIRECTIONS: OCCASIONALLY THE CALCULATIONS FROM ONE DIRECTION APPLIES TO A PARTICULAR SITUATION WHILE THE OTHER DIRECTION CALCS ARE TOO STRINGENT. WHEN THIS HAPPENS, THE DIRECTION WITH THE LOWEST TENSION WOULD APPLY AND MUST BE NOTED ON THE JOB PRINT. CARE SHOULD BE TAKEN TO ENSURE NO OBSTACLES EXIST FOR PULLING IN THIS DIRECTION. NOTE VEHICLE ACCESS, WALLS, TRAFFIC, ETC.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

## INSTALLATION (CONT'D):

### (L) SAMPLE CALCULATION TO DETERMINE PULLING TENSION AND DIRECTION OF FEED:

**GIVEN:** 1/C #2 SOL AL (XPLECN-PEJ) CABLE
1DB2" CONDUIT
90° = ANGULAR CHANGE IN DIRECTION BETWEEN T3 & T4
L1 = 200'
L2 = 120'
$\theta$ = 5°

**UNDERSTOOD:** C = .70

**NEEDED:** VALUE FOR K (AT 90°)
VALUE FOR SIN 5°
VALUE FOR COS 5°
VALUE FOR W (LBS/FT) FOR CABLE INDICATED





**FIGURE 1** (L)

**FEED CABLE FROM PAD "A"**

$T_2$ = 50, ASSUMES 50 LBS REEL TENSION

$T_3 = T_2 + L_1 W C = 50 + (200 \times .44 \times .70)$
$= 50 + 61.6$
$T3 = 111.6$

$T_4 = T_3 K$ (FOR 90°) $= 111.6 \times 1.48 = 165.17$

$T_5 = T_4 + L_2 W [\text{SIN } \theta + C \text{ COS } \theta] = 165.17 + (120 \times .44 [.087 + (.70 \times .996)])$
$= 165.17 + ( 52.8 [.087 + .697 ])$
$= 165.17 + ( 52.8 [ .784 ])$
$= 165.17 + ( 52.8 \times .784 )$
$= 165.17 + 41.39$
$T_5 = 206.6$

$T_6 = T_5 K$ (FOR 90°) $= 206.6 \times 1.48 = 305.7$

$T_{TOTAL} = T_6 = 306$ LBS

**FEED CABLE FROM PAD "B"**

$T_5$ = 50, ASSUMES 50 LBS REEL TENSION

$T_4 = T_5 - L_2 W [\text{SIN } \theta - C \text{ COS } \theta] = 50 - (120 \times .44 [.087 + (.70 \times .996)])$
$= 50 - ( 52.8 [.087 + .697])$
$= 50 - ( 52.8 [ - .610 ])$
$= 50 - ( 52.8 \times - .610 )$
$= 50 - ( -32.208 )$
$= 50 + 32.208$
$T_4 = 82.208 = 82.21$

$T_3 = T_4 K = 82.21 \times 1.48 = 121.67$

$T_2 = T_3 + L_1 W C = 121.67 + (200 \times .44 \times .70)$
$= 121.67 + 61.6$
$T_2 = 183.27$

$T_1 = T_2 K = 183.27 \times 1.48 = 271.2$

$T_{TOTAL} = T_1 = 271$ LBS

**RESULTS:** TENSION IS WITHIN ACCEPTABLE LIMITS USING PULLING GRIP (OR EYE) AND PULLING FROM EITHER DIRECTION. SWBP AT ELBOWS IS ALSO WITHIN ACCEPTABLE LIMITS FOR DB2" CONDUIT.

**CONCLUSION:** OKAY TO MAKE THE PULL. SINCE TENSION PULLING FROM PAD "B" IS LOWER, THAT IS THE PREFERRED DIRECTION OF PULL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

## INSTALLATION (CONT'D):

**EXAMPLE:**

(M) MAXIMUM DISTANCE FOR L1 WHEN THE PULL IS FROM PAD OR STRUCTURE TO CABLE POLE PRIMARY LEVEL. THIS ASSUMES NO HORIZONTAL BENDS OR SWEEPS.

(1) MAXIMUM ALLOWABLE PULLING TENSION OF THE GRIP THAT WILL NOT DAMAGE THE CABLE.

(2) MAXIMUM SIDEWALL PRESSURE OF DB 4'-0" RADIUS BEND (300 X 4 = 1,200).

(3) MAXIMUM SIDEWALL PRESSURE OF EB 4'-0" RADIUS BEND (1,250 X 4 = 5,000).

4. $L_1$ LIMITED BY VERTICAL PULLING FORCE UP CABLE POLE.





**FIGURE 2** (M)

## TABLE 5

| MAXIMUM PULLING DISTANCE | | | | | | | |
|---|---|---|---|---|---|---|---|
| **SIZE OF CABLE** | **3-1/C #2 SOL TRXLPECN-PEJ 197622** | **2/0 TRXLPECN-PEJ 197606** | **350 TRXLPECN-PEJ 197608** | **750 COMP EPR-PEJ 195010** | **COMP EPR-PEJ COPPER 195028** | **1000 TRXLPECN-PEJ 197618** | **1000 TRXLPECN-PEJ COPPER 197610** |
| MAX. DISTANCE USING GRIP (1,000 LBS) (M1) | 639 | 497 | 229 | 156 | 50 | 83 | 25 |
| MAX. DISTANCE USING GRIP (1,200 LBS) (M2) | -- | -- | 287 | 198 | 110 | 110 | 75 |
| MAX. DISTANCE USING GRIP (5,000 LBS) (M3) | -- | -- | 808 | 575 | 250 | 375 | 180 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

## INSTALLATION (CONT'D):

**EXAMPLE:**

(N) MAXIMUM DISTANCE FOR L1 WHEN THE PULL IS FROM STRUCTURE TO STRUCTURE OR PAD TO STRUCTURE. THIS ASSUMES NO HORIZONTAL BENDS OR SWEEPS.

(1) MAXIMUM ALLOWABLE PULLING TENSION OF THE GRIP THAT WILL NOT DAMAGE THE CABLE.

(2) MAXIMUM ALLOWABLE PULLING TENSION IS 5,600 LBS.





**FIGURE 3** (N)
PREFERRED

## TABLE 6

| MAXIMUM PULLING DISTANCE | | | | | | | |
|---|---|---|---|---|---|---|---|
| **SIZE OF CABLE** | **3-1/C #2 SOL TRXLPECN-PEJ 197622** | **2/0 TRXLPECN-PEJ 197606** | **350 TRXLPECN-PEJ 197608** | **750 COMP EPR-PEJ 195010** | **COMP EPR-PEJ COPPER 195028** | **1000 TRXLPECN-PEJ 197618** | **1000 TRXLPECN-PEJ COPPER 197610** |
| MAX. DISTANCE USING GRIP (N1) (1,000 LBS) | 1,028 | 813 | 407 | 295 | 135 | 185 | 95 |
| MAX. DISTANCE USING EYE | -- | -- | 1,200 (N2) | 1,200 | 1,020 | 1,200 | 725 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

## INSTALLATION (CONT'D):

**EXAMPLE:**

(O) MAXIMUM DISTANCE FOR $L_1$ WHEN THE PULL IS FROM STRUCTURE TO PAD, OR PAD TO PAD. THIS ASSUMES NO HORIZONTAL BENDS OR SWEEPS.

(1) MAXIMUM SIDEWALL PRESSURE OF DB 3'-0" RADIUS BEND (300 X 3 = 900).

(2) MAXIMUM ALLOWABLE PULLING TENSION OF THE GRIP THAT WILL NOT DAMAGE THE CABLE.

(3) MAXIMUM SIDEWALL PRESSURE OF EB 3'-0" RADIUS BEND (1,250 X 3 = 3,750).





**FIGURE 3** (O)
ALTERNATE
NOT PREFERRED DIRECTION

## TABLE 7

| MAXIMUM PULLING DISTANCE | | | | | | | |
|---|---|---|---|---|---|---|---|
| **SIZE OF CABLE** | **3-1/C #2 SOL TRXLPECN-PEJ 197622** | **2/0 TRXLPECN-PEJ 197606** | **350 TRXLPECN-PEJ 197608** | **750 COMP EPR-PEJ 195010** | **750 COMP EPR-PEJ COPPER 195028** | **1000 TRXLPECN-PEJ 197618** | **1000 TRXLPECN-PEJ COPPER 197610** |
| MAX. DISTANCE USING GRIP (O1) (900 LBS) | 604 | 477 | 239 | 173 | 80 | 108 | 55 |
| MAX. DISTANCE USING GRIP (O2) (1,000 LBS) | 677 | 535 | 268 | 194 | 90 | 122 | 65 |
| MAX. DISTANCE USING GRIP (O3) (3,750 LBS) | -- | -- | 1,060 | 770 | 360 | 480 | 260 |

**NOTES:** NONE

**BILL OF MATERIALS:** NONE

**REFERENCE:**

(a) SEE UG4204.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

**SCOPE:** THIS STANDARD LISTS PROPER CABLE PULLING GRIPS AND CABLE PULLING EYES TO BE USED FOR PULLING UNDERGROUND CABLE.




**FIGURE 1**
CABLE PULLING GRIPS

**TABLE 1**

| CABLE PULLING GRIPS | | | | | | | |
|---|---|---|---|---|---|---|---|
| **CONDUCTOR SIZE AWG/KCMIL** | **CABLE TYPE** | **CONDUCTOR TYPE** | **U-NO "REF."** | **GRIP RANGE** | **GRIP STYLE** | **KELLUMS PART NUMBER** | **STOCK NUMBER** |
| **SECONDARY CABLES** | | | | | | | |
| 2 - #8 | -- | -- | U10.011 | 1/2" - 5/8" | SHORT | 033-03-001 | S393370 |
| 2 - #2 & 1 - #4 | -- | -- | U10.02 | 3/4" - 1" | SHORT | 033-03-003 | S393371 |
| 2 - 1/0 & 1 - #2 | -- | -- | U10.04 | 1" - 1 1/4" | SHORT | 033-03-004 | S393372 |
| 2 - 3/0 & 1 - 1/0 | -- | -- | U10.06 | 1" - 1 1/4" | SHORT | 033-03-004 | S393372 |
| 2 - 3/0 & 1 - 1/0 | -- | -- | U10.062 | 1 1/4" - 1 1/2" | SHORT | 033-03-005 | S393373 |
| 2 - 350 & 1 - 3/0 | -- | -- | U10.08 | 1 1/2" - 2" | STD | 033-03-024 | S393472 |
| 3 - 350 & 1 - 3/0 | -- | -- | U10.082 | 1 1/2" - 2" | STD | 033-03-024 | S393472 |
| 2 - 500 & 1 - 350 | -- | -- | U10.092 | 2" - 2 1/2" | STD | 033-03-025 | S393504 |
| 3 - 1000 & 1 - 750 | -- | -- | U10.095 | 3 1/2" - 4" | STD | 033-03-028 | S393552 |
| **PRIMARY CABLES** | | | | | | | |
| 1/C #2 SOL | XLPECN-PEJ | AL | U12.041 | 3/4" - 1" | SHORT | 033-03-033 | S393371 |
| 2 - 1/C #2 SOL | XLPECN-PEJ | | U12.042 | 3/4" - 1" | STD | -- | -- |
| 3 - 1/C #2 SOL | XLPECN-PEJ | | U12.043 | 2" - 2 1/2" | STD | 033-03-025 | S393504 |
| 3 - 1/C 2/0 STR | XLPECN-PEJ | | U12.061 | 2" - 2 1/2" | STD | 033-03-025 | S393504 |
| 3 - 1/C 350 STR | XLPECN-PEJ | | U12.08 | 2 1/2" - 3" | STD | 033-03-026 | S393536 |
| 3 - 1/C 750 STR | EPR-PEJ | | U13.1 | 3 1/2" - 4" | STD | 033-03-028 | S393552 |
| 3 - 1/C 1000 STR | XLPECN-PEJ | | U12.096 | 3 1/2" - 4" | STD | 033-03-028 | S393552 |
| 3 - 1/C 1000 STR | XLPECN-PEJ | CU | U13.5 | 3 1/2" - 4" | STD | 033-03-026 | S393552 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE CABLE PULLING EYES.



END VIEW SIDE VIEW

**FIGURE 1**
CABLE PULLING EYES

**TABLE 1**

| PRIMARY CABLE PULLING EYES | | | |
|---|---|---|---|
| **CONDUCTOR SIZE (AWG/KCMIL)** | **CABLE TYPE** (A) | **U-NO "REF."** | **ENSLEY PART NUMBER** (B) |
| 3-350 | XLPECN-PEJ | U12.08 | 14-E11 |
| 3-1/C 1000 STR | XLPECN-PEJ | U12.096 | 14-E7 |
| | | U13.5 | |




**FIGURE 2**

**TABLE 2**

| THREE CONDUCTOR PULLING EYE | | | |
|---|---|---|---|
| **CONDUCTOR SIZE (AWG/KCMIL)** | **CABLE TYPE** | **U-NO "REF."** | **PART NUMBER** |
| 3-1/C 1000 STR | XLPECN-PEJ | U12.097 | CONTACT STANDARDS FOR INFORMATION |

**INSTALLATION:**

(A) CABLE PULLING EYES SHALL NOT BE USED TO PULL SECONDARY CABLE.

(B) ENSLEY 3 CONDUCTOR PULLING EYE NO LONGER COMMERCIALLY AVAILABLE.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG4005 FOR PROPER APPLICATION OF CABLE PULLING EYE.

b. SEE CONSTRUCTION MANAGEMENT STANDARD PRACTICES MANUAL, PRACTICE NUMBER 215 FOR INSTALLATION PRACTICES FOR THE PULLING EYE.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | JE | JJ | 11/29/2005 | F | MOVED FROM UG4003 | EDM | JIK | - | - | 09/16/2021 |
| B | REVISION | - | - | JE | JJ | 11/17/2005 | E | REVISION | - | - | TR | DW | 02/24/2014 |
| A | REVISION | - | - | AS | VCR | 01/01/2000 | D | REVISION | - | - | JE | MJC | 05/10/2010 |

**SCOPE:** PROVIDE MINIMUM BENDING RADII FOR U.G. ALUMINUM AND COPPER CABLE TO INSURE INTEGRITY OF INSULATION SYSTEM.





**FIGURE 1** (A)

**TABLE 1**

| MINIMUM BENDING RADIUS R (IN) (I) | | |
|---|---|---|
| **CABLE SIZE** | **ONE CONDUCTOR (IN) (II)** | **TRIPLEX (IN)** |
| 2 AL | 6 1/4 | 15 1/4 |
| 2/0 AL | 7 | 17 1/2 |
| 350 AL | 8 3/4 | 21 3/4 |
| 750 AL | 11 | 27 3/4 |
| 1000 AL | 12 | 30 1/4 |
| 750 COMP AL | 9 3/4 | 24 1/4 |
| 750 COMP CU | 9 3/4 | 24 1/4 |
| 1000 CU | 16 | 30 1/4 |

**TABLE 2**

| JACKETED CABLE DIAMETER | | |
|---|---|---|
| **CABLE TYPE** | **CABLE SIZE** | **DIAMETER (IN)** |
| 1/C | #2 | 1.008 |
| | #2/0 | 1.153 |
| | 350 | 1.438 |
| | 750 COMP | 1.600 |
| | 750 | 1.832 |
| | 1000 | 1.997 |
| TRIPLEXED | #2 | 2.172 |
| | #2/0 | 2.485 |
| | 350 | 3.099 |
| | 750 COMP | 3.448 |
| | 750 | 3.948 |
| | 1000 | 4.304 |

## INSTALLATION:

**EXAMPLE:**

(A) 2/0 TRIPLEX (JACKETED) IN 3315 HANDHOLE

OD = (2)(R)+(2)(CABLE DIA) = MINIMUM OUTSIDE DIAMETER

=(2)(17 1/2")+(2)(2.485)

=39.97

**BILL OF MATERIALS:** NONE

## NOTES:

(I) RADIUS IS TO INSIDE BEND, NOT FROM CENTERLINE TO CENTERLINE. SEE FIGURE 1.

(II) ONE CONDUCTOR ALSO APPLIES TO INDIVIDUAL TRIPLEXED CABLES WHEN THEY ARE UNTRIPLEXED.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG4004 | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | JE | MJC | 09/07/2010 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

MINIMUM BENDING RADIUS FOR U.G. ALUMINUM CABLES/COPPER CABLES

UG4008.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS CABLE PULLING COMPOUND USED WHEN PULLING SECONDARY AND PRIMARY CABLES INTO CONDUIT.

## INSTALLATION:

A. ALWAYS USE COMPOUND ON PRIMARY JACKETED OR SECONDARY CABLE DURING CABLE PULLING FOR THE PROTECTION OF CABLE JACKETING AND TO REDUCE FRICTION.

B. COMPOUND IS NOT TO BE CONSIDERED DURING DESIGN PROCESS TO ALLOW A LONGER PULL THAN PERMITTED OTHERWISE.

C. APPLY COMPOUND DIRECTLY ONTO CABLE(S) AS IT IS ENTERING CONDUIT. FRONT END PACKS (LUBRICANT IN PLASTIC BAGS) ARE TO BE PLACED INTO THE CONDUIT DIRECTLY IN FRONT OF THE CABLE PRIOR TO CABLE PULLING. FOLLOW INSTRUCTIONS ON PACKAGE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | COMPOUND, CABLE PULLING, 1 CASE OF 6, 1/2 GALLON FRONT END PACKS | AS REQ'D | -- | S247380 | -- |
| 2 | COMPOUND, CABLE PULLING, 5 GALLON | AS REQ'D | -- | S247384 | -- |

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG4006 | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | - | JLB/ROG | 01/01/1993 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

CABLE PULLING COMPOUND

UG4010.1

**SCOPE:** THIS STANDARD ESTABLISHES CABLE TAIL LENGTH REQUIRED TO LOCATE AND TERMINATE UNDERGROUND CABLE IN EQUIPMENT OR ON CABLE POLES. IT PROVIDES THE NECESSARY ADDITIONAL CABLE FOOTAGE (CABLE TAIL LENGTH) TO THE TOTAL CABLE REQUIREMENTS.

## DEFINITIONS:

- **CABLE TAIL LENGTH:** ADDITIONAL CABLE FOOTAGE REQUIRED BEYOND LATERAL DISTANCE TO ALLOW FOR THE TRENCH DEPTH (Y) AND CABLE TERMINATION (Z).
- **LATERAL DISTANCE:** HORIZONTAL SEPARATION (X) BETWEEN POINTS OF CABLE ENTRY INTO UNDERGROUND EQUIPMENT. THIS IS NORMALLY REPRESENTED AS TRENCH LENGTH BETWEEN ADJACENT PIECES OF EQUIPMENT.





**FIGURE 1**

## TABLE 1





| STANDARD CABLE TAIL LENGTHS FOR CABLE POLES | | |
|---|---|---|
| **DESIGN CONFIGURATION** | **ILLUSTRATIONS** | **CABLE TAIL LENGTHS (FT)** |
| PRIMARY CABLE<br>SECONDARY CABLE |  | CALCULATION OF CABLE TAIL LENGTHS FOR CABLE POLES IS BASED ON THE MEASUREMENT FROM GROUND LINE TO TOP OF CONDUIT PLUS 8 FEET OF CABLE |
| **STANDARD CABLE TAIL LENGTHS FOR PADMOUNTS** | | |
| SINGLE-PHASE TERMINATOR 3522 |  | 6<br>7 WITH HANDHOLE |
| THREE-PHASE TERMINATOR 3520 OR 3521 |  | 8 |
| SINGLE-PHASE FUSE CABINET 3512 |  | 6 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4008 | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | JE | MC | 08/26/2008 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1990 | D | | | | | | |

## TABLE 1 (CONT'D)










| STANDARD CABLE TAIL LENGTHS FOR CABLE POLES | | |
|---|---|---|
| **DESIGN CONFIGURATION** | **ILLUSTRATIONS** | **CABLE TAIL LENGTHS (FT)** |
| THREE-PHASE FUSE CABINET 3513 |  | 8 |
| SINGLE-PHASE LIVEFRONT OR DEADFRONT TRANSFORMER 3711 OR 3712 |  | 6 |
| SINGLE-PHASE DEADFRONT, CLOSED DELTA TRANSFORMER BANK AND HANDHOLE 3714 |  | 14 |
| SINGLE-PHASE DEADFRONT, OPEN DELTA TRANSFORMER WITH HANDHOLE 3713 |  | 11 |
| THREE-PHASE DEADFRONT TRANSFORMER |  | 7 |
| THREE-PHASE LIVEFRONT TRANSFORMER (225 TO 1,000KVA) |  | 10 |
| THREE-PHASE LIVEFRONT TRANSFORMER (1,500 TO 2,500KVA) |  | 13 |
| **STANDARD CABLE TAIL LENGTHS FOR HANDHOLES** | | |
| 3312 |  | 6 |
| 3312 |  | 7<br>(DOUBLE BODY)<br>7 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4008 | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | JE | MC | 08/26/2008 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1990 | D | | | | | | |

## TABLE 1 (CONT'D)











| STANDARD CABLE TAIL LENGTHS FOR HANDHOLES | | |
|---|---|---|
| **DESIGN CONFIGURATION** | **ILLUSTRATIONS** | **CABLE TAIL LENGTHS (FT)** |
| 3314 |  | 8 |
| |  | 19 |
| 3314 WITH CABLE TAPS |  | 9 |
| 3315 |  | 8 |
| 3315 WITH CABLE TAPS |  | 10 |
| 3315 WITH PAD MOUNTED SWITCH 3549 |  | 12 |
| 3316 |  | 13 |
| |  | 25 |
| 3316 WITH CABLE TAPS |  | 16 |
| 3316 WITH PAD MOUNTED SWITCH |  | 14 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4008 | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | JE | MC | 08/26/2008 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1990 | D | | | | | | |

## TABLE 1 (CONT'D)



















| STANDARD CABLE TAIL LENGTHS FOR HANDHOLES | | |
|---|---|---|
| **DESIGN CONFIGURATION** | **ILLUSTRATIONS** | **CABLE TAIL LENGTHS (FT)** |
| 3316<br>WITH SUBSURFACE SWITCH<br>3670 |  | 30 |
| |  | 16 |
| **STANDARD CABLE TAIL LENGTHS FOR MANHOLES** | | |
| 3322<br>EXISTING |  | 25 |
| |  | 11 |
| 3322<br>#2/0 AND BELOW<br>EXISTING |  | 8 |
| 3322<br>350 KCMIL AND ABOVE<br>EXISTING |  | 30 |
| 3322<br>WITH SWITCH<br>EXISTING |  | 12 |
| 3322<br>WITH SWITCH<br>EXISTING |  | 19 |
| 3324<br>14'-0" |  | 16 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4008 | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | JE | MC | 08/26/2008 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1990 | D | | | | | | |

## TABLE 1 (CONT'D)

| STANDARD CABLE TAIL LENGTHS FOR MANHOLES | | |
|---|---|---|
| **DESIGN CONFIGURATION** | **ILLUSTRATIONS** | **CABLE TAIL LENGTHS (FT)** |
| 3324<br>14'-0"<br>2/0 AND BELOW |  | 10 |
| 3324<br>20'-0" |  | 22 |
| 3324<br>20'-0"<br>350 KCMIL AND ABOVE<br>EXISTING |  | 50 |
| 3324<br>14'-0"<br>ONE SWITCH<br>EXISTING |  | 16 |
| 3324<br>14'-0"<br>ONE SWITCH<br>EXISTING |  | 19 |
| 3324<br>20'-0"<br>ONE SWITCH<br>EXISTING |  | 22 |
| 3324<br>20'-0"<br>ONE SWITCH<br>EXISTING |  | 40 |
| 3324<br>20'-0"<br>TWO SWITCHES |  | 34 |
| 3324<br>26'-0"<br>TWO SWITCHES<br>EXISTING |  | 40 |
| 3324<br>26'-0"<br>TWO SWITCHES<br>EXISTING |  | 65 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4008 | EDM | JIK | - | - | 09/16/2021 | F | | | | | | |
| B | REVISION | - | - | JE | MC | 08/26/2008 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1990 | D | | | | | | |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD LISTS THE AMPACITY LIMITATIONS FOR UNDERGROUND CABLES IN NORMAL LOADING SITUATIONS.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THE TABLES PROVIDE THE ALLOWED CABLE AMPACITY ASSUMING ALL CABLES ARE EQUALLY LOADED, ARE THE SAME SIZE AND ARE SPACED 7 1/2 INCHES APART UNLESS OTHERWISE STATED. FOR A MORE ACCURATE DESIGN RATING OR EMERGENCY OVERLOAD RATING, CONTACT DISTRICT ENGINEERING OR DESIGN PLANNING.

**ALUMINUM CABLES**

II. 15KV ALUMINUM CABLE, EB CONDUIT (CONCRETE ENCASED). AMPACITIES ARE PER RUN (FOR EACH PHASE).

**TABLE 1**

| AMPACITY LIMITATIONS | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CABLE SIZE | CONCRETE ENCASED CONDUIT SIZE (IN) | NUMBER OF CONDUCTORS (1/C) | NUMBER OF RUNS, XLPE | | | | | | NUMBER OF RUNS, HMWPE | | | | |
| | | | 1 | 2 | 3 | 4 | 5 | 6 | 2 | 3 | 4 | 5 | 6 |
| 1000 | 5 | 3 | -- | 580 | 530 | 490 | 460 | 430 | -- | -- | -- | -- | -- |
| 750 | 5 | 3 | -- | 500 | 455 | 425 | 395 | 375 | -- | -- | -- | -- | -- |
| 350 | 5 | 3 | -- | 320 | 300 | 280 | 260 | 250 | -- | -- | -- | -- | -- |
| 2/0 | 5 | 3 | -- | 175 | 160 | 155 | 145 | 140 | 155 | 145 | 140 | 130 | 125 |
| #2 | 5 | 3 | -- | 130 | 120 | 110 | 105 | 100 | 115 | 105 | 100 | 95 | 90 |
| #2 | 5 | 1 | -- | 135 | 130 | 125 | 120 | 115 | 120 | 115 | 110 | 105 | 100 |

III. 15KV ALUMINUM CABLE, DB CONDUIT (DIRECT BURIED). AMPACITIES ARE PER RUN (FOR EACH PHASE).

**TABLE 2**

| AMPACITY LIMITATIONS | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CABLE SIZE | DIRECT BURIED CONDUIT SIZE (IN) | NUMBER OF CONDUCTORS (1/C) | NUMBER OF RUNS, XLPE | | | | | | NUMBER OF RUNS, HMWPE | | | | | |
| | | | 1 | 2 | 3 | 4 | 5 | 6 | 1 | 2 | 3 | 4 | 5 | 6 |
| 1000 | 5 | 3 | 620 | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 750 | 5 | 3 | 530 | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 350 | 5 | 3 | 340 | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 2/0 | 4 | 3 | 170 | 160 (IX) | 150 (IX) | 145 | 140 | 130 | 155 | 140 | 135 | 130 | 125 | 120 |
| #2 | 4 | 3 | 125 | 115 (IX) | 110 (IX) | 100 | 95 | 90 | 110 | 100 | 95 | 90 | 90 | 85 |
| #2 | 2 | 1 | 130 | 120 (IX) | 115 (IX) | 115 | 110 | 105 | 115 | 110 | 105 | 105 | 100 | 95 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG4011 | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1992 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## NOTES (CONT'D):

IV. 600V SECONDARY ALUMINUM CABLE, DB CONDUIT (DIRECT BURIED). TOTAL AMPACITY FOR EACH PHASE (WITH 7 1/2 INCHES CENTERLINE TO CENTERLINE SPACING BETWEEN CONDUITS).

### TABLE 3

| AMPACITY LIMITATIONS | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CABLE SIZE | DIRECT BURIED CONDUIT SIZE (IN) | NUMBER OF CONDUCTORS (1/C) | NUMBER OF RUNS | | | | | | | | | | |
| | | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
| 1000 | 5 | 3 | 605 | 1,104 | 1,527 | 1,892 | 2,335 | 2,526 | 2,821 | 3,080 | 3,339 | 3,550 | 3,707 | 3,828 |
| 500 | 4 | 3 | 397 | 736 | 1,029 | 1,288 | 1,595 | 1,746 | 1,953 | 2,144 | 2,313 | 2,470 | 2,607 | 2,712 |
| 350 | 3 | 2 | 318 | 600 | 852 | 1,076 | 1,285 | 1,482 | 1,673 | 1,840 | 2,016 | 2,160 | 2,266 | 2,376 |
| 350 | 3 | 3 | 313 | 586 | 822 | 1,036 | 1,230 | 1,416 | 1,589 | 1,760 | 1,908 | 2,040 | 2,145 | 2,232 |
| 3/0 | 2 | 2 | 202 | 386 | 552 | 704 | 875 | 984 | 1,113 | 1,232 | 1,250 | 1,440 | 1,518 | 1,608 |
| 3/0 | 3 | 3 | 199 | 376 | 534 | 676 | 810 | 936 | 1,057 | 1,160 | 1,269 | 1,350 | 1,419 | 1,500 |
| 1/0 | 2 | 2 | 152 | 292 | 420 | 536 | 645 | 750 | 854 | 944 | 1,044 | 1,130 | 1,188 | 1,248 |
| #2 | 2 | 2 | 113 | 218 | 315 | 404 | 490 | 570 | 651 | 720 | 792 | 860 | 913 | 960 |
| #8 | 1 | 1 | 47 | 92 | 135 | 176 | 215 | 252 | 287 | 320 | 306 | 380 | 407 | 432 |

V. 600V SECONDARY ALUMINUM CABLE, DB CONDUIT (DIRECT BURIED). TOTAL AMPACITY FOR EACH PHASE (WITHOUT 7 1/2 INCHES CENTERLINE TO CENTERLINE SPACING BETWEEN CONDUITS).

### TABLE 4

| AMPACITY LIMITATIONS | | | | | | |
|---|---|---|---|---|---|---|
| CABLE SIZE | DIRECT BURIED CONDUIT SIZE (IN) | NUMBER OF CONDUCTORS (1/C) | NUMBER OF RUNS | | | |
| | | | 1 | 2 | 3 | 4 |
| 1000 | 5 | 3 | -- | 1,092 | 1,476 | 1,848 |
| 500 | 4 | 3 | -- | 724 | 996 | 1,244 |
| 350 | 3 | 2 | -- | 588 | 816 | 1,036 |
| 350 | 3 | 3 | -- | 572 | 789 | 992 |
| 3/0 | 2 | 2 | -- | 376 | 531 | 664 |
| 3/0 | 3 | 3 | -- | 370 | 516 | 644 |
| 1/0 | 2 | 2 | -- | 287 | 405 | 506 |
| #2 | 2 | 2 | -- | 214 | 303 | 384 |
| #8 | 1 | 1 | -- | 92 | 132 | 168 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG4011 | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1992 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## NOTES (CONT'D):

**COPPER CABLES**

VI. 15KV COPPER CABLE, EB CONDUIT (CONCRETE ENCASED). AMPACITIES ARE PER RUN (FOR EACH PHASE).

### TABLE 5

| AMPACITY LIMITATIONS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| CABLE SIZE | CONCRETE ENCASED CONDUIT SIZE (IN) | NUMBER OF CONDUCTORS (1/C) | NUMBER OF RUNS | | | | | |
| | | | 1 | 2 | 3 | 4 | 5 | 6 |
| 1000 (PILC) | 4 | 3/C | -- | 580 | 535 | 495 | 455 | 435 |
| 500 (PILC) | 3 | 3/C | -- | 395 | 370 | 345 | 325 | 310 |
| 500 (PECN) (VIII) | 5 | 3 | -- | 450 | 410 | 390 | 365 | 340 |
| 4/0 (VIII) | 5 | 3 | -- | 275 | 255 | 240 | 225 | 220 |
| #2 (VIII) | 4 | 3 | -- | 130 | 125 | 120 | 115 | 110 |
| #2 (VIII) | 4 | 1 | -- | 155 | 150 | 145 | 140 | 135 |

VII. 15KV COPPER CABLE, DB CONDUIT (DIRECT BURIED). AMPACITIES ARE PER RUN (FOR EACH PHASE).

### TABLE 6

| AMPACITY LIMITATIONS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| CABLE SIZE | DIRECT BURIED CONDUIT SIZE (IN) | NUMBER OF CONDUCTORS (1/C) | NUMBER OF RUNS | | | | | |
| | | | 1 | 2 | 3 | 4 | 5 | 6 |
| 1000 (PILC) | 4 | 3/C | 615 | -- | -- | -- | -- | -- |
| 500 (PILC) | 3 | 3/C | 420 | -- | -- | -- | -- | -- |
| 500 (PECN) (VIII) | 5 | 3 | 470 | -- | -- | -- | -- | -- |
| 4/0 (VIII) | 5 | 3 | 285 | -- | -- | -- | -- | -- |
| #2 (VIII) | 3 | 3 | 145 | 135 (IX) | 125 (IX) | 120 | 115 | 105 |
| #2 (VIII) | 3 | 1 | 175 | 165 (IX) | 155 (IX) | 145 | 140 | 130 |

(VIII) NO LONGER PURCHASED.

(IX) CABLE AMPACITY WITHOUT 7 1/2-INCH CENTERLINE TO CENTERLINE SPACING BETWEEN CONDUITS.

## REFERENCE:

a. SEE DM5521 FOR FEEDER CABLE AMPACITIES BASED ON THERMAL LOADING LIMITS.

b. SEE DM5522 FOR CABLE AMPACITY PROGRAM.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG4011 | EDM | JIK | - | - | 09/16/2021 | E | | | | | | |
| A | REVISION | - | - | JLB | ROG | 01/01/1992 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 4106 | ALUMINUM CONDUCTOR PREPARATION FOR TERMINATIONS |
| 4108 | INSTRUCTIONS FOR SEALING JACKETED CABLE |
| 4109 | CABLE END SEALS |
| 4110 | LOADBREAK ELBOW - PRIMARY NEUTRAL TERMINATION |
| 4111 | OUTDOOR CABLE TERMINALS FOR POLYETHYLENE CABLES |
| 4121 | LIVEFRONT CABLE TERMINATIONS, POLYETHYLENE CABLES (NEW CABLES) |
| 4127 | 15KV CABLE PREPARATION FOR SUBSTATION METAL-CLAD SWITCHGEAR |
| 4147 | 750 COMPACT EPR TO 500 PILC SPLICE |
| 4148 | 3 CONDUCTOR PILC ADAPTER FOR USE WITH 600A ELBOW TEE'S |
| 4167 | SLIP-FIT CONNECTORS |
| 4168 | LAY-IN SECONDARY CONNECTORS |
| 4169 | SECONDARY EXTENSION PLATE FOR PAD-MOUNT TRANSFORMER |
| 4170 | 600V SECONDARY BOLTED CONNECTION AT TRANSFORMER OR BUS |
| 4171 | TRANSFORMER TERMINAL AND BUS COMPRESSION TERMINALS FOR ALUMINUM CONDUCTORS |
| 4172 | STACKING ADAPTERS |
| 4173 | PIN ADAPTERS |
| 4174 | COMPRESSION AND TERMINAL COMPRESSION CONNECTORS |
| 4175 | 0-600V CONNECTORS FOR #8 THROUGH 500 KCMIL ALUMINUM OR COPPER CONDUCTORS & HANDHOLE INSTALLATION |
| 4176 | CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART |
| 4177 | CABLE HANGERS AND ACCESSORIES |
| 4178 | HEAVY DUTY NON-METALLIC CABLE RACK |
| 4179 | 12KV, 200A CONNECTOR ASSEMBLIES IDENTIFICATION CHART |
| 4180 | 12KV, 200A PREMOLDED SPLICE AND CONNECTOR ASSEMBLIES - IDENTIFICATION CHART |


© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | FORMATTING | EDM | JIK | - | - | 06/02/2020 | H | UG4113 MOVED TO FMO | EDM | EJA | GLW | FRC | 02/14/2022 |
| D | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 | G | UG4122 & UG4183 MOVED TO FMO | EDM | EJA | GLW | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | EDM | EJA | JES | CZH | 12/09/2019 | F | EDITORIAL CHANGES | EDM | ADW | GLW | CZH | 11/09/2020 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TERMINATIONS, SPLICING CONNECTIONS
TABLE OF CONTENTS

UG4101.1

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 4181 | 12KV, 200 AND 600A CONNECTOR ASSEMBLIES, CONNECTORS, SPLICES, ACCESSORIES & DESIGN UNITS IDENTIFICATION CHART |
| 4182 | 12KV, 600/200A SPLICES, CONNECTORS AND ACCESSORIES |
| 4184 | VAULT STRETCHER CONNECTOR, DEADBREAK |
| 4185 | 600A EXTENSION SPLICE |
| 4186 | 12KV 600 TO 200A JUNCTION |
| 4187 | CAM-LINK OPERABLE 600A CONNECTOR |
| 4188 | 600A T EXTENSION |
| 4190 | LOADBREAK ELBOW CONNECTOR - 12,000V AND BELOW |
| 4191 | 200A 6930V LOADBREAK 6.9KV, 7.2KV, OR 12KV FUSED ELBOW CONNECTOR |
| 4192 | 200A 15KV LOADBREAK ELBOW EXTENSION |
| 4195 | 200A LOADBREAK ACCESSORIES, 12KV |
| 4196 | 200A DEADBREAK CONNECTORS, 12KV |
| 4197 | 200A DEADBREAK ACCESSORIES, 12KV |
| 4198 | N-JUNCTION CLEER 600A 25KV & SQUARE CLEER 600A 25KV |


© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | FORMATTING | EDM | JIK | - | - | 06/02/2020 | H | UG4113 MOVED TO FMO | EDM | EJA | GLW | FRC | 02/14/2022 |
| D | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 | G | UG4122 & UG4183 MOVED TO FMO | EDM | EJA | GLW | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | EDM | EJA | JES | CZH | 12/09/2019 | F | EDITORIAL CHANGES | EDM | ADW | GLW | CZH | 11/09/2020 |

**SCOPE:** THIS STANDARD DESCRIBES INSTRUCTIONS FOR INSTALLING ALUMINUM CONNECTORS.

## ATTENTION:

* DO NOT POSITION ALUMINUM CONDUCTOR BELOW COPPER TO PREVENT COPPER SALTS FROM RUNNING ONTO ALUMINUM CONDUCTOR.

## INSTALLATION:

A. COMPRESSION CONNECTION - WHERE A CONNECTOR IS COMPRESSED ONTO A CONDUCTOR. (a)

1. WIRE BRUSH THE CONDUCTOR(S) TO CLEAN OFF THE OXIDATION.
2. USE CONNECTOR PREFILLED WITH INHIBITOR BY MANUFACTURER.
3. CRIMP WITH POWER TOOL (IN CORRECT ADJUSTMENT), PROPER DIE, AND PROPER NUMBER OF INDENTS.

B. BOLTED CONNECTION - WHERE A CONNECTOR IS BOLTED TO A CONDUCTOR OR FLAT TERMINAL PAD. A BOLTED CONNECTOR REQUIRES CARE WHEN INSTALLING FOR RELIABILITY: (b)

1. WIRE BRUSH THE CONDUCTOR(S), BOLTED CONNECTOR (UNLESS PREINHIBITED) AND FLAT PADS WITH INHIBITOR (STOCK NUMBER S247200). THE INTENT IS TO WIRE BRUSH/INHIBIT ALL MATING SURFACES, ALUMINUM AND COPPER, TO PREVENT DAMAGE TO ALUMINUM FROM CORROSION IN BOLTED JOINT.
2. BOLT WITH PROPER HARDWARE SILICON BRONZE STAINLESS STEEL FASTENERS FROM SDG&E STOCK (FLAT ROUND WASHERS, HEX HEAD NUTS, CAP SCREWS) AND BELLEVILLE WASHERS. TORQUE STAINLESS STEEL FASTENERS AS FOLLOWS:

   3/8" = 25 FT. LB.

   1/2" = 40 FT. LB.

C. USE TRANSITION PLATE IF BOLTED TO UNTINNED COPPER FLAT PAD. (c)

## BILL OF MATERIALS: NONE

## NOTES:

I. **COMPRESSED AND BOLTED ALUMINUM CONNECTORS**:

a. THE INSTALLATION OF ALUMINUM CONDUCTORS HAS ALWAYS REQUIRED MORE CARE THAN COPPER, DUE TO THE OXIDIZING AND COLD FLOW CHARACTERISTICS OF ALUMINUM WHICH CAN CAUSE PREMATURE CONNECTOR FAILURE IF NOT PROPERLY INSTALLED.

B. FAILED CONNECTORS RECEIVED BY THE MATERIALS TEST LAB ARE ANALYZED FOR CAUSE OF FAILURE. AS A RESULT OF THESE OBSERVATIONS, STANDARDIZED UNDERGROUND INSTRUCTIONS ARE WRITTEN FOR YOUR REFERENCE WHEN INSTALLING ALUMINUM CONNECTORS.

## REFERENCE:

(a) REFER TO UG4121, UG4171, UG4172, UG4173, UG4182, UG4190, UG4196.

(b) REFER TO UG4121, UG4168, UG4171.

(c) REFER TO UG4168.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | -- | -- | 06/02/2020 | E | | | | | | |
| A | REVISION | -- | -- | -- | RSW/VCR | 08/31/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

ALUMINUM CONDUCTOR PREPARATION FOR TERMINATIONS

UG 4106.1

**SCOPE:** THIS STANDARD SHOWS METHODS OF SEALING JACKETED CONCENTRIC NEUTRAL TYPE CABLES WHEN TERMINATING FOR SUBSURFACE OR ABOVE GROUND INSTALLATION APPLICATIONS. ALSO SHOWN ARE MEASUREMENTS OF CONCENTRIC NEUTRAL TERMINATIONS FROM PREMOLDED COMPONENTS/COLD SHRINK OR PORCELAIN POTHEADS.

**TABLE 1**

| ITEM | DESCRIPTION | QUANTITY | STOCK NUMBER |
|---|---|---|---|
| 1 | ELEC-TRO CUT OR EQUIVALENT (80 GRIT) | AS REQ'D | S239682 |
| 2 | ELEC-TRO CUT OR EQUIVALENT (180 GRIT) | AS REQ'D | S239684 |
| 3 | AQUA-SEAL OR EQUIVALENT | AS REQ'D | S442976 |
| 4 | GLASS TAPE, 1/2" | AS REQ'D | S720256 |
| 5 | VINYL PLASTIC TAPE, 3/4" | AS REQ'D | S720580 |
| 6 | SLEEVES, HEAT SHRINK (4-2/0 SIZE) | AS REQ'D | S777984 |
| 7 | SLEEVES, HEAT SHRINK (350 SIZE) | AS REQ'D | S778016 |
| 8 | SLEEVES, HEAT SHRINK (750-1000 SIZE) | AS REQ'D | S778020 |

## INSTALLATION:

### SUBSURFACE INSTALLATION:

(A) SCORE AND CLEAN A MINIMUM OF 2 INCHES, THE CONCENTRIC NEUTRAL JACKET WITH ELEC-TRO CUT CLOTH BEFORE REMOVING THE JACKETING.





**FIGURE 1** (A)

(B) REMOVE CONCENTRIC NEUTRAL JACKET AS REQUIRED.

(C) PULL THE CONCENTRIC NEUTRAL WIRES BACK AND AWAY FROM THE SEMICONDUCTING INSULATION SHIELD.

(D) CLEAN THE SEMICONDUCTING MATERIAL FOR A MINIMUM OF 2 1/2 INCHES NEXT TO THE CONCENTRIC NEUTRAL JACKET WITH ELEC-TRO CUT CLOTH. **DO NOT USE SOLVENT IN THIS AREA.**





**FIGURE 2** (B) (C) (D)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | REVISION | - | - | - | TR/MC | 8/26/2008 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDEGROUND CONSTRUCTION STANDARDS

INSTRUCTIONS FOR SEALING JACKETED CABLE



UG4108.1

TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(E) APPLY A 2 INCH WIDE STRIP OF SEALING COMPOUND OVER THE SEMICONDUCTING MATERIAL NEXT TO THE CONCENTRIC NEUTRAL JACKET.





**FIGURE 3** (E)

(F) BEND CONCENTRIC NEUTRAL WIRES BACK INTO PLACE AROUND THE CABLE AND PRESS THEM INTO THE SEALING COMPOUND.

(G) APPLY A SECOND 2 INCH WIDE LAYER OF SEALING COMPOUND. 1 INCH OF THIS STRIP WILL GO OVER THE CONCENTRIC NEUTRAL JACKET AND 1 INCH OVER THE CONCENTRIC NEUTRAL WIRES & A PORTION OF THE FIRST LAYER OF SEALING COMPOUND.

(H) AT THE EDGE OF THE FIRST LAYER OF SEALING COMPOUND TOWARD THE CUT END OF THE CABLE, APPLY 3 LAYERS OF 1/2 INCH GLASS TAPE OVER THE SEALING COMPOUND. APPLY 3 LAYERS OF 3/4 INCH VINYL PLASTIC TAPE OVER THE GLASS TAPE. DO NOT LEAVE ANY POCKETS UNDER THE TAPE FOR WATER TO COLLECT.





**FIGURE 4** (F)(G)(H)

J. APPLY HEAT SHRINK TUBE OR VINYL PLASTIC TAPE AS DESCRIBED IN J1 AND J2.

(1) APPLY A HEAT SHRINK TUBE OVER THE SEALING COMPOUND, GLASS TAPE, VINYL PLASTIC TAPE & CONCENTRIC NEUTRAL JACKET. APPLY HEAT ALLOWING THE EDGE OF THE HEAT SHRINK TUBE TO BE CENTERED ON THE 3/4 INCH VINYL PLASTIC TAPE. DO NOT APPLY HEAT TO SEMI-CONDUCTING MATERIAL. DO NOT ALLOW HEAT SHRINK MATERIAL TO COME IN CONTACT WITH SEMI-CONDUCTING MATERIAL.





**FIGURE 5** (J1)

(2) VINYL PLASTIC TAPE MAY BE USED INSTEAD OF A HEAT SHRINK TUBE DESCRIBED IN STEP (J1). APPLY 3 LAYERS OF VINYL PLASTIC TAPE COVERING AT LEAST HALF THE CONCENTRIC NEUTRAL BINDING TAPE AND EXTEND AT LEAST 2 INCHES OVER THE CONCENTRIC NEUTRAL JACKET.





**FIGURE 6** (J2)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | REVISION | - | - | - | TR/MC | 8/26/2008 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDEGROUND CONSTRUCTION STANDARDS

INSTRUCTIONS FOR SEALING JACKETED CABLE



UG4108.2

TABLE OF CONTENTS

## INSTALLATION (CONT'D):

**ABOVE GROUND INSTALLATION:**

(K) SCORE AND CLEAN A MINIMUM OF 2 INCHES, THE CONCENTRIC NEUTRAL JACKET WITH ELEC-TRO CUT CLOTH BEFORE REMOVING THE JACKETING.





**FIGURE 7** (K)

(L) REMOVE THE CONCENTRIC NEUTRAL JACKET AS REQUIRED.

(M) APPLY 3 LAYERS OF 1/2 INCH GLASS TAPE OVER THE CONCENTRIC NEUTRAL 1 INCH AWAY FROM THE CONCENTRIC NEUTRAL JACKET AND APPLY 3 LAYERS OF VINYL PLASTIC TAPE OVER THE GLASS TAPE FORMING A PERMANENT BINDING.

(N) BEND THE CONCENTRIC NEUTRAL OVER THE GLASS & VINYL TAPE AND TWIST TOGETHER.





**FIGURE 8** (L)(M)(N)

(O) APPLY A 2 INCH WIDE STRIP OF SEALING COMPOUND, 1 INCH OVER THE CONCENTRIC NEUTRAL JACKET AND 1 INCH OVER THE SEMICONDUCTING MATERIAL AND CONCENTRIC NEUTRALS. TIGHTLY PUSH THE SEALING COMPOUND AROUND THE CONCENTRIC NEUTRAL WIRES.





**FIGURE 9** (O)

P. APPLY HEAT SHRINK TUBE OR VINYL PLASTIC TAPE AS DESCRIBED IN P1 AND P2.

(1) PRESS THE AQUA SEAL IN TO THE CONCENTRIC NEUTRAL WIRES TO THE EDGE OF THE CLOTH TAPE. PLACE THE EDGE OF THE HEAT SHRINK TUBE ON THE CLOTH TAPE, APPLY EVEN HEAT TO THE EDGE OF THE TUBE SO IT SHRINKS DOWN ON THE CLOTH TAPE. **AVOID** EXCESS HEAT ON THE SEMI CONDUCTING MATERIAL, AVOID HEAT SHRINK MATERIAL CONTACTING THE SEMI CONDUCTING MATERIAL. CONTINUE TO APPLY EVEN HEAT ON SHRINK TUBE MOVING TOWARD THE JACKET AND MAKE SURE THE TUBE SHRINKS ONTO THE SEALING COMPOUND AND THE OUTER CABLE JACKETING.





**FIGURE 10** (P1)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | REVISION | - | - | - | TR/MC | 8/26/2008 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(2) VINYL PLASTIC TAPE MAY BE USED INSTEAD OF A HEAT SHRINK TUBE DESCRIBED IN STEP (P1). APPLY 3 LAYERS OF VINYL PLASTIC TAPE COVERING THE SEALING COMPOUND AND EXTENDING AT LEAST 2 INCHES OVER THE CONCENTRIC NEUTRAL JACKET.





**FIGURE 11** (P2)

**BILL OF MATERIALS:** NONE

## NOTES:

(I) DUE TO THE FACT THAT OVERHEAD FAULT INDICATORS ARE REQUIRED ON CABLE POLES, THE 5 INCH SPACE BELOW THE TERMINAL (POTHEAD) IS NOT REQUIRED. FOLLOW THE MANUFACTURERS INSTRUCTIONS WHICH SEALS THE CABLE JACKET FROM MOISTURE.





**FIGURE 12**
200 AMP & 600 AMP CABLE





**FIGURE 13**
200 AMP & 600 AMP CABLE





**FIGURE 14**
CABLE POLE APPLICATION
200 AMP & 600 AMP CABLE

## REFERENCE:

a. SEE UG4176 FOR CONCENTRIC NEUTRAL WIRE SIZE CHART.

(b) SEE UG4525 FOR GROUNDING PREMOLDED CONNECTORS.

c. SEE UG4174 FOR COPPER COMPRESSION CONNECTORS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1993 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | REVISION | - | - | - | TR/MC | 8/26/2008 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE APPROVED METHOD FOR SEALING CABLE ENDS TO PREVENT THE ENTRY OF WATER INTO 12KV CABLES.




**FIGURE 1**
CABLE END SEAL

**TABLE 1**

| CABLE END SEAL | |
|---|---|
| **STOCK NUMBER** | **CABLE SIZE** |
| S627240 X | #2, #2/0 |
| S627242 X | 350, 750 |
| S627246 X | 1000 KCMIL |

## INSTALLATION:

A. SEAL ENDS OF ALL PRIMARY CABLES IMMEDIATELY AFTER PULLING UNLESS YOU ARE GOING TO CONNECT CABLES RIGHT AWAY. THIS APPLIES TO CABLE ON REELS AND TO CABLE IN SUBSTRUCTURES. AS AN ADDITIONAL PRECAUTION, AFTER CABLES IN SUBSTRUCTURES HAVE BEEN SEALED, TIE THE ENDS UP AS HIGH AS POSSIBLE ABOVE THE FLOOR.

B. FOR CABLE POLE RUNS OF 1000 KCMIL CABLE AND FOR OTHER RUNS OF 1000 KCMIL CABLE, WHEN A FEEDER TUBE IS USED IT IS NECESSARY TO REMOVE THE CABLE JACKET BEYOND THE END OF THE PULLING GRIP (SEE FIGURE 2). IF THE ENSLEY CABLE EYE IS USED REFER TO STANDARD PRACTICE #215.

C. WHEN USING END CAPS OVER CONCENTRIC NEUTRALS, IT IS NECESSARY TO APPLY A PAD OF SEALING COMPOUND OVER THE END OF THE CABLE AND AT THE JACKET CUTBACK TO ENSURE AN ADEQUATE WATER SEAL (SEE FIGURES 3 AND 4).

D. PREPARE CABLE

1. SQUARE CUT CABLE.
2. THOROUGHLY CLEAN CABLE END FOR APPROXIMATELY SIX INCHES.

E. APPLY COLD SHRINK END CAP

1. SLIP END CAP OVER CABLE END AS FAR AS POSSIBLE.
2. PULL CORE COMPLETELY OUT OF END CAP. THE CAP WILL SHRINK AROUND THE CABLE.

F. REMOVAL

1. LIFT THE EDGE OF THE CAP AND SLICE THE MATERIAL ALONG THE LENGTH OF THE CAP.
2. PULL THE CAP OFF THE CABLE.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | -- | -- | -- | TR/JJ | 7/28/2005 | E | | | | | | |
| A | REVISION | -- | -- | -- | JLB/RDJ | 1/1/1993 | D | | | | | | |

## INSTALLATION (CONT'D):

**INSTALLATION INSTRUCTIONS FOR CABLE POLE RUNS AND WHEN FEEDER TUBE IS USED:**

(G) PREPARE CABLES WITH STAGGERED JACKET CUTBACK.





**FIGURE 2** (G)
JACKET CUTBACK DIMENSIONS

(H) PLACE PAD OF SEALING COMPOUND OVER AND BACK ONE INCH ONTO END OF CABLE AND PLACE A ONE INCH BAND OF SEALING COMPOUND JUST AHEAD OF JACKET CUTOFF.





**FIGURE 3** (H)

(J) INSTALL CABLE END SEAL OVER CABLE END AND ONE-HALF OF LARGE HEAT SHRINK TUBE (S778020) TO SEAL JACKET.





**FIGURE 4** (J)

**BILL OF MATERIALS:** NONE

**NOTES:**

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | -- | -- | -- | TR/JJ | 7/28/2005 | E | | | | | | |
| A | REVISION | -- | -- | -- | JLB/RDJ | 1/1/1993 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CABLE END SEALS



UG4109.2

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE PRIMARY NEUTRAL INSTALLATION FOR SUBSURFACE TRANSFORMERS FITTED WITH LOADBREAK ELBOWS.





**FIGURE 1**

## INSTALLATION:

(A) CLEAN SURFACE WITH SOLVENT
(B) TWO HALF LAP LAYERS
(C) THREE HALF LAP LAYERS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | VINYL PLASTIC TAPE, 3/4" | AS REQ'D | -- | S720580 | -- |
| 2 | #2 CU THW WIRE | AS REQ'D | -- | S808162 (X) | -- |
| 3 | ELBOW, GROUNDING, 1/0 | 1 | 4191 | S603600 | -- |
| 4 | H.V. INSULATING TAPE, 3/4" | AS REQ'D | -- | S720480 | -- |
| 5 | COMPRESSION CONNECTOR | 1 | 4172 | S257760 | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE FMO UG3799.205 AND FMO UG3799.206 FOR SUBSURFACE TRANSFORMERS.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | EDM | EJA | GLW | KRG | 05/31/2022 | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | GLW | CZH | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1993 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

LOADBREAK ELBOW - PRIMARY NEUTRAL TERMINATION

UG4110.1

**SCOPE:** THIS STANDARD SHOWS CABLE TERMINALS USED FOR OUTDOOR PRIMARY CABLE TERMINATIONS.





**FIGURE 1**
3M, JOSLYN, RAYCHEM





**FIGURE 2**
3M, JOSLYN, RAYCHEM



**DETAIL 1**

## TABLE 1

| CABLE POLYETHYLENE | TERMINAL | | FIGURE NUMBER | AERIAL LUG CATALOG NUMBER/ STOCK NUMBER | COMPRESSION CONNECTOR | | COMPRESSION DIE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| | CATALOG NUMBER | STOCK NUMBER | | | CATALOG NUMBER | STOCK NUMBER | | |
| 2 SOL AL | 5641<br>JPT15J1<br>TFT151E | S732918 | 1 | - (C) | 8898-6 | S729930 | BG | CP-#2N |
| 2/0 AL | 5641<br>JPT15J1<br>TFT151E | S732918 | 1 | - (C) | X5U20-6 | S729934 | 840 | CP2/0N |
| 350 KCMIL AL | 5642<br>TFT-152E | S727140 | 1 | S262336 | PTB-350-2.5 | S729938 | 316 | CP350N |
| | 5642<br>TFT-152E | S727140 | 2 | - | AHL350 | S728864 | 317 | T350L |
| 750 KCMIL COMP AL | 5642<br>TFT-152E | S727140 | 1 | S262432 | PTL-750-2.5 | S729940 | 301 | CP750C |
| | 5642<br>TFT-152E | S727140 | 2 | - | CAL750NLP | S729280 | 301 | T750L |
| 1000 KCMIL AL | 5644<br>JPT15J4 | S727138 | 1 | S262370 (X) | PTL-1000-2.5 | S729944 | 301 | C1000N |
| | 5644<br>TFT-154E | S727138 | 2 | - | CAL1000NLP | S729282 | 301 | T1000L |
| 1000 KCMIL CU | 5644 | S727138 | 2 | - | - | S265850 | P44ART | T1KLCU |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/JJ | 07/14/2005 | F | | | | | | |
| B | REVISION | - | - | - | TR/JJ | 06/28/2005 | E | EDITORIAL CHANGES | EDM | EIA | GLW | CZH | 07/29/2021 |
| A | REVISION | - | - | - | JCE/VCR | 03/01/2002 | D | FIGURE UPDATE | EDM | EJA | GLW | CZH | 10/09/2020 |

## INSTALLATION:

(A) SUPPLIED WITH CABLE TERMINAL KIT.

(B) FOR 350, 750 AND 1000 KCMIL CABLE POLE TERMINALS, INSTALL TOP PORTION OF COMPRESSION CONNECTOR IN BOTTOM POSITION OF THE 2-BOLT CONNECTOR (AERIAL LUG).

(C) AERIAL LUG NOT REQUIRED.

## BILL OF MATERIALS: NONE

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE OH287UG3140 FOR CONTAMINATION DISTRICTS.

b. SEE OH1407UG4207 FOR CABLE TERMINAL MOUNTING INFORMATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/JJ | 07/14/2005 | F | | | | | | |
| B | REVISION | - | - | - | TR/JJ | 06/28/2005 | E | EDITORIAL CHANGES | EDM | EIA | GLW | CZH | 07/29/2021 |
| A | REVISION | - | - | - | JCE/VCR | 03/01/2002 | D | FIGURE UPDATE | EDM | EJA | GLW | CZH | 10/09/2020 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

OUTDOOR CABLE TERMINALS FOR POLYETHYLENE CABLES

UG4111.2

**SCOPE:** THIS STANDARD SHOWS LIVEFRONT TERMINATION ON HIGH VOLTAGE CABLE FOR EXISTING FACILITIES.






**FIGURE 1**




**DETAIL 1**

## TABLE 1

| AL 175 MIL XLPE CABLES | | | | |
|---|---|---|---|---|
| CONDUCTOR SIZE/MATERIAL | COMPRESSION TERMINAL | | STRESS RELIEF KIT | |
| | STOCK NUMBER | DESIGN UNITS | CATALOG NUMBER | STOCK NUMBER |
| #2 SOL AL | S728688 | SC-#02 | 5671 | S732978 |
| #2/0 AL | S728696 | SC-2/0 | | |
| 350 KCMIL AL | S728864 | SC-350 | 5672 | S732972 |
| 750 KCMIL AL | S72980 | SC-750 | | |
| 1000 KCMIL AL | S729282 | SC1000 | | |

## TABLE 2

| CU 220 MIL HMWPE CABLES | | | | |
|---|---|---|---|---|
| CONDUCTOR SIZE/MATERIAL | COMPRESSION TERMINAL | | STRESS RELIEF KIT | |
| | STOCK NUMBER | DESIGN UNITS | CATALOG NUMBER | STOCK NUMBER |
| #4 CU | S259040 | SC-#4C | 5671 | S732978 |
| #2 CU | S259008 | SC-#2C | | |
| #4/0 CU | S729792 | SC4/0C | 5672 | S732972 |
| 50 KCMIL CU | S729856 | SC500C | | |
| 1000 KCMIL CU | S265850 | SC-1KC | | |

## INSTALLATION:

A. CONSTRUCT STRESS RELIEF KIT INSTALLATION AS SHOWN IN SKETCH. DESIGN UNIT INCLUDES COMPRESSION TERMINAL AND STRESS RELIEF KIT.

(B) BEVEL TOP EDGE OF CABLE INSULATION BACK 1/4". FOR ALUMINUM CABLES LEAVE 1/4" BARE CONDUCTOR BELOW COMPRESSION TERMINAL AND SEAL THE CABLE INSULATION TO THE TERMINAL WITH A MINIMUM OF THREE HALF-LAP LAYERS OF HIGH VOLTAGE INSULATING TAPE (STOCK NUMBER S720480). FOR COPPER CABLES LEAVE 1/2" GAP.

(C) USE MODERATE OR SLIGHT TENSION TO APPLY SILICONE TAPE (STOCK NUMBER S720384). HALF-LAP TAPE STARTING ABOUT 1/2" BELOW TOP OF STRESS RELIEF KIT AND ENDING 1/4 WAY UP THE LUG. DO NOT END TAPE INSIDE THE CRIMP OF THE COMPRESSION TERMINAL, BECAUSE IT MAY COLLECT MOISTURE.

(D) GROUND STRESS RELIEF KIT. USE A PIECE OF NO. 14 SOLID COPPER WIRE (STOCK NO. S812934) OR A SURPLUS PIECE OF CONCENTRIC NEUTRAL TAIL THAT IS LONG ENOUGH TO REACH THE NEAREST COMPRESSION CONNECTOR. DO NOT USE ANY CONCENTRIC NEUTRAL ATTACHED TO THE CABLE UNLESS THE CABLE IS 2/0 OR 2 SOLID TRIPLEX.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JJ/TR | 5/26/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

LIVE FRONT CABLE TERMINATIONS, POLYETHYLENE CABLES (NEW CABLES)



UG4121.1

TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(E) FOR INSTALLATIONS IN EXISTING LIVE FRONT EQUIPMENT, INSTALL THE CONCENTRIC NEUTRAL AT THE SAME HEIGHT AS EXISTING CABLES AND DELETE THE 5 INCH MEASUREMENT.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. SEE UG4111 FOR OUTDOOR TERMINATIONS.

b. SEE UG4122 FOR INDOOR CABLE TERMINATIONS FOR EXISTING CABLES.

(c) SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMODELED CONNECTORS.

(d) SEE UG4108 FOR INSTRUCTIONS ON SEALING JACKETED CABLE AND CONCENTRIC NEUTRAL MEASUREMENTS FROM CONNECTORS.

e. SEE UG4199.203/UG4199.204 FOR LIVE FRONT CABLE TERMINATIONS ON "FIELD MAINTENANCE ONLY" CABLES.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JJ/TR | 5/26/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

LIVE FRONT CABLE TERMINATIONS,
POLYETHYLENE CABLES (NEW CABLES)

UG4121.2

**SCOPE:** THIS STANDARD SHOWS LIVEFRONT TERMINATION FOR SUBSTATION METAL-CLAD SWITCHGEAR.





**FIGURE 1**

## INSTALLATION:

A CLEAN SURFACE WITH SOLVENT.
B ONE LOOSELY APPLIED HALF-LAPPED LAYER.
C APPLY TO SHARP CORNERS.
D TWO HALF-LAPPED LAYERS.
E TRANSITION PLATE IS REQUIRED FOR ALL ALUMINUM INSTALLATIONS.
F FOUR HALF-LAPPED LAYERS.
G FOURTEEN HALF-LAPPED LAYERS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1994 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

15 KV CABLE PREPARATION FOR SUBSTATION METAL-CLAD SWITCHGEAR

UG4127.1



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(H) AS REQUIRED TO FILL VOID.
(J) TERMINATE 3/4" VARNISH CAMBRIC TAPE 1" UP ONTO FACTORY INSULATION.
(K) TERMINATE HIGH VOLTAGE INSULATING TAPE 2" UP ONTO FACTORY INSULATION.
(L) TERMINATE 3/4" VARNISH CAMBRIC TAPE 1" BELOW BEVEL ON CABLE.
(M) TERMINATE HIGH VOLTAGE INSULATING TAPE 2" BELOW BEVEL ON CABLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | COMPRESSION TERMINAL | - | 4121 | - | - |
| 2 | CONDUCTOR | - | - | - | - |
| 3 | FACTORY XLPE INSULATION | - | - | - | - |
| 4 | DUCT SIL | - | - | S247490 (X) | - |
| 5 | VARNISH CAMBRIC TAPE, 1 1/2" | - | - | S721056 | - |
| 6 | VARNISH CAMBRIC TAPE, 3/4" | - | - | S721024 | - |
| 7 | HIGH VOLTAGE INSULATING TAPE | - | - | S720480 | - |
| 8 | VINYL PLASTIC TAPE | - | - | S720580 | - |
| 9 | SILICONE TAPE, 1" | - | - | S720384 | - |
| 10 | TRANSITION PLATE, ALUMINUM TO COPPER | - | 4168 | S543208 | - |

## NOTES:

(I) ALL NUTS AND BOLTS INSTALLED IN SUBSTATIONS SHALL BE GALVANIZED.
(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1994 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

15 KV CABLE PREPARATION FOR SUBSTATION METAL-CLAD SWITCHGEAR

UG4127.2

**SCOPE:** THIS STANDARD COVERS CONDUCTORS TO SPLICING OF 750 COMPACT EPR TO 500 PILC 15KV CONDUCTORS.




**FIGURE 1**
750C/500 SLEEVE
DIE 936 YRB 390304

**TABLE 1**

| FIGURE 1 | | |
|---|---|---|
| **MANUFACTURER TYCO NUMBER** | **STOCK NUMBER** | **DESIGN UNITS** |
| HVS-T-15835S | - | 750CSL |
| SLEEVE | SXXXXXX | 750 |

## INSTALLATION:

A. CUT CABLES TO CORRECT LENGTH, INSTALL CABLE SUPPORTS, PREPARE CABLES FOR TERMINATION AND FOLLOW MANUFACTURER'S INSTRUCTIONS FOR APPLICATION.

**BILL OF MATERIALS:** NONE

## NOTES:

I. IF THE FACILITY IS TOO SMALL FOR TERMINATION PULL THE PILC CABLE OUT TO THE NEXT LARGEST STRUCTURE.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | JES | CZH | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/JW | 12/9/2005 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

750 COMPACT EPR TO 500 PILC SPLICE

UG4147.1

**SCOPE:** THIS STANDARD COVERS THE RE-TERMINATION OF 3 CONDUCTOR PILC TO 600 AMP ELBOW TEE CONNECTIONS. THIS TERMINATION IS DESIGNED FOR THE LIMITED SPACE TRANSITION FROM 500 KCMIL PILC CABLE TO MOLDED CONNECTIONS ON EPR-PEJ OR XLPECN-PEJ CABLES.

**ATTENTION:**

* SDG&E HAS NOT PURCHASED OR INSTALLED PAPER INSULATED LEAD COVERED CONDUCTORS IN THE PAST 10 YEARS. LEAD COVERED CONDUCTORS HAVE HAD A SUPERIOR LIFE SPAN BUT ENVIRONMENTAL ISSUES WITH LEAD AND SAFETY ISSUES HANDLING HOT COMPOUND FILLING AND HOT METAL HAVE CHANGED THE UTILITY INDUSTRY'S FOCUS TO POLYMER CABLES. THE LEAD COVERING CREATES OPERATIONAL AND GROUNDING PROBLEMS, AS WELL AS INCREASED TIME REQUIREMENTS FOR INSTALLATION AND TERMINATION. AS LOADS INCREASE AND RECONSTRUCTION OF THE AREAS THAT HAVE LEAD COVERED CONDUCTORS DECREASES, ALL RE-TERMINATION OF LEAD CABLES SHALL BE WITH COLD OR HEAT SHRINK PRODUCTS DETERMINED BY DISTRIBUTION ENGINEERING AND STANDARDS.




**FIGURE 1**

**TABLE 1**

| FIGURE 1 | | |
|---|---|---|
| **MANUFACTURER TYCO NUMBER** | **STOCK NUMBER** | **DESIGN UNITS** |
| HVE-3-1593-SDG&E | S445870 | 500TRC |
| 500 MCM LUG | S258700 | SPD500 |

**INSTALLATION:**

A. CUT CABLES TO CORRECT LENGTH, INSTALL CABLE SUPPORTS, PREPARE CABLES FOR TERMINATION AND FOLLOW MANUFACTURER'S INSTRUCTIONS FOR APPLICATION.

**BILL OF MATERIALS:** NONE

**NOTES:**

I. IF THE FACILITY IS TOO SMALL FOR TERMINATION PULL THE PILC CABLE OUT TO THE NEXT LARGEST STRUCTURE.

**REFERENCE:**

a. CONNECTION APPLICATION STANDARDS: UG4181, UG4183, UG4184 COVER CONNECTIONS THAT MAY BE USED WITH THIS CABLE TERMINATION KIT.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | MOVED FROM UG4147 | EDM | JIK | JES | CZH | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/JW | 04/09/2006 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

3 CONDUCTOR PILC ADAPTER FOR USE WITH 600 AMP ELBOW TEE'S

UG4148.1

**SCOPE:** THIS STANDARD SHOWS SLIP-FIT CONNECTORS THAT ARE REQUIRED ON ALL NEW SINGLE-PHASE DEADFRONT TRANSFORMER LOW VOLTAGE SECONDARY INSTALLATIONS.




**DETAIL A**

**FIGURE 1**
SLIP-FIT CONNECTORS

**TABLE 1**

| SLIP-FIT CONNECTORS (8-PORT) | | | |
|---|---|---|---|
| **SINGLE-PHASE TRANSFORMER SIZE** | **CABLE SIZE** | **STOCK NUMBER** | **DESIGN UNITS** |
| 25 THRU 75 KVA (5/8" STUD) | #8 THRU 500 KCMIL | S269990 | 500-8SL |
| 100 THRU 167 KVA (1" STUD) | | | |

## INSTALLATION:

A. CONNECTORS MAY BE USED FOR ALUMINUM OR COPPER CONDUCTORS BUT NEVER COMBINE COPPER AND ALUMINUM IN THE SAME PORT.

B. WHEN NECESSARY MULTIPLE CONDUCTORS PER PORT ARE ALLOWED.

C. CONNECTOR IS A SLIP FIT CONNECTION EVEN THOUGH THE TERMINAL IS THREADED.

(D) ON "PS" CONNECTORS, SLIDE CONNECTOR ONTO THE TRANSFORMER STUD, ANGLE CONNECTOR TO ALLOW A STRAIGHT, SMOOTH CABLE ENTRY AND TIGHTEN SET SCREW TO LOCK THE CONNECTOR IN PLACE. DO NOT OVER-TIGHTEN JAM NUT AGAINST CONNECTOR.

(E) ON THE NEUTRAL CONNECTOR, SLIDE THE GROUNDING STRAP ONTO THE TRANSFORMER STUD, THEN SLIDE THE CONNECTOR ALL THE WAY ONTO THE STUD, ANGLE CONNECTOR TO ALLOW A STRAIGHT, SMOOTH CABLE ENTRY, AND TIGHTEN THE SET SCREW TO LOCK CONNECTOR IN PLACE. WITHOUT OVER-TIGHTENING JAM NUT, SNUG GROUND STRAP ONTO CONNECTOR.

F. TO PREPARE CABLE, REMOVE INSULATION BY PENCILING, WIRE BRUSH CONDUCTOR AND APPLY INHIBITOR.

G. INSERT THE CONDUCTOR IN THE PORT AND TIGHTEN SET SCREW. CAUTION SHOULD BE EXERCISED TO ENSURE THAT NO STRANDS ARE EITHER SEVERED OR FORCED BACK OUT OF THE PORT WHEN TIGHTENING FIRMLY.

H. AFTER COMPLETING WORK ON THE SECONDARY CONNECTORS, MAKE SURE ALL CONNECTIONS ARE TIGHTENED FIRMLY.

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) USE S270290 ONLY WHEN 500 KCMIL CABLES ARE BEING INSTALLED.

II. S/N S270290, S270296, S270296 WILL BE DEPLETED AND REPLACED WITH S269990.

**REFERENCE:** NONE

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 12/13/2011 | F | TABLE UPDATE | ARC | RSL | JES | KRG | 03/09/2023 |
| B | REVISION | - | - | - | MC/TR | 04/29/2008 | E | FIGURE UPDATE | EDM | EJA | GLW | CZH | 07/28/2021 |
| A | REVISION | - | - | - | JJ/TR | 10/26/2006 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

SLIP-FIT CONNECTORS

UG4167.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF LAY-IN SECONDARY TRANSFORMER CABLE CONNECTIONS FOR THREE PHASE TRANSFORMERS. THE LAY-IN CONNECTOR REPLACES THE STANDARD SECONDARY LUG APPLICATION FOR TRANSFORMERS. THE LAY-IN CONNECTOR CONDUCTOR RANGE IS 1/0 TO 1000 KCMIL FOR ALUMINUM AND COPPER CABLES.





**FIGURE 1**
LAY-IN CONNECTOR (F)





**FIGURE 2**
SINGLE CONNECTOR (D)

**TABLE 1**

| HARDWARE | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| B1 | BOLT, 1/2" X , S.S. |
| N1 | NUT, 1/2" BRONZE |
| W1 | WASHER, 1/2", FLAT, S.S. |
| W2 | WASHER, 1/2" BELLVILLE, S.S. |





**FIGURE 3**
DOUBLE CONNECTOR (D)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 12/13/2011 | F | | | | | | |
| B | REVISION | - | - | - | MC/TR | 04/29/2008 | E | | | | | | |
| A | REVISION | - | - | - | JJ/TR | 10/26/2006 | D | MOVED FROM UG4167 | EDM | JIK | - | - | 06/02/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



LAY-IN SECONDARY CONNECTORS

UG4168.1

## TABLE 2 (H)

| CONDUCTOR SIZE AND TORQUE VALUE | |
|---|---|
| CABLE SIZE | TORQUE VALUE IN INCH-POUNDS |
| 1/0 | 200 |
| 3/0 | 250 |
| 350 | 350 |
| 500 | 450 |
| 750 | 500 |
| 1000 | 500 |

## TABLE 3

| CONNECTORS | | | |
|---|---|---|---|
| CONNECTION POINTS | BOLT HOLES | STOCK NUMBER | DESIGN UNITS |
| 1 CONNECTION PORT | 2-HOLES | S256370 | 1CNPOR |
| 2 CONNECTION PORTS | 4-HOLES | S256372 | 2CNPOR |
| 3 CONNECTION PORTS | 6-HOLES | S256374 | 3CNPOR |
| 4 CONNECTION PORTS | 8-HOLES | S256376 | 4CNPOR |
| 6 CONNECTION PORTS | 12-HOLES | S256378 | 6CNPOR |
| 8 CONNECTION PORTS | 16-HOLES | S256380 | 8CNPOR |

## TABLE 4

| PARTS LIST | | |
|---|---|---|
| ITEM | DESCRIPTION | QUANTITY |
| 1 | LAY-IN CONNECTOR | AS REQ'D |
| 2 | PENATROX OXIDE INHIBITOR | AS REQ'D |
| 3 | STAINLESS STEEL BOLT SET UP WITH BELLEVILLE WASHER | AS REQ'D |
| 4 | 3M SCOTCH BRIGHT PAD | AS REQ'D |

## INSTALLATION:

A. SELECT THE CORRECT LAY-IN CONNECTOR FOR THE NUMBER OF CABLE RUNS. THEY MAY BE ARRANGED IN COMBINATIONS TO CONNECT MULTIPLE RUNS.

B. USE A 3M SCOTCH BRIGHT PAD TO CLEAN ALL CONNECTION SURFACES, INCLUDING THE CABLE LAY-IN CONNECTION AREA.

C. APPLY A THIN COAT OF OXIDE INHIBITOR ON ALL CONNECTION SURFACES. THIS WILL ENSURE GOOD CONTACT, LOW RESISTANCE, IMPROVE CONDUCTIVITY AND SEAL OUT CONTAMINATES.

(D) SELECT THE CORRECT STAINLESS STEEL BOLT LENGTH. THE BELLEVILLE WASHER SHALL BE LOCATED BETWEEN SILICON BRONZE NUT AND THE HEAVY DUTY FLAT WASHER. THIS ALSO REQUIRES A FLAT WASHER UNDER THE BOLT HEAD. WHEN TWO LAY-IN CONNECTORS ARE USED, A BELLEVILLE WASHER SHALL BE ADDED BETWEEN THE BOLT HEAD AND THE WASHER.

(E) INSTALL ALL NECESSARY BOLTS AND TIGHTEN DOWN IN A CROSS PATTERN. ALL 1/2" BOLTS SHOULD BE TORQUED TO 44 FT-LBS IN THE SAME PATTERN. MAKE SURE THE BELLEVILLE WASHERS ARE FLAT.

(F) INSTALL CABLE AND CUT TO CORRECT LENGTH TO FIT INTO MILLED OUT AREA ON BODY OF LAY-IN PLATE.

(G) STRIP 3" OF INSULATION FROM THE END OF CONDUCTOR AND INSTALL IN LAY UP POSITION, INSTALL COVER PLATE WITH HEX SCREWS.

(H) THE 5/16" HEX SCREWS SHALL BE TIGHTENED DOWN EVENLY, TIGHTEN THE BOTTOM SET SCREW FIRST.

**BILL OF MATERIALS:** NONE

## NOTES:

I. LAY-IN CONNECTORS MAY BE APPLIED ON BOTH SIDES OF THE TRANSFORMER FLAG FOR MULTIPLE CONDUCTOR INSTALLATIONS. THE TORQUE SCREW REQUIRES A 5/16" HEX DRIVE SOCKET TO TORQUE CABLE CONDUCTOR HEX SCREWS.

II. LAY-IN CONNECTORS MAY BE ARRANGED BY THE NUMBER OF LAY-IN POSITIONS TO FILL THE NUMBER OF CABLES REQUIRED ON EACH TRANSFORMER FLAG. THE LAY-IN CONNECTORS MAY ONLY EXTEND ONE POSITION MORE THAN THE TRANSFORMER BUSHING; IT MUST HAVE SAFE CLEARANCE FROM THE CLOSED AIR CABINET DOOR WHEN THIS IS DONE.

III. DUE TO CLEARANCE ISSUES IN SOME ERMCO THREE-PHASE TRANSFORMERS, LAY-IN CONNECTORS MAY NOT BE USED.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 12/13/2011 | F | | | | | | |
| B | REVISION | - | - | - | MC/TR | 04/29/2008 | E | | | | | | |
| A | REVISION | - | - | - | JJ/TR | 10/26/2006 | D | MOVED FROM UG4167 | EDM | JIK | - | - | 06/02/2020 |

**SCOPE:** THIS STANDARD SHOWS THE EXTENSION PLATE USED TO CONNECT MULTIPLE SECONDARY CABLES TO TRANSFORMERS.





**FIGURE 1**
ADAPTER PLATE
FRONT VIEW





**FIGURE 1**
ADAPTER PLATE
SIDE VIEW

**INSTALLATION:** NONE

**BILL OF MATERIALS:** SEE UG4170

**TABLE 1**

| STOCK NUMBER |
|---|
| S542372 |

**NOTES:**

I. ADAPTER PLATE TO BE TINNED COPPER.

**REFERENCE:** NONE

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | RSL | JES | FRC | 02/14/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1989 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


SHEET 1 OF 2

SECONDARY EXTENSION PLATE FOR PADMOUNT TRANSFORMER

UG4169.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INLINE SPADE USED FOR CONNECTING MULTIPLE SECONDARY CABLES TO TRANSFORMERS.








**FIGURE 1**
INLINE SPADE
ISOMETRIC VIEW








**FIGURE 1**
INLINE SPADE

**INSTALLATION:** NONE

**BILL OF MATERIALS:** SEE UG4170

**NOTES:**

I. INLINE SPADE IS TIN PLATED.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | RSL | JES | FRC | 02/14/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1989 | D | | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INLINE SPADE

UG4169.2

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF A LUG CONNECTOR TO A SECONDARY 600V TRANSFORMER OR BUS.





**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | TRANSFORMER TERMINAL OR BUS | - | - | - | - |
| | SPADE, 4H, INLINE | AS REQ'D | 4169 | S270280 | SP4H |
| 2 | WASHER, 1/2", BELLEVILLE, SS | AS REQ'D | - | S798970 | - |
| 3 | WASHER, 1/2", FLAT, SS | AS REQ'D | - | S799680 | - |
| 4 | NUT, 1/2", HEX HEAD MACHINE THREAD, BRONZE | AS REQ'D | - | S506112 | - |
| 5 | BOLT, 1/2", HEX HEAD MACHINE THREAD, SS | AS REQ'D | - | S247200 | - |
| 6 | INHIBITOR (a) | AS REQ'D | 4106 | - | - |
| 7 | LUG, ALUMINUM | AS REQ'D | 4171 | - | - |
| 8 | TAPE, PVC | AS REQ'D | - | - | - |
| 9 | CABLE, ALUMINUM | AS REQ'D | 4002 | - | - |

**NOTES:** NONE

**REFERENCE:**

(a) SEE UG4106 FOR INSTALLATION INSTRUCTIONS.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | EDM | RSL | JES | FRC | 02/14/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | RSW/VCR | 10/23/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

600V SECONDARY BOLTED CONNECTION AT TRANSFORMER OR BUS

UG4170.1

**SCOPE:** THIS STANDARD SHOWS CONNECTORS TO TERMINATE PRIMARY AND/OR SECONDARY CONDUCTORS ON TRANSFORMER TERMINATING PLATES OR FLAT BUS CONNECTIONS.

## TABLE 1

| COMPRESSION TERMINALS - 1 - HOLE FOR 3/8" BOLT - SECONDARY SERVICE | | | | | | |
|---|---|---|---|---|---|---|
| AL WIRE SIZE | BURNDY DIE SIZE | STOCK NUMBER | SECONDARY WORK | | SEVICE WORK | |
| | | | DESIGN UNITS | SAP CU | DESIGN UNITS | SAP CU |
| 4 | 840 | S729216 | 1LG-04 | 1LG-04 | 1LG-04 | 1LG-04 |
| 2 | | S728800 | 1LG-02 | 1LG-02 | 1LG-02 | 1LG-02 |
| 1/0 | | S728640 | 1LG1/0 | 1LG1/0 | 1LG1/0 | 1LG1/0 |
| 3/0 | | S728960 | 1LG3/0 | 1LG3/0 | 1LG3/0 | 1LG3/0SV |
| 350 | | S470464 | 1LG350 | 1LG350 | 1LG350 | 1LG350 |
| 500 | 316 | S729252 | 1LG500 | 1LG500 | 1LG500 | 1LG500 |




**FIGURE 1**
1 HOLE FOR 3/8" BOLTS

## TABLE 2

| COMPRESSION TERMINALS - 2 - HOLE FOR 1/2" BOLT - SECONDARY SERVICE | | | | | | |
|---|---|---|---|---|---|---|
| AL WIRE SIZE | BURNDY DIE SIZE | STOCK NUMBER | SECONDARY WORK | | SEVICE WORK | |
| | | | DESIGN UNITS | SAP CU | DESIGN UNITS | SAP CU |
| 4 | 840 | S729172 | - | - | - | - |
| 2 | | S728672 | 2LG-02 | 2LG-02 | 2LG-02 | 2LG-02 |
| 1/0 | | S728608 | 2LG1/0 | 2LG1/0 | 2LG1/0 | 2LG1/0 |
| 3/0 | | S728896 | 2LG3/0 | 2LG3/0 | 2LG3/0 | 2LG3/0 |
| 350 | 316 | S729024 | 2LG350 | 2LG350 | 2LG350 | 2LG350SV |
| 500 | 316 | S729256 | 2LG500 | 2LG500 | 2LG500 | 2LG500 |
| 750 | 301 | S729280 | 2LG750 | 2LG750 | 2LG750 | 2LG750SV |
| 1000 | | S256420 | 2LG1000 | 2LG1000 | 2LG1000 | 2LG1000 |




**FIGURE 2**
2 HOLE FOR 1/2" BOLTS

## TABLE 3

| COMPRESSION TERMINALS - 1 - HOLE FOR 3/8" BOLT - INDOOR PRIMARY TERMINATIONS | | |
|---|---|---|
| AL WIRE SIZE | BURNDY DIE SIZE | STOCK NUMBER |
| 2 SOL | BG | S728688 |
| 2/0 | 840 | S728696 |




**FIGURE 3**
1 HOLE FOR 3/8" BOLTS

## TABLE 4

| COMPRESSION TERMINALS - 2 - HOLE FOR 1/2" BOLT - INDOOR PRIMARY TERMINATIONS | | |
|---|---|---|
| AL WIRE SIZE | BURNDY DIE SIZE | STOCK NUMBER |
| 350 | 317 | S728864 |
| 750 MCM 750 COMP. | 301 | S729280 |
| 1000 AL | 302 | S729282 |
| 1000 CU | P44RT | S265850 |




**FIGURE 4**
2 HOLE FOR 1/2" BOLTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/13/2014 | F | | | | | | |
| B | REVISION | - | - | - | KN/DW | 1/10/2014 | E | | | | | | |
| A | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRANSFORMER TERMINAL & BUS COMPRESSION TERMINALS FOR ALUMINUM CONDUCTORS



UG4171.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS STACKING ADAPTERS WHICH ARE TO BE USED FOR FLAT BUS CONNECTIONS IN PULL CANS WHERE THERE ARE LESS POSITIONS ON THE LANDING TERMINAL THAN THERE ARE CABLES.




**FIGURE 1**




**FIGURE 2**

**TABLE 1**

| STACKING ADAPTER | | | | |
|---|---|---|---|---|
| AL WIRE SIZE | MANUFACTURER/CATALOG NUMBER | | STOCK NUMBER | DESIGN UNITS |
| | BURNDY | UTILCO/ILSCO | | |
| 3/0 | ASA-250U | ASL-250 | S102860 | 3/0STA |
| 350 | ASA-800U | ASL-750 | S102862 | 350STA |
| 500 | ASA-800U | ASL-750 | S102862 | 500STA |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. USE APPROPRIATE STACKING ADAPTER FROM TABLE ABOVE WITH STANDARD 3/0, 350, AND 500 KCMIL 2-HOLE COMPRESSION TERMINALS AS SHOWN ON UG4171.

b. STACKING LUGS SHOWN ON FMO UG4171 ARE NO LONGER AVAILABLE.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/13/2014 | F | | | | | | |
| B | REVISION | - | - | - | KN/DW | 1/10/2014 | E | | | | | | |
| A | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | D | MOVED FROM 4171 | EDM | JIK | JES | CZH | 06/02/2020 |

**SCOPE:** THIS STANDARD SHOWS PIN ADAPTERS WHICH ARE TO BE USED WHEN SERVICE LATERAL CONDUCTORS ARE LARGER THAN THE LISTED RATING OF THE TERMINALS SUPPLIED IN SAFETY SOCKET CANS OR RESIDENTIAL COMBINATION PULL SECTION AND METER CANS.




**FIGURE 1**
PIN ADAPTER

**TABLE 1**

| PIN ADAPTERS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| AL WIRE SIZE | BURNDY DIE SIZE | MANUFACTURER/CATALOG NUMBER | | | STOCK NUMBER | SECONDARY WORK | | SERVICE WORK | |
| | | BURNDY | UTILCO/ILSCO | PENN-UNION | | DESIGN UNITS | SAP CU | DESIGN UNITS | SAP CU |
| 3/0 | 298 | AYPO3/0 | ACO-3/0 | TPO-3/0 | S102864 | 3/0PIN | 3/0PIN | 3/0PIN | 3/0PIN2M |
| 350 | 299 | AYPO350 | ACO-350 | TPO-350 | S102866 | 350PIN | 350PIN | 350PIN | 350PIN2M |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. 3/0 PIN ADAPTER FOR USE IN STANDARD DUTY CANS (100 AMP) WITH LISTED TERMINAL SIZE RATED NOT TO EXCEED #1/0 AWG CU-AL WIRE. IN THIS CASE, 350 MCM CONDUCTORS CANNOT BE INSTALLED.

II. EXCEPTION: SOME MANUFACTURERS INSTALL 250 MCM CU-AL TERMINALS IN 100 AMP CANS. IN THIS CASE, #3/0 AWG CONDUCTORS MAY BE INSTALLED WITHOUT THE NEED FOR PIN ADAPTERS. THIS ALSO ALLOWS THE USE OF 350 MCM CONDUCTORS USING 350 ADAPTERS.

III. 350 PIN ADAPTER FOR USE IN HEAVY DUTY CANS (200 AMP) WITH LISTED TERMINAL SIZE RATED NOT TO EXCEED 250 MCM CU-AL WIRE.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/13/2014 | F | | | | | | |
| B | REVISION | - | - | - | KN/DW | 1/10/2014 | E | | | | | | |
| A | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | D | MOVED FROM 4171 | EDM | JIK | JES | CZH | 06/02/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



PIN ADAPTERS

UG4173.1

**SCOPE:** THIS STANDARD SHOWS COPPER COMPRESSION FOR COPPER TO COPPER JUMPER AND TAP.



**FIGURE 1**
DOUBLE TAB SQUEEZONS

**TABLE 1**

| LINE SIDE | TAP SIDE | | | | | | | | | | | TOOL & INDEX DIE | | STOCK NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | #8 | #6 | | #4 | | #2 | | #1 | #1/0 | #2/0 | #4/0 | NO. INDENTS | | |
| | SOL | SOL | STR | SOL | STR | SOL | STR | STR | STR | STR | STR | MD-6 | Y-35 | |
| | | | | | | | | | | | | 3 | 1 | |
| #6 SOL #4 SOL STR | X | X | X | X | - | - | - | - | - | - | - | WKT | N/A | S257952 |
| #4 SOL #2 SOL STR | - | - | - | X | X | X | - | - | - | - | - | WKK | N/A | S257920 |
| #2, 1 - 1/0 (ALL STR) | - | X | X | X | X | X | - | - | - | - | - | N/A | 0 | S257792 |
| | - | - | - | - | - | - | X | X | X | - | - | N/A | 0 | S257760 |
| #2/0 - 4/0 STR | - | - | - | X | X | X | - | - | - | - | - | N/A | U-D3 | S257888 |
| | - | - | - | - | - | - | X | X | X | - | - | N/A | U-D3 | S257856 |
| | - | - | - | - | - | - | - | - | - | X | X | N/A | U-D3 | S257824 |

## INSTALLATION:

A. UNDERGROUND CONCENTRIC NEUTRAL CONNECTIONS SHOULD BE SQUEEZED WITH COMPRESSION CONNECTORS UNLESS OTHERWISE SPECIFIED IN THE UNDERGROUND CONSTRUCTION STANDARDS BOOK.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | TABLE UPDATE | - | JIK | JES | CZH | 11/12/2019 | G | FIGURE UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | - | JC | JES | CZH | 06/13/2019 | F | MOVED FROM 4172 | EDM | JIK | - | - | 06/02/2020 |
| B | FIGURE UPDATE | - | JAC | JES | CZH | 04/20/2019 | E | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

COPPER COMPRESSION CONNECTORS

OH784.1
UG4174.1

**SCOPE:** THIS STANDARD SHOWS CONNECTORS USED FOR SPLICING SECONDARY OR SERVICE CONDUCTORS.





**FIGURE 1**
SECONDARY OR SERVICE CONDUCTORS

**TABLE 1**

**INSULINK COMPRESSION-SECONDARY OR SERVICE CONNECTORS (NON-TENSION)**

| END A | | END B | | | | | | | | | | END CAP COLOR CODE (C) | | CATALOG NUMBERS | | | | STOCK NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| ACSR OR 5005 | ALL ALUM OR COPPER | ALL ALUMINUM OR COPPER | | | | | | | | | ACSR OR 5005 | | | BLACK-BURN | BURNDY | HOMAC (SOMERSET) | PENN UNION | |
| | | 8 | | 6 | | 4 | | 2 | | 1/0 | | | | | | | | |
| | | SOL | STR | SOL | STR | SOL | STR | SOL | STR | STR | | END A | END B | | | | | |
| - | 8 STR & 6 SOL | X | - | - | - | - | - | - | - | - | - | GREEN | BROWN | ICS60 | ES6W8W | U1N81 | - | - |
| | | - | X | X | - | - | - | - | - | - | - | GREEN | GREEN | ICS61 | ES6W6W | U1N88 | - | S258496 |
| 6 | 6 STR & 4 SOL | X | - | - | - | - | - | - | - | - | - | BLUE | BROWN | ICS62 | ES4W8W | U1N61 | - | - |
| | | - | X | X | - | - | - | - | - | - | - | BLUE | GREEN | ICS63 | ES4W6W | U1N68 | PIK 46 | S258464 |
| | | - | - | - | X | X | - | - | - | - | 6 | BLUE | BLUE | ICS64 | ES4W4W | U1N66 | - | S258336 |
| 4 | 4 STR & 2 SOL | X | - | - | - | - | - | - | - | - | - | ORANGE | BROWN | ICS65 | ES2W8W | U1N41 | PIK 28 | S258384 |
| | | - | X | X | - | - | - | - | - | - | - | ORANGE | GREEN | ICS66 | ES2W6W | U1N48 | PIK 26 | S258432 |
| | | - | - | - | X | X | - | - | - | - | 6 | ORANGE | BLUE | ICS67 | ES2W4W | U1N46 | - | S258272 |
| | | - | - | - | - | - | X | X | - | - | 4 | ORANGE | ORANGE | ICS68 | ES2W2W | U1N44 | - | S258562 (X) |
| 2 | 2 STR | X | - | - | - | - | - | - | - | - | - | RED | BROWN | ICS69 | ES2R8W | U1N21 | - | S258368 |
| | | - | X | X | - | - | - | - | - | - | - | RED | GREEN | ICS70 | ES2R6W | U1N28 | - | S258400 |
| | | - | - | - | X | X | - | - | - | - | 6 | RED | BLUE | ICS71 | ES2R4W | U1N26 | - | S258240 |
| | | - | - | - | - | - | X | X | - | - | 4 | RED | ORANGE | ICS72 | ES2R2W | U1N24 | PIK 12 | S258528 |
| | | - | - | - | - | - | - | - | X | - | 2 | RED | RED | ICS73 | ES2R2R | U1N22 | - | S258624 |
| 1/0 | 1/0 STR | - | X | X | - | - | - | - | - | - | - | YELLOW | GREEN | ICS74 | ES25R6W | U1N108 | - | S258692 |
| | | - | - | - | X | X | - | - | - | - | 6 | YELLOW | BLUE | ICS75 | ES25R4W | U1N106 | - | S258304 |
| | | - | - | - | - | - | X | X | - | - | 4 | YELLOW | ORANGE | ICS76 | ES25R2W | U1N104 | - | S258592 |
| | | - | - | - | - | - | - | - | X | - | 2 | YELLOW | RED | ICS77 | ES25R2R | U1N102 | - | S258656 |
| | | - | - | - | - | - | - | - | - | X | 1/0 | YELLOW | YELLOW | ICS78 | ES25R25R | U1N1010 | - | S258688 |

**TABLE 2**

**COMPRESSION SLEEVE SECONDARY OR SERVICE CONNECTORS (NON TENSION)**

| AL WIRE SIZE | INSTALLING DIE SIZE | MANUFACTURER/CATALOG NUMBER | | COMPRESSION SPLICE STOCK NUMBER |
|---|---|---|---|---|
| | | HOMAC | PENN UNION | |
| 3/0 | 247 | ASC 3/0 | BCUA-3/0 | S668420 |
| 350 | U31ART | ASC 350 | BCUA-350 | S668418 (X) |
| 500 | 317 | ASC 500 | BCUA-500 | S668424 |
| 750 | 301 | ASC 750 | BCUA-750 | S668426 |
| 1000 | 302 | ASC 1000 | BCUA-1000 | S668428 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | TABLE UPDATE | - | JIK | JES | CZH | 11/12/2019 | G | FIGURE UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | - | JC | JES | CZH | 06/13/2019 | F | MOVED FROM 4172 | EDM | JIK | - | - | 06/02/2020 |
| B | FIGURE UPDATE | - | JAC | JES | CZH | 04/20/2019 | E | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 |

**TABLE 3**

| TRIPLEX NEUTRAL SLEEVES (TENSION) | | | | | |
|---|---|---|---|---|---|
| NEUTRAL SIZE | COLOR CODE | INDENTS EACH END | LENGTH - INCHES | CATALOG NUMBERS | STOCK NUMBER |
| | | MD-6 | KEARNEY | KEARNEY | |
| 6 | BLUE | 6 | 3 1/4 | 30008 | S652690 (X) |
| 4 | ORANGE | 6 | 3 1/4 | 30009 | S652640 |
| 2 | RED | 6 | 3 1/4 | 30010 | S652576 |
| 1/0 | CLEAR | 14 (B) | 7 1/2 | OHR-1/0-61AJ | S650274 (X) |

## INSTALLATION:

A. WIRE BRUSH THE CONDUCTORS BEFORE INSTALLING CONNECTOR.

(B) USE THE WK. 737 DIE IN THE MD-6 TOOL OR U-247 DIE IN THE Y35 TOOL OR KEARNEY INSULINK TOOL.

(C) MAKE **THREE INDENTS IN EACH END** OF THE COMPRESSION CONNECTOR STARTING FROM THE CENTER AND WORK OUTWARD USING THE FIXED NOSE DIE (5/8) OR W-BG DIE OF THE MD-6 TOOL.

D. USE NEUTRAL SLEEVES AS TENSION SPLICE ON 5005 AND ACSR SERVICE CABLE NEUTRAL.

E. USE HEAT SHRINK TUBES OVER CONNECTORS WHEN PLACED IN ANY BELOW GRADE INSTALLATION.

**BILL OF MATERIALS:** NONE

## NOTES:

I. CONNECTORS WILL ACCEPT EITHER ALUMINUM OR COPPER CONDUCTORS.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | TABLE UPDATE | - | JIK | JES | CZH | 11/12/2019 | G | FIGURE UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | - | JC | JES | CZH | 06/13/2019 | F | MOVED FROM 4172 | EDM | JIK | - | - | 06/02/2020 |
| B | FIGURE UPDATE | - | JAC | JES | CZH | 04/20/2019 | E | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 |

**SCOPE:** THIS STANDARD SHOWS A 2-HOLE ALUMINUM COMPRESSION TERMINAL, USED FOR TERMINATING ALUMINUM CONDUCTORS ON POLE TOP SWITCH TABS AND TRANSFORMER FLAG CONNECTORS.





**FIGURE 1**

## TABLE 1

| CAST ALUMINUM ALLOY TERMINALS | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| WIRE | | | | | | | TOOL AND DIE | | | CATALOG NUMBER | | | | | | STOCK NUMBER | DESIGN UNITS |
| 5005 | | ACSR | | ALUMINUM | | | BURNDY | | | | | | | | | | |
| SIZE | STRAND | SIZE | STRAND | SIZE | STRAND | | MD6 | Y-35 | Y-46 | HOMAC | BURNDY | FRANKEL | KEARNEY | PENN-UNION | ANDERSON | | |
| 2 | 7 | 2 | 6/1 | 2 | 7 | - | W-BG 5 CRIMPS | - | - | - | - | - | 36918 | - | - | S728672 | CT2A |
| 1/0 | | 1/0 | | 1/0 | | 19 | - | U840 5 CRIMPS | - | SAK 1/0-N | - | - | 104741-2 | - | - | S728608 | CT1/0A |
| 3/0 | | 3/0 | | 3/0 | | | - | U317 5 CRIMPS | - | - | YCAK27R-2G2 | GTN-3/0-2NE16 | - | - | VAUD 3/0-12BN-S | S728928 | CT3/0A |
| - | - | 336.4 KCM | 18/1 | 350 KCM | 19 | 37 | - | | - | - | YCAK31A-2G1 | GTM-35-2NE16 | 36364-2 | KBLUA-035-D2 | VAUD 350-12BN | S729024 | - |
| 394.5 KCM | 19 | | 26/7 | 400 KCM | | | - | | - | - | - | - | 36364-3 | - | - | S729120 | CT336A |
| - | - | 397.5 KCM | | 500 KCM | 37 | 61 | - | | - | - | YCAK361R-2G2 | - | - | - | - | - | - |
| | | 636 KCM | 24/7 | 750 KCM | | | - | - | 342 | SAL 750 NTN | - | - | - | - | - | S729266 (X) | CT636A |

## INSTALLATION:

A. THOROUGHLY CLEAN CONDUCTOR WITH WIRE BRUSH BEFORE INSERTING INTO BARREL.

B. MAKE OVERLAPPING CRIMPS FROM CONDUCTOR TO PAD.

C. USE 1/2" STAINLESS STEEL BOLTS FOR ALUMINUM TO COPPER CONNECTIONS.

D. WHEN USING TERMINALS, APPLY INHIBITOR (S247200) AT EACH ALUMINUM CONNECTION.

**BILL OF MATERIALS:** NONE

## NOTES:

I. ALUMINUM COMPRESSION TERMINALS ARE FACTORY FILLED WITH INHIBITOR.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | TABLE UPDATE | - | JIK | JES | CZH | 11/12/2019 | G | FIGURE UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | - | JC | JES | CZH | 06/13/2019 | F | MOVED FROM 4172 | EDM | JIK | - | - | 06/02/2020 |
| B | FIGURE UPDATE | - | JAC | JES | CZH | 04/20/2019 | E | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 |

**SCOPE:** THIS STANDARD SHOWS A 2-HOLE COPPER COMPRESSION TERMINAL, USED FOR TERMINATING COPPER CONDUCTORS ON POLE TOP SWITCH TABS AND TRANSFORMER FLAG CONNECTORS.





**FIGURE 1**

## TABLE 1

**TINNED COPPER TUBULAR COMPRESSION TERMINALS**

| WIRE | | | TOOL AND DIE SET CATALOG NUMBERS | | | | NUMBER OF CRIMPS | CATALOG NUMBER | | | | LENGTH (INCHES) | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | BURNDY | | | ALCOA | | | | | | | | |
| SIZE | STRANDING | | MD6 | Y-35 | Y-45 | 60A | | BURNDY | DOSSERT | PENN- UNION | HOMAC | | | |
| 1/0 | 7 | 19 | W163 | - | - | - | 4 | YA25-2N | DPL10-2N | BBLU 1/0 D3 | L 1/0-N | 3 7/16 | S729664 | CT1/0C |
| | | | - | U25RT | U25RT (D) | - | 2 | | | | | | | |
| | | | | U163 | U163 (D) | - | 2 | | | | | | | |
| 4/0 | 7 | 19 | W243 | - | - | - | 3 | YA28-2N | DPL21-2N | BBLU 4/0 D | L 4/0-N | 5 9/32 | S729792 | CT4/0C |
| | | | W BG | U28RT | U28RT (D) | - | 2 | | | | | | | |
| | | | | U243 | U243 (D) | - | 2 | | | | | | | |
| 350 KCM | 19 | 37 | - | U267 | U267 (D) | - | 6 | YCA31-2N | - | - | - | 6 1/2 | S729744 | CT350C |
| 400 KCM | 19 | 37 | - | U32RT | U32RT (D) | - | 4 | YA32-2N | DPL40-2N | BBLU 040 D | L 400-N | 5 31/32 | S729824 | CT400C |
| | | | | U169 | U169 (D) | - | 5 | | | | | | | |
| 500 KCM | 19 | 37 | - | U34RT | U34RT (D) | - | 4 | YA34-2N | DPL50-2N | BBLU 050 D | L 500-N | 6 3/16 | S729856 | CT500C |
| | | | | U251 | U251 (D) | - | 3 | | | | | | | |
| 750 KCM | 37 | 61 | - | - | S39RT | - | 6 | YA39-2N | DPL75-2N | BBLU 075 D | L 750-N | 7 | S729920 | CT750C |
| | | | | | - | L39RT | 2 | | | | | | | |

## INSTALLATION:

A. USE 1/2 INCH EVERDUR BOLTS FOR COPPER TO COPPER CONNECTIONS.

B. USE 1/2 INCH STAINLESS STEEL BOLTS FOR ALUMINUM TO COPPER CONNECTIONS.

C. USE FOR TERMINATING COPPER CONDUCTORS ON:

1. TRANSFORMER FLAG CONNECTORS, OH793.
2. MULTIPLE SERVICE CONNECTOR, OH793.
3. POLE TOP SWITCH TABS.

(D) USE ADAPTER DIE 6515 WITH BURNDY Y45 TOOL.

E. MAKE OVERLAPPING INDENTS FROM CONDUCTOR TO PAD.

F. WIRE BRUSH THE CONDUCTOR BEFORE INSTALLING TERMINAL.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | TABLE UPDATE | - | JIK | JES | CZH | 11/12/2019 | G | FIGURE UPDATE | EDM | RSL | JES | CZH | 12/12/2021 |
| C | EDITORIAL CHANGES | - | JC | JES | CZH | 06/13/2019 | F | MOVED FROM 4172 | EDM | JIK | - | - | 06/02/2020 |
| B | FIGURE UPDATE | - | JAC | JES | CZH | 04/20/2019 | E | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 04/13/2020 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE EQUIPMENT AND INSTALLATION OF 600 VOLT TYPE 1 CONNECTORS TO CONNECT SECONDARY AND SERVICE CABLE IN SUBSTRUCTURES.

**ATTENTION:**

* SLEEVES FROM DIFFERENT SUPPLIERS ARE NOT INTERCHANGEABLE.





**FIGURE 1**
TYPE 1 CONNECTOR





**FIGURE 2**
SLEEVE (D)




**FIGURE 3**
WIRE STRIPPING (E)

**TABLE 1**

| FIGURE 1 | | | | |
|---|---|---|---|---|
| **ITEM** | **DESCRIPTION** | | **STOCK NUMBER** | **DESIGN UNITS** |
| 1 | CONNECTOR WITH SLEEVES #8 THRU #350 | 4 TERMINALS, AL-CU | S256132 (B) | SEC-4W |
| | | 5 TERMINALS, AL-CU | S256134 (B) | SEC-5W |
| | | 6 TERMINALS, AL-CU | S256136 (B) | SEC-6W |
| | | 7 TERMINALS, AL-CU | S256138 (B) | SEC6SL |
| | CONNECTOR WITH SLEEVES #8 THRU #500 | 4 TERMINALS, AL-CU | S256146 (X) (B) | 500-4W |
| | | 5 TERMINALS, AL-CU | S484514 (X) (a) | 500-5W |
| | | 6 TERMINALS, AL-CU | S256148 (X) (B) | 500-6W |
| | | 8 TERMINALS, AL-CU | S484516 (X) (a) | 500-8W |
| 2 | INHIBITOR (USE AS REQUIRED) | - | S247200 | - |

**INSTALLATION:**

A. INSTALL THE SOURCE IN A MIDDLE TERMINAL AND LOAD CABLES IN THE REMAINING TERMINALS.

(B) THIS CONNECTOR UNIT ONLY ALLOWS ONE CONDUCTOR PER TERMINAL THE MINIMUM CABLE SIZE FOR A STREET LIGHT TERMINAL POSITION SHALL BE #8 AL OR CU AND SHALL OCCUPY ONE TERMINAL BY ITSELF.

C. PREPARE CABLE BY REMOVING ALL DIRT AND/OR MOISTURE FROM THE CABLE ENDS FOR A DISTANCE OF 12 T0 18 INCHES. LIBERALLY APPLY LUBRICANT (SILICONE GREASE) ON CABLE INSULATION AND INTERIOR SURFACES OF INSULATING SLEEVE WITH SUPPLIED LUBRICANT IN PREPARATION OF SLEEVE INSTALLATION.

(D) CUT THE SLEEVE STRAIGHT ACROSS THE PROPER STEP ACCORDING TO THE CONDUCTOR SIZE BEING INSTALLED. SEE FIGURE 2. FOR THE #8 THRU 350 CONNECTOR THE SLEEVE IS NOT USED FOR 350 KCMIL CABLE. INSERT THE 350 KCMIL DIRECTLY INTO THE CONNECTOR. FOR THE #8 THRU 500 CONNECTOR INSERT THE 500 KCMIL DIRECTLY INTO THE CONNECTOR AND CUT THE SLEEVE FOR 350 KCMIL AND BELOW.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 6/17/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

0 - 600 VOLT CONNECTORS
FOR #8 THRU 500 KCMIL AL OR CU CONDUCTORS

UG4175.1

## INSTALLATION (CONT'D):

(E) WIRE STRIPPING

1. SLIDE CONDUCTOR THROUGH SLEEVE UNTIL APPROXIMATELY 4 INCHES OF INSULATION IS SHOWING.
2. STRIP INSULATION FROM THE END OF THE CONDUCTOR ACCORDING TO THE STRIP GAUGE ON THE CONNECTOR (1 1/8" OR 1 1/4" DEPENDING ON MANUFACTURER). SEE FIGURE 3.

(F) PULL SCREW SEALING PLUG AND BACK OFF THE SET SCREW.

G. WIRE BRUSH CONDUCTOR WITH INHIBITOR AND INSERT CONDUCTOR INTO TERMINAL UNTIL IT STOPS AGAINST THE BACK OF THE CONNECTOR. (b)

H. TIGHTEN SCREW SECURELY AGAINST THE CONDUCTOR.

J. AFTER THE INITIAL CONNECTIONS HAVE BEEN MADE, VERIFY THAT THE PROPER TORQUE VALUES HAVE BEEN APPLIED, IT IS EXTREMELY IMPORTANT THAT SET SCREWS MEET THE FOLLOWING TORQUE VALUES:

1. #8 THRU #4: 8.5 FT-LBS TORQUE
2. #2 THRU 350 KCMIL: 25 FT-LBS TORQUE
3. 500 KCMIL: 35 FT-LBS TORQUE

K. RE-INSTALL SCREW SEALING PLUG. DO NOT LUBRICATE OR GREASE THE SCREW SEALING PLUG OR ITS PORT.

L. SLIDE INSULATING SLEEVES UP OVER CABLE SO THAT SLEEVES BUTT AGAINST THE TERMINAL.

M. USE UNCUT SLEEVES ON SPARE TERMINALS.

## BILL OF MATERIALS: NONE

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) REFER TO SHEET 3 THIS DOCUMENT.

(b) SEE UG4106, ALUMINUM CONDUCTOR PREPARATION FOR TERMINATIONS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 6/17/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

0 - 600 VOLT CONNECTORS
FOR #8 THRU 500 KCMIL AL OR CU CONDUCTORS

UG4175.2

**SCOPE:** THIS STANDARD SHOWS THE EQUIPMENT AND INSTALLATION OF 600 VOLT GEL PORT TYCO SECONDARY MOLD CONNECTORS TO CONNECT SECONDARY AND SERVICE CABLE IN SUBSTRUCTURES.





**FIGURE 1**
5-WAY





**FIGURE 2**
8-WAY





**FIGURE 3**
5-WAY INSTALLATION

## INSTALLATION:

A. REMOVE SHIPPING CAPS, IDENTIFY CABLE SIZE AND CABLE PORT SIZE.
   1. BLACK CAP FOR #14-350 KCMIL CABLE
   2. BLUE CAP FOR #2-500KCMIL CABLE

B. CLEAN 6" OF CABLE JACKET.

C. MARK CABLE 3 3/4" FROM END OF CABLE WITH TAPE OR WHITE MARKER.

D. CABLE STRIPPING
   1. REMOVE 1 3/4" OF INSULATION FROM END OF CABLE. CHECK STRIP LENGTH WITH THE GUIDE ON THE END OF THE MOLD.
   (2) STRIP LENGTH EQUALS CABLE PORT LENGTH.

E. SNAP OPEN SCREW CAP USING A 5/16" HEX WRENCH. BACK OFF HEX SCREW COUNTER CLOCKWISE ABOUT 3/4".

F. INSERT CABLE INTO CABLE PORT. CABLE SHOULD BOTTOM OUT AND THE MARK SHOULD BE FLUSH WITH END OF CABLE PORT. CHECK HEX SCREW IS BACKED OFF WHEN CABLE IS INSTALLED.

G. TIGHTEN HEX SCREW PER TORQUE GUIDE:
   1. NO. #14-6 175 INCH-LBS
   2. NO. #4-1/0 275 INCH-LBS
   3. NO. #2/0-500 350 INCH-LBS

H. MAKE SURE CABLE REMAINS SEATED AND DOES NOT BACK OUT WHEN TORQUE IS APPLIED.

J. CLOSE CAP WHEN COMPLETED MAKING SURE LATCH SNAPS FULLY CLOSED.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 6/17/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

0-600 VOLT CONNECTIONS AND HANDHOLE INSTALLATION
FOR #8 THROUGH 500 KCMIL CONDUCTORS

UG4175.3

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF HANDHOLES FOR 600 VOLT CONNECTORS TO CONNECT SECONDARY AND SERVICE CABLE.

**CAUTION:**

* WHEN INSTALLING HEAT SHRINK SLEEVES. DO NOT ALLOW FLAME TO BE APPLIED TO CONNECTOR INSULATION AS TRACES OF "HCI" (HYDROCHLORIC ACID) AND "CO" (CARBON MONOXIDE) GASES WILL BE GIVEN OFF.






**FIGURE 1**
FINAL CONNECTOR POSITION




TYPICAL PLAN VIEW

HANDHOLE MAY BE INSTALLED ON EITHER SIDE OF LOT LINE OR IN CENTER OF LOT LINE IN AREA WITH LIMITED SPACE. BUT AGAINST BACK OF SIDEWALK.

**FIGURE 2**
HANDHOLE LOCATION





**FIGURE 3**
HANDHOLE INSTALLATION
(3309.1/3309.2)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 6/17/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

0-600 VOLT CONNECTIONS AND HANDHOLE INSTALLATION FOR #8 THROUGH 500 KCMIL CONDUCTORS

UG4175.4

TABLE OF CONTENTS

## INSTALLATION:

(A) CUT THE CONDUIT (NOT THE NINETY DEGREES). IF A CONDUIT IS (OTHER THAN SERVICE LATERAL CONDUIT) EMPTY FOR FUTURE CABLE PULLING. SECURE THE MEASURING AND PULLING TAPE AND INSTALL AQUA-SEAL (STOCK NUMBER S442976) AND GRAY TAPE (STOCK NUMBER S721120) SECURELY TO PREVENT WATER ENTRY. CONDUITS MUST ENTER HANDHOLE AT ONE END FOR MAXIMUM TRAINING ROOM. SET HANDHOLE(S). COMPACT SOIL TO 90% AROUND HANDHOLE AREA. DO NOT BACKFILL WITH LARGE ROCKS THAT COULD BREAK HANDHOLE WHEN TAMPED. (c) (d)

B. CUT AND PREPARE CABLE.

(C) FINAL CONNECTOR POSITION MUST ENSURE THAT CONNECTOR WILL NOT TOUCH CONCRETE OR ABRASION DAMAGE WILL CAUSE PREMATURE FAILURE. PROVIDE PROPER CABLE LENGTHS AND CABLE TRAINING TO PREVENT ABRASION.

(D) MINIMUM CONDUCTOR BENDING RADIUS IS FIVE TIMES CABLE DIAMETER.

E. BOLT DOWN LID. (e)

(F) IF RIGHT OF WAY OR OBSTRUCTIONS CAUSE A PROBLEM THE HANDHOLE MAY BE TURNED TO WHERE LONG SIDE OF THE HANDHOLE PARALLELS THE SIDEWALK OR PROPERTY LINE.


## BILL OF MATERIALS: NONE

## NOTES:

I. 3309.1 HANDHOLE SINGLE-PHASE ALLOWS A MAXIMUM OF THREE CONNECTORS WITH EIGHT TERMINAL POSITIONS EACH. THE EIGHT RUNS SHALL NOT EXCEED ONE RUN 500 KCMIL, THREE RUNS 350 KCMIL, TWO RUNS 3/0 AND ONE STREET LIGHT RUN.

II. 3309.2 HANDHOLE SINGLE-PHASE ALLOWS A MAXIMUM THREE CONNECTORS WITH SEVEN TERMINAL POSITIONS EACH. THE SEVEN RUNS SHALL NOT EXCEED TWO RUNS 500 KCMIL, TWO RUNS 350 KCMIL, AND TWO RUNS 3/0 AND ONE STREET LIGHT RUN.

III. 3309.2 HANDHOLE THREE-PHASE ALLOWS A MAXIMUM OF FOUR CONNECTORS WITH SEVEN TERMINAL POSITIONS EACH. THIS SHALL NOT EXCEED FIVE RUNS THREE-PHASE CONSISTING OF ONE RUN 350 KCMIL AND FOUR RUNS 3/0 AND ONE SINGLE-PHASE STREET LIGHT RUN.




**EXAMPLE**

## REFERENCE:

a. SEE UG3312 FOR THE HANDHOLE MEASUREMENTS.

b. SEE UG3370 FOR TRENCH DEPTHS, BASE SHADING AND BACKFILL REQUIREMENTS.

(c) SEE UG3948 FOR SEALING SERVICE LATERAL CONDUITS AND FOR CONDUIT SEALANT TO USE FOR EXCESSIVE WATER ENTRY PROBLEMS.

(d) SEE UG3305 FOR SETTING TO FINAL GRADE IF SLOPED.

(e) SEE G.O. 128.32.7; COVERS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | TR/DW | 6/17/2014 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

0-600 VOLT CONNECTIONS AND HANDHOLE INSTALLATION
FOR #8 THROUGH 500 KCMIL CONDUCTORS

UG4175.5

**SCOPE:** THIS STANDARD SHOWS THE EQUIVALENT CONDUCTOR SIZE (PER PHASE) OF THE CONCENTRIC NEUTRAL WIRES FOR UNDERGROUND CABLES. USE THE CHART BELOW IN SELECTING PROPER COMPRESSION CONNECTORS (SQUEEZONS).

## INSTALLATION:

A. WIRE #14 AWG SOLID BARE SOFT DRAWN COPPER (STOCK NO. S812934) ON A 10LB. SPOOL IS AVAILABLE FOR GROUNDING PREMOLDED CONNECTORS.

### TABLE 1

| CONCENTRIC NEUTRAL INFORMATION - UNDERGROUND CABLES | | | | |
|---|---|---|---|---|
| **CABLE** | **APPROX EQUIVALENT CONDUCTOR (PER PHASE) AWG** | **APPROX EQUIVALENT CONDUCTOR (PER PHASE) CIRC MILS** | **NO. OF CONCENTRIC NEUTRAL WIRES (PER PHASE)** | **AWG SIZE (PER EACH CONCENTRIC NEUTRAL WIRE)** |
| 2 CU 1/C | #2 - 7 STRAND | 66,360 | 16 | 14 |
| 2 CU 3-1/C | #6 - 7 STRAND | 26,240 | 6 | 14 |
| 2 SOLID AL 1/C | #4 - 7 STRAND | 41,740 | 10 | 14 |
| 2 SOLID AL 3-1/C | #6 - 7 STRAND | 26,240 | 6 | 14 |
| 2/0 AL 3-1/C | #6 - 7 STRAND | 26,240 | 7 | 14 |
| 4/0 CU 3-1/C | #2 - 7 STRAND | 66,360 | 11 | 12 |
| 350 AL 3-1/C NEW | #4 - 7 STRAND | 41,740 | 9 | 14 |
| 350 AL 3-1/C OLD | #2 - 7 STRAND | 66,360 | 11 | 12 |
| 500 CU 3-1/C | #3/0 - 19 STRAND | 167,800 | 17 | 10 |
| 750 AL 3-1/C NEW | #1 - 19 STRAND | 83,690 | 12 | 12 |
| 750 AL 3-1/C OLD | #3/0 - 19 STRAND | 167,800 | 16 | 10 |
| 1000 AL 3-1/C NEW | #1/0 - 19 STRAND | 105,600 | 16 | 12 |
| 1000 AL 3-1/C OLD | #4/0 - 19 STRAND | 211,600 | 20 | 10 |

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE OH4174 FOR COPPER COMPRESSION CONNECTORS (SQUEEZONS).

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4174 | EDM | JIK | - | - | 6/2/2020 | F | | | | | | |
| B | MOVED FROM UG4172 | EDM | JIK | JES | CZH | 04/13/2020 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1992 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART

UG4176.1

**SCOPE:** THIS STANDARD SHOWS THE TEE BRACKET USED TO INSTALL 600A TEE CONNECTORS AT AN ANGLE IN HANDHOLES AND THE STAND OFF BAR USED TO FASTEN TO THE TEE BRACKET ALLOWING A PLACE TO PARK LOADBREAK ELBOWS.





**FIGURE 1**
STAND OFF BAR
FRONT VIEW





**FIGURE 2**
TEE BRACKET
SIDE VIEW





**FIGURE 2**
TEE BRACKET
FRONT VIEW

## INSTALLATION:

(A) THE STAND OFF BAR IS TO BE USED AS A TOOL AND SHOULD NOT BE PERMANENTLY INSTALLED WITH THE TEE BRACKET.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BAR, STAND OFF | AS REQ'D | -- | S677240 | -- |
| 2 | INSULATOR, UNISTRUT (REPLACEMENT ITEM) | AS REQ'D | -- | S430560 | -- |
| 3 | BRACKET, TEE | AS REQ'D | -- | S166675 | T/BRKT |

## NOTES:

I. TEE BRACKET COMES WITH ACCESSORIES SHOWN.

**REFERENCE:** NONE

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 3/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 3/7/2008 | E | FIGURE UPDATE | EDM | EJA | GLW | FRC | 02/15/2022 |
| A | REVISION | - | - | - | JJ/TR | 1/9/1992 | D | MOVED FROM UG4178 | EDM | JIK | - | - | 6/2/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

CABLE HANGERS AND ACCESSORIES

UG4177.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE APPLICATION AND INSTALLATION OF THE PREFERRED HEAVY DUTY NON-METALLIC EQUIPMENT/CABLE RACK.

**ATTENTION:**

* THIS ANCHOR SYSTEM SHALL **NOT** BE INSTALLED IN BRICK, BLOCK OR CONCRETE GROUT. THIS PRODUCT IS DESIGNED TO SUPPORT CABLE, EQUIPMENT AND CONNECTING LOADS.





**FIGURE 1**
EQUIPMENT/CABLE
SUPPORT ASSEMBLY





**FIGURE 1** (A1)
EQUIPMENT/CABLE
SUPPORT ASSEMBLY
FRONT VIEW




**FIGURE 1**
EQUIPMENT/CABLE
SUPPORT CHANNEL
ISO FRONT VIEW




**FIGURE 1**
EQUIPMENT/CABLE
SUPPORT CHANNEL
ISO REAR VIEW





**FIGURE 2**
SUPPORT BRACKET WITH TOP PIECE EXTENDED

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HEAVY DUTY NON-METALLIC EQUIPMENT/CABLE RACK
(PREFERRED)



UG4178.1

TABLE OF CONTENTS





**FIGURE 3**
CHANNEL, CABLE SADDLE, CABLE CLAMPS, (B)
AND CABLE/EQUIPMENT ARMS





**FIGURE 4**
CABLE AND EQUIPMENT ARMS
SUPPORT FLANGE TOP INSTALLATION (B)







**FIGURE 5**
LARGE STRAP

**TABLE 1**


| DIMENSION OF CABLE & EQUIPMENT ARMS | | | |
|---|---|---|---|
| **ITEM** | **Z (IN)** | **Y (IN)** | **X (IN)** |
| 7 | 6 | 4 1/4 | 4 5/16 |
| 8 | 5 1/2 | 5 13/16 | 2 3/8 |
| 9 | 7 | 5 7/8 | 3 7/8 |
| 10 | 7 1/2 | 5 | - |
| 11 | 11 | 5 | - |
| 12 | 20 13/16 | 8 3/16 | - |




**DETAIL 1**
LOCK FOR CABLE
SUPPORT BRACKET (B4)




**DETAIL 2**
TYPICAL SLIDING LOCK TAB
(RETRACTABLE VIA PRY SLOT
ON TOP OF LOCK TAB)



**DETAIL 2**
VIEW A-A

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HEAVY DUTY NON-METALLIC EQUIPMENT/CABLE RACK
(PREFERRED)

UG4178.2

## INSTALLATION:

(A) ANCHOR SYSTEM INSTALLATION

(1) WALL CHANNELS SHALL BE SET 22 1/8" APART, CENTER TO CENTER.

2. DRILL 1/2-INCH DIAMETER HOLE 2 INCHES DEEP.

(B) WALL CHANNELS, SUPPORT BRACKETS AND SADDLES INSTALLATION

1. SELECT WALL CHANNEL SIZE AS NEEDED. INSTALL A WASHER AND BOLT INTO EACH BOLT SLOT. TIGHTEN BOLT TO ATTAIN A SNUG FIT. DO NOT OVER TIGHTEN.
2. WALL CHANNELS SHOULD BE PLACED TO PROVIDE SUPPORT TO CABLE AND CONNECTION AS NEEDED.
3. ASSEMBLE SUPPORT BRACKETS, CLAMPS AND CABLE SADDLES INTO WALL CHANNEL. TAP SUPPORT BRACKETS, CLAMPS AND SADDLES DOWN LIGHTLY UNTIL SEATED.
4. INSTALL LOCKING PLUG. PLACE LOCKING PLUG INTO RECTANGULAR SLOT ABOVE SUPPORT BRACKET, CLAMPS OR SADDLE WITH LOCKING BARBS DOWN. PUSH LOCK IN UNTIL THE FLANGES ON LOCKING CLIP HIT WALL CHANNEL. LOCK WILL CLICK INTO PLACE.
5. IN ADDITION TO OR IN PLACE OF LOCK PLUG THE SECURING TOOL (PIN) MAY BE INSTALLED INTO WALL CHANNEL RIGHT ABOVE CABLE ARM OR SADDLE TO SECURE IT TO THE WALL.
6. USE LARGE BLACK TIE STRAPS TO SECURE CABLE AND CONNECTIONS AS NEEDED.

(C) WIDE TOP FLANGE

1. WIDE TOP FLANGES MAY BE INSTALLED TO PROVIDE FOR EQUIPMENT STABILITY OR ADDED HEIGHT TO CABLE TEE BODIES WHEN NEEDED.
2. TO INSTALL, SLIDE INTO PLACE UTILIZING GROOVES ON TOP OF SUPPORT BRACKET.
3. IF ADDED LENGTH OF CABLE ARM IS NEEDED WIDE TOP FLANGE MAY BE MOVED AWAY FROM WALL CHANNEL TO ADD LENGTH.
4. ROTATE LOCK TAB UPWARD USING PRY SLOT AND SLIDE OUT TO DESIRED LENGTH.

(D) CABLE CLAMP ASSEMBLY COMES WITH A REMOVABLE INSERT THAT MAY BE REMOVED TO ADJUST FOR CABLE SIZE.

## BILL OF MATERIALS:

| ITEM | | DESCRIPTION | MANUFACTURER | MANUFACTURER PART NUMBER | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| 1 | a | CHANNEL, WALL, 30" | ELECTRICAL MATERIALS CO. | 600ALBSUP | AS REQ'D | -- | S564478 | EQRACK (V) |
| | b | BRACKET, SUPPORT, 23 1/2" | | | | | | |
| | c | ANGLE PIECE, LEFT, 316 SS, 2" X 2" X 1/8" | | | | | | |
| | d | ANGLE PIECE, RIGHT, 316 SS, 2" X 2" X 1/8" | | | | | | |
| | e | TOP PIECE, FLAT, 316 SS, 23 1/4" X 4 7/8" X 1/8" | | | | | | |
| 2 | | LOCK, RACK, ARM TO CHANNEL | ELECTRICAL MATERIALS CO. | LOCKPLUG | AS REQ'D | -- | S564510 | -- |
| 3 | | STRAP, LARGE, BLACK | -- | -- | AS REQ'D | -- | S738440 | -- |
| 4 | | CHANNEL, WALL, 13" | ELECTRICAL MATERIALS CO. | CHNF13382 | AS REQ'D | -- | S564482 | -- |
| 5 | | CHANNEL, WALL, 24" | ELECTRICAL MATERIALS CO. | CHNF24387 | AS REQ'D | -- | S564484 | -- |
| 6 | | CHANNEL, WALL, 36" | ELECTRICAL MATERIALS CO. | CHNF3638T | AS REQ'D | -- | S564486 | -- |
| 7 | | SADDLE ASSEMBLY, CABLE, 3" X 5" | ELECTRICAL MATERIALS CO. | CS3X5P | AS REQ'D | -- | S564506 | -- |
| 8 | | CLAMP ASSEMBLY, CABLE, 2 3/8" I.D. | ELECTRICAL MATERIALS CO. | CACL2.36 | AS REQ'D | -- | S564504 | -- |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |



TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | MANUFACTURER | MANUFACTURER PART NUMBER | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 9 | CLAMP ASSEMBLY, CABLE, 3 1/2" (QTY. 2) | ELECTRICAL MATERIALS CO. | CACL3.53S | AS REQ'D | -- | S564502 | -- |
| 10 | BRACKET, SUPPORT, 7 1/2" | ELECTRICAL MATERIALS CO. | CSUP7HD | AS REQ'D | -- | S564488 | -- |
| 11 | BRACKET, SUPPORT, 11 1/2" (D) | ELECTRICAL MATERIALS CO. | CSUP11HD | AS REQ'D | -- | S564492 | -- |
| 12 | BRACKET, SUPPORT, 20" (D) | ELECTRICAL MATERIALS CO. | CSUP20HD | AS REQ'D | -- | S564500 | -- |
| 13 | FLANGE, WIDE TOP, TALL, 13 1/2" (IV) | ELECTRICAL MATERIALS CO. | WTOP132H | AS REQ'D | -- | S564498 | -- |
| 14 | FLANGE, WIDE TOP, SHORT, 13 1/2" (IV) | ELECTRICAL MATERIALS CO. | WTOP132S | AS REQ'D | -- | S564496 | -- |
| 15 | FLANGE, WIDE TOP, TALL, 20" | ELECTRICAL MATERIALS CO. | WTOP202H | AS REQ'D | -- | TBD | -- |
| 16 | FLANGE, WIDE TOP, SHORT, 20" | ELECTRICAL MATERIALS CO. | WTOP202S | AS REQ'D | -- | TBD | -- |
| 17 | ANCHOR, DROP-IN, 303 STAINLESS, 1/2" | HILTI | -- | AS REQ'D | 3675.3 | S108864 (X) | -- |
| | BOLT, HILTI, EZ, 1/2" X 3 1/2" | HILTI | -- | | -- | S108434 | -- |
| | BOLT, TITEN HD, ZINC PLATED, 3/8" X 4" | HILTI | -- | | -- | S152716 (X) | -- |

## NOTES:

I. NON-METALLIC CABLE RACKING STANDARD: UNDERGROUND DEVICES RACKING SYSTEM IS A FIBERGLASS REINFORCED POLYPROPYLENE OF EQUAL STRENGTH TO CURRENT GALVANIZED STEEL. IT IS THERMAL RESISTANT, WITH HIGH DIELECTRIC STRENGTH. IT IS CORROSION AND CHEMICAL RESISTANT AND WILL REDUCE CONTAMINATION AND WATER DISCOLORATION IN SUB-STRUCTURES. CABLE SADDLES AND CABLE BRACKETS HAVE SLOTS TO INSTALL CABLE TIES FOR CONDUCTOR AND CONNECTION TIE DOWN.

II. CABLE RACKING SYSTEM MAY BE INSTALLED IN ALL WALK-IN VAULTS AND MANHOLES. THIS SYSTEM MAY BE USED IN HAND HOLE APPLICATION WITH ATTENTION TO CABLE BRACKET LENGTH DOES NOT ENCROACH IN THE WORKING SPACE.

III. BEFORE DRILLING AND INSTALLING ANCHORS AND CHANNELS, CHECK THE GENERAL CONDITION OF CONCRETE THAT WILL HOLD ANCHOR. SURFACE SHOULD BE FLAT FOR A QUALITY INSTALLATION.

(IV) NOT SHOWN IN FIGURES.

(V) INCLUDES ALL HARDWARE SHOWN ON FIGURE 1.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HEAVY DUTY NON-METALLIC EQUIPMENT/CABLE RACK (PREFERRED)

UG4178.4

**SCOPE:** THIS STANDARD SHOWS THE APPLICATION AND INSTALLATION OF THE ALTERNATE HEAVY DUTY NON-METALLIC CABLE RACK.

**ATTENTION:**

* THIS ANCHOR SYSTEM SHALL **NOT** BE INSTALLED IN BRICK, BLOCK OR CONCRETE GROUT. THE RACKING SYSTEM CAN SUPPORT 250 LBS TO 450 LBS DEPENDING ON THE LENGTH OF THE CABLE ARM. THIS PRODUCT IS DESIGNED TO SUPPORT CABLE AND CONNECTING LOAD AND IS NOT TO BE USED AS A STEP OR LADDER AT ANY TIME.





**FIGURE 1**
ANCHOR SYSTEM INSTALLATION (A)





**FIGURE 2**
STANCHION, CABLE ARMS AND HOOKS
SIDE VIEW





**FIGURE 3**
STANCHION
FRONT VIEW (B)





**FIGURE 4**
LARGE STRAP






**FIGURE 5**
LOCKING CLIP


TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |




STEP 1




STEP 2 - CUT ABOVE BAR



STEP 3



STEP 4



STEP 5

**FIGURE 6**
CUTTING STANCHIONS FOR CUSTOM FIT (B3)

## INSTALLATION:

(A) ANCHOR SYSTEM INSTALLATION

1. DRILL AND INSTALL ANCHOR FOR EACH STANCHION HOLE, **THIS IS REQUIRED.**
2. USE A PLUMB LINE TO MARK DRILL POINTS. THIS WILL ENSURE STRAIGHT VERTICAL STANCHION INSTALLATION.
3. DRILL 5/8-INCH DIAMETER HOLE 2 INCHES DEEP.
4. BLOW OUT HOLE. IT MUST BE CLEAN TO SET ANCHOR CORRECTLY.
5. DRIVE ANCHOR FLUSH TO 1/16-INCH BELOW SURFACE OF CONCRETE.
6. EXPAND ANCHOR WITH FRT-112 SETTING TOOL. ANCHOR IS PROPERLY SET WHEN SHOULDER OF SETTING TOOL IS FLUSH WITH THE TOP OF THE ANCHOR.

(B) STANCHIONS, CABLE ARMS AND HOOKS INSTALLATION

1. SELECT STANCHION SIZE AS NEEDED. INSTALL A WASHER AND BOLT INTO EACH BOLT SLOT. TIGHTEN BOLT TO ATTAIN A SNUG FIT. DO NOT OVER TIGHTEN.
2. STANCHIONS SHOULD BE PLACED TO PROVIDE SUPPORT TO CABLE AND CONNECTION AS NEEDED.
3. (3) STANCHIONS MAY BE CUT FOR CUSTOM FIT IN SOME APPLICATIONS. SEE FIGURE 6 FOR CUTTING AT THE CORRECT POINT.
4. ASSEMBLE ARMS AND CABLE HOOKS INTO STANCHION. TAP THE ARMS AND HOOKS DOWN LIGHTLY UNTIL SEATED.
5. INSTALL LOCKING CLIP. PLACE THE LOCKING CLIP INTO RECTANGULAR SLOT ABOVE ARM OR HOOK WITH LOCKING BARBS UP. PUSH LOCK IN UNTIL THE FLANGES ON THE LOCKING CLIP HIT THE STANCHION. THE LOCK WILL CLICK INTO PLACE.
6. USE LARGE BLACK TIE STRAPS TO SECURE CABLE AND CONNECTIONS AS NEEDED.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | MANUFACTURER NUMBER | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | ANCHOR, DROP-IN 1/2-13, 303 STAINLESS | FSRM-12 | 1/SLOT | -- | S108864 (X) | -- |
| 2 | WASHER, FLAT, STAINLESS STEEL, 1/2" | -- | 1/SLOT | -- | S799680 | -- |
| 3 | BOLT, STAINLESS STEEL, 1/2 - 13 X 1 3/8" | FHC316-16-044 | AS REQ'D | -- | S148810 (X) | -- |
| 4 | SETTING TOOL | FRT-112 | AS REQ'D | -- | S746758 | -- |
| 5 | STANCHION, 12" | CR12-B | AS REQ'D | -- | S677288 (X) | -- |
| 6 | STANCHION, 24" | CR24-B | AS REQ'D | -- | S677290 (X) | -- |
| 7 | STANCHION, 36" | CR36-B | AS REQ'D | -- | S677292 (X) | -- |
| 8 | HOOK, CABLE, 3" | 3HDS | AS REQ'D | -- | S415432 (X) | -- |
| 9 | HOOK, CABLE, 4 15/16" | 4.9HDS | AS REQ'D | -- | S610948 (X) | -- |
| 10 | ARM, CABLE, 6" | RA06 | AS REQ'D | -- | S110564 (X) | -- |
| 11 | ARM, CABLE, 8" | RA08 | AS REQ'D | -- | S110570 (X) | -- |
| 12 | ARM, CABLE, 11" | RA11 | AS REQ'D | -- | S110576 (X) | -- |
| 13 | ARM, CABLE, 14" | RA14 | AS REQ'D | -- | S110582 (X) | -- |
| 14 | ARM, CABLE, 20" | RA20 | AS REQ'D | -- | S110590 (X) | -- |
| 15 | CLIP, LOCKING, BLACK | HDL | AS REQ'D | -- | S237512 (X) | -- |
| 16 | STRAP, LARGE, BLACK | -- | AS REQ'D | -- | S738440 | -- |

## NOTES:

I. NON-METALLIC CABLE RACKING STANDARD: UNDERGROUND DEVICES RACKING SYSTEM IS A FIBERGLASS REINFORCED NYLON OF EQUAL STRENGTH TO CURRENT GALVANIZED STEEL. IT IS THERMAL RESISTANT, WITH HIGH DIELECTRIC STRENGTH. IT IS CORROSION AND CHEMICAL RESISTANT AND WILL REDUCE CONTAMINATION AND WATER DISCOLORATION IN SUB-STRUCTURES. CABLE HOOKS AND ARMS HAVE SLOTS TO INSTALL CABLE TIES FOR CONDUCTOR AND CONNECTION TIE DOWN.

II. CABLE RACKING SYSTEM MAY BE INSTALLED IN ALL WALK-IN VAULTS AND MANHOLES. THIS SYSTEM MAY BE USED IN HAND HOLE APPLICATION WITH ATTENTION TO CABLE ARM LENGTH AS NOT TO ENCROACH IN THE WORKING SPACE.

III. BEFORE DRILLING AND INSTALLING ANCHORS AND STANCHIONS, CHECK THE GENERAL CONDITION OF THE CONCRETE THAT WILL HOLD THE ANCHOR. THE SURFACE SHOULD BE FLAT FOR A QUALITY INSTALLATION.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JJ/TR | 03/20/2008 | F | | | | | | |
| B | REVISION | - | - | - | JJ/TR | 03/07/2008 | E | DRAWING UPDATE | EDM | ADW | GLW | KRG | 07/14/2022 |
| A | REVISION | - | - | - | JJ/TR | 01/09/1992 | D | FORMATTING | EDM | JIK | - | - | 06/02/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

HEAVY DUTY NON-METALLIC CABLE RACK
(ALTERNATE)

UG4178.7

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AMP SPLICE AND CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION ORDERS.

**ATTENTION:**

* THIS CHART SHOWS HOW 200 AMP LOADBREAK CONNECTORS ARE ASSEMBLED TO FORM SOME OF THE COMBINATIONS SHOWN ON THIS STANDARD.





**FIGURE 1**
PAD-MOUNTED AND SUBSURFACE CONNECTOR APPLICATION CHART
200 AMP LOADBREAK

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | MOVED FROM UG4180 | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |



TABLE OF CONTENTS





**FIGURE 2**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**UG MAP SYMBOL**





**TABLE 1**

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | 3OO | 5OO |
| **CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC-300 | CC-500 |

## BILL OF MATERIALS (FIGURE 2):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 3-WAY | - | 1 | - | S718312 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | RECEPTACLE, INSULATING | - | 2 | - | S204304 | - |





**FIGURE 3**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**UG MAP SYMBOL**





**TABLE 2**

| ADDITIONAL MACRO UNITS | | | | | |
|---|---|---|---|---|---|
| CC-3BB | CC-3BC | CC-3B0 | CC-5BB | CC-5BC | CC-5CC |

**TABLE 3**

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 33O | 55O | 53O | 5BO | 5CO |
| **CABLE SIZE** | #2 AL-#2 AL | 2/0 AL-2/0 AL | 2/0 AL-#2 AL | 2/0 AL-#2 AL F.E. | 2/0 AL-2/0 AL F.E. |
| **MACRO UNITS** | CC-330 | CC-550 | CC-530 | CC-5B0 | CC-5C0 |

## BILL OF MATERIALS (FIGURE 3):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 3-WAY | - | 1 | - | S718312 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 1 OR 2 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED (a) | #2 AL | 0 OR 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |
| 4 | ELBOW, INSULATING | - | 1 | - | S204304 | - |





**FIGURE 4**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**UG MAP SYMBOL**





**TABLE 4**

| TYPICAL COMBINATIONS | | | | |
|---|---|---|---|---|
| **CODE** | 333 | 555 | 533 | 553 |
| **CABLE SIZE** | #2 AL-#2 AL #2 AL | 2/0 AL-2/0 AL 2/0 AL | 2/0 AL-#2 AL #2 AL | 2/0 AL-2/0 AL #2 AL |
| **MACRO UNITS** | CC-333 | CC-555 | CC-533 | CC-553 |

## BILL OF MATERIALS (FIGURE 4):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 3-WAY | - | 1 | - | S718312 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 3 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | MOVED FROM UG4180 | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |






**FIGURE 5**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**UG MAP SYMBOL**




## TABLE 5

| TYPICAL COMBINATIONS | | | | |
|---|---|---|---|---|
| **CODE** | 33B | 55C | 33C | 55B |
| **CABLE SIZE** | #2 AL-#2 AL #2 AL F.E. | 2/0 AL-2/0 AL 2/0 AL F.E. | #2 AL-#2 AL 2/0 AL F.E. | 2/0 AL-2/0 AL #2 AL F.E. |
| **MACRO UNITS** | CC-33B | CC-55C | CC-33C | CC-55B |

## BILL OF MATERIALS (FIGURE 5):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 3-WAY | - | 1 | - | S718312 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 2 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED (a) | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |






**FIGURE 6**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**UG MAP SYMBOL**




## TABLE 6

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | 3OOO | 5OOO |
| **CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC3000 | CC5000 |

## BILL OF MATERIALS (FIGURE 6):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY | - | 1 | - | S718328 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | RECEPTACLE, INSULATING | - | 3 | - | S204304 | - |





**FIGURE 7**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**UG MAP SYMBOL**




## TABLE 7

| ADDITIONAL MACRO UNITS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| CC3BB0 | CC3BC0 | CC3B00 | CC3C00 | CC3CC0 | CC5BBC | CC5BB0 | CC5BC0 | CC5CC0 |

## TABLE 8

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 33OO | 55OO | 53OO | 5BOO | 5COO |
| **CABLE SIZE** | #2 AL-#2 AL | 2/0 AL-2/0 AL | 2/0 AL-#2 AL | 2/0 AL-#2 AL F.E. | 2/0 AL-2/0 AL F.E. |
| **MACRO UNITS** | CC3300 | CC5500 | CC5300 | CC5B00 | CC5C00 |

## BILL OF MATERIALS (FIGURE 7):


| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY | - | 1 | - | S718328 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 1 OR 2 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED (a) | #2 AL | 0 OR 2 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |
| 4 | RECEPTACLE, INSULATING | - | 2 | - | S204304 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | MOVED FROM UG4180 | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |



TABLE OF CONTENTS




**UG MAP SYMBOL**




**FIGURE 8**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**TABLE 9**


| ADDITIONAL MACRO UNITS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| CC55CC | CC53BC | CC53B0 | CC53CC | CC55BB | CC55BC | CC33BB | CC33BC | CC33B0 | CC33CC | CC53BB |

**TABLE 10**

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 333O | 555O | 533O | 553O | 55BO | 55CO |
| **CABLE SIZE** | #2 AL-#2 AL -#2 AL | 2/0 AL-2/0 AL -2/0 AL | 2/0 AL-#2 AL -#2 AL | 2/0 AL-2/0 AL -#2 AL | 2/0 AL-2/0 AL #2 AL F.E. | 2/0 AL-2/0 AL 2/0 AL F.E. |
| **MACRO UNITS** | CC3330 | CC5550 | CC5330 | CC5B00 | CC55B0 | CC55C0 |

**BILL OF MATERIALS (FIGURE 8):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY | - | 1 | - | S718328 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 2 OR 3 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED (a) | #2 AL | 0 OR 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |
| 4 | RECEPTACLE, INSULATING | - | 1 | - | S204304 | - |




**UG MAP SYMBOL**






**FIGURE 9**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**TABLE 11**

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 3333 | 5555 | 5553 | 5533 | 5333 |
| **CABLE SIZE** | #2 AL-#2 AL-#2 AL-#2 AL | 2/0 AL-2/0 AL-2/0 AL-2/0 AL | 2/0 AL-2/0 AL-2/0 AL-#2 AL | 2/0 AL-2/0 AL-#2 AL-#2 AL | 2/0 AL-#2 AL-#2 AL-#2 AL |
| **MACRO UNITS** | CC3333 | CC5555 | CC5553 | CC5533 | CC5333 |

**BILL OF MATERIALS (FIGURE 9):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY | - | 1 | - | S718328 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 4 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |




**UG MAP SYMBOL**





**FIGURE 10**
PAD-MOUNTED AND SUBSURFACE CONNECTIONS
200 AMP LOADBREAK

**TABLE 12**

| ADDITIONAL MACRO UNITS | |
|---|---|
| CC533B | CC533C |

**TABLE 13**

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 333B | 555C | 333C | 555B | 553B |
| **CABLE SIZE** | #2 AL-#2 AL -#2 AL -#2 AL F.E. | 2/0 AL-2/0 AL -2/0 AL -2/0 AL F.E. | #2 AL-#2 AL -#2 AL -2/0 AL F.E. | 2/0 AL-2/0 AL -2/0 AL -#2 AL F.E. | 2/0 AL-2/0 AL -#2 AL -#2 AL F.E. |
| **MACRO UNITS** | CC333B | CC555C | CC333C | CC555B | CC553B |

**BILL OF MATERIALS (FIGURE 10):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY | - | 1 | - | S718328 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 3 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED (a) | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | MOVED FROM UG4180 | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |






**FIGURE 11**
PAD-MOUNTED
200 AMP LOADBREAK

**UG MAP SYMBOL**




## TABLE 14

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | 3OOONB | 5OOONB |
| **CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | C-3000 | C-5000 |

## BILL OF MATERIALS (FIGURE 11):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY (NO BRACKET) | - | 1 | - | S718338 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | RECEPTACLE, INSULATING | - | 3 | - | S204304 | - |





**FIGURE 12**
PAD-MOUNTED
200 AMP LOADBREAK

**UG MAP SYMBOL**




## TABLE 15

| ADDITIONAL MACRO UNITS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| C-3BB0 | C-3BC0 | C-3B00 | C-3C00 | C-3CC0 | C-5BBC | C-5BB0 | C-5BC0 | C-5CC0 |

## TABLE 16

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 33OONB | 55OONB | 53OONB | 5BOONB | 5COONB |
| **CABLE SIZE** | #2 AL-#2 AL | 2/0 AL-2/0 AL | 2/0 AL-#2 AL | 2/0 AL-#2 AL F.E | 2/0 AL-2/0 AL F.E. |
| **MACRO UNITS** | C-3300 | C-5500 | C-5300 | C-5B00 | C-5C00 |

## BILL OF MATERIALS (FIGURE 12):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY (NO BRACKET) | - | 1 | - | S718338 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 1 OR 2 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED | #2 AL | 0 OR 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |
| 4 | RECEPTACLE, INSULATING | - | 2 | - | S204304 | - |





**FIGURE 13**
PAD-MOUNTED
200 AMP LOADBREAK

**UG MAP SYMBOL**




## TABLE 17

| ADDITIONAL MACRO UNITS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| C-55CC | C-53BC | C-53B0 | C-53CC | C-55BB | C-55BC | C-33BB | C-33BC | C-33B0 | C-33CC | C-53BB |

## TABLE 18

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 333ONB | 555ONB | 533ONB | 553ONB | 55BONB | 55CONB |
| **CABLE SIZE** | #2 AL-#2 AL -#2 AL | 2/0 AL-2/0 AL -2/0 AL | 2/0 AL-#2 AL -#2 AL | 2/0 AL-2/0 AL -#2 AL | 2/0 AL-2/0 AL -#2 AL F.E. | 2/0 AL-2/0 AL -2/0 AL F.E. |
| **MACRO UNITS** | C-3330 | C-5550 | C-5330 | C-5530 | C-55B0 | C-55C0 |

## BILL OF MATERIALS (FIGURE 13):


| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY (NO BRACKET) | - | 1 | - | S718338 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 2 OR 3 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED | #2 AL | 0 OR 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |
| 4 | RECEPTACLE, INSULATING | - | 1 | - | S204304 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | MOVED FROM UG4180 | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |



TABLE OF CONTENTS




**UG MAP SYMBOL**






**FIGURE 14**
PAD-MOUNTED
200 AMP LOADBREAK

## TABLE 19

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 3333NB | 5555NB | 5553NB | 5533NB | 5333NB |
| **CABLE SIZE** | #2 AL-#2 AL-#2 AL-#2 AL | 2/0 AL-2/0 AL-2/0 AL-2/0 AL | 2/0 AL-2/0 AL-2/0 AL-#2 AL | 2/0 AL-2/0 AL-#2 AL-#2 AL | 2/0 AL-#2 AL-#2 AL-#2 AL |
| **MACRO UNITS** | C-3333 | C-5555 | C-5553 | C-5533 | C-5333 |

## BILL OF MATERIALS (FIGURE 14):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY (NO BRACKET) | - | 1 | - | S718338 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 4 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |




**UG MAP SYMBOL**





**FIGURE 15**
PAD-MOUNTED
200 AMP LOADBREAK

## TABLE 20

| ADDITIONAL MACRO UNITS | |
|---|---|
| C-533B | C-533C |

## TABLE 21

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | 333BNB | 555CNB | 333CNB | 555BNB | 553BNB |
| **CABLE SIZE** | #2 AL-#2 AL-#2 AL-#2 AL F.E. | 2/0 AL-2/0 AL-2/0 AL-2/0 AL F.E. | #2 AL-#2 AL-#2 AL-2/0 AL F.E. | 2/0 AL-2/0 AL-2/0 AL-#2 AL F.E. | 2/0 AL-2/0 AL-#2 AL-#2 AL F.E. |
| **MACRO UNITS** | C-333B | C-555C | C-333C | C-555B | C-553B |

## BILL OF MATERIALS (FIGURE 15):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TAP, CABLE, 4-WAY (NO BRACKET) | - | 1 | - | S718338 | - |
| 2 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 3 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | - |
| 3 | CONNECTOR, ELBOW, FUSED | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | - |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES.

**NOTES:**

I. **TABLE 22**

| CODES USED IN THE TABLES ON THIS STANDARD | |
|---|---|
| **CODE** | **TYPE** |
| **CABLE** | |
| 3 | #2 AL |
| 5 | 2/0 AL |
| **COMPONENT** | |
| B | #2 AL FUSED ELBOWS |
| C | 2/0 AL FUSED ELBOW |
| O | 200 AMP INSULATING RECEPTACLE |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE CONNECTIONS SHOWN.

**REFERENCE:**

(a) SEE UG3649 FOR "EQUIPMENT COMBINATION GUIDELINES" FOR FUSED ELBOWS.

b. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4191 AND UG4195.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | MOVED FROM UG4180 | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AMP PREMOLDED SPLICE AND CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION ORDERS.

**ATTENTION:**

* THIS CHART SHOWS HOW 200 AMP SPLICE CONNECTORS ARE ASSEMBLED.





**FIGURE 1**
SUBSURFACE SPLICE CONNECTOR APPLICATION CHART
200 AMP DEADBREAK

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | FORMATTING | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



12KV 200 AMP PREMOLDED SPLICE AND CONNECTOR ASSEMBLIES - IDENTIFICATION CHART

UG4180.1

TABLE OF CONTENTS





**FIGURE 2**
SUBSURFACE SPLICE CONNECTIONS
200 AMP DEADBREAK

**UG MAP SYMBOL**




**TABLE 1**

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | S3 | S5 |
| **CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC--S5<br>CC--S3 | CC--S5<br>CC--S5 |

**BILL OF MATERIALS (FIGURE 2):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | STRAIGHT PLUG | #2 AL | 1 | - | S547314 | - |
| | | 2/0 AL | | - | S547316 | - |
| 2 | DEADEND RECEPTACLE | - | 1 | - | S570304 | - |
| 3 | BAIL ASSEMBLY<br>(2 RINGS & 2 STRAPS IN KIT) | - | 1 | - | S120384 | - |






**FIGURE 3**
SUBSURFACE SPLICE CONNECTIONS
200 AMP DEADBREAK

**UG MAP SYMBOL**




1 - SC

**TABLE 2**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | S33 | S53 | S55 |
| **CABLE SIZE** | #2 AL-#2 AL | #2 AL-2/0 AL | 2/0 AL-2/0 AL |
| **MACRO UNITS** | CC-S33 | CC-S53 | CC-S55 |

**BILL OF MATERIALS (FIGURE 3):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | STRAIGHT PLUG | #2 AL | 1 | - | S547314 | - |
| | | 2/0 AL | | - | S547316 | - |
| 2 | STRAIGHT RECEPTACLE | #2 AL | 1 | - | S570816 | - |
| | | 2/0 AL | | - | S570848 | - |
| 3 | BAIL ASSEMBLY<br>(2 RINGS & 2 STRAPS IN KIT) | - | 1 | - | S120384 | - |





**FIGURE 4**
SUBSURFACE SPLICE CONNECTIONS (III)
200 AMP DEADBREAK

**TABLE 3**

| TYPICAL COMBINATIONS | | | | | |
|---|---|---|---|---|---|
| **CODE** | Q11 | Q13 | Q15 | Q33 | Q55 |
| **CABLE SIZE** | #2 CU-<br>#2 CU | #2 CU-<br>#2 AL | #2 CU-<br>2/0 AL | #2 AL-<br>#2 AL | 2/0 AL-<br>2/0 AL |
| **DESIGN UNITS** | NB-Q11 | NB-Q13 | NB-Q15 | NB-Q33 | NB-Q55 |

**BILL OF MATERIALS (FIGURE 4):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | EXTENSION SPLICE<br>200 AMP DEADBREAK | #2 CU | 1 | - | S668400 | - |
| | | #2 AL | | - | S668402 | - |
| | | 2/0 AL | | - | S668404 | - |
| | | #2 CU-#2 AL | | - | S668406 | - |
| | | #2 CU-2/0 AL | | - | S668408 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | FORMATTING | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |



TABLE OF CONTENTS





**FIGURE 5**
SUBSURFACE SPLICE CONNECTIONS
200 AMP DEADBREAK

**UG MAP SYMBOL**





**TABLE 4**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | D33 | D53 | D55 |
| **CABLE SIZE** | #2 AL-#2 AL | #2 AL-2/0 AL | 2/0 AL-2/0 AL |
| **MACRO UNITS** | CC-D33 | CC-D53 | CC-D55 |

## BILL OF MATERIALS (FIGURE 5):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | "T" SPLICE CONNECTOR | - | 1 | - | S256112 | - |
| 2 | DEADBREAK ELBOW CONNECTOR | #2 AL | 2 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | - |
| 3 | DEADEND PLUG | - | 1 | - | S544864 | - |
| 4 | BAIL ASSEMBLY (HOLD-DOWN BAIL & FLANGE IN KIT) | - | 1 | - | S120352 | - |
| 5 | BAIL ASSEMBLY (2 IN KIT) | - | 1 | - | S120448 | - |





**FIGURE 6**
SUBSURFACE SPLICE CONNECTIONS
200 AMP DEADBREAK

**UG MAP SYMBOL**





**TABLE 5**

| TYPICAL COMBINATIONS | | | | |
|---|---|---|---|---|
| **CODE** | D333 | D353 | D535 | D555 |
| **CABLE SIZE** | #2 AL-#2 AL-#2 AL | #2 AL-2/0 AL-#2 AL | 2/0 AL-#2 AL-2/0 AL | 2/0 AL-2/0 AL-2/0 AL |
| **MACRO UNITS** | CCD333 | CCD353 | CCD535 | CCD555 |

## BILL OF MATERIALS (FIGURE 6):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | "T" SPLICE CONNECTOR | - | 1 | - | S256112 | - |
| 2 | DEADBREAK ELBOW CONNECTOR | #2 AL | 2 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | - |
| 3 | STRAIGHT PLUG | #2 AL | 1 | - | S547314 | - |
| | | 2/0 AL | | - | S547316 | |
| 4 | BAIL ASSEMBLY (2 RINGS & 2 STRAPS IN KIT) | - | 1 | - | S120384 | - |
| 5 | BAIL ASSEMBLY (2 IN KIT) | - | 1 | - | S120448 | - |








TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | FORMATTING | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |

## TABLE 6

**PARTS IDENTIFICATION CHART**

| PART | WIRE SIZE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|
|  3 OR 4 WAY CABLE TAP | 3-WAY | S718312 | TAP-3W |
| | 4-WAY | S718328 | TAP-4W |
|  LOADBREAK ELBOW | #2 CU | S443837 | LBE-2C |
| | #2 AL | S443838 | LBE-2A |
| | #2/0 AL | S443840 | LBE2/0 |
|  DEADBREAK ELBOW BAIL | #2 CU | S443456 | NBE-2C |
| | #2 AL | S443842 | NBE-2A |
| | #2/0 AL | S443844 | NBE2/0 |
|  EXTENSION SPLICE | #2 CU | S668400 | NB-Q11 |
| | #2 AL | S668402 | NB-Q33 |
| | #2/0 AL | S668404 | NB-Q55 |
| | #2 CU- #2 AL | S668406 | NB-Q13 |
| | #2 CU- 2/0 AL | S668408 | NB-Q15 |
|  FUSED ELBOW | #2 CU | S443864 | FE-2CU |
| | #2 AL | S443850 | FE-2AL |
| | 2/0 AL | S443882 | FE-2/0 |
|  STRAIGHT RECEPTACLE | #4 CU | S570768 | REC-4C |
| | #2 CU | S570256 | REC-2C |
| | #2 AL | S570816 | REC-2A |
| | 2/0 AL | S570848 | REC2/0 |
|  STRAIGHT PLUG | #4 CU | S544694 | PLG-4C |
| | #2 CU | S544688 | PLG-2C |
| | #2 AL | S547314 | PLG-2A |
| | 2/0 AL | S547316 | PLG 2/0 |







| PART | STOCK NUMBER | DESIGN UNITS |
|---|---|---|
|  FEED-THRU INSERT | S544678 | FEED-I |
|  BUSHING PLUG | S544676 | BSHPLG |
|  "T" SPLICE | S256112 | NLBTEE |
|  DEADEND RECEPTACLE | S570304 | DE-REC |
|  DEADEND PLUG | S544864 | NLB-DE |
|  STAND-OFF PLUG | S547312 | S/0PLG |
|  FEED-THRU BUSHING | S182016 | FEED-B |
|  200 AMP INSULATING RECEPTACLE | S204304 | INSREC |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | FORMATTING | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES.

**NOTES:**

I. **TABLE 7**

| CODES USED IN THE TABLES ON THIS STANDARD | |
|---|---|
| **CODE** | **TYPE** |
| **CABLE** | |
| 1 | #2 CU |
| 3 | #2 AL |
| 5 | 2/0 AL |
| **COMPONENT** | |
| D | 200 AMP TEE SPLICE |
| Q | 200 AMP EXTENSION SPLICE |
| S | 200 AMP SPLICE |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE CONNECTIONS SHOWN.

(III) THIS SPLICE ONLY TO BE USED FOR SPLICING WHEN EXTRA CABLE IS REQUIRED ON EXISTING SYSTEMS. EXAMPLE (TRANSFORMER OR OTHER PAD-MOUNTED EQUIPMENT REPLACEMENT, CABLE TAPS BEING RAISED IN HANDHOLES, ETC.) THIS SPLICE IS NOT TO BE USED FOR ANY OTHER TYPE OF SPLICING. SEE PAGE UG4196.4 FOR EXTENSION SPLICE APPLICATIONS.

**REFERENCE:**

a. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4191 AND UG4195.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | F | FORMATTING | EDM | JIK | - | - | 6/2/2020 |
| B | REVISION | - | - | - | SLC/DTE | 1/1/1990 | E | REVISION | - | - | - | TR/MJC | 7/9/2012 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1989 | D | REVISION | - | - | - | TR/MJC | 11/8/2011 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV 200 AMP PREMOLDED SPLICE AND CONNECTOR ASSEMBLIES - IDENTIFICATION CHART

UG4180.5

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AND 600 AMP CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION WORK ORDERS FOR HANDHOLE INSTALLATIONS.

**ATTENTION:**

* THIS FIGURE SHOWS HOW 200 AMP AND 600 AMP CONNECTORS ARE ASSEMBLED.

** ALWAYS USE THE MANUFACTURERS RECOMMENDED TORQUE SETTINGS WHEN ASSEMBLING CONNECTORS.





**FIGURE 1**
SUBSURFACE CONNECTOR APPLICATION CHART
3315 & 3316 HANDHOLE INSTALLATION ONLY
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV 200 & 600 AMP CONNECTOR ASSEMBLIES
IDENTIFICATION CHART
HANDHOLE INSTALLATIONS



UG4181.1

TABLE OF CONTENTS





**FIGURE 2**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

**TABLE 1**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | O7 | O8 | O9 |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | CC-07 | CC-08 | CC-09 |

**BILL OF MATERIALS (FIGURE 2):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |
| 5 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 6 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 7 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |





**FIGURE 3**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

**TABLE 2**

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | L37 | L57 | L38 | L58 | L39 | L59 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | #2 AL<br>350 AL | 2/0 AL<br>350 AL | #2 AL<br>750 AL | 2/0 AL<br>750 AL | #2 AL<br>1000 AL | 2/0 AL<br>1000 AL |
| **MACRO UNITS** | CC-L37 | CC-L57 | CC-L38 | CC-L58 | CC-L39 | CC-L59 |

**BILL OF MATERIALS (FIGURE 3):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 5 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 6 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 7 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |





**FIGURE 4**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK
AND 600 AMP DEADBREAK

**TABLE 3**

| ADDITIONAL MACRO UNITS | | |
|---|---|---|
| C-07D5 | C-08D5 | C-09D5 |

**TABLE 4**

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | L37D5 | L57D5 | L38D5 | L58D5 | L39D5 | L59D5 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | #2 AL<br>350 AL<br>2/0 AL | 2/0 AL<br>350 AL<br>2/0 AL | #2 AL<br>750 AL<br>2/0 AL | 2/0 AL<br>750 AL<br>2/0 AL | #2 AL<br>1000 AL<br>2/0 AL | 2/0 AL<br>1000 AL<br>2/0 AL |
| **MACRO UNITS** | CL37D5 | CL57D5 | CL38D5 | CL58D5 | CL39D5 | CL59D5 |

**BILL OF MATERIALS (FIGURE 4):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | LOAD BREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 5 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 6 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 7 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |





**FIGURE 5**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK
AND 600 AMP DEADBREAK

**TABLE 5**

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | B7 | C7 | B8 | C8 | B9 | C9 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | #2 AL<br>350 AL | 2/0 AL<br>350 AL | #2 AL<br>750 AL | #2 AL<br>750 AL | 2/0 AL<br>1000 AL | 2/0 AL<br>1000 AL |
| **MACRO UNITS** | CC-B7 | CC-C7 | CC-B8 | CC-C8 | CC-B9 | CC-C9 |

**BILL OF MATERIALS (FIGURE 5):**


| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |
| 5 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 6 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 7 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |



TABLE OF CONTENTS









**FIGURE 6**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK
AND 600 AMP DEADBREAK

## TABLE 6

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | B7D5 | C7D5 | B8D5 | C8D5 | B9D5 | C9D5 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | #2 AL<br>350 AL<br>2/0 AL | 2/0 AL<br>350 AL<br>2/0 AL | #2 AL<br>750 AL<br>2/0 AL | 2/0 AL<br>750 AL<br>2/0 AL | #2 AL<br>1000 AL<br>2/0 AL | 2/0 AL<br>1000 AL<br>2/0 AL |
| **MACRO UNITS** | C-B7D5 | C-C7D5 | C-B8D5 | C-C8D5 | C-B9D5 | C-C9D5 |

## BILL OF MATERIALS (FIGURE 6):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |
| 5 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S544832 | |
| 6 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 7 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 8 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |








**FIGURE 7**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

## TABLE 7

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | O77 | O88 | O99 |
| **600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | 350 AL<br>350 AL | 750 AL<br>750 AL | 1000 AL<br>1000 AL |
| **MACRO UNITS** | CC-077 | CC-088 | CC-099 |

## BILL OF MATERIALS (FIGURE 7):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |





**FIGURE 8**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK
AND 600 AMP DEADBREAK

## TABLE 8

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | L377 | L577 | L388 | L588 | L399 | L599 |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL | #2 AL | 2/0 AL | #2 AL | 2/0 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **MACRO UNITS** | C-L377 | C-L577 | C-L388 | C-L588 | C-L399 | C-L599 |

## BILL OF MATERIALS (FIGURE 8):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |





**FIGURE 9**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK
AND 600 AMP DEADBREAK

## TABLE 9

| ADDITIONAL MACRO UNITS | | |
|---|---|---|
| CO77D5<br>CO77D3 | CO88D5<br>CO88D3 | CO99D5<br>CO99D3 |

## TABLE 10


| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | L377D5 | L577D5 | L388D5 | L588D5 | L399D5 | L599D5 |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL | #2 AL | 2/0 AL | #2 AL | 2/0 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **200 AMP CABLE SIZE** | 2/0 AL | 2/0 AL | 2/0 AL | 2/0 AL | 2/0 AL | 2/0 AL |
| **MACRO UNITS** | L377D3<br>L377D5 | L577D3<br>L577D5 | L388D3<br>L388D5 | L588D5 | L399D5 | L599D5 |

## BILL OF MATERIALS (FIGURE 9):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 6 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 7 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |









**FIGURE 10**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

## TABLE 11

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | B77 | C77 | B88 | C88 | B99 | C99 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | #2 AL<br>350 AL<br>350 AL | 2/0 AL<br>350 AL<br>350 AL | #2 AL<br>750 AL<br>750 AL | 2/0 AL<br>750 AL<br>750 AL | #2 AL<br>1000 AL<br>1000 AL | 2/0 AL<br>1000 AL<br>1000 AL |
| **MACRO UNITS** | CC-B77 | CC-C77 | CC-B88 | CC-C88 | CC-B99 | CC-C99 |

## BILL OF MATERIALS (FIGURE 10):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544832 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |








**FIGURE 11**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS - 200 AMP
LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

## TABLE 12

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | B77D5 | C77D5 | B88D5 | C88D5 | B99D5 | C99D5 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | #2 AL<br>350 AL<br>350 AL<br>2/0 AL | 2/0 AL<br>350 AL<br>350 AL<br>2/0 AL | #2 AL<br>750 AL<br>750 AL<br>2/0 AL | 2/0 AL<br>750 AL<br>750 AL<br>2/0 AL | #2 AL<br>1000 AL<br>1000 AL<br>2/0 AL | 2/0 AL<br>1000 AL<br>1000 AL<br>2/0 AL |
| **MACRO UNITS** | CB77D5 | CC77D5 | CB88D5 | CC88D5 | CB99D5 | CC99D5 |

## BILL OF MATERIALS (FIGURE 11):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 6 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 7 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |





**FIGURE 12**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

**UG MAP SYMBOL**





**TABLE 13**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | O777 | O888 | O999 |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | C-0777 | C-0888 | C-0999 |

## BILL OF MATERIALS (FIGURE 12):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 3 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 2 | - | S544832 | - |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 3 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |





**FIGURE 13**
3315 & 3316 HANDHOLE INSTALLATION ONLY
SUBSURFACE CONNECTIONS
200 AMP LOADBREAK/DEADBREAK AND 600 AMP DEADBREAK

**UG MAP SYMBOL**





**TABLE 14**

| ADDITIONAL MACRO UNIT |
|---|
| CL5889 |

**TABLE 15**

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | L3777 | L5777 | L3888 | L5888 | L3999 | L5999 |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL | #2 AL | 2/0 AL | #2 AL | 2/0 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **MACRO UNITS** | CL3777 | CL5777 | CL3888 | CL5888 | CL3999 | CL5999 |

## BILL OF MATERIALS (FIGURE 13):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 3 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 5 | DOUBLE-ENDED CONNECTOR PLUG | - | 2 | - | S544832 | - |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 3 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

## INSTALLATION:

A. THREE TEE COMBINATIONS SHOWN IN THIS STANDARD SHALL ONLY BE USED TO FEED A SWITCHED TIE POSITION.

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

## NOTES:

I. **TABLE 16**

| CODES USED IN TABLES 1-15 (HANDHOLE INSTALLATIONS) | |
|---|---|
| **CODE** | **TYPE** |
| **CABLE** | |
| 7 | 350 AL |
| 8 | 750 AL |
| 9 | 1000 AL |
| **COMPONENT** | |
| D3 | DEADBREAK ELBOW #2 AL |
| D5 | DEADBREAK ELBOW 2/0 |
| L3 | LOADBREAK ELBOW #2 AL |
| L5 | LOADBREAK ELBOW 2/0 AL |
| B | #2 AL FUSED ELBOW |
| C | 2/0 AL FUSED ELBOW |
| O | 200 AMP INSULATING RECEPTACLE |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE COMBINATIONS SHOWN.

III. EXCEPTION FOR COMBINATIONS NOT SHOWN:

a. FOR ANTICIPATED 200 AMP LOAD IN THE NEAR FUTURE, INSTALL DEADBREAK ELBOWS (PRESENT LOAD) ON THE BOTTOM OF THE 600 AMP TEES AND 200 AMP INSULATING RECEPTACLES ON THE TOP.

## REFERENCE:

a. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4182, UG4190, UG4191 AND UG4196.

(b) FOR GROUNDING ELBOW KIT, REFER TO UG4179.1.

(c) FOR INFORMATION ON COLD SHRINK ELBOW TEE, REFER TO UG4189 (FUTURE).

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AND 600 AMP CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION WORK ORDERS FOR MANHOLE INSTALLATIONS.

**ATTENTION:**

* THIS FIGURE SHOWS HOW 200 AMP AND 600 AMP CONNECTORS ARE ASSEMBLED.

** ALWAYS USE THE MANUFACTURERS RECOMMENDED TORQUE SETTINGS WHEN ASSEMBLING CONNECTORS.





**FIGURE 1**
SUBSURFACE CONNECTOR APPLICATION CHART
200 AND 600 AMP DEADBREAK MANHOLE INSTALLATION

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SHEET 9 OF 28

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


12KV 200 & 600 AMP CONNECTOR ASSEMBLIES IDENTIFICATION CHART
MANHOLE INSTALLATIONS

UG4181.9

TABLE OF CONTENTS




**UG MAP SYMBOL**




3 - T


**FIGURE 2**
MANHOLE INSTALLATION SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 1

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | 7 | 8 | 9 |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | CC---7 | CC---8 | CC---9 |

## BILL OF MATERIALS (FIGURE 2):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 2 | - | S544848 | - |
| 3 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |




**UG MAP SYMBOL**




3 - T

**FIGURE 3**
MANHOLE INSTALLATION SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 2

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 73 | 75 | 83 | 85 | 93 | 95 |
| **600 AMP CABLE SIZE<br>200 AMP CABLE SIZE** | 350 AL<br>#2 AL | 350 AL<br>2/0 AL | 750 AL<br>#2 AL | 750 AL<br>2/0 AL | 1000 AL<br>#2 AL | 1000 AL<br>2/0 AL |
| **MACRO UNITS** | CC--73 | CC--75 | CC--83 | CC--85 | CC--93 | CC--95 |

## BILL OF MATERIALS (FIGURE 3):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 4 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 5 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |





**FIGURE 4**
MANHOLE INSTALLATION SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 3

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 375 | 575 | 583 | 585 | 593 | 595 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | #2 AL<br>350 AL<br>2/0 AL | 2/0 AL<br>350 AL<br>2/0 AL | 2/0 AL<br>750 AL<br>#2 AL | 2/0 AL<br>750 AL<br>2/0 AL | 2/0 AL<br>1000 AL<br>#2 AL | 2/0 AL<br>1000 AL<br>2/0 AL |
| **MACRO UNITS** | CC-375 | CC-575 | CC-583 | CC-585 | CC-593 | CC-595 |

## BILL OF MATERIALS (FIGURE 4):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 3 | DEADBREAK ELBOW CONNECTOR | #2 AL | 2 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AN 1000 | | - | S471316 | P6ALR5 |






**FIGURE 5**
MANHOLE INSTALLATION SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK




## TABLE 4

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 77 | 87 | 88 | 97 | 98 | 99 |
| **600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | 350 AL<br>350 AL | 350 AL<br>750 AL | 750 AL<br>750 AL | 350 AL<br>1000 AL | 750 AL<br>1000 AL | 1000 AL<br>1000 AL |
| **MACRO UNITS** | CC--77 | CC--87 | CC--88 | CC--97 | CC--98 | CC--99 |

## BILL OF MATERIALS (FIGURE 5):


| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | 600/200 AMP TAP PLUG | - | 2 | - | S547324 | - |
| 3 | DOUBLE ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 TO 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 TO 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |



TABLE OF CONTENTS









**FIGURE 6**
MANHOLE INSTALLATION SUBSURFACE
CONNECTIONS - 200 AND 600 AMP DEADBREAK

## TABLE 5

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 773 | 775 | 883 | 885 | 993 | 995 |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL | #2 AL | 2/0 AL | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC-773 | CC-775 | CC-883 | CC-885 | CC-993 | CC-995 |

## BILL OF MATERIALS (FIGURE 6):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | DOUBLE ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 4 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 5 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |








**FIGURE 7**
MANHOLE INSTALLATION SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 6

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 5773 | 5775 | 5883 | 5885 | 5993 | 5995 |
| **200 AMP CABLE SIZE** | 2/0 AL | 2/0 AL | 2/0 AL | 2/0 AL | 2/0 AL | 2/0 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **600 AMP CABLE SIZE** | 350 AL | 350 AL | 750 AL | 750 AL | 1000 AL | 1000 AL |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL | #2 AL | 2/0 AL | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC5773 | CC5775 | CC5883 | CC5885 | CC5993 | CC5995 |

## BILL OF MATERIALS (FIGURE 7):


| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | DOUBLE ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 3 | 600/200 AMP TAP PLUG | - | 2 | - | S547324 | - |
| 4 | DEADBREAK ELBOW CONNECTOR | #2 AL | 2 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 5 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |



TABLE OF CONTENTS









**FIGURE 8**
MANHOLE INSTALLATION SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 7

| TYPICAL COMBINATIONS | | | | |
|---|---|---|---|---|
| **CODE** | 777 | 888 | 889 | 999 |
| **600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | 350 AL<br>350 AL<br>350 AL | 750 AL<br>750 AL<br>750 AL | 750 AL<br>750 AL<br>1000 AL | 1000 AL<br>1000 AL<br>1000 AL |
| **MACRO UNITS** | CC-777 | CC-888 | CC-889 | CC-999 |

## BILL OF MATERIALS (FIGURE 8):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 3 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 2 | - | S544848 | - |
| 3 | DOUBLE ENDED CONNECTOR PLUG | - | 2 | - | S544832 | - |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 3 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |








**FIGURE 9**
MANHOLE INSTALLATION
SUBSURFACE CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 8

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 7773 | 7775 | 8883 | 8885 | 9993 | 9995 |
| **600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | 350 AL<br>350 AL<br>350 AL<br>#2 AL | 350 AL<br>350 AL<br>350 AL<br>2/0 AL | 750 AL<br>750 AL<br>750 AL<br>#2 AL | 750 AL<br>750 AL<br>750 AL<br>2/0 AL | 1000 AL<br>1000 AL<br>1000 AL<br>#2 AL | 1000 AL<br>1000 AL<br>1000 AL<br>2/0 AL |
| **MACRO UNITS** | CC7773 | CC7775 | CC8883 | CC8885 | CC9993 | CC9995 |

## BILL OF MATERIALS (FIGURE 9):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 3 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | DOUBLE ENDED CONNECTOR PLUG | - | 2 | - | S544832 | - |
| 4 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 5 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 6 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 3 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

## INSTALLATION:

A. THREE TEE COMBINATIONS SHOWN IN THIS STANDARD SHALL ONLY BE USED TO FEED A SWITCHED TIE POSITION.

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

## NOTES:

I. **TABLE 9**

| CODES USED IN TABLES 1-8 | |
|---|---|
| **CODE** | **TYPE** |
| **CABLE** | |
| 3 | #2 AL |
| 5 | 2/0 AL |
| 6 | 4/0 AL |
| 7 | 350 AL |
| 8 | 750 AL |
| 9 | 1000 AL |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE COMBINATIONS SHOWN.

## REFERENCE:

a. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4182 AND UG4196.

(b) FOR INFORMATION ON COLD SHRINK ELBOW TEE, REFER TO UG4189 (FUTURE).

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AND 600 AMP CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION WORK ORDERS FOR SUBSURFACE/SURFACE OPERABLE SWITCH CONNECTIONS.

**ATTENTION:**

* THIS FIGURE SHOWS HOW 200 AMP AND 600 AMP CONNECTORS ARE ASSEMBLED.

** ALWAYS USE THE MANUFACTURERS RECOMMENDED TORQUE SETTINGS WHEN ASSEMBLING CONNECTORS.





**FIGURE 1**

SUBSURFACE/SURFACE OPERABLE SWITCH CONNECTOR APPLICATION CHART
200 AND 600 AMP DEADBREAK

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV 200 & 600 AMP CONNECTOR ASSEMBLIES
IDENTIFICATION CHART
SUBSURFACE/SURFACE OPERABLE SWITCH CONNECTIONS



UG4181.15

TABLE OF CONTENTS






**FIGURE 2**
SUBSURFACE/SURFACE OPERABLE
SWITCH CONNECTIONS
200 AND 600 AMP DEADBREAK

**UG MAP SYMBOL**





## TABLE 1

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | T7 | T8 | T9 |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | CC-T7 | CC-T8 | CC-T9 |

## BILL OF MATERIALS (FIGURE 2):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 3 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |




**UG MAP SYMBOL**





**FIGURE 3**
SUBSURFACE/SURFACE OPERABLE
SWITCH CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 2

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | T73 | T75 | T83 | T85 | T93 | T95 |
| **600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | 350 AL<br>#2 AL | 350 AL<br>2/0 AL | 750 AL<br>#2 AL | 750 AL<br>2/0 AL | 1000 AL<br>#2 AL | 1000 AL<br>2/0 AL |
| **MACRO UNITS** | CC-T73 | CC-T75 | CC-T83 | CC-T85 | CC-T93 | CC-T95 |

## BILL OF MATERIALS (FIGURE 3):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 3 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |




**UG MAP SYMBOL**





**FIGURE 4**
SUBSURFACE/SURFACE OPERABLE
SWITCH CONNECTIONS
200 AND 600 AMP DEADBREAK

## TABLE 3

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | F3 | F5 |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC-F3 | CC-F5 |

## BILL OF MATERIALS (FIGURE 4):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 2 | 600/200 AMP TAP PLUG | - | 1 | - | S547324 | - |
| 3 | DEADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443842 | - |
| | | 2/0 AL | | - | S443844 | |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV 200 & 600 AMP CONNECTOR ASSEMBLIES
IDENTIFICATION CHART
SUBSURFACE/SURFACE OPERABLE SWITCH CONNECTIONS

UG4181.16

TABLE OF CONTENTS





**FIGURE 5**
SUBSURFACE/SURFACE OPERABLE
SWITCH CONNECTIONS
200 AND 600 AMP DEADBREAK

**UG MAP SYMBOL**






**TABLE 4**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | F7 | F8 | F9 |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | CC--F7 | CC--F8 | CC--F9 |

**BILL OF MATERIALS (FIGURE 5):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 3 | INSULATED PLUG W/ TEST POINT | - | 1 | - | S544848 | - |
| 4 | DOUBLE ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 5 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

TABLE OF CONTENTS




**UG MAP SYMBOL**





**FIGURE 6**
SUBSURFACE/SURFACE OPERABLE
SWITCH CONNECTIONS
200 AND 600 AMP DEADBREAK

**TABLE 5**

| TYPICAL COMBINATIONS | |
|---|---|
| **CODE** | H |
| **MACRO UNITS** | CC---H |

**BILL OF MATERIALS (FIGURE 6):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | 600 AMP INSULATING RECEPTACLE | - | 1 | - | S570608 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

## INSTALLATION:

A. DO NOT "PIGGYBACK" 600 AMP TEES ON TOP OF EACH OTHER AT ANY TIME ON THE SWITCH BUSHING.

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

## NOTES:

I. **TABLE 6**

| CODES USED IN TABLES 1-5 (SUBSURFACE/SURFACE OPERABLE SWITCH CONNECTIONS) | |
|---|---|
| **CODES** | **TYPE** |
| **CABLE** | |
| 3 | #2 AL |
| 5 | 2/0 AL |
| 7 | 350 AL |
| 8 | 750 AL |
| 9 | 1000 AL |
| **COMPONENT** | |
| F | 600 AMP SUBSURFACE/SURFACE OPERABLE SWITCH BUSHING EXTENSION |
| H | 600 AMP SUBSURFACE/SURFACE OPERABLE SWITCH INSULATING RECEPTACLE |
| T | 600 AMP SUBSURFACE/SURFACE OPERABLE SWITCH TEE |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE COMBINATIONS SHOWN.

## REFERENCE:

a. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4182 AND UG4196.

(b) FOR INFORMATION ON COLD SHRINK ELBOW TEE, REFER TO UG4189 (FUTURE).

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AND 600 AMP CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION WORK ORDERS FOR PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTOR APPLICATIONS.

**ATTENTION:**

* THIS FIGURE SHOWS HOW 200 AMP AND 600 AMP CONNECTORS ARE ASSEMBLED.





**FIGURE 1**
PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTOR APPLICATION CHART
200 AMP LOADBREAK AND 600 AMP DEADBREAK

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SHEET
19 OF 28

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV 200 & 600 AMP CONNECTOR ASSEMBLIES
IDENTIFICATION CHART
PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTORS

UG4181.19

TABLE OF CONTENTS





**FIGURE 2**
PAD-MOUNTED 200/600 AMP
EQUIPMENT CONNECTIONS
200 AMP LOADBREAK

## TABLE 1

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | P73 | P75 | P83 | P85 | P93 | P95 |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | #2 AL<br>350 AL | 2/0 AL<br>350 AL | #2 AL<br>750 AL | 2/0 AL<br>750 AL | #2 AL<br>1000 AL | 2/0 AL<br>1000 AL |
| **MACRO UNITS** | CC-P73 | CC-P75 | CC-P83 | CC-P85 | CC-P93 | CC-P95 |

## BILL OF MATERIALS (FIGURE 2):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |





**FIGURE 3**
PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTIONS
200 AMP LOADBREAK

## TABLE 2

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | P7B | P7C | P8B | P8C | P9B | P9C |
| **200 AMP CABLE SIZE**<br>**600 AMP CABLE SIZE** | #2 AL<br>350 AL | 2/0 AL<br>350 AL | #2 AL<br>750 AL | 2/0 AL<br>750 AL | #2 AL<br>1000 AL | 2/0 AL<br>1000 AL |
| **MACRO UNITS** | CC-P7B | CC-P7C | CC-P8B | CC-P8C | CC-P9B | CC-P9C |

## BILL OF MATERIALS (FIGURE 3):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |





**FIGURE 4**
PAD-MOUNTED 200/600 AMP
EQUIPMENT CONNECTIONS
200 AMP LOADBREAK

**TABLE 3**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | P7O | P8O | P9O |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | CC-P70 | CC-P80 | CC-P90 |

**BILL OF MATERIALS (FIGURE 4):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |





**FIGURE 5**
PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTIONS
200 AMP LOADBREAK

**TABLE 4**

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | E3 | E5 |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC--E3 | CC--E5 |

**BILL OF MATERIALS (FIGURE 5):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |



TABLE OF CONTENTS








**FIGURE 6**
PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTIONS
200 AMP LOADBREAK

**TABLE 5**

| TYPICAL COMBINATIONS | | |
|---|---|---|
| **CODE** | EB | EC |
| **200 AMP CABLE SIZE** | #2 AL | 2/0 AL |
| **MACRO UNITS** | CC--EB | CC--EC |

**BILL OF MATERIALS (FIGURE 6):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |





**FIGURE 7**
PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTIONS
200 AMP LOADBREAK

**TABLE 6**

| TYPICAL COMBINATIONS | |
|---|---|
| **CODE** | EO |
| **MACRO UNITS** | CC--E0 |

**BILL OF MATERIALS (FIGURE 7):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | 200 AMP INSULATING | - | 1 | - | S204304 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

## INSTALLATION:

A. DO NOT "PIGGYBACK" 600 AMP TEES ON TOP OF EACH OTHER AT ANY TIME ON THE EQUIPMENT BUSHING.

B. THE 200 AMP/600 AMP LOADBREAK CONFIGURATIONS ON THESE PAGES ARE ONLY TO BE USED ON PAD-MOUNTED EQUIPMENT INSTALLATIONS

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

## NOTES:

I. **TABLE 7**

| CODES USED IN TABLES 1-6 (PAD-MOUNTED 200/600 AMP EQUIPMENT CONNECTOR) | |
|---|---|
| **CODE** | **TYPE** |
| **CABLE** | |
| 3 | #2 AL |
| 5 | 2/0 AL |
| 7 | 350 AL |
| 8 | 750 AL |
| 9 | 1000 AL |
| **COMPONENT** | |
| B | #2 AL FUSED ELBOW |
| C | 2/0 AL FUSED ELBOW |
| E | 600 AMP PAD-MOUNTED EQUIPMENT BUSHING EXTENSION |
| P | 600 AMP PAD-MOUNTED EQUIPMENT TEE |
| O | 200 AMP INSULATING RECEPTACLE |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE COMBINATIONS SHOWN.

## REFERENCE:

a. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4182, UG4190, UG4191 AND UG4192.

(b) FOR GROUNDING ELBOW KIT, REFER TO UG4179.1.

(c) FOR INFORMATION ON COLD SHRINK ELBOW TEE, REFER TO UG4189 (FUTURE).

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 200 AND 600 AMP CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION WORK ORDERS FOR SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH CONNECTIONS.

**ATTENTION:**

* THIS FIGURE SHOWS HOW 200 AMP AND 600 AMP CONNECTORS ARE ASSEMBLED.

** ALWAYS USE THE MANUFACTURERS RECOMMENDED TORQUE SETTINGS WHEN ASSEMBLING CONNECTORS.





**FIGURE 1**
SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH CONNECTOR APPLICATION CHART
200 AMP LOADBREAK AND 600 AMP DEADBREAK


© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |



TABLE OF CONTENTS

TABLE OF CONTENTS









**FIGURE 2**
SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH
200 AMP LOADBREAK CONNECTIONS

## TABLE 1

| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | T73 | T75 | T83 | T85 | T93 | T95 |
| **600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | 350 AL<br>#2 AL | 350 AL<br>2/0 AL | 750 AL<br>#2 AL | 750 AL<br>2/0 AL | 1000 AL<br>#2 AL | 1000 AL<br>2/0 AL |
| **MACRO UNITS** | CC--T73 | CC--T75 | CC--T83 | CC--T85 | CC--T93 | CC--T95 |

## BILL OF MATERIALS (FIGURE 2):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | LOADBREAK ELBOW CONNECTOR | #2 AL | 1 | - | S443838 | - |
| | | 2/0 AL | | - | S443840 | |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |








**FIGURE 3**
SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH
200 AMP LOADBREAK CONNECTIONS

## TABLE 2


| TYPICAL COMBINATIONS | | | | | | |
|---|---|---|---|---|---|---|
| **CODE** | 7B | 7C | 8B | 8C | 9B | 9C |
| **600 AMP CABLE SIZE**<br>**200 AMP CABLE SIZE** | 350 AL<br>#2 AL | 350 AL<br>2/0 AL | 750 AL<br>#2 AL | 750 AL<br>2/0 AL | 1000 AL<br>#2 AL | 1000 AL<br>2/0 AL |
| **MACRO UNITS** | CC--T7B | CC--T7C | CC--T8B | CC--T8C | CC--T9B | CC--T9C |

## BILL OF MATERIALS (FIGURE 3):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | FUSED ELBOW CONNECTOR | #2 AL | 1 | - | S443850 | - |
| | | 2/0 AL | | - | S443882 | |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |




**UG MAP SYMBOL**

600A


**FIGURE 4**
SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH
200 AMP LOADBREAK CONNECTIONS

**TABLE 3**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | T7O | T8O | T9O |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | CC-T70 | CC-T80 | CC-T90 |

**BILL OF MATERIALS (FIGURE 4):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |
| 4 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 1 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |




**UG MAP SYMBOL**

600A
600A

**FIGURE 5**
SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH
200 AMP LOADBREAK CONNECTIONS

**TABLE 4**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | TT7O | TT8O | TT9O |
| **600 AMP CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | C-TT70 | C-TT80 | C-TT90 |

**BILL OF MATERIALS (FIGURE 5):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 2 | DOUBLE ENDED CONNECTOR PLUG | - | 1 | - | S544832 | - |
| 3 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 4 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |
| 5 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | 2 | - | S471314 | P6ALR3 |
| | | 750 AND 1000 | | - | S471316 | P6ALR5 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |





**FIGURE 6**
SUBSURFACE/SURFACE OPERABLE ON-OFF SWITCH
200 AMP LOADBREAK CONNECTIONS

**TABLE 5**

| TYPICAL COMBINATIONS | |
|---|---|
| **CODE** | FO |
| **MACRO UNITS** | CC---FO |

## BILL OF MATERIALS (FIGURE 6):

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | BUSHING EXTENSION | - | 1 | - | S336204 | - |
| 2 | ELBOW TAP PLUG | - | 1 | - | S547328 | - |
| 3 | 200 AMP INSULATING RECEPTACLE | - | 1 | - | S204304 | - |

## INSTALLATION:

A. "PIGGYBACK" TEES SHOWN IN THIS STANDARD SHALL ONLY BE USED TO FEED A SWITCH TIE POSITION.

B. DO NOT INSTALL LOADBREAK ELBOWS ON SWITCHES INSTALLED IN MANHOLES.

C. DO NOT INSTALL LOADBREAK ELBOWS ON "PIGGYBACK" TEES.

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

## NOTES:

I. **TABLE 6**

| CODES USED IN TABLES 1-5 | |
|---|---|
| **CODE** | **TYPE** |
| **CABLE** | |
| 3 | #2 AL |
| 5 | 2/0 AL |
| 7 | 350 AL |
| 8 | 750 AL |
| 9 | 1000 AL |
| **COMPONENT** | |
| B | #2 AL FUSED ELBOW |
| C | 2/0 AL FUSED ELBOW |
| T | 600 AMP SUBSURFACE/SURFACE OPERABLE TEE |
| F | 600 AMP SUBSURFACE/SURFACE OPERABLE SWITCH BUSHING EXTENSION |

II. OTHER COMBINATIONS MAY BE CODED USING THE ABOVE CODES FOR THE SAME TYPE COMBINATIONS SHOWN.

## REFERENCE:

a. FOR SPECIFICATIONS AND INSTALLATION INSTRUCTIONS, REFER TO UG4182, UG4190, UG4191 AND UG4192.

(b) FOR GROUNDING ELBOW KIT, REFER TO UG4179.1.

(c) FOR INFORMATION ON COLD SHRINK ELBOW TEE, REFER TO UG4189 (FUTURE).

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |













TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 600 AMP SPLICE AND CONNECTOR ASSEMBLIES ON ELECTRIC CONSTRUCTION ORDERS.

**TABLE 1**

**PARTS IDENTIFICATION CHART**

| PART | WIRE SIZE | STOCK NUMBER | DESIGN UNITS | PART | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
|  COLD SHRINK ELBOW TEE (a) | 4/0, 350 AND 500 | S326572 | 600AT |  INSULATED PLUG W/TEST POINT | S544848 | PLUG-F |
| | 750 AND 1000 | S326574 | 600ATL |  600/200 AMP TAP PLUG | S547324 | TAP-FE |
|  EXTENSION SPLICE | 350 AL | S668434 | SS-350 |  DOUBLE-ENDED CONNECTOR PLUG | S544832 | PLUG-C |
| | 750 AL | S668436 | SS-750 | | | |
| | 750 AL COMP | S668442 | SS750C |  600/200 AMP REDUCING TAP WELL | S719600 | REDTAP |
| | 750 AL-750 AL COMP | S668444 | SS750B | FMO | | |
| | 1000 AL | S668438 | SS1000 | | | |
| | #4/0 CU | S668430 | SS-4/0 | | | |
| | 500 CU | S668432 | SS-500 |  ELBOW TAP PLUG | S547328 | ETP650 |
| | 1000 KCML CU ONLY | S668460 | SS1KCU | | | |
|  CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | S471314 | P6ALR3 |  200 AMP LOADBREAK BUSHING PLUG | S544676 | BSHPLG |
| | 750 AND 1000 | S471316 | P6ALR5 | | | |
|   INSULATING RECEPTACLE WITH TEST POINT | - | S570608 | IN-REC |  STUD | S701100 | STUD |
| | | | |  BUSHING EXTENSION AND STUD | S336204 | BUSH-X |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) FOR INFORMATION ON COLD SHRINK ELBOW TEE, REFER TO UG4189 (FUTURE).

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 07/24/2012 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | REVISION | - | - | - | TR/MJC | 11/14/2011 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |
| A | REVISION | - | - | - | TR/MJC | 11/08/2011 | D | REVISION | - | - | - | TR/MJC | 10/30/2012 |

**SCOPE:** THIS STANDARD SHOWS 600A CONNECTORS AND ACCESSORIES USED TO TERMINATE 12KV, 200 AND 600A CABLES.

**ATTENTION:**

* ALWAYS USE THE MANUFACTURERS RECOMMENDED TORQUE SETTINGS WHEN ASSEMBLING CONNECTORS.

**TABLE 1**

**PART IDENTIFICATION CHART**






| PART | MAJOR USE | SERIES | WIRE SIZE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
|  ELBOW TEE | ELBOW-TEE FOR SPLICING AND 600/200A TAPS | 650 | -- | S326578 | ELBO-T |
|  BUSHING EXTENSION | **ON SUBSURFACE SWITCH**: USED IN CENTER POSITION FOR ADDITIONAL CABLE TRAINING OR FOR THE INSTALLATION OF 200A DEADBREAK ELBOWS WHERE 600A TEES ARE NOT INSTALLED<br><br>**ON PAD MOUNTED SWITCH:** USED FOR THE INSTALLATION OF 200A LOADBREAK ELBOWS OR INSULATING RECEPTACLES WHERE 600A TEES ARE NOT INSTALLED | -- | -- | S336204 | BUSH-X |
|  CABLE ADAPTER | TO ADAPT CABLE TO ELBOW-TEE | 650 | 4/0 CU | S102026 | ADP4/0 |
| | | | 2/0 AL | S103088 | TBD |
| | | | 350 AL | S102027 | ADP350 |
| | | | 500 CU | S102028 | ADP500 |
| | | | 750 COMP AL | S102051 | AD750C |
| | | | 750 AL | S102034 | ADO750 |
| | | 1000 | 1000 AL | S102050 | AD1MIL |
|  SPANNER WRENCH | TOOL USED FOR TIGHTENING ELBOW-TEE COMPONENT PARTS | -- | -- | S818616 | -- |
|  INSULATED PLUG W/ TEXT POINT | FOR DEADENDING END OF ELBOW-TEE | -- | -- | S544848 | PLUG-F |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 07/24/2012 | E | FIGURE UPDATE | GLC | EJA | GLW | KRG | 01/09/2023 |
| A | REVISION | - | - | - | RSW/VCR | 01/01/2000 | D | TABLE UPDATE | EDM | EJA | GLW | KRG | 06/29/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV, 600/200A SPLICES, CONNECTORS AND ACCESSORIES

UG4182.1

## TABLE 1 (CONT'D)







| PART IDENTIFICATION CHART | | | | | |
|---|---|---|---|---|---|
| **PART** | **MAJOR USE** | **SERIES** | **WIRE SIZE** | **STOCK NUMBER** | **DESIGN UNITS** |
|  DOUBLE-ENDED CONNECTOR PLUG | USED FOR MULTIPLE ELBOW-TEE SPLICE | -- | -- | S544832 | PLUG-C |
|   INSULATING RECEPTACLE WITH TEST POINT (NOT TO BE OPERATED ENERGIZED) | INSULATES, SHIELDS AND WATERSEALS OPEN 600A BUSHINGS | -- | -- | S570608 | IN-REC |
|  600/200A TAP PLUG | FEMALE END USE TO ATTACH TO ELBOW-TEE OR BUSHING EXTENSION AND CONNECT 200A DEADBREAK ELBOW | -- | -- | S547324 | TAP-FE |
|  ELBOW TAP PLUG | | -- | -- | S547328 | ETP650 |
|  1/2" DRIVE X 3/8" HEX WRENCH | | -- | -- | S818726 | -- |
|  STUD | | -- | -- | S701100 | STUD |

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 07/24/2012 | E | FIGURE UPDATE | GLC | EJA | GLW | KRG | 01/09/2023 |
| A | REVISION | - | - | - | RSW/VCR | 01/01/2000 | D | TABLE UPDATE | EDM | EJA | GLW | KRG | 06/29/2022 |

## TABLE 2

| SPADE COMPRESSION CONNECTOR | | | | | | | |
|---|---|---|---|---|---|---|---|
| FIGURE | CONNECTOR | | | DIE INDEX | TOOL AND DIE | | |
| | WIRE SIZE | STOCK NO. | DESIGN UNITS | | Y35 | Y45 | Y46 |
|  | 4/0 | S258694 (X) | -- | 299 COOPER/RTE | U31ART | U31ART W/6515 ADAPTER | U31ART W/PU-ADP ADAPTER |
| | | | | 298 ELASTIMOLD | U28ART | U28ART W/6515 ADAPTER | U28ART W/PU-ADP ADAPTER |
| | 2/0 AL | S471318 | TBD | -- | -- | -- | -- |
| | 350 AL | S258698 | SPD350 | 299 | U31ART | U31ART W/6515 ADAPTER | U31ART W/PU-ADP ADAPTER |
| | 500 CU | S258700 | SPD500 | 300 | U34ART | U34ART W/6515 ADAPTER | U34ART W/PU-ADP ADAPTER |
| | 750 COMP AL | S258708 | SP750C | | | | |
| | 750 AL | S258704 | SPD750 | 301 | -- | S39ART | P39ART |
| | 1000 AL | S258702 | SP1000 | 302 | -- | S44ART | P44ART |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) SUPPLIED WITH A STUD. IF STUD IS NOT REQUIRED IN ASSEMBLY, SUCH AS ON SWITCH TERMINATIONS, DO NOT THROW AWAY. RETURN TO STOREROOM.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS


© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 07/24/2012 | E | FIGURE UPDATE | GLC | EJA | GLW | KRG | 01/09/2023 |
| A | REVISION | - | - | - | RSW/VCR | 01/01/2000 | D | TABLE UPDATE | EDM | EJA | GLW | KRG | 06/29/2022 |

**SCOPE:** THIS STANDARD SHOWS THE VAULT STRETCHER. THIS IS A 600-AMP DEAD BREAK CONNECTION USED ON FEEDER CABLE. THE VAULT STRETCHER IS A SPACE SAVING CONNECTION FOR NEW AND EXISTING CONSTRUCTION WHEN SPACE IS LIMITED.

**ATTENTION:**

* THREE TEE COMBINATIONS SHOWN IN THIS STANDARD SHALL ONLY BE USED TO FEED A SWITCH TIE POSITION..




| DESIGN UNITS (DU) |
|---|
| VS |

**FIGURE 1**
VAULT STRETCHER ASSEMBLY (A)(I)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 7/24/2012 | E | | | | | | |
| A | REVISION | - | - | - | TR/MJC | 11/8/2011 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

VAULT STRETCHER CONNECTOR, DEADBREAK

UG4184.1

TABLE OF CONTENTS





**FIGURE 2**
VAULT AND MANHOLE INSTALLATION ONLY
VAULT & SUBSURFACE CONNECTIONS
600 AMP DEADBREAK

**UG MAP SYMBOL**





**TABLE 1**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | VS777 | VS888 | VS999 |

**BILL OF MATERIALS (FIGURE 2):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | VAULT STRETCHER | - | 1 | S790456 | - |
| 2 | INSULATED PLUG W/ TEST POINT | - | 2 | S544848 | - |
| 3 | CONDUCTOR CONNECTOR | (350 AL) | 3 | S258698 | - |
| | | (750 AL) | | S258704 | - |
| | | (750C AL) | | S258708 | - |
| | | (1000 AL) | | S258702 | - |
| 4 | CABLE ADAPTER | (350 AL) | 3 | S102027 | - |
| | | (750 AL) | | S102034 | - |
| | | (750C AL) | | S102051 | - |
| | | (1000 AL/CU) | | S102050 | - |
| 5 | ELBOW TEE | - | 1 | S326578 | - |
| 6 | DOUBLE ENDED CONNECTOR PLUG | - | 1 | S544832 | - |





**FIGURE 3**
VAULT AND MANHOLE INSTALLATION ONLY
VAULT & SUBSURFACE CONNECTIONS
600 AMP DEADBREAK

**UG MAP SYMBOL**





**TABLE 2**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | VS773 | VS883 | VS993 |
| | VS775 | VS885 | VS995 |

**BILL OF MATERIALS (FIGURE 3):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | VAULT STRETCHER | - | 1 | S790456 | - |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | S544848 | - |
| 3 | CONDUCTOR CONNECTOR | (350 AL) | 2 | S258698 | - |
| | | (750 AL) | | S258704 | - |
| | | (750C AL) | | S258708 | - |
| | | (1000 AL) | | S258702 | - |
| 4 | CABLE ADAPTER | (350 AL) | 2 | S102027 | - |
| | | (750 AL) | | S102034 | - |
| | | (750C AL) | | S102051 | - |
| | | (1000 AL/CU) | | S102050 | - |
| 5 | 600/200 AMP TAP PLUG | - | 1 | S547324 | - |
| 6 | DEADBREAK ELBOW CONNECTOR | (#2 AL) | 1 | S443842 | - |
| | | (2/0 AL) | | S443844 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 7/24/2012 | E | | | | | | |
| A | REVISION | - | - | - | TR/MJC | 11/8/2011 | D | | | | | | |



TABLE OF CONTENTS





**FIGURE 4**
VAULT AND MANHOLE INSTALLATION ONLY
VAULT & SUBSURFACE CONNECTIONS
600 AMP DEADBREAK

**UG MAP SYMBOL**




3 - VS

**TABLE 3**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | VS77 | VS88 | VS99 |

**BILL OF MATERIALS (FIGURE 4):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | VAULT STRETCHER | - | 1 | S790456 | - |
| 2 | INSULATED PLUG W/ TEST POINT | - | 2 | S544848 | - |
| 3 | CONDUCTOR CONNECTOR | (350 AL) | 2 | S258698 | - |
| | | (750 AL) | | S258704 | - |
| | | (750C AL) | | S258708 | - |
| | | (1000 AL/CU) | | S258702 | - |
| 4 | CABLE ADAPTER | (350 AL) | 2 | S102027 | - |
| | | (750 AL) | | S102034 | - |
| | | (750C AL) | | S102051 | - |
| | | (1000 AL/CU) | | S102050 | - |





**FIGURE 5**
VAULT AND MANHOLE INSTALLATION ONLY
VAULT & SUBSURFACE CONNECTIONS
600 AMP DEADBREAK

**UG MAP SYMBOL**




3 - VS

**TABLE 4**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CABLE SIZE** | 350 AL | 750 AL | 1000 AL |
| **MACRO UNITS** | VS770 | VS880 | VS990 |

**BILL OF MATERIALS (FIGURE 5):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | VAULT STRETCHER | - | 1 | S790456 | - |
| 2 | INSULATED PLUG W/ TEST POINT | - | 1 | S544848 | - |
| 3 | CONDUCTOR CONNECTOR | (350 AL) | 2 | S258698 | - |
| | | (750 AL) | | S258704 | - |
| | | (750C AL) | | S258708 | - |
| | | (1000 AL/CU) | | S258702 | - |
| 4 | CABLE ADAPTER | (350 AL) | 2 | S102027 | - |
| | | (750 AL) | | S102034 | - |
| | | (750C AL) | | S102051 | - |
| | | (1000 AL/CU) | | S102050 | - |
| 5 | ELBOW TAP PLUG | - | 1 | S547328 | - |
| 6 | 200 AMP INSULATING RECEPTACLE | - | 1 | S204304 | - |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 7/24/2012 | E | | | | | | |
| A | REVISION | - | - | - | TR/MJC | 11/8/2011 | D | | | | | | |

## TABLE 5

| CODES USED IN TABLES 1-4 | |
|---|---|
| **CABLE** | |
| **CODE** | **TYPE** |
| 3 | #2 AL |
| 5 | 2/0 AL |
| 7 | 350 AL |
| 8 | 750 AL |
| 9 | 1000 AL |
| **COMPONENT** | |
| 0 | 200 AMP INSULATING RECEPTACLE |

## INSTALLATION:

(A) FOLLOW MANUFACTURERS MAKE UP INSTRUCTIONS FOR INSTALLATION. THE LONGER LUG SUPPLIED WITH THE VAULT STRETCHERS IS SPECIFICALLY DESIGNED FOR THIS EQUIPMENT ONLY AND SHALL NOT BE USED FOR ANY OTHER APPLICATION.

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

## NOTES:

(I) **MAJOR USE:**

a. NEW & RE-CABLING IN VAULTS AND MANHOLES WITH MULTIPLE CIRCUITS WHEN FEEDER CABLE REQUIRES CONNECTIONS.

b. LOAD TAP INSTALLATIONS WITH LIMITED SPACE, CAN BE INSTALLED WHERE A FUTURE DISTRIBUTION TAP MAY BE REQUIRED.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 7/24/2012 | E | | | | | | |
| A | REVISION | - | - | - | TR/MJC | 11/8/2011 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS 600 AMP EXTENSION SPLICES FOR USE ON FEEDER CABLES.

**CAUTION:**

* THE SILICONE GREASE PROVIDED WITH THESE SPLICES IS INTENDED FOR USE WITH SPLICES ONLY AND MUST NOT BE USED WITH ANY OTHER SEPARABLE CONNECTOR PRODUCTS SUCH AS LOADBREAK ELBOWS, ETC.





**FIGURE 1**

**UG MAP SYMBOL**





**TABLE 1**

| SPLICE LENGTH | |
|---|---|
| CONDUCTOR SIZE | Z (IN) SPLICE LENGTH |
| 350 | 14 |
| 750 | 15 |
| 1000 | 15 3/4 |

**TABLE 2**

| EXTENSION SPLICE | | | |
|---|---|---|---|
| CONDUCTOR | INSTALLING DIE | STOCK NUMBER | DESIGN UNITS |
| 350 KCMIL AL | U31ART/299 | S668434 | SS-350 |
| 350 AL - 4/0 CU | | S668500 | SS-3540 |
| 750 KCMIL AL | P39ART/301 | S668436 | SS-750 |
| 750 KCMIL AL COMP (Ia) | | S668442 | SS750C |
| 750 AL-750-AL COMP | | S668444 | SS750B |
| 1000 KCMIL AL (Ia) | P40ART/474 | S668438 | SS1000 |
| #4/0 CU | U28RT/15 | S668430 | SS-4/0 |
| 500 KCMIL CU | U34RT/20 | S668432 | SS-500 |
| 750 KCMIL CU COMP | U36RT | S668464 | SS75CU |
| 750 CU COMP-1000 CU | U36RT & 44RT | S668466 | SS71CU |
| 750 CU COMP-1000 AL | P44ART/302 | S668470 | SS71CA |
| 1000 KCMIL CU ONLY | P44RT/27 | S668460 | SS1KCU |

TABLE OF CONTENTS

**INSTALLATION:**

A. FOR EXTENSION SPLICE INSTALLATION PROCEDURE, CONSULT INDIVIDUAL MANUFACTURER'S CURRENT INSTRUCTIONS.

B. DO NOT INSTALL WHERE A FUTURE DISTRIBUTION TAP IS LIKELY TO BE REQUIRED.

**BILL OF MATERIALS:** NONE

**NOTES:**

I. SPLICE IS COMPLETELY SEALED AND MAY BE INSTALLED IN SUBSURFACE EQUIPMENT.

(a) THIS SPLICE CAN CONNECT ALUMINUM TO COPPER CONDUCTORS.

II. MAJOR USE:

a. RELOCATION OF EQUIPMENT WITHIN A SUBSTRUCTURE.

b. RELOCATION OF SWITCH FROM MANHOLE TO PAD-MOUNT.

c. REPLACEMENT OF EXOTHERMIC (CADWELD) SPLICES.

d. SPLICING OF SUBSTATION GETAWAY AND EXPRESS RUNS FOR LOCATIONS WITHIN A SUBSTRUCTURE WHERE LOCAL DISTRIBUTION TAP WILL NOT BE REQUIRED.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | -- | -- | 06/02/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | -- | JS | JS | CZH | 06/01/2018 | E | | | | | | |
| A | TABLE UPDATE | -- | JS | TR | MDJ | 10/31/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

600 AMP EXTENSION SPLICE

UG4185.1

**SCOPE:** THIS STANDARD SHOWS THE CONNECTIONS AND ASSEMBLY CODES USED FOR CALLING OUT 600 AMP TO 200 AMP JUNCTION ASSEMBLIES.

**ATTENTION:**

* SURFACE CONNECTOR APPLICATION CHART 600 AMP TO 200 AMP DEAD FRONT TERMINATOR.

** THIS CHART SHOWS HOW 600A AND 200A CONNECTORS ARE ASSEMBLED TO FORM SOME OF THE COMBINATIONS SHOWN ON SHEET 2.





**FIGURE 1**
600 AMP TO 200 AMP JUNCTION
ASSEMBLY CHART

**BILL OF MATERIALS (FIGURE 1):**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | JUNCTION | 1 | - | S439860 | JUN6/2 |
| 2 | SPACER PLATE | 1 | - | - | - |
| 3 | MOUNTING STRAPS | 4 | - | - | - |
| 4 | FASTENERS | 8 | - | - | - |

**TABLE 1**

| CODES USED IN TABLES ON SHEETS 2 & 3 | | | |
|---|---|---|---|
| **CODE** | **TYPE** | **CODE** | **TYPE** |
| **CABLE** | | **COMPONENTS** | |
| 3 | #2 AL | B | #2 AL FUSED ELBOW |
| 5 | 2/0 AL | C | 2/0 AL FUSED ELBOW |
| 7 | 350 AL | H | 600A INSULATING RECEPTACLE |
| 8 | 750C AL | O | 200A INSULATING RECEPTACLE |
| 9 | 1000 AL | - | - |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 11/8/2011 | E | | | | | | |
| A | REVISION | - | - | - | RSW/CAK | 1/1/2000 | D | UPDATED BILL OF MATERIALS | ARC | EJA | MBL | KRG | 09/07/2022 |



TABLE OF CONTENTS





**FIGURE 2**
600 AMP JUNCTION ASSEMBLY

**UG MAP SYMBOL**





**TABLE 2**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | 7HOOO | 8HOOO | 9HOOO |
| **CABLE SIZE** | 350 AL | 750C AL | 1000 AL |
| **MACRO UNITS** | J7H000 | J8H000 | J9H000 |

**BILL OF MATERIALS (FIGURE 2):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | JUNCTION, 600A - 200A | - | 1 | - | S439860 | JUN6/2 |
| 2 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 3 | RECEPTACLE, INSULATING, 600A | - | 1 | - | S570608 | - |
| 4 | CONNECTOR, CONDUCTOR (III) | 350 AL | 1 | - | S258698 | - |
| | | 750C AL | | | S258708 | - |
| | | 1000 AL | | | S258702 | - |
| 5 | ADAPTER, CABLE (III) | 350 AL | 1 | - | S102027 | - |
| | | 750C AL | | | S102051 | - |
| | | 1000 AL | | | S102050 | - |
| 6 | STUD (III) | - | 1 | - | S701100 | - |
| 7 | PLUG, BUSHING, LOADBREAK | - | 3 | - | S544676 | - |
| 8 | RECEPTACLE, INSULATING, 200A | - | 3 | - | S204304 | - |
| 9 | TAG, "DO NOT OPERATE ENERGIZED" | - | 1 | - | S647966 | - |





**FIGURE 3**
600 AMP TO 200 AMP JUNCTION ASSEMBLY

**UG MAP SYMBOL**





**TABLE 3**

| ADDITIONAL MACRO UNITS | | |
|---|---|---|
| J7H330 | J8H330 | J9H330 |
| J7H550 | J8H550 | J9H550 |
| J7HBB0 | J8HBB0 | J9HBB0 |
| J7HCC0 | J8HCC0 | J9HCC0 |

**TABLE 4**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | 7H35O | 8H35O | 9H35O |
| **CABLE SIZE** | 350 AL | 750C AL | 1000 AL |
| **MACRO UNITS** | J7H350 | J8H350 | J9H350 |

**BILL OF MATERIALS (FIGURE 3):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | JUNCTION, 600A - 200A | - | 1 | - | S439860 | JUN6/2 |
| 2 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 1 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 3 | RECEPTACLE, INSULATING, 600A | - | 1 | - | S570608 | - |
| 4 | CONNECTOR, CONDUCTOR (III) | 350 AL | 1 | - | S258698 | - |
| | | 750C AL | | | S258708 | - |
| | | 1000 AL | | | S258702 | - |
| 5 | ADAPTER, CABLE (III) | 350 AL | 1 | - | S102027 | - |
| | | 750C AL | | | S102051 | - |
| | | 1000 AL | | | S102050 | - |
| 6 | STUD (III) | - | 1 | - | S701100 | - |
| 7 | PLUG, BUSHING, LOADBREAK | - | 3 | - | S544676 | - |
| 8 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 2 | - | S443838 | - |
| | | 2/0 AL | | | S443840 | - |
| 9 | CONNECTOR, ELBOW, FUSED | #2 AL | 2 | - | S443850 | - |
| | | 2/0 AL | | | S443882 | - |
| 10 | RECEPTACLE, INSULATING, 200A | - | 3 | - | S204304 | - |
| 11 | TAG, "DO NOT OPERATE ENERGIZED" | - | 1 | - | S647966 | - |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 11/8/2011 | E | | | | | | |
| A | REVISION | - | - | - | RSW/CAK | 1/1/2000 | D | UPDATED BILL OF MATERIALS | ARC | EJA | MBL | KRG | 09/07/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

600 AMP TO 200 AMP JUNCTION ASSEMBLY CHART

UG4186.2





**FIGURE 4**
600 AMP - 200 AMP JUNCTION ASSEMBLY

**UG MAP SYMBOL**





**TABLE 5**

| ADDITIONAL MACRO UNITS | | |
|---|---|---|
| J78000 | J79000 | J89000 |

**TABLE 6**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | 77OOO | 88OOO | 99OOO |
| **CABLE SIZE** | 350 AL | 750C AL | 1000 AL |
| **MACRO UNITS** | J77000 | J88000 | J99000 |

**BILL OF MATERIALS (FIGURE 4):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | JUNCTION, 600A - 200A | - | 1 | - | S439860 | JUN6/2 |
| 2 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 3 | CONNECTOR, CONDUCTOR (III) | 350 AL | 2 | - | S258698 | - |
| | | 750C AL | | | S258708 | - |
| | | 1000 AL | | | S258702 | - |
| 4 | ADAPTER, CABLE (III) | 350 AL | 2 | - | S102027 | - |
| | | 750C AL | | | S102051 | - |
| | | 1000 AL | | | S102050 | - |
| 5 | PLUG, BUSHING, LOADBREAK | - | 3 | - | S544676 | - |
| 6 | RECEPTACLE, INSULATING, 200A | - | 3 | - | S204304 | - |





**FIGURE 5**
600 AMP - 200 AMP JUNCTION ASSEMBLY

**UG MAP SYMBOL**





**TABLE 7**

| ADDITIONAL MACRO UNITS | | |
|---|---|---|
| J78350 | J79350 | J89350 |
| J77330 | J88330 | J99330 |
| J77550 | J88550 | J99550 |
| J77BB0 | J88BB0 | J99BB0 |
| J77CC0 | J88CC0 | J99CC0 |
| J77BBB | J88BBB | J99BBB |

**TABLE 8**

| TYPICAL COMBINATIONS | | | |
|---|---|---|---|
| **CODE** | 7735O | 8835O | 9935O |
| **CABLE SIZE** | 350 AL | 750C AL | 1000 AL |
| **MACRO UNITS** | J77350 | J88350 | J99350 |

**BILL OF MATERIALS (FIGURE 5):**

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | JUNCTION, 600A - 200A | - | 1 | - | S439860 | JUN6/2 |
| 2 | COLD SHRINK ELBOW TEE | 4/0, 350 AND 500 | 2 | - | S326572 | 600AT |
| | | 750 AND 1000 | | - | S326574 | 600ATL |
| 3 | CONNECTOR, CONDUCTOR (III) | 350 AL | 2 | - | S258698 | - |
| | | 750C AL | | | S258708 | - |
| | | 1000 AL | | | S258702 | - |
| 4 | ADAPTER, CABLE (III) | 350 AL | 2 | - | S102027 | - |
| | | 750C AL | | | S102051 | - |
| | | 1000 AL | | | S102050 | - |
| 5 | PLUG, BUSHING, LOADBREAK | - | 3 | - | S544676 | - |
| 6 | RECEPTACLE, INSULATING, 200A | - | 1 | - | S204304 | - |
| 7 | CONNECTOR, ELBOW, LOADBREAK | #2 AL | 2 | - | S443838 | - |
| | | 2/0 AL | | | S443840 | - |
| 8 | CONNECTOR, ELBOW, FUSED | #2 AL | 2 | - | S443850 | - |
| | | 2/0 AL | | | S443882 | - |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 11/8/2011 | E | | | | | | |
| A | REVISION | - | - | - | RSW/CAK | 1/1/2000 | D | UPDATED BILL OF MATERIALS | ARC | EJA | MBL | KRG | 09/07/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 3 OF 4

600 AMP TO 200 AMP JUNCTION ASSEMBLY CHART

UG4186.3

TABLE OF CONTENTS

**INSTALLATION:** NONE

**BILL OF MATERIALS:** INDIVIDUALLY INCLUDED WITH FIGURES

**NOTES:**

I. JUNCTION SHIPPED WITH SPACER PLATE, MOUNTING STRAPS AND FASTENERS.

(II) STUD NOT SUPPLIED WITH JUNCTION.

(III) ITEM NOT SHOWN IN FIGURE.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | TR/MJC | 11/8/2011 | E | | | | | | |
| A | REVISION | - | - | - | RSW/CAK | 1/1/2000 | D | UPDATED BILL OF MATERIALS | ARC | EJA | MBL | KRG | 09/07/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 4 OF 4

600 AMP TO 200 AMP JUNCTION ASSEMBLY CHART

UG4186.4

**SCOPE:** THIS STANDARD SHOWS THE CAM LINK. OPERABLE DEADBREAK CONNECTOR SYSTEM.





**FIGURE 1**




**FIGURE 2**

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | RJW/VCR | 11/30/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

CAM LINK OPERABLE 600 AMP CONNECTOR

UG4187.1

## INSTALLATION:

A. THE CAM LINK IS TO BE INSTALLED ON THE NON-SWITCHED SIDE OF THE PME-3 SCADA SWITCH.

B. THE CAM LINK SHALL ALSO BE INSTALLED ON ALL SIX POSITIONS OF THE PAD-MOUNTED SERVICE RESTORER.

C. FOLLOW THE MANUFACTURERS INSTALLATION INSTRUCTIONS.

(D) SECURE THE HOTSTICK EYE TO THE 600 AMP ELBOW TEE WITH LARGE CABLE TIE STRAP.

(E) ATTACH A "DO NOT OPERATE ENERGIZED" TAG TO THE HOT STICK EYE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | ADAPTER, CABLE | 1 | - | COMPLETE KIT S270240 | C-LINK |
| 2 | TEE, ELBOW | 1 | - | | |
| 3 | CONNECTOR, CONDUCTOR (V) | 1 | - | | |
| 4 | CLAMP, ELBOW | 1 | - | | |
| 5 | BRACKET, ALIGNMENT | 1 | - | | |
| 6 | PLUG, STAND OFF (V) | 1 | - | | |
| 7 | CLAMP, BUSHING EXTENSION | 1 | - | | |
| 8 | HEX BOLT, NUT AND WASHER | 4 | - | | |
| 9 | EXTENSION, BUSHING | 1 | - | | |
| 10 | CONTACT, RETAINER | 1 | - | | |
| 11 | LINK | 1 | - | | |
| 12 | EYE, HOT STICK | 1 | - | | |
| 13 | VISIBLE LINK (III) | 1 | - | S270242 | V-LINK |
| 14 | CABLE TIE, LARGE | 1 | - | S738440 | - |
| 15 | TAG, DO NOT OPERATE ENERGIZED | 1 | - | S647966 | - |
| 16 | RECEPTACLE, INSULATING, 200A | 3 | - | S204304 | - |

TABLE OF CONTENTS

## NOTES:

I. ONE KIT CONTAINS ENOUGH MATERIAL TO CONNECT ONE 1000 KCM PHASE TO THE APPARATUS. FOR SMALLER CONDUCTORS ORDER CABLE ADAPTERS AND COMPRESSION CONNECTORS SEPARATELY.

II. THE DU "C-LINK" ORDERS 3 KITS OR ENOUGH MATERIAL TO CONNECT THREE-PHASES.

(III) THE VISIBLE LINK IS NOT INCLUDED IN KIT AND IS ORDERED SEPARATELY.

IV. THE DU "V-LINK" ORDERS 3 VISIBLE LINKS.

(V) ITEM NOT SHOWN ON THE FIGURES.

## REFERENCE:

a. REFERENCE UG4525 CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PRE-MOLDED CONNECTORS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/02/2020 | E | | | | | | |
| A | REVISION | - | - | - | RJW/VCR | 11/30/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CAM LINK OPERABLE 600 AMP CONNECTOR

UG4187.2

**SCOPE:** THIS STANDARD SHOWS THE 600 AMP TEE EXTENSION.





**FIGURE 1**

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | -- | -- | 06/02/2020 | E | | | | | | |
| A | REVIEW | -- | -- | -- | TR/DW | 4/23/2013 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |
| SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS | | | | |
| SHEET 1 OF 3 | 600A T EXTENSION | | | UG4188.1 |

TABLE OF CONTENTS



**FIGURE 2**





**FIGURE 3**

**TABLE 1**

| TEE EXTENSION KITS | | | |
|---|---|---|---|
| **CABLE** | **KIT** | **STOCK NUMBER** | **DESIGN UNIT** |
| 1000KCMIL PEJ-XLPE | K656RLR-N0410 | S445216 | TEX100 |
| 750KCMIL PEJ-XLPE | K656RLR-L0380 | S445214 | TEX750 |
| 750 KCMIL PEJ-XLPE COMPACT | K656RLR-L0360 | S445212 | TEX75C |
| 350KCMIL PEJ-XLPE | K656RLR-J0300 | S445210 | TEX350 |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | -- | -- | 06/02/2020 | E | | | | | | |
| A | REVIEW | -- | -- | -- | TR/DW | 4/23/2013 | D | | | | | | |

## INSTALLATION:

A. FOLLOW MANUFACTURER'S INSTRUCTIONS TO RE-TERMINATE CABLE AND TEE CONNECTIONS.

B. KEEP COMPONENTS CLEAN WHEN ASSEMBLING TEE EXTENSION.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | INSULATING END CAP & BIP (BASIC INSULATING PLUG) | AS REQ'D | -- | SUPPLIED IN KIT (REFERENCE TABLE 1) | SUPPLIED IN KIT (REFERENCE TABLE 1) |
| 2 | STUD, 1/2" | | -- | | |
| 3 | TEE, ELBOW WITH TEST POINT | | -- | | |
| 4 | ADAPTER, ONE INCH | | -- | | |
| 5 | BOLT, STAINLESS STEEL, 1/2" | | -- | | |
| 6 | WASHER, FLAT, STAINLESS STEEL, 1 /2" | | -- | | |
| 7 | WASHER, BELLEVILLE, 1 /2" | | -- | | |
| 8 | LUG, COMPRESSION | | -- | | |
| 9 | RING, RETAINING, SUPPLIED IN KIT | | -- | | |
| 10 | ADAPTER, CABLE | | -- | | |
| 11 | EXTENSION HOUSING | | -- | | |
| 12 | CONDUCTOR | | -- | | |
| 13 | SEMI CON | | -- | | |
| 14 | CONCENTRIC NEUTRAL | | -- | | |
| 15 | JACKET, CABLE | | -- | | |
| 16 | ROD, VENTING | | -- | | |
| 17 | PLUG, END, ETP650 | AS REQ'D | -- | S547328 | -- |
| 18 | CAP, INSULATING | AS REQ'D | -- | S204304 | -- |

## NOTES:

I. THE ELASTIMOLD TEE EXTENSION 600 AMP CONNECTOR IS DESIGNED TO PROVIDE ADDITIONAL LENGTH WHEN CABLE OR CONVENTIONAL ELBOWS DO NOT REACH. WHEN CABLE IS RE-TERMINATED A TEE EXTENSION CAN PROVIDE 13" OF ADDITIONAL LENGTH.

II. THIS CONNECTION CAN BE USED FOR SWITCH REPLACEMENTS, REMOVAL OF ON/OFF SWITCHES, REPAIRING FAILED TEE CONNECTIONS AND ANY TIME ADDITIONAL LENGTH IS NECESSARY.

III. ELASTIMOLD TEE EXTENSION SPECIFICATIONS:

a. 15KV CLASS

b. 8.3KV PHASE TO GROUND

c. 14.4KV MAXIMUM PHASE TO PHASE

d. 95KV BIL

(IV) 600 RRT TOOL SUPPLIED BY STANDARDS

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | -- | -- | 06/02/2020 | E | | | | | | |
| A | REVIEW | -- | -- | -- | TR/DW | 4/23/2013 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

600A T EXTENSION

UG4188.3

**SCOPE:** THIS STANDARD SHOWS 200 AMP 14KV LOADBREAK ELBOW CONNECTOR (LOADBREAK AT 12KV, 6.9 KV, 4.16KV AND 2.4KV) USED ON SUBSURFACE, PAD-MOUNTED TRANSFORMERS AND SECTIONALIZING EQUIPMENTS.





**FIGURE 1**

**TABLE 1**

| ITEM | SPARE PARTS | STOCK NUMBER |
|---|---|---|
| 1 | MALE CONTACT | S444434 |
| 2 | 2 SOL AL COMPRESSION TERMINAL | S730200 |
| | 2/0 AL COMPRESSION TERMINAL | S730210 |
| - | SILICON GREASE | S391424 |

**TABLE 2**

| RATINGS | |
|---|---|
| KV | 14.0 |
| AMPERES | 200 |
| KV-BIL | 95 |
| LOAD BREAK OR LOAD MAKE-10 OPERATIONS | 200 AMPS AT 70-80% POWER FACTOR |
| FAULT CLOSE RMS SYMMETRICAL AMPERES | 10,000 |

## INSTALLATION:

A. FOR INSTALLATION PROCEDURES CONSULT INDIVIDUAL MANUFACTURER'S CONTAINERS FOR CURRENT INSTRUCTIONS.

B. ENSURE THAT THE ARC FOLLOWER MATERIAL IS NOT CONTAMINATED WITH SOLVENT, SILICONE, OIL OR ANY OTHER FOREIGN SUBSTANCE. WIPE THE ARC FOLLOWER MATERIAL WITH A CLEAN, DRY, WHITE CLOTH IF CONTAMINATION IS SUSPECTED. CONTAMINATION (SOLVENT, SILICONE, ETC.,) CAN CAUSE DETERIORATION OF THE ARC FOLLOWER MATERIAL.

C. SILICONE LUBRICANT SHALL BE APPLIED TO 100% OF THE BUSHING/ELBOW INSULATION INTERFACE TO ENSURE FUTURE OPERABILITY. FOLLOW MANUFACTURERS INSTRUCTIONS PRECISELY (DO NOT SILICONE WRONG AREAS) FOR THE APPLICATION OF SILICONE. SILICONE THAT IS CONTAMINATED BY DIRT, WATER, OR OTHER MATTER SHALL BE REMOVED AND NEW SILICONE GREASE (STOCK NUMBER S391424) SHALL BE PROPERLY APPLIED. AVOID GETTING SILICONE ON THE ARC FOLLOWER MATERIAL AND CONDUCTIVE PARTS WHICH BECOME ENERGIZED.

D. REMOVE THE VOLTAGE TEST POINT COVER (ITEM 4). LUBE THE INSIDE OF THE COVER AND TEST POINT WITH A LIGHT COATING OF SILICONE GREASE. INSTALL THE COVER AND ROTATE IT 5 TIMES CLOCKWISE. THIS WILL ALLOW EASIER REMOVAL OF THE COVER AND PREVENT CORROSION OF THE TEST POINT.

E. ORIENT ADJACENT ELBOWS VERTICALLY OR PERPENDICULAR TO FEED-THRU BUSHINGS AND 3 OR 4-WAY CABLE TAPS IN ORDER TO GIVE MAXIMUM PHASE TO GROUND CLEARANCES FOR ENERGIZED SWITCHING. INSTALL CABLE STRAIGHT FOR AT LEAST 6 INCHES BELOW ENTRANCE TO ELBOW TO PREVENT VOIDS AND WATER ENTRY INTO ELBOW.

F. TO PREVENT BREAKAGE OF THE ARC FOLLOWER MATERIAL, CABLING MUST BE CAREFULLY INSTALLED TO PROVIDE FOR STRAIGHT IN INSERTION OF THE ELBOW INTO THE BUSHING. ALWAYS USE THE HOT STICK WHEN INSERTING THE ELBOW INTO THE BUSHING. (DO NOT OPERATE BY HAND, EVEN ON A DE-ENERGIZED CIRCUIT, AS THIS CAN LEAD TO ARC FOLLOWER DAMAGE SINCE STRAIGHT AXIAL MOVEMENT IS NOT ASSURED AND BENDING OF COMPRESSION LUG MAY OCCUR.) A FIVE FOOT MINIMUM CLEARANCE IS REQUIRED IN FRONT OR SIDES OF THE SUBSTRUCTURES WITH LOADBREAK EQUIPMENT AND EIGHT FOOT MINIMUM CLEARANCE IN FRONT OF PAD-MOUNTED EQUIPMENT FOR HOT STICK OPERATION.

G. AFTER INSTALLATION, WHILE SYSTEM IS DE-ENERGIZED, THE ELBOWS SHOULD BE MECHANICALLY OPERATED WITH HOT STICK TO VERIFY THAT CABLES ARE TRAINED FOR GOOD OPERABILITY. RE-INSPECT THE ARC FOLLOWERS BEFORE PUTTING THEM INTO SERVICE.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | COMPLETELY REVISED | - | JBH | TR | MDJ | 03/22/2001 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1990 | E | MOVED FROM UG4191 | EDM | JIK | - | - | 06/02/2020 |
| A | REVISON | - | - | - | JLB/RDJ | 1/1/1988 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 12/20/2016 |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

H. CHANGE 12KV ELBOW MALE CONTACT (ITEM 1 - STOCK NUMBER S444434) WHEN:

1. ELBOW HAS BEEN INADVERTENTLY FAULT CLOSED. THE BUSHING SHOULD NOT BE USED AGAIN AND SHOULD BE REPLACED. NOTE: THOROUGHLY CLEAN USING A CLEAN, DRY RAG. INSPECT AND RE-LUBRICATE ELBOW AND BUSHING LOADBREAK INTERFACES. IF FURTHER DAMAGE IS NOTED AT SAME TIME, THEN ELBOW REPLACEMENT IS ALSO NECESSARY.
2. ELBOW CONTACT OR BUSHING CONTACT SHOW ANY EVIDENCE OF MECHANICAL DAMAGE (CHANGEOUT SHOULD NOT BE NECESSARY UNDER NORMAL FIELD OPERATING CONDITIONS).

J. ALWAYS SMOOTH OFF CRIMPS (FILE SHARP EDGES AND CLEAN OFF FILINGS) ON COMPRESSION SOCKET TERMINAL TO PREVENT DAMAGE TO ELBOW INSULATION WHEN INSERTING CABLE.

K. ALL SINGLE AND THREE PHASE DEADFRONT TRANSFORMERS, LOW PROFILE FUSED SWITCHING CABINETS WITH GE TYPE EJO FUSE CLIPS, AND THREE-PHASE FUSED SWITCHING CABINETS HAVE 12KV LOADBREAK RATED BUSHINGS INSTALLED BY MANUFACTURERS EVEN THOUGH THEY MAY NOT HAVE WHITE-BLACK-WHITE BAND. (b) (c) (d)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | | | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| | | | | 2CU | 2 SOL AU | 2/0 AL | |
| 1 | MALE CONTACT | AS REQ'D | -- | S443837 | S443838 | S443840 | -- |
| 2 | TERMINAL, COMPRESSION | AS REQ'D | -- | | | | -- |
| 3 | ELBOW PULLING EYE | AS REQ'D | -- | | | | -- |
| 4 | VOLTAGE TEST POINT AND COVER | AS REQ'D | -- | | | | -- |
| 5 | GROUNDING POINT | AS REQ'D | -- | | | | -- |
| 6 | CABLE | AS REQ'D | -- | | | | -- |
| 7 | BAND, ID, WHITE - BLACK - WHITE (III) | AS REQ'D | -- | | | | -- |
| 8 | TAG, "DO NOT OPERATE ENERGIZED" | AS REQ'D | -- | S647966 | | | -- |
| 9 | STRAP, TIE, 6" | AS REQ'D | -- | S698224 | | | -- |

## NOTES:

(I) THIS ELBOW IS DESIGNED FOR OPERATION AS A LOADBREAK DEVICE ON 12.0, 6.9 & 4.16KV SYSTEMS. HOWEVER, IF IT IS INSTALLED ON A 12KV SYSTEM WITHOUT A 12KV RATED BUSHING OR IN A MANHOLE, A TAG (3232) "DO NOT OPERATE ENERGIZED" IS THEN ATTACHED.

(II) UNDER PROPER SUPERVISION THIS ELBOW MAY BE USED AS A LOADBREAK DEVICE AT 12KV AND BELOW. HOWEVER THIS DOES NOT APPLY ON ELBOWS INSTALLED IN MANHOLES. UNDER NO CIRCUMSTANCES ARE ELBOWS TO BE OPERATED ENERGIZED IN MANHOLES.

(III) WHITE - BLACK - WHITE BAND IDENTIFIES ELBOW THAT CAN BE USED FOR 12KV (2 OR 3-PHASE) SWITCHING WITH 12KV RATED BUSHING AND 6930 VOLT (SINGLE-PHASE) SWITCHING.

## REFERENCE:

a. REFER TO ELECTRIC STANDARD PRACTICE 212 FOR CAPACITOR TEST POINT CLEANING AND LUBRICATING.

(b) REFER TO UG3711, UG3712, UG3751, AND UG3752 FOR SINGLE AND THREE-PHASE TRANSFORMERS.

(c) REFER TO 3512 FOR LOW PROFILE FUSED SWITCHING CABINETS.

(d) REFER TO 3514 FOR THREE-PHASE FUSED SWITCHING CABINETS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | COMPLETELY REVISED | - | JBH | TR | MDJ | 03/22/2001 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1990 | E | MOVED FROM UG4191 | EDM | JIK | - | - | 06/02/2020 |
| A | REVISON | - | - | - | JLB/RDJ | 1/1/1988 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 12/20/2016 |

**SCOPE:** THIS STANDARD ILLUSTRATES THE 200A, 6,930V LOADBREAK FUSED ELBOW CONNECTOR USED ON A 6.9KV, 7.2KV OR 12KV SYSTEM.





**FIGURE 1**

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | COMPLETELY REVISED | - | JBH | TR | MDJ | 03/22/2016 | F | BILL OF MATERIALS UPDATE | EDM | RSL | JAS | KRG | 09/29/2022 |
| B | REVISION | - | - | - | JLB/RDJ | 01/01/1990 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1988 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 12/20/2016 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

200A 6,930V LOADBEAK 6.9KV, 7.2KV OR 12KV FUSED ELBOW CONNECTOR

UG4191.1

TABLE OF CONTENTS

**TABLE 1**

| VOLTAGE RATING AND CHARACTERISTICS | |
|---|---|
| **DESCRIPTION** | **KV** |
| STANDARD VOLTAGE | 15 |
| MAXIMUM RATING PHASE TO PHASE | 8.3 |
| MAXIMUM RATING PHASE TO GROUND | 8.3 |
| AC 60HZ 1 MINUTE WITHSTAND | 34 |
| DC 15 MINUTE WITHSTAND | 53 |
| BIL AND FULL WAVE CREST | 95 |
| MINIMUM CORONA VOLTAGE LEVEL | 11 |

**TABLE 2**

| CURRENT RATING AND CHARACTERISTICS | |
|---|---|
| **DESCRIPTION** | **AMPERES** |
| CONTINUOUS | FUSE RATING |
| SWITCHING | 10 OPERATIONS AT FUSE CURRENT RATING AT 8.3KV |
| FAULT CLOSURE | 10,000 A RMS SYMMETRICAL AT 8.3KV AFTER 10 SWITCHING OPERATIONS |

## INSTALLATION:

A. THIS ELBOW MAY BE USED AS A LOADBREAK DEVICE FOR 6,930V SINGLE-PHASE TRANSFORMERS. IF IT IS INSTALLED FUSING A PHASE TO PHASE CONNECTED LOAD WITH EXPULSION FUSING (FOR EXAMPLE, HDL, HZB TRANSFORMERS) OR A 12KV SYSTEM, A TAG "DO NOT OPERATE UNDER LOAD" IS TO BE ATTACHED. ELBOW SHALL NEVER BE INSTALLED TO SERVE UN-FUSED 12KV TRANSFORMERS. (a)

B. FOR INSTALLATION PROCEDURE, CONSULT MANUFACTURERS CONTAINERS FOR INSTRUCTIONS.

C. WHEN USING THE TEST POINT TO DETERMINE WHETHER OR NOT THE FUSED ELBOW IS ENERGIZED, FOLLOW THESE STEPS:

1. REMOVE THE TEST POINT COVER WITH THE HOT STICK.
2. THE TEST POINT IS A CAPACITIVE DEVICE WHICH WILL INDICATE A READING OF ABOUT 10 PERCENT OF THE VOLTAGE THE CONDUCTOR IS CARRYING. USE THE VOLTAGE DETECTOR AND PHASING TESTER (MANUFACTURED BY SAFETYLINE OR STB), FOR OBTAINING AN ACCURATE VOLTAGE INDICATION.
3. REMOVE EACH VOLTAGE TEST POINT COVER. LUBE THE INSIDE OF THE COVERS AND TEST POINTS WITH A LIGHT COATING OF SILICONE GREASE. INSTALL THE COVERS AND ROTATE THEM FIVE (5) TIMES CLOCKWISE. THIS WILL ALLOW EASIER REMOVAL OF THE COVERS AND PREVENT CORROSION OF THE TEST POINTS.

D. THE TEST POINTS CAN ALSO BE USED TO LOCATE AN OPEN FUSE AS FOLLOWS:

1. REMOVE THE TEST POINT COVERS WITH THE HOT STICK.
2. WITH THE VOLTAGE DETECTOR AND PHASING TESTER, CHECK THE VOLTAGE ON EACH TEST POINT. A VOLTAGE DIFFERENCE OF 50 PERCENT OR MORE INDICATES AN OPEN FUSE.
3. AFTER REPLACEMENT OF THE FUSE (SEE REPLACING CLEARED FUSE), RECHECK THE VOLTAGE ON THE TEST POINTS.
4. A VOLTAGE DIFFERENCE OF LESS THAN 20 PERCENT INDICATES A GOOD FUSE. LUBE THE INSIDE OF THE COVERS WITH A LIGHT COATING OF SILICONE GREASE. INSTALL THE COVERS AND ROTATE THEM FIVE (5) TIMES CLOCKWISE. THIS WILL ALLOW EASIER REMOVAL OF THE COVERS AND PREVENT CORROSION OF THE TEST POINTS.

E. REPLACING CLEARED FUSE:

1. DE-ENERGIZE AND GROUND CABLE AT THE SOURCE.
2. WITH THE VOLTAGE DETECTOR AND PHASING TESTER, CHECK THE VOLTAGE ON EACH TEST POINT TO ASSURE IT IS DE-ENERGIZED.
3. REMOVE THE PROBE FROM THE FUSED ELBOW WITH THE TORQUE LIMITING WRENCH OR SDG&E APPROVED TOOL.
4. INSERT BLEEDER STRAP BETWEEN THE ELBOW HOUSING AND THE CABLE HOUSING AND SLIDE STRAP AROUND THE ENTIRE CIRCUMFERENCE TO VENT INTERFACES. REMOVE THE ELBOW HOUSING USING A TWIST AND PULL MOTION.
5. REMOVE THE PROBE ADAPTER BY LOOSENING THE SET SCREW WITH A 1/8-INCH HEX WRENCH.
6. UNSCREW THE CLEARED FUSE FROM THE CABLE HOUSING USING A 3/16-INCH HEX WRENCH.
7. REPLACE CLEARED FUSE IN REVERSE ORDER.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | COMPLETELY REVISED | - | JBH | TR | MDJ | 03/22/2016 | F | BILL OF MATERIALS UPDATE | EDM | RSL | JAS | KRG | 09/29/2022 |
| B | REVISION | - | - | - | JLB/RDJ | 01/01/1990 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1988 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 12/20/2016 |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | ELBOW, FUSED, 30A (FUSE INCLUDED) | #2 SOLID | AS-REQ'D | -- | S321680 | CFE2SL |
| | | 2/0 | | | S321682 | FE-2/0 |
| 2 | FUSE, CURRENT LIMITING, 30A (REPLACEMENT) | -- | AS-REQ'D | -- | S365694 | CFE30A |

## NOTES:

I. MAY NOT BE USED ON 4KV SYSTEMS. DURING FUSE OPERATION THE FUSE MAY CAUSE AN "OVER VOLTAGE CONDITION" ON EQUIPMENT.

II. MAY NOT BE APPLIED TO SYSTEMS CAPABLE OF IMPRESSING 12KV ACROSS FUSE SUCH AS TRANSFORMERS NOT EQUIPPED WITH FUSING.

III. IF A FAULT IS EXPERIENCED, THE FUSED LOADBREAK ELBOW AND PROBE SHALL BE REPLACED.

IV. TO LOCATE AN OPEN FUSE, ONLY THE VOLTAGE DETECTOR AND PHASING TESTER CAN BE USED.

V. DO NOT OPERATE ON KNOWN FAULTS.

**SPECIAL OPERATING INSTRUCTIONS**

VI. IN ADDITION TO NORMAL OPERATING INSTRUCTIONS FOR ELBOWS, THE FOLLOWING APPLICATIONS SHALL BE MAINTAINED FOR FUSED ELBOWS:

a. WHEN USED TO FUSE 6,930V, SINGLE-PHASE TRANSFORMERS, THE ELBOW MAY BE OPERATED LOADBREAK FOR UP TO TEN LOADMAKE AND LOADBREAK OPERATIONS. (VIb)

(b) IF VISUAL EVIDENCE OF CARBON DEPOSITS ARE PRESENT, MALE CONTACT PROBE AND BUSHING CHANGEOUT PLUS CLEANING ELBOW/BUSHING COMBINATION SHOULD BE DONE BEFORE TEN OPERATIONS.

c. DO NOT USE FUSED ELBOW FOR FAULT LOCATING CLOSE-INS. BUT IF ELBOW IS CLOSED IN ON A FAULT, THEN THE MALE CONTACT PROBE AND FUSE SHOULD BE REPLACED.

## REFERENCE:

(a) SIGNS AND TAGGING, SEE UG3232.

b. DESIGN FUSED ELBOW APPLICATION CRITERIA, SEE ELECTRIC DISTRIBUTION DM6121.4-6121.5.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | COMPLETELY REVISED | - | JBH | TR | MDJ | 03/22/2016 | F | BILL OF MATERIALS UPDATE | EDM | RSL | JAS | KRG | 09/29/2022 |
| B | REVISION | - | - | - | JLB/RDJ | 01/01/1990 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 01/01/1988 | D | EDITORIAL CHANGES | - | JS | JS | MDJ | 12/20/2016 |

**SCOPE:** THIS STANDARD ILLUSTRATES THE 200A, 15KV LOADBREAK ELBOW EXTENSIONS.

**ATTENTION:**

* FOR REPAIR OR REPLACEMENT OF A FAILED ELBOW CONNECTION WHERE THE CABLE MUST BE STRIPPED BACK AND A NEW COMPRESSION LUG APPLIED.

** TO GAIN EXTRA LENGTH WHEN CABLES HAVE BEEN ACCIDENTALLY TRIMMED TOO SHORT OR TO CONNECT NEW APPARATUS TO EXISTING CABLES.





**FIGURE 1**
200A REPAIR LOADBREAK ELBOW





**FIGURE 2**
200A REPLACEMENT LOADBREAK ELBOW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ADW | JES | CZH | 11/9/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

200A 15KV LOADBEAK ELBOW EXTENSION

UG4192.1

## TABLE 1

| VOLTAGE RATING AND CHARACTERISTICS | |
|---|---|
| **DESCRIPTION** | **KV** |
| STANDARD VOLTAGE | 15 |
| MAXIMUM RATING PHASE TO PHASE | 14.4 |
| MAXIMUM RATING PHASE TO GROUND | 8.3 |
| AC 60HZ 1 MINUTE WITHSTAND | 34 |
| DC 15 MINUTE WITHSTAND | 53 |
| BIL IMPULSE WITHSTAND | 95 |
| CORONA EXTINCTION @ 3pC SENSITIVITY | 11 |

## TABLE 2

| CURRENT RATING AND CHARACTERISTICS | |
|---|---|
| **DESCRIPTION** | **AMPERES** |
| CONTINUOUS AND LOADBREAK | 200 |
| 10 CYCLES MOMENTARY & FAULT CLOSE | 10K |

## INSTALLATION:

A. FOR INSTALLATION PROCEDURE, CONSULT MANUFACTURERS INSTRUCTIONS.

B. WHEN USING TEST POINT TO DETERMINE WHETHER OR NOT ELBOW IS ENERGIZED, FOLLOW THESE STEPS:

1. REMOVE TEST POINT COVER WITH THE HOT STICK. PEEL OFF AT AN ANGLE RATHER THAN PULLING DIRECTLY IN LINE WITH TEST POINT ASSEMBLY.
2. THE TEST POINT IS A CAPACITIVE DEVICE WHICH WILL INDICATE A READING OF ABOUT 10 PERCENT OF THE VOLTAGE THE CONDUCTOR IS CARRYING. USE THE VOLTAGE DETECTOR AND PHASING TESTER (MANUFACTURED BY SAFETYLINE OR STB), TO OBTAIN AN ACCURATE VOLTAGE INDICATION.
3. REMOVE EACH VOLTAGE TEST POINT COVER. LUBE THE INSIDE OF THE COVERS AND TEST POINTS WITH A LIGHT COATING OF SILICONE GREASE. INSTALL THE COVERS AND ROTATE THEM FIVE (5) TIMES CLOCKWISE. THIS WILL ALLOW EASIER REMOVAL OF THE COVERS AND PREVENT CORROSION OF THE TEST POINTS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | ELBOW, REPAIR, EXTENDED LENGTH, W/ TEST POINT | #2 SOLID | - | - | S321684 | 2 SOLES |
| | | 2/0 STRANDED | - | - | S321686 | 2/0-ES |
| 2 | ELBOW, REPLACEMENT, EXTENDED LENGTH, W/ TEST POINT | #2 SOLID | - | - | S321688 | 2/0-SL |
| | | 2/0 STRANDED | - | - | S321690 | 2/0-EL |

TABLE OF CONTENTS

## NOTES:

I. ELBOWS SHALL NOT BE INSTALLED IN MANHOLES.

II. DO NOT OPERATE ON KNOWN FAULTS.

III. IF A FAULT IS EXPERIENCED, THE LOADBREAK ELBOW AND BUSHING SHALL BE REPLACED.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ADW | JES | CZH | 11/9/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

200A 15KV LOADBEAK ELBOW EXTENSION

UG4192.2

**SCOPE:** THIS STANDARD SHOWS THE LOADBREAK ACCESSORIES AND THE INSTALLATION PROCEDURES FOR THE ACCESSORIES USED ON A 12KV AND/OR 6.9KV SYSTEM.

**TABLE 1**

**PART IDENTIFICATION CHART**



| PART | MAJOR USE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|
|   INSULATING RECEPTACLE (CAP) | USED AS INSULATING CAP FOR LOADBREAK BUSHING | S204304 | - |
|   STAND-OFF PLUG | USED AS LOADBREAK STAND-OFF PLUG<br>ELECTRICALLY ISOLATES AND WATERSEALS A LOADBREAK CONNECTOR | S547312 | - |
|   BUSHING PLUG (A) | USED IN BUSHING WELL OR REDUCING TAP WELL FOR ELBOW CONNECTION POINT | S544676 | - |
|   BAILING INSERT FEED-THRU INSERT (A)(B) | USED ON TRANSFORMERS AND THREE-PHASE FUSE CABINETS FITTED WITH BUSHING WELLS TO ALLOW LOOP-FEED CAPABILITY WITH ELBOWS | S544678 | - |
|   FEED-THRU BUSHING (A) | USED AS TEMPORARY TOOL TO ISOLATE LOW PROFILE TRANSFORMER | S182016 | - |
|   GROUNDING ELBOW | | S603000 | - |
|   TEST ROD | USED WITH FEED-THRU BUSHING TO PROVIDE TEST POINT | S603428 (X) | - |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | RSW | RDJ | 01/01/1996 | F | | | | | | |
| B | REVISION | - | - | JLB | RDJ | 01/01/1986 | E | TABLE UPDATE | EDM | EJA | GLW | CZH | 08/27/2020 |
| A | REVISION | - | - | JLB | RDJ | 01/01/1983 | D | MOVED FROM UG4192 | EDM | JIK | - | - | 06/02/2020 |

## TABLE 1 (CONT'D)

| PART IDENTIFICATION CHART | | | |
|---|---|---|---|
| **PART** | **MAJOR USE** | **STOCK NUMBER** | **DESIGN UNITS** |
|  4-WAY CABLE TAP WITH BRACKET | USED TO ESTABLISH TWO LATERAL TAPS OR LOOP FROM CIRCUIT | S718328 | TAP-4W |
|   4-WAY CABLE TAP WITHOUT BRACKET (I) | USED TO ESTABLISH TWO LATERAL TAPS OR LOOP FROM CIRCUIT | S718338 | TAP4NB |

## INSTALLATION:

(A) INSTALL WHITE-BLACK-WHITE BAND, STOCK NUMBER S122495, TO IDENTIFY 12KV SWITCHING CAPABILITY.

(B) INSTALLATION OF INSULATING RECEPTACLE PROCEDURE:

1. REMOVE PROTECTIVE CAP.
2. CONNECT ONE CONCENTRIC NEUTRAL WIRE FROM INSULATING RECEPTACLE TO GROUNDING POINT. ALLOW ENOUGH WIRE FOR HOT STICK OPERATION.
3. LUBRICATE INTERNAL SURFACES WITH SILICONE GREASE.
4. ATTACH HOT STICK TO RECEPTACLE PULLING RING.
5. INSERT THE PROBE OF THE RECEPTACLE INTO THE BUSHING UNTIL IN PLACE AND LOCKING RING IS SEATED.
6. WHEN REMOVING, ATTACH HOT STICK TO THE PULLING RING, ROTATE RECEPTACLE ON BUSHING TO BREAK FRICTION AND PULL.

(C) INSTALLATION OF STAND-OFF PLUG PROCEDURE:

1. AFTER REMOVING INSULATING CAP, LUBRICATE PLUG SURFACE WITH SILICONE GREASE.
2. ATTACH STAND-OFF PLUG EYE FIRMLY TO HOT STICK.
3. SLIDE STAND-OFF PLUG ONTO PARKING STAND AND TIGHTEN UNTIL SNUG BY TURNING EYE CLOCKWISE.
4. MAKE CAPACITANCE TEST ON ELBOW CONNECTOR BEFORE REMOVING FROM BUSHING.
5. AFTER PLACING STAND-OFF PLUG ON PARKING STAND, REMOVE ELBOW CONNECTOR FROM BUSHING AND PLACE ON THE STAND-OFF PLUG.
6. IF ENTIRE ASSEMBLY (ELBOW AND STAND-OFF PLUG) IS TO BE REMOVED FROM PARKING STAND, ATTACH TOOL TO EYE OF THE STAND-OFF PLUG. REMOVE FROM PARKING STAND, AND PLACE WHERE DESIRED.
7. WHEN RETURNING ELBOW CONNECTOR TO THE EQUIPMENT BUSHING, REVERSE THE PROCEDURE.

(D) INSTALLATION OF BUSHING PLUG PROCEDURE -- (DE-ENERGIZED OPERATION ONLY):

1. CHECK BUSHING WELL FOR CLEANLINESS.
2. LUBRICATE BASE WITH SILICONE GREASE. PLACE LUBRICATED PORTION OF THE BUSHING PLUG IN THE BUSHING WELL (FLOWER POT).

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | RSW | RDJ | 01/01/1996 | F | | | | | | |
| B | REVISION | - | - | JLB | RDJ | 01/01/1986 | E | TABLE UPDATE | EDM | EJA | GLW | CZH | 08/27/2020 |
| A | REVISION | - | - | JLB | RDJ | 01/01/1983 | D | MOVED FROM UG4192 | EDM | JIK | - | - | 06/02/2020 |

## INSTALLATION (CONT'D):

3. ROTATE THE BUSHING PLUG IN A CLOCKWISE DIRECTION UNTIL IT BOTTOMS ON THE BUSHING WELL STUD.
4. WIPE BUSHING PLUG SURFACE CLEAN BEFORE INSTALLING ELBOW CONNECTOR OR INSULATING RECEPTACLE.

(E) INSTALLATION OF FEED-THRU INSERT -- (DE-ENERGIZED OPERATION ONLY):

1. CHECK BUSHING WELL FOR CLEANLINESS.
2. LUBRICATE BASE WITH SILICONE GREASE. PLACE LUBRICATED PORTION OF THE FEED-THRU INSERT INTO THE BUSHING WELL (FLOWER POT).
3. ROTATE THE INSERT IN A CLOCKWISE DIRECTION UNTIL IT BOTTOMS ON THE BUSHING WELL STUD.
4. IF THE INSERT DOES NOT LINE UP WITH THE ELBOWS IT MAY BE TURNED COUNTERCLOCKWISE 180 DEGREES. THIS WILL NOT AFFECT THE DIELECTRIC OR CURRENT CARRYING CAPABILITY.
5. INSTALL THE SUPPLIED BAILING ASSEMBLY OVER THE INSERT. THIS WILL FIRMLY SUPPORT THE INSERT AT THE DESIRED LOCATION.
6. WIPE THE INSERT CLEAN BEFORE INSTALLING ELBOWS OR INSULATING RECEPTACLES.

(F) INSTALLATION OF FEED-THRU BUSHING PROCEDURE:

(USE 182832 ONLY ON ENERGIZED SINGLE-PHASE 6930 VOLT CIRCUITS. 182016 IS GOOD FOR ALL ENERGIZED CIRCUITS.)

1. AFTER REMOVING INSULATING CAP, LUBRICATE FEED-THRU BUSHING WITH SILICONE GREASE.
2. ATTACH FEED-THRU EYE FIRMLY TO HOT STICK.
3. SLIDE FEED-THRU ONTO PARKING STAND. TIGHTEN DOWN EYE BY TURNING CLOCKWISE UNTIL SNUG.
4. MAKE CAPACITANCE TEST ON ONE ELBOW TO ESTABLISH CONDITION OF CIRCUIT. REMOVE ELBOW FROM THE BUSHING AND PLACE ON NEAREST BUSHING OF THE FEED-THRU. INSERT THE PROBE AND LOADBREAK ELBOW INTO THE BUSHING AND PUSH UNTIL IT IS FIRMLY IN PLACE AND THE LOCKING RING IS SEATED.
5. MAKE CAPACITANCE TEST ON OTHER ELBOW.
6. AFTER CIRCUIT HAS BEEN TESTED, TO ESTABLISH CONDITION OF CIRCUIT, REMOVE THE LOAD-BREAK ELBOW FROM THE BUSHING AND PLACE ON REMAINING BUSHING OF THE FEED-THRU.
7. TO RETURN THE LOADBREAK ELBOW TO THE EQUIPMENT BUSHING, REVERSE THE PROCEDURE.

(G) INSTALLATION OF GROUNDING ELBOW KIT PROCEDURE -- (DE-ENERGIZED OPERATION ONLY):

1. RECEIVE CLEARANCE FROM SWITCHING CENTER, WHEN NEEDED.
2. ATTACH THE GROUNDING ELBOW CABLE CLAMP TO THE EQUIPMENT GROUND. LAY GROUNDING ELBOW ON EQUIPMENT PAD, TO BE USED LATER.
3. INSTALL CLEAN FEED-THRU BUSHING ONTO PARKING STAND OF THE EQUIPMENT AND TIGHTEN UNTIL SNUG BY TURNING EYE CLOCKWISE.
4. USING HOT STICK, REMOVE THE LOADBREAK ELBOW THAT IS TO BE GROUNDED FROM SOURCE OF FEED.
5. PARK THIS ELBOW ON FEED-THRU BUSHING.
6. TEST ELBOW BY APPROVED MEANS, TO INSURE THAT CABLE IS DE-ENERGIZED. (SEE TEST ROD INSTALLATION PROCEDURE.)
7. AFTER TESTING IS COMPLETED AND IT HAS BEEN DETERMINED THAT THE CABLE IS DE-ENERGIZED, USE A HOT STICK TO INSTALL THE GROUNDING ELBOW ONTO FEED-THRU BUSHING. PROCEDURE IS NOW COMPLETED.
8. TO REMOVE GROUND ALWAYS REMOVE THE GROUNDING ELBOW FROM THE FEED-THRU BUSHING PRIOR TO REMOVING FROM THE EQUIPMENT GROUND.

(H) INSTALLATION OF TEST ROD PROCEDURE:

1. INSTALL CLEAN FEED-THRU BUSHING IN PARKING STAND ON EQUIPMENT AND TIGHTEN UNTIL SNUG BY TURNING EYE CLOCKWISE.
2. USING HOT STICK, REMOVE THE LOADBREAK ELBOW THAT IS TO BE TESTED FROM SOURCE OF FEED.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | RSW | RDJ | 01/01/1996 | F | | | | | | |
| B | REVISION | - | - | JLB | RDJ | 01/01/1986 | E | TABLE UPDATE | EDM | EJA | GLW | CZH | 08/27/2020 |
| A | REVISION | - | - | JLB | RDJ | 01/01/1983 | D | MOVED FROM UG4192 | EDM | JIK | - | - | 06/02/2020 |

**INSTALLATION (CONT'D):**

3. PARK THIS ELBOW ON FEED-THRU BUSHING.
4. USING HOT STICK, INSTALL TEST ROD INTO FEED-THRU BUSHING.
5. TEST.

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) USED IN THE 200 AMP, THREE-PHASE LOW PROFILE CABLE TERMINATING CABINET.

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | RSW | RDJ | 01/01/1996 | F | | | | | | |
| B | REVISION | - | - | JLB | RDJ | 01/01/1986 | E | TABLE UPDATE | EDM | EJA | GLW | CZH | 08/27/2020 |
| A | REVISION | - | - | JLB | RDJ | 01/01/1983 | D | MOVED FROM UG4192 | EDM | JIK | - | - | 06/02/2020 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

200 AMP LOADBREAK ACCESSORIES, 12KV

UG4195.4

**SCOPE:** THIS STANDARD SHOWS 200 AMP DEADBREAK CONNECTORS USED ON A 12KV AND BELOW SYSTEMS.

**CAUTION:**

* THIS ELBOW CONNECTOR MUST BE OPERATED DE-ENERGIZED ONLY. TAG, (ITEM 9) "DO NOT OPERATE ENERGIZED", MUST BE ATTACHED THRU ITEM 3.





**TABLE 1**

| RATINGS | |
|---|---|
| KV LINE TO GROUND | 8.3 |
| AMPERES | 200 |
| KV-BIL | 95 |

**FIGURE 1**
200 AMP DEADBREAK ELBOW





**FIGURE 2**
INSTALLATION EXAMPLE 1
SINGLE-PHASE LIVE FRONT TO DEAD FRONT

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JLB/RDJ | 1/1/1987 | F | | | | | | |
| B | REVISION | - | - | - | RES/DRH | 1/1/1985 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1985 | D | REVISION | - | - | - | RSW/RDJ | 1/1/1996 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



200 AMP DEADBREAK CONNECTORS, 12KV

UG4196.1







**FIGURE 3**
INSTALLATION EXAMPLE 2
OLD STYLE RADIAL TO NEW STYLE RADIAL/LOOP TRANSFORMER REPLACEMENT

**TABLE 2**



**PART IDENTIFICATION CHART**

| PART | MAJOR USE | CABLE SIZE | STOCK NUMBER |
|---|---|---|---|
|  "T" CONNECTOR | USED TO JOIN THREE CABLES (TWO DEADBREAK ELBOWS & ONE STRAIGHT PLUG) USE WITH BAIL ASSEMBLIES | -- | S256112 |
|  STRAIGHT RECEPTACLE (III) | USED TO JOIN A STRAIGHT PLUG USE WITH BAIL ASSEMBLY | #2 CU | S570256 |
| | | #4 CU | S570768 |
| | | 2/0 AL | S570848 |
| | | #2 SOL AL | S570816 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JLB/RDJ | 1/1/1987 | F | | | | | | |
| B | REVISION | - | - | - | RES/DRH | 1/1/1985 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1985 | D | REVISION | - | - | - | RSW/RDJ | 1/1/1996 |

## TABLE 2 (CONT'D)

| PART IDENTIFICATION CHART | | | |
|---|---|---|---|
| **PART** | **MAJOR USE** | **CABLE SIZE** | **STOCK NUMBER** |
|  STRAIGHT PLUG (III) | USED TO JOIN A STRAIGHT RECEPTACLE OR "T" CONNECTOR<br>USE WITH BAIL ASSEMBLY | #2 CU | S544688 |
| | | #4 CU | S544694 |
| | | 2/0 AL | S547316 |
| | | #2 SOL AL | S547314 |
|  EXTENSION SPLICE (C)(II) | THIS SPLICE TO BE USED WHEN EXTRA CABLE IS REQUIRED ON EXISTING SYSTEMS WITHIN THE SAME STRUCTURE OR SUBSTRUCTURE<br><br>EXAMPLES ARE:<br>- CABLE TO EXISTING EQUIPMENT LOCATED DIRECTLY ON TOP OF SUBSTRUCTURE<br>- CABLE TAPS OR OTHER EQUIPMENT BEING RAISED OR RELOCATED IN SUBSTRUCTURES<br>- TRANSFORMER OR OTHER PAD-MOUNTED EQUIPMENT REPLACEMENT.<br>- SPLICING OF CABLE WHERE 200 AMP TEES ARE NOT REQUIRED. | #2 CU | S668400 |
| | | #2 SOL AL | S668402 |
| | | 2/0 AL | S668404 |
| | | #2 CU - #2 SOL AL | S668406 |
| | | #2 CU - 2/0 AL | S668408 |

## INSTALLATION:

A. FOR INSTALLATION PROCEDURES, CONSULT INDIVIDUAL MANUFACTURERS CONTAINERS FOR INSTRUCTIONS.

B. BAILING PROCEDURES FOR DEADBREAK ELBOW AND INSERT.

1. OPERATION OF EXISTING ASSEMBLY - REBAIL TO EXISTING STOP NUT POSITION. (THIS WILL PRODUCE THE LEAST AMOUNT OF CHANGE TO AN INTERFACE CONDITION THAT IS WORKING. REDUCING OR INCREASING THE TURNS MAY RESULT IN CREATING PROBLEMS WHERE NONE EXIST.)
2. INSTALLATION OF NEW ASSEMBLY (ELBOW AND/OR INSERT) - WITH THE ELBOW FULLY SEATED ON THE BUSHING, PULL HOLD-DOWN BAIL UP OVER THE TOP OF ELBOW SO THAT THE EYE BOLT ON THE BAIL IS DIRECTLY OVER THE HOLD DOWN BAIL PRESSURE PLATE. TURN THE EYE BOLT IN A CLOCKWISE DIRECTION UNTIL INITIAL CONTACT IS MADE WITH THE HOLD DOWN BAIL PRESSURE PLATE; THEN TIGHTEN THE EYE BOLT TWO FULL (360°) TURNS MAXIMUM, 1 1/2 TURNS MINIMUM. WITH THE EYE BOLT IN ITS ASSEMBLED POSITION, ADJUST THE STOP NUT BY BRINGING THE NUT DOWN TO THE TOP PLATE OF THE BAIL. THE NUT SHOULD ACT AS A STOP TO PREVENT THE EYE BOLT FROM APPLYING EXCESSIVE FORCE ON THE ELBOW FOR FUTURE OPERATION WITH A HOT STICK.

(C) FOR EXTENSION SPLICE INSTALLATION PROCEDURE, CONSULT INDIVIDUAL MANUFACTURERS CURRENT INSTRUCTIONS.

(D) 3312 HANDHOLE IS REQUIRED ON REPLACEMENT OF SINGLE-PHASE LIVE FRONT TRANSFORMERS.

(E) 3312 HANDHOLE IS NOT REQUIRED ON REPLACEMENT OF THREE-PHASE LIVE FRONT OR DEAD FRONT TRANSFORMERS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JLB/RDJ | 1/1/1987 | F | | | | | | |
| B | REVISION | - | - | - | RES/DRH | 1/1/1985 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1985 | D | REVISION | - | - | - | RSW/RDJ | 1/1/1996 |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | QUANTITY | STANDARD PAGE | STOCK NUMBER | | | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|
| | | | | | 2 CU | 2 SOL AL | 2/0 AL | |
| 1 | ELECTRICAL MALE CONTACT | PART OF DEADBREAK ELBOW CONNECTOR KIT | -- | -- | S443456 | S443842 | S443844 | -- |
| 2 | COMPRESSION SOCKET TERMINAL | | -- | -- | | | | |
| 3 | ELBOW PULLING EYE | | -- | -- | | | | |
| 4 | VOLTAGE TEST POINT AND COVER | | -- | -- | | | | |
| 5 | PRESSURE PLATE FOR HOLD DOWN BAIL | | -- | -- | | | | |
| 6 | GROUNDING POINT | | -- | -- | | | | |
| 7 | CABLE | | -- | -- | | | | |
| 8 | HOLD DOWN BAIL (I) | | -- | -- | S120416 (IV) | | | -- |
| 9 | TAG, "DO NOT OPERATE ENERGIZED" | -- | -- | 3232 | S647966 | | | -- |
| 10 | TIE STRAP - 6 IN | -- | -- | 3232 | S698224 | | | -- |

## NOTES:

(I) ELBOW COMES COMPLETE WITH HOLD DOWN BAIL.

(II) SPLICE IS COMPLETELY SEALED AND MAY BE INSTALLED IN SUBSURFACE EQUIPMENT.

(III) **DO NOT** USE A STRAIGHT RECEPTACLE AND STRAIGHT PLUG WHEN EXTRA CABLE IS REQUIRED ON EXISTING SYSTEMS WITHIN THE SAME STRUCTURE OR SUBSTRUCTURE. INSTEAD OF THE STRAIGHT RECEPTACLE AND STRAIGHT PLUG, USE EXTENSION SPLICE SHOWN ON TABLE 2. NON USE EXAMPLES ARE:

a. CABLE TO EXISTING EQUIPMENT LOCATED DIRECTLY ON TOP OF SUBSTRUCTURE.

b. CABLE TAPS OR OTHER EQUIPMENT BEING RAISED OR RELOCATED IN SUBSTRUCTURES.

c. TRANSFORMER OR OTHER PAD-MOUNTED EQUIPMENT REPLACEMENT.

(IV) SPARE PART NUMBER.

**REFERENCE:** NONE

TABLE OF CONTENTS





© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | JLB/RDJ | 1/1/1987 | F | | | | | | |
| B | REVISION | - | - | - | RES/DRH | 1/1/1985 | E | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1985 | D | REVISION | - | - | - | RSW/RDJ | 1/1/1996 |

**SCOPE:** THIS STANDARD SHOWS 200 AMP ACCESSORIES USED ON 12KV AND BELOW SYSTEM.

## TABLE 1

**PART IDENTIFICATION CHART**

| PART | MAJOR USE | STOCK NUMBER |
|---|---|---|
|  DEADEND RECEPTACLE (C) | USED TO CAP DEADBREAK TRANSFORMER BUSHING, "TEE" CONNECTOR OR STRAIGHT PLUG | S570304 |
|  DEADEND PLUG (D) | USED FOR DEADBREAK TO CAP "TEE" CONNECTOR, DEADBREAK ELBOW OR STRAIGHT RECEPTACLE<br><br>TO BE USED WITH ASSEMBLY BAIL (STOCK NUMBER S120352) | S544864 |
|  GROUNDING PLUG (TOOL) (E) | USED FOR GROUNDING ELBOW RECEPTACLES | S544844 |
|  BUSHING PLUG (F) | USED IN DEADBREAK TRANSFORMER "FLOWER POT" BUSHING WELLS, AND FORMS THE MATING BUSHING FOR THE DEADBREAK ELBOWS | S544684 |

## INSTALLATION:

A. BEFORE ASSEMBLING BUSHING PLUG, MAKE SURE THE "FLOWER POT" BUSHING WELL IS CLEAR OF ALL CONTAMINANTS.

B. IF THE ELBOW CONNECTOR IS NOT TO BE IMMEDIATELY ASSEMBLED, REPLACE RED PROTECTIVE SHIPPING CAP. NOTE: THIS IS A PROTECTIVE CAP ONLY, NOT AN INSULATING RECEPTACLE.

(C) DEADEND RECEPTACLE PROCEDURE:

1. LUBRICATE PLUG NOSE WITH SILICONE GREASE, (STOCK NUMBER S391424).
2. REMOVE PROTECTIVE CAP ON RECEPTACLE AND INSERT NYLON ROD.
3. INSERT PLUG INTO RECEPTACLE.
4. REMOVE NYLON STRING OR ROD.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1987 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1976 | D | | | | | | |

## INSTALLATION (CONT'D):

(D) DEADEND PLUG PROCEDURE:

1. REMOVE PROTECTIVE CAP AND LUBRICATE NOSE OF PLUG WITH SILICONE GREASE, (STOCK NUMBER S391424).
2. PLACE NYLON ROD INTO RECEPTACLE.
3. INSERT PLUG INTO RECEPTACLE.
4. REMOVE NYLON STRING OR ROD.

(E) GROUNDING PLUG PROCEDURE:

1. AFTER REMOVING PROTECTIVE CAP AND CLEANING PLUG, LUBRICATE SURFACE WITH SILICONE GREASE, (STOCK NUMBER S391424). ALWAYS REPLACE PROTECTIVE CAP WHEN PLUG IS NOT IN USE.
2. CONNECT SYSTEM GROUND TO CONDUCTOR PROVIDED ON PLUG CARRIAGE ASSEMBLY.
3. ATTACH PLUG CARRIAGE EYE TO HOT STICK.
4. SLIDE CARRIAGE ASSEMBLY ONTO PARKING STAND. THE CARRIAGE CAN BE PUSHED OR PULLED ONTO PARKING STAND DEPENDING ON POSITION OF ELBOWS AND WORK SPACE AVAILABLE.
5. MAKE CAPACITANCE TEST BEFORE REMOVING FROM APPARATUS BUSHING.
6. AFTER PLACING CARRIAGE ON PARKING STAND, REMOVE ELBOW CONNECTOR FROM BUSHING OF THE APPARATUS AND PLACE ON PLUG.
7. APPLY PLUG HOLD DOWN BAIL TO ELBOW BY TURNING BAIL EYE CLOCKWISE WITH HOT STICK.
8. IF ENTIRE ASSEMBLY IS TO BE REMOVED FROM PARKING STAND, ATTACH HOT STICK TO EYE OF CARRIAGE ASSEMBLY, REMOVE FROM PARKING STAND AND PLACE WHERE DESIRED.
9. TO RETURN ELBOW CONNECTOR TO THE APPARATUS BUSHING, SIMPLY REVERSE THE OPERATIONAL SEQUENCE.

(F) BUSHING PLUG PROCEDURE:

1. LUBRICATE BASE OF BUSHING WITH LUBRICANT SUPPLIED. (DO NOT SUBSTITUTE.) PLACE THE LUBRICATED PORTION OF THE BUSHING IN THE "FLOWER POT".
2. ROTATE THE BUSHING IN A CLOCKWISE DIRECTION UNTIL THE BUSHING CONTACT BOTTOMS ON THE "FLOWER POT" STUD. (THE CONDUCTIVE LIP ON THE BUSHING SHOULD TOUCH OR BE APPROXIMATELY 1/16" FROM THE "FLOWER POT" FLANGE.)
3. WIPE BUSHING SURFACE CLEAN BEFORE ASSEMBLY WITH ELBOW CONNECTOR.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. STANDARD PRACTICES IN THE CONSTRUCTION MANAGEMENT STANDARD PRACTICE MANUAL MUST BE FOLLOWED IN THESE INSTALLATION PROCEDURES.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/02/2020 | F | | | | | | |
| B | REVISION | - | - | - | JLB/RDJ | 1/1/1987 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1976 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD COVERS THE CLEER, 600A, LIVE LINE TOOL OPERATED, SEPARABLE CONNECTOR.

**CAUTION:**

* FEEDER MUST BE DE-ENERGIZED DURING ANY CONSTRUCTION AND INTERCONNECTION WITH THE COOPER CLEER.




| UG MAP SYMBOL |
|---|
| T IG T |
| 3-IG |

**TABLE 1**

| SYMBOL | DESCRIPTION |
|---|---|
| IG | ACTIVE |
| IG | PRELIM |





**FIGURE 1**
IN-LINE BRACKET (XIII)

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | COMPLETELY REVISED | - | DG | JS | CZH | 03/18/2019 | G | DRAWING UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 |
| C | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/22/2018 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 10/13/2017 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |



TABLE OF CONTENTS

TABLE OF CONTENTS





**FIGURE 2**
SQUARE BRACKET (XIII)

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | COMPLETELY REVISED | - | DG | JS | CZH | 03/18/2019 | G | DRAWING UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 |
| C | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/22/2018 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 10/13/2017 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |



**FIGURE 3**
INSULATED PROTECTIVE CAP (III)(VIII)



**FIGURE 4**
GROUNDING ELBOW (I)(VIII)








**FIGURE 5**
IN-LINE BRACKET





**FIGURE 6**
SQUARE BRACKET (XIII)

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | COMPLETELY REVISED | - | DG | JS | CZH | 03/18/2019 | G | DRAWING UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 |
| C | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/22/2018 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 10/13/2017 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |



TABLE OF CONTENTS

## INSTALLATION:

(A) N-JUNCTION CLEER PROVIDES A TEST, GROUND, AND ISOLATION POINT FOR 600A TEE CONNECTIONS.

(B) N-JUNCTION CLEER INSTALLED WITH THE TEE BODY, ELBOW TAP PLUG, 200A INSULATION RECEPTACLE.

(C) N-JUNCTION CLEER CAN BE MOUNTED ON A CONCRETE WALL OR UNISTRUT.

(D) MOUNT UNITS AWAY FROM THE MANHOLE ENTRY AREA.

(E) N-JUNCTION CLEER CAN BE SET AT A DESIRED ANGLE FOR LIVE LINE TOOL OPERATION.

(F) MINIMUM HEIGHT NEEDED FOR STACKED 3 IN-LINE CLEER INSTALLATION IS 36 INCHES. MINIMUM VERTICAL SPACING BETWEEN ADJACENT IN-LINE CLEER BRACKET IS 4 INCHES.

(G) EACH N-JUNCTION CLEER UNIT IS TO BE CONNECTED TO THE SYSTEM GROUND.

(H) N-JUNCTION CLEER HAS GROUND ATTACHMENT POINTS AND COMES WITH TWO (2) GROUND LUGS (#8 SOL TO 2/0 STRANDED).

(J) BOND THE LOAD BREAK "C" CONNECTOR TO GROUND.

K. TORQUE TEE BODY TO MANUFACTURER'S SPECIFICATION OF 50-60 FOOT-POUNDS.

L. ALL EXISTING CABLE(S) MUST BE RETERMINATED & RECRIMPED TO LAND LUG(S) PROPERLY TO PREVENT UNNECESSARY STRESS TO CABLE(S) WHICH WILL CAUSE PREMATURE FAILURE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | JUNCTION BAR, 600A CLEER, 15KV, LOAD BREAK - INLINE | -- | 3 | -- | S439870 | CCL-JB |
| 2 | JUNCTION BAR, 600A CLEER, 15KV, LOAD BREAK - SQUARE | -- | 3 | -- | S439872 | CCL-SQ |
| 3 | ELBOW TEE, COLD SHRINK (XII)(b) | 4/0, 350, 500 | 6 | 4189 (FUTURE) | S326572 | 600AT |
| | | 750, 1000 | | | S326574 | 600ATL |
| 4 | ELBOW TAP PLUG | -- | 6 | 4182 | S547328 | LRTP |
| 5 | INDICATOR, FAULT, LOAD TRACKER (FI) (XIII)(XIV) | -- | AS REQ'D | 4360 | S423714 | -- |
| 6 | EXTENSION BUSHING, 600A WITH LOAD TAP PLUG | -- | AS REQ'D | 4182 | S336198 | EXLRTP |
| 7 | INSULATION RECEPTACLE, 200A | -- | 6 | 4180 | S204304 | INSREC |
| 8 | WIRE, BARE COPPER, #2, 7 STRANDED, SOFT DRAWN | -- | AS REQ'D | 4002 | S812818 (X) | GDWIRE |
| 9 | CONNECTOR, COPPER, COMPRESSION | -- | AS REQ'D | 4172 | -- | -- |
| 10 | CONDUCTOR CONNECTOR | 4/0, 350 AND 500 | AS REQ'D | -- | S471314 | P6ALR3 |
| | | 750 AND 1000 | | | S471316 | P6ALR5 |

## NOTES:

(I) GROUNDING WITH THE N-JUNCTION CLEER REQUIRES A 600A LOAD BREAK GROUNDING ELBOW (S493780).

II. N-JUNCTION CLEER IS FULLY SHIELDED AND FULLY SUBMERSIBLE.

(III) THE N-JUNCTION CLEER CAN BE FULLY ISOLATED USING THE 600A LOAD BREAK PROTECTIVE CAP (S204300). ALL BUSHINGS OF THE CONNECTOR SYSTEM ARE THEN INSULATED AND DEADFRONT.

(IV) NO LOAD SHALL BE CONNECTED TO THE 200A TEST POINT.

(V) NO STACKING OF TEES ALLOWED ON THE N-JUNCTION CLEER UNITS.

VI. BATTERY-OPERATED EQUIPMENT IS NOT TO BE USED WHEN TORQUING REQUIREMENTS EXIST.

(VII) ALTHOUGH THIS DEVICE IS RATED AS A 600A LOAD BREAK DEVICE, SDG&E WILL ONLY PERFORM OPERATIONS WHEN DE-ENERGIZED.

(VIII) SIX (6) GROUNDING JUMPERS (S439780 - KEARNY STOREROOM ITEM) AND SIX (6) ISOLATION CAPS (S204300 - AVAILABLE AT ALL DISTRICTS) WILL BE NEEDED. THESE ARE REUSABLE (CHECKED IN/OUT).

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | COMPLETELY REVISED | - | DG | JS | CZH | 03/18/2019 | G | DRAWING UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 |
| C | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/22/2018 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 10/13/2017 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |



TABLE OF CONTENTS

## NOTES (CONT'D):

IX. FEEDER MUST BE DE-ENERGIZED DURING ANY CONSTRUCTION AND INTERCONNECTION WITH THE COOPER CLEER. THIS CONNECTION MAY BE PLACED IN WALK-IN VAULTS AND MANHOLES TO CREATE A VISIBLE OPEN IN THE 600A UNDERGROUND SYSTEM. IT CAN BE INSTALLED DURING OUTAGES TO RESTORE PARTIAL SERVICE BY OPENING TEE'S; SEPARATING TEE'S DURING OUTAGES CAN BE FOUND IN ELECTRIC STANDARD PRACTICE 222 SECTION 4.5.3 FOR PARTIAL RESTORATION. IN THE PLANNING AND DESIGN PHASE, THE CONNECTION MAY BE PLACED IN MANHOLES ON LONG, CONTINUOUS RUNS TO SUPPLY A MANUAL, STICK-OPERABLE, DISCONNECT POINT. PLACEMENT WILL ALSO INCLUDE EVERY OTHER MANHOLE AND VAULT BETWEEN SECTIONALIZING DEVICES.

(X) THIS ITEM IS EXEMPT.

XI. DESIGN SCOPE SHOULD INCLUDE VAULTS AND MANHOLES THAT HAVE SUFFICIENT SPACE AND LENGTH TO OPERATE WITHIN THE STRUCTURE. 3325, 3326, AND 3327 (TRANSMISSION SUBSTRUCTURE NEAR SUBSTATIONS GENERALLY) MANHOLES SHOULD HAVE SUFFICIENT SPACE (4198). 3322, 3324 (BOTH TYPES), AND 3399 MANHOLES WILL REQUIRE APPROVAL FROM EDE DEPENDING ON THE LAYOUT OF THE SUBSTRUCTURE.

(XII) ELBOW TEE S326589 IS FMO ONLY.

(XIII) LOAD TRACKER FAULT INDICATOR (FI) IS REQUIRED ON ALL 600A CLEER CONNECTOR INSTALLATIONS. (c)

(XIV) NOT SHOWN ON FIGURES.

## REFERENCE:

a. FOR PARTIAL RESTORATION, SEE ESP222.

(b) SEE UG4189 (FUTURE) FOR COLD SHRINK ELBOW TEE WITH INTEGRATED CABLE ADAPTER.

(c) SEE UG4360: LOAD TRACKER FAULT INDICATOR.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | COMPLETELY REVISED | - | DG | JS | CZH | 03/18/2019 | G | DRAWING UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 |
| C | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/22/2018 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 10/13/2017 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |

**SCOPE:** THIS STANDARD DESCRIBES THE CLEER 200A L BRACKET 27" X 4" X 4".





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BRACKET, CLEER TEE, 27" X 4" X 4" | AS REQ'D | -- | S165456 | CLWLBK |

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| D | COMPLETELY REVISED | - | DG | JS | CZH | 03/18/2019 | G | DRAWING UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 |
| C | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/22/2018 | F | FORMATTING | EDM | JIK | - | - | 06/02/2020 |
| B | EDITORIAL CHANGES | - | DG | JS | MDJ | 10/13/2017 | E | FIGURE UPDATE | - | EJA | GLW | CZH | 12/09/2019 |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CLEER 200A L BRACKET
27" X 4" X 4"



UG4198.6

TABLE OF CONTENTS

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 4202 | STANDARD JOINT CABLE POLE RISER POSITIONS USING LADDER ARM BRACKETS AND SINGLE RISER |
| 4203 | POLE QUADRANT AND RISER IDENTIFICATION |
| 4204 | CABLE POLE RISER INSTALLATION |
| 4205 | INSTALLATION OF PERMANENT POLE STEPS |
| 4206 | GENERAL INFORMATION - 12.47KV AND BELOW CABLE POLES |
| 4214 | 0-750V UNDERGROUND SERVICE FROM AN OVERHEAD LINE |
| 4218 | 12.47KV AND BELOW CROSSARM CABLE POLE, THREE-PHASE NON-PORCELAIN TERMINALS, LINE AND BUCK |
| 4235 | CABLE POLE MVI / MV200 / 600A CABLE POLE APPLICATION |
| 4240 | 12.47KV AND BELOW CROSSARM CABLE POLE, SINGLE-PHASE AND THREE-PHASE, 1/C PER PHASE, NON-PORCELAIN TERMINALS |
| 4242 | THREE-PHASE, CABLE-POLE-12KV, NON-PORCELAIN 900A DISCONNECT |
| 4244 | POLE TOP SWITCH 12KV RISER LOADBREAKER TYPE SINGLE CIRCUIT |
| 4247 | 12.47KV AND BELOW CABLE POLE THREE-PHASE, 1/C PER PHASE, ALLEY ARM CONSTRUCTION, NON-PORCELAIN TERMINALS |
| 4251 | 12.47KV AND BELOW DEADEND CABLE POLE, 6 OR 7 CONDUCTORS, 1/C PER PHASE, HOOKSTICK SWITCHED, NON-PORCELAIN TERMINALS |
| 4252 | ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | EDITORIAL CHANGES | EDM | DWC | JES | CZH | 03/09/2020 | H | FORMATTING | EDM | JIK | - | - | 09/16/2021 |
| D | EDITORIAL CHANGES | - | MRF | JES | CZH | 07/16/2019 | G | UG4230 MOVED TO FMO | EDM | JIK | JES | CZH | 07/27/2021 |
| C | 4232 MOVED TO FMO | - | JK | JS | CZH | 03/18/2019 | F | EDITORIAL CHANGES | GLC | JIK | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLES
TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS NORMAL CABLE POLE RISER POSITIONS FOR SDG&E AND COMMUNICATIONS COMPANIES.





**FIGURE 1**
DEADEND OR
Ⓥ THROUGH CONSTRUCTION
MULTIPLE RISER





**FIGURE 2**
DEADEND CONSTRUCTION
SINGLE POWER RISER





**FIGURE 3**
THROUGH CONSTRUCTION
SINGLE POWER RISER

**TABLE 1:**

| TITLE | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | SDG&E PRIMARY RISER |
| 2 | SDG&E SECONDARY RISER |
| 3 | SDG&E EXISTING RISER |
| 4 | SDG&E GROUND |
| 5 | BRACKET, LADDER ARM ASSEMBLY |
| 6 | COMMUNICATION RISER STATION |
| 7 | COMMUNICATION TANGENT THRU POSITION |
| 8 | COMMUNICATION GROUND |

**INSTALLATION:**

Ⓐ COMMUNICATIONS ONLY POINT OF ATTACHMENT FOR LADDER ARM BRACKET CONSTRUCTION SHALL BE ON THE BACKSIDE OF LADDER ARM BRACKET ASSEMBLY. GALVANIZED UNISTRUT PIPE CLAMPS SHALL BE USED TO SECURE THE CONDUIT. COMMUNICATIONS MAY ATTACH ON THE BACK OF THE LADDER ARM ASSEMBLY ALONGSIDE SDG&E'S RISER. LADDER ARMS MAY BE INSTALLED BY COMMUNICATIONS COMPANY PROVIDED THEY ARE INSTALLED PER SDG&E CONSTRUCTION STANDARDS AND MEET SDG&E MATERIAL SPECIFICATIONS.

Ⓑ FOR NEW CONSTRUCTION WITH AN EXISTING SDG&E RISER ON THE POLE (FIGURE 3), ONE THREE-INCH RISER MAX. ON THE POLE AND ONE THREE-INCH RISER MAX. ON THE BACKSIDE OF THE LADDER ARM BRACKET ARE PERMITTED BACK TO BACK.

Ⓒ WHEN A LADDER ARM IS EXISTING, AND THE BACK OF LADDER ARM POSITIONS AND POLE POSITIONS ON COMMUNICATIONS SIDE OF POLE ARE OCCUPIED, ADDITIONAL COMMUNICATIONS RISERS MUST BE PLACED ON ANOTHER POLE.

**BILL OF MATERIALS:** NONE

**NOTES:**

I. 1/2 POLE CLIMBING SPACE APPLIES TO A LEVEL 4 FEET BELOW THE LOWEST LEVEL OF FACILITIES. COMMUNICATIONS, SECONDARY, PRIMARY, ETC., SEE OVERHEAD STANDARD SECTION 200 FOR CLIMBING SPACE REQUIREMENTS.

II. CHANGES TO THESE STANDARD RISER POSITIONS MUST NOT REDUCE THE CLIMBING SPACE TO LESS THAN 1/2 POLE.

III. CONDUIT RISER AT BASE OF POLE NOT TO INFRINGE ON CURB OR SIDEWALK POSITIIONS.

IV. SPARE CONDUITS ARE NOT CONSIDERED AS RISERS.

Ⓥ NEW CONSTRUCTION WITH EXISTING SDG&E RISER.

**REFERENCE:**

a. PVC RISERS ARE NOT PERMITTED WITHIN THE CLIMBING SPACE PER G.O. 95 RULE 22.2C.

b. NO C.A.T.V. OR TELCO JUMPERS ALLOWED IN CLIMBING SPACE PER G.O. 95 RULE 84.7.

c. SEE OVERHEAD STANDARDS SECTION 200 FOR ALLOWABLE G.O. 95 CLIMBING SPACE OBSTRUCTIONS.

d. SEE OH363UG4205 FOR INSTALLATION OF POLE STEPS.

e. SEE OH1403UG4203 FOR POLE QUADRANT AND RISER IDENTIFICATION.

f. SEE STANDARD OH1404UG4204 WHEN INSTALLING A SINGLE RISER, MODIFYING EXISTING CABLE POLE TO INCLUDE SECOND RISER OR FOR MULTIPLE CONDUIT RUNS AND JOINT POLE INSTALLATION.

g. SEE UG4620 FOR TELECOMMUNICATION INSTALLATION.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | GLC/DV | JIK | - | - | 01/27/2022 |
| C | DRAWING UPDATE | EDM | JAC | GLW | CZH | 02/10/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**STANDARD JOINT CABLE POLE RISER POSITIONS USING LADDER ARM BRACKETS AND SINGLE RISER**

SCALE: NOT TO SCALE

DRAWING NO: OH1402.1 UG4202.1


SHEET: 1 OF 1

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS


**SCOPE:** THIS STANDRD SHOWS CABLE POLE RISER LOCATIONS, SDGE QUADRANT AND SIGNS FOR MARKING POLE RISER INSTALLATIONS.




CONFIGURATION 1
DEAD END THROUGH CONSTRUCTION
MULTIPLE POWER RISER




CONFIGURATION 2
DEAD END CONSTRUCTION
SINGLE POWER RISER




CONFIGURATION 3
THROUGH CONSTRUCTION
SINGLE POWER RISER

**FIGURE 1**
IDENTIFYING CABLE POLE RISER LOCATION

## INSTALLATION:

(A) NAIL THE SIGN TO THE RISER POLE APPROXIMATELY 5 FEET ABOVE GROUND WITH THE PROPER SIDE SHOWING.

(B) USE ONE MARKER TO SHOW SDG&E RISER LOCATION.

## BILL OF MATERIAL:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNIT |
|---|---|---|---|---|---|
| 1 | MARKER, YELLOW PLASTIC WITH RAISED LETTERING STATING "PLACE-ELECTRIC RISER HERE 1" CLEAR-FROM-POLE SDG&E" ON ONE SIDE AND "PLACE ELECTRIC RISER HERE" FOLLOWED BY THREE ILLUSTRATIONS, THEN "SDGE" ON REVERSE SIDE. TWO 1/8" HOLES, APPROX. DIMENSIONS 3" X 9.25" X 1/16" | 1 | 1403/4203 | S476312 | - |
| 2 | NAIL, ROOFING, 1-3/4", #11, 1/2" HEAD | AS REQ'D | - | S492192 | - |

**NOTES:** NONE

## REFERENCE:

a. SEE OH1402UG4202 FOR STANDARD JOINT CABLE POLE RISER POSITIONS.

b. SEE OH1404UG4204 FOR CABLE POLE RISER POSITION.

**SCOPE:** THIS STANDARD SHOWS THE SIGN USED FOR MARKING POLE RISER INSTALLATIONS.





**FIGURE 1**
PREFERRED CONSTRUCTION (A)
FRONT





**FIGURE 2**
ALTERNATE CONSTRUCTION (B)
REVERSE

## INSTALLATION:

(A) USE THE SIDE OF THE SIGN STATING "PLACE ELECTRIC RISER HERE" (FRONT), WHEN LADDER ARM BRACKETS ARE INSTALLED.

(B) FOR ALTERNATIVE CONSTRUCTION USE THE SIDE OF THE SIGN STATING "PLACE ELECTRIC RISER HERE 1-INCH CLEAR FROM POLE" REVERSE, WHEN A SINGLE CONDUIT IS INSTALLED.

C. REMOVE SIGN WHEN THE POLE RISER(S) IS INSTALLED.

**BILL OF MATERIAL:** NONE

## NOTES:

I. SIGN IS AVAILABLE TO MARK SDG&E RISER LOCATIONS ON CABLE. THE SIGN STOCK NUMBER S476312 IS MADE OF FLEXIBLE PLASTIC, WITH RAISED LETTERING ON EACH SIDE. SIGNS ARE TO BE ATTACHED TO POLES WITH 1 3/4 INCH NAILS STOCK NUMBER S492192.

II. "PLACE ELECTRIC RISER HERE SHOWING 3 POLE RISER POSITIONS, SDG&E" IS PRINTED ON FRONT SIDE.

III. "PLACE ELECTRIC RISER HERE 1-INCH CLEAR FROM POLE, SDG&E" ON THE REVERSE SIDE.

IV. WHEN THE RISER LOCATION HAS BEEN DETERMINED, THE SIGNS ARE TO BE PLACED ON THE POLE, APPROXIMATELY 5 FEET ABOVE GROUND LEVEL BY THE CUSTOMER PROJECT PLANNER, PROJECT COORDINATOR, GENERAL FOREMAN, INSPECTOR OR WORKING FOREMAN SETTING THE POLE. RISER LOCATIONS ARE SHOWN ON OH1402UG4202.

## REFERENCE:

a. SEE OH1403UG4203 FOR POLE QUADRANT AND RISER IDENTIFICATION.

b. SEE OH1404/UG4204 FOR CABLE POLE RISER INSTALLATION.

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | AMP | JIK | - | - | 04/14/2022 |
| C | DRAWING UPDATE | EDM | JAC | GLW | CZH | 02/10/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E
A Sempra Energy utility®

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

# POLE QUADRANT AND RISER IDENTIFICATION

SCALE: NOT TO SCALE

DRAWING NO: OH1403.1 UG4203.1

SHEET: 1 OF 1

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD SHOWS NEW CONSTRUCTION FOR SINGLE AND MULTIPLE CONDUIT RISERS





**FIGURE 1**
SIDE VIEW





**FIGURE 1**
FRONT VIEW





**FIGURE 2**
PREFERRED CONSTRUCTION FOR NEW SINGLE RISER WITH AND WITHOUT EXISTING RISER(S) ON POLE
G





**FIGURE 3**
NEW MULTIPLE RISER CONSTRUCTION
H





**FIGURE 4**
NEW MULTIPLE RISER CONSTRUCTION WITH RISER(S) ON POLE
J





**FIGURE 5**
ALTERNATE NEW CONSTRUCTION FOR ONE RISER UP TO 3-INCH CABLE POLE
K

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISE TO 3D FORMAT | DV | JIK | - | - | 11/11/2021 |
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E
A Sempra Energy utility

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

SCALE: NOT TO SCALE

# CABLE POLE RISER INSTALLATION

DRAWING NO: OH1404.1 UG4204.1

SHEET: 1 OF 3

© 1998 - 2021 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS

## INSTALLATION:

(A) MOUNT FIRST BRACKET LADDER ARM NO LOWER THAN 9'-6". IF THE FIRST BRACKET EXTENDS TOWARD A STREET OR DRIVEWAY, OFFSET THE UNISTRUT CHANNEL TO CLEAR LARGE VEHICLES.

(B) INSTALL AT LEAST ONE LADDER ARM BRACKET FOR EACH COUPLING JOINT OF CONDUIT - 10-FOOT MAX. DISTANCE BETWEEN BRACKETS. ALL LADDER ARM BRACKETS ARE TO BE ATTACHED TO THE POLE WITH BOLTS. NOT LAG SCREWS.

(C) REFER TO INDIVIDUAL CABLE POLE STANDARD FOR CORRECT MEASUREMENT.

(D) CENTER CONDUIT POSITION SHALL BE USED FOR MULTIPLE SDG&E SECONDARY RUNS OR SDG&E TELECOMMUNICATION CONDUIT. OTHER CONDUIT POSITIONS ON THE FRONT OF THE BRACKET SHALL BE USED FOR A SINGLE OR DOUBLE CONDUIT. THE 8 INCH UNISTRUT CHANNEL (ITEM 19) MAY BE INSTALLED FOR A SINGLE RISER WHERE NO COMMUNICATIONS IS ANTICIPATED.

(E) RISERS OF PLASTIC CONDUIT SHALL BE EPC-80 PVC SCHEDULE 80, FROM THE GROUND LINE TO A LEVEL NOT LESS THAN 8 FEET ABOVE THE GROUND LINE PER G.O. 95 RULE 54.6-E AND SDG&E CONDUIT SIZING REQUIREMENTS.

(F) FOR SINGLE RISER CONSTRUCTION, SEPARATION OF PIPE STRAPS (ITEM 8) SHALL BE 3 FEET MAXIMUM.

(G) USE FIGURE 2 FOR PREFERRED CONSTRUCTION FOR A SINGLE RISER

1. WHEN INSTALLING A SINGLE RISER.
2. WHEN ADDING A SINGLE RISER TO AN EXISTING RISER POLE. AN EXISTING SINGLE SDG&E RISER WOULD REMAIN ON THE POLE UNLESS IT IS CREATING A G.O. 95 INFRACTION. IF AN INFRACTION EXISTS, MOVE THE EXISTING RISER TO THE LADDER ARM BRACKET ALONG WITH THE NEW RISER SHOWN IN DETAIL "B".

(H) USE FIGURE 3:
WHEN INSTALLING MORE THAN ONE RISER.

(J) USE FIGURE 4:
WHEN ADDING A RISER(S) TO AN EXISTING SDG&E RISER POLE. AN EXISTING SINGLE SDG&E RISER WOULD REMAIN ON THE POLE UNLESS IT IS CREATING A G.O. INFRACTION. IF AN INFRACTION EXISTS, MOVE THE EXISTING RISER TO THE LADDER ARM BRACKET.

(K) USE FIGURE 5 FOR ALTERNATE CONSTRUCTION FOR A SINGLE RISER

1. FIELD CONDITIONS DO NOT ALLOW ROOM FOR LADDER ARM BRACKETS, (I.E. CONDUIT WOULD EXTEND INTO THE STREET, SIDEWALK, DRIVEWAY, ETC.). THIS INSTALLATION WOULD BE LIMITED TO ONE SDG&E RISER, UP TO 3" (NO OTHER RISER(S) LARGER THAN 3 INCH WOULD BE ON THE POLE). ONE HALF OF THE POLE MUST REMAIN CLEAR FOR CLIMBING SPACE AND G.O. REQUIREMENTS MUST BE FOLLOWED.
2. WHEN AN EXISTING RISER IS ALREADY ON THE POLE AND IT MAY BE RE-USED. (I.E. REMOVING A STREET LIGHT FUSE BOX FROM A POLE AND NEW CONDUIT WILL CONNECT TO THE EXISTING CONDUIT WHERE THE FUSE BOX WAS LOCATED, CUSTOMER RE-WIRE JOB, ETC.).

(L) ONE RISER ON THE POLE 3-INCH MAX. AND ONE RISER ON THE BACK SIDE OF THE LADDER ARM BRACKET 3-INCH MAX. ARE PERMITTED BACK-TO-BACK. A MAXIMUM OF TWO 4-INCH COMMUNICATIONS RISERS ARE PERMITTED ON THE BACK SIDE OF A LADDER ARM ASSEMBLY. THE ADJACENT POLE QUADRANT MUST BE VACANT TO INSTALL ANY 4 INCH RISER ON THE BACK OF THE LADDER ARM BRACKET, AND MUST REMAIN VACANT AFTER INSTALLATION.

(M) SLURRY ENCASEMENT IS REQUIRED AROUND THE ELBOW(S) FOR 5-INCH PRIMARY CONDUIT(S).

(N) EACH CONDUIT RUN BETWEEN SUBSTRUCTURES, PADS, CUSTOMER SERVICE RISERS, ETC., SHALL BE ONE SIZE CONDUIT CONTINUOUSLY, I.E. NO REDUCERS ARE ALLOWED WITHIN A CONDUIT RUN EXCEPT WHERE THE CONDUIT ENTERS A SUBSTRUCTURE OR ABOVE GROUND LEVEL ON A RISER POLE. IF A 3-INCH RISER IS ALREADY INSTALLED AND THE GRIP SIZE REQUIRES A 2-INCH RISER, A 2" TO 3" REDUCER MAY BE USED TO ACCOMMODATE THE GRIP. THE SAME WOULD APPLY TO OTHER SIZE CONDUITS AS HAS BEEN DESCRIBED. GRIPS ARE NOT REQUIRED ON SECONDARY RISERS.

(O) SPARE CONDUIT REFERS TO AN EMPTY CONDUIT THAT IS SPECIFIED BY THE PLANNER FOR OPERATING AND MAINTENANCE REQUIREMENTS.

## INSTALLATION (CONT'D):

SPARE CONDUITS SHOULD BE CONSIDERED OR INSTALLED:

1. WHEN REQUESTED BY A CUSTOMER AT HIS OWN EXPENSE, BUT NOT TO EXCEED CONDUIT LIMITATIONS IN THIS STANDARD.
2. WHEN IT IS ECONOMICAL TO INSTALL CONDUIT IN LIEU OF CONCRETE, BUT NOT TO EXCEED
3. BASED ON FUTURE CONSTRUCTION LIMITATIONS SUCH AS BENEATH BRIDGES, ROADWAYS AND RAILROAD TRACKS, BUT NOT TO EXCEED CONDUIT LIMITATIONS IN THIS STANDARD.
4. IN CONVERSION OR NEW BUSINESS PROJECTS TO ALLOW EASY BYPASS OF THE POLE DURING REMOVAL. CONDUITS INSTALLED FOR THIS PURPOSE SHALL NOT GO UP THE POLE BUT, RATHER, SHALL EXTEND PAST THE POLE A MINIMUM OF 6 FEET.

P FUTURE SPARE CONDUIT REFERS TO AN EMPTY CONDUIT SPECIFIED BY EITHER THE PLANNER OR DISTRIBUTION PLANNING FOR AREAS WITH GROWTH POTENTIAL. FUTURE FEEDER CONDUIT SPECIFIED BY DISTRIBUTION PLANNING MUST BE SUPPORTED BY THE LONG TERM FEEDER ARRANGEMENT PLAN.

(Q) COMMUNICATIONS ONLY POINT OF ATTACHMENT FOR LADDER ARM BRACKET CONSTRUCTION SHALL BE ON THE BACK SIDE OF THE ARM BRACKET ASSEMBLY, (GALVANIZED UNISTRUT PIPE CLAMPS SHALL BE USED TO SECURE THE CONDUIT). COMMUNICATIONS MAY ATTACH ON THE BACK OF THE ASSEMBLY ALONGSIDE SDG&E'S RISER.

(R) SLOPE SLURRY ENCASEMENT 1/4-INCH ABOVE GRADE OF PAVED AREA TO DRAIN WATER AWAY FROM CONDUIT RISER.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | CONDUIT SIZE | AL CABLE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNIT |
|---|---|---|---|---|---|---|---|
| 1 | COUPLING, 3" IPS DIRECT/ENCASED BURIAL | 3" | - | AS REQ'D | - | S279904 | - |
| | COUPLING, 4" DB/EB, PVC | 4" | - | AS REQ'D | - | S279936 | - |
| | COUPLING, 5" IPS, DIRECT/ENCASED BURIAL | 5" | - | AS REQ'D | - | S280032 | - |
| 2 | ELBOW, 3" SCH 80 PVC (CONDUIT RISER | 3" - 36" R | - | AS REQ'D | - | S322472 | 3"CP-B |
| | CONDUIT RISER BEND, SCHEDULE 80 4"_48" | 4" - 48" R | - | AS REQ'D | - | S322480 | 4"CP-B |
| | ELBOW, (CONDUIT RISER BEND) SCHEDULE 80, | 5" - 48" R | - | AS REQ'D | - | S322488 | 5"CP-B |
| 3 | REDUCER, 4" X 3" SCH.80, SPIGOT TO SPIGOT | 4" TO 3" | - | AS REQ'D | - | S573408 | 4-3RED |
| | REDUCER, 5" IPS TO 4" IPS, PVC SCHED | 5" TO 4" | - | AS REQ'D | - | S573424 | 5-4RED |
| 4 | PVC SCHEDULE 80 3" W/CPLG | 3" | - | AS REQ'D | - | S251552 | S80-3" |
| | CONDUIT, PVC, SCH. 80, 4" X 10' | 4" | - | AS REQ'D | - | S251584 | S80-4" |
| | CONDUIT. 5" X 10' SCH. 80 PVC | 5" | - | AS REQ'D | - | S251592 | S80-5" |
| 5 | COUPLING, PVC, SCHEDULE 80, 3" IPS | 3" | - | AS REQ'D | - | S280544 | - |
| | COUPLING, 4" PVC SCH 80 SWEDGED, PER NEMA TC2 | 4" | - | AS REQ'D | - | S280576 | - |
| | COUPLING, 5" SCH.80 PVC, SWEDGED | 5" | - | AS REQ'D | - | S280592 | - |
| 6 | COUPLING 3" PVC SCHEDULE 40, PER NEMA | 3" | - | AS REQ'D | - | S280448 | - |
| | COUPLING 4" SCHEDULE 40 PVC PER NEMA TC2 | 4" | - | AS REQ'D | - | S280480 | - |
| | COUPLING, 5" PVC SCH 40, PER NEMA TC2. | 5" | - | AS REQ'D | - | S280496 | - |
| 7 | 3" SCHEDULE 40 PVC | 3" | - | AS REQ'D | - | S251360 | S40-3" |
| | 4" SCHEDULE 40 PVC | 4" | - | AS REQ'D | - | S251392 | S40-4" |
| | CONDUIT PVC 5 IN X 10FT SCH 40, WITH | 5" | - | AS REQ'D | - | S251408 | S40-5" |
| 8 | STRAP, CONDUIT, 3 INCH, 2-1/4 INCH DIAMETER | 3" | - | AS REQ'D | - | S697920 | - |
| | STRAP, CONDUIT,4IN, TWO 1/4IN DIAMETER | 4" | - | AS REQ'D | - | S697952 | - |
| | STRAP, PIPE, 5", TWO HOLE | 5" | - | AS REQ'D | - | S697984 | - |
| 9 | GRIP, CONDUIT RISER, CLOSED DOUBLE MESH 1-COND #2 SOLID, 2" CONDUIT, 1"-1.24" | 3" | 1/C#2 SOL | AS REQ'D | - | S393984 (N) | 2G1#2A |
| | GRIP, CONDUIT RISER, CLOSED DOUBLE MESH 2 OR 3 COND #2 SOLID, 3" CONDUIT, 2"-2.49" | 3" | 2-1/C#2 SOL, 3-1/C#2 SOL | AS REQ'D | - | S394048 (N) | 3G2#2A, 3G3#2A |
| | GRIP, 4" CONDUIT RISER, CLOSED SINGLE MESH FOR #2 SOLID CABLE. | 4" | 3-1/C#2 SOL | AS REQ'D | - | S394104 (N) | 4G3#2A |
| | GRIP, CONDUIT RISER, CLOSED DOUBLE MESH 3-1COND #2 SOLID, 4" CONDUIT, 2.5"-2.99" ALSO 3-1COND 4/0 COPPER | 4" | 4/0 | AS REQ'D | - | S394080 (N) | 4G#2/0, 4G4/0C |
| | GRIP, 4" CONDUIT RISER, CLOSED SINGLE MESH FOR 350MCM CABLE. | 4" | 350 KCMIL | AS REQ'D | - | S394100 (N) | 4G-350 |

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISE TO 3D FORMAT | DV | JIK | - | - | 11/11/2021 |
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E A Sempra Energy utility

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**CABLE POLE RISER INSTALLATION**

SCALE: NOT TO SCALE

DRAWING NO: OH1404.2 UG4204.2

SHEET: 2 OF 3

© 1998 - 2021 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

## BILL OF MATERIALS: (CONT'D)

| ITEM | DESCRIPTION | QUANTITY | CONDUIT SIZE | AL CABLE | STANDARD PAGE | STOCK NUMBER | DESIGN UNIT |
|---|---|---|---|---|---|---|---|
| 9 | GRIP, 5" CONDUIT RISER, CLOSED SINGLE MESH FOR 350MCM CABLE. | AS REQ'D | 5" | 350 KCMIL | - | S394102 (N) | 5G-350 |
| | GRIP, 5" CONDUIT RISER, CLOSED SINGLE MESH FOR 750MCM OR 500MCM CABLE. | AS REQ'D | 5" | 500 KCMIL 750 KCMIL | - | S394096 (N) | 5G500C, 5G-750 |
| | GRIP, 5" CONDUIT RISER, CLOSED SINGLE MESH FOR 1000 MCM CABLE. | AS REQ'D | 5" | 1000 KCMIL | - | S394098 (N) | 5G1000 |
| 10 | PROTECTOR, NYLON CABLE | AS REQ'D | - | - | - | S558720 | - |
| 11 | BRACKET, CONDUIT STANDOFF, CONSTRUCTED | AS REQ'D | - | - | - | S167186 (X)(B) | LA-ARM |
| 12 | CHANNEL, 1-5/8" X 1-5/8" BACK TO BACK | AS REQ'D | - | - | - | S216702 (X)(B) | LA-ARM |
| 13 | NUT, STUD, 1/2" X 1-3/8" | AS REQ'D | - | - | - | S507000 | - |
| 14 | 2" UNISTRUT PIPE CLAMPS | AS REQ'D | - | - | - | S229536 (VI) | CL-2IN |
| 15 | BOLT, MACHINE, 5/8" X 16", GALV W/ NUT | AS REQ'D | - | - | OH390 | S154912 (B) | - |
| | WASHER CURVED RIB, 3" X 3" W/11/16" HOLE FOR 5/8" BOLT HOT DIPPED GALVANIZED | AS REQ'D | - | - | OH390 | S797792 (B) | - |
| | WASHER, 5/8", DOUBLE COIL SPRING, TYPE M-W, STEEL, TIN/ZINC COAT | AS REQ'D | - | - | OH390 | S798560 (B) | - |
| 16 | CLAMP, PIPE, STEEL, GALV., UNISTRUT, 4" | AS REQ'D | - | - | - | S229664 | CL-4IN |
| 17 | 5" GALV. PIPE CLAMP | AS REQ'D | - | - | - | S229668 | CL-5IN |
| 18 | CLAMP, PIPE, STEEL 3" | AS REQ'D | - | - | - | S229632 | CL-3IN |
| 19 | CHANNEL, GALV., 8" | AS REQ'D | - | - | - | S216840 (D) | - |

## NOTES:

I. ALL CABLE POLE RISERS, PRIMARY AND SECONDARY SHALL BE 3 IN MINIMUM CONDUIT.

II. THIS CONSTRUCTION IS LIMITED TO A MAXIMUM OF FOUR SDG&E RISERS (NO MORE THAN TWO PRIMARY RISER).

III. WHEN POSSIBLE, RISER SHOULD BE INSTALLED ON THE SIDE OF THE POLE OPPOSITE TRAFFIC FLOW.

IV. SPARE CONDUITS SHALL BE CAPPED JUST ABOVE GROUND LEVEL TO PREVENT MOISTURE OR WIRE ENTRY AND KEEP DEBRIS OUT, SPARES ARE NOT TO BE CONSIDERED AS A RISER.

V. WHENEVER POSSIBLE, SINGLE RISES SHOULD BE INSTALLED AWAY FROM THE TRAFFIC TOWARD THE SIDEWALK.

(VI) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR POLE STEPS, SEE OH363UG4205.

b. FOR MATERIAL REQUIREMENTS, ETC., SEE UG3944.

c. FOR POSITIONING OF RISERS INVOLVING MORE THAN ONE UTILITY, SEE OH1402UG4202.

(d) FOR NON-PORCELAIN TERMINAL MOUNTING BRACKET INSTALLATION AND MATERIALS, SEE OH1407UG4207.

(e) FOR 0 - 750V UNDERGROUND SERVICE FROM AN OVERHEAD LINE, SEE OH1414UG4214.

f. FOR TELECOMMUNICATION INSTALLATION, SEE UG4620, UG4621, UG4622, UG4623, UG4624, UG4625, AND UG4626.

g. PVC RISERS ARE NOT PERMITTED WITHIN THE CLIMBING SPACE PER G.O. 95 RULE 22.2C.

(h) FOR DEPTH REQUIREMENTS, SEE UG3370.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISE TO 3D FORMAT | DV | JIK | - | - | 11/11/2021 |
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E

A Sempra Energy utility

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**CABLE POLE RISER INSTALLATION**

SCALE: NOT TO SCALE

DRAWING NO: OH1404.3 UG4204.3

SHEET: 3 OF 3

© 1998 - 2021 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF POLE STEPS IN ACCORDANCE WITH SDG&E REQUIREMENTS.





**FIGURE 1**





**FIGURE 2**
POLE-ROOF, PARAPET, STRUCTURE CONFLICT





**FIGURE 3**
CLIMBING SPACE CONSIDERATIONS (B)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | JS | GW | MDJ | 9/28/2016 | F | DRAWING UPDATE | EDM | JAC | JES | CZH | 7/1/2020 |
| B | EDITORIAL CHANGES | - | JS | IL | MDJ | 6/23/2016 | E | NOTES UPDATE | - | JC | JS | MDJ | 1/17/2018 |
| A | UPDATE NOTES | - | JC | JE/IL | DW | 12/16/2014 | D | NOTES UPDATE | - | JS | JS | MDJ | 6/26/2017 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PERMANENT POLE STEPS



OH363.1
UG4205.1





**FIGURE 4**
VALMONT POLE STEP (J) (III)
TOP VIEW





**FIGURE 5**
VAF POLE STEP (H)
TOP VIEW





**FIGURE 4**
VALMONT POLE STEP (J) (III) (IV)
SIDE VIEW





**FIGURE 5**
VAF POLE STEP (H) (IV)
SIDE VIEW

## INSTALLATION:

(A) EIGHT FOOT MINIMUM RADIAL CLEARANCE IS REQUIRED FROM THE FIRST POLE STEP TO THE TOP OF ANY OBSTACLE WHEN THE POLE IS SET FOUR FEET OR LESS FROM THE OBSTACLE. IF THE POLE IS SET MORE THAN FOUR FEET AWAY FROM THE OBSTACLE, THIS REQUIREMENT DOES NOT APPLY.

(B) POLE STEPS SHOULD BE LOCATED NEAR THE EDGES OF THE CLIMBING SPACE BUT MUST BE LOCATED SO THEY ARE ALWAYS USABLE. FOR INSTANCE, IF VERTICAL RISERS WOULD INTERFERE WITH NORMALLY LOCATED POLE STEPS, INSTALL THE STEPS WITHIN THE CLIMBING SPACE AS SHOWN. APPLIES ONLY TO WOOD POLES.

(C) NO STEPS ALLOWED IN THIS AREA.

D. THE FOLLOWING WOOD POLES SHALL BE STEPPED:

1. POLES THAT ARE DIFFICULT TO CLIMB (E.G. SHELL ROT, LARGE CRACKS).
2. POLES THAT ARE FREQUENTLY CLIMBED BY TROUBLESHOOTER FOR MAINTENANCE OR OPERATING PURPOSES, OR, AS REQUESTED.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | JS | GW | MDJ | 9/28/2016 | F | DRAWING UPDATE | EDM | JAC | JES | CZH | 7/1/2020 |
| B | EDITORIAL CHANGES | - | JS | IL | MDJ | 6/23/2016 | E | NOTES UPDATE | - | JC | JS | MDJ | 1/17/2018 |
| A | UPDATE NOTES | - | JC | JE/IL | DW | 12/16/2014 | D | NOTES UPDATE | - | JS | JS | MDJ | 6/26/2017 |

Indicates Latest Revision | X Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION CONTINUED:

E. FIBERGLASS AND STEEL POLES THAT ARE INACCESSIBLE SHALL EITHER BE PERMANENTLY STEPPED OR HAVE PROVISIONS TO BE STEPPED CONSISTENT WITH SDG&E CONSTRUCTION STANDARDS. THE FIRST POLE STEP SHALL BE INSTALLED AT TEN FEET ABOVE THE GROUND LEVEL.

(F) POLE STEPS ON ALL POLES ARE TO BE SPACED A MINIMUM OF 15" TO 18", TEN FEET ABOVE GROUND LEVEL. THE FIRST TEN FEET OF THE POLE, STEPS ARE TO BE SPACED A MAX. OF 18".

G. TRANSMISSION POLES WITH DISTRIBUTION UNDER BUILD SHALL BE STEPPED TEN FEET FROM GROUND LEVEL AND MAY EXTEND UP TO AND ABOVE PRIMARY.

(H) POLESTEP INSTALLATION (VAF):

1. UNSCREW THE HEX NUTS AT THE END OF THE "J" BOLT TO THE END OF THE THREADS. DO NOT REMOVE THE HEX NUTS FROM THE BOLT.
2. PUSH "J" BOLT BACK INTO THE STEP TO ALLOW THE "ELBOW" TO EXTEND OUT PAST THE SLOT OPENING.
3. FEED "J" BOLT THROUGH THE PROPER STEP OPENING IN THE UTILITY POLE AND PLACE THE BACKING PLATE AGAINST THE OUTSIDE WALL OF THE POLE. MAKE SURE THE RADIUS SIDE OF THE PLATE FACES THE POLE.
4. USING THE HEX NUT, PULL THE "J" BOLT BACK OUT MAKING SURE THAT THE "ELBOW" SLIDES THROUGH THE SLOT AND FITS SNUG AGAINST THE INSIDE POLE WALL.
5. TIGHTEN FIRST HEX NUT AGAINST THE OUTSIDE OF THE STEP. DO NOT OVER TIGHTEN.
6. TIGHTEN SECOND HEX NUT TIGHTLY AGAINST THE FIRST HEX NUT.
7. VISUALLY CHECK STEP TO VERIFY IT IS INSTALLED PROPERLY.

(J) POLESTEP INSTALLATION (VALMONT):

1. INSERT L-BOLT THROUGH STEP CASTING WITH "L" ON THE INSERT SIDE OF THE CASTING.
2. INSERT "L" BOLT AND STEP CASTING INSERT INTO POLESTEP HOLE IN POLE WALL.
3. HAND TIGHTEN INSIDE HEX-NUT TO A SNUG FIT. A GENTLE WIGGLE ON THE STEP ASSEMBLY WILL ALLOW THIS.
4. USING A STANDARD WRENCH, TIGHTEN INSIDE NUT ONE TO ONE AND A HALF (1-1.5) TURNS PAST THE HAND SNUG CONDITION.
5. INSTALL SECOND HEX-NUT TO LOCK THE FIRST IN PLACE.
6. REMOVAL OF THE STEP ASSEMBLY FROM THE POLE IS ACCOMPLISHED BY REVERSING THE STEPS OUTLINED ABOVE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | COLOR | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | STEP, POLE, DRIVING TYPE (FOR WOOD POLE) (II) | -- | -- | -- | S692992 | STEP |
| 2 | STEP, POLE, VALMONT | -- | -- | -- | S693000 | -- |
| 3 | STEP, POLE, VAF | BROWN | -- | -- | S692018 | VAF-B |
| | | SILVER | -- | -- | S693012 | VAF-S |

## NOTES:

I. JOINT POLE WHERE ANOTHER PARTY OWNS THE POLE, G.O. 95 WILL BE MAINTAINED.

(II) NOT SHOWN IN FIGURES.

(III) STEP PARTS SHALL NOT BE ALTERED IN ANY MANNER. HANDLE STEP CASTINGS WITH CARE. DO NOT DROP, STRIKE OR IMPACT.

(IV) MAXIMUM ALLOWABLE LOAD OF 500LBS. A SAFETY FACTOR OF 2.5 IS INCLUDED IN THIS VALUE.

## REFERENCE:

a. POLE STEPPING JOINT USE POLES, SEE G.O. 95 RULE 91.3A.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | JS | GW | MDJ | 9/28/2016 | F | DRAWING UPDATE | EDM | JAC | JES | CZH | 7/1/2020 |
| B | EDITORIAL CHANGES | - | JS | IL | MDJ | 6/23/2016 | E | NOTES UPDATE | - | JC | JS | MDJ | 1/17/2018 |
| A | UPDATE NOTES | - | JC | JE/IL | DW | 12/16/2014 | D | NOTES UPDATE | - | JS | JS | MDJ | 6/26/2017 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PERMANENT POLE STEPS

OH363.3
UG4205.3

**SCOPE:** THIS STANDARD SHOWS GENERAL INFORMATION FOR CABLE POLES AT 12.47KV & BELOW.

**ATTENTION**

* NEW PRIMARY CABLE POLE INSTALLATIONS SHALL BE TRUCK ACCESSIBLE. EXISTING POLE LOCATIONS THAT ARE NOT TRUCK ACCESSIBLE CAN BE GRANDFATHERED BY DEVIATION.





**FIGURE 1**
CONFIGURATION 1





**FIGURE 1**
CONFIGURATION 2





**FIGURE 1**
CONFIGURATION 3

**TABLE 1**

| CLEARANCES | | | | | | |
|---|---|---|---|---|---|---|
| VOLTAGE OF LEAD WIRES CONNECTED TO TERMINALS V (V) (I) | MINIMUM SEPARATION TO CONDUCTORS BELOW | | | | | |
| | SUPPLY ON CROSSARMS W (IN) (a)(b) | | | RACK CONSTRUCTION 0-750V X (IN) (c) | CABLE 0-750V Y (IN) (d) | COMMUNICATIONS CROSSARMS AND CABLE Z (IN) (e) |
| | 0-750V | 750-7,500V | 7,500-20,000V | | | |
| 0-750 | 24 | -- | -- | 72 UNGUARDED OR 48 WITH GUARD | 72 | 36 |
| 750-7,500 | 48 | 48 | -- | | | 48 |
| 7,500-20,000 | 48 | 48 | 48 | | | 60 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) TERMINALS MAY BE BRACKET OR CROSSARM MOUNTED.
(II) 24-INCH MINIMUM RADIAL DIMENSION. (a)
(III) 18-INCH MINIMUM VERTICAL DIMENSION FROM CONDUIT EDGE OR LOWEST POINT OF CONDUCTOR LOOP. (a)
IV. USE THIS PAGE ONLY TO OBTAIN MINIMUM SEPARATIONS BETWEEN CONDUCTORS. DO NOT USE FOR CONSTRUCTION.
(V) 22'-6" MINIMUM TO GROUND.

**REFERENCE:**

(a) SEE G.O. 95 RULE 54.6F.
(b) SEE G.O. 95 TABLE 2, CASES 9, 10, 11.
(c) SEE G.O. 95 RULE 54.9E.
(d) SEE G.O. 95 RULE 54.10E
(e) SEE G.O. 95 RULE 92.1F3.

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| E | EDITORIAL CHANGES | EDM | MRF | GLW | KRG | 06/27/2022 |
| D | REVISED TO 3D FORMAT | AMP | JIK | - | - | 01/27/2022 |
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**GENERAL INFORMATION - 12.47KV & BELOW CABLE POLES**

SCALE: NOT TO SCALE

DRAWING NO: OH1406.1 UG4206.1

SHEET: 1 OF 1

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE VARIOUS METHODS OF SECONDARY CONSTRUCTION WHEN UNDERGROUND CUSTOMERS ARE SERVED FROM OVERHEAD SECONDARY.



**FIGURE 1**
TERMINAL CONSTRUCTION (a)
ISOMETRIC VIEW





**FIGURE 1**
TERMINAL CONSTRUCTION (a)
FRONT VIEW




**FIGURE 1**
TERMINAL CONSTRUCTION (a)
SIDE VIEW




**FIGURE 2**
OPEN SECONDARY "AIR MAILING"
ISOMETRIC VIEW





**FIGURE 2**
OPEN SECONDARY "AIR MAILING"
FRONT VIEW




**FIGURE 2**
OPEN SECONDARY "AIR MAILING"
SIDE VIEW




**FIGURE3**
CROSSARM CONSTRUCTION
#2 CABLE MAX.
ISOMETRIC VIEW





**FIGURE 3**
CROSSARM CONSTRUCTION
#2 CABLE MAX.
FRONT VIEW




**FIGURE 3**
CROSSARM CONSTRUCTION
#2 CABLE MAX.
SIDE VIEW




**FIGURE 4**
SECONDARY AERIAL CABLE
TANGENT CONSTRUCTION
ISOMETRIC VIEW





**FIGURE 4**
SECONDARY AERIAL CABLE
TANGENT CONSTRUCTION
FRONT VIEW





**FIGURE 4**
SECONDARY AERIAL CABLE
TANGENT CONSTRUCTION
SIDE VIEW

**INSTALLATION:**

(A) INSTALL CONDUIT ON THE BACK SIDE OF THE LADDER ARM BRACKET.

(B) INSTALL CABLE IN SCHEDULE 40 PVC UNDER ARM.

C. PVC RISER SHALL NOT BE INSTALLED IN THE CLIMBING SPACE. (b)

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) FOR RISER CONSTRUCTION, SEE OH1404UG4204.

(b) SEE G.O. 95, RULE 22.2 (C).

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | EDM | JIK | - | - | 02/23/2022 |
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**0-750V UNDERGROUND SERVICE FROM AN OVERHEAD LINE**

SCALE: NOT TO SCALE

DRAWING NO: OH1414.1 UG4214.1

SHEET: 1 OF 1

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD TO BUILD A BUCK POSITION, 12.47KV AND BELOW, THREE-PHASE CABLE POLE WITH CUTOUT MOUNTED NON-PORCELAIN TERMINALS FOR #2/0 AND SMALLER UNDERGROUND CABLE IS TO BE USED ONLY WHEN NECESSARY TO AVOID THE SETTING OF AN ADDITIONAL POLE.





**FIGURE 1**
FRONT VIEW




**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 1**
CLIMBING SPACE VIEW
PLAN VIEW

**INSTALLATION:**

A. THE CONSTRUCTION SHOWN BELOW THE BUCK ARM IS TYPICAL AND IS FOR ILLUSTRATION ONLY. FOR PROPER RISER, POTHEAD AND POTHEAD ARM CONSTRUCTION, SEE APPROPRIATE CABLE POLE STANDARDS IN THIS SECTION.

(B) TO MAINTAIN CLIMBING SPACE, BUCK ARM MINIMUM FOR THREE-PHASE CABLE POLE IS 12-FEET. BUCK ARM MINIMUM FOR SINGLE-PHASE CABLE POLE IS 10-FEET.

(C) A MINIMUM OF 48 INCHES MUST EXIST BETWEEN THE LINE ARM AND BUCK ARM TO MAINTAIN CLIMBING SPACE THROUGH THE BUCK ARM LEVEL AND UP TO THE LINE ARM LEVEL. (b)

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) ON ALL NEW CONSTRUCTION AND WHEN ADDING TO EXISTING CONSTRUCTION, NEUTRAL TO BE INSTALLED IN OUTSIDE PIN POSITION PER DM5124.

(b) SEE OH251.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| D | REVISED TO 3D FORMAT | EDM | JIK | - | - | 04/12/2022 |
| C | FORMATTING | EDM | JIK | - | - | 09/16/2021 |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 |

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**12.47KV AND BELOW CROSSARM CABLE POLE, THREE-PHASE NON-PORCELAIN TERMINALS, LINE AND BUCK**

SCALE: NOT TO SCALE

DRAWING NO: OH1418.1 UG4218.1

SHEET: 1 OF 1

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

**SCOPE:** THIS STANDARD SHOWS CONSTRUCTION OF A MOLDED VACUUM INTERRUPTER (MVI) ON A DEADEND OR TANGENT CABLE POLE UTILIZING 200A OR 600A CABLE.

**ATTENTION:**

* NEW PRIMARY CABLE POLE INSTALLATIONS SHALL BE TRUCK ACCESSIBLE. EXISTING CABLE POLE LOCATIONS THAT ARE NOT TRUCK ACCESSIBLE CAN BE GRANDFATHERED BY DEVIATION.





**FIGURE 1**
FUSING WORKFLOW CHART

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |



TABLE OF CONTENTS

TABLE OF CONTENTS





**FIGURE 2**
FRONT VIEW (XII)





**FIGURE 2**
SIDE VIEW (XII)





**FIGURE 3**
600A GROUND WIRING





**FIGURE 4**
200A GROUND WIRING

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

Indicates Latest Revision | X Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200/600A THREE-PHASE
CABLE POLE APPLICATION

OH1435.2
UG4235.2

TABLE OF CONTENTS





**FIGURE 5**
FRONT VIEW

**FIGURE 5**
SIDE VIEW

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200/600A THREE-PHASE
CABLE POLE APPLICATION

OH1435.3
UG4235.3

**ATTENTION:**

* THIS FIGURE ILLUSTRATES SINGLE-PHASE OVERHEAD CONSTRUCTION WITH TWO SINGLE-PHASE UNDERGROUND CABLES.





**FIGURE 6**
FRONT VIEW (XI)





**FIGURE 6**
SIDE VIEW (XI)

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed




SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200A SINGLE-PHASE CONSTRUCTION
CABLE POLE APPLICATION


OH1435.4
UG4235.4

TABLE OF CONTENTS


TABLE OF CONTENTS





EXAMPLE 1




EXAMPLE 2




EXAMPLE 3




EXAMPLE 4

**FIGURE 7**
VARIOUS COMMON CROSSARM AND JUMPER CONFIGURATIONS

XIII e

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200/600A
CABLE POLE APPLICATION

OH1435.5
UG4235.5





**FIGURE 8**
600A/200A CONNECTOR
200A APPLICATION ONLY








**FIGURE 9**
200A





**DETAIL 1**
THREE-PHASE SWITCH





**DETAIL 2**
SINGLE-PHASE SWITCH




**DETAIL 3**




**DETAIL 4**
OPTION 1




**DETAIL 4**
OPTION 2

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

Indicates Latest Revision | X | Completely Revised | | New Page | | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200/600A
CABLE POLE APPLICATION

OH1435.6
UG4235.6

## INSTALLATION:

A. NEW CABLE POLES SHALL HAVE A STANDARD DEPTH OF 9 FEET. IN MOST CASES, THIS WILL REQUIRE A 5-FOOT TALLER POLE.

B. THIS CONSTRUCTION IS FOR BOTH 200A AND 600A MVI CONSTRUCTION, WIRE SIZE TO MATCH PRIMARY REQUIREMENTS.

C. CONNECT OVERHEAD NEUTRAL, UNDERGROUND CONCENTRIC CABLE NEUTRAL, AND ARRESTER GROUND TO BUS UNDER CUTOUT/ARRESTOR ARM.

(D) SEAL CABLE WITH MASTIC FOR WATER TIGHT SEAL.

E. REDUCE QUANTITIES AS REQUIRED WHEN NOT USING NEUTRAL.

(F) BRUSH WIRE, INSTALL PENETROX "INHIBITOR" AND BELLEVILLE WASHER.

G. DIMENSIONS CAN VARY BASED ON CROSSARM SIZE AND/OR CONFIGURATION.

(H) REQUIRES TWO TAP LUGS PER CONNECTION.

J. ARM MAY BE DRILLED TO REPOSITION BOTTOM BRACKET BOLT ALLOWING CONDUIT TO SET FLUSH ON BOTTOM OF CROSSARM.

(K) CONCENTRIC WITH POLE GROUND, CONNECTION AREA.

(L) MAINTAIN SIX INCHES OF BARE WIRE BELOW DISCONNECT FOR PROPER GROUNDING OF UNDERGROUND CABLE.

(M) DOUBLE EQUIPMENT-ARM CONSTRUCTION IS REQUIRED FOR CONTAMINATION DISTRICT I.

N. **BEFORE MVI INSTALLATION THE CORRECT PREPROGRAMMED SETTINGS MUST BE SENT TO KEARNY AND THE MVI LOAD CURVE PROGRAM INSTALLED BEFORE IT CAN BE RELEASED FOR CONSTRUCTION AND READY FOR PICK UP BY THE CREW. SEE MVI FUSING REQUEST AND APPROVAL PROCESS FLOWCHART.**

O. PHASE MARKING SHALL BE COMPLETED USING THE PHASE TRAKKER JR. OR AP30 AND MARKED ON THE CROSS ARM AND MVI FOR ALL INSTALLATIONS.

P. REQUIRES 24/7 ACCESS FOR AERIAL LIFT/DERRICK.

(Q) MAKE UP JUMPERS SO THEY DO NOT INTERFERE WITH HANDLES NORMAL OPERATION.

(R) NEUTRAL TIE REQUIRED ON FOUR WIRE SYSTEM.

## BILL OF MATERIALS:

TABLE OF CONTENTS

| ITEM | DESCRIPTION | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | POLE MIN. 50-1 STEEL OR WOOD | -- | 1 | 303 | -- | -- |
| 2 | CROSSARM | -- | AS REQ'D | 379 | -- | -- |
| 3 | CONNECTOR, STIRRUP, BAIL, #2 TIN PLATED CU | -- | AS REQ'D | -- | S227650 | BAIL |
| 4 | CONNECTOR, WEDGE, STIRRUP OR BAIL, #2 SOLID CU | -- | AS REQ'D | 783 | -- | -- |
| 5 | SIGN HIGH VOLTAGE 8 NAILS/SCREWS | -- | AS REQ'D | -- | S647648 | HV |
| 6 | BUSHING PLUG | -- | AS REQ'D | -- | S544676 | -- |
| 7 | PIN & INSULATORS-HENDRIX | -- | AS REQ'D | 750 | -- | -- |
| 8 | ARRESTORS, 12KV | -- | AS REQ'D | 1247 | S113248 | LA12 |
| 9 | FLEXIBLE ARRESTOR GROUND STRAP (DISTRICTS I AND II) | -- | AS REQ'D | 1002 | S698754 | -- |
| 10 | WEDGE TAP CONNECTIONS (V) | -- | AS REQ'D | 784 | -- | -- |
| 11 | WIRE, HENDRIX, 1/0 STR. CU. SOFT-DRAWN, COVERED (CONCENTRIC BUS WIRE) (IX) 200A | -- | 30'-0" | 711 | S812120 | HEND1/0 |
| | WIRE, 4/0 STR. CU. SOFT-DRAWN, COVERED (CONCENTRIC BUS WIRE) (IX) 600A | -- | 30'-0" | 711 | S812126 | HEND4/0 |
| 12 | SWITCH, DISCONNECT, 27KV, 900A | -- | AS REQ'D | -- | S706670 (III) | PS900 |
| | | | | -- | S707004 (XIII) | P900D |
| | BRACKET, MOUNTING, CUTOUT | | | 397 | S166070 | CO/B |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

Indicates Latest Revision | X Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200/600A
CABLE POLE APPLICATION

OH1435.7
UG4235.7

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | | WIRE SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 13 | STRAP, ARRESTOR GROUND (V) | | -- | AS REQ'D | 1002 | S698754 | LAGND |
| 14 | CUTOUT/ARRESTOR BRACKETS | | -- | AS REQ'D | -- | S165452 | COBKT |
| 15 | MVI 600A TO 200A | | -- | SELECT | 3675 | S708416 | S63PFI |
| | MVI 600A TO 600A | | | | | S708418 | S66PFI |
| 16 | CONNECTOR, BRONZE, 2 BOLT, CONNECTOR, COPPER TAP 3/0-1000 | | -- | -- | -- | S262370 (X) | CN1000 |
| 17 | CONNECTOR, CLAMP, HOT LINE | | -- | AS REQ'D | 788 | S227680 (X) | -- |
| 18 | AERIAL BUSHING KIT FOR MVI, THREE PHASE (VI) | | -- | 1 | -- | S442500 | AKMV13 |
| 19 | LEAD WIRE, THW, LENGTH PER PHASE | 200A | 1/0 | 10'-0" | -- | S808034 (X) | -- |
| | | 600A | 500 KCMIL | | -- | S808928 | -- |
| 20 | CONNECTOR, TERMINAL COMPRESSION LUG (V) | | -- | AS REQ'D | 4174 | -- | -- |
| 21 | GROUNDING, #4 PVC GRND WIRE, RODS, & CONNECTORS | STEEL POLE | -- | 1 | 1002 | -- | GNDPSP |
| | | WOOD POLE | | | | | GNDPVC |
| 22 | CABLE GRIP FOR PRIMARY CABLE (V) | | -- | 1 | 4204 | -- | -- |
| 23 | CONDUIT, SQ. 2" X 2" X 10'-0" PVC (SQUARE) | | -- | AS REQ'D | -- | S251534 | SQC-2 |
| | CONDUIT, SCH 40, 2" X 10'-0" PVC (ROUND) | | -- | | -- | S251296 | PVC2 |
| 24 | GRIP, RISER, 5-INCH, KELLEMS (1000 AL) | | -- | AS REQ'D | 4204 | S394098 | 5G1000 |
| 25 | WIRE, POLY COVERED 4/7 STRAND COPPER | | -- | AS REQ'D | 711 | S812490 | POLY4 |
| 26 | TRXLPECN-PEJ, STR, 3-1/C (V) | | 350 KCMIL | -- | -- | S197608 | PJN350 |
| 27 | EPR-PEJ, COMP, 3-1/C (V) | | 750 KCMIL | -- | -- | S195010 | CPJ750 |
| 28 | TRXLPECN-PEJ, STR, 3-1/C (V) | | 1000 KCMIL | -- | -- | S197618 | PJI000 |
| 29 | TRXLPECN-PEJ, SOL, 3-1/C (V) | | #2 | -- | -- | S197622 | PJN3/2 |
| 30 | TRXLPECN-PEJ, STR, 3-1/C (V) | | #2/0 | -- | -- | S197606 | PJN2/0 |
| 31 | ELBOW TEE | | -- | AS REQ'D | -- | S326578 | -- |
| 32 | ELBOW TAP PLUG | | -- | AS REQ'D | -- | S547328 | -- |
| 33 | RECEPTACLE, INSULATING, 200A | | -- | AS REQ'D | -- | S204304 | -- |
| 34 | CONNECTOR, TAP LUG, 1/0 TO 500MCM CU TAP LUG BRONZE | | -- | AS REQ'D | -- | S471232 | TL1/0 |
| 35 | CONDUCTOR CONNECTOR | | 350 AL | AS REQ'D | -- | S258698 | -- |
| | | | 750 AL | | | S258704 | |
| | | | 750 AL | | | S258708 | |
| | | | 1000 AL | | | S258702 | |
| 36 | CABLE ADAPTER | | 350 AL | AS REQ'D | -- | S102027 | -- |
| | | | 750 AL | | | S102034 | |
| | | | 750 AL | | | S102051 | |
| | | | 1000 AL | | | S102050 | |
| 37 | LOADBREAK ELBOW CONNECTOR | | #2 AL | AS REQ'D | -- | S443838 | -- |
| | | | 2/0 AL | | | S443840 | |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

**NOTES:**

I. THIS APPLICATION OFFERS THE ABILITY TO PROGRAM SINGLE-PHASE AND THREE-PHASE SWITCHES FOR HIGHER LOAD AND RELIABILITY ISSUES FOR NEW AND EXISTING FACILITIES.

II. THE THREE-PHASE SWITCH WILL ALSO REDUCE THE POSSIBILITY OF FERRO-RESONANCE DURING SERVICE RESTORATION.

(III) REQUIRED IN CONTAMINATION DISTRICT 1 AND PREFERRED IN COASTAL DISTRICTS (OC, NC, BC, CM). (m)

(IV) MINIMUM 480A COPPER WIRE REQUIRED (OPTION FOR USE OF COVERED WIRE).

(V) NOT SHOWN OF FIGURES.

(VI) BRACKET IS INCLUDED.

VII. ONLY TRANSPORT IN CLOSED POSITION TO PROLONG LIFE OF UNIT.

(VIII) USE APPROPRIATE AVIAN COVER AS REQUIRED.

(IX) ALLOWED SUBSTITUTION FOR CONCENTRIC BUS WIRE SHOULD MATCH EQUIVALENT AMPERAGE.

(X) THIS ITEM IS EXEMPT.

(XI) CAN ALSO BE CONSTRUCTED WITH SINGLE MVI FOR N TYPE TRANSFORMERS.

(XII) CAN ALSO BE CONSTRUCTED WITHOUT CENTER PHASE FOR SINGLE-PHASE DELTA SYSTEM.

(XIII) PREFERRED FOR INLAND DISTRICTS (NE, RA, EA, ME).

**REFERENCE:**

a. FOR CABLE IDENTIFICATION, SEE UG3202.

b. FOR STRUCTURE/EQUIPMENT IDENTIFICATION, SEE UG3211.

c. FOR HIGH VOLTAGE DECAL, SEE UG3221.

d. FOR MVI SPECIFICATIONS, SEE UG3675.

(e) FOR POLE GROUNDING, SEE OH1002.

f. FOR SEALING JACKETED CABLE, SEE UG4108.

g. FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE, SEE UG4510.

h. FOR EQUIPMENT GROUNDING, SEE UG4512.

i. FOR GROUNDING PAD MOUNTED EQUIPMENT, SEE UG4520.

j. FOR GROUNDING HARDWARE AND CONNECTIONS, SEE UG4505.

k. FOR CABLE POLE RISERS, SEE OH1404UG4204.

(l) FOR AVIAN PROTECTION/COVER-UP, SEE OH1600 SECTION.

(m) FOR CONTAMINATION DISTRICTS, SEE OH287.

(n) FOR BONDING GENERAL INFORMATION, SEE OH1003.

o. FOR SPLICING, SEE UG4180.

(p) SEE OH750: INSULATORS.

(q) SEE OH396: INSULATOR PINS AND SPACERS.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | H | DRAWING UPDATE | EDM | DWC | GLW | KRG | 05/10/2022 |
| D | COMPLETELY REVISED | - | JCL | TR | MJC | 10/05/2012 | G | BILL OF MATERIALS UPDATE | EDM | DEC | JES | CZH | 02/08/2021 |
| C | COMPLETELY REVISED | - | JC | TR | MDC | 09/27/2012 | F | TABLE UPDATE | - | JAC | JES | CZH | 11/12/2019 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

CABLE POLE MVI/MV200/600A
CABLE POLE APPLICATION

OH1435.9
UG4235.9

**SCOPE:** THIS STANDARD SHOWS THE CONSTRUCTION METHOD FOR THREE-PHASE UNDERGROUND CABLE, UNDER 15KV WITH LESS THAN 200A CAPACITY.





**FIGURE 1** (a)
TOP VIEW





**FIGURE 1** (II)
FRONT VIEW





**FIGURE 1**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | EDM | JCE | JES | CZH | 11/09/2020 | F | | | | | | |
| B | COMPLETLY REVISED | - | JBH | IL | MDJ | 10/25/2016 | E | | | | | | |
| A | COMPLETLY REVISED | - | JBH | IL | MDJ | 09/08/2016 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |

SHEET
1 OF 4

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW CROSSARM CABLE POLE,
THREE-PHASE, 1/C PER PHASE,
NON-PORCELAIN TERMINALS

OH1440.1
UG4240.1





**FIGURE 2** (a)
TOP VIEW





**FIGURE 2** (II)
FRONT VIEW








**FIGURE 2**
SIDE VIEW




**DETAIL 1** (D) (c)




**DETAIL 2**




**DETAIL 3**
GROUND WIRING

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | EDM | JCE | JES | CZH | 11/09/2020 | F | | | | | | |
| B | COMPLETLY REVISED | - | JBH | IL | MDJ | 10/25/2016 | E | | | | | | |
| A | COMPLETLY REVISED | - | JBH | IL | MDJ | 09/08/2016 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW CROSSARM CABLE POLE,
THREE-PHASE, 1/C PER PHASE,
NON-PORCELAIN TERMINALS



OH1440.2
UG4240.2

TABLE OF CONTENTS

## INSTALLATION:

(A) NEW CABLE POLES SHALL HAVE A STANDARD DEPTH OF NINE FEET. IN MOST CASES, THIS WILL REQUIRE A FIVE-FOOT TALLER POLE.

B. REDUCE QUANTITIES AS REQUIRED WHEN NOT USING NEUTRAL OR WHEN CONSTRUCTING SINGLE-PHASE.

(C) INTERCONNECT OVERHEAD NEUTRAL AND CONCENTRIC CABLE NEUTRAL CONDUCTORS TO LIGHTNING ARRESTER GROUND. INSTALL NEUTRAL JUMPER FROM LINE TO CONCENTRIC ON ARRESTER SIDE OF POLE.

(D) BOND CUTOUTS IN HEAVY CONTAMINATION DISTRICTS. IN AREAS WHERE BONDING IS REQUIRED, TO AVOID BONDWIRE AND LIGHTNING ARRESTER GROUNDWIRE ON THE SAME CROSSARM, USE TWO CROSSARMS: ONE FOR CUTOUTS AND ONE FOR LIGHTNING ARRESTERS. (i)

(E) WRAP HALF OF EXPOSED ALUMINUM PORTION OF PIN CONNECTOR WITH SILICONE TAPE TO PREVENT CORROSION. INSERT PIN INTO BOTTOM OF CUTOUT CLAMP.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CROSSARM, FIBERGLASS, DEADEND (SIZE AS REQ'D) | 1 | 379 | -- | -- |
| 2 | CROSSARM, FIBERGLASS, TANGENT (SIZE AS REQ'D) | 1 | 379 | -- | -- |
| 3 | SIGN, "HIGH VOLTAGE" STICKER | AS REQ'D | 208 | S647650 | HV/D |
| 4 | SIGN, "PN", ADHESIVE | AS REQ'D | 208 | S648004 (X) | PN-D |
| 5 | PIN, INSULATOR (SIZE AS REQ'D) (V) | AS REQ'D | 396 | -- | -- |
| 6 | INSULATOR, POLY, VISE-TOP (SIZE AS REQ'D) | AS REQ'D | 750 | -- | -- |
| 7 | TERMINATIONS, OUTDOOR, #2 SOLID | 3 | 4111 | S732918 | CP-#2N |
| | CONNECTOR, COMPRESSION, #2 SOLID | | | S729930 | |
| | TERMINATIONS, OUTDOOR, 2/0 ALUMINUM | 3 | | S732918 | CP2/0N |
| | CONNECTOR, COMPRESSION, 2/0 ALUMINUM | | | S729934 | |
| 8 | BOLT, MACHINE, 3/4" (SIZE AS REQ'D) | AS REQ'D | 390 | -- | -- |
| 9 | WASHER, SPRING LOCK, 3/4" | AS REQ'D | 390 | S796802 (X) | LK-WSH |
| 10 | WASHER, SQUARE CURVED | AS REQ'D | | S797760 | RIBWSH |
| 11 | INSULATOR, SUSPENSION, CLEVIS, 35KV | AS REQ'D | 750 | S428958 | LONGDE |
| 12 | CLAMP, STRAIGHT LINE, DEADEND | AS REQ'D | 739 | -- | -- |
| 13 | STRAP, PIPE, GALV., 1/4", ONE HOLE | AS REQ'D | 1002 | S697302 | BOND8 |
| 14 | SCREW, SELF-TAPPING, 1 1/4", #12, 24 THREAD | AS REQ'D | 1002 | S618086 (X) | -- |
| 15 | BRACKET, CUTOUT/ARRESTER, FOR CROSSARM MOUNTING | AS REQ'D | 397 | S166070 | CO/B |
| 16 | BRACKET, DOUBLE, CUTOUT/ARRESTER FOR CROSSARM MOUNTING | 3 | | S165446 (X) | DBLBKT |
| 17 | CUTOUT, 12KV, (AS NEEDED PER FUSING REQUEST) | 3 | 1212 | -- | -- |
| 18 | FUSE HOLDER, (AS NEEDED PER FUSING REQUEST) | 3 | 1212 | -- | -- |
| 19 | COVER, CUTOUT (V) | 3 | 1640 | S289626 | CCOVSL |
| 20 | ARRESTER, LIGHTNING, 12KV | 3 | 1247 | S113248 | LA12 |
| 21 | STRAP, ARRESTER GROUND | AS REQ'D | 1002 | S698754 | LAGND |
| 22 | WIRE, COPPER, AWG 2 (CONCENTRIC BUS WIRE) | 50'-0" | 711 | S812122 | HEND2 |
| 23 | PIN, TRANSFORMER ADAPTER, LEAD THREAD, 1" | 1 | 396 | S529248 | PS/01 |
| 24 | CLAMP, HOTLINE | AS REQ'D | 788 | S227680 | -- |
| 25 | CONNECTOR, WEDGE, STIRRUP | 3 | | -- | -- |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | EDM | JCE | JES | CZH | 11/09/2020 | F | | | | | | |
| B | COMPLETLY REVISED | - | JBH | IL | MDJ | 10/25/2016 | E | | | | | | |
| A | COMPLETLY REVISED | - | JBH | IL | MDJ | 09/08/2016 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 26 | BRACKET, LADDER ARM | AS REQ'D | 1404/4204 | S167186 (X) | RSARM |
| 27 | NUT STUD 1/2" X 1 3/8" CLAMPING CHANNEL WITH SPRING | AS REQ'D | | S507000 | |
| 28 | CHANNEL, DOUBLE, GALVANIZED, 24" X 1 5/8" X 1 5/8" | AS REQ'D | | S216702 (X) | |
| 29 | WIRE, #4-7, POLY COVERED, STRANDED COPPER (ARRESTER JUMPER) | 20'-0" | -- | S8115044 | POLY4J |
| 30 | CONNECTORS, WIRE COMPRESSION, CU OR AL | AS REQ'D | 785 | -- | -- |
| 31 | GROUNDING, #4 PVC GRND WIRE, RODS, CONN-STEEL POLE | 1 | 1002 | -- | GNDPSP |
| | GROUNDING, WIRE, #4 PVC, RODS & CONNECTORS (FOR WOOD POLES) | AS REQ'D | | -- | GNDPVC |
| 32 | TAPE, SILICONE | AS REQ'D | -- | S720384 | -- |

## NOTES:

(I) INSTALL TERMINATION BY FOLLOWING MANUFACTURER'S INSTRUCTIONS INCLUDED IN KIT.

(II) USE FIGURE 1 FOR ALL NEW CONSTRUCTION AND WHEN ADDING TO EXISTING CONSTRUCTION WITH NEUTRAL ON OUTSIDE PIN POSITION. (j)

(III) NEW CONSTRUCTION SHALL USE AERIAL CABLE CONSTRUCTION FOR SECONDARY APPLICATIONS. EXISTING CONSTRUCTION CAN USE CROSSARMS FOR OPEN WIRE SECONDARY CONSTRUCTION. (h)

(IV) MINIMUM 230A COPPER WIRE REQUIRED (OPTION FOR USE OF COVERED WIRE).

(V) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) FOR ALLOWABLE WORKING AND CLIMBING SPACE, SEE OH251.

(b) FOR POLE STEPPING, SEE OH363.

(c) FOR GROUNDING METHODS, SEE OH1002.

(d) FOR FUSING, SEE OH SECTION 1200 AND UG SECTION 4300.

(e) FOR RISER POSITIONS, SEE OH1402UG4202.

(f) FOR MINIMUM VERTICAL SEPARATION PER G.O. 95, SEE OH1406UG4206.

g. FOR VISE-TOP INSULATORS, SEE OH750.

(h) FOR SECONDARY CABLE CONSTRUCTION, SEE OH612.

(i) FOR BONDING, SEE CONTAMINATION DISTRICTS OH287.

(j) SEE DM5124.2.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | EDM | JCE | JES | CZH | 11/09/2020 | F | | | | | | |
| B | COMPLETLY REVISED | - | JBH | IL | MDJ | 10/25/2016 | E | | | | | | |
| A | COMPLETLY REVISED | - | JBH | IL | MDJ | 09/08/2016 | D | FORMATTING | EDM | JIK | - | - | 09/16/2021 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW CROSSARM CABLE POLE,
THREE-PHASE, 1/C PER PHASE,
NON-PORCELAIN TERMINALS

OH1440.4
UG4240.4

**SCOPE:** THIS STANDARD ILLUSTRATES THE CONSTRUCTION METHODS FOR 3-PHASE 12KV 350-1000KCM UNDERGROUND CABLE USING 900A DISCONNECTS.





**FIGURE 1**
BACK VIEW OF ARM




**DETAIL 1**
GROUND WIRING (1)





**FIGURE 1**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 3/9/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | REVISION | - | - | PEA | JJ | 10/20/2005 | D | DRAWING UPDATE | EDM | DWC | JES | CZH | 12/11/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

SHEET
1 OF 6

THREE PHASE, CABLE-POLE-12KV,
NON-PORCELAIN 900 AMP DISCONNECT
PREFERRED METHOD

OH1442.1
UG4242.1





**FIGURE 2**
SIDE VIEW





**FIGURE 3**
SIDE VIEW
ILLUSTRATES SECOND ARM FOR BONDING





**FIGURE 4**
SIDE VIEW





**FIGURE 5**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 3/9/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | REVISION | - | - | PEA | JJ | 10/20/2005 | D | DRAWING UPDATE | EDM | DWC | JES | CZH | 12/11/2020 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS


THREE PHASE, CABLE-POLE-12KV,
NON-PORCELAIN 900 AMP DISCONNECT
OPTIONAL METHOD




OH1442.2
UG4242.2





**DETAIL 1**
FRONT VIEW
CONDUIT WITH CABLE SUPPORT BRACKETS





**DETAIL 1**
SIDE VIEW, ENLARGED
CONDUIT WITH CABLE SUPPORT BRACKETS





**DETAIL 2**
PREFERRED BRACKET
CONFIGURATION




**DETAIL 2**
OPTIONAL BRACKET
CONFIGURATION
(NOT SHOWN)




**DETAIL 3**
DOUBLE BRACKET




**DETAIL 4**
SINGLE BRACKET

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 3/9/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | REVISION | - | - | PEA | JJ | 10/20/2005 | D | DRAWING UPDATE | EDM | DWC | JES | CZH | 12/11/2020 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

THREE PHASE, CABLE-POLE-12KV,
NON-PORCELAIN 900 AMP DISCONNECT


OH1442.3
UG4242.3





**DETAIL 5**
OPTION 1
PREFERRED





**DETAIL 5**
OPTION 2





**DETAIL 6**
OPTION 1





**DETAIL 6**
OPTION 2




**DETAIL 7**
INSULATOR PIN FOR
35KV INSULATORS




DETAIL 8
35KV F-NECK INSUL ATOR
TANGENT OR SINGLE DEADEND ARM




DETAIL 9
35KV F-NECK INSULATOR
STACKED ARM

**TABLE 1**

| DESCRIPTION | A | B | C | D | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| HARDWARE POST INSULATOR STUD, FIBERGLASS,WOOD | 7 1/2" | 3 1/2" | 4 1/2" | 3/4" | S701760 | STUD-W |
| | 10" | 4" | 5/8" | 1 3/4" | S701762 | STUD-L |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 3/9/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | REVISION | - | - | PEA | JJ | 10/20/2005 | D | DRAWING UPDATE | EDM | DWC | JES | CZH | 12/11/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

THREE PHASE, CABLE-POLE-12KV,
NON-PORCELAIN 900 AMP DISCONNECT

OH1442.4
UG4242.4

TABLE OF CONTENTS

## INSTALLATION:

A. NEW CABLE POLES SHALL HAVE A STANDARD DEPTH OF 9 FEET. IN MOST CASES, THIS WILL REQUIRE A 5-FOOT TALLER POLE.

B. THIS CONSTRUCTION TO BE USED WITH 350 AND LARGER UNDERGROUND CABLE.

C. INTERCONNECT OVERHEAD NEUTRAL, AND CONCENTRIC CABLE NEUTRAL CONDUCTOR TO LIGHTNING ARRESTER GROUND.

(D) INSTALLATION OF WIRE CAN BE MADE ON EITHER SIDE OF TERMINAL COMPRESSION LUG.

(E) REDUCE QUANTITIES AS REQUIRED WHEN NOT USING NEUTRAL.

(F) BRUSH WIRE, INSTALL PENETROX "INHIBITOR" AND BELLEVILLE WASHER.

G. DIMENSIONS CAN VARY BASED ON CROSSARM SIZE AND/OR CONFIGURATION.

(H) REQUIRES TWO TAP LUGS PER CONNECTION.

(J) ARM MAY BE DRILLED TO REPOSITION BOTTOM BOLT ALLOWING CONDUIT TO SET FLUSH ON BOTTOM OF CROSSARM.

(K) CONCENTRIC WITH POLE GROUND, CONNECTION AREA.

(L) MAINTAIN SIX INCHES OF BARE WIRE BELOW DISCONNECT FOR PROPER GROUNDING OF UNDERGROUND CABLE.

(M) CENTER OF CUTOUT ARM SHALL NOT BE MOUNTED HIGHER THAN THIRTY-FIVE FEET FROM GROUND.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WIRE RANGE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 1 | CONNECTOR, WEDGE (PREFERRED) | -- | AS REQ'D | 783 | -- | -- | -- |
| 2 | CONNECTOR, TERMINAL COMPRESSION LUG | -- | AS REQ'D | 4174.2 | -- | -- | -- |
| 3 | CONNECTOR, TAP LUG, 1/0 TO 500MCM CU TAP LUG - BRONZE | -- | 12 TO 18 | -- | S471232 | TL1/0 | TL1/0 |
| 4 | CONNECTOR, CLAMP, HOT LINE | -- | 3 | 788 | S227680 (X) | -- | -- |
| 5 | CONNECTOR PIN (PREFERRED) UNDERGROUND STANDARD | -- | AS REQ'D | UG4111.2 | -- | -- | -- |
| 6 | CONNECTOR, BRONZE, 2 BOLT, CONNECTOR, COPPER TAP 3/0-1000 | -- | -- | -- | S262370 (X) | CN1000 | CN1000 |
| 7 | CONNECTOR, WEDGE, STIRRUP OR BAIL, #2 SOLID CU | -- | 3 | 783 | -- | -- | -- |
| 8 | CONNECTOR, STIRRUP, BAIL, #2 TIN PLATED CU | -- | AS REQ'D | -- | S227650 | BAIL | BAIL |
| 9 | CONDUIT, SQ. 2" X 2" X 10'-0" PVC (SQUARE) | -- | AS REQ'D | -- | S251534 | SQC-2 | SQC-2 |
| | CONDUIT, SCH 40, 2" X 10'-0" PVC (ROUND) | -- | AS REQ'D | -- | S251296 | PVC2 | PVC2 |
| 10 | EQUIPMENT, ARRESTER, LIGHTNING | -- | 3 | 1247.2 | S113248 | LA12 | LA12 |
| 11 | EQUIPMENT, POLYMER, SINGLE-DISC, 900A, SWITCH, CABLE POLE | -- | 3 | -- | S707004 (VI) | P900DC | P900DC |
| | | | | | S706670 (V) | PS900 | -- |
| 12 | GROUNDING, #4 PVC GRND WIRE, RODS, CONN-STEEL POLE (II) | -- | 1 | 1002 | -- | GNDPSP | GNDPSP |
| | GROUNDING, WIRE, #4 PVC, RODS & CONNECTORS (FOR WOOD POLES) (II) | -- | -- | -- | -- | GNDPVC | GNDPVC |
| 13 | HARDWARE, CROSSARM, FIBERGLASS, 10'-0", 4 PIN TANGENT (MINIMUM) | -- | AS REQ'D | 379 | S294378 | 4TF | 4TF |
| 14 | HARDWARE, BRACKET, DOUBLE, CUTOUT, ARRESTER | -- | 3 | -- | S165454 | DBLBKT | DBLBKT |
| 15 | HARDWARE, STAND OFF PIN, 1 3/8" (E) | -- | 2 | 396 | S529214 | PS/O1+ | PS/O1LG |
| 16 | HARDWARE, BRACKET, CABLE SUPPORT, WITH POLY | -- | 3 | 4207 | S166064 | NP-BKT | NP-BKT |
| 17 | HARDWARE, BRACKET, CUTOUT/ARRESTOR CROSSARM MOUNTING | -- | 3 | 397 | S165452 (X) | CO/B | -- |
| 18 | HARDWARE, CLAMP, STRAIGHT LINE, D.E. (AS NEEDED) (II) | -- | AS REQ'D | 739 | -- | -- | -- |
| 19 | HARDWARE, GRIP, RISER, 5-INCH, KELLEMS (1000 AL) | -- | AS REQ'D | 4204 | S394098 | 5G1000 | 5G1000 |
| 20 | HARDWARE, RISER ARM BRACKET & 24" CHANNEL (ASSEMBLY) | -- | AS REQ'D | 1404/4204 | -- | RSRARM (I) | RSRARM |
| 21 | HARDWARE, STANDOFF (350MCM AND ABOVE) (OPTIONAL) | -- | AS REQ'D | -- | S429040 (X) | -- | -- |
| 22 | HARDWARE, PIN, POST, STUD, FG/WOOD (STANDARD ARM) (II) | -- | AS REQ'D | 396.2 | S701760 | STUD-W | STUD-W |
| 23 | HARDWARE, PIN, POST, STUD, FG/WOOD (STACKED DEADEND ARM) (II) | -- | AS REQ'D | 396.2 | S701762 | STUD-L | STUD-L |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 3/9/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | REVISION | - | - | PEA | JJ | 10/20/2005 | D | DRAWING UPDATE | EDM | DWC | JES | CZH | 12/11/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

THREE PHASE, CABLE-POLE-12KV,
NON-PORCELAIN 900 AMP DISCONNECT

OH1442.5
UG4242.5

## BILL OF MATERIALS: (CONT'D)

| ITEM | DESCRIPTION | WIRE RANGE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 24 | HARDWARE,PIN, 1 3/8" COBB FORGED STEEL GALV. (II) | -- | 2 | -- | S532448 | PS1+ | PS1LG |
| 25 | INSULATOR, VICE TOP, PIN, 1 3/8", UNIVERSAL (g) | -- | 3 TO 4 | 750.2 | S429272 | IPULG | IPULG |
| 26 | INSULATOR, WHITE, NEUTRAL, "F" NECK, 1 3/8" PIN (OPTIONAL) | -- | 2 | -- | S432220 | IWN | IWN |
| 27 | INSULATOR, SUSPENSION, 35KV, POLYMER | -- | AS REQ'D | 750.3 | S428958 | LONGDE | LONGDE |
| 28 | INSULATOR, HENDRIX 35KV POLY LINE POST (II) | -- | AS REQ'D | 750 | S429144 | LP-14F | LP-14F |
| 29 | STICKER, "HIGH VOLTAGE", VINYL, ADHESIVE | -- | AS REQ'D | 208.3 | S647650 (X) | -- | -- |
| 30 | STICKER, TAGS, SWITCH NUMBER | -- | -- | 208 | -- | -- | -- |
| 31 | STICKER, "PN", VINYL, ADHESIVE | -- | AS REQ'D | -- | S648004 (X) | -- | -- |
| 32 | WIRE, 500 STR. CU, BARE (III) | -- | AS REQ'D | 711 | S813792 | BS500 | BS500 |
| 33 | WIRE, 4/0 STR. CU, SOFT-DRAWN, COVERED (CONCENTRIC BUS WIRE) | -- | 30'-0" | 711 | S812126 | HEND4/0 | HEND4/0 |
| 34 | WIRE, POLY COVERED 4/7 STRAND COPPER | -- | AS REQ'D | 711 | S815044 | POLY4J | POLY4J |
| 35 | STRAP, ARRESTER GROUND | -- | AS REQ'D | 1002 | S698754 | LAGND | LAGND |
| 36 | WIRE, POLY COVERED, #4 SOLID COPPER (POLE GROUND) | -- | AS REQ'D | 711 | S812490 | POLY4 | POLY4 |
| 37 | WILDLIFE, COVER, 900A DISCONNECT (AS REQ'D) (II) | -- | 3 | 1620.7 | S286948 | 9COCVR | 9COCVR |

## NOTES:

(I) MINIMUM CROSSARM TEN-FOOT.
(II) NOT SHOWN ON FIGURES.
(III) WIRE SIZE IS APPLICABLE TO AMPERAGE OF PRIMARY SOURCE.
(IV) MINIMUM 480A COPPER WIRE REQUIRED (OPTION FOR USE OF COVERED WIRE).
(V) REQUIRED IN CONTAMINATION DISTRICT 1 AND PREFERRED IN COASTAL DISTRICTS (OC, NC, BC, CM).
(VI) PREFERRED FOR INLAND DISTRICTS (NE, RA, EA, ME).
(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. ALLOWABLE WORKING AND CLIMBING SPACE - SEE OH251.
(b) POLE STEPPING - SEE OH363.
c. GROUNDING METHODS - SEE OH1002.
d. RISER POSITION - SEE OH1404/UG4204.
(e) MINIMUM VERTICAL SEPARATION AS PER G.O. 95 - SEE OH1406/UG4206.
(f) FOR BONDING GENERAL INFORMATION - SEE OH1003.
(g) PER CONTAMINATION DISTRICT REQUIREMENTS - SEE OH287.
(h) REFERENCE GELPACT - SEE OH783.16.
i. MINIMUM CROSSARM BOLT REQUIREMENT - SEE OH379.
(j) FIBERGLASS CROSSARM GROUNDING DETAIL OPTION, SEE OH1002.1. FIGURE 5 AND FIGURE 6.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 3/9/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | REVISION | - | - | PEA | JJ | 10/20/2005 | D | DRAWING UPDATE | EDM | DWC | JES | CZH | 12/11/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

THREE PHASE, CABLE-POLE-12KV,
NON-PORCELAIN 900 AMP DISCONNECT

OH1442.6
UG4242.6

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS A SIDE BREAK GANG OPERATED POLE TOP 900A RISER MOUNTING SWITCH FOR CIRCUIT TIES OR SECTIONALIZING PURPOSES.





**FIGURE 1**
FRONT VIEW





**FIGURE 1**
SIDE VIEW

**ATTENTION:**

* NEW PRIMARY CABLE POLE INSTALLATIONS SHALL BE TRUCK ACCESSIBLE. EXISTING CABLE POLE LOCATIONS THAT ARE NOT TRUCK ACCESSIBLE CAN BE GRANDFATHERED BY DEVIATION.





**FIGURE 1**
DETAIL A
POSITION OF HANDLE FOR
CONTROL ROD COMPRESSION





**FIGURE 1**
DETAIL D
CONFIGURATION 1





**FIGURE 1**
DETAIL D
CONFIGURATION 2
2/0 AND BELOW





**FIGURE 1**
DETAIL D
CONFIGURATION 3
350 AND ABOVE





**FIGURE 1**
DETAIL B





**FIGURE 1**
DETAIL C





**FIGURE 1**
SECTION A-A





**FIGURE 1**
SECTION B-B

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| E | REVISE TO 3D FORMAT/BILL OF MATERIALS UPDATE | DV | JIK | - | - | 3/15/2023 |
| D | FIGURE UPDATE | EDM | MRF | GLW | KRG | 5/31/2022 |
| C | FORMATTING | EDM | JIK | - | - | 9/16/2021 |

© 1998 - 2023 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

# POLE TOP SWITCH 12KV
# RISER LOADBREAK TYPE SINGLE CIRCUIT

SCALE: NOT TO SCALE

DRAWING NO: OH1444.1 UG4244.1

SHEET: 1 OF 3

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS

## TABLE 1:

| SWITCH CONFIGURATIONS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| TYPE | SWITCH WEIGHT (LBS) | Z (FT) | Y (IN) | X (IN) | W (IN) | T (IN) | U (IN) | STOCK NUMBER | DESIGN UNIT |
| CENTER PH. LEFT | 240 LBS. | 10 | 33 | 26 | 55 | 31 5/8 | 34 1/8 | S709312 | RGS10L |
| CENTER PH. RIGHT | 240 LBS. | 10 | 33 | 24 | 57 | 31 5/8 | 34 1/8 | S709310 | RGS10R |
| CENTER PH. LEFT | 250 LBS. | 12 | 33 | 36 | 69 | 31 5/8 | 34 1/8 | S709316 | RGS12L |
| CENTER PH. RIGHT | 250 LBS. | 12 | 33 | 36 | 69 | 31 5/8 | 34 1/8 | S709314 | RGS12R |
| CENTER PH. LEFT | 265 LBS. | 15 | 33 | 54 | 87 | 44 7/8 | 47 5/8 | S709318 | RGS15L |
| CENTER PH. RIGHT | 265 LBS. | 15 | 33 | 54 | 87 | 44 7/8 | 47 5/8 | S709320 | RGS15R |

## INSTALLATION:

(A) REFLECTOR STRIPS ARE REQUIRED ON ALL SECTIONALIZING/TIE SWITCHES AND SERVICE RESTORER POLES. (d)

B. NEUTRALS SHALL BE SOLIDLY TIED TOGETHER AT ALL SWITCHES REGARDLESS OF WHETHER THEY ARE NORMAL OPEN OR CLOSED. THIS INCLUDES CIRCUIT TIES. (e)

**RECIPROCATING CONTROL ROD SWITCH INSTALLATION:**

C. THE SWITCH IS SUPPLIED WITH THE CONTACTS TIED IN THE CLOSED POSITION. DO NOT CUT THESE TIES UNTIL THE SWITCH AND CONTROL ROD INSTALLATION IS COMPLETE.

D. PROVIVED V-BRACES ARE REQUIED ON THE FIFTEEN-FOOT SWITCHES.

(E) VERIFY THE POLE QUADRANT WHERE THE CONTROL ROD WILL BE INSTALLED.

F. THE OPERATION HANDLE SHOULD BE LOCATED 42 INCHES FROM GROUND GRADE, OR AT ANY INCREASED ELEVATION.

G. DRILL 13/16-INCH SWITCH MOUNTING HOLES ACCORDING TO THE DIMENSION GIVEN ON THE CONSTRUCTION DRAWING. INSTALL SWITCH WITH 3/4-INCH BOLTS AND SHEAR PLATES ARE REQUIRED BY CONSTRUCTION STANDARDS.

(H) INSTALL CONTROL ROD, WORKING FROM THE SWITCH DOWN TO THE OPERATING HANDLE. INSTALL CONTROL ROD GUIDES AS SHOWN ON THE CONSTRUCTION DRAWING. MAKE CERTAIN THAT THE SWITCH IS IN THE CLOSED POSITION PRIOR TO DRILLING HOLES FOR THE CONTROL ROD GUIDES. SWING ARM STYLE GUIDES SHOULD POINT UPWARDS AT 45 DEGREES WHEN THE SWITCH IS CLOSED. CHECK THAT 17 INCHES MINIMUM SPACE IS AVAILABLE ABOVE EYEBOLT GUIDES FOR CONTROL RODS SPLICES WHEN EYE BOLT TYPE GUIDES ARE USED (1-INCH FIBERGLASS AND 3/4-INCH PIPE ONLY). MINIMUM TWO GUIDES PER TEN-FOOT SECTION OF CONTROL ROD.

J. DRILL CONTROL HANDLE MOUNTING BOLT HOLES AT THE DESIRED LOCATION (42-INCH MINIMUM HEIGHT). ATTACH THE MANUAL OPERATION HANDLE ADJUSTING SCREW CLAMP, OR FITTING TO THE CONTROL ROD SECTION. PUT THE HANDLE IN THE "UP" POSITION. CONNECT THE CONTROL HANDLE ADJUSTING SCREW CLAMP OR FITTING TO THE CONTROL ROD. A COMPRESSIVE LOAD (20-30 LBS.) SHOULD BE FELT ON THE CONTROL AS THE CONTROL MOVES TO THE FULLY CLOSED/LOCKED POSITION. USE THE ADJUSTING SCREW TO ACHIEVE THE PROPER COMPRESSION LOAD.

K. CHECK ALL BOLTS TO ENSURE THAT THEY HAVE BEEN ADEQUATELY TORQUED.

L. CUT THE TIE WIRES ON THE SWITCH CONTACT BLADES.

M. OPERATE THE SWITCH TO OPEN. VERIFY THAT THE PADLOCKING HOLES ON THE HANDLE AND THE HANDLE BASE ALIGN, SWITCH CONTACTS FULL ENGAGED/CLOSED.

N. CLOSE THE SWITCH AND CHECK FOR COMPRESSION IN THE CONTROL ROD.

O. ADJUSTING THE CONTROL ROD COMPRESSION:

1. PULL THE HANDLE DOWNWARD TO ABOUT 45 DEGREES FROM THE VERTICAL CLOSED POSITION.
2. EXTEND THE ADJUSTING SCREW SO THAT THE SLACK IS REMOVED FROM THE CONTROL ROD AND THE HANDLE REQUIRES 20 TO 30 POUNDS OF FORCE TO MAKE IT "TOGGLE" TO THE FULLY CLOSED POSITION.
3. CHECK THAT THE CLOSE PADLOCK HOLE ON THE HANDLE AND THE HANDLE BASE ALIGN.
4. TIGHTEN THE ADJUSTING NUT/LOCK-NUT.

P. OPERATE THE SWITCH SEVERAL TIMES USING A RAPID MOTION THROUGHOUT THE HANDLE ROTATION. SWING THE HANDLE DOWN TO REMOVE THE TOGGLE LOAD AND OPERATE THE SWITCH IN ONE SWIFT MOTION WHEN OPENING THE SWITCH. CLOSE THE SWITCH USING A CONTINUOUS MOTION.

## INSTALLATION (CONT'D):

Q. VERIFY THAT THE SWITCH CONTACT BLADES ARE FULLY SEATED WHEN THE SWITCH IS CLOSED.

R. CHECK THE ARC-HORNS OR INTERRUPTERS ARE OPERATION PROPERLY. SEE THE APPROPRIATE INTERRUPTER INSTALLATION AND ADJUSTMENT INSTRUCTION SHEER INCLUDED IN THE SWITCH INSTALLATION DRAWING PACKAGE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | CALLOUTS | STANDARD PAGE | STOCK NUMBER | DESIGN UNIT |
|---|---|---|---|---|---|---|
| 1 | SWITCH, GANG OPERATED, 15KV, 600A WITH AMPRUPTER, INCLUDING 30'-0" OF CONTROL ROD | 1 | - | - | SEE TABLE 1 | - |
| 2 | ADDITIONAL 10' CONTROL ROD WITH 2 EYE NUTS AND COUPLING | 2 | (VII)(XX) | - | S602932 | I-ROD |
| 3 | FIBERGLASS CROSSARM, DEADEND | 1 | - | 379 | - | - |
| 4 | FIBERGLASS CROSSARM, TANGENT | 1 | - | 379 | - | - |
| 5 | INSULATOR, DEAD-END, 35KV, GALV, SALISBURY | 4 | - | 750 | S428958 | LONGDE |
| 6 | CLAMP, STRAIGHT LINE, DEADEND | 4 | - | 739 | - | - |
| 7 | CONNECTOR, WEDGE TYPE WITH STIRRUP (SIZE AS REQ'D) | 4 | - | 788 | - | - |
| 8 | CLAMP, HOT LINE, BRONZE (SIZE AS REQ'D) | 6 | - | 788 | - | - |
| 9 | TERMINAL, COMPRESSION, CU OR AL (SIZE AS REQ'D) | 6 | (XX) | 795 | - | - |
| 10 | CONNECTOR, TWO-BOLT FOR 4/0 COPPER | - | (XX) | - | S262336 | CN4/0 |
| | CONNECTOR, TWO-BOLT FOR 1000 KCMIL | 4 | (X)(XX) | - | S262370 | CN1000 |
| | CONNECTOR, EYE BOLT (SIZE AS REQ'D) | - | (XX) | 787 | - | - |
| 11 | TERMINAL, PIN, ALUMINUM/COPPER | 3 | (XX) | 4111 | S729944 | C1000N |
| | TERMINAL, PIN, ALUMINUM/COPPER, | - | (XX) | 4111 | S729930 | CP-#2N |
| 12 | TERMINAL, 12KV TERMINAL, POLY | 3 | - | 4111 | S727138 | C1000N |
| 13 | BRACKET, CUTOUT ARRESTER, HOT DIPPED 3/8" | 3 | - | 397 | S165454 | COABKT |
| 14 | INSULATOR, POLYMER COUPLING, 9 INCHES IN LENGTH. | 3 | - | 1355 | S429040 | - |
| 15 | BRACKET, MOUNTING CS 820 | 3 | - | - | S166064 | NP-BKT |
| 16 | ARRESTER, LIGHTNING, 10KV | 3 | - | - | S113248 | - |
| 17 | COVER, LIGHTNING ARRESTER, 4" DIAMETER | 3 | - | 1640 | S289602 | - |
| 18 | BRACKET, CUTOUT / ARRESTER CROSSARM MOUNTING | 1 | - | 397 | S165452 | COBKT |
| 19 | PIN, TRANSFORMER 1-3/8" | 1 | - | 396 | S529214 | PS/O1LG |
| 20 | PIN, INSULATOR, 12KV, FORGED STEEL, GALV | 1 | - | 396 | S532448 | PS1LG |
| 21 | INSULATOR, LINE, 12kV | 2 | - | 750 | - | - |
| 22 | BOLT, MACHINE, 3/4", GALV W/ NUT | 6 | (XX) | 390 | - | - |
| | WASHER, CURVED, RIB, 4" X 4" X 17/32", 13/16" HOLE, FOR 3/4" BOLT, GALV | 6 | (XX) | 390 | S797760 | - |
| | WASHER, 3/4", DOUBLE COIL SPRING, TYPE M-W, STEEL, TIN/ZINC COAT | 6 | (XX) | 390 | S798496 | - |
| 23 | WASHER, FLAT, ROUND, 3/4" X 2", GALV | 4 | (XX) | 390 | S800256 | - |
| 24 | BOLT, MACHINE, 5/8", GALV W/ NUT | 12 | (XX) | 390 | - | - |
| | WASHER, CURVED, RIB, 3" X 3" X 5/16", 11/16" HOLE, FOR 5/8" BOLT, GALV | 12 | (XX) | 390 | S797792 | - |
| | WASHER, 5/8", DOUBLE COIL SPRING, TYPE M-W, STEEL, TIN/ZINC COAT | 12 | (XX) | 390 | S798560 | - |
| 25 | WIRE, BARE STRAND OR POLY COVERED, (SIZE AS REQUIRED) | - | (XX) | 711 | - | - |
| 26 | PADLOCK, SCHLAGE ELECTRIC SERIES | 1 | - | - | S514848 | - |
| 27 | CONDUIT, 4" X 10FT, PVC SCHEDULE 40 | 3 | (XX) | 1404 | S251392 | S40-4" |
| 28 | CLAMP, PIPE, STEEL, GALV., UNISTRUT, 4" | 5 | (XX) | 1404 | S229664 | CL-4IN |
| 29 | CHANNEL, 1-5/8" X 1-5/8" BACK TO BACK | 5 | (XX) | 1404 | S216702 | RARM/L |
| 30 | NUT, STUD, 1/2" X 1-3/8" GALV 13 | 10 | (XX) | - | S507000 | - |
| 31 | BRACKET, CONDUIT STANDOFF, CONSTRUCTED | 5 | (XX) | 1404 | S167186 | RARM/L |

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| E | REVISE TO 3D FORMAT/BILL OF MATERIALS UPDATE | DV | JIK | - | - | 3/15/2023 |
| D | FIGURE UPDATE | EDM | MRF | GLW | KRG | 5/31/2022 |
| C | FORMATTING | EDM | JIK | - | - | 9/16/2021 |

SDGE

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**POLE TOP SWITCH 12KV**
**RISER LOADBREAK TYPE SINGLE CIRCUIT**

SCALE: NOT TO SCALE

DRAWING NO: OH1444.2 UG4244.2

SHEET: 2 OF 3

© 1998 - 2023 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**NOTES:**

I. SWITCH OPERATING RODS MAY EXTEND ONE-HALF THEIR DIAMETER INTO THE CLIMBING SPACE. (d)

(II) IN CONTAMINATION DISTRICT 1, COMPRESSION OR WEDGE CONNECTORS ARE PREFERRED. IN CONTAMINATION DISTRICTS 2 & 3, STIRRUP WEDGE CONNECTORS ARE PREFERRED FOR UG CABLE 2/0 AND BELOW, AND WEDGE CONNECTORS ARE PREFERRED FOR UG CABLE 350 AND ABOVE.

(III) CONTROL ROD IS SHOWN ROTATED 90 DEGREES TO THE RIGHT TO ALLOW FOR EXTERNAL RISERS ALONG FACE OF POLE.

(IV) SWITCH HANDLE SHOWN IN CLOSED POSITION.

(V) SWITCH HANDLE CAN BE ROTATED UP TO 180 DEGREES FROM FACE OF POLE IN EITHER DIRECTION.

(VI) ORIENT SWITCH ARM BRACE BRACKET 180 DEGREES FROM NORMAL POSITION FOR USE AS MOUNTING BRACKET FOR THE NEUTRAL STANDOFF.

(VII) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

(XX) QUANTITY SHOWN IN THE BILL OF MATERIALS ARE FROM THE SPECIFIC CONSTRUCTION THAT IS ILLUSTRATED IN THIS STANDARD. YOU MUST ADJUST THE QUANTITY BASED ON THE NEEDS OF YOUR JOB.

**REFERENCE:**

(a) FOR POLE STEPPING, SEE OH363.

b. FOR FEEDER CIRCUIT SECTIONALIZING AND PROTECTION, SEE DM6111.

c. FOR CONDUCTOR CLEARANCE, SEE G.O. 95, 54.7-A3.

(d) FOR POLE MARKING, SEE OH208.

(e) FOR NEUTRAL REQUIREMENT, SEE DM6221.

f. FOR BONDING REQUIREMENTS, SEE OH1003.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| E | REVISE TO 3D FORMAT/BILL OF MATERIALS UPDATE | DV | JIK | - | - | 3/15/2023 |
| D | FIGURE UPDATE | EDM | MRF | GLW | KRG | 5/31/2022 |
| C | FORMATTING | EDM | JIK | - | - | 9/16/2021 |

© 1998 - 2023 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**POLE TOP SWITCH 12KV**
**RISER LOADBREAK TYPE SINGLE CIRCUIT**

SCALE: NOT TO SCALE

DRAWING NO: OH1444.3 UG4244.3

SHEET: 3 OF 3

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD SHOWS ALLEY ARM CONSTRUCTION FOR 12.47KV AND BELOW, THREE-PHASE CABLE POLE USING NON-PORCELAIN TERMINALS WITH CROSSARM MOUNTED TERMINALS FOR #2/0 AND SMALLER U.G. CABLE. THIS CONSTRUCTION IS TO BE USED FOR ALL CONTAMINATION DISTRICTS.





**FIGURE 1**
TANGENT CONSTRUCTION
SIDE VIEW





**FIGURE 1**
TANGENT CONSTRUCTION
FRONT VIEW





**FIGURE 2**
DEADEND CONSTRUCTION
SIDE VIEW





**FIGURE 2**
DEADEND CONSTRUCTION
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | JIK | JES | CZH | 4/13/2020 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |

SHEET
1 OF 5

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW CABLE POLE THREE-PHASE,
1/C PER PHASE, ALLEY ARM CONSTRUCTION,
NON-PORCELAN TERMINALS

OH1447.1
UG4247.1





**FIGURE 3**
TANGENT CONSTRUCTION
SIDE VIEW





**FIGURE 3**
TANGENT CONSTRUCTION
FRONT VIEW





**FIGURE 4**
DEADEND CONSTRUCTION
SIDE VIEW





**FIGURE 4**
DEADEND CONSTRUCTION
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | JIK | JES | CZH | 4/13/2020 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | | | | | | |





**FIGURE 5**
TANGENT CONSTRUCTION
CLIMBING SPACE






**FIGURE 6**
DEADEND CONSTRUCTION
CLIMBING SPACE




**DETAIL 1** (D)





**FIGURE 7**
TANGENT CONSTRUCTION
CLIMBING SPACE







**FIGURE 8**
DEADEND CONSTRUCTION
CLIMBING SPACE




**DETAIL 2**




**DETAIL 3** (F)
GROUND WIRING

## INSTALLATION:

A. NEW CABLE POLES SHALL HAVE A STANDARD SETTING DEPTH OF 9'. IN MOST CASES THIS WILL REQUIRE A 5' TALLER POLE.

B. THIS CONSTRUCTION TO BE USED WITH #2/0 AND SMALLER UNDERGROUND CABLE.

(C) REDUCE QUANTITIES AS REQUIRED WHEN NOT USING NEUTRAL.

(D) BOND CUTOUTS IN HEAVY CONTAMINATION DISTRICTS AS SHOWN ON STANDARD 287. IN AREAS WHERE BONDING IS REQUIRED, TO AVOID BONDWIRE AND LIGHTNING ARRESTER GROUNDWIRE ON THE SAME CROSSARM, USE TWO CROSSARMS; ONE FOR CUTOUTS AND ONE FOR LIGHTNING ARRESTERS. USE MATERIAL ITEMS (1), (14), (18) AND (29) WHEN ADDING CROSSARM.

**TABLE 1**

(E)

| UG CABLE SIZE AWG OR KCMIL, AL | OH JUMPER COND SIZE, AWG OR KCMIL, CU | OH NEUT JUMPER SIZE | | | CABLE POLE NEUT SIZE (CU) UNDER POTHEAD ARM OR TRIPLE TERM BRKT |
|---|---|---|---|---|---|
| | | CU | AL | - | |
| 2 | 4 | 6 | 2 | - | #6 PER PHASE |
| 2/0 | 4 | 6 | 2 | - | #6 PER PHASE |

(F) INTERCONNECT OVERHEAD NEUTRAL AND CONCENTRIC CABLE NEUTRAL CONDUCTORS TO LIGHTNING ARRESTER GROUND.

(G) WRAP ONE HALF OF EXPOSED ALUMINUM PORTION OF PIN CONNECTOR WITH SILICONE TAPE (S/N 720384) TO PREVENT CORROSION. INSERT THE PIN INTO THE BOTTOM OF THE CUTOUT CLAMP. BEFORE TIGHTENING THE CLAMP, BEND THE TOP OF THE PIN (APPROX. 1-1/2") AT A 90° DEGREE ANGLE.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | JIK | JES | CZH | 4/13/2020 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | QUANTITY FIG. 1 | QUANTITY FIG. 2 | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 1 | CROSSARM, 3-3/4" X 5-3/4" X 10'-0" | | 3 | 3 | 380.2 | - | - |
| 2 | BRACE, DIAGONAL ALLEY ARM, 7' | | 2 | 2 | - | S164352 | - |
| 3 | BRACE, ANGLE CROSSARM, 4' | | 1 | 1 | - | S164032 | - |
| 4 | BOLT, SPACE, GALV, 5/8" X (LENGTH AS REQ'D), 4 SQ FLAT WASH, 1DBL COIL SPR WASH (C) | | 1 | - | 392.1 & .2 | - | - |
| 5 | BOLT, MACH, GALV, 5/8" X (LENGTH AS REQ'D), 2 SQ FLAT WASH, 1 DBL COIL SPR WASH | | 1 | 2 | 392.1 & .2 | - | - |
| 6 | BOLT, SPACE, GALV, 5/8" X (LENGTH AS REQ'D), 2 SQ WASH 2 DBL COIL SPR WASH | | 1 | 1 | 392.1 & .2 | - | - |
| 7 | PIN, INSULATOR, STRAIGHT, 12KV, (C) OR | 1" | 10 | 3 | - | S532706 (X) | - |
| | | 1-3/8" | | | | S532448 | - |
| 8 | BOLT, MACH, GALV, 5/8" X (LENGTH AS REQ'D), 1 DBL COIL SPR WASH | | 1 | 1 | 392.1 & .2 | - | - |
| 9 | BOLT, MACH, GALV, 1/2" X 7", 1 RD WASH, 1 DBL COIL SPR WASH | | 2 | 2 | 392.1 & .2 | S678528 | - |
| 10 | BOLT, MACH, GALV, 5/8" X (LENGTH AS REQ'D), 1 SQ WASH, 1 DBL COIL SPR WASH | | 1 | 1 | 392.1 & .2 | - | - |
| 11 | SIGN, HIGH VOLTAGE, & 8 ROOFING NAILS | | 2 | 2 | - | S647648 | - |
| | | | | | | S492224 | - |
| 12 | INSULATOR, LINE, 12KV | | 8 | 3 | 750.3 | - | - |
| 13 | INSULATOR, LINE, 12KV, NEUTRAL (C) | | 2 | 2 | - | S429216 | - |
| 14 | BOLT SPACE, GALV, 5/8" X (LENGTH AS REQ'D), 3 SQ FLAT WASH, 2 RD AND 2 DBL COIL SPRING WASHER & 2 NUTS | | - | 4 | 392.1 & .2 | - | - |
| 15 | CLEVIS, DEADEND, 5/8" BOLT, STEEL (C) | | - | 4 | - | S235712 | - |
| 16 | INSULATOR, SUSPENSION, 12KV , CLEVIS (C) | | - | 4 | 750.4 | S431650 | - |
| 17 | CLAMP, STRAIGHT LINE, D.E. (C) | | - | 4 | 739-743 | - | - |
| 18 | WIRE, #8, BARE SOLID ANNEALED COPPER | FT | - | 10 | - | S812928 | - |
| | | LB | - | 1 | | | |
| 19 | CUTOUT, FOR CURRENT LIMITING FUSE | | 3 | 3 | 1206 | - | - |
| 20 | WIRE, BARE STRANDED COPPER, (OH JUMPERS) | | 36' | 36' | 715 | - | - |
| 21 | CONNECTOR, WIRE COMPRESSION (SIZE AS REQ'D) | | AS REQ'D | | 784-786 | - | - |
| 22 | WIRE, #6, BARE STRANDED COPPER | | 12' | 12' | - | S813536 | - |
| 23 | WIRE, BARE STRANDED COPPER OR ACSR/AW BARE, (OH NEUTRAL JUMPER) (F) | | 16' | 16' | 711/715 | - | - |
| 24 | CONDUIT, PVC, TYPE 2, SCHEDULE 40, 1" | | 22' | 22' | - | S251202 (X) | - |
| 25 | STRAPS, PIPE, GALV, 1", & 6D NAILS, GALV | | AS REQ'D | | - | S697792 | - |
| 26 | BRACKET, CUTOUT/ARRESTER, FOR CROSSARM MOUNTING | | 3 | 3 | - | S165446 (X) | - |
| 27 | ARRESTER, LIGHTNING W/48" COVERED LEAD WIRE | | 3 | 3 | 1247 | S113256 | 10KTVA |
| 28 | WIRE, BARE STRANDED COPPER (UNDER POTHEAD ARM) (E) | | 12' | 12' | 715 | - | - |
| 29 | BRACKET, ARRESTER OR CUTOUT | | AS REQ'D | | - | S166070 | - |
| 30 | TERMINALS, UNDERGROUND CABLE | | 3 | 3 | 4111 | - | - |
| 31 | FUSE, CURRENT-LIMITING, SIZE AS SPECIFIED ON WORK ORDER | | 3 | 3 | 1207 | - | - |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | JIK | JES | CZH | 4/13/2020 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW CABLE POLE THREE-PHASE,
1/C PER PHASE, ALLEY ARM CONSTRUCTION,
NON-PORCELAN TERMINALS

OH1447.4
UG4247.4

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | | QUANTITY FIG. 1 | QUANTITY FIG. 2 | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 32 | FLEXIBLE ARRESTER GROUND STRAP | | AS REQ'D | | - | S698754 | - |
| 33 | #4 CU SOLID GROUND WIRE, PVC COVERED | | 50' | 50' | - | S812490 | GNDPVC |
| 34 | RISER CONSTRUCTION | | - | - | 1400/4200 | - | - |
| 35 | BRACKET, LADDER ARM | | AS REQ'D | | 1404/4204 | S167186 (X) | - |
| 36 | NUT, CLAMPING CHANNEL, W/SPRING, 1/2" | | AS REQ'D | | 1404/4204 | S503488 | - |
| 37 | CHANNEL, DOUBLE GALV, 24" | | AS REQ'D | | 1404/4204 | S216702 (X) | - |
| 38 | WIRE #6 THW | FT. | 12' | | - | S808288 | - |
| | | LB. | 3 | | | | |
| 39 | GROUND ROD, 5/8" X 8', COPPERWELD | | 1 | 1 | - | S603074 (X) | GNDPVC |
| 40 | COPPER BONDED GROUND CONNECTOR | | 1 | 1 | - | S259010 | - |
| 41 | GALVANIZED STAPLES FOR PVC COVERED GROUND WIRE | | AS REQ'D | | - | S678564 (X) | - |
| 42 | HOT LINE CLAMP | | 3 | 3 | 788 | S227680 | - |

## TABLE 2

| UG MACRO UNITS | | |
|---|---|---|
| CABLE SIZE | W/ LADDER ARMS | W/O LADDER ARMS |
| 3C-#2/0 AL | CP2/0L | CP#2/0 |
| 3C-3#2 AL | CP3#2L | CP-3#2 |

TABLE OF CONTENTS

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) ON ALL NEW CONSTRUCTION AND WHEN ADDING TO EXISTING CONSTRUCTION, NEUTRAL TO BE INSTALLED IN OUTSIDE PIN POSITION PER DESIGN MANUAL PAGE 5124.2.

(b) ALLOWABLE WORKING AND CLIMBING SPACE - SEE STANDARD. 251.

(c) POLE STEPPING - SEE STANDARD. 363/4205.

d. GROUNDING METHODS - SEE PAGE 1002.5.

e. SEE STANDARD SECTION 1200/4300 FOR FUSING.

(f) RISER POSITION - SEE STANDARD 1402/4202.

(g) MINIMUM VERTICAL SEPARATION AS PER G.O. 95 - SEE STANDARD. 1406/4206.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATE | EDM | JIK | JES | CZH | 4/13/2020 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW CABLE POLE THREE-PHASE,
1/C PER PHASE, ALLEY ARM CONSTRUCTION,
NON-PORCELAN TERMINALS

OH1447.5
UG4247.5

**SCOPE:** THIS STANDARD SHOWS 6 OR 7 CONDUCTOR CABLE POLE WITH 900A HOOKSTICK SWITCHES FOR 350 KCM AND LARGER U.G. CABLE.

**ATTENTION:**

* NEW PRIMARY CABLE POLE INSTALLATIONS SHALL BE TRUCK ACCESSIBLE. EXISTING CABLE POLE LOCATIONS THAT ARE NOT TRUCK ACCESSIBLE CAN BE GRANDFATHERED BY DEVIATION.





**FIGURE 1**
FRONT VIEW




**FIGURE 2** (12)
GROUND WIRING





**FIGURE 1**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 08/13/2021 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | EDITORIAL CHANGES | EDM | MRF | FRC | KRG | 05/31/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 6

12.47KV AND BELOW DEADEND CABLE POLE,
6 OR 7 CONDUCTORS 1/C PER PHASE, HOOKSTICK SWITCHED,
NON-PORCELIAN TERMINALS

OH1451.1
UG4251.1





**FIGURE 3**
SIDE VIEW





**FIGURE 4**
SIDE VIEW
ILLUSTRATES SECOND ARM FOR BONDING





**FIGURE 5**
SIDE VIEW





**FIGURE 6**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 08/13/2021 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | EDITORIAL CHANGES | EDM | MRF | FRC | KRG | 05/31/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW DEADEND CABLE POLE,
6 OR 7 CONDUCTORS 1/C PER PHASE, HOOKSTICK SWITCHED,
NON-PORCELIAN TERMINALS

OH1451.2
UG4251.2





**FIGURE 7**
15'-0" ARM 6 HOOKSTICK DISCONNECT SWITCHES AND LIGHTNING ARRESTER BRACKETS MOUNTING DETAIL








**FIGURE 7**
CONDUIT WITH CABLE SUPPORT BRACKETS SIDE VIEW





**DETAIL 1**
PREFERRED BRACKET CONFIGURATION




**DETAIL 1**
OPTIONAL BRACKET CONFIGURATION (NOT SHOWN)




**DETAIL 2**
DOUBLE BRACKET




**DETAIL 2**
SINGLE BRACKET

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 08/13/2021 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | EDITORIAL CHANGES | EDM | MRF | FRC | KRG | 05/31/2022 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW DEADEND CABLE POLE,
6 OR 7 CONDUCTORS 1/C PER PHASE, HOOKSTICK SWITCHED,
NON-PORCELIAN TERMINALS

OH1451.3
UG4251.3




OPTION 1
PREFERRED


OPTION 2

**DETAIL 3**


OPTION 1

OPTION 2


**DETAIL 4**




**DETAIL 6**
INSULATOR PIN FOR
35KV INSULATORS




**DETAIL 5**
35KV F-NECK INSULATOR
TANGENT OR SINGLE DEADEND ARM




**DETAIL 5**
35KV F-NECK INSULATOR
STACKED ARM

**TABLE 1**

| DESCRIPTION | A | B | C | D | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| HARDWARE POST INSULATOR STUD, FIBERGLASS,WOOD | 7 1/2" | 3 1/2" | 4 1/2" | 3/4" | S701760 | STUD-W |
| | 10" | 4" | 5/8" | 1 3/4" | S701762 | STUD-L |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 08/13/2021 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | EDITORIAL CHANGES | EDM | MRF | FRC | KRG | 05/31/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW DEADEND CABLE POLE,
6 OR 7 CONDUCTORS 1/C PER PHASE, HOOKSTICK SWITCHED,
NON-PORCELIAN TERMINALS

OH1451.4
UG4251.4

TABLE OF CONTENTS

## INSTALLATION:

A. NEW CABLE POLES SHALL HAVE A STANDARD DEPTH OF 9 FEET. IN MOST CASES, THIS WILL REQUIRE A 5-FOOT TALLER POLE.

B. THIS CONSTRUCTION TO BE USED WITH 350 AND LARGER UNDERGROUND CABLE.

C. INTERCONNECT OVERHEAD NEUTRAL, AND CONCENTRIC CABLE NEUTRAL CONDUCTOR TO LIGHTNING ARRESTER GROUND.

(D) INSTALLATION OF WIRE CAN BE MADE ON EITHER SIDE OF TERMINAL COMPRESSION LUG.

(E) REDUCE QUANTITIES AS REQUIRED WHEN NOT USING NEUTRAL.

(F) BRUSH WIRE, INSTALL PENETROX "INHIBITOR" AND BELLEVILLE WASHER.

G. DIMENSIONS CAN VARY BASED ON CROSSARM SIZE AND/OR CONFIGURATION.

(H) REQUIRES TWO TAP LUGS PER CONNECTION.

(J) ARM MAY BE DRILLED TO REPOSITION BOTTOM BOLT ALLOWING CONDUIT TO SET FLUSH ON BOTTOM OF CROSSARM. (k)

(K) CONCENTRIC WITH POLE GROUND, CONNECTION AREA.

(L) MAINTAIN SIX INCHES OF BARE WIRE BELOW DISCONNECT FOR PROPER GROUNDING OF UNDERGROUND CABLE.

(M) CENTER OF CUTOUT ARM SHALL NOT BE MOUNTED HIGHER THAN THIRTY-FIVE FEET FROM GROUND.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WIRE RANGE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 1 | CONNECTOR, WEDGE (PREFERRED) | -- | AS REQ'D | 783 | -- | -- | -- |
| 2 | CONNECTOR, TERMINAL COMPRESSION LUG | -- | AS REQ'D | 784/4174 | -- | -- | -- |
| 3 | CONNECTOR, TAP LUG, 1/0 TO 500MCM CU TAP LUG - BRONZE | -- | AS REQ'D | -- | S471232 | TL1/0 | TL1/0 |
| 4 | CONNECTOR, CLAMP, HOTLINE | -- | 6 | 788 | S227680 (X) | -- | -- |
| 5 | CONNECTOR PIN (PREFERRED) UNDERGROUND STANDARD | -- | AS REQ'D | 4111 | -- | -- | -- |
| 6 | CONNECTOR, BRONZE, 2 BOLT, CONNECTOR, COPPER TAP 3/0-1000 | -- | -- | -- | S262370 (X) | CN1000 | CN1000 |
| 7 | CONNECTOR, WEDGE, STIRRUP OR BAIL, #2 SOLID CU | -- | 6 | 783 | -- | -- | -- |
| 8 | CONNECTOR, STIRRUP, BAIL, #2 TIN PLATED CU | -- | AS REQ'D | 788 | S227650 | BAIL | BAIL |
| 9 | CONDUIT, SQ. 2" X 2" X 10'-0" PVC (SQUARE) | -- | AS REQ'D | -- | S251534 | SQC-2 | SQC-2 |
| | CONDUIT, SCH 40, 2" X 10'-0" PVC (ROUND) | -- | AS REQ'D | -- | S251296 | PVC2 | PVC2 |
| 10 | EQUIPMENT, ARRESTER, LIGHTNING | -- | 6 | 1247 | S113248 | LA12 | LA12 |
| 11 | EQUIPMENT, POLYMER, SINGLE-DISC, 900A, SWITCH, CABLE POLE | -- | 6 | -- | S707004 (VI) | P900D | P900D |
| | | | | | S706670 (V) | PS900 | -- |
| 12 | GROUNDING, #4 PVC GRND WIRE, RODS, CONN-STEEL POLE (II) | -- | 1 | 1002 | -- | GNDPSP | GNDPSP |
| | GROUNDING, WIRE, #4 PVC, RODS & CONNECTORS (FOR WOOD POLES) (II) | -- | | -- | -- | GNDPVC | GNDPVC |
| 13 | HARDWARE, CROSSARM, FIBERGLASS, 15'-0", 6 PIN TANGENT (FOR STEEL POLES) | -- | AS REQ'D | 379 | S294370 | 6LTF | 6LTF |
| | HARDWARE, SGALRM 6 PIN 15FT 12KV STD W/6FT ANGLE BR (FOR WOOD POLES) | | | 380 | S293712 | 6L | 6L |
| 14 | HARDWARE, BRACKET, DOUBLE, CUTOUT, ARRESTER | -- | 6 | -- | S165454 | DBLBKT | DBLBKT |
| 15 | HARDWARE, STAND OFF PIN, 1 3/8" (E) | -- | 2 | 396 | S529214 (X) | PS/O1+ | PS/O1LG |
| 16 | HARDWARE, BRACKET, CABLE SUPPORT, WITH POLY | -- | 6 | 4207 | S166064 | NP-BKT | NP-BKT |
| 17 | HARDWARE, BRACKET, CUTOUT/ARRESTOR CROSSARM MOUNTING | -- | 6 | 397 | S165452 (X) | CO/B | -- |
| 18 | HARDWARE, CLAMP, STRAIGHT LINE, D.E. (AS NEEDED) (II) | -- | AS REQ'D | 739 | -- | -- | -- |
| 19 | HARDWARE, GRIP, RISER, 5-INCH, KELLEMS (AS REQ'D) | -- | 6 | 1404/4204 | -- | -- | -- |
| 20 | HARDWARE, RISER ARM BRACKET & 24" CHANNEL (ASSEMBLY) | -- | AS REQ'D | 1404/4204 | -- | RSRARM (I) | RSRARM |
| 21 | HARDWARE, STANDOFF (350MCM AND ABOVE) (OPTIONAL) | -- | AS REQ'D | -- | S429040 (X) | -- | -- |
| 22 | HARDWARE, PIN, POST, STUD, FG/WOOD (STANDARD ARM) (II) | -- | AS REQ'D | 396 | S701760 | STUD-W | STUD-W |
| 23 | HARDWARE, PIN, POST, STUD, FG/WOOD (STACKED DEADEND ARM) (II) | -- | AS REQ'D | 396 | S701762 | STUD-L | STUD-L |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 08/13/2021 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | EDITORIAL CHANGES | EDM | MRF | FRC | KRG | 05/31/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

12.47KV AND BELOW DEADEND CABLE POLE,
6 OR 7 CONDUCTORS 1/C PER PHASE, HOOKSTICK SWITCHED,
NON-PORCELIAN TERMINALS

OH1451.5
UG4251.5

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | WIRE RANGE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | SAP CU |
|---|---|---|---|---|---|---|---|
| 24 | HARDWARE,PIN, 1 3/8" COBB FORGED STEEL GALV. (II) | -- | 2 | -- | S532448 | PS1+ | PS1LG |
| 25 | INSULATOR, VICE TOP, PIN, 1 3/8", UNIVERSAL (g) | -- | AS REQ'D | 750 | S429272 | IPULG | IPULG |
| 26 | INSULATOR, WHITE, NEUTRAL, "F" NECK, 1 3/8" PIN (OPTIONAL) (VII) | -- | AS REQ'D | -- | S432220 | IWN | IWN |
| 27 | INSULATOR, SUSPENSION, 35KV, POLYMER | -- | AS REQ'D | 750 | S428958 | LONGDE | LONGDE |
| 28 | INSULATOR, HENDRIX 35KV POLY LINE POST (II) | -- | AS REQ'D | 750 | S429144 | LP-14F | LP-14F |
| 29 | STICKER, "HIGH VOLTAGE", VINYL, ADHESIVE | -- | AS REQ'D | 208 | S647650 (X) | -- | -- |
| 30 | STICKER, TAGS, SWITCH NUMBER (VII) | -- | -- | 208 | -- | -- | -- |
| 31 | STICKER, "PN", VINYL, ADHESIVE (VII) | -- | AS REQ'D | -- | S648004 (X) | -- | -- |
| 32 | WIRE, 500 STR. CU, BARE (III) | -- | AS REQ'D | 711 | S813792 | BS500 | BS500 |
| 33 | WIRE, 4/0 STR. CU, SOFT-DRAWN, COVERED (CONCENTRIC BUS WIRE) | -- | 30'-0" | 711 | S812126 | HEN4/0 | HEN4/0 |
| 34 | WIRE, POLY COVERED 4/7 STRAND COPPER | -- | AS REQ'D | 711 | S815044 | POLY4J | POLY4J |
| 35 | STRAP, ARRESTER GROUND | -- | AS REQ'D | 1002 | S698754 | LAGND | LAGND |
| 36 | WIRE, POLY COVERED, #4 SOLID COPPER (POLE GROUND) | -- | AS REQ'D | 711 | S812490 | POLY4 | POLY4 |
| 37 | WILDLIFE, COVER, 900A DISCONNECT (AS REQ'D) (II) (VII) | -- | 6 | 1620 | S286948 | 9COCVR | 9COCVR |

## NOTES:

(I) MINIMUM CROSSARM 15-FOOT.
(II) NOT SHOWN ON FIGURES.
(III) WIRE SIZE IS APPLICABLE TO AMPERAGE OF PRIMARY SOURCE.
(IV) MINIMUM 480A COPPER WIRE REQUIRED (OPTION FOR USE OF COVERED WIRE).
(V) REQUIRED IN CONTAMINATION DISTRICT 1 AND PREFERRED IN COASTAL DISTRICTS (OC, NC, BC, CM).
(VI) PREFERRED FOR INLAND DISTRICTS (NE, RA, EA, ME).
(VII) NOT SHOWN ON FIGURES.
(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR ALLOWABLE WORKING AND CLIMBING SPACE, SEE OH251.
(b) FOR POLE STEPPING, SEE OH363.
c. FOR GROUNDING METHODS, SEE OH1002.
d. FOR RISER POSITION, SEE OH1404UG4204.
(e) FOR MINIMUM VERTICAL SEPARATION AS PER G.O. 95, SEE OH1406UG4206.
(f) FOR BONDING GENERAL INFORMATION, SEE OH1003.
(g) FOR CONTAMINATION DISTRICT REQUIREMENTS, SEE OH287.
(h) FOR REFERENCE GELPACT, SEE OH783.
i. FOR MINIMUM CROSSARM BOLT REQUIREMENT, SEE OH379.
(j) FOR FIBERGLASS CROSSARM GROUNDING DETAIL OPTION, SEE OH1002.
(k) FOR CROSSARM DRILLING, SEE OH379.


TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FIGURE UPDATE | EDM | DWC | JES | CZH | 08/13/2021 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | JJ | 10/20/2005 | D | EDITORIAL CHANGES | EDM | MRF | FRC | KRG | 05/31/2022 |

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE MVR (MOLDED VACUUM RECLOSER) FOR CABLE POLE APPLICATIONS AS A LINE SWITCH, SERVICE RESTORER OR TIE SWITCH OR BRANCH LINE EQUIPMENT ISOLATION UNIT FOR NEW CONSTRUCTION. LINE SOURCE CAN BE CONSTRUCTED DEADEND OR TANGENT.

**ATTENTION:** THIS INSTALLATION REQUIRES 24/7, ALL WEATHER VEHICLE ACCESS. A TELECOM COORDINATION FORM MUST BE SUBMITTED BEFORE DESIGN BEGINS TO DETERMINE COMMUNICATION REQUIREMENTS.




© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SHEET 1 OF 10

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS


ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.1
UG4252.1


TABLE OF CONTENTS





**ELASTIMOLD MVR SWITCH WIRING DETAIL** (I)





**SCHEMATIC DIAGRAM**




**GROUND WIRE DETAIL** (b) (c)




**SIDE VIEW**




**3/4 VIEW**

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

SHEET 2 OF 10

OH1452.2
UG4252.2

TABLE OF CONTENTS

## INSTALLATION:

(A) RTU TO BE MOUNTED TEN FEET FROM GROUND LEVEL TO BOTTOM OF RTU CABINET WHEN NOT SUBJECT TO TRAFFIC CONTACT. IF VULNERABLE TO VEHICLE DAMAGE, MOUNT RTU 13' - 6" FROM GROUND LEVEL TO BOTTOM OF RTU CABINET.

B. CONTROL, PT TERMINAL BLOCK-RELAY, AND ANTENNA CONNECTIONS ARE TO BE MADE BY KEARNY CREW. LINE CREW MOUNTS MVR SWITCH TO OLE AND LEAVES CONTROL CABLE AND VOLTAGE CABLE ON SITE OR WITH KEARNY CREW. IF THE CONTROL & VOLTAGE CABLES ARE LEFT ON SITE, DO NOT REMOVE THEM FROM PLASTIC BAG OR REMOVE CAPS. WATER ENTRY WILL DAMAGE THE CABLES.

(C) DELINEATOR/REFLECTOR STRIPS ARE REQUIRED ON ALL SECTIONALIZING/TIELINE SWITCHES AND SERVICE RESTORER POLES. (d)

D. IN AVIAN PROTECTION AREAS, USE APPROPRIATE AVIAN COVER-UP. (e)

E. ALL MVR SITES REQUIRE ALL WEATHER, 24/7 VEHICLE ACCESS FOR AERIAL LIFTS AND DERRICK TRUCKS.

F. ONLY STEEL POLES ARE TO BE USED FOR THIS CONSTRUCTION, POLE LOADING CALCULATIONS SHALL BE COMPLETED AND ARCHIVED FOR ALL INSTALLATIONS FOR NEW AND EXISTING POLES.

G. COIL ANY EXCESS CONTROL CABLE AND ATTACH TO MVR POLE MOUNT BRACKET WITH PLASTIC TIES.

H. ALL MVR SITES SHALL BE PHASE IDENTIFIED WITH THE AP30. THE CROSSARM SHALL BE MARKED FOR "A", "B", AND "C" PHASES. BOTTOM OF THE MVR SHALL BE MARKED FOR "A", B", AND "C" PHASES. CABLE SHALL BE MARKED AND MATCH "A/1", "B/2", AND "C/3" PHASE MARKING.

(J) WHEN USING COVERED WIRE, A VISE-TOP WILL BE USED WITH NYLON JAWS. WHEN USING ALUMINUM WIRE, A VISE-TOP WILL BE USED WITH ALUMINUM JAWS. WHEN USING COPPER WIRE, A VISE-TOP WILL BE USED WITH BRONZE JAWS. THERE ARE NO EXCEPTIONS TO THESE RULES.

(K) IF THE CIRCUIT IS A FOUR-WIRE SYSTEM, THE SYSTEM NEUTRAL SHALL BE CONNECTED TO THE POLE AND THE CONCENTRIC NEUTRAL IN THE UNDERGROUND SYSTEM.

(L) THE LADDER ARM, LOCATED 15 INCHES BELOW THE MVR RACK, SHALL HAVE WIRING HARNESS AND POWER CONDUITS TERMINATED AT ONE INCH BELOW THE MVR RACK.

(M) THE POTENTIAL TRANSFORMER (PT) SHALL BE CONNECTED TO THE 12KV CIRCUIT IN DELTA, DIRECTLY TO THE LINE, #4/7 COVERED WIRE AND AVIAN COVERS ARE REQUIRED ON THE PT.

(N) GROUNDING OF THE ARRESTERS, MVR RACK, YAGI ANTENNA, AND THE MVR RELAY CONTROLLER BOX IS REQUIRED.

(O) PLEASE REFERENCE JUNE 2020 NEWSLETTER; THE MVR SHALL NOT BE INSTALLED INSIDE HFTD TIER 2 OR 3 WITHOUT PRIOR APPROVAL OF EDE & SPACE.

TABLE OF CONTENTS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | ASSEMBLY UNIT |
|---|---|---|---|---|---|
| 1A, B | STEEL POLE REQUIRED IN THE TIER 2 & TIER 3 AREAS SELECT THE FINISH NEEDED BELOW | - | - | - | - |
| 1A | POLE, STEEL GALVANIZED 50-1 (MINIMUM HEIGHT) | 1 | 354.4 | S549604 | - |
| 1B | POLE, STEEL WEATHERING 50-1 (MINIMUM HEIGHT) | 1 | 354.4 | S550420 | - |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.3
UG4252.3

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | ASSEMBLY UNIT |
|---|---|---|---|---|---|
| 2 | FIBERGLASS CROSSARM, DEADEND, 10' | AS REQ'D | - | S294372 | 6DF |
| 3 | BOLT, SPACE, GALV, 3/4" X (LENGTH AS REQ'D) 2 SQUARE, CURVED & 2 COIL SPRING WASHERS | AS REQ'D | 392 | - | - |
| 4 | SWITCH, DISCONNECT, 14.4KV, 900A | 3 | - | S707006 | D900 |
| 5 | SIGN, HIGH VOLTAGE STICKER | AS REQ'D | - | S647650 | - |
| 6 | SCREWS, SELF TAPPING, 1-1/4", #12, 24 THREADED | AS REQ'D | - | S618082 | - |
| 7 | INSULATOR, SUSPENSION, 12KV, LONG DEADEND | AS REQ'D | - | S428958 | LONGDE |
| 8 | CLAMP, STRAIGHT LINE, D.E. | AS REQ'D | 739-743 | - | - |
| 9 | WIRE, #8, BARE SOLID ANNEALED COPPER | 30' | - | S812928 | BOND8 |
| 10 | STRAP, PIPE, GALV. 1/4", ONE HOLE | AS REQ'D | - | S697302 | - |
| 11 | LEAD WIRE, 0-2/0, 200AMP 1/0 POLY | 30' | 4242.4 | S812108 | CW1/0 |
| | LEAD WIRE, 350MCM, 600AMP 4/0 POLY | 30' | 4242.4 | S812106 | CW500 |
| | LEAD WIRE, 750MCM-1000MCM, 600AMP 500MCM POLY | 30' | 4242.4 | S812102 | CW4/0 |
| 12 | CONNECTOR, WIRE, WEDGE (SIZE AS REQ'D) | AS REQ'D | 784 | - | - |
| 13 | TAPE, HIGH VOLTAGE, SELF FUSING, SCOTCH 70 | AS REQ'D | - | S720384 | - |
| 14 | TAPE, HIGH VOLTAGE, LINELESS RUBBER, SCOTCH 130C | AS REQ'D | 1272.8 | S720480 | - |
| 15 | TAPE, HIGH VOLTAGE, VINYL, SCOTCH SUPER 88 | AS REQ'D | - | S720600 | - |
| 16 | TERMINAL, COMPRESSION, CU OR AL (SIZE AS REQ'D) | AS REQ'D | 794-795 | - | - |
| 17 | PIN, INSULATOR, 12KV, 1" | AS REQ'D | 396 | S532704 | PS1 |
| 18 | INSULATOR, LINE 12KV TANGENT, VICE TOP | AS REQ'D | 750 | - | - |
| 19 | FIBERGLASS, CROSSARM, TANGENT, 10' | AS REQ'D | - | S294374 | 6TF |
| 20 | WIRE, POLY COPPER, (SIZE AS REQ'D WITH MINIMUM SIZE EQUAL TO LINE CONDUCTOR AMPACITY OR GREATER) | 25' | - | - | - |
| 21 | SIGN, PN DECAL | 2 | 208 | S648002 | PN-D |
| 22 | GRIP, RISER, KELLEMS (SIZE AS REQUIRED) | 1 | 4204.3 | - | - |
| 23 | ELASTIMOLD RECLOSER/SWITCH SCADA COMPATIBLE, 800A, INCLUDES: MOUNTING BRACKET, INTERNAL VOLTAGE SENSOR, AND 12000/120 VOLT (O) | 1 | 3675.2 | S571970 | EM-SW OR EM-SR |
| 24 | CONTROLLER, SEL 651R2, COMPATIBLE WITH ELASTIMOLD SWITCH, INCLUDES: 40' FT. 32-PIN CONFIG. CONTROL CABLE (IV) | 1 | - | S274578 | - |
| | TRANSCEIVER, MDS RADIO (IV) | AS REQ'D | - | S749500 | SOTRAN |
| | TRANSCEIVER, MDS RADIO SPREADSPECTRUM (IV) | AS REQ'D | - | S749504 | SSTRAN |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | ASSEMBLY UNIT |
|---|---|---|---|---|---|
| 25 | BOLT, MACH, GALV, 3/4" X (LENGTH AS REQ'D), 1 SQUARE CURVED RIBBED & 1 COIL SPRING WASHER | 4 | 392 | - | - |
| 26 | BUSHING COVER, TRANSFORMER | 2 | 1630.1 | S289190 | BSHCOV |
| 27 | POLY COVERED 4/7 STRAND COPPER | AS REQ'D | - | S815044 | POLY4J |
| 28 | FLEXIBLE ARRESTER GROUND STRAP | AS REQ'D | - | S698754 | LAGND |
| 29 | ARRESTER, LIGHTNING, 12KV | 3 | 1247 | S113248 | LA12 |
| 30 | GRIP, CONTROL CABLE, MVR | 1 | - | S392408 | - |
| 31 | LADDER ARM BRACKET | - | 1401.1 | S167184 | RARM/L |
| 32 | 2' DOUBLE UNISTRUT ARM | - | 1401.1 | S216700 | |
| 33 | 1/2" CLAMPING CHANNEL NUT W/SPRING | - | 1401.1 | S503488 | |
| 34 | 5/8" GALVANIZED BOLTS (LENGTH AS REQUIRED) | AS REQ'D | 392.1, .2 | - | - |
| 35 | NUT STUD 1/2" X 1-3/8", CLAMPING UNISTRUT | AS REQ'D | 1401.1 | S507000 | - |
| 36 | 2" SCHEDULE 40 PVC | AS REQ'D | 4204.3 | S251296 | S40-2" |
| 37 | 3" SCHEDULE 40 PVC | AS REQ'D | 4204.3 | S251360 | S40-3" |
| 38 | 4" SCHEDULE 40 PVC | AS REQ'D | 4204.3 | S251392 | S40-4" |
| 39 | 5" SCHEDULE 40 PVC | AS REQ'D | 4204.3 | S251408 | S40-5" |
| 40 | 2" UNISTRUT PIPE CLAMP | AS REQ'D | 4204.3 | S229536 | CL-2IN |
| 41 | 3" UNISTRUT PIPE CLAMP | AS REQ'D | 4204.3 | S229632 | CL-3IN |
| 42 | 4" UNISTRUT PIPE CLAMP | AS REQ'D | 4204.3 | S229664 | CL-4IN |
| 43 | 5" UNISTRUT PIPE CLAMP | AS REQ'D | 4204.3 | S229668 | CL-5IN |
| 44 | WEATHER HEAD 2" | 1 | - | S203290 | - |
| 45 | NIPPLE, PIPE 2" X 7", ALUMINUM (IV) | 1 | - | - | ANTXMB |
| 46 | BOLT, MACH GALV, 5/8" X 14" | 1 | - | S154880 | |
| 47 | CENTERING WASHER, GALV | 2 | - | S795520 | |
| 48 | CABLE, FLEXIBLE, 1/2" COAXIAL SCADA ANTENNA (IV) | AS REQ'D | - | S191906 | ANTCAB |
| 49 | CONNECTOR, COAXIAL, STRAIGHT (IV) | 2 | - | S254170 | - |
| 50 | GROUNDING BALL STUD, 5/8" X 3" SHANK | 3 | - | S700100 | GDSTUD |
| 51 | TAG "CONTROLS" | 1 | 204 | - | - |
| 52 | PADLOCK, SCHLAGE ELECTRIC SERIES | 2 | - | S514848 | - |

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.5
UG4252.5

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | ASSEMBLY UNIT |
|---|---|---|---|---|---|
| 53 | TAG, SWITCH NUMBER (IV) | 2 | 204 | - | - |
| 54 | DECAL "SCADA" "INFORM S.C.O. UPON ENTRY" (IV) | 1 | 207 | S301934 | - |
| 55 | VISIBILITY STRIP (C) | 1 | 208 | S304064 | - |
| 56 | #4 CU SOLID GROUND WIRE, PVC COVERED | 50' | - | S812490 | GNDPVC |
| 57 | GROUND ROD, 5/8" X 8', COPPERWELD | 1 | - | S603072 | GNDPVC |
| 58 | COPPER BONDED GROUND CONNECTOR | 1 | - | S259010 | GNDPVC |
| 59 | GROUND ENHANCING POWER SOLUTION (GEM) | AS REQ'D | - | S424390 | - |
| 60 | BRACKET, LIGHTNING ARRESTER | 3 | 397 | S166070 | LA/BKT |
| 61 | ANTENNA, SCADA, COMMUNICATION, BROADBAND & CONNECTORS | 1 | - | S109570 | ANT |

## NOTES:

(I) SEL 651R2 CONTROLLER REQUIRES 120-VOLT SUPPLY COMING FROM THE SOURCE SIDE USING A PT MOUNTED TO THE MVR SWITCH FRAME.

(II) PLANNER TO SPECIFY QUADRANT OF POLE FOR ANTENNA MOUNT WITH DATA FROM THE "SCADA TELECOMMUNICATIONS COORDINATION" FORM. SEE PROJECT MANAGEMENT INTRANET SITE FOR FORMS.

III. THE NEW MVR SWITCH COMES WITH INTERNAL AND SUPPLEMENTAL VOLTAGE SENSORS AND DO NOT NEED EXTERNAL LINDSEY SENSORS INSTALLED.

(IV) ITEMS SUPPLIED BY KEARNY.

## REFERENCES:

a. POLE STEPPING, SEE STANDARD 363.

(b) GROUNDING METHODS, SEE STANDARD 1002.

(c) TRENCH GROUNDING, SEE STANDARD 4510.

(d) DELINEATOR/REFLECTOR STRIPS, SEE STANDARD 208.

(e) AVIAN PROTECTION, SEE STANDARD 1610.

f. CABLE PULLING LIMITATIONS, SEE STANDARD 4003.

(g) MINIMUM CONDUIT SIZES, SEE STANDARD 4002.3

h. CABLE POLE RISER INSTALLATION, SEE STANDARD 4204.

i. ALLOWABLE WORKING AND CLIMBING SPACE, SEE STANDARD 251.

j. MINIMUM VERTICAL SEPARATION AS PER G.O. 95, SEE STANDARD 1406/4206.

k. CABLE IDENTIFICATION, SEE STANDARD 3202.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.6
UG4252.6

## Instructions for Applying Animal Guard Taping

1. To begin the coverup of the recloser bushings, first remove the three preinstalled supplemental voltage sensors attached to the vertical NEMA-4 pad terminals.




Once the supplemental sensors are removed, apply the Scotch 70 Self Fusing Tape (**stock# S720384**) to the base of each NEMA-4 vertical terminal with enough wraps to cover the entire metal surface.





TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

After applying the Scotch 70 tape to the NEMA-4 vertical terminal bases, make the high voltage connections to the terminal as required. Apply a layer of Scotch 130C Tape (**Stock #S720480**) over the area covered by the Scotch 70 tape until the Scotch 130C is no longer visible.




4. REATTACH THE SUPPLEMENTAL VOLTAGE SENSORS BACK TO THE VERTICAL NEMA-4 BUSHINGS USING A RATCHET WRENCH AT A TORQUE SETTING OF 25 FT-LBS. MAKE SURE TO RECONNECT THE SMALL CANNON PLUG FROM THE BOTTOM OF THE SUPPLEMENTAL SENSORS INTO THE RECEPTACLES FOUND ON THE FRAME OF THE RECLOSER FOR EACH PHASE.





TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.8
UG4252.8

5. Once the external sensors have been reattached, continue applying the Scotch 70 tape to the remaining exposed metal surface on the NEMA-4 vertical terminals until a complete coverup is made.




6. After applying the Scotch 70, apply the Scotch 130C to the rest of the area until the Scotch 130C covers up the entire section.





TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.9
UG4252.9

After applying coverup with the Scotch 70 and 130C tape, apply the Scotch Super 88 Tape (**Stock #S720600**) to the entire the NEMA-4 vertical terminals.




Repeat Steps 1-7 for each of the 3 NEMA-4 vertical bushing terminals.

Repeat Steps 2-3 and 5-7 for each of the 3 NEMA-4 horizontal bushing terminals. These terminations do not have any external voltage sensor devices.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | PEI | - | - | 02/18/2019 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 03/01/2018 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JC | TR | MDJ | 10/25/2016 | D | EDITORIAL CHANGES | PEI | JA | JES | CZH | 10/12/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

ELASTIMOLD MVR SWITCH AND SCADA 651R2 CONTROLLER CABLE POLE

OH1452.10
UG4252.10

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| | **FUSES** |
| 4302 | FUSE APPLICATION GUIDE |
| 4305 | CUTOUT ASSEMBLY-CMU, SMD20, INTERCHANGEABLE |
| 4306 | OVERHEAD 12KV CURRENT-LIMITING FUSE INSTALLATION |
| 4307 | FUSES USED IN OVERHEAD CONSTRUCTION |
| 4309 | FUSES USED ON 1200 KVAR PAD MOUNTED CAPACITOR |
| 4310 | CURRENT-LIMITING TO SM-4 FUSE CONVERSION FOR PME SWITCH |
| 4311 | CURRENT-LIMITING FUSES |
| 4312 | CURRENT-LIMITING AND SOLID BLADE FUSE TABLE |
| 4313 | EXPULSION FUSE TABLE |
| 4314 | TRANSFORMER FUSING TABLES |
| | **FAULT INDICATORS** |
| 4344 | SEL 8301 WIRELESS FAULT INDICATOR |
| 4352 | AUTOMATIC FAULT INDICATOR-SELF RESETTING, HOT STICK OPERABLE |
| 4354 | CAPACITIVE TEST POINT FAULTED INDICATOR |
| 4355 | AUTOMATIC FAULT INDICATOR INSTALLATION |
| 4359 | OVERHEAD FAULT INDICATOR-SELF RESETTING, HOT STICK OPERABLE |
| 4360 | LOAD TRACKER FAULT INDICATOR |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 09/28/2020 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JES | JES | CZH | 01/14/2020 | E | 4308 MOVED TO FMO | GLC | RSL | JES | CZH | 12/12/2021 |
| A | ADDED 4354 | - | JS | JS | CZH | 07/10/2018 | D | ADDED UG4360 | EDM | ADW | GLW | CZH | 07/29/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FUSES AND FAULT INDICATORS
TABLE OF CONTENTS

**SCOPE:** THIS STANDARD DESCRIBES A GENERAL GUIDE FOR EXPULSION AND CURRENT-LIMITING FUSE APPLICATIONS AND REFERENCE TO THE SPECIFIC STANDARDS PAGE.

**TABLE 1**

| FUSE TYPE | DISTRIBUTION APPLICATION | CONSTRUCTION STANDARD |
|---|---|---|
| BUSSMAN TYPE MDS | USED IN EKSTROM LIMITER ADAPTER TO LIMIT FAULT CURRENT TO CUSTOMER SERVICE PANEL | FMO UG4303 |
| KEARNEY & RTE TYPE B | USED IN OVERHEAD CUTOUTS FOR CABLE POLE CONSTRUCTION | OH1206UG4306 |
| VARIOUS TYPES | VARIOUS TYPES OF FUSES USED ON THE OVERHEAD DISTRIBUTION SYSTEM | OH1207UG4307 |
| GENERAL ELECTRIC TYPE J-1 | USED TO FUSE 12KV (P.T) TRANSFORMER INSIDE CABINET OF PAD-MOUNTED CAPACITOR | UG4309 |
| COMBINED TECHNOLOGY TYPE X LIMITER MC-GRAW EDISON TYPE NXC | USED TO FUSE CAPACITORS INSIDE CABINET OF PAD-MOUNTED CAPACITOR | UG4309, UG4311, UG4312 |
| NELSON TYPE E | NOT APPROVED FOR USE | -- |
| GENERAL ELECTRIC TYPE EJO-1 COMBINED TECHNOLOGY TYPE EOD | FUSING SINGLE- PHASE AND THREE-PHASE LATERALS FROM FUSE CABINETS. THREE-PHASE PORTABLE SWITCH (GREEN BOX) (a) | UG4311 & UG4312 |
| MC-GRAW EDISON TYPE NX | FUSING SINGLE-PHASE AND THREE-PHASE LIVEFRONT TRANSFORMER (YP, HP, HQ, HAP, HAQ, HLP, HMP, HPP), SINGLE-PHASE GREEN BOX, G&W OIL FUSED CUTOUTS, OLD THREE-PHASE FUSE COMPARTMENT (b) | UG4311 |
| KEARNEY TYPE A | FUSING SINGLE-PHASE LATERALS FROM LOW PROFILE FUSE CABINET FOR REPLACEMENT OF EXISTING UNITS ONLY (c) | -- |
| KEARNEY & RTE TYPE B | FUSING THREE-PHASE LATERALS FROM FUSED SWITCHING CABINET AND RETROFITTING S&C FUSE CABINETS (d) | UG4311 & UG4312 |
| RTE/ELRP KEARNEY/TYPE B COMBINED TECHNOLOGY TYPE BOI | USED IN WALL MOUNTED AND SUBSURFACE FUSE CABINETS, ALSO IN PAD-MOUNTED PMH-9 & -11 SWITCHGEAR AND 1990 OR NEWER S&C MINI-RUPTER FUSE CABINET, ALSO FOUND ON VAULT WALLS | UG4311 & UG4312 |
| X-LIMITER | USED IN PME-9 AND 11 SWITCHGEAR AND PAD-MOUNTED CAPACITOR | UG4311 & UG4312 |
| BURNDY TYPE PF8 | USED IN LOADBREAK ELBOWS TO FUSE SINGLE-PHASE TRANSFORMERS AND SMALL LATERALS | UG4312 |
| ELASTIMOLD TYPE EFX | USED IN LOADBREAK ELBOWS TO FUSE SINGLE-PHASE TRANSFORMERS AND SMALL LATERALS, FUSED TEST CANISTER (FTC), AND VACUUM-SWITCH CIRCUIT TESTER (VCT) | UG4312 |
| GENERAL ELECTRIC | USED IN D&W (G.E.) OIL FUSED CUTOUTS | UG4313 |
| S&C TYPE SM-4 | USED IN SM-4 HOLDER (TRANSFORMER) 1000 KVA OLDER S&C MINI-RUPTER | UG4313 |
| S&C TYPE SM-5 | USED IN SM-5 HOLDER SUBSTATION CAPACITORS, LIMITED DISTRIBUTION APPLICATION | UG4313 |
| -- | TRANSFORMER FUSING TABLES | UG4314 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) REFER TO UG3512, FMO UG3513.

(b) REFER TO FMO UG3599.109.

(c) REFER TO FMO UG3599.104.

(d) REFER TO FMO UG3599.105-108, 111, 112.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | REVISION | - | - | - | JJ/MF | 8/21/2006 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FUSE APPLICATION GUIDE



UG4302.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE CMU CUTOUT ASSEMBLY, PREPARED FOR USE ON THE 4KV AND 12KV ELECTRIC SYSTEM IN TIER 2 & TIER 3 AREAS.





**FIGURE 1**
CUTOUT BODY WITH FUSE





**FIGURE 2**
FIREFLY




**FIGURE 3**
ASSEMBLED CUTOUT BODY WITH FUSE AND FIREFLY

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | FUSEHOLDER, POLYMER BODY, WITH END FITTINGS FOR CMU FUSE BARREL, CMU, CURRENT RANGE UP TO 150A | -- | -- | S298018 | CMU |
| 2 | FIRELY FOR 100A AND SMALLER SMU/CMU FUSES (c) | -- | -- | S423608 | |
| 3 | FUSE, BARREL, REFER TO SIZES | -- | 1207/4307 | -- | -- |
| 4 | FITTINGS, END, UPPER & LOWER, FOR CMU FUSES (III)(a) | -- | -- | S368690 | -- |

**NOTES:**

I. KEARNY TYPE HX CUTOUTS ARE NO LONGER AVAILABLE. FOR APPLICATIONS IN TIER 2 & TIER 3 AREAS, CMU/SMD20 CUTOUT BODY AND CMU/SMU FUSES WILL NOW BE USED.

II. THE PACKAGE CONTAINS THE CMU CUTOUT BODY AND UPPER AND LOWER END FITTINGS.

(III) TROUBLESHOOTER: END FITTINGS CAN BE ORDERED SEPARATELY.

IV. DO NOT DISCARD END FITTING FROM AN ASSEMBLED USED OR BLOWN FUSE.

V. WHEN ASSEMBLING END FITTINGS TO THE FUSE BARREL, MAKE SURE NOT TO OVER TIGHTEN BOLTS. FINGER TIGHTEN AND HALF A TURN WITH A WRENCH WILL SUFFICE.

VI. USE ON 2.4KV - 12KV.

VII. CROSSARM MOUNTING BRACKETS ARE INCLUDED WITH THE MATERIALS SUPPLIED BY THE OH DESIGN UNITS (USED ON DESIGN BY LOCATION JOBS). BRACKETS MUST BE ORDERED SEPARATELY ON MANUALLY PREPARED FIELD MEMO JOBS. (b)

a. DOUBLE CUTOUT & ARRESTER MTG BKT = S165454 (X)

b. CUTOUT OR ARRESTER MTG BKT = S165452 (X)

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

(a) SEE OH1207UG4307.

(b) SEE OH397.

(c) SEE OH1208.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | RSL | JES | CZH | 03/09/2020 | F | | | | | | |
| B | DRAWING UPDATE | - | JCE | JS | CZJ | 03/18/2019 | E | EDITORIAL CHANGES | EDM | CWB | JES | CZH | 09/30/2021 |
| A | ORGINAL ISSUE | - | GW | JS | MDJ | 04/01/2018 | D | FORMATTING | EDM | JIK | - | - | 09/28/2020 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE SMD20 CUTOUT ASSEMBLY, SECOND CHOICE FOR USE ON THE 4KV AND 12KV ELECTRIC SYSTEM IN TIER 2 & TIER 3 AREAS.

**CAUTION:**

* NOT FOR USE ON CABLE POLES DUE TO POSSIBILITY OF CONTACT WITH PHASE WIRES WHEN OPENED.





**FIGURE 1**
CUTOUT BODY WITH FUSE





**FIGURE 2**
FIREFLY



**FIGURE 3**
ASSEMBLED CUTOUT BODY WITH FUSE AND FIREFLY

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | FUSEHOLDER, POLYMER BODY, WITH END FITTINGS FOR SMU FUSE BARREL SMD20, CURRENT RANGE UP TO 200A (VII) | -- | -- | S298022 | SMD20 |
| 2 | FIREFLY FOR 100A AND SMALLER SMU/CMU FUSES (c) | -- | -- | S423608 | |
| 3 | FUSE, BARREL, REFER TO SIZES | -- | 1207/4307 | -- | -- |
| 4 | FITTINGS, END, UPPER & LOWER, END FOR SMU FUSES (III)(a) | -- | -- | S368660 | -- |

**NOTES:**

I. KEARNY TYPE HX CUTOUTS ARE NO LONGER AVAILABLE. FOR APPLICATIONS IN TIER 2 & TIER 3 AREAS, CMU/SMD20 CUTOUT BODY AND CMU/SMU FUSES WILL NOW BE USED.

II. THE PACKAGE CONTAINS THE SMD20 CUTOUT BODY AND UPPER AND LOWER END FITTINGS.

(III) TROUBLESHOOTER: END FITTINGS CAN BE ORDERED SEPARATELY.

IV. DO NOT DISCARD END FITTING FROM AN ASSEMBLED USED OR BLOWN FUSE.

V. WHEN ASSEMBLING END FITTINGS TO THE FUSE BARREL, MAKE SURE NOT TO OVER TIGHTEN BOLTS. FINGER TIGHTEN AND HALF A TURN WITH A WRENCH WILL SUFFICE.

VI. USE ON 2.4KV - 12KV.

(VII) CROSSARM MOUNTING BRACKETS ARE INCLUDED WITH THE MATERIALS SUPPLIED BY THE OH DESIGN UNITS (USED ON DESIGN BY LOCATION JOBS). BRACKETS MUST BE ORDERED SEPARATELY ON MANUALLY PREPARED FIELD MEMO JOBS. (b)

a. DOUBLE CUTOUT & ARRESTER = S165454 (X)

b. CUTOUT OR ARRESTER = S165452 (X)

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

(a) SEE OH1207UG4307.

(b) SEE OH397.

(c) SEE OH1208.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | RSL | JES | CZH | 03/09/2020 | F | | | | | | |
| B | DRAWING UPDATE | - | JCE | JS | CZJ | 03/18/2019 | E | EDITORIAL CHANGES | EDM | CWB | JES | CZH | 09/30/2021 |
| A | ORGINAL ISSUE | - | GW | JS | MDJ | 04/01/2018 | D | FORMATTING | EDM | JIK | - | - | 09/28/2020 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE POLYMER INTERCHANGEABLE CUTOUT BODY.





**FIGURE 1**
POLYMER INTERCHANGEABLE CUTOUT
WITH FUSE AND FIREFLY





**FIGURE 2**
FIREFLY





**FIGURE 3**
FUSEHOLDERS

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | CURRENT RANGE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CUTOUT BODY, INTERCHANGEABLE WITHOUT FUSEHOLDER (IV) | 0-300A | -- | -- | S298024 (VI) | NPCO-1 |
| | | | -- | -- | S298020 (VI) | NPCO |
| | | | -- | -- | S298026 (VII) | |
| 2 | FUSEHOLDER, 100A, WITH SOLID CAP AND ARC SHORTENING ROD, FOR USE IN CUTOUT BODY ITEM #4 (II) (III) | FUSE 5 THRU 100A | -- | -- | S413394 | X100FH |
| 3 | FIREFLY FOR 100A QA FUSE DOORS (II) (III) | | -- | -- | S423606 | |
| 4 | FUSEHOLDER, 200A, WITH SOLID CAP, FOR USE IN CUTOUT BODY ITEM #4 (c) | FUSE 125 THRU 200A | -- | -- | S413396 | X200FH |

**NOTES:**

I. TO BE USED ONLY IN TIER 1 AREAS.

(II) ITEMS 2, 3 AND 4 ARE INTERCHANGEABLE WITH CUTOUT BODY ITEM 1 REGARDLESS OF MANUFACTURER.

(III) CUTOUTS SHALL BE BONDED IF INSTALLED IN CONTAMINATION DISTRICT 1. (d)

(IV) CROSSARM MOUNTING BRACKETS ARE INCLUDED WITH THE MATERIALS SUPPLIED BY THE OH DESIGN UNITS (USED ON DESIGN BY LOCATION JOBS). BRACKETS MUST BE ORDERED SEPARATELY ON MANUALLY PREPARED FIELD MEMO JOBS. (a)

a. DOUBLE CUTOUT & ARRESTER MTG BKT = S165454 (X)

b. CUTOUT OR ARRESTER MTG BKT = S165452 (X)

V. USE ON 2.4 - 12KV.

(VI) FOR USE IN INLAND AREAS ONLY.

(VII) REQUIRED FOR COASTAL DISTRICTS; PERMITTED IN INLAND AREA.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

(a) SEE OH397.

b. SEE OH1207UG4307 FOR FUSES.

(c) SEE OH1208.

(d) SEE OH287UG3140.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | DRAWING UPDATE | - | RSL | JES | CZH | 03/09/2020 | F | | | | | | |
| B | DRAWING UPDATE | - | JCE | JS | CZJ | 03/18/2019 | E | EDITORIAL CHANGES | EDM | CWB | JES | CZH | 09/30/2021 |
| A | ORGINAL ISSUE | - | GW | JS | MDJ | 04/01/2018 | D | FORMATTING | EDM | JIK | - | - | 09/28/2020 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS CURRENT LIMITING FUSES USED FOR CABLE POLE CONSTRUCTION.





**FIGURE 1**
POLYMER INTERCHANGEABLE CUTOUT




**FIGURE 2**
SINGLE BARREL ELF FUSE





**FIGURE 3**
DOUBLE BARREL ELF FUSE

## INSTALLATION:

(A) THESE FUSES DROP WHEN THEY OPERATE, ARE TOTALLY EXPENDABLE AND HAVE NO SALVAGEABLE PARTS. DISCARD ENTIRE FUSE ASSEMBLY AFTER OPERATION.

(B) INSTALL FUSE SIZE WITH DECALS ON EACH FUSE SO IT WILL BE VISIBLE AFTER INSTALLATION.(c)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS OH | DESIGN UNITS UG |
|---|---|---|---|---|---|---|
| 1 | CUTOUT, POLYMER, 25KV NOMINAL, 27KV MAX, 150 BIL | AS REQ'D | - | S298020 (III) | NPCO | NPCO |
| | CUTOUT, 12KV, 300A | AS REQ'D | - | S298026 (I)(IV) | NPCO-2 | NPCO-2 |
| 2 | FUSE, CURRENT LIMITING, 30 AMP, 8.3KV, (A)(B)(I)(II) | AS REQ'D | - | S365654 | 30AELF | ELF30A |
| 3 | FUSE, CURRENT LIMITING, 65 AMP, 8.3KV, (A)(B)(I)(II) | AS REQ'D | - | S365656 | 65AELF | ELF65A |

## NOTES:

(I) PERMITTED IN ALL CONTAMINATION DISTRICTS (d)

(II) FOR USE IN INTERCHANGEABLE CUTOUT.

(III) FOR USE IN CONTAMINATION DISTRICTS II AND III ONLY (d)

(IV) REQUIRED FOR CONTAMINATION DISTRICT I (d)

## REFERENCE:

a. FOR APPLICATION OF THESE FUSES, SEE DM SECTION 6100.

b. FOR EQUIPMENT MOUNTING BRACKETS, SEE OH397.

(c) SEE OH208 AND UG3212.

(d) SEE OH287UG3140: CONTAMINATION DISTRICTS.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| F | EDITORIAL CHANGES | EDM | JAC | JAS | KRG | 11/03/2022 |
| E | REVISED TO 3D FORMAT | AMP | JIK | - | - | 05/10/2022 |
| D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |

SDGE — A Sempra Energy utility

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**OVERHEAD 12KV CURRENT-LIMITING FUSE INSTALLATION**

SCALE: NOT TO SCALE

DRAWING NO: OH1206.1 UG4306.1

SHEET: 1 OF 1

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD SHOWS VARIOUS TYPES OF FUSES USED ON THE OVERHEAD DISTRIBUTION SYSTEM.

## TABLE 1:

| CURRENT-LIMITING FUSES (II)(d) | | |
|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** |
| 30 | CURRENT-LIMITING (HXELF) | S365732 (B) |
| 30 | CURRENT-LIMITING (ELF) | S365654 (C) |
| 65 | CURRENT-LIMITING (ELF) | S365656 (C) |
| 65 | CURRENT-LIMITING (HXELF) | S365738 (B) |
| 150 | CURRENT-LIMITING (HX) | S365689 (B) |
| 12 | CURRENT-LIMITING (BACK-UP) | S365634 (A) |
| 40 | CURRENT-LIMITING (BACK-UP) | S365636 (A) |

## TABLE 2:

| 15.5KV NX FUSES FOR CURRENT-LIMITING FUSE TOOL (USED FOR TESTING DISTRIBUTION TRANSFORMERS) | | |
|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** |
| 8 | CURRENT-LIMITING | S368000 |
| 10 | CURRENT-LIMITING | S367552 |
| 12 | CURRENT-LIMITING | S367584 |
| 18 | CURRENT-LIMITING | S367648 |
| 21 | CURRENT-LIMITING | S367712 |
| 25 | CURRENT-LIMITING | S367744 |
| 30 | CURRENT-LIMITING | S367808 |
| 40 | CURRENT-LIMITING | S367872 |

## TABLE 3:

| 15.5KV ELF FUSES (USED FOR TESTING DISTRIBUTION TRANSFORMERS) | | | |
|---|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** | **DESIGN UNITS** |
| 12 | CURRENT-LIMITING | S365664 | - |
| 50 | CURRENT-LIMITING | S365666 | - |

## TABLE 4:

| 15.5KV CURRENT-LIMITING FUSE, CAPACITOR POWER TRANSFORMER | | | |
|---|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** | **DESIGN UNITS** |
| 3 | CURRENT-LIMITING | S365732 | - |

## TABLE 5:

| SECONDARY CURRENT-LIMITING FUSE FOR EKSTROM ADAPTER (b) | | | |
|---|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** | **DESIGN UNITS** |
| 125 | CURRENT-LIMITING | S365643 | - |

## TABLE 6:

| SMU FUSES FOR SMD20 CUTOUT BODY (I)(III) | | | | |
|---|---|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** | **DESIGN UNITS** | |
| | | | **UG** | **OH** |
| 5 | SMU-5 | S368550 | 5SMU | SMU5 (D) |
| 10 | SMU-10 | S368552 | 10SMU | SMU10 (D) |
| 15 | SMU-15 | S368554 | 15SMU | SMU15 (D) |
| 20 | SMU-20 | S368556 | 20SMU | SMU20 (D) |
| 25 | SMU-25 | S368662 | 25SMU | SMU25 (D) |
| 30 | SMU-30 | S368664 | 30SMU | SMU30 (D) |
| 40 | SMU-40 | S368666 | 40SMU | SMU40 (D) |
| 50 | SMU-50 | S368668 | 50SMU | SMU50 (D) |
| 65 | SMU-65 | S368670 | 65SMU | SMU65 (D) |
| 80 | SMU-80 | S368672 | 80SMU | SMU80 (D) |
| 100 | SMU-100 | S368674 | 100SMU | SMU100 (D) |
| 125 | SMU-125 | S368676 | 125SMU | SMU125 |
| 150 | SMU-150 | S368678 | 150SMU | SMU150 |
| 200 | SMU-200 | S368680 | 200SMU | SMU200 |

## TABLE 7:

| END FITTINGS FOR SMU FUSES | |
|---|---|
| **DESCRIPTION** | **STOCK NUMBER** |
| FUSE END FITTINGS | S368660 |

## TABLE 8:

| CMU FUSES FOR CMU CUTOUT BODY (I) | | | | |
|---|---|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** | **DESIGN UNITS** | |
| | | | **UG** | **OH** |
| 5 | CMU-5 | S368692 | 5CMU | CMU5 (D) |
| 10 | CMU-10 | S368694 | 10CMU | CMU10 (D) |
| 15 | CMU-15 | S368696 | 15CMU | CMU15 (D) |
| 20 | CMU-20 | S368698 | 20CMU | CMU20 (D) |
| 25 | CMU-25 | S368700 | 25CMU | CMU25 (D) |
| 30 | CMU-30 | S368702 | 30CMU | CMU30 (D) |
| 40 | CMU-40 | S368704 | 40CMU | CMU40 (D) |
| 50 | CMU-50 | S368706 | 50CMU | CMU50 (D) |
| 65 | CMU-65 | S368708 | 65CMU | CMU65 (D) |
| 80 | CMU-80 | S368710 | 80CMU | CMU80 (D) |
| 100 | CMU-100 | S368712 | 100CMU | CMU100 (D) |
| 125 | CMU-125 | S368714 | 125CMU | CMU125 |
| 150 | CMU-150 | S368716 | 150CMU | CMU150 |

## TABLE 9:

| END FITTINGS FOR CMU FUSES | |
|---|---|
| **DESCRIPTION** | **STOCK NUMBER** |
| FUSE END FITTINGS | S368690 |

## TABLE 10:

| EXPULSION FUSES (a) | | | | | |
|---|---|---|---|---|---|
| **SIZE (AMPS)** | **TYPE** | **STOCK NUMBER** | **DESIGN UNITS** | | |
| | | | **OH ACCTS.** | **UG ACCTS.** | **OVERHEAD (B)(C)** |
| 5 | 200 | S366016 | - | EXP-05 | EX5 (D) |
| 10 | 200 | S365696 | - | EXP-10 | EX10 (D) |
| 15 | QA | S365792 | 015-QA | QA-015 | QA15 (D) |
| 20 | QA | S365856 | 020-QA | QA-020 | QA20 (D) |
| 25 | QA | S365920 | 025-QA | QA-025 | QA25 (D) |
| 30 | QA | S365952 | 030-QA | QA-030 | QA30 (D) |
| 40 | QA | S365984 | 040-QA | QA-040 | QA40 (D) |
| 50 | QA | S366048 | 050-QA | QA-050 | QA50 (D) |
| 60 | QA | S366080 | 060-QA | QA-060 | QA60 (D) |
| 75 | QA | S366112 | 075-QA | QA-075 | QA75 (D) |
| 100 | QA | S365728 | 100-QA | QA-100 | QA100 (D) |
| 125 | QA | S365760 | 125-QA | QA-125 | QA125 |
| 150 | QA | S365824 | 150-QA | QA-150 | QA150 |
| 200 | 200 | S365888 | 200-QA | QA-200 | QA200 |

## INSTALLATION:

(A) NO LONGER PURCHASED.

(B) USE WITH KEARNEY CUTOUT. (c)(d)

(C) USE WITH INTERCHANGEABLE CUTOUT. (c)(d)

(D) CORRESPONDING FIREFLY SHOULD BE INSTALLED WITH APPLICABLE NEW FUSE INSTALLATION OR FUSE REPLACEMENT EXCEPT WHEN FUSING TRANSFORMERS. (e)

**BILL OF MATERIALS:** NONE

## NOTES:

(I) THESE FUSES ARE CAL-FIRE EXEMPT. THEY WILL BE USED IN TIER 2 & TIER 3 AREAS.

(II) THESE FUSES ARE ALLOWED IN THE ENTIRE SERVICE TERRITORY.

(III) SMU FUSES ARE NOT TO BE LEFT HANGING IN THE OPEN POSITION. (f)

## REFERENCE:

(a) SEE DESIGN STANDARDS SECTION 6100.

(b) SEE OH1204.

(c) SEE OH1207UG4307 FOR EXPLOSION FUSE.

(d) SEE OH1206UG4306 FOR CURRENT-LIMITING FUSE.

(e) SEE OH1208 FOR FIREFLY FUSED CUTOUT INDICATOR.

(f) SEE S&C INSTRUCTION SHEET 252-550.

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| G | REVISED TO 3D FORMAT | GLC/DV | JIK | - | - | 01/27/2022 |
| F | FORMATTING | EDM | JIK | - | - | 09/28/2020 |
| E | EDITORIAL CHANGES | - | SL | JES | CZH | 03/09/2020 |

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**FUSES USED IN OVERHEAD CONSTRUCTION**

SCALE: NOT TO SCALE

DRAWING NO: OH1207.1 UG4307.1

SHEET: 1 OF 1

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

Indicates Latest Revision | Completely Revised | New Page | Information Removed

**SCOPE:** THIS STANDARD DESCRIBES THE 1200 KVAR PAD-MOUNTED CAPACITOR.





**FIGURE 1**
SCHEMATIC DIAGRAM (II)
NEW STYLE





**FIGURE 2**
SCHEMATIC DIAGRAM (III)
OLD STYLE





**FIGURE 3**
BACK VIEW
EXPOSED





**FIGURE 3**
SIDE VIEW
EXPOSED

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | TRANSFORMER (P.T), 12KV | 1 | 3821 | S762714 | -- |
| 2 | FUSE, CURRENT-LIMITING 0.5 AMP, 14.4 KV - GE TYPE J-1 | 2 | -- | S366456 | -- |
| 3 | CAPACITOR, 400 KVAR, 7200V, SINGLE-PHASE | 3 | 3821 | S207348 | -- |
| 4 | FUSE, COMBINED TECHNOLOGIES, 15.5 KV, 80 AMP, TYPE X-LIMITER (II) | 3 | 4311 | S365695 | -- |

**NOTES:**

(I) P.T. TRANSFORMER FUSES, GE TYPE J-1 ARE THE SAME FOR NEW AND OLD STYLE CAPACITORS.
(II) NEW STYLE 3-80A, COMBINED TECHNOLOGY FUSES TYPE X LIMITER. (a)
(III) 6-45A, MCGRAW EDISON FUSES TYPE NXC: S365718. (b)

**REFERENCE:**

(a) REFER TO UG3821.
(b) REFER TO FMO UG3899.201-203.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



1200 KVAR PAD-MOUNTED CAPACITOR

UG4309.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD PROVIDES INSTALLATION INSTRUCTIONS FOR THE SML-4Z FUSE CONVERSION KIT FOR THE PME 9 AND 11 SWITCH TRANSFUSER DOOR.





**FIGURE 1**
CURRENT LIMITING






**FIGURE 2**
SM-4




**DETAIL 1**





**FIGURE 3** (K)





**FIGURE 4**

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | GLC | JA | JAS | KRG | 04/07/2023 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | REVISION | - | - | - | RSW/CAK | 01/01/2000 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 2

CURRENT LIMITING TO SM-4
FUSE CONVERSION FOR PME SWITCH

UG4310.1

## INSTALLATION:

A. IF THIS WORK IS TO BE DONE IN THE FIELD ON AN ENERGIZED SWITCH, IT MUST BE DE-ENERGIZED AND ALL CABLES GROUNDED.

B. OPEN THE THREE TRANSFUSER DOORS TO BE CONVERTED.

(C) REMOVE PLUGS FROM PRE-DRILLED HOLES IN TRANSFUSER DOOR.

D. RELOCATE THE UPPER INSULATOR WITH LATCH BRACKET TO LOWER SET OF HOLES. REUSE EXISTING HARDWARE. TIGHTEN THE BOLTS.

(E) REMOVE THE LOWER FUSE CONTACT AND INSTALL ITEMS 1, 2 & 3. MAKE SURE ITEM 3 IS INSTALLED WITH ONE LEG BEHIND THE HINGE BRACKET AND THE OTHER LEG OVER THE CONTACT AND CONTACT BACKUP.

(F) REPLACE PLUGS.

G. INSTALL THE FUSE HOLDER. MAKE SURE THAT THE FUSE MAKES GOOD CONTACT WITH THE CONTACT ASSEMBLY.

H. CHECK THAT THE FUSE HOLDER LATCHES CORRECTLY. IT IS NORMAL FOR THE FUSE HOLDER TO MOVE SLIGHTLY AT THE LATCHING END.

J. ONCE ADJUSTMENT IS ACHIEVED, TIGHTEN HARDWARE TO 35-40 FT/LBS.

(K) SNAP THE CONTACT BACKUP ITEM 2 OVER THE CONTACT ITEM 1 PRIOR TO INSTALLING ON HINGE BRACKET.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CONTACT | 3 | -- | S442944 | CL-SM4 (I) |
| 2 | CONTACT BACKUP | 3 | -- | | |
| 3 | SHUNT (E) | 3 | -- | | |
| 4 | HOLDER, FUSE | 3 | -- | | |
| 5 | PLUGS (C)(F) | AS REQ'D | -- | -- | -- |
| 6 | CONTACT, FUSE | AS REQ'D | UG4313.1 | -- | -- |
| 7 | BRACKET, HINGE | AS REQ'D | -- | -- | -- |
| 8 | BRACKET, LATCH | AS REQ'D | -- | -- | -- |
| 9 | SCREW, HEX CAP, 3/8"-16 X 1" | AS REQ'D | -- | -- | -- |
| 10 | SCREW, HEX CAP, 3/8"-16 X 1 1/4" | AS REQ'D | -- | -- | -- |
| 11 | WASHER, LOCK, STD., 3/8" | AS REQ'D | -- | -- | -- |
| 12 | WASHER, FLAT, STD., 3/8" | AS REQ'D | -- | -- | -- |

## NOTES:

(I) DESIGN UNIT CL-SM4 ORDERS ENOUGH MATERIAL FOR 3 FUSES OR ONE COMPARTMENT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | BILL OF MATERIALS UPDATE | GLC | JA | JAS | KRG | 04/07/2023 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | REVISION | - | - | - | RSW/CAK | 01/01/2000 | D | | | | | | |

**SCOPE:** THIS STANDARD DESCRIBES THE VARIOUS TYPES OF FUSES USED ON THE UNDERGROUND DISTRIBUTION SYSTEM.





**FIGURE 1**
COOPER POWER SYSTEMS/ MC-GRAW EDISON
TYPE NX





**FIGURE 2**
COOPER POWER SYSTEMS/ MC-GRAW EDISON
TYPE NX





**FIGURE 3**
COOPER POWER SYSTEMS/ MC-GRAW EDISON
TYPE NX





**FIGURE 4**
COOPER POWER SYSTEMS/ MC-GRAW EDISON
TYPE NX





**FIGURE 5**
MERSEN/ GENERAL ELECTRIC
TYPE EJO-1 & COMBINED TECHNOLOGIES TYPE EOD





**FIGURE 6**
MERSEN/ GENERAL ELECTRIC
TYPE EJO-1





**FIGURE 7**
COOPER POWER SYSTEMS/ BUSSMANN

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 1/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 8/11/2016 | E | | | | | | |
| A | TABLE UPDATE | - | JS | TR | MDJ | 5/24/2016 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |



TABLE OF CONTENTS





**FIGURE 9**





**FIGURE 8**
RTE TYPE B, COOPER POWER HX-XLIMITER, & COMBINED TECHNOLOGIES TYPE BOI, 150 AMP





**FIGURE 10**
COOPER POWER SYSTEMS/ COMBINED TECHNOLOGIES 80 AMP X-LIMITER





**FIGURE 11**
140 AMP X-LIMITER CURRENT LIMITING FUSE





**FIGURE 12**
30 AMP FULL-RANGE CURRENT LIMITING FUSE USED WITH FUSE TEST CANISTER/FTC





**FIGURE 13**
50 AMP FULL-RANGE CURRENT LIMITING FUSE USED WITH VACUUM-SWITCH CIRCUIT TESTER/VCT





**FIGURE 14**
30 AMP FULL-RANGE CURRENT LIMITING FUSE USED WITH FUSED ELBOW

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 1/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 8/11/2016 | E | | | | | | |
| A | TABLE UPDATE | - | JS | TR | MDJ | 5/24/2016 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD PROVIDES A TABLE OF CURRENT-LIMITING FUSES AND SOLID BLADES.

## TABLE 1

**CURRENT-LIMITING FUSE & SOLID BLADE TABLE**

| MANUFACTURER | NOMINAL VOLTAGE (KV) | RATING CONTINUOUS CURRENT (AMP) | | | INTERRUPTING SYMMETRICAL CURRENT (AMP) | FIGURE NUMBER (a) | CATALOG NUMBER | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|
| COOPER POWER SYSTEMS/ TYPE NX | 8.3 | 8 | K | -- | 50,000 | 1 | FA3A8 | S367936 | -- |
| | | 10 | | -- | | | FA3A10 | S368032 | -- |
| | | 12 | | -- | | | FA3A12 | S367616 | -- |
| | | 18 | | -- | | 2 | FA3A18 | S367680 | -- |
| | | 25 | | -- | | | FA3A25 | S367776 | -- |
| | | 30 | | -- | | | FA3A30 | S367840 | -- |
| | | 40 | | -- | | | FA3A40 | S367904 | -- |
| | -- | 200 | -- | -- | -- | -- | FA1B1 | S139552 | SB200N |
| | 8.3 | 25 | K | -- | 50,000 | 4 | FA3H25 | S365684 | -- |
| | | 30 | | -- | | | FA3H30 | S365688 | -- |
| | | 40 | | -- | | | FA3H40 | S365692 | -- |
| | | 8 | | -- | | -- | FC11Y8 | S367968 | -- |
| | 15.5 | 8 | K | -- | 50,000 | 3 | FA4A8 | S368000 | -- |
| | | 10 | | -- | | | FA4A10 | S367552 | -- |
| | | 12 | | -- | | | FA4A12 | S367584 | -- |
| | | 18 | | -- | | | FA4A18 | S367648 | -- |
| | | 20 | | -- | | | FA4A20 | S367712 | -- |
| | | 25 | | -- | | | FA4A25 | S367744 | -- |
| | | 30 | | -- | | | FA4A30 | S367808 | -- |
| | | 40 | | -- | | | FA4A40 | S367872 | -- |
| | -- | 200 | -- | -- | -- | -- | FA3B1 | S139488 | -- |
| MERSEN/TYPE EJO-1 | 8.3 | 30 | G | -- | 80,000 | 5 | 9F60FJE030 | S365714 | EJO-30 |
| | | 40 | | -- | | | 9F60FJE040 | S365716 | EJO-40 |
| | | 65 | | -- | | | 9F60FJE065 | S365720 | EJO-65 |
| | | 80 | | -- | | | 9F60FJE080 | S365722 | EJO-80 |
| | | 100 | | H | | | 9F60FJE100 | S365724 | EJO100 |
| | | 150 | | -- | | 6 | 9F60HJE150 | S365725 | EJO150 |
| | | 200 | | -- | | | 9F60HJE200 | S365726 | EJO200 |
| | -- | 200 | -- | -- | -- | -- | (C) | S368034 | SB200E |
| | | | | | | | | | 12/6.9KV / 4KV |
| COOPER POWER SYSTEMS/TYPE EOD | 8.3 | 40 | G | -- | 80,000 | 5 | 83F40-EOD | S365716 | EJO-40 / 40CL4 |
| | | 65 | | -- | | | 83F65-EOD | S365720 | EJO-65 / 65CL4 |
| | | 80 | | -- | | | 83F080-EOD | S365722 | EJO-80 / 80CL4 |
| | | 100 | | -- | | | 83F100-EOD | S365724 | EJO100 / 100CL4 |
| | | 150 | | | | | 83F150-SD | S365725 | EJO150 / 150CL4 |
| | | 200 | | | | 6 | 83F200-EOD | S365726 | EJO200 / 200CL4 |
| TYPE BOI | | 150 | K | A | 40,000 | 8 | 83F150-BO1 | S365687 | CL150W |
| X-LIMITER | 15 | 80 | K | B | 50,000 | 10 | 155F80-I/I | S365695 | -- |
| | 8.3 | 140 | K | -- | 50,000 | 11 | 83F140-I/I | S365730 | XL-140 |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 01/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 08/11/2016 | E | NOTES UPDATE | EDM | ADW | GLW | KRG | 11/07/2022 |
| A | TABLE UPDATE | - | JS | TR | MDJ | 05/24/2016 | D | MOVED FROM UG4311 | EDM | JIK | - | - | 09/28/2020 |



TABLE OF CONTENTS

## TABLE 1 (CONT'D)

| CURRENT-LIMITING FUSE & SOLID BLADE TABLE | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| MANUFACTURER | NOMINAL VOLTAGE (KV) | RATING CONTINUOUS CURRENT (AMP) | | | INTERRUPTING SYMMETRICAL CURRENT (AMP) | FIGURE NUMBER (a) | CATALOG NUMBER | STOCK NUMBER | DESIGN UNITS |
| BUSSMANN TYPE SDL | 7.2 | 40 | (K) | -- | 40,000 | 7 | SDL-S-L-40 | S365672 | CLF40A |
| | | 80 | | -- | | | SDL-S-J-80 | S365680 | CLF80A |
| | -- | 200 | -- | -- | -- | -- | (C) | S368036 | SB200A |
| COOPER POWER SYSTEMS/ HX-X-LIMITER | 8.3 | 30 (E) | (K) | -- | 40,000 | 9 | 83F030-HX | S365670 | CLF30B |
| | | 80 (E) | | -- | | | 83F080-HX | S365681 | CLF80B |
| COOPER POWER SYSTEMS/ RTE TYPE B | | 150 (D) | -- | -- | | 9 | (C) | S365691 | CL150S |
| | | 150 (F) | | (A) | | 8 | 3575150M01M | S365687 | CL150W |
| BURNDY/T&B TYPE PF8 | | -- | | -- | -- | -- | -- | -- | -- |
| | | 30 | | -- | | | PF8-30K | S365723 | PF8-30 |
| ELASTIMOLD TYPE EFX | | 30 | -- | -- | -- | 12 | EFX155030 | S365740 | -- |
| | | 50 | | -- | | 13 | EFX155050 | S365750 | -- |
| | | 30 | | -- | | 14 | EFX083030 | S365698 | FE-30A |

## INSTALLATION:

(A) 150A RTE TYPE B FUSE AND THE 150A COMBINED TECHNOLOGIES TYPE BOI HAVE THE SAME CHARACTERISTICS AND ARE INTERCHANGEABLE. THEY MAY BE COMBINED FOR THREE-PHASE LOAD IN A FUSING CABINET ETC.

(B) THIS FUSE IS TO BE USED FOR REPLACEMENT OF THE NEW STYLE PADMOUNT CAPACITOR WITH (3) 400 KVAR CAPACITORS.

(C) FABRICATED BY SDG&E.

(D) S&C MINI-RUPTER FUSE CABINET, WHICH COMES WITH END FITTINGS. (a)

(E) WHEN KEARNEY TYPE "B" FUSE, WHICH COMES WITH END FITTINGS, IS REQUIRED IN WALL MOUNTED FUSE CABINET. SUBSURFACE FUSE CABINET, 1990 OR NEWER S&C MINI-RUPTER FUSE CABINET, OR PAD MOUNTED PMH 9 & 11 SWITCHGEAR, REMOVE END FITTINGS AND SEND THEM TO KEARNEY SHOP FOR RE-USE. STOCK NUMBER: S351008

(F) COMES WITHOUT END FITTINGS, USED IN WALL MOUNTED FUSE CABINETS, SUBSURFACE FUSE CABINETS, 1990 OR NEWER S&C MINI-RUPTER FUSE CABINET, OR PAD MOUNTED PMH 9 & 11 SWITCHGEAR. (a)

(G) MAY NOT BE USED ON 4KV SYSTEMS, AN 8.3KV RATED G.E. TYPE EJO-1 AND COMBINED TECHNOLOGIES FUSES WILL GENERATE A MAXIMUM ARC PEAK VOLTAGE OF 25KV. THE 12KV SYSTEM CAN WITHSTAND THIS PEAK, WHEREAS THE 4KV SYSTEM MAY NOT.

(H) 100A GENERAL ELECTRIC TYPE EJO-1 FUSE AND THE 150 & 200A COMBINED TECHNOLOGIES TYPE EOD FUSES ARE THE MAXIMUM SIZE ALLOWED IN A SINGLE-PHASE FUSE CABINET DUE TO PHYSICAL CONSTRAINT OF CABINET.

J. DOUBLE BARREL FUSES CAN ONLY BE USED WITH THREE-PHASE FUSE CABINETS.

(K) INSTALL FUSE SIZE WITH DECALS ON EACH FUSE SO IT WILL BE VISIBLE AFTER INSTALLATION. (a)

(L) COMBINED TECHNOLOGIES' FUSES AND GENERAL ELECTRIC-EJO TYPE FUSES, HAVE THE SAME OPERATING CURVE CHARACTERISTICS AND ARE INTERCHANGEABLE. THEY MAY BE COMBINED FOR THREE-PHASE LOAD IN PAD MOUNTED FUSE CABINETS, SUBSURFACE FUSE CABINETS, 1990 OR NEWER S&C MINI-RUPTER FUSE CABINETS, OR PAD MOUNTED PMH 9 & 11 SWITCHGEAR. (a)

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**


(a) FOR FIGURES, SEE UG4311.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 01/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 08/11/2016 | E | NOTES UPDATE | EDM | ADW | GLW | KRG | 11/07/2022 |
| A | TABLE UPDATE | - | JS | TR | MDJ | 05/24/2016 | D | MOVED FROM UG4311 | EDM | JIK | - | - | 09/28/2020 |

**SCOPE:** THIS STANDARD PROVIDES A TABLE OF EXPULSION FUSES.

## TABLE 1

| EXPULSION FUSE TABLE | | | | | | |
|---|---|---|---|---|---|---|
| **MANUFACTURER** | **NOMINAL VOLTAGE (KV)** | **RATING CONTINUOUS CURRENT (AMP)** | **INTERRUPTING SYMMETRICAL CURRENT (AMP)** | **CATALOG NUMBER** | **STOCK NUMBER** | **DESIGN UNITS** |
| GENERAL ELECTRIC<br><br>[FOR USE IN D&W (G.E.) OIL FUSED CUTOUTS]<br><br><br>FUSE | 5.2 | 6 | (B) | 9F57CAA006 | S466752 | DW-006 |
| | | 10 | | 9F57CAA010 | S466400 | DW-010 |
| | | 15 | | 9F57CAA015 | S466496 | DW-015 |
| | | 20 | | 9F57CAA020 | S466560 | DW-020 |
| | | 25 | | 9F57CAA025 | S466624 | DW-025 |
| | | 30 | | 9F57CAA030 | S466656 | DW-030 |
| | | 40 | | 9F57CAA040 | S466720 | DW-040 |
| | | 50 | | 9F57CAA050 | S466784 | DW-050 |
| | | 65 | | 9F57CAA065 | S466816 | DW-065 |
| | | 75 | | 9F57CAA075 | S466848 | DW-075 |
| | | 100 | | 9F57CAA100 | S466432 | DW-100 |
| | | 125 | | 9F57CAA125 | S466464 | DW-125 |
| | | 150 | | 9F57CAA150 | S466528 | DW-150 |
| | | 200 | | 9F57CAA200 | S466592 | DW-200 |
| | | 300 | | 9F57BAA300 | S466688 | DW-300 |
| S&C<br><br>(FOR USE IN SM-4 HOLDER) | 14.4 | 10 | 12,500 BASED ON X/R=15 | 122015R4 | S366976 (A) | SM4-10 |
| | | 15 | | 122025R4 | S367104 (A) | SM4-15 |
| | | 30 | | 122050R4 | S367232 (A) | SM4-30 |
| | | 40 | | 122060R4 | S367248 (A) | SM4-40 |
| | | 50 | | 122075R4 | S367296 (A) | SM4-50 |
| | | 65 | | 122100R4 | S367328 (A) | SM4-65 |
| | | 80 | | 122125R4 | S367392 (A) | SM4-80 |
| | | 100 | | 122150R4 | S367008 (A) | SM4100 |
| | | 125 | | 122200R4 | S367040 (A) | SM4125 |
| | | 150 | | 122250R4 | S367136 (A) | SM4150 |
| | | 200 | | 122300R4 | S367168 (A) | SM4200 |
| | | SNUFFLER | | -- | S657408 | -- |
| | | 200 (D) | -- | (E) | S368060 | -- |
| SM-4 HOLDER | | -- | -- | 86632 | S413248 | -- |
| S&C<br>(FOR USE IN SM-5 HOLDER) | 14.4 | 100 | 25,000 BASED ON X/R=15 (C) | 132150R4 | S367424 (A) | SM5100 |
| | | 150 | | 132250R4 | S367456 (A) | SM5150 |
| | | 200 | | 132300R4 | S367488 (A) | SM5200 |
| SM-5 HOLDER | | -- | -- | 86152RZ | S413280 | -- |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 1/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 8/11/2016 | E | | | | | | |
| A | TABLE UPDATE | - | JS | TR | MDJ | 5/24/2016 | D | MOVED FROM UG4311 | EDM | JIK | - | - | 9/28/2020 |



TABLE OF CONTENTS

**INSTALLATION:**

(A) FOR FUSING AND REFUSING TRANSFORMERS, S&C THREE-PHASE FUSED SWITCHING CABINETS AND VAULT ASSEMBLIES. THE S&C THREE-PHASE FUSED SWITCHING CABINETS USE EITHER AN SM-4 OR SM-5 FUSE ASSEMBLY WHICH DIFFER IN OVERALL SIZE. THEY ARE NOT INTERCHANGEABLE.

(B) INTERRUPTING SYMMETRICAL CURRENT (AMP) RATING FOR G.E. (D&W) OIL CUTOUTS ARE: 3,100 A FOR 100 A CUTOUT, 6,200 A FOR 200 A CUTOUT, AND 6,400 A FOR 300 A CUTOUT BASED ON X/R RATIO OF MORE THAN 4. FOR X/R RATIOS OF LESS THAN 4, THE SYMMETRICAL INTERRUPTION RATINGS ARE: 4,100 A FOR 100 A, 8,300 A FOR 200A AND 8,540 A FOR 300 A CUTOUTS.

(C) SYMMETRICAL INTERRUPTION RATINGS OF S&C FUSES FOR X/R=10 IS 27,400 A AND FOR X/R=5 IS 32,000 A.

(D) SOLID BLADE.

(E) FABRICATED BY SDG&E.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 1/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 8/11/2016 | E | | | | | | |
| A | TABLE UPDATE | - | JS | TR | MDJ | 5/24/2016 | D | MOVED FROM UG4311 | EDM | JIK | - | - | 9/28/2020 |

**SCOPE:** THIS STANDARD PROVIDES A TABLE OF FUSES USED FOR TRANSFORMERS.

TABLE OF CONTENTS


## TABLE 1

| LIVE FRONT TRANSFORMER FUSING TABLE TYPE "NX" FUSE UNITS | | | |
|---|---|---|---|
| TRANSFORMER RATING (KVA) | FUSE SIZE (AMPS) | | |
| | SINGLE PHASE | | THREE PHASE |
| | 6.9KV | 12KV | 12KV |
| 15 | 8 | 8 | - |
| 25 | | | - |
| 30 | - | | 8 |
| 37.5 | 10 | | - |
| 45 | - | | 8 |
| 50 | 12 | | - |
| 75 | 18 | 10 | 8 |
| 100 | 25 | 12 | - |
| 112.5 | - | - | 12 |
| 150 | - | - | 12 |
| 167 | 30 | 20 | - |
| 225 | - | - | 18 |
| 250 | - | 30 | - |
| 300 | - | - | 25 |
| 333 | - | 30 | - |
| 500 | - | - | 40 |
| 750 | - | - | 2-25 |
| 1,000 | - | - | 2-30 |

## TABLE 2

| LIVE FRONT TRANSFORMER FUSING TABLE THREE-PHASE, 12KV TYPE SM-4 RATED 14.4KV | |
|---|---|
| TRANSFORMER RATING (KVA) | FUSE SIZE (AMPS) |
| 1,500 | 125 |
| 2,000 | 150 |
| 2,500, 3,000 | 200 |

## TABLE 3

| D & W (G.E.) CUTOUT FUSES FOR 4KV-WS, WSV, WUS TRANSFORMER | | |
|---|---|---|
| FIGURE | TRANSFORMER RATING (KVA) | FUSE SIZE (AMPS) |
|  FUSE | 5 | 6 |
| | 7.5 | 6 |
| | 10 | 10 |
| | 15 | 10 |
| | 25 | 15 |
| | 30 | 20 |
| | 37.5 | 25 |
| | 50 | 30 |
| | 75 | 50 |
| | 100 | 75 |
| | 167 | 100 |

## TABLE 4

| REPLACEMENT FUSE FOR SUBSURFACE TRANSFORMER (HSS) (HTS) (CURRENT LIMITING) | | | |
|---|---|---|---|
| TRANSFORMER RATING (KVA) | AMPS | FUSE RATING (KVA) | STOCK NUMBER |
| 25 | 6 | 15.5 | S365682 |
| 50 | 10 | | S365686 |
| 75 | 12 | | S365690 |
| 100 | 15 | | S365712 |

## TABLE 5

| REPLACEMENT FUSE FOR BAY-O-NET | | | | | | |
|---|---|---|---|---|---|---|
| TRANSFORMER | | FUSE CATALOG NUMBER | | | | STOCK NUMBER |
| KV | KVA | KEARNY | AMPS | CPS | AMPS | |
| 2.4 1PH | 25 | 124080-15 | 15 | 4038108C07 | 15 | S363534 |
| | 50 | 124080-30 | 30 | - | - | S363538 |
| | 75 | - | - | 4038108C12 | 50 | S366150 |
| 4.16 3PH | 75 | 124080-15 | 15 | 4038108C07 | 15 | S363534 |
| | 150 | 124080-30 | 30 | - | - | S363538 |
| | 225 | - | - | 4000353C12 | 40 | S363540 |
| | 500 | - | - | 4000353C16 | 100 | S363546 |
| 6.9 1PH (A) | 25 | 124080-6 | 6 | 4038108C04 | 6 | S363530 |
| | 50 | 124080-12 | 12 | 4038108C06 | 12 | S363532 |
| | 75 | 124080-15 | 15 | 4038108C07 | 15 | S363534 |
| | 100 | 124080-25 | 25 | 4038108C09 | 25 | S363536 |
| 12.0 | 25 | 124080-5 | 5 | 4038108C03 | 5 | S363528 |
| | 45 3PH | 124080-5 | 5 | 4038108C03 | 5 | S363528 |
| | 50 | 124080-8 | 8 | 4038108C05 | 8 | S366138 |
| | 75 1PH | 124080-12 | 12 | 4038108C06 | 12 | S363532 |
| | 75 3PH | 124080-6 | 6 | 4038108C04 | 6 | S363530 |
| | 100 1PH | 124080-15 | 15 | 4038108C07 | 15 | S363534 |
| | 167 1PH | 124080-12 | 12 | 4038108C09 | 25 | S363536 |
| | 225 | 124080-15 | 15 | 4038108C07 | 15 | S363534 |
| | 250 1PH | - | - | 4000353C12 | 40 | S363540 |
| | 300 | 124080-25 | 25 | 4038108C09 | 25 | S363536 |
| | 500 | 124080-30 | 30 | 4000353C12 | 40 | S353540 |
| | 750 | - | - | 4000353C14 | 65 | S363542 |
| | 1,000 | - | - | 4000353C14 | 65 | S363542 |
| | 1,500 | - | - | 4038361C04CB | 100 | S366140 |
| | 2,000 | - | - | 4038361C05CB | 125 | S366142 |
| | 2,500 | - | - | 4038361C05CB | 125 | S366142 |
| ALL | SLUG | - | - | - | - | S656300 |

## TABLE 6

| CLT FUSES FOR WESTINGHOUSE (YP) TRANSFORMERS (FOR REFUSING ONLY) | | | |
|---|---|---|---|
| TRANSFORMER RATING (KVA) | FUSE SIZE (AMPS) | CATALOG NUMBER | STOCK NUMBER |
| 15 | 5 | 678C248G03 | S366848 |
| 25 | 5 | 678C248G03 | S366848 |
| 37.5 | 8 | 678C248G06 | S366912 |
| 50 | 12 | 591C273G03 | S366624 |
| 75 | 18 | 678C276G03 | S366688 |
| 100 | 25 | 678C276G06 | S366752 |
| 167 | 30 | 680C386G01 | S366800 |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 1/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 8/11/2016 | E | | | | | | |
| A | TABLE UPDATE | - | JS | TR | MDJ | 5/24/2016 | D | MOVED FROM UG4311 | EDM | JIK | - | - | 9/28/2020 |

**INSTALLATION:**

(A) 6.9KV FUSE MAY ALSO BE USED FOR 7.2KV.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE DESIGN MANUAL PAGES 6131.1-7 FOR U.G. TRANSFORMER/FUSE COORDINATION TABLES.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | TABLE UPDATES | - | KR | JS | MDJ | 1/25/2017 | F | | | | | | |
| B | EDITORIAL CHANGES | - | JBH | JBH | MDJ | 8/11/2016 | E | | | | | | |
| A | TABLE UPDATE | - | JS | TR | MDJ | 5/24/2016 | D | MOVED FROM UG4311 | EDM | JIK | - | - | 9/28/2020 |

**SCOPE:** THIS STANDARD PROVIDES INFORMATION ON THE MATERIAL AND INSTALLATION OF THE SCHWEITZER ENGINEERING LABORATORIES (SEL) 8301 UNDERGROUND WIRELESS FAULT INDICATOR ON THE ELECTRIC DISTRIBUTION SYSTEM.



**FIGURE 1**
SEL 8301
UNDERGROUND WIRELESS FAULT INDICATOR (A)




**FIGURE 2**
MAGNETIC MOUNTING KIT ASSEMBLY (A)

**ATTENTION:**

* FOR INSTALLATION IN A MAGNETIC STEEL PAD-MOUNT ENCLOSURE, USE THE PROVIDED MAGNETIC MOUNTING KIT. FOR INSTALLATION TO A NONMAGNETIC SURFACE, SKIP TO SECTION 4.2.1.8, STEP 7 OF THE ESP 246.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

SHEET 1 OF 16

SEL 8301 WIRELESS FAULT INDICATOR

UG4344.1




**FIGURE 3**
REMOTE ANTENNA BRACKET (A)

**ATTENTION:**

* USE THE MOUNTING HOLES SHOWN TO ATTACH THE MAGNETIC MOUNTS TO THE REMOTE ANTENNA BRACKET.

TABLE OF CONTENTS




**FIGURE 4**
ANTENNA BRACKET MAGNETIC MOUNTING KIT ASSEMBLY (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

SEL 8301 WIRELESS FAULT INDICATOR

UG4344.2

TABLE OF CONTENTS




**FIGURE 5**
PLACE ANTENNA ON CABLE (A)




**FIGURE 6**
PORT PLUG (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |




**FIGURE 7**
REMOVE COVERS FROM ANTENNA CABLES (A)




**FIGURE 8**
PLUG THE ANTENNA CABLE INTO THE FAULT INDICATORS (A)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |





**FIGURE 9**
CORRECT AND INCORRECT NEUTRAL TRAINING (A)

**ATTENTION:**

* PROPER CONCENTRIC NEUTRAL TRAINING IS ESSENTIAL FOR PROPER FUNCTION OF THE CURRENT TRANSFORMERS.

** INSTALL THE CURRENT TRANSFORMERS AT GROUND POTENTIAL.

TABLE OF CONTENTS





**FIGURE 10**
CURRENT TRANSFORMER INSTALLATION ON CABLE (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |



SINGLE CABLE TIE | DOUBLE CABLE TIE | FIGURE-EIGHT CABLE TIE

**FIGURE 11**
CLOSE AND SECURE THE CURRENT TRANSFORMER TO THE CABLE (A)




**FIGURE 12**
LOCK CURRENT TRANSFORMER (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

SHEET 6 OF 16

SEL 8301 WIRELESS FAULT INDICATOR

UG4344.6

TABLE OF CONTENTS




**FIGURE 13**
REMOVE CAP FROM THE CURRENT TRANSFORMER CABLE PLUG (A)





**FIGURE 14**
PINCHED O-RING (A)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS





**FIGURE 15**
CURRENT TRANSFORMER PLUG ALIGNMENT (A)




**FIGURE 16**
CURRENT TRANSFORMER PLUG ALIGNMENT (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |




**FIGURE 17**
INSTALL THE CURRENT TRANSFORMER PLUG (A)

TABLE OF CONTENTS




**FIGURE 18**
WATER DEPTH SENSOR (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




**FIGURE 19**
WATER DEPTH SENSOR MOUNTING BRACKET (A)




**FIGURE 20**
INSTALL WDS IN THE MOUNTING BRACKET (A)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

TABLE OF CONTENTS





**FIGURE 21**
MOUNT THE COUPLER AND TRAP TO WDS (A)




**FIGURE 22**
REMOVE PROTECTIVE CAP FROM WDS PLUG (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS



SEL 8301 WIRELESS FAULT INDICATOR

UG4344.11





**FIGURE 23**
INCORRECT INSTALL. PINCHED O-RING (A)





**FIGURE 24**
INCORRECT INSTALL. PINCHED O-RING
ENSURE THE INNER O-RING IS PROPERLY INSTALLED (A)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

SHEET 12 OF 16

SEL 8301 WIRELESS FAULT INDICATOR

UG4344.12

TABLE OF CONTENTS





**FIGURE 25**
ACTIVATION RADIO SYSTEM BUTTONS (A)





**FIGURE 26**
RADIO STATUS (A)





**FIGURE 27**
SUCCESSFUL CONNECTION TO THE LPCN NETWORK (A)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed





**FIGURE 28**
FAULT INDICATOR SENSORS STATUS DISPLAY (A)
SENSOR STATUS





**FIGURE 29**
EXAMPLE SENSOR STATUS DISPLAY (A)

TABLE OF CONTENTS

**TABLE 1**

| SENSOR STATUS LED DESCRIPTION | | |
|---|---|---|
| **LED STATE** | **SENSOR STATUS** | **DESCRIPTION** |
| OFF | N/A | UNPOPULATED |
| FLASHING GREEN | UNARMED | SYSTEM DETECT OR NEW EVENT DETECTED |
| SOLID GREEN | ARMED | READY TO DETECT FUTURE EVENTS |
| FLASHING RED | UNARMED | PERMANENT FAULT |
| SOLID RED | UNARMED | PERMANENT LOSS OF CURRENT |

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |





**FIGURE 30**
WATER DEPTH SENSOR STATUS (A)





**FIGURE 31**
WATER DEPTH SENSOR HAS NOT BEEN (A) ZEROED (RED X)





**FIGURE 32**
WATER DEPTH SENSOR ZEROING COMPLETE (A)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

SEL 8301 WIRELESS FAULT INDICATOR

UG4344.15

## INSTALLATION:

(A) REFERENCE ESP 246 FOR INSTALLATION AND OPERATING INSTRUCTIONS.

## BILL OF MATERIALS: NONE

## NOTES:

I. IT IS ESSENTIAL FOR FAULT AND LOADING INTERPRETATION THAT EACH CURRENT TRANSFORMER IS PROPERLY MAPPED TO THE CORRECT PORT ON THE FAULT INDICATOR, INDICATED BY THE PHASE AND WAY.

II. 4.3.1. THE WATER DEPTH SENSOR (WDS) REPORTS THE PERCENTAGE OF WATER IN A SUBSURFACE VAULT, MANHOLE, OR HANDHOLE BY MEASURING THE DISTANCE BETWEEN THE SENSOR AND THE WATER SURFACE. MOUNT THE WDS AS CLOSE TO THE TOP OF THE VAULT, MANHOLE, OR HANDHOLE AS POSSIBLE. THE WDS MUST BE INSTALLED IN ALL VAULTS, MANHOLES, AND HANDHOLES.

III. 4.3.1.3 THE SYSTEM STATUS LEDS INDICATE WHAT INFORMATION THE SENSOR STATUS DISPLAY IS PRESENTLY SHOWING. THE ILLUMINATED STATUS 1 LED INDICATES THAT THE SENSOR STATUS DISPLAY IS SHOWING THE RADIO STATUS INFORMATION.

IV. 4.3.1.4.3 ALL FOUR A-PHASE LEDS ILLUMINATE AS RED TO INDICATE RADIO DEACTIVATION. IF THIS OCCURS REPEAT SECTIONS 4.3.1.1 - 4.3.1.4.2.

V. 4.3.1.4.4 THE C-PHASE LEDS IN THE SENSOR STATUS DISPLAY WILL INDICATE THE STRENGTH TO THE LPCN NETWORK.

VI. 4.3.1.4.5 CONTACT SEL FOR TECHNICAL SUPPORT IF THE A-PHASE LEDS IN THE SENSOR STATUS DISPLAY SHOW ANYTHING OTHER THAN FOUR SOLID GREEN LEDS TEN MINUTES AFTER RADIO ACTIVATION.

VII. 4.3.4.3 LOG INTO OTV USING A COMPANY LAN ID AND PASSWORD.

a. IF REQUIRING ACCESS, EMAIL RESPONSIBLE ENGINEER WITHIN EDE.

VIII. 4.3.4.11.11 COMPLETE ALL FIELDS AS FOLLOWS.

a. USE CAPITALIZATION FOR ALL LETTERS.

IX. 4.3.4.3.11.11 EACH "WAY" AND "PHASE" NEEDS A SWITCH POSITION ASSIGNED. SWITCH POSITIONS CAN BE LEFT BLANK IF NOT APPLICABLE IN THIS LOCATION.

a. THIS SHOULD BE RECORDED IN THE JOB PACKAGE BY THE INSTALLATION CREW AND HANDED BACK TO THE IN-HOUSE PLANNER OR DISTRICT ENGINEER.

## REFERENCE:

a. SCHWEITZER ENGINEERING LABORATORIES DOCUMENT QUICK START GUIDE.

b. SCHWEITZER ENGINEERING LABORATORIES DATA SHEET.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 9/28/2020 | E | | | | | | |
| A | ORIGINAL VERSION | EDM | JES | JES | CZH | 1/14/2020 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

SEL 8301 WIRELESS FAULT INDICATOR

UG4344.16

**SCOPE:** THIS STANDARD SHOWS AUTOMATIC SELF RESETTING, HOT STICK OPERABLE FAULT INDICATORS AND INSTALLATION REQUIREMENTS USED FOR INSTALLING AND LOCATING FAULTS IN THE UNDERGROUND SYSTEM.

**CAUTION:**

* NOT FOR USE ON UNSHIELDED CABLE OR BARE CONDUCTORS.







**FIGURE 1**




FOR INSTALLATIONS ON
NEW TERMINATIONS




FOR INSTALLATIONS ON
EXISTING TERMINATIONS

**FIGURE 2**
CORRECT SENSOR CORE INSTALLATION (J) (K)




**FIGURE 3**
INCORRECT SENSOR CORE INSTALLATION (K) (VI)

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 9/28/2020 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1994 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

AUTOMATIC FAULT INDICATOR
SELF RESETTING, HOT STICK OPERABLE



UG4352.1

## INSTALLATION:

A. ATTACH THE EYE OF THE INDICATOR TO A HOT STICK.

B. OPEN THE FLEXIBLE CURRENT SENSING ARM AND, USING THE CABLE AS A LEVERAGE POINT, STRETCH THE SPRING AROUND THE CABLE.

C. GRASP THE EYE ON THE CURRENT SENSING ARM AND CLOSE THE LATCH USING A SECOND HOT STICK.

D. UPON COMPLETION, TRIP TEST EACH SENSOR WITH TEST TOOL (STOCK NUMBER: S746754).

(E) THE THREE-PHASE INDICATORS HAVE THREE SENSOR CORES ATTACHED TO ONE INDICATOR. THE INDICATOR WILL SHOW AN ORANGE OR RED TARGET WHEN A FAULT CURRENT EXCEEDING A TRIP VALUE PASSES THROUGH ANY OF THE THREE SENSOR CORES. RESET WILL OCCUR WHEN A NORMAL LOAD CURRENT OF 5 AMPERES OR MORE FLOWS IN ALL THREE CABLES. ALL THREE SENSOR CORES MUST BE MOUNTED FACING THE SAME DIRECTION.

F. FAULT INDICATORS ARE COMPLETELY SUBMERSIBLE AND WILL READ ACCURATELY MOUNTED IN CORRECT POSITION. DO NOT INSTALL INDICATORS IF THEY CANNOT BE MOUNTED PERMANENTLY.

G. ALL NEW INSTALLATIONS OR REPLACEMENTS MUST BE APPROVED BY DISTRIBUTION PLANNING.

(H) AUXILIARY CONTACT, FOR SCADA USE ONLY.

(J) APPLY FAULT INDICATOR DIRECTLY OVER SEMI-CONDUCTING LAYER "INSULATION SHIELD".

(K) FOR CABLE WITH OR WITHOUT JACKETING.

## BILL OF MATERIALS: NONE

## NOTES:

I. THE USE OF RUBBER GLOVES FOR APPLICATION OF A FAULT INDICATOR IN THE STRESS CONE AREA ON 12KV UNDERGROUND INSTALLATIONS IS PROHIBITED. ANY WORK ON CONDUCTORS OR EQUIPMENT ABOVE 7,500 VOLTS (4,350 VOLTS TO GROUND) MUST BE DONE WITH SUITABLE DEVICES, IE., HOT STICK TOOLS. THIS DOES NOT APPLY TO WORK ON DE-ENERGIZED COMPONENTS (NEW CONDUCTORS BEING PULLED, ETC.) PROVIDED ALL ENERGIZED PARTS WITHIN THE MINIMUM WORKING DISTANCES (2-FOOT RULE) ARE COVERED WITH SUITABLE PROTECTIVE DEVICES.

II. ANY "OLD STYLE" FAULT INDICATORS REMAINING IN THE SYSTEM SHOULD BE REMOVED AND SCRAPPED. THESE ARE MADE BY EDISON CONTROL AND ARE MADE OF BLACK PLASTIC.

III. THE LATEST APPROVED FAULT INDICATORS ARE THREE-PHASE, CURRENT RESET, WHITE PLASTIC UNITS WITH INRUSH RESTRAINT. THAT IS, THEY WILL RESET WITHIN A MINUTE AT 3 AMPS OF LOAD OR MORE AND WILL NOT TRIP ON INRUSH.

IV. EXCESS LEAD LENGTH CAN BE COILED UP AND TAPED AWAY FROM 12KV CABLE AND TERMINATIONS.

V. DUE TO LIMITED SPACE, FAULT INDICATOR SHALL NOT BE INSTALLED IN TERMINATORS.

(VI) MAGNETIC FIELD DUE TO CURRENT IN CENTER CONDUCTOR WILL BE CANCELED BY CURRENT IN CONCENTRIC NEUTRAL.

TABLE OF CONTENTS

### TABLE 1

| CURRENT RESET (THREE-PHASE) FAULT INDICATORS | | | | | |
|---|---|---|---|---|---|
| FOR APPLICATION ON CONDUCTOR SIZE (KCMIL) | TRIP RATING (AMPS) | CALBRATED EXTERNAL DIAMETER (IN) | LEAD LENGTH (FT) | STOCK NUMBER | DESIGN UNITS |
| 350, 750, 1,000 | 800 | 1.5 | 35 | S423762 | FI8-35 |
| 350, 750, 1,000 | 1,000 | 1.5 | 35 | S423760 | FI1K35 |

## REFERENCE:

a. SEE DESIGN MANUAL 6113 FOR APPLICATION CRITERIA.

b. SEE UG3212.5 FOR FAULT INDICATOR LOCATION IDENTIFICATION TAGS.

c. SEE UG4355 FOR INSTALLATION OF FAULT INDICATORS.

d. SEE UG4359 FOR CABLE POLE APPLICATIONS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 9/28/2020 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1994 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS AUTOMATIC SELF RESETTING, HOT STICK OPERABLE FAULT INDICATORS AND INSTALLATION REQUIREMENTS USED FOR INSTALLING AND LOCATING FAULTS IN THE UNDERGROUND SYSTEM.





**FIGURE 1**
TEST POINT CAP TYPE





**FIGURE 2**
INTERNAL ADAPTER RING




**FIGURE 3**
PHASE SENSOR BOOT

## INSTALLATION:

A. INSTALL THE INTERNAL ADAPTER RING (IF NEEDED).

1. FOR HUBBELL, CHARDON, RTE, OR GE-CHARDON ELBOWS WITH MOLDED IN TEST POINTS, SKIP INSTALLATION STEP B.
2. FOR ELASTIMOLD 15, 25, OR 35KV LBE ELBOWS HAVING MOLDED IN TEST POINTS, INSTALL INTERNAL ADAPTER RINGS AS SHOWN IN FIGURE 2. (OTHER ELBOW TYPES CONSULT FACTORY).

B. INSTALL THE PHASE SENSOR BOOT.

(1) REMOVE TEST POINT CAP. CLEAN & DRY TEST POINT. APPLY A LIGHT COAT OF SILICONE DIELECTRIC GREASE TO THE INSIDE OF THE BOOT.

(2) USING A PUSHING AND ROTATING MOTION SEAT THE BOOT ONTO TEST POINT OF THE ELBOW.

(3) ALIGN ARROW ON TEST POINT LABEL WITH ELBOW PULLING EYE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CAPACITIVE TEST POINT FAULTED CIRCUIT INDICATOR | -- | -- | S423770 | FI1-TP |

**NOTES:** NONE

**REFERENCE:** NONE

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | ADW | JES | CZH | 11/12/2019 | F | | | | | | |
| B | TABLE UPDATE | - | JK | JS | CZH | 03/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | AW | JS | CZH | 07/05/2018 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CAPACITIVE TEST POINT FAULTED CIRCUIT INDICATOR



UG4354.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF FAULT INDICATORS IN PAD-MOUNTED AND SUBSURFACE EQUIPMENT.





**FIGURE 1**






**FIGURE 2**

**TABLE 1**

| ITEM | STOCK NUMBER |
|---|---|
| LEXAN VIEWING WINDOW | S443830 |




**DETAIL 1**
LEXAN VIEWING WINDOW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/CAK | 1/1/1998 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FAULT INDICATOR INSTALLATION
PAD-MOUNTED INSTALLATION

UG4355.1





**FIGURE 3**
THREE-PHASE PAD-MOUNTED SWITCH

**TABLE 2**

| THREE-PHASE PAD-MOUNTED SWITCH | | |
|---|---|---|
| **REPLACEMENT SWITCH SILL** | **STOCK NUMBER** | **DESIGN UNITS** |
| NELSON SWITCH SILL (E) | S648502 | SILL-N |
| ESCO SWITCH SILL (E) | S648500 | SILL-E |

## INSTALLATION:

A. FOLLOW INSTALLATION INSTRUCTIONS IN VIEWING WINDOW KIT.

B. FOR RETROFIT INSTALLATION OF VIEWING WINDOWS IN NON-STANDARD (OLD STYLE) PAD-MOUNTED SWITCHES, ABOVE TO SENSOR.

C. APPLY RUST INHIBITOR AND SAME COLOR PAINT AS CABINET ON ALL HOLES DRILLED OR PUNCHED IN CABINET.

D. STANDARD AND NON-STANDARD PAD-MOUNTED SWITCHES SHALL REQUIRE FAULT INDICATORS WITH 35-FOOT LEADS. TIE OFF EXCESS LEADS AS NEEDED.

(E) FOR STANDARD PAD-MOUNTED SWITCHES, USE NELSON OR ESCO REPLACEMENT SILLS FOR RETROFIT INSTALLATION.

F. ALL NEW SWITCHES COME WITH VIEWING WINDOWS INSTALLED IN FRONT BOTTOM SILL OF CABINET.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG3212.5 FOR FAULT INDICATOR IDENTIFICATION.

b. SEE UG4352 FOR AUTOMATIC FAULT INDICATORS APPLICATION AND SELECTION.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/CAK | 1/1/1998 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF FAULT INDICTORS IN PME 9, 10 AND 11 AIR BREAK SECTIONALIZING SWITCHES.





**FIGURE 1**





**FIGURE 2**
FRONT VIEW





**FIGURE 2**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/CAK | 1/1/1998 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |





**FIGURE 3**
HANDHOLE INSTALLATION

**TABLE 1**

| ITEM | STOCK NUMBER |
|---|---|
| 1/4" ANCHOR | S107666 |





**FIGURE 4**
HANDHOLE INSTALLATION

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/CAK | 1/1/1998 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



FAULT INDICATOR INSTALLATION

UG4355.4

TABLE OF CONTENTS






**FIGURE 5**
MANHOLE INSTALLATION




**DETAIL 1**

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/CAK | 1/1/1998 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |

## INSTALLATION:

A. REMOVE THE STAINLESS STEEL BRACKET SUPPLIED BY THE FAULT INDICATOR MANUFACTURER.

B. THE REMAINING STAINLESS STEEL NUT AND BOLT IS USED TO ATTACH THE FAULT INDICATOR TO MOUNTING PLATE SUPPLIED BY SWITCH MANUFACTURER.

(C) ALL MEASUREMENTS SHOWN ARE APPROXIMATE - EXACT PLACEMENT OF THE FAULT INDICATOR TARGET WILL HAVE TO BE DETERMINED INDIVIDUALLY, USING THE FRAME AND COVER INTENDED FOR THAT INSTALLATION.

D. ATTACH LEADS TO HANDHOLE WALL.

(E) THREE FAULT INDICATORS MAY BE INSTALLED UNDER ONE VIEWING PORT.

(F) MOUNT FAULT INDICATORS SO THE TARGET IS VISIBLE WHEN MANHOLE COVER IS REMOVED.

G. ATTACH LEADS TO MANHOLE WALL.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG3212.5 FOR FAULT INDICATOR IDENTIFICATION.

b. SEE UG4352 FOR AUTOMATIC FAULT INDICATORS APPLICATION AND SELECTION.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | RSW/CAK | 1/1/1998 | F | | | | | | |
| B | REVISION | - | - | - | RSW/RDJ | 1/1/1996 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1992 | D | FORMATTING | EDM | JIK | - | - | 9/28/2020 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

FAULT INDICATOR INSTALLATION



UG4355.6

**SCOPE:** THIS STANDARD SHOWS AND DESCRIBES THE INSTALLATION OF OVERHEAD FAULT INDICATORS WITH RATINGS OF 800 AND 1000 AMPS ON 3/0, 4/0, 336 AND 636 CONDUCTORS.

**CAUTION:**

* DO NOT INSTALL DOWNSTREAM OF A FUSE.





**FIGURE 1**

**TABLE 1**

| OVERHEAD FAULT INDICATORS | | | | | |
|---|---|---|---|---|---|
| FOR APPLICATION ON CONDUCTOR SIZE | TRIP RATING (AMPS) | CALIBRATED EXTERNAL DIAMETER (IN) | STOCK NUMBER | DESIGN UNITS | |
| | | | | UG | OH |
| 3/0, 4/0, 336, 636 | 800 | 0.700 | S423750 | FI800 | 800FI |
| 3/0, 4/0, 336, 636 | 1,000 | 0.700 | S423752 | FI1000 | 1000FI |

**INSTALLATION:**

A. THESE ARE SINGLE PHASE, SELF-CONTAINED UNITS WITH ELECTROSTATIC RESET AND INRUSH RESTRAINT. THEY WILL RESET THEMSELVES AFTER SEVERAL MINUTES OF AT LEAST 5KV LINE-TO-GROUND POTENTIAL.

(B) THE INDICATOR WILL SHOW AN ORANGE OR RED TARGET WHEN A FAULT CURRENT EXCEEDING A TRIP VALUE PASSES THROUGH IT'S SENSOR CORE. RESET WILL OCCUR WITHIN SEVERAL MINUTES WHEN THE CONDUCTOR HAS A LINE TO GROUND VOLTAGE OF 5KV OR MORE.

C. ALL NEW INSTALLATION OR REPLACEMENT OF FAULT INDICATORS MUST BE APPROVED BY DISTRIBUTION PLANNING.

D. ANY "OLD STYLE" FAULT INDICATORS REMAINING IN THE SYSTEM SHOULD BE REMOVED AND SCRAPPED. THESE ARE SINGLE AND THREE PHASE UNITS WITH A REMOTE TARGET, BLACK IN COLOR, AND MANUFACTURED BY EDISON CONTROL.

E. UPON COMPLETION OF INSTALLATION, TRIP TEST EACH FAULT INDICATOR WITH TEST TOOL (STOCK NO. S746756).

**BILL OF MATERIALS:** NONE

**NOTES:**

I. TYPICAL APPLICATIONS ARE FEEDER CABLE POLES, LINE SWITCHES AND FEEDER SPLIT POINTS.

II. INSTALL FAULT INDICATORS DIRECTLY ON OVERHEAD LINE CONDUCTORS UNLESS MONITORING A CABLE FED FROM A POLE WITH TANGENT OVERHEAD CONDUCTORS. IN THIS CASE, INSTALL FAULT INDICATORS ON JUMPERS FROM OVERHEAD CONDUCTOR TO SWITCH.

III. THE INDICATOR IS PLACED ON AN OVERHEAD CONDUCTOR USING HOT LINE TOOLS. REFER TO INSTALLATION SHEET PROVIDED WITH EACH UNIT FOR DETAILS.


**REFERENCE:**

a. SEE DESIGN MANUAL DM6113 FOR APPLICATION CRITERIA.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 9/28/2020 | F | | | | | | |
| B | DRAWING UPDATE | - | PEI | - | - | 2/18/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | RDG | 1/1/1996 | D | | | | | | |

**SCOPE:** THIS STANDARD DESCRIBES THE LOAD TRACKER FAULT INDICATOR FOR INSTALLATION ON CLEER TEES.




CONFIGURATION 1
ALLOWED INSTALLATION (V)
ABOVE CONCENTRIC NEUTRAL GROUND

CONFIGURATION 2
ALLOWED INSTALLATION
OVER CONCENTRIC NEUTRAL (VI)
GROUND AND FOLDBACK

CONFIGURATION 2
VIEW A-A

CONFIGURATION 3
NOT ALLOWED INSTALLATION
ELBOW MOUNTED

**FIGURE 1**
LOAD TRACKER INSTALLATION CONFIGURATIONS





**FIGURE 2**
INSTALLATION ON (b)
N-JUNCTION CLEER




**FIGURE 3**
LOAD TRACKER
IN CLOSED POSITION




**FIGURE 4**
LOAD TRACKER
IN OPEN POSITION

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ADW | GLW | CZH | 07/29/2021 | D | | | | | | |

## INSTALLATION:

(A) IF THERE IS A FAULT IN A PHASE, A LIGHT WILL FLASH ON THIS DEVICE INDICATING WHICH PHASE HAS THE FAULT. THE FIBER PORT HOLE MUST BE POSITIONED SO THE FLASHING LIGHT WILL BE VISIBLE WHEN INSTALLATION IS COMPLETE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| 1 | LOAD TRACKER, FAULT INDICATOR, UG, PDP, LARGE (VIII) | | | AS REQ'D | -- | S423714 | DULTFI |
| 2 | LOAD TRACKER, FAULT INDICATOR, UG, PDP, SMALL (IX) | | | AS REQ'D | -- | S423718 | RFOS |
| 3 | BAR, JUNCTION, 600A CLEER, 15KV, LOADBREAK (IX) | A | INLINE | AS REQ'D | 4198 | S439870 | CCL-JB |
| | | B | SQUARE | | | S439872 | CCL-SQ |

## NOTES:

I. THE POWER DELIVERY PRODUCTS (PDP) LOAD TRACKER IS AN UNDERGROUND FAULT INDICATOR WHICH CAN BE ELBOW OR CABLE MOUNTED. IT IS REQUIRED WITH 600A CLEER CONNECTORS, FOR ISOLATING PADMOUNT EQUIPMENT SUCH AS MVI (MOLDED VACUUM INTERRUPTER) AND IN DEADFRONT TERMINATOR CONSTRUCTION.

II. THIS DEVICE IDENTIFIES PEAK LOAD CURRENT, ADJUSTS TO THE PROPER TRIP RATING AND HOLDS IT FOR 72 HOURS.

III. APPROVED FOR 200A AND 600A SYSTEMS.

IV. THIS DEVICE CAN BE UTILIZED UNDER WATER AS IT HAS A PORT FOR FIBER OPTIC CABLE TO BRING INDICATION TO A VISIBLE POINT WITHOUT DEWATERING A STRUCTURE.

(V) FAULT CURRENT INDICATOR (FCI) SEES FAULT CURRENT AND DOES NOT SEE RETURN CURRENT.

(VI) FCI SEES FAULT CURRENT TWO TIMES IN THE FORWARD DIRECTION AND ONE TIME IN THE REVERSE DIRECTION.

(VII) LOAD TRACKER SHALL NOT BE INSTALLED IN THIS AREA BECAUSE FAULT CURRENT AND RETURN CURRENT WILL CANCEL EACH OTHER OUT.

(VIII) THE 600A CLEER CONNECTOR WILL ONLY USE THIS ITEM.

(IX) NOT SHOWN ON FIGURES.

## REFERENCE:

a. FOR FAULT CLOSE TEST JUMPER, SEE ESP 220.

(b) SEE UG4198: N-JUNCTION CLEER 600A 25KV AND SQUARE CLEER 600A 25KV.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FIGURE UPDATE | EDM | EJA | JAS | KRG | 04/11/2023 | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ADW | GLW | CZH | 07/29/2021 | D | | | | | | |

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 4405 | FMO LUMINAIRE REPLACEMENT BALLASTS AND STARTERS |
| 4410 | HIGH INTENSITY DISCHARGE LAMPS |
| 4412 | PHOTOELECTRIC CONTROLS |
| 4413 | NUMBERING ORNAMENTAL STREET LIGHT POLES |
| 4414 | STREET LIGHT OWNERSHIP AND MAINTENANCE IDENTIFICATION DECAL |
| 4422 | STANDARD AND DECORATIVE LUMINAIRES |
| 4423 | POST TOP LUMINAIRES |
| 4424 | DOMESTIC WALKWAY LIGHTING (DWL) LUMINAIRES |
| 4430 | DIRECT BURIAL POLE INSTALLATION FOR VICTORIAN LUMINAIRES |
| 4431 | DIRECT BURIAL POLE INSTALLATION FOR CONVENTIONAL LUMINAIRES |
| 4432 | DIRECT BURIAL POLE INSTALLATION FOR MISSION BELL LUMINAIRES |
| 4433 | DIRECT BURIAL POLE INSTALLATION FOR DECORATIVE LUMINAIRES |
| 4434 | DIRECT BURIAL POLE INSTALLATION FOR DOMESTIC WALKWAY LIGHTING AND POST TOP LUMINAIRES |
| 4435 | HANDHOLE (INSIDE DIMENSIONS - 10-1/4" X 15-3/8") |
| 4470 | ROADWAY LED LIGHTING INSTALLATION |
| 4471 | GE EVOLVE LED ROADWAY LIGHTING FIXTURES |
| 4472 | CREE LED ROADWAY LIGHTING FIXTURES |
| 4473 | ACUITY LED ROADWAY LIGHTING FIXTURES |
| 4480 | LED DECORATIVE LIGHTING FIXTURES (RESERVED) |


© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | ADDED 4470, 4471, 4480 | - | JIK | JES | CZH | 08/20/2019 | F | REFORMAT | EDM | JIK | - | - | 01/18/2022 |
| B | UPDATES TO 4412 | - | GW | TR | MDJ | 10/25/2016 | E | ADDED 4472 TO TABLE OF CONTENTS | AMP | RSL | JES | CZH | 04/28/2021 |
| A | UPDATES TO 4414 | - | GW | TR | MDJ | 09/27/2016 | D | EDITORIAL CHANGES | GLC | JIK | GLW | CZH | 06/08/2020 |

Indicates Latest Revision | Completely Revised | New Page X | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

LIGHTING SECTION
TABLE OF CONTENTS

**SCOPE:** THIS STANDARD PROVIDES ALL THE NECESSARY ORDERING INFORMATION FOR REPLACEMENT BALLASTS AND STARTERS FOR LUMINAIRES IN FMO SECTION.

## TABLE 1

| REPLACEMENT BALLASTS FOR LUMINAIRES (a) | | | | | | |
|---|---|---|---|---|---|---|
| BALLAST | | LAMP SIZE (WATTS) | MANUFACTURER | | STOCK CODE | KIT/ASSEMBLY |
| TYPE | SOURCE VOLTAGE | | MANUFACTURER | TYPE/SERIES | | |
| REACTOR-NPF | 120 | 150 | GENERAL ELECTRIC | M250A2 | S121108 | ASSEMBLY |
| | | | | M250A | | |
| | | 100 | | M250A | S121142 | |
| | | 150 | | M400A | S121146 | |
| | | 250 | | M400A2 | S121148 | |
| | | 400 | | M250A2 | S121150 | |

## TABLE 2

| REPLACEMENT STARTERS FOR LUMINAIRES (a) | | | | |
|---|---|---|---|---|
| MANUFACTURER | TYPE | LAMP SIZE (WATTS) | SOURCE VOLTAGE | STOCK NUMBER |
| AMERICAN ELECTRIC | SERIES 113 | 35-400 | 120 | S679130 |
| GENERAL ELECTRIC | M250R2 | 50-150 | | S679132 |
| | M400R2 | 250-400 | | S679134 |

## TABLE 3

| REPLACEMENT BALLASTS FOR LUMINAIRES | | | | | | |
|---|---|---|---|---|---|---|
| BALLAST | | LAMP SIZE (WATTS) | MANUFACTURER | | STOCK CODE | KIT/ASSEMBLY |
| TYPE | SOURCE VOLTAGE | | MANUFACTURER | TYPE/SERIES | | |
| REACTOR-NPF | 120 | 150 | GENERAL ELECTRIC | MISSION BELL | S121171 | ASSEMBLY |
| | | 100 | | | S121170 | |
| | | 150 | | | S121168 | |

## TABLE 4

| REPLACEMENT STARTERS FOR LUMINAIRES | | | | |
|---|---|---|---|---|
| MANUFACTURER | TYPE | LAMP SIZE (WATTS) | SOURCE VOLTAGE | STOCK NUMBER |
| GENERAL ELECTRIC | MISSION BELL | 50-150 | 120 | S679132 |

## TABLE 5

| REPLACEMENT BALLASTS FOR LUMINAIRES | | | | | | |
|---|---|---|---|---|---|---|
| BALLAST | | LAMP SIZE (WATTS) | MANUFACTURER | | STOCK CODE | KIT/ASSEMBLY |
| TYPE | SOURCE VOLTAGE | | MANUFACTURER | TYPE/SERIES | | |
| REACTOR-NPF | 120 | 50 | McGRAW EDISON | TRADITIONAIRE | S442934 | KIT |
| | | 70 | | | S442921 | |
| | | 100 | | | S442922 | |
| | | 150 | | | S442924 | |

## TABLE 6

| REPLACEMENT STARTERS FOR LUMINAIRES | | | | |
|---|---|---|---|---|
| MANUFACTURER | TYPE | LAMP SIZE (WATTS) | SOURCE VOLTAGE | STOCK NUMBER |
| ADVANCE TRANSFORMER CO. | TRADITIONAIRE | 50-150 | 120 | S422612 |
| GENERAL ELECTRIC | | | | S679136 |
| COOPER LIGHTING | | 35-150 | | S679138 |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | - | PJA/MJC | 12/13/2011 | E | | | | | | |
| A | REVISION | - | - | - | PJA/JJ | 02/13/2007 | D | | | | | | |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

(a) SEE FMO PAGES OH1599.203UG4499.203

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | - | PJA/MJC | 12/13/2011 | E | | | | | | |
| A | REVISION | - | - | - | PJA/JJ | 02/13/2007 | D | | | | | | |

**SCOPE:** THIS STANDARD DESCRIBES ALL THE NECESSARY INFORMATION WHEN ORDERING LAMPS FOR MERCURY VAPOR, HIGH PRESSURE AND LOW PRESSURE SODIUM LUMINARIES.

## INSTALLATION:

(A) CLEAR MERCURY VAPOR LAMPS.

(B) DELUXE WHITE OR PHOSPHOR COATED LAMPS, IDENTIFIED BY 'DX'.

C. RATING BASED ON 16,000 HOURS ON LAMPS.

(D) LAMPS NOW BEING PURCHASED WILL WORK IN EITHER BASE UP OR BASE DOWN CONFIGURATION.

(E) LPSV LAMPS MUST BE INSTALLED HORIZONTAL OR BASE UP, AS SHOWN ON THE FOLLOWING FIGURES:





**FIGURE 1**
FOR 35 AND 55W (E)





**FIGURE 2**
FOR 90, 135 AND 180W (E)

F. INSTALLER IS TO SCRIBE A VERTICAL LINE UNDER THE MONTH AND LAST DIGIT OF THE CURRENT YEAR WHEN INSTALLING LAMPS.

**BILL OF MATERIALS:** NONE

## TABLE 1

| HIGH PRESSURE SODIUM VAPOR (HPSV) (D) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| LAMP SIZE (WATTS) | MANUFACTURER | | | ANSI LAMP DESIGNATION | LENGTH (IN) | APPROXIMATE LUMENS | | STOCK NUMBER | DESIGN UNITS |
| | GE LUCALUX | SYLVANIA LUMALUX | N.A. PHILIPS CERAMALUX | | | INITIAL | MEAN | | |
| 50 | LU-50 | LU-50 | C-50S68 | S68MS-50 | 7 3/4 | 4,000 | 3,600 | S452578 | LH50 |
| 70 | LU-70 | LU-70 | C-70S62 | S62ME-70 | 7 3/4 | 5,800 | 5,220 | S452580 | LH70 |
| 100 | LU-100 | LU-100 | C-100S54 | S54SB-100 | 7 3/4 | 9,500 | 8,550 | S452582 | LH100 |
| 150 | LU-150/55 | LU-150/55 | C-150S55 | S55SC-150 | 7 3/4 | 16,000 | 14,400 | S452584 | LH150 |
| 200 | LU-200 | LU-200 | C-200S66 | S66MN-200 | 9 3/4 | 22,000 | 19,800 | S452587 | LH200 |
| 250 | LU-250 | LU-250 | C-250S50/S | S50VA-250/S | 9 3/4 | 30,000 | 27,000 | S452588 | LH250 |
| 310 | LU-310 | LU-310 | C-310S67 | S67MR-310 | 9 3/4 | 37,000 | 33,000 | S452591 | LH310 |
| 400 | LU-400 | LU-400 | C-400S51 | S51WA-400 | 9 3/4 | 50,000 | 45,000 | S452592 | LH400 |
| 1000 | LU-1000 | LU-1000 | C-1000S52 | S52XB-1000 | 15 1/16 | 140,000 | 126,000 | S452594 | LH1000 |

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/04/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | RDG | 01/01/1996 | D | | | | | | |

## TABLE 2

| MERCURY VAPOR (MV) (D) (NO LONGER USED IN NEW INSTALLATION) | | | | | | | |
|---|---|---|---|---|---|---|---|
| LAMP SIZE (WATTS) | MANUFACTURER | | ANSI LAMP DESIGNATION | LENGTH (IN) | APPROXIMATE LUMENS | | STOCK NUMBER |
| | GE CATALOG NUMBER | SYLVANIA & N.A. PHILIPS CATALOG NUMBERS | | | INITIAL | MEAN (B) | |
| 175 | H175A39-22 | H39KB-175 | H39KB-175 | 8 1/4 | 7,950 | 7,470 | S452352 (A) |
| | H175DX39-22 | H39KC-175/DX | H39KC-175/DX | | 8,600 | 7,650 | S452580 (B) |
| 250 | H25OA37-5 | H37KB-250 | H37KB-250 | 8 1/4 | 11,200 | 10,300 | S452384 (A) |
| | H25ODX37-5 | H37KC-250/DX | H37KC-250/DX | | 12,100 | 10,400 | S452400 (B) |
| 400 | H40OA33-1 | H33CD-400 | H33CD-400 | 11 5/16 | 21,000 | 19,100 | S452416 (A) |
| | H40ODX33-1 | H33GL-400/DX | H33GL-400/DX | | 22,500 | 19,100 | S452448 (B) |
| 700 | H70ODX35-18 | H35ND-700/DX | H35ND-700/DX | 14 5/16 | 42,000 | 33,600 | S452576 (B) |

## TABLE 3

| LOW PRESSURE SODIUM VAPOR (LPSV) (E) | | | | | |
|---|---|---|---|---|---|
| LAMP SIZE (WATTS) | ANSI LAMP DESIGNATION | LENGTH (IN) | APPROXIMATE LUMENS | STOCK NUMBER | DESIGN UNITS |
| 35 | L70RB-35 | 12.2 | 4,800 | S452270 | LL35 |
| 55 | L71RC-55 | 16.7 | 8,000 | S452280 | LL55 |
| 90 | L72RD-90 | 20.8 | 13,500 | S452282 | L90 |
| 135 | L73RE-135 | 30.5 | 22,500 | S452284 | LL135 |
| 180 | L74RF-180 | 44.1 | 33,000 | S452286 | LL180 |

TABLE OF CONTENTS

## NOTES:

(I) ALL LAMPS MUST BE DATE CODED WHEN INSTALLED. SCRIBE A VERTICAL LINE BELOW THE MONTH AND YEAR LOCATED ON THE BASE OF LAMPS. SINCE LAMPS ARE GROUP REPLACED, ONLY THE LAST DIGIT OF THE YEAR IS USED. THEY SHOULD NEVER BE OLDER THAN TEN YEARS. THE FOLLOWING EXAMPLE INDICATES A JUNE 1985 INSTALLATION:




**FIGURE 3** (I)

## REFERENCE:

a. FOR G.O. 95 MINIMUM CLEARANCE, SEE OH1509.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/04/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | PTA | RDG | 01/01/1996 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS SEVERAL TYPES OF PHOTOELECTRIC CONTROLS THAT CAN BE USED FOR STREET LIGHT LUMINAIRES.





**FIGURE 1**





**FIGURE 2**





**FIGURE 3**

## INSTALLATION:

A. PHOTOELECTRIC CONTROL SHOULD BE MOUNTED WITH THE PHOTO CELL FACING NORTH.

B. FOR USE ON AUXILIARY HOLIDAY LIGHTING.

(C) USED ON AMERON VICTORIAN LUMINAIRE, LAWNAIRE, LOMALITER.

(D) WHEN INSTALLING AND REMOVING PHOTO-ELECTRIC CONTROLS, INSTALLER IS TO SCRIBE A VERTICAL LINE UNDER THE CURRENT MONTH AND YEAR OR ENTER THE CURRENT DATE IN THE SPACE PROVIDED.

E. USED ON AMERON VICTORIAN LUMINAIRES.

**TABLE 1**

| PHOTOELECTRIC CONTROLS | | | | | |
|---|---|---|---|---|---|
| ITEM | RATING | | NEMA COLOR CODE | STOCK NUMBER | DESIGN UNITS |
| | VOLTS | WATTS | | | |
| (1) | 120 TO 277 | 1,000 | GRAY | S273884 (I) | PC-TL |
| (2) | 185 to 305 | 1,000 | RED | S273890 | PCTL |
| (3) | 120 | 1,000 | GRAY | S273886 | PC-AUX |
| (4) | 105 TO 130 | 1,000 | GRAY | S273700 (C) | PC-MGE |
| (5) | 105 TO 130 | 1,000 | GRAY | S273700 (C) | PC-AM |

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) S273884 HAS A TEN YEAR WARRANTY. PHOTO-CELL FAILURE RETURN TO ELECTRIC DISTRIBUTION ENGINEERING.

**REFERENCE:** NONE

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/04/2019 | E | | | | | | |
| A | COMPLETELY REVISED | - | GW | IL | MDJ | 10/03/2016 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| SHEET 1 OF 1 | X Indicates Latest Revision | Completely Revised | New Page | Information Removed |
| | SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS | | | |
| | PHOTOELECTRIC CONTROLS | | | OH1512.1 UG4412.1 |

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND REQUIREMENTS FOR TAGGING SDG&E OWNED ORNAMENTAL STREET LIGHT POLES.





**FIGURE 1**





**FIGURE 2**

## INSTALLATION:

A. ALL TAGS TO BE ATTACHED BY DRILLING TWO HOLES AS SHOWN ABOVE USING SELF TAPPING SCREWS OR EPOXY PASTE.

B. WORK ORDER SKETCHES, TEXT AND MATERIAL LISTS WILL SPECIFY NUMBERS TO BE ATTACHED TO POLES.

(C) FOR USE IN CORROSIVE AREAS.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | TAPE, ROLL, ALUMINUM EMBOSSING, 7/8" | AS REQ'D | -- | S720704 | -- |
| 2 | TAPE, ROLL, BRASS EMBOSSING, 7/8" | AS REQ'D | -- | S720736 (C) | -- |
| 3 | SCREW, SELF TAPPING DRIVE, STAINLESS STEEL, #4 - 1/4" | 2 | -- | S621346 (X) | -- |
| 4 | EPOXY PASTE | AS REQ'D | -- | S213244 | -- |

## NOTES:

I. TAG SDG&E OWNED POLES ONLY-DO NOT TAG POLES OWNED BY OTHERS.

II. DO NOT RETAG (WITH NEW IDENTIFICATION NUMBERS). EXISTING POLES THAT HAVE OLD CAL-GRID OR POLE DISTRICT NUMBERS. THE OLD NUMBER STILL APPLIES FOR IDENTIFICATION PURPOSES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR EXISTING CAL-GRID OR POLE NUMBERING DISTRICT TAGS, SEE FMO UG4499.101.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | REVISION | - | - | - | RW/CAK | 01/01/1998 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

NUMBERING ORNAMENTAL STREET LIGHT POLES



UG4413.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS A UNIFORM METHOD FOR IDENTIFYING SDG&E OWNED AND/OR MAINTAINED STREET LIGHTS.DECALS WILL BE ADDED TO ALL APPLICABLE NEW STREET LIGHTS WHEN INSTALLED, OR ON EXISTING LIGHTS WHEN MAINTAINED.





**FIGURE 1**





**FIGURE 2**





**FIGURE 3**





**FIGURE 4**




**FIGURE 5**





**FIGURE 6**

**TABLE 1**

| DECALS FOR STREET LIGHT IDENTIFICATION | | | |
|---|---|---|---|
| **ITEM** | **DESCRIPTION** | **SCHEDULE** | **STOCK NUMBER** |
| 1 | "SDG&E" DECAL, 2 5/8" X 1 7/8" | LSI, OL1, DWL | S332850 |
| 2 | YELLOW "M" DECAL, 1" X 1" | LS2B | S302112 |

TABLE OF CONTENTS

## INSTALLATION:

A. CLEAN SURFACE WITH SOLVENT BEFORE APPLYING DECAL. DECAL HAS A PRESSURE SENSITIVE ADHESIVE BACKING.

B. THE DECAL SHALL BE LOCATED ON THE STREET SIDE OF ALL LUMINAIRES.

C. THE DECAL SHALL BE LOCATED SO IT IS VISIBLE FROM THE GROUND. DO NOT PLACE DECAL ON THE REFRACTOR OR OBSTRUCT EXISTING DECALS OR VENT HOLES. IF VARIATIONS FROM THESE LOCATION ARE REQUIRED, CONTACT DISTRIBUTION STANDARDS.

D. DECAL SHALL BE SECURED TO THE UNDERSIDE OF THE MAST ARM, 3 INCHES MINIMUM FROM POLE.

E. FOR DUAL LUMINAIRE INSTALLATIONS, TWO (2) DECALS ARE REQUIRED.

F. IF DURING MAINTENANCE, A YELLOW LETTER "O" OR A BLUE LETTER "M" DECAL EXISTS, REMOVE THE OLD DECAL AND REPLACE WITH "SDG&E" OR YELLOW "M" DECAL.

**BILL OF MATERIALS:** NONE

## NOTES:

I. FIGURES 1 THROUGH 4 ARE SHOWN AS TYPICAL STREET LIGHT LUMINAIRES ONLY. (a)

II. THE "SDG&E" DECAL INDICATES THE STREET LIGHT IS OWNED AND MAINTAINED BY SDG&E.

III. THE YELLOW "M" DECAL INDICATES THE STREET LIGHT IS MAINTAINED BY SDG&E AND OWNED BY OTHERS.

## REFERENCE:

(a) FOR SPECIFIC DETAILS, SEE UG4421, UG4422, UG4423, AND UG4424.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | DRAWING UPDATE | PEI | - | - | - | 02/04/2019 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | GW | MDJ | 09/15/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

STREET LIGHT OWNERSHIP AND MAINTENANCE IDENTIFICATION - DECAL

OH1514.1
UG4414.1

**SCOPE:** THIS STANDARD SHOWS STANDARD AND DECORATIVE LUMINAIRES USED FOR ROADWAY AND AREA LIGHTING.





**FIGURE 1**
SIERRA LIGHTING
MISSION BELL LUMINAIRE
(70, 100, 150 & 250W HPSV SHOWN)





**FIGURE 2**
GENERAL ELECTRIC
DECASHIELD LUMINAIRE
D-400
(250W SHOWN)





**FIGURE 3**
GENERAL ELECTRIC
POWER FLOOD
(1000W SHOWN)





**FIGURE 4**
BIEBER
PARK LANE LUMINAIRE
(70W SHOWN)






**FIGURE 5**
COOPER CONCOURSE
(70W SHOWN)




**DETAIL 1**
DRILLING DETAIL

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 03/24/2008 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 01/22/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

STANDARD AND DECORATIVE LUMINAIRES



UG4422.1

## TABLE 1

| STANDARD AND DECORATIVE LUMINAIRES | | | | | | |
|---|---|---|---|---|---|---|
| FIGURE NO. | BALLAST | | | | LUNINAIRE | |
| | TYPE | LAMP (WATTS) | LAMP TYPE | SOURCE (VOLTS) | MANUFACTURER | STOCK NUMBER |
| 1 | REACTOR - NPF | 70 | HPSV | 120 | SIERRA LIGHTING | S474662 |
| | REACTOR - NPF | 100 | | | | S474620 |
| | REACTOR - NPF | 150 | | | | S474624 |
| | REGULATOR | 250 | | | | S474660 |
| 2 | AUTO - REGULATOR | | | | GENERAL ELECTRIC CO. | S474426 |
| 3 | REGULATOR | | | | | S474452 |
| | REGULATOR | 400 | | | | S474454 |
| | AUTO - REGULATOR | 1,000 | | | | S474456 |
| 4 | REACTOR - NPF | 70 | | | BIEBER LIGHTING | S473384 |
| 5 | REACTOR - NPF | | | | COOPER | S473220 |

## INSTALLATION:

A. ALL PHOTO ELECTRIC RECEPTACLES ARE WIRED FOR 120V.

B. DUAL VOLTAGE BALLASTS RATED 120 X 240V ARE FACTORY WIRED FOR 120V OPERATION.

C. THESE LUMINAIRES ARE INSTALLED ON AN 8-INCH LONG, 2-INCH DIAMETER MAST ARM.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. FOR REPLACEMENT LAMPS, SEE UG4410.

b. FOR DIRECT BURIAL POLE INSTALLATION FOR MISSION BELL LUMINAIRES, SEE UG4432.

c. FOR DIRECT BURIAL POLE INSTALLATION FOR DECORATIVE LUMINAIRES, SEE UG4433.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 03/24/2008 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 01/22/2007 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS POST TOP LUMINAIRES FOR ROADWAY LIGHTING.





**FIGURE 1**
GENERAL ELECTRIC
POST TOP
(LAWNAIRE REPLACEMENT)





**FIGURE 2**
GENERAL ELECTRIC
SALEM POST TOP
(REPLACES TRADITIONAIRE)





**FIGURE 3**
GENERAL ELECTRIC
TOWN & COUNTRY





**FIGURE 4**
HOLOPHANE
RSL 350





**FIGURE 5**
GENERAL ELECTRIC
STREET ORNAMENT COLONIAL 2

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | - | PJA/JJ | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | - | PJA/JJ | 01/22/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



POST TOP LUMINAIRES

UG4423.1

## TABLE 1

| POST TOP LUMINAIRE | | | | | | |
|---|---|---|---|---|---|---|
| FIGURE | BALLAST | | | | LUMINAIRE | |
| | TYPE | LAMP (WATTS) | LAMP TYPE | SOURCE (VOLTS) | MANUFACTURER | STOCK NUMBER |
| 1 | REACTOR-NPF | 70 | HPSV | 120 | GENERAL ELECTRIC CO. | S473212 |
| | | 100 | | | | S473232 |
| 2 | | 70 | | | | S473216 (C) |
| | | 100 | | | | S474688 (C) |
| | | 150 | | | | S474696 (C) |
| 3 | | 70 | | | | S473226 |
| | | 100 | | | | S474590 |
| 4 | | | | | HOLOPHANE | S474594 |
| 5 | REACTOR | 70 | | | GENERAL ELECTRIC CO. | S473210 |

## INSTALLATION:

A. ALL P.E. RECEPTACLES ARE WIRED FOR THE SOURCE VOLTAGE SHOWN.

B. FIGURES 1, 2, 3, AND 5 ARE EQUIPPED WITH ACRYLIC REFRACTORS. FIGURE 4 IS EQUIPPED WITH GLASS REFRACTORS.

(C) THIS LUMINAIRE SHALL BE INSTALLED SO THAT THE LADDER ARM IS PARALLEL TO THE CURB.

D. THE MOUNTING HEIGHT FOR THESE LUMINAIRES IS 17 FEET.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

## REFERENCE:

a. FOR REPLACEMENT LAMPS, SEE UG4410.

b. FOR REPLACEMENT PHOTO ELECTRIC CONTROLS, SEE UG4412.

c. FOR DIRECT BURIAL POLE INSTALLATION FOR DOMESTIC WALKWAY LIGHTING, SEE UG4434.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | - | PJA/JJ | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | - | PJA/JJ | 01/22/2007 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS POST TOP LUMINAIRES FOR WALKWAY LIGHTING.





**FIGURE 1**
GENERAL ELECTRIC
SALEM POST TOP
(REPLACES TRADITIONAIRE)





**FIGURE 2**
GENERAL ELECTRIC
TOWN & COUNTRY

## TABLE 1

| DOMESTIC WALKWAY LIGHTING (DWL) LUMINAIRES | | | | | | |
|---|---|---|---|---|---|---|
| FIGURE NO. | BALLAST | | | | LUMINAIRE | |
| | TYPE | LAMP (WATTS) | LAMP TYPE | SOURCE (VOLTS) | MANUFACTURER | STOCK NUMBER |
| 1 | REACTOR -NPF | 50 | HPSV | 120 | GENERAL ELECTRIC CO. | S474678 |
| 2 | | | | | | S474516 |

## INSTALLATION:

A. NORMALLY USED WITH AN IES TYPE V SYMMETRIC LIGHT PATTERN.
B. ALL P.E. RECEPTACLES ARE WIRED FOR 120V.
C. DUAL VOLTAGE BALLASTS RATED 120 X 240V ARE FACTORY WIRED FOR 120V OPERATION.
D. THE MOUNTING HEIGHT FOR THE LUMINAIRES IS 9 FEET.

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. FOR REPLACEMENT LAMPS, SEE UG4410.
b. FOR REPLACEMENT PHOTO ELECTRIC CONTROLS, SEE UG4412.
c. FOR "DIRECT BURIAL POLE INSTALLATION FOR DECORATIVE LUMINAIRES, SEE UG4434.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 01/22/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF DIRECT BURIAL VICTORIAN STYLE OCTAGONAL POLE WITH LUMINAIRE FOR ROADWAY LIGHTING.





**FIGURE 1**







**FIGURE 2**
CONNECTION DIAGRAM

**TABLE 1**

| VICTORIAN POLE/LUMINARE DESIGN UNITS | | |
|---|---|---|
| **MAXIMUM LUMENS** | **LED DESIGN UNIT** | **LED STANDARD PAGE** |
| 5KL | ACORNLED | UG4481 |
| 4KL | ACULED | UG4481 |




**DETAIL 1**




**DETAIL 2**
VIEW FROM STREET

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 07/27/2006 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 03/16/2006 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 09/30/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DIRECT BURIAL POLE INSTALLATION
FOR VICTORIAN LUMINAIRES

UG4430.1

## INSTALLATION:

(A) ALL LUMINAIRES ARE TO BE WIRED FOR 120V.

(B) REFRACTOR DIRECTION SHOULD BE PROPERLY PLACED.

(C) POLE TO CONTAIN ONE OF THREE GROUNDING METHODS:

1. A #8 COPPER WIRE.
2. STAINLESS STEEL BOLT TO CONNECT #6 COPPER WIRE.
3. COPPER GROUND STRAP.

(D) PHOTO ELECTRIC CONTROL FOR DECORATIVE LED FIXTURES ARE LOCATED INSIDE THE LUMINAIRE.

(E) PLACE POLE DIRECTLY BEHIND SIDEWALK IF CURB AND SIDEWALK IS 5 FEET WIDE OR LESS. ALLOW ROOM FOR CONCRETE SUPPORT COLLAR. OTHERWISE PLACE POLE DIRECTLY BEHIND CURB LEAVING ROOM FOR COLLAR. MAKE A JOINTER MARK BETWEEN THE CURB OR SIDEWALK AND THE COLLAR.

(F) WHEN CONDUIT IS INITIALLY INSTALLED, CONDUIT SHALL EXTEND 2 FEET ABOVE FINAL GRADE.

(G) CUT CONDUIT NO MORE THAN 6 INCHES BELOW HANDHOLE OPENING IN THE POLE FOR FINAL INSTALLATION.

(H) FACE PHOTO CELL TO THE NORTH.

(J) ROTATE THE POLE TO LINE UP CABLE ENTRANCE WITH CONDUIT. HANDHOLE OPENING IN POLE SHALL FACE THE SIDEWALK.

(K) INSTALL 30 FEET OF GROUND WIRE IN THE TRENCH AS SHOWN IN FIGURE 2, ON UG4510. THE ALTERNATE METHOD OF GROUNDING IS TO INSTALL (2) 8-FOOT GROUND RODS 6 FEET MINIMUM APART. USE #6 BARE STRAND SOFT DRAWN COPPER WIRE TO ATTACH TO THE RODS AND POLE.

(L) NATURAL SPOIL WITH 3/4-INCH MAXIMUM AGGREGATE, SAND, DECOMPOSED GRANITE, 3/4-INCH MAXIMUM AGGREGATE, OR POLESET (LISTED IN ORDER OF LEAST EXPENSE) MAY BE USED AS BACKFILL. TAMP THE BACKFILL (EXCEPT POLESET) THOROUGHLY.

(M) CONCRETE SUPPORT COLLAR TO BE POURED IN PLACE.

## BILL OF MATERIALS:

TABLE OF CONTENTS

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | WIRE, 2 #8, 600V, ALUMINUM | 16'-0" | -- | S196176 | -- |
| 2 | KIT, CONNECTOR FUSED | 1 | -- | S443392 | -- |
| 3 | CARTRIDGE, FUSE, DUAL ELEMENT, 10A, 250V | 1 | -- | S363936 | -- |
| 4 | WIRE, 2 #8, 600V | AS REQ'D | -- | S196176 | -- |
| 5 | POLE, PRESTRESSED CONCRETE, DIRECT BURIAL, VICTORIAN STYLE, OCTAGONAL | 1 | -- | S678112 | -- |
| 6 | LUMINAIRE, HOLOPHANE TAFT OR KING ACORN STYLE | 1 | UG4481 | -- | -- |
| 7 | DECAL, STREET LIGHT OWNERSHIP/MAINTENANCE IDENTIFICATION | 1 | 4414 | -- | -- |
| 8 | CONTROL, PHOTO ELECTIC | 1 | UG4412 | S273884 | -- |
| 9 | WIRE, BARE COPPER, #2, 7 STR. SOFT DRAWN | 33'-0" | -- | S812818 (X) | -- |
| 10 | CONNECTOR, COPPER COMPRESSION | 1 | -- | S257792 | -- |
| 11 | CONNECTOR, COMPRESSION | 1 | -- | S256432 | -- |
| 12 | TAG, POLE | 1 | 4413 | -- | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4510.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 07/27/2006 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 03/16/2006 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 09/30/2022 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DIRECT BURIAL POLE INSTALLATION FOR VICTORIAN LUMINAIRES

UG4430.2

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF DIRECT BURIAL POLES WITH CONVENTIONAL LUMINAIRES FOR ROADWAY LIGHTING.





**FIGURE 1**





**FIGURE 3**
CONNECTION DIAGRAM FOR FIGURE 1






**FIGURE 4**
CONNECTION DIAGRAM FOR FIGURE 2




**FIGURE 2**




**DETAIL 1**
VIEW FROM STREET

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PSW | JJ | 07/27/2006 | E | | | | | | |
| A | REVISION | - | - | JLB | RDJ | 01/01/1987 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 07/25/2022 |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

DIRECT BURIAL POLE INSTALLATION FOR CONVENTIONAL LUMINAIRES

UG4431.1

## TABLE 1

| PRESTRESSED CONCRETE DIRECT BURIAL POLE | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LUMINAIRE MAXIMUM LUMENS | LED STANDARD PAGE | NORMAL MOUNTING HEIGHT (FT) | MAST ARM | | OVERALL POLE LENGTH | HOLE DEPTH | HOLE WIDTH | ACTUAL MOUNTING HEIGHT | STOCK NUMBER (B) | | | |
| | | | ARM SPAN | ARM RISE | | | | | NATURAL AGGREGATE | | | |
| | | | | | | | | | SINGLE ARM | REPLACE SINGLE ARM | DOUBLE ARM | REPLACE DOUBLE ARM |
| 2-7KL | UG4471, UG4472, UG4473 | 26 | 6'-0" | 2'-3" | 29'-6" | 5'-0" | 18" | 26'-9" | S678144 | S110822 | S678162 | S110824 |
| 8-15KL | UG4471, UG4472, UG4473 | 30 | 6'-0" | 2'-3" | 32'-10" | 5'-0" | 18" | 30'-1" | S678180 | S110822 | S678198 | S110824 |
| 20-25KL | UG4471, UG4472, UG4473 | 35 | 6'-0" | 2'-3" | 38'-5" | 5'-6" | 18" | 35'-2" | S678216 | S110822 | -- | -- |

## INSTALLATION:

(A) ALL LUMINAIRES ARE TO BE WIRED FOR 120V.

(B) STOCK NUMBERS ARE FOR POLES WITH MAST ARMS AND REPLACEMENT MAST ARMS.

(C) POLE TO CONTAIN ONE OF THREE GROUNDING METHODS:

1. #8 COPPER WIRE.
2. STAINLESS STEEL BOLT TO CONNECT #6 COPPER WIRE.
3. COPPER GROUND STRAP.

(D) PHOTO ELECTRIC CONTROL FOR ROADWAY LED LIGHT FIXTURES ARE LOCATED ON TOP OF THE UNIT.

(E) PLACE POLE DIRECTLY BEHIND SIDEWALK IF CURB AND SIDEWALK IS 5 FEET WIDE OR LESS. ALLOW ROOM FOR CONCRETE SUPPORT COLLAR. OTHERWISE PLACE POLE DIRECTLY BEHIND CURB LEAVING ROOM FOR COLLAR. MAKE A JOINTER MARK BETWEEN THE CURB OR SIDEWALK AND THE COLLAR.

(F) WHEN CONDUIT IS INITIALLY INSTALLED, CONDUIT SHALL EXTEND 2 FEET ABOVE FINAL GRADE.

(G) CUT CONDUIT NO MORE THAN 6 INCHES BELOW HANDHOLE OPENING IN THE POLE FOR FINAL INSTALLATION.

(H) FACE PHOTO CELL TO THE NORTH.

(J) ROTATE THE POLE TO LINE UP CABLE ENTRANCE WITH CONDUIT. HANDHOLE OPENING IN POLE SHALL FACE THE SIDEWALK.

(K) INSTALL 30 FEET OF GROUND WIRE IN THE TRENCH AS SHOWN IN FIGURE 2, ON UG4510. THE ALTERNATE METHOD OF GROUNDING IS TO INSTALL (2) 8-FOOT GROUND RODS 6 FEET MINIMUM APART. USE #6 BARE STR. SOFT DRAWN COPPER WIRE TO ATTACH TO THE RODS AND POLE.

(L) NATURAL SPOIL WITH 3/4-INCH MAXIMUM AGGREGATE, SAND, DECOMPOSED GRANITE, 3/4-INCH MAXIMUM AGGREGATE, OR POLESET (LISTED IN ORDER OF LEAST EXPENSE) MAY BE USED AS BACKFILL. TAMP THE BACKFILL (EXCEPT POLESET) THOROUGHLY.

(M) CONCRETE SUPPORT COLLAR TO BE POURED IN PLACE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | | | | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | | | FIGURE 2 | | | | | |
| | | 26'-0" MH | 30'-0" MH | 35'-0" MH | 26'-0" MH | 30'-0" MH | 35'-0" MH | | | |
| 1 | WIRE, 2 #8, 600V, ALUMINUM | 31'-0" | 35'-0" | 40'-0" (I) | 44'-0" | 47'-0" | 52'-0" (I) | -- | S196176 | -- |
| 2 | KIT, CONNECTOR FUSED | 1 | | | 1 | | | -- | S443392 | -- |
| 3 | CARTRIDGE, FUSE, DUAL ELEMENT, 10A, 250V | 1 | | | -- | | | -- | S363936 | -- |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PSW | JJ | 07/27/2006 | E | | | | | | |
| A | REVISION | - | - | JLB | RDJ | 01/01/1987 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 07/25/2022 |



TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | | | | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | | | FIGURE 2 | | | | | |
| | | 26'-0" MH | 30'-0" MH | 35'-0" MH | 26'-0" MH | 30'-0" MH | 35'-0" MH | | | |
| 4 | FUSE, LIMITRON, 20A, 600V | -- | | | 1 | | | -- | S366128 | -- |
| 5 | WIRE, 2 #8, 600V | AS REQ'D | | | AS REQ'D | | | -- | S196176 | -- |
| 6 | POLE, PRESTRESSED CONCRETE, DIRECT BURIAL, INCLUDING MAST ARMS | 1 | | | 1 | | | -- | SEE TABLE 1 | -- |
| 7 | LUMINAIRE, ROADWAY "COBRAHEAD" LED | 1 | | | 2 | | | OH1570 / UG4470 | -- | -- |
| 8 | CONTROL, PHOTO ELECTRIC | 1 | | | 2 | | | UG4412 | TBD | -- |
| 9 | WIRE, BARE COPPER, #2, 7 STR. SOFT DRAWN | 33'-0" | | | 33'-0" | | | -- | S812818 (X) | -- |
| 10 | CONNECTOR, COPPER COMPRESSION | 1 | | | 1 | | | -- | S257792 | -- |
| 11 | CONNECTOR, COMPRESSION | 1 | | | 1 | | | -- | S256432 | -- |
| 12 | TAG, POLE | 1 | | | 1 | | | 4413 | -- | -- |
| 13 | DECAL, STREET LIGHT MAINTENANCE IDENTIFICATION | 1 | | | 2 | | | 4414 | -- | -- |

## NOTES:

(I) ADD 1FT TO WIRE QUANTITY FOR EVERY ADDITIONAL FOOT ABOVE TYPICAL 35FT MOUNTING HEIGHT FOR ITEM 1.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4510.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PSW | JJ | 07/27/2006 | E | | | | | | |
| A | REVISION | - | - | JLB | RDJ | 01/01/1987 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 07/25/2022 |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF DIRECT BURIAL POLES WITH MISSION BELL LUMINAIRES FOR ROADWAY LIGHTING.






**FIGURE 1**




**DETAIL 1**





**FIGURE 3** (I)
CONNECTION DIAGRAM FOR FIGURE 1






**FIGURE 4** (I)
CONNECTION DIAGRAM FOR FIGURE 2




**DETAIL 2**
VIEW FROM STREET

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | JLB | RDJ | 01/01/1987 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

DIRECT BURIAL POLE INSTALLATION FOR MISSION BELL LUMINAIRES

UG4432.1

TABLE OF CONTENTS

## TABLE 1

| PRESTRESSED CONCRETE DIRECT BURIAL POLE | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| MISSION BELL LUMINAIRE | NORMAL MOUNTING HEIGHT (FT) | MAST ARM | | OVERALL POLE LENGTH | HOLE DEPTH | HOLE WIDTH | ACTUAL MOUNTING HEIGHT | STOCK NUMBER (B) | | | |
| | | SPAN | RISE | | | | | NATURAL AGGREGATE | | | |
| | | | | | | | | SINGLE ARM | REPLACE SINGLE ARM | DOUBLE ARM | REPLACE DOUBLE ARM |
| 70W, 100W, 150W HPSV | 26 | 4'-0" | 1'-9" | 29'-6" | 5'-0" | 18" | 26'-3" | S678288 | S110820 | S678306 | -- |
| 200W, 250W, HPSV | 30 | 4'-0" | 1'-9" | 32'-10" | 5'-0" | 18" | 29'-7" | S378324 | | -- | -- |

## INSTALLATION:

(A) ALL LUMINAIRES ARE TO BE WIRED FOR 120V.

(B) STOCK NUMBERS ARE FOR POLES ARMS AND MAST ARMS ONLY.

(C) POLE TO CONTAIN ONE OF THREE GROUNDING METHODS:

1. #8 COPPER WIRE.
2. STAINLESS STEEL BOLT TO CONNECT #6 COPPER WIRE.
3. COPPER GROUND STRAP.

(D) BIRDCAGE AND DECORATIVE SCROLLS ARE NOT A STANDARD INSTALLATION. BIRDCAGE AND DECORATIVE SCROLLS TO BE PROVIDED BY CUSTOMER OR BY GOVERNMENTAL AGENCY. SDG&E WILL INSTALL THE BIRDCAGE AND DECORATIVE SCROLL AT THE TIME THE POLE IS INSTALLED.

(E) PLACE POLE DIRECTLY BEHIND SIDEWALK IF CURB AND SIDEWALK IS 5 FEET WIDE OR LESS. ALLOW ROOM FOR CONCRETE SUPPORT COLLAR. OTHERWISE PLACE POLE DIRECTLY BEHIND CURB LEAVING ROOM FOR COLLAR. MAKE A JOINTER MARK BETWEEN THE CURB OR SIDEWALK AND THE COLLAR.

(F) WHEN CONDUIT IS INITIALLY INSTALLED, IT SHALL EXTEND 2 FEET ABOVE FINAL GRADE.

(G) CUT CONDUIT NO MORE THAN 6 INCHES BELOW HANDHOLE OPENING IN THE POLE FOR FINAL INSTALLATION.

(H) FACE PHOTO CELL TO THE NORTH.

(J) ROTATE THE POLE TO LINE UP CABLE ENTRANCE WITH CONDUIT. HANDHOLE OPENING IN POLE SHALL FACE THE SIDEWALK.

(K) INSTALL 30 FEET OF GROUND WIRE IN THE TRENCH AS SHOWN IN FIGURE 2, ON UG4510. THE ALTERNATE METHOD OF GROUNDING IS TO INSTALL (2) 8-FOOT GROUND RODS 6 FEET MINIMUM APART. USE #6 BARE STR. SOFT DRAWN COPPER WIRE TO ATTACH TO THE RODS AND POLE.

(L) NATURAL SPOIL WITH 3/4-INCH MAXIMUM AGGREGATE, SAND, DECOMPOSED GRANITE, 3/4-INCH MAXIMUM AGGREGATE, OR POLESET (LISTED IN ORDER OF LEAST EXPENSE) MAY BE USED AS BACKFILL. TAMP THE BACKFILL (EXCEPT POLESET) THOROUGHLY.

(M) CONCRETE SUPPORT COLLAR TO BE POURED IN PLACE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | | | | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | | | FIGURE 2 | | | | | |
| | | 26'-0" MH | 30'-0" MH | 35'-0" MH | 26'-0" MH | 30'-0" MH | 35'-0" MH | | | |
| 1 | WIRE, #8 THW, 600V, ALUMINUM (II) | 31'-0" | 35'-0" | 40'-0" | 43'-0" | 47'-0" | 52'-0" | -- | S196176 | -- |
| 2 | KIT, CONNECTOR FUSED | 1 | | | 1 | | | -- | S443392 | -- |
| 3 | CARTRIDGE, FUSE, DUAL ELEMENT, 10A, 250V | 1 | | | -- | | | -- | S363936 | -- |
| 4 | FUSE, LIMITRON, 20A, 600V | -- | | | 1 | | | -- | S366128 | -- |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | JLB | RDJ | 01/01/1987 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DIRECT BURIAL POLE INSTALLATION FOR MISSION BELL LUMINAIRES

UG4432.2

TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | | | | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | | | FIGURE 2 | | | | | |
| | | 26'-0" MH | 30'-0" MH | 35'-0" MH | 26'-0" MH | 30'-0" MH | 35'-0" MH | | | |
| 5 | WIRE, #8 THW, 600V, ALUMINUM INSULATED CABLE | AS REQ'D | | | AS REQ'D | | | -- | S196176 | -- |
| 6 | POLE, PRESTRESSED CONCRETE, DIRECT BURIAL INCLUDING MAST ARMS | 1 | | | 1 | | | -- | SEE TABLE 1 | -- |
| 7 | LUMINAIRE, MISSION BELL | 1 | | | 2 | | | 4422 | -- | -- |
| 8 | LAMP, HPSV | 1 | | | 2 | | | 4410 | -- | -- |
| 9 | REFRACTOR, REPLACEMENT | 1 | | | 2 | | | 4411 | -- | -- |
| 10 | CONTROL, PHOTO ELECTRIC, 105-285V, 1,000W | 1 | | | 1 | | | -- | S273888 | -- |
| 11 | ADAPTER, P. E. RECEPTACLE | 1 | | | 1 | | | -- | S102544 | -- |
| 12 | WIRE, BARE COPPER, #2, 7 STR. SOFT DRAWN | 33'-0" | | | 33'-0" | | | -- | S812818 (X) | -- |
| 13 | CONNECTOR, COPPER COMPRESSION | 1 | | | 1 | | | -- | S257792 | -- |
| 14 | CONNECTOR, COMPRESSION (II) | 1 | | | 1 | | | -- | S256432 | -- |
| 15 | TAG, POLE | 1 | | | 1 | | | 4413 | -- | -- |
| 16 | DECAL, STREET LIGHT MAINTENANCE IDENTIFICATION | 1 | | | 2 | | | 4414 | -- | -- |
| 17 | CAP, BONNET | 1 | | | 1 | | | -- | S203902 | -- |
| 18 | WIRE, #10 THW, 600V, COPPER (II) | AS REQ'D | | | AS REQ'D | | | -- | S808064 | -- |

## NOTES:

(I) USE #10 WIRE (ITEM 18) FROM THE PHOTO ELECTRIC CONTROL TO THE LUMINAIRE.

(II) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4510.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | PIA | JJ | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | JLB | RDJ | 01/01/1987 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DIRECT BURIAL POLE INSTALLATION FOR MISSION BELL LUMINAIRES

UG4432.3

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF DIRECT BURIAL POLES WITH DECORATIVE LUMINAIRES FOR ROADWAY LIGHTING.





**FIGURE 1**





**FIGURE 3**
CONNECTION DIAGRAM FOR FIGURE 1





**FIGURE 4**
CONNECTION DIAGRAM FOR FIGURE 2






**FIGURE 2**




**DETAIL 1**
VIEW FROM STREET

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 02/13/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

# DIRECT BURIAL POLE INSTALLATION FOR DECORATIVE LUMINAIRES



UG4433.1

TABLE OF CONTENTS

## TABLE 1

| PRESTRESSED CONCRETE DIRECT BURIAL POLE | | | | | | | |
|---|---|---|---|---|---|---|---|
| DECORATIVE LUMINAIRE | NORMAL MOUNTING HEIGHT (FT) | OVERALL POLE LENGTH | HOLE DEPTH | HOLE WIDTH (IN) | ACTUAL MOUNTING HEIGHT | STOCK NUMBER (B) | POLE SHAPE |
| 70W HPSV | 24 | 27'-7" | 4'-7" | 18 | 23'-0" | S677900 | OCTAGONAL |
| 70W, 100W, 150W HPSV | 26 | 29'-6" | 5'-0" | | 24'-6" | S678000 | ROUND |
| 100W, 150W, 175W HPSV | 28 | 32'-10" | 4'-11" | | 27'-11" | S677902 | OCTAGONAL |
| 200W, 250W HPSV | 30 | 32'-10" | 5'-0" | | 27'-10" | S678036 | ROUND |
| 400W HPSV | 35 | 38'-5" | 5'-6" | | 32'-11" | S678072 | |

## INSTALLATION:

(A) ALL LUMINAIRES ARE TO BE WIRED FOR 120V.

(B) STOCK NUMBERS ARE FOR POLES ONLY.

(C) POLE TO CONTAIN ONE OF THREE GROUNDING METHODS.

1. A #8 COPPER WIRE.
2. STAINLESS STEEL BOLT TO CONNECT #6 COPPER WIRE.
3. COPPER GROUND STRAP.

(D) PLACE POLE DIRECTLY BEHIND SIDEWALK IF CURB AND SIDEWALK IS 5 FEET WIDE OR LESS. ALLOW ROOM FOR CONCRETE SUPPORT COLLAR. OTHERWISE PLACE POLE DIRECTLY BEHIND CURB LEAVING ROOM FOR COLLAR. MAKE A JOINTER MARK BETWEEN THE CURB OR SIDEWALK AND THE COLLAR.

(E) CONCRETE SUPPORT COLLAR TO BE POURED IN PLACE.

(F) WHEN CONDUIT IS INITIALLY INSTALLED, IT SHALL EXTEND 2 FEET ABOVE FINAL GRADE.

(G) CUT CONDUIT NO MORE THAN 6 INCHES BELOW HANDHOLE OPENING IN THE POLE FOR FINAL INSTALLATION.

(H) FACE PHOTO CELL TO THE NORTH.

(J) ROTATE THE POLE TO LINE UP CABLE ENTRANCE WITH CONDUIT. HANDHOLE OPENING IN POLE SHALL FACE THE SIDEWALK.

(K) INSTALL 30 FEET OF GROUND WIRE IN THE TRENCH AS SHOWN IN FIGURE 2 ON UG4510. THE ALTERNATE METHOD OF GROUNDING IS TO INSTALL (2) 8-FOOT GROUND RODS 6 FEET MINIMUM APART. USE #6 BARE STR. SOFT DRAWN COPPER WIRE TO ATTACH TO THE RODS AND POLE.

(L) NATURAL SPOIL WITH 3/4-INCH MAXIMUM AGGREGATE, SAND, DECOMPOSED GRANITE, 3/4-INCH MAXIMUM AGGREGATE, OR POLESET (LISTED IN ORDER OF LEAST EXPENSE) MAY BE USED AS BACKFILL. TAMP THE BACKFILL (EXCEPT POLESET) THOROUGHLY.

TABLE OF CONTENTS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | | | | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | | | FIGURE 2 | | | | | |
| | | 26'-0" MH | 30'-0" MH | 35'-0" MH | 26'-0" MH | 30'-0" MH | 35'-0" MH | | | |
| 1 | WIRE, #8 THW, 600V, ALUMINUM | 27'-0" | 31'-0" | 36'-0" | 25'-0" | 32'-0" | 37'-0" | -- | S196176 | -- |
| 2 | KIT, CONNECTOR FUSED | 1 | | | 1 | | | -- | S443392 | -- |
| 3 | CARTRIDGE, FUSE, DUAL ELEMENT, 10A, 250V | 1 | | | -- | | | -- | S363936 | -- |
| 4 | FUSE, LIMITRON, 20A, 600V | -- | | | 1 | | | -- | S366128 | -- |
| 5 | WIRE, #8 THW, 600V, ALUMINUM, INSULATED CABLE | AS REQ'D | | | AS REQ'D | | | -- | S196176 | -- |
| 6 | POLE, PRESTRESSED CONCRETE, DIRECT BURIAL, INCLUDING MAST ARMS | 1 | | | 1 | | | -- | SEE TABLE 1 | -- |
| 7 | LUMINAIRE, DECORATIVE | 1 | | | 2 | | | 4422 | -- | -- |
| 8 | LAMP, HPSV | 1 | | | 2 | | | 4410 | -- | -- |

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 02/13/2007 | D | | | | | | |

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | | | | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | | | FIGURE 2 | | | | | |
| | | 26'-0" MH | 30'-0" MH | 35'-0" MH | 26'-0" MH | 30'-0" MH | 35'-0" MH | | | |
| 9 | REFRACTOR, REPLACEMENT | 1 | | | 2 | | | 4411 | -- | -- |
| 10 | CONTROL, PHOTO ELECTRIC, 105-285V, 1,000W | 1 | | | 2 | | | -- | S273888 | -- |
| 11 | WIRE, #2, BARE COPPER, 7 STR, SOFT DRAWN | 33'-0" | | | 33'-0" | | | -- | S812818 (X) | -- |
| 12 | CONNECTOR, COMPRESSION, COPPER | 1 | | | 1 | | | -- | S257792 | -- |
| 13 | CONNECTOR, COMPRESSION | 1 | | | 1 | | | -- | S256432 | -- |
| 14 | TAG, POLE | 1 | | | 1 | | | 4413 | -- | -- |
| 15 | DECAL, STREET LIGHT MAINTENANCE IDENTIFICATION | 1 | | | 2 | | | 4414 | -- | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4510.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | REVISION | - | - | PIA | JJ | 02/13/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DIRECT BURIAL POLE INSTALLATION FOR DECORATIVE LUMINAIRES

UG4433.3

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION OF DIRECT BURIAL POLES WITH POST TOP LUMINAIRES FOR DOMESTIC WALKWAY AND ROADWAY LIGHTING.





**FIGURE 1**
DWL
WALKWAY LIGHT





**FIGURE 3**
CONNECTION DIAGRAM
FOR FIGURE 1





**FIGURE 4**
CONNECTION DIAGRAM
FOR FIGURE 2






**FIGURE 2**
SINGLE POST TOP
ROADWAY LIGHT




**DETAIL 1**

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | SA | JS | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | PSW | JJ | 01/22/2007 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 02/16/23 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 3

DIRECT BURIAL POLE INSTALLATION FOR DOMESTIC WALKWAY LIGHTING & POST TOP LUMINAIRES

UG4434.1

## TABLE 1

| PRESTRESSED CONCRETE DIRECT BURIAL POLE | | | | | | | |
|---|---|---|---|---|---|---|---|
| FIGURE | LED STANDARD PAGE | LUMINAIRE MAXIMUM LUMENS | OVERALL POLE LENGTH | HOLE DEPTH | HOLE WIDTH (IN) | ACTUAL MOUNTING | STOCK NUMBER |
| 1 | UG4481 FIG.2 & 3 | 7KL | 11'-0" | 3'-0" | 18 | 10'-0" | S678108 |
| 2 | UG4481 FIG.1-3 | 4KL & 7KL | 20'-0" | 4'-0" | | 17'-0" | S678126 |

## INSTALLATION:

(A) ALL LUMINAIRES ARE TO BE WIRED FOR 120V.

(B) CONCRETE SUPPORT COLLAR TO BE POURED IN PLACE.

(C) PRESTRESSED CONCRETE POLE TO CONTAIN ONE OF THREE GROUNDING METHODS.

1. A #8 COPPER WIRE.
2. STAINLESS STEEL BOLT TO CONNECT #6 COPPER WIRE.
3. COPPER GROUND STRAP.

(D) PHOTOELECTRIC CONTROL FOR DECORATIVE LED FIXTURES ARE LOCATED INSIDE THE LUMINAIRE.

(E) THIS LUMINAIRE SHALL BE INSTALLED SO THAT THE LADDER ARM IS PARALLEL TO THE CURB.

(F) WHEN CONDUIT IS INITIALLY INSTALLED, IT SHALL EXTEND 2 FEET ABOVE FINAL GRADE.

(G) CUT CONDUIT NO MORE THAN 6 INCHES BELOW HANDHOLE OPENING IN THE POLE FOR FINAL INSTALLATION.

(H) FACE PHOTO CELL TO THE NORTH.

(J) ROTATE THE POLE TO LINE UP CABLE ENTRANCE WITH CONDUIT. HANDHOLE OPENING IN POLE SHALL FACE THE SIDEWALK.

(K) GROUND PRESTRESSED CONCRETE POLE ONLY BY INSTALLING 30 FEET OF GROUND WIRE IN THE TRENCH AS SHOWN IN FIGURE 2 ON UG4510. THE ALTERNATE METHOD OF GROUNDING IS TO INSTALL TWO 8 FOOT GROUND RODS 6 FEET APART MINIMUM. USE #6 BARE STRANDED SOFT DRAWN COPPER WIRE TO ATTACH THE RODS TO POLE.

(L) NATURAL SPOIL WITH 3/4-INCH MAXIMUM AGGREGATE, SAND, DECOMPOSED GRANITE, 3/4-INCH MAXIMUM AGGREGATE, OR POLESET (LISTED IN ORDER OF LEAST EXPENSE) MAY BE USED AS BACKFILL.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | FIGURE 2 | | | | |
| | | | SINGLE | DOUBLE | | | |
| 1 | WIRE, 2 #8, 600V, ALUMINUM | 9'-0" | 16'-0" | 16'-0" (2) | -- | S196176 | -- |
| 2 | HOLDER, FUSE | 1 | 1 | 1 | -- | S443392 | -- |
| 3 | CARTRIDGE, FUSE, DUAL ELEMENT, 10A, 250V | 1 | 1 | 1 | -- | S363936 | -- |
| 4 | FUSE, LIMITRON, 20A, 600V | -- | -- | 1 | -- | S366128 | -- |
| 5 | WIRE, 2 #8, 600V, ALUMINUM, INSULATED CABLE | AS REQ'D | AS REQ'D | AS REQ'D | -- | S196176 | -- |
| 6 | POLE, DIRECT BURIAL | 1 | 1 | 1 | -- | SEE TABLE 1 | -- |
| 7 | LUMINAIRE, ROADWAY POST TOP | -- | 1 | 2 | UG4481 | -- | -- |
| 8 | CONTROL, PHOTO ELECTRIC | 1 | 1 | 2 | UG4412 | S273884 | -- |
| 9 | LUMINAIRE, DWL POST TOP | 1 | 1 | 2 | UG4481 | -- | -- |
| 10 | WIRE, #2, BARE COPPER, 7 STR, SOFT DRAWN | 33'-0" | 33'-0" | 33'-0" | -- | S812818 (X) | -- |
| 11 | CONNECTOR, COMPRESSION, COPPER | 1 | 1 | 1 | -- | S257792 | -- |
| 12 | CONNECTOR, COMPRESSION (K) | 1 | 1 | 1 | -- | S256432 | -- |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | SA | JS | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | PSW | JJ | 01/22/2007 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 02/16/23 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

DIRECT BURIAL POLE INSTALLATION FOR DOMESTIC WALKWAY LIGHTING & POST TOP LUMINAIRES

UG4434.2

TABLE OF CONTENTS

## BILL OF MATERIALS (CONT'D):

| ITEM | DESCRIPTION | QUANTITY | | | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| | | FIGURE 1 | FIGURE 2 | | | | |
| | | | SINGLE | DOUBLE | | | |
| 13 | TAG, POLE | 1 | 1 | 1 | 4413 | -- | -- |
| 14 | DECAL, STREET LIGHT MAINTENANCE IDENTIFICATION | 1 | 1 | 2 | 4414 | -- | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4510.

TABLE OF CONTENTS

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | REVISION | - | - | SA | JS | 02/13/2007 | E | | | | | | |
| A | REVISION | - | - | PSW | JJ | 01/22/2007 | D | LED CONTENT REVISION | AMP | RSL | JAS | KRG | 02/16/23 |

**SCOPE:** THIS STANDARD SHOWS THE INSTALLATION AND CONNECTIONS FOR THE NO. 3-1/2 HANDHOLE USED WHEN INSTALLING STREET LIGHTS OWNED BY THE CITY OF SAN DIEGO.





**FIGURE 1**
NO. 3-1/2 HANDHOLE INSTALLATION

## INSTALLATION:

(A) 1-INCH POLYETHYLENE CONDUIT FROM SERVICE POINT.

(B) 1-INCH POLYETHYLENE CONDUIT TO STREET LIGHT.

(C) NO CONNECTIONS ARE REQUIRED IF ONLY ONE STREET LIGHT IS CONNECTED TO SERVICE POINT. LOOP CABLE THROUGH HANDHOLE TO SERVICE POINT.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | WIRE, #8XLPE, 600V, ALUMINUM CABLE | AS REQ'D | -- | S196176 | U/2-#8 |
| 2 | CONDUIT, POLYETHYLENE, 1" | AS REQ'D | -- | S249630 | 1" PE |
| 3 | HANDHOLE, NO. 3-1/2 | 1 | -- | (I) | 31/2PB |

## NOTES:

(I) HANDHOLE SUPPLIED BY CITY OF SAN DIEGO.

## REFERENCE:

(a) FOR HANDHOLE DIMENSIONS, SEE UG3308.

(b) FOR EXCAVATION DIMENSIONS, SEE UG3308.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | REVISION | - | - | - | RW/ROG | 01/01/1998 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

HANDHOLE
(INSIDE DIMENSIONS - 10 1/4" X 15 3/8")

UG4435.1

**SCOPE:** THIS STANDARD SHOWS TYPICAL LED STREET LIGHT CONSTRUCTION INSTALLED ON WOOD, STEEL, OR FIBERGLASS POLES TO PROVIDE ROADWAY LIGHTING.





**FIGURE 1**
6'-0" ARM INSTALLATION

**TABLE 1**

| LED FIXTURES | | | |
|---|---|---|---|
| **LUMENS (IN THOUSANDS)** | **MANUFACTURER** | **STANDARD PAGE** | **STOCK NUMBER** |
| 0-5L | GE | 1571 | S473100, S473102, S473104 |
| | CREE | 1572 | S473132, S473136, S473138, S473140 |
| | ACUITY | 1573 | S473434 |
| 6-10L | GE | 1571 | S473106, S473108 |
| | CREE | 1572 | S473130, S473134, S473142 |
| | ACUITY | 1573 | S473434, S473438 |
| 11-15L | GE | 1571 | S473112, S473114 |
| | CREE | 1572 | S473144 |
| | ACUITY | 1573 | S473438, S473440 |
| 20-25L | GE | 1571 | S473110 |
| | CREE | 1572 | S473146 |
| | ACUITY | 1573 | S473440 |

**INSTALLATION:**

A. ITEMS REQUIRED FOR SECONDARY LINE ARM CONSTRUCTION.

(B) FACE PHOTO CELL TO THE NORTH.

C. UTILIZE LEVELING FEATURE WITHIN FIXTURE PER MANUFACTURER'S SPECIFICATIONS BEFORE ENERGIZING.

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | STD PAGE & STOCK NUMBERS | AMP | RSL | JAS | KRG | 08/12/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JIK | JES | CZH | 08/20/2019 | D | | | | | | |



TABLE OF CONTENTS

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BRACKET, UPSWEEP, 2" DIA, 6'-0" | 1 | -- | S167264 | BKT6 |
| 2 | BRACKET, SERVICE INSULATOR | 1 | 631 | S166880 | INSBKT |
| 3 | BOLT, MACH, GALV, 5/8" X (LENGTH AS REQ.), 2 SQ. WASHERS & 1 DOUBLE COIL SPRING WASHER. | 1 | OH390.7 | -- | -- |
| 4 | SCREW, LAG, 1/2" X 4" (WOOD POLES ONLY) (I) | 2 | OH390.7 | S621568 (X) | 1/2L |
| | BLIND NUT, 1/2" (STEEL POLES ONLY) (I) | 2 | OH390.7 | S503460 (X) | -- |
| 5 | LIGHTING FIXTURE | 1 | (b) | -- | -- |
| 6 | CONTROL, PHOTOELECTRIC, TWISTLOCK BASE 105-285V | 1 | 1512 | S273884 | PC-TL |
| 7 | WIRE, COPPER #8 600V, FLEXIBLE POLYETHYLENE INSULATED DUPLEX | 10'-0" | OH711 | S196432 | DX8C |
| 8 | CONNECTOR, WIRE | 2 | 783-785 | -- | -- |
| 9 | CLEVIS, SECONDARY, DEADEND | 1 | OH612 | S235488 | SDE |

## NOTES:

(I) THE BLIND NUT AND LAG SCREW ARE OPTIONAL FOR ATTACHING SUPPORT BRACE TO POLE.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR G.O. 95 MINIMUM CLEARANCE REQUIRED FOR STREET LIGHT INSTALLATIONS, SEE OH1509.

(b) FOR MANUFACTURER INDICES, SEE OH1571 FOR GENERAL ELECTRIC (GE) PRODUCT INDEX, OH1572 FOR CREE PRODUCT INDEX, AND OH1573 FOR ACUITY PRODUCT INDEX.

c. FOR UNDERGROUND INSTALLATIONS, SEE UG4431.

TABLE OF CONTENTS

© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | STD PAGE & STOCK NUMBERS | AMP | RSL | JAS | KRG | 08/12/2022 | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 01/18/2022 | E | | | | | | |
| A | ORIGINAL ISSUE | - | JIK | JES | CZH | 08/20/2019 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GE LED FIXTURES USED TO PROVIDE ROADWAY LIGHTING.

## TABLE 1

**GE LED FIXTURE INDEX**

| DESCRIPTION | MOUNTING HEIGHT (FT) | WATTAGE (II) (III) (A) | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | FIGURE DETAIL | HPSV/LPSV EQUIVALENT STOCK NUMBERS (a) (b) |
|---|---|---|---|---|---|---|---|
| 2KL ERL1 TYPE II WIDE | 26 | 14 | SHEETS 4-5 | S473800 | LC14GE | 1 | S473800 |
| 4KL ERL1 TYPE II WIDE | 26 | 31 | SHEETS 6-7 | S473102 | LC31GE | 1 | S473400 |
| 5KL ERL1 TYPE II WIDE | 26 | 39 | SHEETS 8-9 | S473104 | LC39GE | 1 | S473802<br>S473402 |
| 8KL ERL1 TYPE II WIDE | 30 | 71 | SHEETS 10-11 | S473106 | LC78GE | 1 | S473404<br>S473804 |
| 10KL ERL1 TYPE III | 30 | 97 | SHEETS 12-13 | S473108 | LC99GE | 1 | S473406 |
| 20KL ERL2 TYPE III | 35 | 174 | SHEETS 14-15 | S473110 | LC174G | 3 | S473410 |
| 11KL ERLH TYPE IV | 30 | 98 | SHEETS 16-17 | S473112 | LC96GE | 2 | S473806 |
| 15KL ERLH TYPE III | 30 | 136 | SHEETS 18-19 | S473114 | LC136G | 2 | S473408 |

TABLE OF CONTENTS




**FIGURE 1**
ERL1




**FIGURE 2**
ERLH




**FIGURE 3**
ERL2

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

## INSTALLATION:

(A) HPSV/LPSV CONVERSION TO LED: REMOVE AND REPLACE ENTIRE HPSV/LPSV STREET LIGHTING FIXTURE AND BALLAST AND REPLACE WITH EQUIVALENT LED FIXTURE SHOWN IN TABLE 1. FOR OVERHEAD FEED CONVERSIONS, MOUNT THE REPLACEMENT LED FIXTURE AT THE EXISTING FIXTURE HEIGHT OR HIGHER WHILE MAINTAINING REQUIRED CLEARANCES TO OTHER FACILITIES PER OH1509.

B. MECHANICAL INSTALLATION OF FIXTURE

1. BIRD SHIELDS: THE BIRD SHIELD BEHIND THE PIPE CLAMP HAS A 1 1/4-INCH (1.660 OD) OPENING. REMOVE SHIELD IF LARGER PIPE IS USED. SEE FIGURE 4.
2. MOUNTING ARM: UNFASTEN, OPEN AND REMOVE DOOR FROM HINGE CRADLE. ADJUST PIPE CLAMP OPENING SLIGHTLY LARGER THAN PIPE SIZE. INSERT MOUNTING ARM THROUGH BIRD-SHIELD (IF USED) AND INTO THE LUMINAIRE UNTIL IT HITS THE LEVELING-STEPS EXTENDING FROM TOP OF HOUSING. SEE FIGURE 4.
3. LEVELING: TILT THE LUMINAIRE UP OR DOWN USING LEVELING-STEPS. TO LEVEL, HOLD LUMINAIRE APPROXIMATELY LEVEL AND SNUG UP BOLTS. ONCE LEVEL, TIGHTEN EACH MOUNTING BOLT ALTERNATING BETWEEN BOLTS. REFER TO INSTALLATION INSTRUCTIONS FOR BOLT TORQUES. DO NOT OVERTIGHTEN BOLTS. IF UPWARD TILT IS NEEDED, LOOSEN BOLTS SLIGHTLY, LIFT LUMINAIRE AND INSERT IT TO THE NEXT SET OF STEPS. IF DOWNWARD TILT IS NEEDED, EXTRACT THE MOUNTING ARM FROM LUMINAIRE TO SIT ON THE REARWARD STEPS. SEE FIGURE 4.
4. REFERENCE ELECTRICAL CONNECTIONS SECTION FOR COMPLETING ELECTRICAL CONNECTIONS.
5. PHOTOELECTRIC CONTROL: ORIENT THE PHOTOELECTRIC (PE) RECEPTACLE SO THAT THE WORD "NORTH" IS DIRECTED TRUE NORTH. SEAT AND LOCK THE PE CONTROL/RECEPTACLE AND ROTATE CLOCKWISE UNTIL WORD "NORTH" IS TRUE NORTH. LOWER PE RECEPTACLE INTO POSITION, SEE FIGURE 5 AND 6.

(6) FINAL ASSEMBLY: DOOR INTERLOCKS WITH TOP HOUSING IN ALL POSITIONS EXCEPT IN VICINITY OF REMOVAL LOCATION. DOORS ARE DESIGNED TO BE ASSEMBLED TO TOP HOUSING WHILE IN UPRIGHT POSITION. TO REPLACE DOOR, HOLD SLIGHTLY PAST VERTICAL AND TOWARD POLE-SIDE OF HINGE. INSERT HINGE PIN INTO HINGE CRADLE AND LOWER DOOR TO HANG FREE.





**FIGURE 4**
INTERNAL VIEW (B6)





**FIGURE 5**
TOP VIEW (B6)





**FIGURE 6**
BOTTOM VIEW (B6)

C. ELECTRICAL CONNECTIONS OF FIXTURE

1. MAKE ALL CONNECTIONS IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE AND APPLICABLE LOCAL CODE REQUIREMENTS INCLUDING GROUNDING. VERIFY SUPPLY VOLTAGE MATCHES NAMEPLATE RATING. USE #6 THRU #16 AWG SERVICE LEADS AND MATCH THE NAMEPLATE'S SERVICE LEAD TEMPERATURE RATING. EXTEND SERVICE LEADS APPROXIMATELY 7 INCHES PAST PIPE/MOUNTING BRACKET END.

TABLE OF CONTENTS
RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

## INSTALLATION (CONT'D):

(2) ATTACH SERVICE LEADS TO TERMINAL BLOCK AS SHOWN ON THE WIRING SCHEMATIC. SEE FIGURE 7.





**FIGURE 7**
WIRING SCHEMATIC (C2)

(3) DIMMING CONTROL INSTRUCTIONS ARE FOR REFERENCE SINCE LUMENS SETTINGS ARE PRESET BY MANUFACTURER FOR ALL STOCK FIXTURES. FOR WIRED DIMMING CONTROLS, ATTACH DIMMING LEADS PER WIRING SCHEMATIC. REFER TO INSTALLATION INSTRUCTIONS FOR BOLT TORQUES. DO NOT OVER TIGHTEN BOLT. SEE FIGURE 8.





**FIGURE 8**
DIMMING CONTROL SCHEMATIC (C3)

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THIS IS A REPRODUCTION OR ADAPTATION OF MANUFACTURER DATA. REFER TO SPECIFIC PRODUCT INSTALLATION MANUALS PROVIDED WITH STOCK MATERIALS FOR COMPLETE SAFETY AND INSTALLATION INSTRUCTIONS.

(II) MOUNTING HEIGHTS PROVIDED ON PAGE OH1571.1 ARE SPECIFIC TO NEW UNDERGROUND FEED INSTALLATIONS DUE TO STANDARD CONCRETE POLE SIZES AVAILABLE. NEW LED STREETLIGHT INSTALLATIONS OR HPSV-TO-LED UPGRADE INSTALLATIONS MAY BE MOUNTED WITHIN 2 FEET OF THESE REFERENCE MOUNTING HEIGHTS AS LONG AS THE REQUIRED CLEARANCES TO OTHER FACILITIES ARE MAINTAINED PER OH1509.

(III) FOR NEW SDG&E OWNED STREETLIGHT INSTALLATIONS (NOT EXISTING CONVERSIONS), A LIGHTING DESIGN ANALYSIS MAY BE REQUIRED TO DETERMINE THE REQUIRED MOUNTING HEIGHT IF THE REFERENCE MOUNTING HEIGHTS PROVIDED HERE ARE NOT FEASIBLE. CONTACT THE STREET LIGHTING GROUP IN THIS SCENARIO FOR GUIDANCE.

**REFERENCE:**

(a) OVERHEAD FIELD MAINTENANCE ONLY SECTION 1500 FOR HPSV AND LPSV FIXTURE DETAIL.
(b) SOME FIXTURES ARE NO LONGER AVAILABLE.
c. SEE OH1570 FOR OVERHEAD LIGHTING INSTALLATION.
d. SEE UG4431 FOR UNDERGROUND LIGHTING INSTALLATION.
e. SEE OH1512 FOR PHOTOELECTRIC CONTROLS AVAILABLE.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



TABLE OF CONTENTS
RETURN TO LED FIXTURE INDEX

**SCOPE:** THIS STANDARD SHOWS VARIOUS GE EVOLVE LED ROADWAY LIGHTING FIXTURES.

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 1**
TOP VIEW




**FIGURE 2**
ISOMETRIC





**FIGURE 3**
SIDE VIEW





**FIGURE 4**
FRONT VIEW





**FIGURE 5**
BACK VIEW





**FIGURE 6**
BOTTOM VIEW

**TABLE 1**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERL1 | 1900L | 3,000K | 15.5 | SEE TABLE 3 | TYPE II WIDE | S473100 | LC14GE |





TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

## TABLE 2

| PHOTOMETRIC DIAGRAMS | | | |
|---|---|---|---|
| **FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD** | | **PLOT DRAWN IN FOOTCANDLES** | **GRAPH RADIUS LINES IN CANDELAS** |
| LUMENS | 1,900 |  |  |
| WATTS | 14 | | |
| MOUNTING HEIGHT | 26' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_02B330_-120V.IES | | |
| **FIXTURE DESIGN WITH BACKLIGHT SHIELD** (C) | | **PLOT DRAWN IN FOOTCANDLES** | **GRAPH RADIUS LINES IN CANDELAS** |
| LUMENS | 1,800 |  |  |
| WATTS | 14 | | |
| MOUNTING HEIGHT | 26' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_02B330_-120V-ELSHS-ERL1-BLCK.IES | | |









## TABLE 3


| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| **HORIZONTAL TENON. CONFIG.** | **SINGLE** | **2 @ 90°** | **2 @ 180°** |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 7**
TOP VIEW




**FIGURE 8**
ISOMETRIC





**FIGURE 9**
SIDE VIEW





**FIGURE 10**
FRONT VIEW





**FIGURE 11**
BACK VIEW





**FIGURE 12**
BOTTOM VIEW

**TABLE 4**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERL1 | 3900L | 3,000K | 15.5 | SEE TABLE 6 | TYPE II WIDE | S473102 | LC31GE |

TABLE OF CONTENTS



RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



## TABLE 5

**PHOTOMETRIC DIAGRAMS**

| FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 3,900 |  |  |
| WATTS | 31 | | |
| MOUNTING HEIGHT | 26' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_04B330_ -120-277V.IES | | |






| FIXTURE DESIGN WITH BACKLIGHT SHIELD (C) | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 3,700 |  |  |
| WATTS | 31 | | |
| MOUNTING HEIGHT | 26' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_4B330_ -120-277V-ELSHS -ERL1-BLCK.IES | | |





## TABLE 6

| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 13**
TOP VIEW




**FIGURE 14**
ISOMETRIC





**FIGURE 15**
SIDE VIEW





**FIGURE 16**
FRONT VIEW





**FIGURE 17**
BACK VIEW





**FIGURE 18**
BOTTOM VIEW

**TABLE 7**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERL1 | 4900L | 3,000K | 15.5 | SEE TABLE 9 | TYPE II WIDE | S473104 | LC39GE |

TABLE OF CONTENTS



RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



## TABLE 8

**PHOTOMETRIC DIAGRAMS**

| FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 4,900 |  |  |
| WATTS | 39 | | |
| MOUNTING HEIGHT | 26' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_05B330_ -120-277V.IES | | |





| FIXTURE DESIGN WITH BACKLIGHT SHIELD (C) | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 4,600 |  |  |
| WATTS | 39 | | |
| MOUNTING HEIGHT | 26' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_05B330_ -120-277V-ELSHS -ERL1-BLCK.IES | | |





## TABLE 9


| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 19**
TOP VIEW




**FIGURE 20**
ISOMETRIC





**FIGURE 21**
SIDE VIEW





**FIGURE 22**
FRONT VIEW





**FIGURE 23**
BACK VIEW





**FIGURE 24**
BOTTOM VIEW

**TABLE 10**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERL1 | 7800L | 3,000K | 15.5 | SEE TABLE 12 | TYPE II WIDE | S473106 | LC78GE |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.





| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

## TABLE 11

| PHOTOMETRIC DIAGRAMS | | | |
|---|---|---|---|
| **FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD** | | **PLOT DRAWN IN FOOTCANDLES** | **GRAPH RADIUS LINES IN CANDELAS** |
| LUMENS | 7,800 |  |  |
| WATTS | 71 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_08B330_ .IES | | |
| **FIXTURE DESIGN WITH BACKLIGHT SHIELD** (C) | | **PLOT DRAWN IN FOOTCANDLES** | **GRAPH RADIUS LINES IN CANDELAS** |
| LUMENS | 7,400 |  |  |
| WATTS | 71 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_08B330_ -ELSHS-ERL1-BLCK.IES | | |









## TABLE 12


| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| **HORIZONTAL TENON. CONFIG.** | **SINGLE** | **2 @ 90°** | **2 @ 180°** |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 25**
TOP VIEW




**FIGURE 26**
ISOMETRIC





**FIGURE 27**
SIDE VIEW





**FIGURE 28**
FRONT VIEW





**FIGURE 29**
BACK VIEW





**FIGURE 30**
BOTTOM VIEW

**TABLE 13**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERL1 | 9600L | 3,000K | 15.5 | SEE TABLE 15 | TYPE III | S473108 | LC99GE |

TABLE OF CONTENTS



RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



## TABLE 14

**PHOTOMETRIC DIAGRAMS**

| FIXTURE WITHOUT BACKLIGHT SHIELD | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 9,600 |  |  |
| WATTS | 97 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_10C330_ .IES | | |






| FIXTURE WITH BACKLIGHT SHIELD (C) | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 9,400 |  |  |
| WATTS | 97 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL1_10C330_ -ELSHS-ERL1-BLCK.IES | | |





## TABLE 15

**LUMINAIRE ESTIMATED PROJECTED AREA (EPA)**

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 31**
TOP VIEW




**FIGURE 32**
ISOMETRIC





**FIGURE 33**
SIDE VIEW





**FIGURE 34**
FRONT VIEW





**FIGURE 35**
BACK VIEW





**FIGURE 36**
BOTTOM VIEW

**TABLE 16**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERL2 | 20100L | 3,000K | 24.0 | SEE TABLE 18 | TYPE III | S473110 | LC174G |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |





TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX



## TABLE 17

**PHOTOMETRIC DIAGRAMS**

| FIXTURE WITHOUT BACKLIGHT SHIELD | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 20,100 |  |  |
| WATTS | 174 | | |
| MOUNTING HEIGHT | 35' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL2_21C330_ -120-277V.IES | | |





| FIXTURE WITH BACKLIGHT SHIELD (C) | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 19,700 |  |  |
| WATTS | 174 | | |
| MOUNTING HEIGHT | 35' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERL2_21C330_ -120-277V-ELSHS -ERL2-BLCK.IES | | |





## TABLE 18


| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.57 | 1.14 | 1.14 |

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 37**
TOP VIEW




**FIGURE 38**
ISOMETRIC





**FIGURE 39**
SIDE VIEW





**FIGURE 40**
FRONT VIEW





**FIGURE 41**
BACK VIEW





**FIGURE 42**
BOTTOM VIEW

**TABLE 19**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERLH | 11000L | 3,000K | 15.15 | SEE TABLE 21 | TYPE IV | S473112 | LC96GE |

TABLE OF CONTENTS



RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



## TABLE 20

**PHOTOMETRIC DIAGRAMS**

| FIXTURE WITHOUT BACKLIGHT SHIELD | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 11,000 |  |  |
| WATTS | 98 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERLH_11D330_ .IES | | |





| FIXTURE WITH BACKLIGHT SHIELD (C) | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 10,700 |  |  |
| WATTS | 98 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERLH_11D330_ ELSHS-ERL1 -BLCK.IES | | |





## TABLE 21


| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

**ATTENTION:**

* SEE NOTES AND REFERENCES SHEET 21.





**FIGURE 43**
TOP VIEW




**FIGURE 44**
ISOMETRIC





**FIGURE 45**
SIDE VIEW





**FIGURE 46**
FRONT VIEW





**FIGURE 47**
BACK VIEW





**FIGURE 48**
BOTTOM VIEW

**TABLE 22**

| MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT (LBS) | PROJECTED AREA | DISTRIBUTION TYPE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| GE/ERLH | 14400L | 3,000K | 15.15 | SEE TABLE 24 | TYPE III | S473114 | LC136G |

TABLE OF CONTENTS



RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |



## TABLE 23

**PHOTOMETRIC DIAGRAMS**

| FIXTURE WITHOUT BACKLIGHT SHIELD | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 14,400 |  |  |
| WATTS | 136 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERLH_15C330_ .IES | | |





| FIXTURE WITH BACKLIGHT SHIELD (C) | | PLOT DRAWN IN FOOTCANDLES | GRAPH RADIUS LINES IN CANDELAS |
|---|---|---|---|
| LUMENS | 14,000 |  |  |
| WATTS | 136 | | |
| MOUNTING HEIGHT | 30' | | |
| ARM LENGTH | 6' | | |
| ARRANGEMENT | SINGLE | | |
| .IES FILE NAME | ERLH_15C330_ ELSHS-ERL1 -BLCK.IES | | |





## TABLE 24


| LUMINAIRE ESTIMATED PROJECTED AREA (EPA) | | | |
|---|---|---|---|
| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
| -- |  |  |  |
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.50 | 1.0 | 1.0 |

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |





**FIGURE 49**
ISOMETRIC





**FIGURE 50**
TOP VIEW





**FIGURE 51**
ISOMETRIC





**FIGURE 52**
TOP VIEW

## TABLE 25

| GE LED BACK LIGHT SHIELD | | | | |
|---|---|---|---|---|
| **DESCRIPTION** | **FIGURE** | **FIXTURE TYPE COMPATIBILITY BY STOCK NUMBER** | **STOCK NUMBER** | **DESIGN UNITS** |
| ERL1 & ERLH BACK LIGHT SHIELD, 5 1/4" X 3 1/4" X 9 7/8" LONG | 49 | S473100, S473102, S473104, S473106, S473108, S473112, S473114 | S643014 | GEBLS1 |
| ERL2 BACK LIGHT SHIELD, 5 1/4" X 4 1/2" X 10 7/8" LONG | 51 | S473110 | S643016 | GEBLS2 |

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS
RETURN TO LED FIXTURE INDEX

## INSTALLATION:

A. REMOVE DOOR FROM LUMINAIRE BEFORE INSTALLING SCREWS TO PREVENT INTERNAL DAMAGE. UNFASTEN DOOR LATCH SCREW, OPEN DOOR, AND REMOVE DOOR FROM HINGE CRADLE.

B. FASTEN SHIELD TO DOOR BY SECURING THE INCLUDED THREAD CUTTING SCREWS INTO THE TWO 3/16-INCH HOLES ON THE SHIELD (SHOWN ON FIGURES 50 AND 52).

C. MAKE SURE THE SHIELD IS ORIENTED CORRECTLY BY VERIFYING THE 1-INCH HOLE IN THE CENTER OF THE SHIELD LINES UP WITH THE LATCH SCREW ON THE DOOR (SHOWN ON FIGURES 49 AND 51). FOR THE ERL2 SHIELD, THE SQUARE CUTOUTS ON THE SHIELD SHOULD LINE UP WITH THE SQUARE BUMPS ON THE DOOR (SHOWN ON FIGURE 51).

D. TO REPLACE DOOR INTO LUMINAIRE, HOLD SLIGHTLY PAST VERTICAL TOWARD THE POLE-SIDE OF THE HINGE. INSERT HINGE PIN INTO HINGE CRADLE AND LOWER DOOR TO VERIFY DOOR CAN HANG FREE. CLOSE DOOR AND SECURE LATCH SCREW.

## BILL OF MATERIALS: NONE

## NOTES:

I. REFER TO SPECIFIC PRODUCT INSTALLATION MANUALS PROVIDED WITH ITEM FOR COMPLETE SAFETY AND INSTALLATION INSTRUCTIONS.

II. SEE NON-OPERATIONAL ESP TBD FOR IES DESIGN FILES.

(III) MANUFACTURER DATA REPRODUCED OR ADAPTED WHERE NOTED FROM PRODUCT CUT SHEET OLP-3128 (REV 09/06/17) AND INSTALLATION GUIDE GEH-6064-SP (REV 05/17/17).

## REFERENCE:

a. FOR OVERHEAD LIGHTING INSTALLATION, SEE OH1570.

b. FOR UNDERGROUND LIGHTING INSTALLATION, SEE UG4431.

(c) FOR BACKLIGHT SHIELD AND INSTALLATION DETAILS, SEE SHEET 20.

TABLE OF CONTENTS

RETURN TO LED FIXTURE INDEX

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 01/18/2022 | F | | | | | | |
| B | TABLE UPDATE | AMP | JIK | JES | CZH | 02/12/2020 | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | JIK | JES | CZH | 08/20/2019 | D | NOTES UPDATE | AMP | RSL | JAS | KRG | 02/16/2023 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

GE EVOLVE LED ROADWAY LIGHTING FIXTURES - NOTES AND REFERENCES

OH1571.21
UG4471.21

**SCOPE:** THIS STANDARD SHOWS CREE RSW & TRAVEYO TYPE LED FIXTURES USED TO PROVIDE ROADWAY LIGHTING.

## TABLE 1

| CREE LED FIXTURE INDEX | | | | | | | |
|---|---|---|---|---|---|---|---|
| **DESCRIPTION** | **DESIGN UNITS** | **MOUNTING HEIGHT** (II) (III) (A) | **MAXIMUM SYSTEM WATTAGE** | **STANDARD PAGE** | **STOCK NUMBER** | **FIGURE DETAIL** | **HPSV/LPSV EQUIVALENT STOCK NUMBERS** (a) (b) |
| 5KL RSW TYPE 3 | RWS3 | 26' | 45 | OH 1572.6 | S473138 | 1 | S473800, S473400, S473802, S473402 |
| 5KL RSW TYPE 2 | RWS2 | 26' | 45 | OH 1572.8 | S473140 | 1 | S473800, S473400, S473802, S473402 |
| 9KL RSW TYPE 3 | RWM3 | 30' | 83 | OH 1572.10 | S473142 | 2 | S473406, S473806, S473404, S473804 |
| 9KL RSW TYPE 2 | RWM2 | 30' | 83 | OH 1572.12 | S473150 | 2 | S473406, S473806, S473404, S473804 |
| 14KL RSW TYPE 3 | RWL3 | 30' | 136 | OH 1572.14 | S473144 | 3 | S473408 |
| 24KL RSW TYPE 3 | RWX3 | 35' | 223 | OH 1572.16 | S473146 | 3 | S473410 |
| 5KL TRV TYPE 3 | RESERVED FOR FUTURE USE | | | | | | |
| 5KL TRV TYPE 2 | | | | | | | |
| 10KL TRV TYPE 3 | | | | | | | |
| 10KL TRV TYPE 2 | | | | | | | |
| 25KL TRV TYPE 3 | | | | | | | |

TABLE OF CONTENTS




**FIGURE 1**
RSW SMALL




**FIGURE 2**
RSW MEDIUM




**FIGURE 3**
RSW LARGE/XL

**FUTURE FIGURE**

**FIGURE 4**
TRV SMALL

**FUTURE FIGURE**

**FIGURE 5**
TRV MEDIUM

**FUTURE FIGURE**

**FIGURE 6**
TRV LARGE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ROADWAY LED LIGHTING FIXTURES
CREE - MANUFACTURER INDEX

**ATTENTION:** INSTALLATION FOR RSW TYPE LED FIXTURES

## INSTALLATION:

(A) HPSV/LPSV CONVERSION TO LED: REMOVE AND REPLACE ENTIRE HPSV/LPSV STREET LIGHTING FIXTURE AND BALLAST AND REPLACE WITH EQUIVALENT LED FIXTURE SHOWN IN TABLE 1. FOR OVERHEAD CIRCUIT RECONDUCTOR OR REBUILD, MOUNT THE REPLACEMENT LED FIXTURE AT THE EXISTING FIXTURE HEIGHT OR HIGHER WHILE MAINTAINING REQUIRED CLEARANCES TO OTHER FACILITIES PER OH1509.

B. MECHANICAL INSTALLATION OF FIXTURE

1. SLIDE FIXTURE ON TO A MINIMUM 8" LONG TENON (MAST), THROUGH OPENING ON THE REAR OF HOUSING. SEE **FIGURE 7**.
2. ONCE DESIRED POSITION IS ACHIEVED, OPEN COVER BY HOLDING FIXTURE AND PULLING THE HANDLE AND ALLOW THE COVER TO SWING OPEN. SEE **FIGURE 8 AND 9**.
3. TO LEVEL FIXTURE, USE BUBBLE LEVEL LOCATED INSIDE HOUSING. ADJUST LEVELING OF FIXTURE FROM SIDE TO SIDE BY ROTATION FIXTURE ON POLE. TO LEVEL FROM FRONT TO BACK, SLIDE POLE IN OR OUT TO DIFFERENT STEP IN UPPER HOUSING. EACH STEP CHANGES THE ANGLE IN 2.5 DEGREE INCREMENTS.
4. WHEN TIGHTENING BOLTS, MAKE SURE TO ALTERNATE BETWEEN BOLTS TO KEEP BRACKET STRAIGHT. TIGHTEN MOUNTING BOLTS TO THE APPROPRIATE TORQUE VALUES AS SPECIFIED IN THE MANUFACTURER INSTALLATION GUIDE. DO NOT OVER TIGHTEN. SEE **FIGURE 7** FOR BOLT LOCATION.





**FIGURE 7**
INTERNAL VIEW





**FIGURE 8**
BOTTOM VIEW




**FIGURE 9**
BOTTOM VIEW LID OPEN

C. ELECTRICAL CONNECTIONS OF FIXTURES

1. FOR 120/277V CONNECT THE BLACK FIXTURE LEAD TO THE VOLTAGE SUPPLY POSITION OF THE TERMINAL BLOCK (HOT 1 FOR 208/240V WIRING).
2. FOR 120/277V CONNECT THE WHITE FIXTURE LEAD TO THE NEUTRAL SUPPLY POSITION OF THE TERMINAL BLOCK OR (HOT 2 FOR 208/240V WIRING).
3. CONNECT THE GREEN OR GREEN/YELLOW GROUND LEAD TO THE GREEN WIRE POSITION OF THE TERMINAL BLOCK.
4. PUSH EXCESS SUPPLY WIRES INTO POLE AND CLOSE COVER. MAKE SURE THAT NO WIRES ARE PINCHED AND COVER LATCHES ARE FULLY ENGAGED.





**FIGURE 10**
WIRING SCHEMATIC

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ROADWAY LED LIGHTING FIXTURES
INSTALLATION FOR RSW SERIES

OH1572.2
UG4472.2

TABLE OF CONTENTS

D. MODIFYING FIELD ADJUSTABLE OUTPUT (FAO) SETTINGS OF FIXTURE

1. THE FIELD ADJUSTABLE OUTPUT MODULE ENABLES THE RSW FIXTURE TO BE DIMMED AS NEEDED FOR A PARTICULAR INSTALLATION. ALL FIXTURES WILL BE SHIPPED FROM THE FACTORY AT THE MAXIMUM LUMEN OUTPUT AND CAN BE MANUALLY ADJUSTED TO LOWER OUTPUTS FOR PROJECT SPECIFIC NEEDS DURING INSTALLATION.
2. THE FIELD ADJUSTABLE OUTPUT MODULE IS LOCATED INSIDE THE FIXTURE. OPEN THE COVER BY HOLDING FIXTURE AND PULLING THE HANDLE. ALLOW THE COVER TO SWING OPEN.
3. ESTABLISH THE DESIRED POWER OR LUMEN SETTING BY TURNING THE MODULE SWITCH TO THE POSITION DEFINED BY THE AU/CU POWER LEVEL INCLUDED WITH THE DESIGN PACKAGE. REFER TO THE MANUFACTURER SPECIFICATIONS AND FIELD ADJUSTABLE SETTINGS TABLES INCLUDED WITHIN THIS STANDARD FOR EACH FIXTURE. SEE FIGURE 11, 12, AND 13 ADJUSTMENT SWITCH DETAILS FOR EACH FIXTURE SIZE.
4. CLOSE THE COVER ENSURING NO WIRES ARE PINCHED. APPLY A WATTAGE LABEL THAT INDICATES THE ADJUSTED FIXTURE POWER SETTING.





**FIGURE 11**
SMALL RSW
FAO SWITCH





**FIGURE 12**
MEDIUM RSW
FAO SWITCH





**FIGURE 13**
LARGE/XL RSW
FAO SWITCH

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THIS IS A REPRODUCTION OR ADAPTATION OF MANUFACTURER DATA. REFER TO SPECIFIC PRODUCT INSTALLATION MANUALS PROVIDED WITH STOCK MATERIALS FOR COMPLETE SAFETY AND INSTALLATION INSTRUCTIONS.

(II) MOUNTING HEIGHTS PROVIDED ON PAGE OH1572.1 ARE SPECIFIC TO NEW UNDERGROUND FEED INSTALLATIONS DUE TO STANDARD CONCRETE POLE SIZES AVAILABLE. NEW LED STREETLIGHT INSTALLATIONS OR HPSV-TO-LED UPGRADE INSTALLATIONS MAY BE MOUNTED WITHIN 2 FEET OF THESE REFERENCE MOUNTING HEIGHTS AS LONG AS THE REQUIRED CLEARANCES TO OTHER FACILITIES ARE MAINTAINED PER OH1509.

(III) FOR NEW SDG&E OWNED STREETLIGHT INSTALLATION (NOT EXISTING CONVERSIONS), A LIGHTING DESIGN ANALYSIS MAY BE REQUIRED TO DETERMINE THE MOUNTING HEIGHT IF THE REFERENCE MOUNTING HEIGHT PROVIDED HERE ARE NOT FEASIBLE. CONTACT THE STREET LIGHTING GROUP IN THIS SCENARIO FOR GUIDANCE.

**REFERENCE:**

(a) SEE OVERHEAD FIELD MAINTENANCE ONLY SECTION 1500 FOR HPSV AND LPSV FIXTURE DETAILS.

(b) SOME FIXTURES ARE NO LONGER AVAILABLE.

c. SEE OH1570 FOR OVERHEAD LIGHTING INSTALLATION.

d. SEE UG4431 FOR UNDERGROUND LIGHTING INSTALLATION.

e. SEE OH1512 FOR PHOTOELECTRIC CONTROLS AVAILABLE.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS TRAVEYO TYPE LED FIXTURES USED TO PROVIDE ROADWAY LIGHTING.

**ATTENTION:** INSTALLATION FOR TRAVEYO TYPE LED FIXTURES

**INSTALLATION:**

RESERVED FOR FUTURE CONTENT

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE OH1570 FOR OVERHEAD LIGHTING INSTALLATION.

b. SEE UG4431 FOR UNDERGROUND LIGHTING INSTALLATION.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ROADWAY LED LIGHTING FIXTURES INSTALLATION FOR TRAVEYO SERIES

OH1572.5
UG4472.5

**SCOPE:** THIS STANDARD SHOWS VARIOUS CREE LED ROADWAY LIGHTING FIXTURES.

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1572.19. LUMEN OUTPUT SETTING MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 2 ON NEXT SHEET.




**FIGURE 1**
ISOMETRIC





**FIGURE 2**
BOTTOM





**FIGURE 3**
FRONT





**FIGURE 4**
SIDE

TABLE OF CONTENTS

## TABLE 1

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473138 | CREE / RSW SMALL | 5000L | 3000K | 8.45 LBS | SEE LUMINAIRE EPA TABLE | TYPE III MEDIUM | RWS3 |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.61 | 0.89 | 1.22 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed


## PHOTOMETRIC DIAGRAMS

FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD

LUMENS: 5000
WATTS: 45
MOUNTING HEIGHT: 26'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWS-A-HT-3ME-5L-30K7-UL_CONFIGURED.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


FIXTURE DESIGN WITH BACKLIGHT SHIELD

LUMENS: 4630
WATTS: 45
MOUNTING HEIGHT: 26'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWS-A-HT-3ME-3L-30K7-UL W-RSW-BLSS_11675461.01.IES

SEE SHEET OH1572.18 FOR BACKLIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

TABLE OF CONTENTS

**ATTENTION:** LUMEN OUTPUT "Q" SETTING MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

**TABLE 2**

| Q OPTION SETTING | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAGE | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPSV EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| Q4 (FULL POWER) | 45 | 50 | 5,000 | 4,630 | 100 |
| Q3 | 41 | 40 | 4,654 | 4,310 | 70 |
| Q2 | 36 | 40 | 4,105 | 3,801 | 50-70 |
| Q1 | 30 | 30 | 3,617 | 3,350 | 50-70 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

CREE RSW ROADWAY LIGHTING
5KL FIXTURE

OH1572.7
UG4472.7

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1572.19. LUMEN OUTPUT SETTING MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 4 ON NEXT SHEET.





**FIGURE 5**
ISOMETRIC





**FIGURE 6**
BOTTOM





**FIGURE 7**
FRONT





**FIGURE 8**
SIDE

## TABLE 3

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473140 | CREE / RSW SMALL | 5000L | 3000K | 8.45 LBS | SEE LUMINAIRE EPA TABLE | TYPE II MEDIUM | RWS2 |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.61 | 0.89 | 1.22 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

CREE RSW ROADWAY LIGHTING
5KL FIXTURE


OH1572.8
UG4472.8

TABLE OF CONTENTS


## PHOTOMETRIC DIAGRAMS

FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD

LUMENS: 5000
WATTS: 45
MOUNTING HEIGHT: 26'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWS-A-HT-2ME-5L-30K7-UL_11644102.07.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


FIXTURE DESIGN WITH BACKLIGHT SHIELD

LUMENS: 4630
WATTS: 45
MOUNTING HEIGHT: 26'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWS-A-HT-2ME-5L-30K7-UL W-RSW-BLSS_11675461.01.IES

SEE SHEET OH1572.18 FOR BACKLIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

**ATTENTION:** LUMEN OUTPUT "Q" SETTING MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

**TABLE 4**

| Q OPTION SETTING | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAGE | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPSV EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| Q4 (FULL POWER) | 45 | 50 | 5,000 | 4,630 | 100 |
| Q3 | 41 | 40 | 4,654 | 4,310 | 70 |
| Q2 | 36 | 40 | 4,105 | 3,801 | 50-70 |
| Q1 | 30 | 30 | 3,617 | 3,350 | 50-70 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



TABLE OF CONTENTS

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1572.19. LUMEN OUTPUT SETTING MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 6 ON NEXT SHEET.





**FIGURE 9**
ISOMETRIC





**FIGURE 10**
BOTTOM





**FIGURE 11**
FRONT





**FIGURE 12**
SIDE

TABLE OF CONTENTS

## TABLE 5

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473142 | CREE / RSW MEDIUM | 9000L | 3000K | 15.6 LBS | SEE LUMINAIRE EPA TABLE | TYPE III MEDIUM | RWM3 |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.86 | 1.24 | 1.71 |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |


## PHOTOMETRIC DIAGRAMS

FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD

LUMENS: 9325
WATTS: 83
HT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWM-A-HT-3ME-9L-30K7-UL-GY-N_12311460.02A.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


FIXTURE DESIGN WITH BACKLIGHT SHIELD

LUMENS: 8550
WATTS: 83
MOUNTING HEIGHT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWM-A-HT-3ME-9L-30K7-UL W_RSW-BLSM_11705478.03.IES

SEE SHEET OH1572.18 FOR BACKLIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

TABLE OF CONTENTS

**ATTENTION:** LUMEN OUTPUT "Q" SETTING MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

**TABLE 6**

| Q OPTION SETTING | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAGE | LUMEN OUTPUT | HPSV EQUIVALENT WATTAGE |
|---|---|---|---|---|
| Q8 (FULL POWER) | 83 | 80 | 9,325 | 150 |
| Q7 | 81 | 80 | 9,100 | 150 |
| Q6 | 75 | 80 | 8,975 | 150 |
| Q5 | 69 | 70 | 8,325 | 150 |
| Q4 | 65 | 70 | 7,750 | 100-150 |
| Q3 | 61 | 60 | 7,300 | 100 |
| Q2 | 60 | 60 | 7,000 | 100 |
| Q1 | 50 | 50 | 6,500 | 100 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

CREE RSW ROADWAY LIGHTING
9KL FIXTURE

OH1572.11
UG4472.11

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1572.19. LUMEN OUTPUT SETTING MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 8 ON NEXT SHEET.




**FIGURE 13**
ISOMETRIC





**FIGURE 14**
BOTTOM





**FIGURE 15**
FRONT





**FIGURE 16**
SIDE

## TABLE 7

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473150 | CREE / RSW MEDIUM | 9000L | 3000K | 15.6 LBS | SEE LUMINAIRE EPA TABLE | TYPE II MEDIUM | RWM2 |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 0.86 | 1.24 | 1.71 |


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |


## PHOTOMETRIC DIAGRAMS

FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD

LUMENS: 9325
WATTS: 83
HT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWM-A-HT-2ME-9L-30K7-UL-GY-N_12311460.05A.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


FIXTURE DESIGN WITH BACKLIGHT SHIELD

LUMENS: 8550
WATTS: 83
MOUNTING HEIGHT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWM-A-HT-2ME-9L-30K7-UL W-RSW-BLSM_11705478.01.IES

SEE SHEET OH1572.18 FOR BACKLIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

TABLE OF CONTENTS

**ATTENTION:** LUMEN OUTPUT "Q" SETTING MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

**TABLE 8**

| Q OPTION SETTING | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAGE | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPSV EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| Q8 (FULL POWER) | 83 | 80 | 9,325 | 8,550 | 150 |
| Q7 | 81 | 80 | 9,100 | 8,350 | 150 |
| Q6 | 75 | 80 | 8,975 | 8,250 | 150 |
| Q5 | 69 | 70 | 8,325 | 7,650 | 150 |
| Q4 | 65 | 70 | 7,750 | 7,125 | 100-150 |
| Q3 | 61 | 60 | 7,300 | 6,700 | 100 |
| Q2 | 60 | 60 | 7,000 | 6,425 | 100 |
| Q1 | 50 | 50 | 6,500 | 5,975 | 100 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

CREE RSW ROADWAY LIGHTING
9KL FIXTURE

OH1572.13
UG4472.13

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1572.19. LUMEN OUTPUT SETTING MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 10 ON NEXT SHEET.




**FIGURE 17**
ISOMETRIC





**FIGURE 18**
SIDE





**FIGURE 19**
FRONT





**FIGURE 20**
BOTTOM

TABLE OF CONTENTS

## TABLE 9

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473144 | CREE / RSW LARGE | 14000L | 3000K | 20.2 LBS | SEE LUMINAIRE EPA TABLE | TYPE III MEDIUM | RWL3 |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 1.00 | 1.55 | 2.00 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed


## PHOTOMETRIC DIAGRAMS

FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD

LUMENS: 14575
WATTS: 136
HT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWL-A-H-T-3ME-14L-30K7-UL-GY-N_12081584.04A.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


FIXTURE DESIGN WITH BACKLIGHT SHIELD

LUMENS: 12875
WATTS: 136
MOUNTING HEIGHT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWL-A-HT-3ME-14L-30K7-UL-GY-N W RSW-BLSL_12081584.07A.IES

SEE SHEET OH1572.18 FOR BACKLIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

TABLE OF CONTENTS

**ATTENTION:** LUMEN OUTPUT "Q" SETTING MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

**TABLE 10**

| Q OPTION SETTING | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAGE | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPSV EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| Q9 (FULL POWER) | 136 | 140 | 14,575 | 12,875 | 250 |
| Q8 | 133 | 130 | 14,425 | 12,725 | 250 |
| Q7 | 126 | 130 | 13,850 | 12,225 | 250 |
| Q6 | 120 | 120 | 13,400 | 11,825 | 150-250 |
| Q5 | 110 | 110 | 12,375 | 10,925 | 150-250 |
| Q4 | 102 | 100 | 11,575 | 10,225 | 150 |
| Q3 | 90 | 90 | 10,500 | 9,275 | 150 |
| Q2 | 81 | 80 | 9,250 | 8,175 | 100-150 |
| Q1 | 70 | 70 | 8,350 | 7,375 | 100-150 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

CREE RSW ROADWAY LIGHTING
14KL FIXTURE

OH1572.15
UG4472.15

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1572.19. LUMEN OUTPUT SETTING MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 12 ON NEXT SHEET.





**FIGURE 21**
ISOMETRIC





**FIGURE 22**
BOTTOM





**FIGURE 23**
FRONT





**FIGURE 24**
SIDE

TABLE OF CONTENTS

## TABLE 11

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473146 | CREE / RSW EXTRA LARGE | 24000L | 3000K | 28.8 LBS | SEE LUMINAIRE EPA TABLE | TYPE III MEDIUM | RWX3 |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | 1.17 | 1.93 | 2.33 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS


CREE RSW ROADWAY LIGHTING
24KL FIXTURE

OH1572.16
UG4472.16


## PHOTOMETRIC DIAGRAMS

FIXTURE DESIGN WITHOUT BACKLIGHT SHIELD

LUMENS: 23800
WATTS: 223
HT: 35'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
RSWX-A-HT-3ME-24L-30K7-UL-GY-N_11983868.04.IES




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

THIS SPACE INTENTIONALLY LEFT BLANK - NO BACKLIGHT SHIELD AVAILABLE FOR THIS FIXTURE

TABLE OF CONTENTS

**ATTENTION:** LUMEN OUTPUT "Q" SETTING MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

**TABLE 12**

| Q OPTION SETTING | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAGE | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPSV EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| Q9 (FULL POWER) | 223 | 220 | 23,800 | 22,800 | 400 |
| Q8 | 212 | 210 | 22,800 | 21,800 | 400 |
| Q7 | 200 | 200 | 21,700 | 20,800 | 400 |
| Q6 | 191 | 190 | 20,900 | 20,000 | 250-400 |
| Q5 | 172 | 170 | 19,100 | 18,300 | 250-400 |
| Q4 | 156 | 160 | 17,800 | 17,100 | 250-400 |
| Q3 | 138 | 140 | 15,900 | 15,300 | 250 |
| Q2 | 121 | 120 | 14,350 | 13,725 | 250 |
| Q1 | 107 | 110 | 12,875 | 12,325 | 150-250 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |





**FIGURE 25**
ISOMETRIC





**FIGURE 26**
TOP VIEW





**FIGURE 27**
TOP VIEW





**FIGURE 28**
TOP VIEW

## TABLE 13

| RSW LED BACK LIGHT SHIELD | | | | |
|---|---|---|---|---|
| **STOCK NUMBERS** | **DESCRIPTION** | **FIGURE** | **FIXTURE TYPE COMPATIBILITY BY STOCK NUMBER** | **DESIGN UNITS** |
| S643018 | RSW, BACK LIGHT SHIELD, SMALL | 26 | S473138, S472140 | RWBSS |
| S643020 | RSW, BACK LIGHT SHIELD, MEDIUM | 27 | S473142, S473150 | RWBSM |
| S643022 | RSW, BACK LIGHT SHIELD, LARGE | 28 | S473144 | RWBSL |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed



TABLE OF CONTENTS





**FIGURE 29**
ISOMETRIC





**FIGURE 30**
TOP VIEW





**FIGURE 31**
TOP VIEW

## TABLE 14

| RSW CUL-DE-SAC LIGHT SHIELD | | | | |
|---|---|---|---|---|
| **STOCK NUMBERS** | **DESCRIPTION** | **FIGURE** | **FIXTURE TYPE COMPATIBILITY BY STOCK NUMBER** | **DESIGN UNITS** |
| S643024 | RSW, CUL-DE-SAC LIGHT SHIELD, SMALL | 30 | S473138, S472140 | RWCSS |
| S643026 | RSW, CUL-DE-SAC LIGHT SHIELD, MEDIUM | 31 | S473142, S473150 | RWCSM |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

## INTSALLATION

A. CUL-DE-SAC AND BACK LIGHT SHIELDS

1. INSERT ONE OF THE TABS ON THE LIGHT SHIELD INTO THE FIRST SLOT IN THE LUMINAIRE VENT BY PRESSING THE TAB DOWN INTO THE SLOT. SEE FIGURES 25 AND 29 FOR BACK LIGHT OR CUL-DE-SAC LIGHT SHIELD VARIATIONS RESPECTIVELY.
2. INSERT THE OTHER LIGHT SHIELD TAB INTO THE LAST SLOT ON THE LUMINAIRE VENT BY PRESSING THE TAB DOWN INTO THE SLOT. SEE FIGURES 25 AND 29 FOR BACK LIGHT OR CUL-DE-SAC LIGHT SHIELD VARIATIONS RESPECTIVELY.

**BILL OF MATERIALS:** NONE

## NOTES:

I. REFER TO SPECIFIC PRODUCT INSTALLATION MANUALS PROVIDED WITH ITEM FOR COMPLETE SAFETY AND INSTALLATION INSTRUCTIONS.

## REFERENCES:

a. SEE OVERHEAD CONSTRUCTION STANDARD 1570 FOR OVERHEAD LIGHTING INSTALLATION.

b. SEE UNDERGROUND CONSTRUCTION STANDARD 4431 FOR UNDERGROUND LIGHTING INSTALLATION.

c. SEE OVERHEAD CONSTRUCTION STANDARD 1512 FOR PHOTOELECTRIC CONTROLS AVAILABLE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | RSL | JES | CZH | 04/28/21 | D | | | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| | Indicates Latest Revision | | Completely Revised | X | New Page | Information Removed |

SHEET 20 OF 20

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

CREE RSW ROADWAY LIGHTING
FIXTURE - LIGHT SHIELDS

OH1572.20
UG4472.20

**SCOPE:** THIS STANDARD SHOWS ACUITY BRANDS ATB TYPE LED LIGHT FIXTURES USED TO PROVIDE ROADWAY LIGHTING.

## TABLE 1

| ACUITY LED FIXTURE INDEX | | | | | | | |
|---|---|---|---|---|---|---|---|
| **DESCRIPTION** | **DESIGN UNIT** | **MOUNTING HEIGHT** (II) (III) (A) | **MAXIMUM SYSTEM WATTAGE** | **STANDARD PAGE** | **STOCK NUMBER** | **FIGURE DETAIL** | **HPSV/LPSV EQUIVALENT STOCK NUMBERS** (a) (b) |
| 7KL ATBX TYPE II | ATBX | 26' | 60 | OH1573.5 | S473434 | 1 | S473800, S473400, S473802, S473402 |
| 11KL ATBS TYPE III | ATBS | 30' | 82 | OH1573.7 | S473438 | 2 | S473404, S473804, S473406, S473806 |
| 20KL ATBM TYPE III | ATBM | 35' | 190 | OH1573.9 | S473440 | 3 | S473410, S473408 |




**FIGURE 1**
ATBX




**FIGURE 2**
ATBS




**FIGURE 3**
ATBM

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ROADWAY LED LIGHTING FIXTURES
ACUITY BRANDS MANUFACTURER INDEX

OH1573.1
UG4473.1

**ATTENTION:** INSTALLATION FOR ATB TYPE LED FIXTURES

## INSTALLATION:

(A) HPSV/LPSV CONVERSION TO LED: REMOVE AND REPLACE ENTIRE HPSV/LPSV STREET LIGHTING FIXTURE AND BALLAST AND REPLACE WITH EQUIVALENT LED FIXTURE SHOWN IN TABLE 1. FOR OVERHEAD FEED CONVERSIONS, MOUNT THE REPLACEMENT LED FIXTURE AT THE EXISTING FIXTURE HEIGHT OR HIGHER WHILE MAINTAINING REQUIRED CLEARANCES TO OTHER FACILITIES PER OH1509.

B. MECHANICAL INSTALLATION OF FIXTURE

1. DETERMINE THE SIZE OF THE MAST ARM**.** THIS LUMINAIRE IS DESIGNED TO ACCOMMODATE A MAST ARM FROM 1-1/4 INCH TO 2 INCH DIAMETER.

2. THE LUMINAIRE IS FACTORY SET TO MOUNT TO THE 1-1/4 INCH ARM. TO MOUNT TO A 2 INCH ARM, THE V-SHAPED BRACKET MUST BE FLIPPED. REMOVE THE FITTER BOLTS AND FLIP THE BRACKET.

3. THE REAR OPENING MUST BE ENLARGED FOR ATBS AND ATBM FIXTURE TYPES. KNOCKOUTS ARE CAST AROUND THE REAR OPENING FOR THIS PURPOSE. TO REMOVE THIS EXCESS MATERIAL, STRIKE WITH A HAMMER OR GRASP WITH PLIERS AND BREAK OFF.

4. LOOSEN (DO NOT REMOVE) THE FITTER BOLTS. LIFT THE LUMINAIRE INTO POSITION IN FRONT OF THE MAST ARM SUCH THAT THE MAST ARM ENTERS THROUGH THE OPENING AT THE REAR OF THE LUMINAIRE HOUSING. THE LUMINAIRE SHOULD BE MOUNTED WITH THE PLASTIC LENS FACING DOWN. THE LUMINAIRE TILT ANGLE MAY BE ADJUSTED BY THE ADJUSTMENT STEPS LOCATED IN THE REAR OF THE HOUSING. TIGHTEN THE FITTER BOLTS TO THE VALUES SPECIFIED IN MANUFACTURER INSTALLATION GUIDE. DO NOT OVER TIGHTEN BOLTS.

5. **PHOTOELECTRIC CONTROL:** PLUG THE PHOTOCONTROL INTO THE RECEPTACLE ENSURING GASKET IS FIRMLY SEATED. TWIST CLOCKWISE UNTIL IT LOCKS INTO POSITION. IF PHOTOCONTROL RECEPTACLE ROTATION IS REQUIRED, LOOSEN THE TWO PHILIPS HEAD RECEPTACLE SCREWS COMPLETELY. ROTATE 90°, 180° OR 270°, THEN RE-TIGHTEN SCREWS UNTIL SNUG, USING 20-25 IN-LBS OF TORQUE.

TABLE OF CONTENTS





**FIGURE 4**
INTERNAL VIEW





**FIGURE 5**
TOP VIEW



**FIGURE 6**
BOTTOM VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ROADWAY LED LIGHTING FIXTURES
INSTALLATION

OH1573.2
UG4473.2

C. ELECTRICAL CONNECTIONS OF FIXTURE

1. PULL UP THE TERMINAL BLOCK COVER.

2. FEED THE SUPPLY WIRES THROUGH THE MAST ARM, DRESS THEM SO THEY DO NOT INTERFERE WITH ANY COMPONENTS AND SO THEY WILL NOT BE PINCHED IN THE DOOR, AND CONNECT THEM TO THE PROPER TERMINALS ON THE TERMINAL BLOCK.

3. VERIFY THE SUPPLY VOLTAGE IS CORRECT AS NOTED ON THE NAMEPLATE LABEL.

4. ATTACH SERVICE LEADS TO TERMINAL BLOCK AS SHOWN ON THE WIRING SCHEMATIC. SEE DIAGRAM 1.

5. PUSH DOWN THE TERMINAL BLOCK COVER TO KEEP TERMINALS COVERED. TIGHTEN THE TERMINAL BLOCK SCREW TO THE VALUES SPECIFIED IN MANUFACTURER INSTALLATION GUIDE. DO NOT OVER TIGHTEN SCREW.





**DIAGRAM 1**
WIRING SCHEMATIC





**DIAGRAM 2**
DIMMING CONTROL SCHEMATIC

D. MODIFYING FIELD ADJUSTABLE OUTPUT (FAO) SETTINGS OF FIXTURE

1. THE FIELD ADJUSTABLE OUTPUT MODULE IS LOCATED INSIDE THE FIXTURE. OPEN THE COVER BY REMOVING THE WINGNUT AND ALLOW COVER TO SWING OPEN.

2. ESTABLISH THE DESIRED POWER OR LUMEN SETTING BY TURNING THE SWITCH TO THE POSITION DEFINED BY THE POWER LEVEL INCLUDED WITH THE DESIGN PACKAGE. REFER TO THE MANUFACTURER SPECIFICATIONS AND THE FIELD ADJUSTABLE SETTINGS TABLES INCLUDED WITHIN THIS STANDARD FOR EACH FIXTURE. SEE FIGURE 7 FOR ADJUSTMENT SWITCH DETAILS .

3. CLOSE THE COVER ENSURING NO WIRES ARE PINCHED AND SCREW IN WINGNUT. APPLY A WATTAGE LABEL THAT INDICATES THE ADJUSTED FIXTURE POWER SETTING.





**FIGURE 7**
FAO SWITCH

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



TABLE OF CONTENTS

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THIS IS A REPRODUCTION OR ADAPTATION OF MANUFACTURER DATA. REFER TO SPECIFIC PRODUCT INSTALLATION MANUALS PROVIDED WITH STOCK MATERIALS FOR COMPLETE SAFETY AND INSTALLATION INSTRUCTIONS.

(II) MOUNTING HEIGHTS PROVIDED ON PAGE OH1573.1 ARE SPECIFIC TO NEW UNDERGROUND FEED INSTALLATIONS DUE TO STANDARD CONCRETE POLE SIZES AVAILABLE. NEW LED STREETLIGHT INSTALLATIONS OR HPSV-TO-LED UPGRADE INSTALLATIONS MAY BE MOUNTED WITHIN 2 FEET OF THESE REFERENCE MOUNTING HEIGHTS AS LONG AS THE REQUIRED CLEARANCES TO OTHER FACILITIES ARE MAINTAINED PER OH1509.

(III) FOR NEW SDG&E OWNED STREETLIGHT INSTALLATIONS (NOT EXISTING CONVERSIONS), A LIGHTING DESIGN ANALYSIS MAY BE REQUIRED TO DETERMINE THE REQUIRED MOUNTING HEIGHT IF THE REFERENCE MOUNTING HEIGHTS PROVIDED HERE ARE NOT FEASIBLE. CONTACT THE STREET LIGHTING GROUP IN THIS SCENARIO FOR GUIDANCE.

**REFERENCE:**

(a) OVERHEAD FIELD MAINTENANCE ONLY SECTION 1500 FOR HPSV AND LPSV FIXTURE DETAIL.

(b) SOME FIXTURES ARE NO LONGER AVAILABLE.

c. SEE OH1570 FOR OVERHEAD LIGHTING INSTALLATION.

d. SEE UG4431 FOR UNDERGROUND LIGHTING INSTALLATION.

e. SEE OH1512 FOR PHOTOELECTRIC CONTROLS AVAILABLE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| | Indicates Latest Revision | | Completely Revised | X | New Page | Information Removed |



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ROADWAY LED LIGHTING FIXTURES INSTALLATION

OH1573.4
UG4473.4

**SCOPE:** THIS STANDARD SHOWS VARIOUS ACUITY LED ROADWAY LIGHTING FIXTURES

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1573.12. LUMEN OUTPUT SETTINGS MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 2 ON THE NEXT SHEET.




**FIGURE 1**
ISOMETRIC





**FIGURE 2**
TOP VIEW





**FIGURE 3**
REAR VIEW





**FIGURE 4**
SIDE VIEW

TABLE OF CONTENTS

## TABLE 1

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473434 | ACUITY/ATBX | 7,133L | 3000K | 8 LBS | SEE LUMINAIRE EPA TABLE | TYPE II | ATBX |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | .26 | .52 | .52 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS


ACUITY ATB ROADWAY LIGHTING
7KL FIXTURE

OH1573.5
UG4473.5


## PHOTOMETRIC DIAGRAMS

### FIXTURE WITHOUT BACKLIGHT SHIELD

LUMENS: 7133
WATTS: 60
MOUNTING HEIGHT: 26'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
ATBX_P70_XXXXX_R2_3K.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


### FIXTURE WITH BACKLIGHT SHIELD

LUMENS: 6217
WATTS: 60
MOUNTING HEIGHT: 26'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
ATBX_P70_XXXXX_R2_3K
_HSS.IES

SEE SHEET OH1573.11 FOR BACK LIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

**ATTENTION:** LUMEN OUTPUT FAO SWITCH POSITION MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

### TABLE 2

| FAO SWITCH POSITION | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAG | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPS EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| 8 | 60 | 60 | 7133 | 6,217 | 150W |
| 7 | 56 | 60 | 6,776 | 5,906 | 150W |
| 6 | 49 | 50 | 6,063 | 5,284 | 150W |
| 5 | 41 | 40 | 5,278 | 4,601 | 100W |
| 4 | 33 | 30 | 4,422 | 3,855 | 100W |
| 3 | 25 | 30 | 3,495 | 3,046 | 70W |
| 2 | 17 | 20 | 2,497 | 2,176 | 50W |
| 1 | 10 | 10 | 1,427 | 1,243 | N/A |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ACUITY ATB ROADWAY LIGHTING
7KL FIXTURE

OH1573.6
UG4473.6

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS VARIOUS ACUITY LED ROADWAY LIGHTING FIXTURES

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1573.12. LUMEN OUTPUT SETTINGS MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 4 ON THE NEXT SHEET.




**FIGURE 5**
ISOMETRIC





**FIGURE 6**
TOP VIEW





**FIGURE 7**
REAR VIEW





**FIGURE 8**
SIDE VIEW

TABLE OF CONTENTS

## TABLE 3

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473438 | ACUITY/ATBS | 10,624L | 3000K | 12 LBS | SEE LUMINAIRE EPA TABLE | TYPE III | ATBS |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | .30 | .60 | .60 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS


ACUITY ATB ROADWAY LIGHTING
11KL FIXTURE

OH1573.7
UG4473.7


## PHOTOMETRIC DIAGRAMS

### FIXTURE WITHOUT BACKLIGHT SHIELD

LUMENS: 10624
WATTS: 82
MOUNTING HEIGHT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
ATBS_P50_XXXXX_R3_3K.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


### FIXTURE WITH BACKLIGHT SHIELD

LUMENS: 9423
WATTS: 82
MOUNTING HEIGHT: 30'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
ATBS_P50_XXXXX_R3_3K
_HSS.IES

SEE SHEET OH1573.11 FOR BACK LIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

**ATTENTION:** LUMEN OUTPUT FAO SWITCH POSITION MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

### TABLE 4

| FAO SWITCH POSITION | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAG | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPS EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| 8 | 82 | 80 | 10,624 | 9,423 | 250W |
| 7 | 76 | 80 | 9,987 | 8,858 | 200W |
| 6 | 66 | 70 | 8,712 | 7,727 | 200W |
| 5 | 56 | 60 | 7,543 | 6,690 | 150W |
| 4 | 45 | 50 | 6,268 | 5,560 | 150W |
| 3 | 34 | 30 | 4,781 | 4,240 | 100W |
| 2 | 25 | 30 | 3,612 | 3,204 | 70W |
| 1 | 16 | 20 | 2,337 | 2,073 | 50W |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ACUITY ATB ROADWAY LIGHTING
11KL FIXTURE

OH1573.8
UG4473.8

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS VARIOUS ACUITY LED ROADWAY LIGHTING FIXTURES

**ATTENTION:** SEE NOTES & REFERENCES PAGE OH1573.12. LUMEN OUTPUT SETTINGS MUST BE IDENTIFIED FOR THIS FIXTURE INSTALLATION USING TABLE 6 ON THE NEXT SHEET.




**FIGURE 9**
ISOMETRIC





**FIGURE 10**
TOP VIEW





**FIGURE 11**
REAR VIEW





**FIGURE 12**
SIDE VIEW

TABLE OF CONTENTS

## TABLE 5

| STOCK NUMBER | MANUFACTURER NAME/STYLE | LUMENS PACKAGE | COLOR TEMPERATURE | UNIT WEIGHT | PROJECTED AREA | DISTRIBUTION TYPE | DESIGN UNITS |
|---|---|---|---|---|---|---|---|
| S473440 | ACUITY/ATBM | 20,142L | 3000K | 21 LBS | SEE LUMINAIRE EPA TABLE | TYPE III | ATBM |

## LUMINAIRE ESTIMATED PROJECTED AREA (EPA)

| HORIZONTAL TENON. CONFIG. | SINGLE | 2 @ 90° | 2 @ 180° |
|---|---|---|---|
| STANDARD LUMINAIRE ($FT^2$) (TENON EPA NOT INCLUDED) | .30 | .60 | .60 |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS


ACUITY ATB ROADWAY LIGHTING
21KL FIXTURE

OH1573.9
UG4473.9


## PHOTOMETRIC DIAGRAMS

### FIXTURE WITHOUT BACKLIGHT SHIELD

LUMENS: 20142
WATTS: 190
MOUNTING HEIGHT: 35'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
ATBM_P70_XXXXX_R3_3K.IES




PLOT DRAWN IN FOOTCANDLES





GRAPH RADIUS LINES ARE IN CANDELAS


### FIXTURE WITH BACKLIGHT SHIELD

LUMENS: 18978
WATTS: 190
MOUNTING HEIGHT: 35'
ARM LENGTH: 6'
ARRANGEMENT: SINGLE
.IES FILE NAME:
ATBM_P70_XXXXX_R3_3K
_HSS.IES

SEE SHEET OH1573.11 FOR BACK LIGHT SHIELD DETAILS AND INSTALLATION




PLOT DRAWN IN FOOTCANDLES




GRAPH RADIUS LINES ARE IN CANDELAS

**ATTENTION:** LUMEN OUTPUT FAO SWITCH POSITION MUST BE INCLUDED FOR EACH FIXTURE WITHIN THE CONSTRUCTION NOTES FOR EACH LOCATION IN THE JOB PACKAGE.

### TABLE 6

| FAO SWITCH POSITION | ACTUAL SYSTEM WATTS | NOMINAL LABEL WATTAG | LUMEN OUTPUT | LUMEN OUTPUT WITH BACKLIGHT SHIELD | HPS EQUIVALENT WATTAGE |
|---|---|---|---|---|---|
| 8 | 190 | 190 | 20,142 | 18,978 | 400W |
| 7 | 190 | 190 | 20,142 | 18,978 | 400W |
| 6 | 150 | 150 | 17,725 | 16,701 | 310W |
| 5 | 125 | 130 | 15,711 | 14,803 | 310W |
| 4 | 101 | 100 | 13,294 | 12,525 | 250W |
| 3 | 76 | 80 | 10,474 | 9,869 | 200W |
| 2 | 53 | 50 | 7,654 | 7,212 | 150W |
| 1 | 30 | 30 | 4,431 | 4,175 | 100W |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



TABLE OF CONTENTS





**FIGURE 13**
ISOMETRIC





**FIGURE 15**
TOP VIEW





**FIGURE 16**
TOP VIEW





**FIGURE 14**
ISOMETRIC





**FIGURE 17**
TOP VIEW

## TABLE 7

| ATB HOUSE SIDE SHIELD | | | | |
|---|---|---|---|---|
| **STOCK NUMBER** | **DESCRIPTION** | **FIGURE** | **FIXTURE TYPE COMPATIBILITY BY STOCK NUMBER** | **DESIGN UNITS** |
| S643034 | ATB HOUSE SIDE SHIELD, X-SMALL | 15 | S473434 | ATBXHSS |
| S632032 | ATB HOUSE SIDE SHIELD, SMALL | 16 | S473438 | ATBSHSS |
| S643030 | ATB HOUSE SIDE SHIELD, MEDIUM | 17 | S473440 | ATBMHSS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



TABLE OF CONTENTS





**FIGURE 18**
ATBX WITH LTS





**FIGURE 21**
ATBX LTS





**FIGURE 19**
ATBS WITH LTS





**FIGURE 22**
ATBS LTS





**FIGURE 20**
ATBM WITH LTS





**FIGURE 23**
ATBM LTS

## TABLE 7

| ATB LIGHT TRESPASS SHIELD | | | | |
|---|---|---|---|---|
| **STOCK NUMBER** | **DESCRIPTION** | **FIGURE** | **FIXTURE TYPE COMPATIBILITY BY STOCK NUMBER** | **DESIGN UNITS** |
| S463040 | ATB LIGHT TRESPASS SHIELD, X-SMALL | 18 | S473434 | ATBXLTS |
| S463038 | ATB LIGHT TRESPASS SHIELD, SMALL | 19 | S473438 | ATBSLTS |
| S463036 | ATB LIGHT TRESPASS SHIELD, MEDIUM | 20 | S473440 | ATBMLTS |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed



SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ACUITY ATB ROADWAY LIGHTING
FIXTURES - LIGHT TRESPASS SHIELDS

OH1573.12
UG4473.12

TABLE OF CONTENTS

## INSTALLATION:

A. LIGHT SHIELDS

1. PRE-INSTALL PROVIDED #8 HEX WASHER HEAD SCREWS IN HOLES IN LUMINAIRE OPTICAL PLATE. DO NOT FULLY TIGHEN.
2. ALIGN KEYHOLE SLOTS IN SHIELD BASE TO SCREWS. SHIFT SHIELD SLIGHTLY FOWARD TO ENGAGE KEYHOLE SLOTS ONTO SCREW HEADS.
3. TIGHEN SCREWS UNTIL SNUG.

## BILL OF MATERIALS: NONE

## NOTES:

I. REFER TO SPECIFIC PRODUCT INSTALLATION MANUALS PROVIDED WITH ITEM FOR COMPLETE SAFETY AND INSTALLATION INSTRUCTIONS.

## REFERENCE:

a. SEE OVERHEAD CONSTRUCTION STANDARD 1570 FOR OVERHEAD LIGHTING INSTALLATION.

b. SEE UNDERGROUND CONSTRUCTION STANDARD 4431 FOR UNDERGROUND LIGHTING INSTALLATION.

c. SEE OVERHEAD CONSTRUCTION STANDARD 1512 FOR PHOTOELECTRIC CONTROLS AVAILABLE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | AMP | ADW | JES | CZH | 12/13/21 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed

SHEET 13 OF 13

SDG&E ELECTRIC OVERHEAD CONSTRUCTION STANDARDS

ACUITY ATB ROADWAY LIGHTING
FIXTURES - LIGHT SHIELDS

OH1573.13
UG4473.13

| PAGE | SUBJECT |
|---|---|
| 4505 | GROUNDING HARDWARE |
| 4510 | TRENCH GROUND WIRE - STANDARD AND ALTERNATIVE |
| 4512 | EQUIPMENT GROUNDING INSTALLATION - SINGLE AND THREE-PHASE |
| 4514 | GROUNDING TELCO CONDUCTORS IN PAD MOUNTED EQUIPMENT |
| 4520 | GROUNDING PAD MOUNTED EQUIPMENT |
| 4521 | GROUNDING TRAYER PAD MOUNTED EQUIPMENT |
| 4525 | CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS |
| 4530 | NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM |
| 4540 | GROUNDING SUBSTRUCTURES AND EQUIPMENT - 3313, 3314, 3315, 3316, 3317 |
| 4550 | GROUNDING TELCO CONDUCTOR IN HANDHOLES - 3314, 3315, OR 3316 |


MAIN TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | UPDATES TO 4514 | - | JS | TR | MDJ | 6/13/2016 | F | FORMATTING | EDM | JIK | - | - | 06/18/2021 |
| B | UPDATES TO 4512 | - | JS | TR | MDJ | 6/13/2016 | E | EDITORIAL CHANGES | - | JK | JS | CZH | 5/18/2018 |
| A | ORIGINAL ISSUE | - | JS | TR | MDJ | 6/10/2016 | D | UPDATES TO 4540 | - | JS | TR | MDJ | 10/27/2016 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GROUNDING
TABLE OF CONTENTS

**SCOPE:** THIS STANDARD COVERS THE HARDWARE USED IN GROUNDING PAD MOUNTED AND SUB-SURFACE EQUIPMENT AND FACILITIES.

**TABLE 1**

**PARTS IDENTIFICATION CHART**






| ITEM | PART | SIZE | WIRE SIZE | STOCK NUMBER |
|---|---|---|---|---|
| 1 |  SPLIT BOLT STUD BRONZE | 3/8" X 16 | -- | S262626 (X) |
| | | 1/2" X 13 | -- | S262560 |
| 2 |  BRONZE EYE BOLT CLAMP | -- | 8 TO 2/0 | S471312 |
| | | -- | 6 TO 250 | S471296 |
| | | -- | 4/0 TO 500 | S471232 |
| 3 |  STAINLESS STEEL "L" BRACKET | 2" X 3" | -- | S166072 |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 7/28/2015 | D | | | | | | |

## TABLE 1 (CONT'D)

| PARTS IDENTIFICATION CHART | | | | |
|---|---|---|---|---|
| **ITEM** | **PART** | **SIZE** | **WIRE SIZE** | **STOCK NUMBER** |
| 4 |  ANCHOR SHOULDER EYE BOLT STAINLESS STEEL | 1 1/2" X 1/2" | -- | S152722 (X) |
| 5 |  STAINLESS STEEL PULLING EYE BOLT | 6" X 1/2" | -- | S150528 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. ALL NEW CONNECTIONS AND HARDWARE USED IN THE CONNECTION AND MOUNTING OF GROUNDS SHALL BE COPPER, SILICON BRONZE, AND STAINLESS STEEL. GALVANIZED MOUNT HARDWARE FOR GROUNDING SHALL NO LONGER BE USED. THE STAINLESS STEEL EYE BOLTS AND BRACKETS WILL PREVENT CORROSION AND LIMIT RUST IN THE WATER, ALLOWING THE PRACTICE OF PUMPING WATER TO CONTINUE. USE THE 2" x 3" STAINLESS STEEL MOUNTING BRACKET TO ATTACH THE STAINLESS STEEL SHOULDER EYE BOLT FOR DEAD ENDING AND PASSING THE GROUND WIRE AROUND A CORNER. THIS WILL ELIMINATE CUTTING AND DAMAGING THE GROUND WIRE. 1/2" X 6" EYE BOLT IS USED TO PULL GROUND WIRE TAUGHT.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 7/28/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE STANDARD TRENCH GROUND WIRE INSTALLATIONS AND EQUIPMENT GROUNDS FOR ALL NEW CONSTRUCTION FOR ALL PARTIES USED TO PROVIDE GROUNDING, CONDUIT, AND PAD INSTALLATIONS. THIS INCLUDES ALL NEUTRALS SUPPLIED FROM THE SUBSTATION BANK AND NEUTRALS SUPPLIED BY A GROUNDING BANK AND TRENCH GROUNDS FOR DELTA UNDERGROUND SYSTEMS.





**FIGURE 1** (6)





**FIGURE 2** (6)





**FIGURE 3** (6)
FOR VAULTS ONLY

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 7/28/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRENCH GROUND WIRE - STANDARD

UG4510.1



TABLE OF CONTENTS

**ATTENTION:**

* USE ALTERNATIVE TRENCH GROUND WIRE WHEN TRENCH IS SHORT AND CANNOT MEET REQUIREMENTS OF SHEET 1, AS OUTLINED BELOW, FOR CONDUIT AND PAD INSTALLATIONS. THIS INCLUDES ALL NEUTRALS SUPPLIED FROM THE SUBSTATION BANK AND NEUTRALS SUPPLIED BY A GROUNDING BANK AND TRENCH GROUNDS FOR DELTA UNDERGROUND SYSTEMS.





**FIGURE 4** (7)






**FIGURE 5** (7)




**DETAIL 1**





**FIGURE 6** (7)
FOR VAULTS ONLY

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 7/28/2015 | D | | | | | | |



TABLE OF CONTENTS

## INSTALLATION:

(A) GROUND RODS TO HAVE A SIX-FOOT MINIMUM SEPARATION.

(B) LEAVE 24 INCHES OF WIRE (EXPOSED TAILOUT) ABOVE TOP OF FINAL GRADE.

(C) LOCATE GROUND RODS SO THEY DO NOT TOUCH CONDUITS. GENERAL ORDER 128 REQUIRES GROUND RODS TO BE DRIVEN. THEY MAY BE DRIVEN AT ANGLES IF IT IS DIFFICULT OR NOT POSSIBLE TO DRIVE STRAIGHT DOWN.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD | 1 | -- | REFER TO WORK ORDER | -- |
| 2 | WIRE, BARE COPPER, SOFT DRAWN, #2, 7 STR. (b) | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 3 | GROUND ROD, COPPERWELD, 5/8" X 8'-0" | AS REQ'D | -- | S603074 (X) | -- |
| 4 | CONNECTORS, GROUND, COPPER BONDED | AS REQ'D | -- | S259010 | -- |
| 5 | CU, BARE STRAND, 4/0 | AS REQ'D | -- | -- | -- |
| 6 | WIRE, GROUND, TRENCH (WITHOUT RODS) | AS REQ'D | -- | -- | TG-T-W |
| 7 | WIRE, GROUND, TRENCH (WITH RODS) | AS REQ'D | -- | -- | TG-T-R |

## NOTES:

I. CUSTOMER PRIMARY SERVICE TRENCHES, CUSTOMER PRIMARY METERING, CUSTOMER PRIMARY EQUIPMENT INSTALLATIONS, APPLICANT INSTALLED, SDG&E INSTALLED TRENCH GROUNDS AND ALL PRIMARY EQUIPMENT.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG3480 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

(b) SEE UG4003 FOR WIRE INFORMATION.

(c) SEE UG3960 FOR PREVENTION OF WATER ENTRY.

TABLE OF CONTENTS


© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | DRAWING UPDATE | - | JC | TR | JS/MDJ | 7/28/2015 | D | | | | | | |


**SCOPE:** THIS STANDARD SHOWS SINGLE AND THREE-PHASE EQUIPMENT GROUNDING INSTALLATION USED WITH STANDARD OR ALTERNATE TRENCH GROUND WIRE, AS INSTALLED PER UG4510.

**ATTENTION:**

* SINGLE-PHASE EQUIPMENT GROUNDING.




**DETAIL 1**









**FIGURE 1**

TYPICAL PAD WITHOUT HANDHOLE




**DETAIL 2**





**FIGURE 2**

SECTION VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

EQUIPMENT GROUNDING INSTALLATION
SINGLE-PHASE

UG4512.1

TABLE OF CONTENTS





**FIGURE 3**
PAD WITH 3312 HANDHOLE(S)
SECTION VIEW





**FIGURE 4**
3416 PAD WITH 3311 HANDHOLE
SECTION VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


EQUIPMENT GROUNDING INSTALLATION
SINGLE-PHASE

UG4512.2

TABLE OF CONTENTS

**ATTENTION:**

* THREE-PHASE EQUIPMENT GROUNDING.








**FIGURE 5**

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

EQUIPMENT GROUNDING INSTALLATION
THREE-PHASE

UG4512.3

## INSTALLATION:

(A) IN CASES WHERE THERE ARE TWO GROUND WIRES, SQUEEZE THE GROUND WIRES TOGETHER WITH A COMPRESSION CONNECTOR. WHERE THERE IS ONLY ONE TRENCH GROUND WIRE, ADD THE SECOND 24-INCH TAILOUT WIRE. SDG&E SHALL FURNISH AND INSTALL THE COMPRESSION CONNECTOR AND THE SECOND 24-INCH TAILOUT WIRE.

(B) STANDARD OR ALTERNATE TRENCH GROUND WIRE IS REQUIRED, FOR ALL EQUIPMENT AND TRENCH GROUNDS.

(C) BUTT TRENCH GROUND WIRE AGAINST 3314 HANDHOLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD | 1 | -- | REFER TO WORK ORDER | -- |
| 2 | WIRE, BARE COPPER, #2, 7 STR. SOFT DRAWN (A) | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 3 | CONNECTOR, COMPRESSION (A) | AS REQ'D | -- | S257760 | -- |

## NOTES:

(I) SECOND TRENCH GROUND WIRE MAY BE REQUIRED. (C)

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) SEE UG3484 FOR PAD INSTALLATION USED FOR MOUNTING PAD MOUNTED EQUIPMENT.

(b) SEE UG4003 FOR WIRE INFORMATION.

(c) SEE UG4510 FOR STANDARD AND ALTERNATE TRENCH GROUND WIRE INSTALLATION.

(d) SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

(e) SEE UG3426 & UG3427 FOR THREE-PHASE TRANSFORMER PAD INSTALLATION.

f. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | GW | JS | MDJ | 4/1/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 5/24/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GROUND WIRE INSTALLATION AT PAD MOUNTED EQUIPMENT.





**FIGURE 1**

## INSTALLATION:

A. SDG&E HAS AGREED TO CONNECT TELCO #6 AWG COPPER GROUND WIRE TO SDG&E'S GROUNDING SYSTEM AT SDG&E'S PAD MOUNTED EQUIPMENT. TELCO PERSONNEL WILL RUN THIS TO SDG&E'S PAD LOCATION BEFORE THE PAD IS SET.

B. IN SOME CASES, TELCO MAY INSTALL THEIR GROUND WIRE IN AN IDENTIFIED GROUND WIRE CONDUIT. IF THE CONDUIT IS PRESENT, ONE OF THE FOLLOWING CONDITIONS MUST BE MET:

1. TELCO GROUND WIRE MUST BE PRESENT.
2. IF TELCO GROUND WIRE IS NOT PRESENT, TELCO SHOULD HAVE IDENTIFIED THE CONDUIT AND SEALED IT WITH A PERMANENT CAP.
3. IF TELCO GROUND WIRE IS NOT PRESENT AND TELCO CONDUIT IS NOT SEALED, SDG&E SHOULD CUT OFF THE CONDUIT BELOW GRADE LEVEL TO PREVENT FUTURE UNAUTHORIZED WIRE ENTRY. SDG&E NEED NOT CAP THE TELCO CONDUIT.

C. WHEN COMPLETING THE SDG&E EQUIPMENT GROUNDING CONNECTIONS, SKIN THE TELCO WIRE AND CONNECT IT TO AN SDG&E GROUND GRID TAILOUT AS SHOWN IN FIGURE 1.

(D) USE COMPRESSION CONNECTORS. (c)

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. SEE UG4512 FOR EQUIPMENT GROUNDING.

b. AVAILABLE IN SERVICE STANDARDS AND GUIDE MANUAL.

(c) SEE UG4174 FOR COMPRESSION CONNECTORS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | NO CHANGES - REAFFIRMED | - | JS | TR | MDJ | 5/23/2016 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT

UG4514.1

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATIONS USED TO PROVIDE PAD MOUNTED EQUIPMENT GROUNDING.





**FIGURE 1**
3522 SINGLE-PHASE CABLE TERMINATOR
FEED THROUGH BUSHING INSTALLATION





**FIGURE 2**
3522 SINGLE-PHASE CABLE TERMINATOR
CABLE TAP INSTALLATION
NEW TAGS

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |





**FIGURE 3**
3512 SINGLE-PHASE
FUSED SWITCHING CABINET





**FIGURE 4**
3514 THREE-PHASE
FUSED SWITCHING CABINET

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |

TABLE OF CONTENTS





**FIGURE 5**
3575/3576 THREE-PHASE SERVICE RESTORER

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |





**FIGURE 6**
PLAN VIEW





**FIGURE 6**
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |

## INSTALLATION:

(A) CONCENTRIC NEUTRAL TAILS OR EQUIVALENT WIRE SIZE PER PHASE. (j)

(B) GROUNDING RODS ARE FOR PERSONAL GROUNDS ONLY. MAKE NO PERMANENT CONNECTIONS ON THIS DEVICE.

(C) INSTALL ONE UNISTRUT CHANNEL FITTING IN EACH CORNER OF THE BOX PAD. MOUNT THE FITTING ON THE VERTICAL SURFACE INSIDE OF THE WINDOW.

(D) INSTALL THE 4/0 COPPER WIRE IN THE CHANNEL FITTINGS. "DO NOT INSTALL EYE BOLT TO TIGHTEN RING BUSS".

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CU, SOLID, #14 (OR SURPLUS STRAND OF CONCENTRIC NEUTRAL) | AS REQ'D | -- | -- | -- |
| 2 | WIRE, BARE COPPER, SOFT DRAWN, #2, 7 STR. (i) | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 3 | WIRE, BARE COPPER, SOFT DRAWN, 1/0 STR. (i) | AS REQ'D | -- | S812752 | -- |
| 4 | WIRE, BARE COPPER, SOFT DRAWN, 4/0 STR. (i) | AS REQ'D | -- | S812764 | 4/0-SD |
| 5 | CONNECTOR, COMPRESSION, 4/0 - #4 | AS REQ'D | -- | S257888 | -- |
| 6 | CONNECTOR, COMPRESSION, 4/0 - 1/0 | AS REQ'D | -- | S257856 | -- |
| 7 | CONNECTOR, COMPRESSION, 4/0 - 4/0 | AS REQ'D | -- | S257824 | -- |
| 8 | CONNECTOR, SERVICE POST | AS REQ'D | -- | S262560 | -- |
| 9 | CONNECTOR, GROUND, PROVIDED WITH EQUIPMENT | -- | -- | -- | -- |
| 10 | ROD, GROUNDING | BY MFG | -- | S230018 (X) | -- |
| 11 | BRACKET, STAINLESS STEEL, 2", C 3" | AS REQ'D | -- | S166072 | -- |
| 12 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | 4 | -- | S616692 | -- |
| 13 | NUT, HEXAGON, BRONZE, 1/2" | 4 | -- | S506112 | -- |
| 14 | WASHER, STANDARD, FLAT ROUND, BRONZE, 1/2" | 8 | -- | S799488 | -- |
| 15 | WIRE, TRENCH GROUND (I) | AS REQ'D | -- | -- | -- |
| 16 | WASHER, LOCK, SILICONE, BRONZE, 1/2" | 4 | -- | S796416 | -- |

## NOTES:

(I) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4108 FOR SEALING JACKETED CABLE.

b. SEE UG4174 AND UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART AND COPPER COMPRESSION CONNECTORS.

c. SEE UG4510 FOR STANDARD AND ALTERNATE TRENCH GROUND WIRE INSTALLATION.

d. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

e. SEE UG4521 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

f. SEE UG4514 FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT.

g. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

h. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

(i) SEE UG4003 (PREVIOUS # UG4002.2) FOR WIRE INFORMATION.

(j) SEE UG4176 FOR EQUIVALENT WIRE SIZE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATION FOR JUNCTION PLATES.





**FIGURE 1**





**FIGURE 2**
600A TO 200A JUNCTION





**FIGURE 3**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |

## INSTALLATION:

(A) GROUND EACH PREMOLDED CONNECTOR ON OR IN THE GROUNDING POINT PROVIDED ON CONNECTOR. LOOP WIRE THRU THE GROUNDING EYE AND TWIST THE WIRE TIGHTLY AROUND ITSELF TAKING CARE NOT TO DAMAGE THE EYE.

(B) GROUND BUSHING PLUGS TO EQUIPMENT GROUND.

(C) CONNECT LIKE PHASE CONCENTRIC NEUTRALS OF FEEDER CABLES TOGETHER. CONNECT CONCENTRIC NEUTRALS TO EQUIPMENT GROUND.

(D) CONNECT THE EQUIPMENT GROUND TO THE EXISTING GROUND RODS IN THE 3314 HANDHOLE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PLATE, JUNCTION | 3 | -- | -- | -- |
| 2 | WIRE, BARE COPPER, #2, STR. SOFT DRAWN | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 3 | CONNECTOR, COPPER, SIZE | AS REQ'D | -- | -- | -- |
| 4 | CONNECTOR, SERVICE POST | AS REQ'D | -- | S262560 | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GROUNDING PAD MOUNTED EQUIPMENT
JUNCTION PLATE

UG4520.7

**SCOPE:** THIS STANDARD SHOWS THE GROUNDING INSTALLATION USED TO PROVIDE TRAYER PAD MOUNTED EQUIPMENT GROUNDING.





**FIGURE 1**





**FIGURE 2**
NEUTRAL AND GROUND SCHEMATIC FOR 4-WAY MANUAL,
4-WAY SCADA, AND 5-WAY SCADA TRAYER PAD MOUNTED SWITCHES.
600A / 200A JUNCTION

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4520 | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GROUNDING TRAYER PAD MOUNTED EQUIPMENT

SHEET 1 OF 2

UG4521.1

TABLE OF CONTENTS

## INSTALLATION:

(A) CONCENTRIC NEUTRAL TAILS OR EQUIVALENT WIRE SIZE PER PHASE. (g)

(B) GROUND SOURCE MAY BE TRENCH GROUND OR GROUND FROM SUB-STRUCTURE.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | STRAND, #14 SOLID CU OR CONCENTRIC NEUTRAL SURPLUS | AS REQ'D | -- | -- | -- |
| 2 | WIRE, BARE COPPER, SOFT-DRAWN, #2, 7 STR. (f) | AS REQ'D | -- | S812818 (X) | GDWIRE |
| 3 | WIRE, BARE COPPER, SOFT-DRAWN, 1/0 STR. (I) (f) | AS REQ'D | -- | S812752 | -- |
| 4 | WIRE, BARE COPPER, SOFT-DRAWN, 4/0 STR. (f) | AS REQ'D | -- | S812764 | 4/0-SD |
| 5 | CONNECTOR, COMPRESSION, 4/0 - #4 | AS REQ'D | -- | S257888 | -- |
| 6 | CONNECTOR, COMPRESSION, 4/0 - 1/0 | AS REQ'D | -- | S257856 | -- |
| 7 | CONNECTOR, COMPRESSION, 4/0 - 4/0 | AS REQ'D | -- | S257824 | -- |
| 8 | CONNECTOR, SERVICE POST | AS REQ'D | -- | S262560 | -- |
| 9 | SWITCH, TRAYER | AS REQ'D | -- | -- | -- |
| 10 | EYE BOLT, STAINLESS STEEL, 6" X 1/2" | 1 | -- | S150528 | -- |
| 11 | BRACKET, STAINLESS STEEL, 2" X 3" | 2 | -- | S166072 | -- |
| 12 | BOLT, STAINLESS, 3 1/2" X 1/2" | 4 | -- | S148804 | -- |
| 13 | WIRE, TRENCH GROUND (I) | AS REQ'D | -- | -- | -- |
| 14 | EYE BOLT, STAINLESS STEEL, 1 1/2" X 1/2" | 1 | -- | S152722 (X) | -- |

## NOTES:

(I) NOT SHOWN ON FIGURES

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) SEE UG4108 FOR SEALING JACKETED CABLE.

b. SEE UG4510 FOR STANDARD AND ALTERNATE TRENCH GROUND WIRE INSTALLATION.

c. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

(d) SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

e. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

(f) SEE UG4003 (PREVIOUS # UG4002.2) FOR WIRE INFORMATION.

(g) SEE UG4176 FOR EQUIVALENT WIRE SIZE.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | MOVED FROM UG4520 | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | SL | JS | CZH | 9/4/2018 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | - | 5/20/2015 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS THE CONCENTRIC NEUTRAL TERMINATION AND THE GROUNDING OF PREMOLDED AND STRESS RELIEF CONNECTORS.





**FIGURE 1**
BUSHING PLUG AND
INSULATING RECEPTACLE





**FIGURE 2**





**FIGURE 3**
CABLE TERMINATION







**FIGURE 4**
STRESS RELIEF KIT FOR
EXISTING FACILITIES
200A AND 600A CABLE




EXAMPLE 1
LIVEFRONT SWITCH
GEAR APPLICATION




EXAMPLE 2
CABLE POLE
APPLICATION

**FIGURE 5**
200A & 600A CABLE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | REVISION | - | - | PSW | RDG | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONCENTRIC NEUTRAL TERMINATIONS AND
GROUNDING PREMOLDED CONNECTORS




UG4525.1

TABLE OF CONTENTS




**DETAIL 1**




**DETAIL 2**

## INSTALLATION:

(A) GROUND EACH PREMOLDED CONNECTOR ON OR IN THE GROUNDING POINT PROVIDED ON CONNECTOR. GROUND STRESS RELIEF KIT PER MANUFACTURER'S INSTALLATION INSTRUCTIONS. ONLY ONE GROUND FOR EACH CONNECTOR OR STRESS RELIEF KIT IS REQUIRED. USE A PIECE OF NO. 14 SOLID COPPER WIRE (STOCK NO. S812934) OR A SURPLUS STRAND OF CONCENTRIC NEUTRAL TAIL. DO NOT USE ANY CONCENTRIC NEUTRAL STRANDS ATTACHED TO THE CABLE UNLESS THE CABLE IS 2/0 OR 2 SOLID TRIPLEXED.

(B) ON PREMOLDED CONNECTORS MAKE A SMALL LOOP THRU THE GROUNDING EYE AND TWIST THE WIRE TIGHTLY AROUND ITSELF TAKING CARE NOT TO DAMAGE THE EYE.

(C) ON PREMOLDED CONNECTORS OR STRESS RELIEF KIT, WRAP THE WIRE AROUND THE CONCENTRIC NEUTRAL TAIL (WHEN TAIL IS AVAILABLE), OR TAKE THE WIRE DIRECTLY TO A COMPRESSION CONNECTOR OR TO THE BUSHING WELL TAB USE TO SECURE BAILING ASSEMBLIES. THE GROUND WIRE MAY LOOP FROM ONE CONNECTOR TO ANOTHER WHEN CONNECTORS ARE ASSEMBLED TOGETHER. THIS WILL ENSURE POSITIVE ELECTRICAL CONNECTIONS TO EACH END FOR GROUND RELIABILITY.

(D) ON LOADBREAK EQUIPMENT, LEAVE ENOUGH SLACK IN THE GROUNDING LEAD OR CONCENTRIC NEUTRAL TAIL FOR HOTSTICK OPERATION.

(E) CONNECTORS WITH BAILING ASSEMBLIES SHALL BE GROUNDED THE SAME AS DESCRIBED IN NOTE A IF A GROUNDING POINT IS PROVIDED ON CONNECTOR.

(F) WHEN INSTALLING STRESS RELIEF KITS IN EXISTING LIVEFRONT EQUIPMENT, INSTALL THE CONCENTRIC NEUTRAL AT THE SAME HEIGHT AS EXISTING CABLES AND DELETE THE 5-INCH MEASUREMENT.

**BILL OF MATERIALS:** NONE

## NOTES:

I. GROUND ANY BUSHING PLUGS SUPPLIED WITH TRANSFORMERS, SWITCH CABINETS, ETC.

II. ALL CONCENTRIC NEUTRAL STRANDS ON ANY CABLE EVER PURCHASED BY SDG&E ARE NO. 14 OR LARGER.

## REFERENCE:

(a) SEE UG4108 INSTRUCTIONS FOR SEALING JACKETED CABLE.

(b) SEE UG4122 FOR INDOOR CABLE TERMINATION, POLYETHYLENE CABLE.

c. SEE UG4176 FOR CONCENTRIC NEUTRAL SIZES.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | REVISION | - | - | PSW | RDG | 1/1/1996 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS

UG4525.2

**SCOPE:** THIS STANDARD SHOWS SCHEMATIC DIAGRAMS FOR THE NEUTRAL AND GROUND WIRE USED FOR UNDERGROUND TERMINATIONS.





**FIGURE 1**
600A TEES OR 600A LUGS
PMH 5 SWITCH
SERVICE RESTORER





**FIGURE 2**
600A 4-WAY SWITCH, SUBSURFACE OR PAD MOUNTED
600A PMH OR PME 3, 5, 9, 10, 11 SWITCH, PAD MOUNTED
600A 3, 4, & 6 WAY VISTA

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | REVISION | - | - | - | RDW/VCR | 3/1/2002 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1991 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

NEUTRAL AND GROUND WIRE
SCHEMATIC DIAGRAM



UG4530.1

TABLE OF CONTENTS





**FIGURE 3**
600A ON-OFF SWITCH, SUBSURFACE
600A PAD MOUNTED PMH 5 AIR BREAK SECTIONALIZING SWITCH

## INSTALLATION:

A. WHEN THREE SETS OF TEES ARE REQUIRED FOR THE ON/OFF SWITCH, USE FIGURE 2.

**BILL OF MATERIALS:** NONE

## NOTES:

(I) CONCENTRIC WIRE OR #2 FOR 350 KCMIL PER PHASE.

(II) CONCENTRIC WIRE OR 1/0 FOR 750 OR 1000 KCMIL PER PHASE.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 06/18/2021 | F | | | | | | |
| B | REVISION | - | - | - | RDW/VCR | 3/1/2002 | E | | | | | | |
| A | REVISION | - | - | - | JLB/RDJ | 1/1/1991 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM

UG4530.2

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATION USED TO PROVIDE GROUNDING FOR 200A CONNECTORS IN A 3313 HANDHOLE. USE THIS METHOD IF ALL PARTIES CANNOT MEET THE STANDARD TRENCH GROUND WIRE METHOD. (e)




METHOD 1




METHOD 2

**FIGURE 1**
METHOD FOR GROUNDING USING GROUNDING RODS (d)





**FIGURE 2**
GROUND INSTALLATION BEFORE HANDHOLE IS SET





**FIGURE 3**
PLAN VIEW





**FIGURE 3**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

## INSTALLATION:

(A) LEAVE 24 INCHES OF WIRE (EXPOSED TAILOUT) ABOVE THE TOP OF FINAL GRADE.

(B) INSTALL HANDHOLE GROUND AS SHOWN IN FIGURES.

(C) INSTALL STANDARD OR ALTERNATE TRENCH GROUND WIRE WHEN THE SAME PARTY IS RESPONSIBLE FOR THE CONDUIT AND HANDHOLE INSTALLATION. (a)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO |
|---|---|---|---|---|---|---|
| 1 | WIRE, BARE COPPER, #2, 7 STRAND, SOFT DRAWN | AS REQ'D | 4003 | S812818 (X) | GDWIRE | G3313R |
| 2 | GROUND ROD, COPPERWELD, 5/8" X 8'-0" | 2 | -- | S603074 (X) | -- | |
| 3 | GROUND, BONDED, COPPER, CONNECTED | 2 | -- | S259010 | -- | |
| 4 | CONNECTOR, COMPRESSION | AS REQ'D | 4174.1 | S257856 | -- | |
| 5 | CONNECTOR GROUND, PROVIDED WITH CABLE TAP | -- | -- | -- | -- | |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) SEE UG4510 FOR STANDARD AND ALTERNATE TRENCH GROUND WIRE.

b. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

(c) SEE UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART AND COPPER COMPRESSION CONNECTORS.

(d) SEE UG4510 FOR ALTERNATIVE TRENCH GROUND WIRE METHOD.

(e) SEE UG4510 FOR STANDARD TRENCH GROUND WIRE METHOD.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATION USED TO PROVIDE GROUNDING FOR ALL 200A CONNECTORS IN A 3314 HANDHOLE.






**FIGURE 1**
3314




**DETAIL 1**

## INSTALLATION:

A. INSTALL HANDHOLE GROUND AS SHOWN IN FIGURE 1.

(B) WHEN EQUIPMENT ON OPPOSITE WALL REQUIRES GROUNDING, INSTALL ONE CONTINUOUS WIRE AROUND THE HANDHOLE AND CONNECT THE GROUND WIRE AS SHOWN IN FIGURE 1, OTHERWISE ONLY INSTALL THE GROUND WIRE SHOWN AS A SOLID LINE IN FIGURE 1.

(C) INSTALL THE GROUND WIRE AT THE SAME LEVEL AS THE CONCENTRIC NEUTRAL TERMINATIONS ON THE CABLE.

(D) FOR CONCENTRIC NEUTRAL TAILS OR EQUIVALENT WIRE SIZE PER PHASE, SEE UG4176 FOR EQUIVALENT WIRE SIZE. (b)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | WIRE, BARE COPPER, #2, 7 STRAND, SOFT DRAWN | AS REQ'D | 4003 | S812818 (X) | -- |
| 2 | BRACKET, STAINLESS STEEL, 2" X 3" | AS REQ'D | -- | S166072 | -- |
| 3 | ANCHOR, CONCRETE, STAINLESS STEEL, 1/2" X 3 3/4" | AS REQ'D | 4177 | S107654 | -- |
| 4 | CONNECTOR, COMPRESSION | AS REQ'D | 4174.1 | S257760 | -- |
| 5 | CONNECTOR, SERVICE POST | 2 | -- | S262560 | -- |
| 6 | CONNECTOR, GROUND, PROVIDED WITH CABLE TAP | -- | -- | -- | -- |
| 7 | EYE BOLT, STAINLESS STEEL, 1/2" X 6" | AS REQ'D | -- | S150528 | -- |
| 8 | EYE BOLT, STAINLESS STEEL, 1/2" X 1 1/2" | AS REQ'D | -- | S152722 (X) | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

(b) SEE UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART AND COPPER COMPRESSION CONNECTORS.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATION USED TO PROVIDE GROUNDING FOR ALL 200A AND 600A CONNECTORS IN A 3315 HANDHOLE.






**FIGURE 1**
3315




**DETAIL 1**





**FIGURE 2**
3315

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

## INSTALLATION:

A. INSTALL HANDHOLE GROUND AS SHOWN IN FIGURES.

(B) WHEN EQUIPMENT ON OPPOSITE WALL REQUIRES GROUNDING, INSTALL ONE CONTINUOUS WIRE AROUND THE HANDHOLE AND CONNECT THE GROUND WIRE AS SHOWN IN FIGURES, OTHERWISE ONLY INSTALL THE GROUND WIRE SHOWN AS A SOLID LINE IN FIGURES.

(C) INSTALL THE GROUND WIRE AT THE SAME LEVEL AS THE CONCENTRIC NEUTRAL TERMINATIONS ON THE CABLE.

(D) FOR CONCENTRIC NEUTRAL TAILS OR EQUIVALENT WIRE SIZE PER PHASE, SEE UG4176 FOR CHART AND EQUIVALENT WIRE SIZE.(a)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | WIRE, BARE COPPER, #2, 7 STRAND, SOFT DRAWN | AS REQ'D | 4003 | S812818 (X) | -- |
| 2 | BRACKET, STAINLESS STEEL, 2" X 3" | AS REQ'D | -- | S166072 | -- |
| 3 | ANCHOR, CONCRETE, STAINLESS STEEL, 1/2" X 3 3/4" | AS REQ'D | 4177 | S107654 | -- |
| 4 | CONNECTOR, COMPRESSION | AS REQ'D | 4174.1 | S257760 | -- |
| 5 | CONNECTOR, SERVICE POST | 2 | -- | S262560 | -- |
| 6 | CONNECTOR, GROUND, PROVIDED WITH CABLE TAP | -- | -- | -- | -- |
| 7 | EYE BOLT, STAINLESS STEEL, 1/2" X 6" | AS REQ'D | -- | S150528 | -- |
| 8 | EYE BOLT, STAINLESS STEEL, 1/2" X 1 1/2" | AS REQ'D | -- | S152722 (X) | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) SEE UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART AND COPPER COMPRESSION CONNECTORS.

b. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

(c) SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATION USED TO PROVIDE GROUNDING FOR ALL 200A AND 600A CONNECTORS IN A 3316 HANDHOLE.






**FIGURE 1**
3316




**DETAIL 1**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

## INSTALLATION:

A. INSTALL HANDHOLE GROUND AS SHOWN IN FIGURE 1.

(B) WHEN EQUIPMENT ON OPPOSITE WALL REQUIRES GROUNDING, INSTALL ONE CONTINUOUS WIRE AROUND THE HANDHOLE AND CONNECT THE GROUND WIRE AS SHOWN IN FIGURE 1, OTHERWISE ONLY INSTALL THE GROUND WIRE SHOWN AS A SOLID LINE IN FIGURE 1.

(C) INSTALL THE GROUND WIRE AT THE SAME LEVEL AS THE CONCENTRIC NEUTRAL TERMINATIONS ON THE CABLE.

(D) FOR CONCENTRIC NEUTRAL TAILS OR EQUIVALENT WIRE SIZE PER PHASE, SEE UG4176 FOR EQUIVALENT WIRE SIZE. (b)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | WIRE, BARE COPPER, #2, 7 STRAND, SOFT DRAWN | AS REQ'D | 4003 | S812818 (X) | -- |
| 2 | BRACKET, STAINLESS STEEL, 2" X 3" | AS REQ'D | 4505 | S166072 | -- |
| 3 | ANCHOR, CONCRETE, STAINLESS STEEL, 1/2" X 3 3/4" | AS REQ'D | 4177 | S107654 | -- |
| 4 | CONNECTOR, COMPRESSION | AS REQ'D | 4174.1 | S257760 | -- |
| 5 | CONNECTOR, SERVICE POST | 2 | -- | S262560 | -- |
| 6 | CONNECTOR, GROUND, PROVIDED WITH CABLE TAP | -- | -- | -- | -- |
| 7 | EYE BOLT, STAINLESS STEEL, 1/2" X 6" | AS REQ'D | -- | S150528 | -- |
| 8 | EYE BOLT, STAINLESS STEEL, 1/2" X 1 1/2" | AS REQ'D | -- | S152722 (X) | -- |

## NOTES:

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

(b) SEE UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART AND COPPER COMPRESSION CONNECTORS.

(c) SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS GROUNDING INSTALLATION USED TO PROVIDE GROUNDING FOR THE SWITCH AND CONNECTORS IN THE 3317 HANDHOLE.





**FIGURE 1**
3317

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |



TABLE OF CONTENTS

## INSTALLATION:

A. INSTALL HANDHOLE GROUND AS SHOWN IN FIGURE 1.

B. INSTALL GROUND WIRE 1 1/2" (38mm) BELOW STEEL GRATING ELBOW TO PROVIDE CLEARANCE FROM SUPPORT HARDWARE.

C. FOR CONCENTRIC NEUTRAL TAILS OR EQUIVALENT WIRE SIZE PER PHASE, SEE UG4176 FOR EQUIVALENT WIRE SIZE. (b)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | WIRE, BARE COPPER, #2, 7 STRAND, SOFT DRAWN | AS REQ'D | 4003 | S812818 (X) | -- |
| 2 | BRACKET, STAINLESS STEEL, 2" X 3" | AS REQ'D | -- | S166072 | -- |
| 3 | ANCHOR, CONCRETE, STAINLESS STEEL, 1/2" X 3 3/4" (I) | AS REQ'D | 4177 | S107654 | -- |
| 4 | CONNECTOR, COMPRESSION | AS REQ'D | 4174.1 | S257760 | -- |
| 5 | CONNECTOR, SERVICE POST | 2 | -- | S262560 | -- |
| 6 | LUG, GROUND, PROVIDED BY SWITCH MANUFACTURER | -- | -- | -- | -- |
| 7 | EYE BOLT, STAINLESS STEEL, 1/2" X 6" | AS REQ'D | -- | S150528 | -- |
| 8 | WIRE, BARE COPPER, 4/0 STRANDED | AS REQ'D | -- | S812764 | -- |
| 9 | EYE BOLT, STAINLESS STEEL, 1/2" X 1 1/2" (I) | AS REQ'D | -- | S152722 (X) | -- |

## NOTES:

(I) NOT SHOWN ON FIGURE.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. SEE UG4525 FOR CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

(b) SEE UG4176 FOR CONCENTRIC NEUTRAL/COMPRESSION CONNECTOR APPLICATION CHART AND COPPER COMPRESSION CONNECTORS.

c. SEE UG4530 FOR NEUTRAL AND GROUND WIRE SCHEMATIC DIAGRAM.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JS | TR | MDJ | 6/14/2016 | D | | | | | | |

**SCOPE:** THIS STANDARD DESCRIBES CONNECTION TO TELCO GROUND, IF PRESENT.

**TABLE 1**

| HANDHOLE DIMENSIONS | |
|---|---|
| **HANDHOLE** | **Z (IN)** |
| 3314 | 18 |
| 3315 | 16 |
| 3316 | 16 |





**FIGURE 1**
END VIEW OF HANDHOLE

## INSTALLATION:

(A) OPEN HANDHOLE AND MAKE SURE THERE IS NO EQUIPMENT AT THE DRILLING LOCATION.

(B) DRILL A 1/2-INCH HOLE IN THE END AT ONE OF THE LOCATIONS SHOWN IN FIGURE 1 TO AVOID REBAR.

C. TAKE THE #6 AWG INSULATED COPPER GROUND WIRE FURNISHED BY PT&T AND PUT THROUGH THE HOLE AND INTO THE HANDHOLE.

D. FILL THE DRILLED HOLE WITH EPOXY PUTTY (SEALING COMPOUND). SEE BILL OF MATERIALS ITEM #1.

E. SKIN THE INSULATION AND CONNECT TO THE GROUND OR NEUTRAL WIRE IN THE HANDHOLE WITH A COPPER COMPRESSION CONNECTOR. IF NO GROUND WIRE IS AVAILABLE, ATTACH TO GROUND ROD.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | SEALING COMPOUND (III) | -- | -- | S442976 | -- |

## NOTES:

I. IF TELCO GROUND WIRE IS PRESENT AT THE TIME OF INSTALLATION OF THE HANDHOLE, INSERT GROUND WIRE TAIL BETWEEN PAD AND TOP SECTION OR HANDHOLE SECTIONS THROUGH THE GROUT OR PLASTIC MASTIC SEALANT.

II. GROUNDING OF TELCO CONDUCTORS MUST BE AUTHORIZED ON INDIVIDUAL CONSTRUCTION ORDERS FOR BOTH NEW AND EXISTING HANDHOLES.

(III) NOT SHOWN IN FIGURE.

## REFERENCE:

a. SEE UG4174 FOR COPPER COMPRESSION CONNECTORS.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 06/18/2021 | E | | | | | | |
| A | EDITORIAL CHANGES | - | JC | TR | JS/MDJ | 7/28/2015 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GROUNDING TELCO CONDUCTOR IN HANDHOLE
3314, 3315, OR 3316



UG4550.1

MAIN TABLE OF CONTENTS


| PAGE | SUBJECT |
|---|---|
| 4620 | TELECOMMUNICATIONS CONDUIT RISER & TRENCH |
| 4621 | HANDHOLE INSTALLATION FOR LOCATING STATIONS FOR FIBER OPTIC CABLE |
| 4622 | TRACER WIRE TERMINATION ON RISER POLES |
| 4623 | TELECOMMUNICATIONS FIBER OPTIC RISER POLE |
| 4624 | 4-INCH CONDUIT, BENDS AND SWEEPS FOR FIBER OPTIC AND TELECOMMUNICATIONS CABLE |
| 4625 | POLYETHYLENE INNERDUCT AND CABLE SLEEVE |
| 4626 | FIBER OPTIC CABLE INSTALLATION |
| 4630 | LTE ANTENNA STAND ALONE/DISTRIBUTION STEEL POLE |
| 4640 | PAD MOUNTED VISTA SCADA INSTALLATION |
| 4641 | SCADA INSTALLATION FOR PAD MOUNTED SWITCHES |
| 4642 | SUB-SURFACE VISTA INSTALLATION |
| 4643 | DRY VAULT SCADA INSTALLATION |
| 4644 | DIRECT BURIED ANTENNA FIBERGLASS POLES |
| 4645 | ANTENNA POLE WITH ANTENNA |
| 4646 | ANTENNA POLE (49 FOOT) |
| 4647 | ANTENNA POLE W/LUMINAIRES |
| 4648 | CELL RELAY/RFLAN RANGE EXTENDER ATTACHMENT TO DISTRIBUTION POLE |
| 4649 | CUSTOMER-OWNED WIRELESS COMMUNICATIONS PROVIDER ATTACHMENT TO DISTRIBUTION POLE (UNMETERED SERVICE) |
| 4650 | CUSTOMER-OWNED WIRELESS COMMUNICATIONS PROVIDER ATTACHMENT TO DISTRIBUTION POLE (METERED SERVICE) |
| 4651 | WEATHER MONITORING SYSTEM |
| 4653 | UNMETERED ELECTRIC SERVICE FOR WIRELESS COMMUNICATIONS PROVIDER |
| 4660 | CUSTOMER-OWNED WIRELESS COMMUNICATIONS PROVIDER ATTACHMENT TO DISTRIBUTION STREET LIGHT POLES (UNMETERED SERVICE) |
| 4661 | STREET LIGHT WITH 5G ATTACHMENT |


THIS SECTION HAS BEEN REMOVED FROM THE EXTERNAL VERSION. DUE TO CONFIDENTIAL INFORMATION.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| E | EDITORIAL CHANGES | - | ADW | JES | CZH | 12/9/2019 | H | DRAWING UPDATE | ARC | ADW | GLW | KRG | 02/16/2023 |
| D | ADDED 4649 | - | JK | JS | CZH | 6/9/2019 | G | ADDED UG4630 | EDM | GLW | JES | CZH | 2/8/2021 |
| C | EDITORIAL CHANGES | - | JK | JS | CZH | 5/18/2018 | F | EDITORIAL CHANGES | EDM | JIK | JES | CZH | 3/5/2020 |

# 4700 - PRIMARY METER/ REGULATOR/ BOOSTER STATION

# 4700 - PRIMARY METER/ REGULATOR/ BOOSTER STATION

| PAGE | SUBJECT |
|---|---|
| 4705 | 12KV SERVICE POINT CONNECTION FOR TROLLEY TRACTION STATION |
| 4710 | INSTALLATION OF PAD MOUNTED REGULATOR |
| 4711 | PAD MOUNTED AUTO TRANSFORMER OR BOOSTER |
| 4712 | GRIDCO PAD MOUNTED POWER REGULATOR IPR50 |
| 4713 | INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1" |
| 4714 | INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR |
| 4720 | ENERGY STORAGE INTERCONNECTION |

MAIN TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | JK | JS | CZH | 05/18/2018 | F | | | | | | |
| B | ADDED 4712.1-6 & 4712.7-.12 | - | KR | JS | MDJ | 12/01/2017 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ADDED SECTION 4712 | - | JBH | TR | MDJ | 04/15/2016 | D | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

MISCELLANEOUS EQUIPMENT
TABLE OF CONTENTS

UG4701.1

**SCOPE:** THIS STANDARD PROVIDES GUIDELINES FOR THE CONNECTION OF SDG&E'S 12KV DISTRIBUTION SYSTEM TO A PRIMARY METERED SERVICE POINT FOR THE 600V DC TROLLEY SYSTEM.




**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. THE FOLLOWING REQUIREMENTS SHALL BE MET WHEN MAKING THIS CONNECTION:

a. SDG&E SHALL LOCATE IT'S SUBSTRUCTURE AS CLOSE AS PRACTICABLE TO THE CUSTOMER'S GROUND GRID BUT IN NO CASE SHALL THE SUBSTRUCTURE BE IN CONTACT WITH THE CUSTOMER'S GROUND GRID (GROUNDING ELECTRODE SYSTEM).

b. THE CONCENTRIC NEUTRALS FROM SDG&E'S CABLE SHALL NOT BE CONNECTED TO THE CUSTOMER'S EQUIPMENT.

c. THE CABLE TERMINATION IN THE CUSTOMER'S SWITCHGEAR CABINET SHALL BE A LIVEFRONT DELTA CONNECTION.

**REFERENCE:**

a. SEE SG609.

b. SEE SERVICE PLANNING MANUAL 254.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | REVISION | - | - | - | WT/MC | 02/08/2010 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

12KV SERVICE POINT CONNECTION FOR TROLLEY TRACTION STATION

SHEET 1 OF 1

UG4705.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE 600A PAD MOUNTED REGULATORS.

**ATTENTION:**

* THE PAD MOUNTED REGULATORS MAY BE INSTALLED IN TWO APPLICATIONS: OVERHEAD CONSTRUCTION REQUIRING 600A VOLTAGE REGULATION, SEE SHEET 4, AND FULL UNDERGROUND CIRCUITS REQUIRING 600A VOLTAGE REGULATION, SEE SHEET 6.





**FIGURE 1**
SIDE VIEW
SEE TABLE 1






**FIGURE 1**
FRONT VIEW
SEE TABLE 1



**DETAIL 1**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |



TABLE OF CONTENTS

TABLE OF CONTENTS

## TABLE 1 (FIGURE 1)

| PAD MOUNTED REGULATOR DESCRIPTION LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | BUSHING, INTEGRAL APPARATUS, HIGH VOLTAGE |
| 2 | BOXOUT, TANK, FOR HV BUSHINGS |
| 3 | BASE, REGULATOR, TANK W/ JACKING AND ROLLING FACILITIES |
| 4 | LIFTING LUGS |
| 5 | BOLTED COVER W/ NUT GUARD |
| 6 | PRESS CONN. & FILL PLUG, 1, 0" UPPER FILTER |
| 7 | VALVE, DRAIN, 1, 0", W/ SAMPLER |
| 8 | DEVICE, AUTO PRESS RELIEF |
| 9 | PRESSURE VACUUM GAUGE PROVISION |
| 10 | GAUGE, MAGNETIC OIL LEVEL |
| 11 | GAUGE, OIL SIGHT |
| 12 | INDICATOR, TAP CHANGER POSITION, W/ DRAGHANDS AND REGULATION RANGE LIMIT SWITCHES |
| 13 | THERMOMETER PROVISION |
| 14 | PLATE, STEEL DIVIDER |
| 15 | REMOVABLE SILL |
| 16 | PAD, GROUND, W/ 2 - 1/2-13 UNC TAPPED HOLES 7/16 DEEP |
| 17 | NAMEPLATE |
| 18 | PARKING STAND |
| 19 | CABINET, BOLTED HIGH SECURITY, W/ PENTAHEAD DOOR BOLTS |
| 20 | ENCLOSURE, CONTROL, LOCKABLE ON INSIDE OF CABINET DOOR |
| 21 | CORRUGATION, COOLING (WHEN REQUIRED) |
| 22 | BUSHING, NEUTRAL/CONCENTRIC GROUND |
| 23 | DOOR HANDLE |
| 24 | CONCENTRIC NEUTRAL/NEUTRAL GROUND STRAP |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

TABLE OF CONTENTS





**FIGURE 2**
CABLE CONNECTION DIAGRAM

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED REGULATOR

UG4710.3





**FIGURE 3**
CONDUIT/SUBSTRUCTURE/PAD/COMMUNICATION/GROUND
INSTALLATION DIAGRAM
PLAN VIEW





**FIGURE 3**
CONDUIT/SUBSTRUCTURE/PAD/COMMUNICATION/GROUND
INSTALLATION DIAGRAM
VIEW A-A

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



INSTALLATION OF PAD MOUNTED REGULATOR

UG4710.4

TABLE OF CONTENTS





**FIGURE 4**
CONDUIT DIAGRAM FOR PME AND PAD MOUNTED REGULATORS





**FIGURE 5** (a)
BOX AND CONDUIT PLACEMENT
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



TABLE OF CONTENTS

## INSTALLATION:

(A) SLURRY ENCASE ALL 3-INCH CONDUITS.

(B) SLURRY ENCASE ALL 3-INCH 90 DEGREE BENDS TO WITHIN 6 INCHES OF THE FINAL CUT.

(C) DO NOT CUT THE 90 DEGREE BENDS.

(D) LOOP A 1-INCH POLYETHYLENE CONDUIT TO EACH PAD. STUB THE CONDUIT 4 FEET FROM THE EDGE OF PAD, CLOSEST TO TELCO, WHEN REQUIRED.

(E) IN SOFT SOILS A CONCRETE BACKFILL (1 SACK MIX.) IS REQUIRED UNDER THE PAD 12 INCHES BEYOND THE SIDE EDGES OF PAD AND 12 INCHES DEEP.

(F) INSTALL A TRENCH GROUND WIRE FOR EACH PAD. INSTALL A SEPARATE GROUND WIRE BETWEEN THE CENTER PAD AND EACH END PAD.

(G) ALL HORIZONTAL BENDS WILL BE MADE WITH ONLY LONG SWEEPS OF 25-FOOT RADIUS OR LONGER.

(H) SET 3313 ON 4 INCHES OF COMPACTED 1/2-INCH GRAVEL.

(J) NEUTRAL/GROUND STRAP FROM NEUTRAL BUSHING TO GROUND PAD.

(K) ATTACH TRENCH GROUND TO GROUND PADS AND CONCENTRIC NEUTRAL.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, 3426 | 3 | 3426 | S514005 | 3426B0 |
| 2 | BASE SECTION, 3313 | 3 | 3313 | S162664 | 3313B |
| 3 | 90 DEGREE BEND, 3" | 6 | 3373 | S322048 | S80-3" |
| 4 | CONDUIT, POLY, 1" | AS REQ'D | 3373 | S249630 | 1"PE |
| 5 | CONDUIT, 3" DB | AS REQ'D | 3373 | S249664 | 1DB3-P |
| 6 | SLURRY, 1-SACK | AS REQ'D | 3376 | S656400 | -- |
| 7 | WIRE, TRENCH GROUND | 3 | 4510 | -- | -- |
| 8 | CONNECTOR, COMPRESSION | AS REQ'D | 4174/4176 | -- | -- |
| 9 | PAD, GROUND W/ 2 - 1/2-13 UNC TAPPED HOLES 7/16 DEEP | AS REQ'D | -- | S262560 | -- |
| 10 | CONNECTOR, "T" TYPE, 600A | 6 | 4181 | -- | -- |
| 11 | REGULATOR, VOLTAGE, SINGLE-PHASE, PADMOUNT | 3 | -- | S581490 | REG600 |
| 12 | CONDUIT, 5", FOR UNDERGROUND BYPASS | AS REQ'D | 3373 | S249728 | 1DB5SL |
| 13 | BEND, 5", 90°, FOR UNDERGROUND BYPASS (I) | AS REQ'D | 3373 | S322112 | 1-5SLB |
| 14 | ENCASE/SLURRY/CONDUITS (I) | AS REQ'D | 3373 | -- | 1EB3IN |

## NOTES:

(I) NOT SHOWN ON FIGURES.

## REFERENCE:

(a) FOR INSTRUCTIONS ON INSTALLATION OF BOX PAD, SEE UG3423.

(b) FOR EQUIPMENT GROUNDING, SEE UG4520.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

**SCOPE:** THIS STANDARD SHOWS NEW CONSTRUCTION FOR MULTIPLE CONDUIT RISERS, USED WITH PAD MOUNTED REGULATOR.





**FIGURE 1** (II)





**FIGURE 1**
VIEW A-A





**FIGURE 1**
NEW MULTIPLE RISER CONSTRUCTION
VIEW B-B

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

**INSTALLATION:** NONE

**BILL OF MATERIALS:**

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CABLE, 1C-1000AL, FOR POLES AND PADMOUNT | AS REQ'D | -- | S197628 | -- |
| 2 | COUPLING, 3" (SIZE AS REQUIRED) | AS REQ'D | -- | S279904 | -- |
| 3 | CONDUIT RISER BEND, SCHEDULE 80, 3", 36" R (SIZE AS REQUIRED) | AS REQ'D | -- | S322472 | 3"CP-B |
| 4 | CONDUIT RISER, PVC, SCHEDULE 80, 3" (SIZE AS REQUIRED) | AS REQ'D | -- | S251552 | S80-3" |
| 5 | COUPLING, PVC, SCHEDULE 80, 3" | AS REQ'D | -- | S280544 | -- |
| 6 | COUPLING, PVC, SCHEDULE 40, 3" (SIZE AS REQUIRED) | AS REQ'D | -- | S280448 | -- |
| 7 | CONDUIT, PVC, SCHEDULE 40, 3" (SIZE AS REQUIRED) | AS REQ'D | -- | S251360 | S40-3" |
| 8 | IN LINE BY-PASS | 3 | 1218 | S707020 | ILD5W |
| 9 | GRIP, CABLE SIZE AS REQUIRED FOR PRIMARY RISERS (FOR 3" CONDUIT, 1/C-1000 AL CABLE) | AS REQ'D | -- | S394048 | 3G2#2A |
| 10 | PROTECTOR, NYLON CABLE | AS REQ'D | -- | S558720 | -- |
| 11 | BRACKET, LADDER ARM | AS REQ'D | -- | S167186 (X) | LA-ARM |
| 12 | CHANNEL, DOUBLE, GALV., 24 3/4" X 7/8" X 2 3/4" | AS REQ'D | -- | S216702 (X) | |
| 13 | NUT STUD 1/2" X 1 3/8" CLAMPING CHANNEL, W/SPRING | AS REQ'D | -- | S507000 | |
| 14 | BOLT, MACH, GALV., 5/8" X (LENGTH AS REQ'D), 1-SQUARE, WASHER & DOUBLE COIL SPRING WASHER | AS REQ'D | 390 | -- | -- |
| 15 | CLAMP, PIPE, STEEL, GALV., UNISTRUT, 3" | AS REQ'D | -- | S229632 | CL-3IN |
| 16 | CABLE POLE | -- | 4242 | -- | -- |
| 17 | CABLE POLE CONNECTION | -- | 4111 | -- | -- |

**NOTES:**

(I) LOCATE INLINE SWITCH NEXT TO SOURCE CABLE.

(II) SEE SHEETS 1-6 FOR REGULATOR INSTALLATION.

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

(a) SEE UG4204, FIGURE 3.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | TR | JDJ | 10/09/2007 | F | | | | | | |
| B | REVISION | - | - | TR | JDJ | 10/08/2007 | E | | | | | | |
| A | REVISION | - | - | TR | JDJ | 01/19/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE 'HHS' THREE-PHASE PAD MOUNTED AUTO TRANSFORMER OR BOOSTER FOR 12,000/6900 TO 12470/7200V. MANUFACTURED BY PARTNER TECHNOLOGIES INC.





**FIGURE 1**
SIDE VIEW





**FIGURE 1**
FRONT VIEW

## INSTALLATION:

A. PAY CLOSE ATTENTION IN CONDUIT INSTALLATION AND CABLE MAKE UP TO THE CORRECT CONNECTIONS WHEN INSTALLING THE AUTO TRANSFORMER. THE AUTO TRANSFORMER WILL BUCK OR BOOST 12KV SYSTEM VOLTAGE. SDG&E CURRENTLY USES THE BOOST FUNCTION OF THE TRANSFORMER.

B. THE TRANSFORMER IS A Y-TO-Y CONNECTION. FOR THE BOOST FUNCTION, THE X1, X2, X3 BUSHINGS ARE THE SOURCE SUPPLY SIDE OF THE TRANSFORMER, THE H1, H2, H3 BUSHINGS ARE THE LOAD SIDE AND HOXO BUSHING IS THE NEUTRAL CONNECTION FOR BOTH SOURCE AND LOAD SIDE OF THE TRANSFORMER.

C. THE BOOSTED APPLICATION FEEDS AREAS WITH 12470/7200 Y, YES, YIS, YSV, YP, YEP, YDP, YTP AND YDQ TRANSFORMERS.

**BILL OF MATERIALS:** NONE

## NOTES:

I. AVAILABLE IN TWO SIZES:

a. 3750KVA 600A WITH DEADBREAK CONNECTORS.

b. 1875KVA 200A WITH LOADBREAK CONNECTORS.

**REFERENCE:** NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 10/23/2012 | F | | | | | | |
| B | REVISION | - | - | - | TR/JDJ | 02/07/2007 | E | | | | | | |
| A | REVISION | - | - | - | TR/JDJ | 01/22/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

**SCOPE:** THIS STANDARD SHOWS REQUIREMENTS FOR INSTALLING A 3425 THREE-PHASE PAD FOR 3750, 1875KVA HHR DEADFRONT BOOSTER TRANSFORMER.





**FIGURE 1**
PAD





**FIGURE 2**
2-4" (200A CABLE)





**FIGURE 2**
2-5" (600A CABLE)





**FIGURE 3**

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 10/23/2012 | F | | | | | | |
| B | REVISION | - | - | - | TR/JDJ | 02/07/2007 | E | | | | | | |
| A | REVISION | - | - | - | TR/JDJ | 01/22/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |



TABLE OF CONTENTS

## INSTALLATION:

(A) SEAL CONDUITS WITH SEALING COMPOUND.

B. BASE OF CABINET SHALL BE CAULKED ONLY TO PREVENT POSSIBLE WIRE ENTRY.

(C) SET 3311 ON 4 INCHES OF COMPACTED 1/2 GRAVEL.

(D) KEYLESS LOCK TO BE ATTACHED TO LATCHING MECHANISM ON CABINET AND PENTAHEAD BOLT TO BE THREADED IN COMPLETELY.

(E) PLAN AND ORDER EARLY, MAY REQUIRE 20 WEEK LEAD TIME.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | WEIGHTS (LBS) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS | MACRO UNITS |
|---|---|---|---|---|---|---|---|
| 1 | HHR BOOSTER, 1875 KVA | (E) (I) | 1 | - | - | 200BST | - |
| | HHR BOOSTER, 3750 KVA | (E) (I) | | | S761324 | HS3750 | - |
| 2 | PAD, 3425 | 1,900 MAX. | 1 | - | S513998 | 3425-3 | 3425-M |
| 3 | HANDHOLE, 3311, 75" X 23" X 14" | (I) | 1 | 3311 | S162660 | 3311-S | |
| 4 | WIRE, TRENCH GROUND | (i) | AS REQ'D | 4510 | - | - | - |
| 5 | CONNECTORS, 600A | | AS REQ'D | 4181 | - | - | CC-P70, CC-P80, CC-P90 |
| | CONNECTORS, 200A | | | | - | - | CC--E3, CC--E5 |
| 6 | GROUNDING PAD MOUNTED EQUIPMENT | | - | 4520, 4530 | - | - | - |
| 7 | NUT, CLAMPING CHANNEL, W/SPRING, 1/2" | | 2 | - | S505520 | - | - |
| 8 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | | 2 | - | S616192 | - | - |
| 9 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | | 2 | - | S799488 | - | - |
| 10 | HOLD DOWN (SUPPLIED WITH CABINET) | | 2 | - | - | - | - |
| 11 | SEALING COMPOUND | (A) (I) | AS REQ'D | - | S442976 | - | - |
| 12 | KEYLESS LOCK | (D) (I) | 1 | - | S468010 | - | - |
| 13 | TAGS, CABLE IDENTIFICATION | (I) | AS REQ'D | 3202 | - | - | - |

## NOTES:

(I) NOT SHOWN ON FIGURES.

## REFERENCE:

a. SEE UG3211 FOR STRUCTURE/EQUIPMENT IDENTIFICATION TAG.

b. SEE UG3408 FOR WIRE ENTRY PREVENTION AND MOISTURE ENTRY.

c. SEE UG3425 FOR PAD AND HANDHOLE INSTALLATION.

d. SEE UG3479 FOR BARRIERS IF THE PAD IS SUBJECT TO VEHICULAR TRAFFIC.

e. SEE UG3480, UG3481, UG3482 AND UG3483 FOR MINIMUM OPERATING CLEARANCE REQUIREMENTS (PAD PLACEMENT).

f. SEE UG3484 FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT.

g. SEE UG3486, UG3487 AND UG3488 FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALLS.

h. SEE UG3489 FOR RETAINING WALLS.

(i) SEE UG4510 FOR PREFERRED I AND ALTERNATE TRENCH GROUND WIRE.

j. SEE UG4512 FOR EQUIPMENT GROUNDING INSTALLATION.

k. SEE UG4520 AND UG4521 FOR GROUNDING PAD MOUNTED EQUIPMENT.

l. SEE UG4525 FOR GROUNDING CONCENTRIC NEUTRAL TERMINATIONS AND GROUNDING PREMOLDED CONNECTORS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | REVISION | - | - | - | TR/MJC | 10/23/2012 | F | | | | | | |
| B | REVISION | - | - | - | TR/JDJ | 02/07/2007 | E | | | | | | |
| A | REVISION | - | - | - | TR/JDJ | 01/22/2007 | D | FORMATTING | EDM | JIK | - | - | 10/26/2021 |

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE GRIDCO IPR-50. THE GRIDCO IPR-50 IS A PAD MOUNTED SINGLE PHASE UNIT THAT CAN BE CONNECTED TO TRANSFORMERS UP TO 50KVA AT ANY PRIMARY VOLTAGE. THE IPR-50 PROVIDES CONTINUOUS, DYNAMIC AND PRECISE LOAD VOLTAGE REGULATION, REACTIVE POWER COMPENSATION AND HARMONIC CANCELLATION DURING FORWARD AND REVERSE POWER FLOW.

**ATTENTION:**

* THE IPR-50 CAN BE APPLIED TO TRANSFORMERS WHERE PV (SOLAR PLANTS) AND EV (ELECTRIC VEHICLE CHARGING) IS PRESENT, TO HELP MAINTAIN VOLTAGE AND POWER FACTOR LEVELS.

** THE IPR-50 IS WIRED TO THE SECONDARY SIDE OF A SINGLE PHASE TRANSFORMER 120/240V.





**FIGURE 1**
ISOMETRIC VIEW





**FIGURE 2**
FRONT VIEW





**FIGURE 3**
REAR VIEW





**FIGURE 4**
REAR VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |





**FIGURE 5**
XFMR
ISOMETRIC VIEW





**FIGURE 6**
GRIDCO IPR50
ISOMETRIC VIEW





**FIGURE 7**
INSTALLATION OF IPR
CONNECTED TO SECONDARY OF XFMR

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |





**FIGURE 8**
INSTALLATION OF IPR
CONNECTED IN SERIES OF SECONDARY





**FIGURE 9**
TOP VIEW





**FIGURE 9**
SIDE VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |


X Indicates Latest Revision | Completely Revised | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GRIDCO PAD MOUNTED POWER REGULATOR
IPR50

UG4712.3




**DETAIL 1**
BYPASS SWITCH




**DETAIL 2**

## INSTALLATION:

A. THE IPR IS DESIGNED TO CONNECT TO THE SECONDARY SIDE OF A DISTRIBUTION TRANSFORMER RATED FOR 50KVA OR LESS. THE MAXIMUM CURRENT LIMIT OF THE IPR IS 250A. IF THE CURRENT EXCEEDS 250A, THE IPR WILL AUTOMATICALLY GO TO BYPASS. WHEN THE CURRENT RETURNS BELOW 250A, THE UNIT WILL AUTOMATICALLY TRANSITION OUT OF BYPASS AND RETURN TO ACTIVE STATE.

B. WEIGHT APPROXIMATELY 355 POUNDS.

C. THE IPR UNIT MUST BE PROPERLY GROUNDED BEFORE ENERGIZING THE SYSTEM.

D. DE-ENERGIZE THE TRANSFORMER BEFORE CONNECTING THE IPR.

E. SOURCE BUSHINGS ARE LOCATED TO THE LEFT SIDE OF THE IPR DESIGNATED AS S1 AND S3. THE LOAD BUSHINGS ARE LOCATED ON THE RIGHT DESIGNATED AS L1 AND L3. FITS CONDUCTORS SIZED #4AWG TO 500MCM.

F. PRIOR TO ENERGIZING THE UNIT, THE BYPASS SWITCH SHOULD BE IN THE BYPASS POSITION. ONCE THE TRANSFORMER IS ENERGIZED, CHECK VOLTAGE ON THE SECONDARY SIDE. TURN BYPASS SWITCH TO "ON" AND CHECK SECONDARY VOLTAGE AGAIN AFTER GIVING THE POWER ELECTRONICS A MINUTE TO BECOME OPERATIONAL. THE SECONDARY VOLTAGE SHOULD BE REGULATED PER THE FACTORY PROGRAM CONFIGURATION, 240V.

**ONLY APPLIES TO IPR CONNECTED TO SECONDARY OF TRANSFORMER:**

G. INSTALL RED ISOLATION BOARD WITH BACKING NUTS TO X1/X3 BUSHINGS.

H. LAND 350MCM ON RIGHT SIDE SECONDARY Z BARS (SHOWN AS S1/S3). RUN BACK TO IPR IN CONDUIT. L1/L3 (350MCM FROM IPR) WILL LAND ON LEFT SIDE SECONDARY Z BARS. THIS WILL BE REGULATED VOLTAGE Z BARS.

J. RUN SECONDARY TO CUSTOMERS (SIZE AND QTY AS NEEDED) OFF LEFT SIDE (REGULATED) Z BARS.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | REGULATOR, IPR-50 | 1 | - | S581252 | UIPR50 |
| 2 | PAD, IPR-50 PAD | 1 | - | S514244 | IPRPAD |
| 3 | GROUND WIRE | AS REQ'D | 4510 | S812818 (X) | GDWIRE |
| 4 | LOCK, KEYLESS | 1 | 3711.3 | S468010 | - |
| 5 | SEALANT, CAULKING (VI) | AS REQ'D | - | S631800 | - |
| 6 | RED ISOLATION BOARD | 1 | - | - | - |
| 7 | SOURCE CABLE TO IPR-50 | AS REQ'D | - | - | - |
| 8 | NUT, CLAMPING CHANNEL | AS REQ'D | 3711.3 | S503520 | - |
| 9 | PAD, TRANSFORMER, 3421 | 1 | 3421 | S514240 | 3421-1 |
| 10 | SOURCE BUSHING, IPR-50 EYEBOLT | 2 | - | - | - |
| 11 | LOAD BUSHING, IPR-50 EYEBOLT | 2 | - | - | - |
| 12 | SL NEUTRAL AND GROUND BUSHINGS, IPR-50 | - | - | - | - |
| 13 | CONNECTIONS, SECONDARY, LINE TO IPR | AS REQ'D | 4167/4168 | - | - |
| 14 | CONNECTIONS, SECONDARY, IPR-50 LOAD & LOAD TO CUSTOMER(S) | AS REQ'D | - | - | - |
| 15 | LOAD CABLE FROM IPR-50 TO SECONDARY | AS REQ'D | - | - | - |

## NOTES:

I. VOLTAGE REGULATION UP TO ±10 PERCENT CONTINUOUS OF NOMINAL ±24V.

II. SOURCE VOLTAGE RANGE -55 PERCENT TO +25 PERCENT OF NOMINAL.

III. THE IPR IS A SERIES COMPONENT, THEREFORE IN BYPASS, UNREGULATED POWER WILL CONTINUE TO FLOW.

IV. THE IPR WILL PROTECT ITSELF FROM OVER CURRENT BY GOING INTO BYPASS. THERE IS A STATUS LIGHT LABELED "ACTIVE" LOCATED ON THE FRONT PANEL OF THE CONTROLLER. WHEN THE "ACTIVE" STATUS LIGHT IS ON, THE UNIT IS ACTIVELY REGULATING. WHEN THE STATUS LIGHT IS OFF, THE UNIT IS IN BYPASS.

V. THE UNIT IS AIR COOLED AND THE SURFACES OF THE IPR CAN EXCEED 100 DEGREES C. BE SURE TO TAKE APPROPRIATE PRECAUTIONS WHEN HANDLING THE DEVICE.

(VI) NOT SHOWN ON FIGURES.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

a. FOR WIRE ENTRY PREVENTION, SEE UG3408.

b. FOR CONDUIT SEALING, SEE UG3948 (G.O. 128 RULE 31.6).

c. FOR SLIP-FIT CONNECTORS, SEE UG4167 AND UG4168.

d. FOR INSTALLATION OF SINGLE PHASE "NTS" TRANSFORMER, SEE UG3711.3.

e. FOR CABLE IDENTIFICATION, SEE UG3202.

f. FOR TRANSFORMER IDENTIFICATION, SEE UG3212, UG3213, UG3214, UG3215, UG3216, UG3217 AND UG3218.

g. FOR PAD AND CONDUIT REQUIREMENTS, SEE UG3421.

h. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT), SEE UG3480, UG3481, UG3482, AND UG3483.

i. FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT, SEE UG3484.

j. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALL, SEE UG3486, UG3487, AND UG3488.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |



TABLE OF CONTENTS

**REFERENCE (CONT'D):**

k. FOR RETAINING WALLS, SEE UG3489.

l. FOR SEALING SERVICE LATERAL CONDUITS, SEE UG3948.

m. FOR (PREFERRED I) AND (ALTERNATE) TRENCH GROUND WIRE, SEE UG4510.

n. FOR (PREFERRED II) EQUIPMENT GROUNDING INSTALLATION, SEE UG4512.

o. FOR EQUIPMENT GROUNDING, SEE UG4512.

p. FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT, SEE UG4514.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

GRIDCO PAD MOUNTED POWER REGULATOR
IPR50

UG4712.6

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE GRIDCO PRT-50. THE GRIDCO PRT-50 IS A PAD MOUNTED, SINGLE PHASE TRANSFORMER THAT PROVIDES CONTINUOUS, DYNAMIC AND PRECISE LOAD VOLTAGE REGULATION, REACTIVE POWER COMPENSATION AND HARMONIC CANCELLATION DURING FORWARD AND REVERSE POWER FLOW.

**ATTENTION:**

* THE PRT-50 CAN BE USED IN PLACE OF STANDARD SINGLE PHASE TRANSFORMERS WHERE PV (PHOTO VOLTAIC) AND EV (ELECTRICAL VEHICLE CHARGING) IS PRESENT TO HELP MAINTAIN VOLTAGE AND POWER FACTOR LEVELS.




**FIGURE 1**
PRT-50

**INSTALLATION:**

(A) LOAD VOLTAGE REGULATION RANGE IS +/- 10 PERCENT AT 208A AT 100 PERCENT CAPACITY.





**FIGURE 2** (A)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(B) CLEARANCE TO ACCESS THE POWER ELECTRONICS REQUIRES A MINIMUM OF 20.5 TO 24.5 INCHES FROM BASE OF UNIT TO FULLY OPEN, DEPENDING ON ALIGNMENT ON THE PAD. FIGURE 3 SIDE VIEW, SHOWN CENTERED ON PAD.





**FIGURE 3** (B)
SIDE VIEW





**FIGURE 3**
BACK VIEW

(C) CUSTOM LIFTING BRACKETS HAVE BEEN SUPPLIED DUE TO THE SHIFT OF BALANCE WITH THE ADDITION OF THE INLINE POWER REGULATOR. TURN LIFTING BRACKETS UPSIDE DOWN AFTER INSTALLATION.



**FIGURE 4** (C)





**FIGURE 4**
ISOMETRIC VIEW (C)

D. TERMINATE PRIMARY AND SECONDARY CONDUITS FLUSH WITH TOP OF PAD. SEAL SECONDARY AND PRIMARY CONDUITS WITH SEALING COMPOUND OR EQUIVALENT. SEAL SERVICE LATERAL CONDUITS. (b)

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |

## INSTALLATION (CONT'D):

(E) BYPASS SWITCH CONTAINS THE FOLLOWING SETTINGS:

1. ON: THE INTEGRATED INLINE POWER REGULATOR IS ACTIVELY REGULATING GRID POWER FLOW.
2. OFF: POWER TO DOOR AND INTEGRATED POWER ELECTRONICS IS OFF DURING WHICH TIME THE SYSTEM IS IN PASS-THROUGH MODE ALLOWING GRID POWER TO PASS THROUGH WITHOUT REGULATING.
3. BYPASS: THE INTEGRATED INLINE POWER REGULATOR IS POWERED ALLOWING MANAGEMENT OF THE DEVICE HOWEVER GRID POWER IS DETOURED AROUND THE ELECTRONICS AND THE UNIT IS NOT REGULATING.




**FIGURE 5**
BYPASS SWITCH (E)

(F) PRIOR TO CONNECTING SECONDARIES, CHECK THAT TORQUE MARKS ON SECONDARY BOLTS ARE ALIGNED THROUGH THE PLEXIGLAS VIEWING WINDOW.

(G) TO PERFORM TRANSFORMER PRE-TEST, DISCONNECT AND ISOLATE X3/X1 CONDUCTORS SHOWN IN FIGURE 6. PERFORM TEST, THEN RE-INSTALL X3/X1 CONDUCTORS, AND TORQUE TO 50 FT. LBS. DO NO OVER/UNDER TIGHTEN.





**FIGURE 6** (F)(G)

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |



TABLE OF CONTENTS

## INSTALLATION (CONT'D):

(H) PRIOR TO ENERGIZING THE UNIT, THE BYPASS SWITCH SHOULD BE IN THE BYPASS POSITION. ONCE THE TRANSFORMER IS ENERGIZED, CHECK VOLTAGE ON THE SECONDARY SIDE. IF VOLTAGE IS ACCEPTABLE, TURN BYPASS SWITCH TO "ON" AND CHECK SECONDARY VOLTAGE AGAIN.





**FIGURE 7** (H)

J. BASE WILL BE CAULKED TO PREVENT WIRE ENTRY. (a)

K. KEYLESS LOCK TO BE ATTACHED TO LATCHING MECHANISM ON TRANSFORMER AND IPR CABINET WITH PENTAHEAD BOLT THREADED IN COMPLETELY.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | TRANSFORMER, REGULATING, 50KVA, 6930/2400V (A) | | 1 | - | S765098 | SPRT50 |
| 2 | PAD, TRANSFORMER, SINGLE PHASE | | 1 | 3421 | S514240 | 3421-1 |
| 3 | CONNECTOR, SLIP-FIT | #8-350KCMIL | 3 | 4167/4168 | S270290 | 350-8S |
| | | #6-55KCMIL | | | S270296 | 500-8S |
| 4 | GROUND WIRE | | AS REQ'D | 4510 | S812818 (X) | GDWIRE |
| 5 | CONNECTOR, SERVICE POST | | 2 | 3711.1 | S262560 | SPCONN |
| 6 | NUT, CLAMPING CHANNEL | | 2 | | S503520 | - |
| 7 | SCREW, HEX HEAD CAP, BRONZE, 1/2" X 1 1/2" | | 2 | | S616192 | - |
| 8 | WASHER, STANDARD FLAT ROUND, BRONZE, 1/2" | | 2 | | S799488 | - |
| 9 | LOCK, KEYLESS | | 2 | | S468010 | - |
| 10 | SEALANT, CAULKING | | AS REQ'D | 3408 | S631800 | - |

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |



TABLE OF CONTENTS

**NOTES:**

I. PRT-50 WEIGHS APPROXIMATELY 1,440 POUNDS.

II. THE HEAT SINKS MOUNTED ON THE OUTSIDE OF THE PRT CAN GET EXTREMELY HOT. BE SURE TO TAKE APPROPRIATE PRECAUTIONS WHEN HANDLING OR SERVICING THE DEVICE.

III. WHEN INSTALLING OR CHANGING SPRT50 FROM 2.4KV TO 6.9KV, CHANGE BAY-O-NET FUSE FROM 40A TO 12A (AND VICE VERSA). SPRT50 IS SUPPLIED WITH 40A 2.4KV FUSE.

IV. SET SCREW CONNECTORS ARE NOT PROVIDED WITH TRANSFORMER. ALWAYS MAKE CERTAIN SECONDARY CONNECTIONS ARE TIGHT BEFORE ENERGIZING TRANSFORMER. (c)

(X) THIS ITEM IS EXEMPT.

**REFERENCE:**

(a) FOR WIRE ENTRY PREVENTION, SEE UG3408.

(b) FOR CONDUIT SEALING, SEE UG3948 (G.O. 128 RULE 31.6).

(c) FOR SLIP-FIT CONNECTORS, SEE UG4167.

d. FOR INSTALLATION OF SINGLE PHASE "SDS" TRANSFORMER, SEE UG3711.1.

e. FOR CABLE IDENTIFICATION, SEE UG3202.

f. FOR TRANSFORMER IDENTIFICATION, SEE UG3214.

g. FOR PAD AND CONDUIT REQUIREMENTS, SEE UG3421.

h. FOR MINIMUM OPERATING AND CLEARANCE REQUIREMENTS (PAD PLACEMENT), SEE UG3480, UG3481, UG3482 AND UG3483.

i. FOR PAD INSTALLATION OF PAD MOUNTED EQUIPMENT, SEE UG3484.

j. FOR RETAINING WALL REQUIREMENTS AND CLEARANCES FROM REVERSE SUBGRADE RETAINING WALL, SEE UG3486, UG3487 AND UG3488.

k. FOR RETAINING WALLS, SEE UG3489.

l. FOR SEALING SERVICE LATERAL CONDUITS, SEE UG3948.

m. FOR PREFERRED I AND ALTERNATE TRENCH GROUND WIRE, SEE UG4510.

n. FOR EQUIPMENT GROUNDING INSTALLATION, SEE UG4512.

o. FOR GROUNDING TELCO CONDUCTOR IN PAD MOUNTED EQUIPMENT, SEE UG4514.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | EDITORIAL CHANGES | - | KR | JS | MDJ | 12/1/2017 | F | | | | | | |
| B | ORIGINAL ISSUE | - | JBH | TR | MDJ | 4/15/2016 | E | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | JC | TR | - | 5/5/2015 | D | TABLE UPDATES | - | KR | JS | MDJ | 12/21/2017 |

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE 600A THREE-PHASE "3 IN 1" PAD MOUNTED REGULATORS. THE PAD MOUNTED REGULATORS MAY BE INSTALLED IN TWO APPLICATIONS.





**FIGURE 1**
WYE CONNECTED REGULATOR (I)(b)(c)
CABINET SIDE REMOVED
SIDE VIEW
SEE TABLE 1





**FIGURE 1**
WYE CONNECTED REGULATOR (I)(b)(c)
CABINET REMOVED
FRONT VIEW
SEE TABLE 1

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.1





**FIGURE 2**
DELTA CONNECTED REGULATOR (I)(b)(c)
CABINET SIDE REMOVED
SIDE VIEW
SEE TABLE 1





**FIGURE 2**
DELTA CONNECTED REGULATOR (I)(b)(c)
CABINET REMOVED
FRONT VIEW
SEE TABLE 1

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.2

## TABLE 1 (FIGURES 1-2)

| PAD MOUNTED REGULATOR DESCRIPTION LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | BUSHING, INTEGRAL APPARATUS, HIGH VOLTAGE |
| 2 | BOXOUT, TANK, FOR HV BUSHINGS |
| 3 | BASE, REGULATOR, TANK W/ JACKING AND ROLLING FACILITIES |
| 4 | LIFTING LUGS |
| 5 | BOLTED COVER W/ NUT GUARD |
| 6 | PRESS CONN. & FILL PLUG, 1, 0" UPPER FILTER |
| 7 | VALVE, DRAIN, 1, 0" , W/ SAMPLER |
| 8 | DEVICE, AUTO PRESS RELIEF |
| 9 | PROVISION PRESSURE VACUUM GAUGE |
| 10 | GAUGE, OIL LEVEL MAGNETIC |
| 11 | GAUGE, OIL SIGHT |
| 12 | INDICATOR, TAP CHANGER POSITION, W/ DRAGHANDS AND REGULATION RANGE LIMIT SWITCHES |
| 13 | THERMOMETER PROVISION |
| 14 | TAP SWITCH, EXTERNAL NON-LOAD, FOR CONTROL TAPS |
| 15 | REMOVABLE SILL |
| 16 | PAD, GROUND, W/ 2 - 1/2-13 UNC TAPPED HOLES 7/16" DEEP |
| 17 | NAMEPLATE |
| 18 | PARKING STAND |
| 19 | CABINET, BOLTED, HIGH SECURITY, W/ PENTAHEAD DOOR BOLTS |
| 20 | ENCLOSURE, CONTROL, LOCKABLE ON INSIDE OF CABINET DOOR |
| 21 | CORRUGATION, COOLING, (WHEN REQUIRED) |
| 22 | BUSHING, NEUTRAL/CONCENTRIC GROUND |
| 23 | DOOR HANDLE |
| 24 | CONCENTRIC NEUTRAL/NEUTRAL GROUND STRAP |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.3

TABLE OF CONTENTS





**FIGURE 3**
CABLE CONNECTION DIAGRAM
WYE CONNECTED REGULATOR

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.4

TABLE OF CONTENTS





**FIGURE 4**
CABLE CONNECTION DIAGRAM
DELTA CONNECTED REGULATOR

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.5





**FIGURE 5**
CONDUIT/SUBSTRUCTURE/PAD/COMMUNICATION/GROUND
INSTALLATION DIAGRAM
TOP VIEW

TABLE OF CONTENTS





**FIGURE 5**
CONDUIT/SUBSTRUCTURE/PAD/COMMUNICATION/GROUND
INSTALLATION DIAGRAM
FRONT VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.6





**FIGURE 6**

CONDUIT DIAGRAM FOR PME AND PAD MOUNTED REGULATORS





**FIGURE 7**

CONDUIT DIAGRAM FOR PME AND PAD MOUNTED REGULATORS (d)
BOX AND CONDUIT PLACEMENT
PLAN VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"

UG4713.7

## INSTALLATION:

(A) SLURRY ENCASE ALL 5-INCH CONDUITS.

(B) SLURRY ENCASE ALL 5-INCH 90 DEGREE BENDS TO WITHIN 6 INCHES OF THE FINAL CUT.

(C) DO NOT CUT THE 90 DEGREE BENDS.

(D) LOOP A 1-INCH POLYETHYLENE CONDUIT TO EACH PAD. STUB THE CONDUIT 4 FEET FROM THE EDGE OF PAD, CLOSEST TO TELCO, WHEN REQUIRED.

(E) IN SOFT SOILS A CONCRETE BACKFILL (1 SACK MIX.) IS REQUIRED UNDER THE PAD 12 INCHES BEYOND THE SIDE EDGES OF PAD AND 12 INCHES DEEP.

(F) INSTALL A TRENCH GROUND WIRE FOR EACH PAD. INSTALL A SEPARATE GROUND WIRE BETWEEN THE CENTER PAD AND EACH END PAD.

(G) ATTACH TRENCH GROUND TO GROUND PADS AND CONCENTRIC NEUTRAL.

(H) ALL HORIZONTAL BENDS WILL BE MADE WITH ONLY LONG SWEEPS OF 25-FOOT RADIUS OR LONGER.

J. SET 3313 ON 4 INCHES OF COMPACTED 1/2 GRAVEL.

(K) NEUTRAL/GROUND STRAP FROM NEUTRAL BUSHING TO GROUND PAD.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD, REGULATOR, THREE-PHASE | 1 | -- | -- | -- |
| 2 | BASE SECTION, 3313 | 3 | 3313 | S162664 | 3313B |
| 3 | BEND, 5", 90° | 2 | 3373 | -- | -- |
| 4 | CONDUIT, POLY, 1" | AS REQ'D | 3373 | S249630 | 1"PE |
| 5 | CONDUIT, 5" DB | AS REQ'D | 3373 | S249728 | 1DB5SL |
| 6 | SLURRY 1-SACK | AS REQ'D | 3376 | S656400 | -- |
| 7 | WIRE, TRENCH GROUND | 3 | 4510 | -- | -- |
| 8 | CONNECTOR, COMPRESSION | AS REQ'D | 4174/4176 | -- | -- |
| 9 | PAD, GROUND W/ 2 - 1/2-13 UNC TAPPED HOLES 7/16" DEEP | AS REQ'D | -- | S262560 | -- |
| 10 | CONNECTOR, "T" TYPE, 600A | 6 | 4181 | -- | -- |
| 11 | REGULATOR, VOLTAGE, THREE-PHASE PADMOUNT, WYE | 1 | -- | S581254 | GYP656 |
| | REGULATOR, VOLTAGE, THREE-PHASE PADMOUNT, DELTA | 1 | -- | S581256 | GDP578 |
| 12 | CONDUIT, 5", FOR UNDERGROUND BYPASS | AS REQ'D | 3373 | S249728 | 1DB5SL |
| 13 | BEND, 5", 90°, FOR UNDERGROUND BYPASS (II) | AS REQ'D | 3373 | S322112 | 1-5SLB |
| 14 | ENCASE/SLURRY/CONDUITS | AS REQ'D | 3373 | -- | 1EB3IN |

## NOTES:

(I) SUB-STRUCTURE AND CONDUIT INSTALLATION, SEE FIGURES 3-5.

(II) NOT SHOWN ON FIGURES.

## REFERENCE:

(a) FOR EQUIPMENT GROUNDING, SEE UG4520.

(b) FOR OVERHEAD CONSTRUCTION REQUIRING 600A VOLTAGE REGULATION, SEE UG4710.

(c) FOR FULL UNDERGROUND CIRCUITS REQUIRING 600A VOLTAGE REGULATION, SEE UG4710.

(d) FOR INSTRUCTIONS ON INSTALLATION OF BOX PAD, SEE UG3423.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |



TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS NEW CONSTRUCTION FOR MULTIPLE CONDUIT RISERS USED WITH PAD MOUNTED REGULATOR.





**FIGURE 1**





**FIGURE 1**
VIEW A-A





**FIGURE 1**
NEW MULTIPLE RISER CONSTRUCTION
VIEW B-B

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR "3 IN 1"



UG4713.9

## INSTALLATION:

(A) STAPLES AND COVERED GROUND WIRE NOT NEEDED ON STEEL POLE.(a)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | SIZE (IN) | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CABLE FOR POLES AND PADMOUNT, USE 1000KCMIL | -- | AS REQ'D | -- | -- | -- |
| 2 | COUPLING (SIZE AS REQUIRED) | 5 | AS REQ'D | -- | S280032 | -- |
| 3 | CONDUIT RISER BEND, SCHEDULE 80 (SIZE AS REQUIRED) | 5, 48R | AS REQ'D | -- | S322488 | 5"CP-B |
| 4 | CONDUIT RISER, PVC, SCHEDULE 80 (SIZE AS REQUIRED) | 5 | AS REQ'D | -- | S251592 | S80-5" |
| 5 | COUPLING, PVC, SCHEDULE 80 | 5 | AS REQ'D | -- | S280592 | -- |
| 6 | COUPLING, PVC, SCHEDULE 40 (SIZE AS REQUIRED) | 5 | AS REQ'D | -- | S280496 | -- |
| 7 | CONDUIT, PVC, SCHEDULE 40 (SIZE AS REQUIRED) | 5 | AS REQ'D | -- | S251408 | S40-5" |
| 8 | GRIP, CABLE SIZE AS REQUIRED FOR PRIMARY RISERS (FOR 5" CONDUIT, 1000KCMIL AL CABLE) | -- | AS REQ'D | -- | S394098 | 5G1000 |
| 9 | PROTECTOR, NYLON CABLE | -- | AS REQ'D | -- | S558720 | -- |
| 10 | BRACKET, LADDER ARM | -- | AS REQ'D | -- | S167186 (X) | LA-ARM |
| 11 | CHANNEL, DOUBLE, GALV., 24 3/4" x 7/8" x 2 3/4" | -- | AS REQ'D | -- | S216702 (X) | |
| 12 | NUT STUD, 1/2" x 1 3/8", CLAMPING CHANNEL, W/SPRING | -- | AS REQ'D | -- | S507000 | |
| 13 | BOLT, MACH, GALV., 5/8" x (LENGTH AS REQ'D), 1-SQUARE, WASHER & DOUBLE COIL SPRING WASHER | -- | AS REQ'D | 390 | -- | -- |
| 14 | CLAMP, PIPE, STEEL, GALV., UNISTRUT, 5" | -- | AS REQ'D | -- | S229668 | CL-5IN |
| 15 | CABLE POLE | -- | -- | 4242 | -- | -- |
| 16 | CABLE POLE CONNECTION | -- | -- | 4111 | -- | -- |
| 17 | IN LINE BYPASS | -- | 3 | 1218 | S707020 | ILD5W |

## NOTES:

(I) LOCATE INLINE SWITCH NEXT TO SOURCE CABLE.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) FOR GROUNDING, SEE OH SECTION 1000.

(b) SEE UG4204, FIGURE 3.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 | E | | | | | | |
| A | ORIGINAL ISSUE | - | KR | JES | CZH | 04/22/2019 | D | | | | | | |

**SCOPE:** THIS STANDARD COVERS THE INSTALLATION OF THE 600A THREE-PHASE "3 IN 1" PAD MOUNTED REGULATORS. THE PAD MOUNTED REGULATORS MAY BE INSTALLED IN TWO APPLICATIONS.





**FIGURE 1**
WYE CONNECTED REGULATOR (a)(b)(c)
CABINET SIDE REMOVED
SIDE VIEW
SEE TABLE 1





**FIGURE 1**
WYE CONNECTED REGULATOR (a)(b)(c)
CABINET REMOVED
FRONT VIEW
SEE TABLE 1

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR

UG4714.1

TABLE OF CONTENTS





**FIGURE 2**
DELTA CONNECTED REGULATOR (a)(b)(c)
CABINET SIDE REMOVED
SIDE VIEW
SEE TABLE 1





**FIGURE 2**
DELTA CONNECTED REGULATOR (a)(b)(c)
CABINET REMOVED
FRONT VIEW
SEE TABLE 1

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR

UG4714.2

## TABLE 1 (FIGURES 1-2)

| PAD MOUNTED REGULATOR DESCRIPTION LIST | |
|---|---|
| **ITEM** | **DESCRIPTION** |
| 1 | BUSHING, INTEGRAL APPARATUS, HIGH VOLTAGE |
| 2 | BOXOUT, TANK, FOR HV BUSHINGS |
| 3 | BASE, REGULATOR, TANK W/ JACKING AND ROLLING FACILITIES |
| 4 | LIFTING LUGS |
| 5 | BOLTED COVER W/ NUT GUARD |
| 6 | PRESS CONN. & FILL PLUG, 1, 0", UPPER FILTER |
| 7 | VALVE, DRAIN, 1, 0", W/ SAMPLER |
| 8 | DEVICE, AUTO PRESS RELIEF |
| 9 | PROVISION, PRESSURE VACUUM GAUGE |
| 10 | GAUGE, OIL LEVEL, MAGNETIC |
| 11 | GAUGE, OIL SIGHT |
| 12 | INDICATOR, TAP CHANGER POSITION, W/ DRAGHANDS AND REGULATION RANGE LIMIT SWITCHES |
| 13 | THERMOMETER PROVISION |
| 14 | TAP SWITCH, EXTERNAL NON-LOAD, FOR CONTROL TAPS |
| 15 | REMOVABLE SILL |
| 16 | PAD, GROUND, W/ 2 - 1/2-13 UNC TAPPED HOLES, 7/16" DEEP |
| 17 | NAMEPLATE |
| 18 | PARKING STAND |
| 19 | CABINET, BOLTED HIGH SECURITY, W/ PENTAHEAD DOOR BOLTS |
| 20 | ENCLOSURE, CONTROL, LOCKABLE ON INSIDE OF CABINET DOOR |
| 21 | CORRUGATION, COOLING, (WHEN REQUIRED) |
| 22 | BUSHING, NEUTRAL/CONCENTRIC GROUND |
| 23 | DOOR HANDLE |
| 24 | CONCENTRIC NEUTRAL/NEUTRAL GROUND STRAP |

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

TABLE OF CONTENTS





**FIGURE 3**
CABLE CONNECTION DIAGRAM
WYE CONNECTED REGULATOR

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

TABLE OF CONTENTS





**FIGURE 4**
CABLE CONNECTION DIAGRAM
DELTA CONNECTED REGULATOR

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |





**FIGURE 5**
CONDUIT / SUBSTRUCTURE / PAD / COMMUNICATION / GROUND
INSTALLATION DIAGRAM
TOP VIEW





**FIGURE 5**
CONDUIT / SUBSTRUCTURE / PAD / COMMUNICATION / GROUND
INSTALLATION DIAGRAM
FRONT VIEW

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |





**FIGURE 6**

CONDUIT DIAGRAM FOR PME AND PAD MOUNTED REGULATORS





**FIGURE 7**

CONDUIT DIAGRAM FOR PME AND PAD MOUNTED REGULATORS (d)
BOX AND CONDUIT PLACEMENT
PLAN VIEW

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS



INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR

UG4714.7

TABLE OF CONTENTS

## INSTALLATION:

(A) SLURRY ENCASE ALL 3-INCH CONDUITS.

(B) SLURRY ENCASE ALL 3-INCH 90-DEGREE BENDS TO WITHIN 6 INCHES OF THE FINAL CUT.

(C) DO NOT CUT THE 90-DEGREE BENDS.

(D) LOOP A 1-INCH POLYETHYLENE CONDUIT TO EACH PAD. STUB THE CONDUIT 4 FEET FROM THE EDGE OF PAD, CLOSEST TO TELCO, WHEN REQUIRED.

(E) IN SOFT SOILS A CONCRETE BACKFILL (1 SACK MIX.) IS REQUIRED UNDER THE PAD 12 INCHES BEYOND THE SIDE EDGES OF PAD AND 12 INCHES DEEP.

(F) INSTALL A TRENCH GROUND WIRE FOR EACH PAD. INSTALL A SEPARATE GROUND WIRE BETWEEN THE CENTER PAD AND EACH END PAD.

(G) ATTACH TRENCH GROUND TO GROUND PADS AND CONCENTRIC NEUTRAL.

(H) ALL HORIZONTAL BENDS WILL BE MADE WITH ONLY LONG SWEEPS OF 25-FOOT RADIUS OR LONGER.

J. SET 3313 ON 4 INCHES OF COMPACTED 1/2 GRAVEL.

(K) NEUTRAL/GROUND STRAP FROM NEUTRAL BUSHING TO GROUND PAD.

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | PAD, TRANSFORMER, 3426 | 3 | 3426 | S514005 | 3426BO |
| 2 | BASE SECTION, 3313 | 3 | 3313 | S162664 | 3313B |
| 3 | BEND, 3", 90° | 6 | 3373 | S322048 | S80-3" |
| 4 | CONDUIT, POLY, 1" | AS REQ'D | 3373 | S249630 | 1"PE |
| 5 | CONDUIT, 3" DB | AS REQ'D | 3373 | S249664 | 1DB3-P |
| 6 | SLURRY, 1-SACK | AS REQ'D | 3376 | S656400 | -- |
| 7 | WIRE, TRENCH GROUND | 3 | 4510 | -- | -- |
| 8 | CONNECTOR, COMPRESSION | AS REQ'D | 4174/4176 | -- | -- |
| 9 | PAD, GROUND, W/ 2 - 1/2-13 UNC TAPPED HOLES, 7/16 DEEP | AS REQ'D | -- | S262560 | -- |
| 10 | CONNECTOR, "T" TYPE, 600A (I) | 6 | 4181 | -- | -- |
| 11 | REGULATOR, VOLTAGE, SINGLE-PHASE PADMOUNT (I) | 3 | -- | S581490 | REG600 |
| 12 | CONDUIT, 5", FOR UNDERGROUND BYPASS | AS REQ'D | 3373 | S249728 | 1DB5SL |
| 13 | BEND, 5", 90°, FOR UNDERGROUND BYPASS (I) | AS REQ'D | 3373 | S322112 | 1-5SLB |
| 14 | ENCASE/SLURRY/CONDUITS (I) | AS REQ'D | 3373 | -- | 1EB3IN |

## NOTES:

(I) NOT SHOWN ON FIGURES.

## REFERENCE:

(a) FOR SUB-STRUCTURE AND CONDUIT INSTALLATION, SEE FIGURES 3-5.

(b) FOR OVERHEAD CONSTRUCTION REQUIRING 600A VOLTAGE REGULATION, SEE UG4710.

(c) FOR FULL UNDERGROUND CIRCUITS REQUIRING 600A VOLTAGE REGULATION, SEE UG4710.

(d) FOR INSTRUCTIONS ON INSTALLATION OF BOX PAD, SEE UG3423.

(e) FOR EQUIPMENT GROUNDING, SEE UG4520.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

**SCOPE:** THIS STANDARD SHOWS NEW CONSTRUCTION FOR MULTIPLE CONDUIT RISERS USED WITH PAD MOUNTED REGULATOR.





**FIGURE 1**





**FIGURE 1**
VIEW A-A





**FIGURE 1**
NEW MULTIPLE RISER CONSTRUCTION
VIEW B-B

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |

| | | | | |
|---|---|---|---|---|
| X Indicates Latest Revision | Completely Revised | New Page | Information Removed | |
| SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS | | | | |
| SHEET 9 OF 10 | INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR | | | UG4714.9 |

## INSTALLATION:

(A) STAPLES AND COVERED GROUND WIRE NOT NEEDED ON STEEL POLE.(a)

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | SIZE | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|---|
| 1 | CABLE FOR POLES AND PADMOUNT, USE 1C-1000AL | -- | AS REQ'D | -- | S197628 | -- |
| 2 | COUPLING, SIZE AS REQ'D | 3" | AS REQ'D | -- | S279904 | -- |
| 3 | CONDUIT RISER BEND, SCHEDULE 80, SIZE AS REQ'D | 3"_36" R | AS REQ'D | -- | S322472 | 3"CP-B |
| 4 | CONDUIT RISER, PVC, SCHEDULE 80, SIZE AS REQ'D | 3" | AS REQ'D | -- | S251552 | S80-3" |
| 5 | COUPLING, PVC, SCHEDULE 80 | 3" | AS REQ'D | -- | S280544 | -- |
| 6 | COUPLING, PVC, SCHEDULE 40, SIZE AS REQ'D | 3" | AS REQ'D | -- | S280448 | -- |
| 7 | CONDUIT, PVC, SCHEDULE 40, SIZE AS REQ'D | 3" | AS REQ'D | -- | S251360 | S40-3" |
| 8 | GRIP, CABLE SIZE AS REQUIRED FOR PRIMARY RISERS (FOR 3" CONDUIT, 1/C-1000 AL CABLE) | -- | AS REQ'D | -- | S394098 | 3G2#2A |
| 9 | PROTECTOR, NYLON CABLE | -- | AS REQ'D | -- | S558720 | -- |
| 10 | BRACKET, LADDER ARM | -- | AS REQ'D | -- | S167186 (X) | LA-ARM |
| 11 | CHANNEL, DOUBLE, GALV., 24 3/4" X 7/8" X 2 3/4" | -- | AS REQ'D | -- | S216702 (X) | |
| 12 | NUT STUD, 1/2" X 1 3/8", CLAMPING CHANNEL, W/SPRING | -- | AS REQ'D | -- | S507000 | |
| 13 | BOLT, MACH, GALV., 5/8" X (LENGTH AS REQ'D), 1-SQUARE, WASHER & DOUBLE COIL SPRING WASHER | -- | AS REQ'D | 390 | -- | -- |
| 14 | CLAMP, PIPE, STEEL, GALV., UNISTRUT | 3" | AS REQ'D | -- | S229632 | CL-3IN |
| 15 | CABLE POLE | -- | -- | 4242 | -- | -- |
| 16 | CABLE POLE CONNECTION | -- | -- | 4111 | -- | -- |
| 17 | IN LINE BYPASS | -- | 3 | 1218 | S707020 | ILD5W |

## NOTES:

(I) LOCATE INLINE SWITCH NEXT TO SOURCE CABLE.

(X) THIS ITEM IS EXEMPT.

## REFERENCE:

(a) FOR GROUNDING, SEE OH SECTION 1000.

(b) SEE UG4204, FIGURE 3.

TABLE OF CONTENTS

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | FORMATTING | EDM | JIK | - | - | 10/26/2021 | F | | | | | | |
| B | EDITORIAL CHANGES | - | KR | JES | CZH | 04/22/2019 | E | | | | | | |
| A | ORIGINAL ISSUE | - | - | - | TR/JDJ | 10/09/2007 | D | | | | | | |



X Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

INSTALLATION OF PAD MOUNTED THREE-PHASE REGULATOR

UG4714.10

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD COVERS ALL APPROVED ENERGY STORAGE INTERCONNECTION CONFIGURATIONS FOR 1MW SYSTEMS AND ABOVE, REGARDLESS OF UTILITY/INDEPENDENT OWNED AND OPERATED.

**ATTENTION:**

* NO DEVIATIONS WILL BE ALLOWED FOR THE APPROVED PHYSICAL ARRANGEMENT CONFIGURATIONS.

** FORMAL INDIVIDUAL EQUIPMENT DEVIATIONS (MANUFACTURER, MODEL, ETC.) WILL STILL BE ALLOWED ON AN APPLICATION. APPROVAL BASIS.

*** THE BATTERY SYSTEM WILL NOT BE INCLUDED IN DETAIL AND WILL BE DEVELOPED IN A SEPARATE STANDARD.





**FIGURE 1**
MULTI BATTERY SYSTEM (C)





**FIGURE 2**
ENERGY STORAGE/SOLAR ONELINE (D)

**INSTALLATION:**

**INTERCONNECTION PROCEDURES:**

A. OVERVIEW: AN OVERVIEW OF THE GENERATOR INTERCONNECTION PROCEDURES IS AVAILABLE ON THE SDG&E WEBSITE AT THE FOLLOWING URL ADDRESS:
HTTPS://WWW.SDGE.COM/GENERATION-INTERCONNECTIONS/OVERVIEW-GENERATION-INTERCONNECTIONS

B. TARIFFS: THERE ARE TWO GENERATOR INTERCONNECTION PROCESSES COVERED BY DIFFERENT TARIFFS: WDAT AND RULE 21.

1. WDAT - WHOLESALE DISTRIBUTION OPEN ACCESS TARIFF: THE WDAT INTERCONNECTION PROCESS IS OVERSEEN BY FERC. THE WDAT TARIFF IS AVAILABLE ON THE SDG&E WEBSITE AT:
HTTPS://WWW.SDGE.COM/GENERATION-INTERCONNECTIONS/WHOLESALE-GENERATOR-TRANSMISSION-INTERCONNECTIONS
THE WDAT INTERCONNECTION PROCESS MUST BE USED FOR PROJECTS INTERCONNECTING TO THE SDG&E DISTRIBUTION SYSTEM THAT WISH TO SELL ENERGY TO ANY PARTY BESIDES SDG&E. TO INITIATE A REQUEST TO INTERCONNECT A PROJECT TO THE SDG&E DISTRIBUTION SYSTEM UNDER THE WDAT PROCESS, AN INTERCONNECTION REQUEST FORM MUST BE FILLED OUT AND SUBMITTED TO THE SDG&E CUSTOMER GENERATION TEAM. THE INTERCONNECTION REQUEST FORM IS AVAILABLE IN THE WDAT TARIFF IN APPENDIX 1 ON PAGES 329 TO 345.
THIS PAGE RANGE SHOULD BE PRINTED, FILLED OUT, AND SUBMITTED TO THE CUSTOMER GENERATION TEAM AT:
WDATSGIPAPPLICATIONS@SEMPRAUTILITIES.COM

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| C | REVISED TO 3D FORMAT | ARC | JIK | - | - | 03/14/2022 |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | DG | JS | MDJ | 04/01/2018 |

SDG&E
A Sempra Energy utility

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**ENERGY STORAGE INTERCONNECTION**

SCALE: NOT TO SCALE

DRAWING NO: OH1920.1 UG4720.1

SHEET: 1 OF 3

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

TABLE OF CONTENTS

**INSTALLATION (CONT'D):**

2. RULE 21: THE ELECTRIC RULE 21 TARIFF INTERCONNECTION PROCESS IS OVERSEEN BY THE CPUC. THE RULE 21 TARIFF IS AVAILABLE ON THE SDG&E WEBSITE AT:
   HTTPS://WWW.SDGE.COM/GENERATION-INTERCONNECTIONS/ELECTRIC-RULE-21
   THE RULE INTERCONNECTION PROCESS CAN ONLY BE USED IF A GENERATOR PROJECT INTERCONNECTING TO THE SDG&E DISTRIBUTION SYSTEM WILL SELL ITS OUTPUT TO SDG&E ONLY. TO INITIATE A REQUEST TO INTERCONNECT A PROJECT TO THE SDG&E DISTRIBUTION SYSTEM UNDER THE RULE 21 PROCESS, AN INTERCONNECTION APPLICATION FORM MUST BE FILLED OUT AND SUBMITTED TO THE SDG&E CUSTOMER GENERATION TEAM. THE INTERCONNECTION APPLICATION FORM IS AVAILABLE ON THE SDG&E WEBSITE AT:
   HTTP://REGARCHIVE.SDGE.COM/TM2/PDF/ELEC_ELEC-SF_142-05203.PDF
   THIS APPLICATION FORM SHOULD BE PRINTED OUT, FILLED OUT, AND SUBMITTED TO THE CUSTOMER GENERATION TEAM AT:
   DGAPPLICATIONS@SEMPRAUTILITIES.COM

**CAUTION:**

* FOR GENERATION INTERCONNECTION OVERVIEW AND RULES FOLLOWED, GO TO THE LINK:
HTTP://WWW.SDGE.COM/GENERATION-INTERCONNECTIONS/OVERVIEW-GENERATION-INTERCONNECTIONS

**CONFIGURATIONS:** PRIMARY AND NON-PRIMARY METERING TO BE DETERMINED BY ELECTRIC METERING

Ⓒ GENERAL AND MULTI-BATTERY (REQUIRES HSCC SCADA TRAYER - S704738), SEE FIGURE 1:
WAY 1: ENERGY STORAGE
WAY 2: CRITICAL LOAD
WAY 3: GRID SOURCE
WAY 4: NON-CRITICAL LOAD

1. WAYS 1-4 WILL REQUIRE AUTOMATION CONTROL. WAY 3 WILL BE THE ONLY NON-FAULT INTERRUPTING POSITION. TRIP/CLOSE MODULES WILL NEED TO BE CLOSED, AND THE TRIP CIRCUIT WILL NEED TO BE ENABLED. WORK METHODS WILL CHANGE REGARDING CRITICAL AND NON-CRITICAL LOADS.
2. DESIGN OF ENERGY STORAGE SYSTEM WITH THE INVERTER AND TRANSFORMER AS A SINGLE UNIT IS AN APPROVED OPTION TO HE PRIMARY DISTRIBUTION SYSTEM.

Ⓓ CONFIGURATION 02 (TRADITIONAL SCADA TRAYER), SEE FIGURE 2:
WAY 1: ENERGY STORAGE
WAY 2: SOLAR
WAY 3: GRID SOURCE
WAY 4: LOAD

1. WAYS 1-4 WILL REQUIRE AUTOMATION CONTROL. WAY 3 WILL BE THE ONLY NON-FAULT INTERRUPTING POSITION. TRIP/CLOSE MODULES WILL NEED TO BE CLOSED, AND THE TRIP CIRCUIT WILL NEED TO BE ENABLED. WORK METHODS WILL CHANGE REGARDING CRITICAL AND NON-CRITICAL LOADS.
2. DESIGN OF ENERGY STORAGE SYSTEM WITH THE INVERTER AND TRANSFORMER AS A SINGLE UNIT, AND THE BATTERY AS A SEPARATE UNIT IS AN APPROVED OPTION TO THE PRIMARY DISTRIBUTION SYSTEM.

**VOLTAGE LIMITATIONS:**

E. PRIMARY METERED SWITCHGEAR INTERCONNECTIONS: 12.0KV (DELTA) OR 12.47KV (WYE) NOMINAL.
F. NON-PRIMARY METERED SWITCHGEAR INTERCONNECTIONS: 480VAC BETWEEN INVERTER OUTPUT AND UTILITY HYS TRANSFORMER.
G. LESS THAN 12KV NOMINAL INTERCONNECTIONS: INTERCONNECTION STUDY TO BE PERFORMED TO DETERMINE EQUIPMENT/CIRCUIT UPGRADING.

**CONDUCTOR/CONDUIT LIMITATIONS:**

H. ONLY SDG&E APPROVED CONDUITS AND CONDUCTORS WILL BE UTILIZED IN ANY ENERGY STORAGE PROJECT.

**AUXILIARY POWER:** REFER TO COMPANY POLICY FOR DETAILED AUXILIARY PROCEDURES/PROCESSES.

J. FIRE SUPPRESSION/PROTECTION
K. DETERMINE CONNECTIONS/PLACEMENT (WAYS FOR SWITCH)
L. UPS (INTERCONNECTION)
M. NETWORKING/TELECOMMUNICATIONS/METERING POWERED BY DC AND/OR AC VOLTAGE
N. STATION LIGHT AND POWER

**GIS MAPPING:**

O. INDIVIDUAL TECH DEVICES WILL BE IDENTIFIED BY PAD STRUCTURES.

**COMMUNICATIONS:** REFER TO COMPANY POLICY FOR DETAILED COMMUNICATION PROTOCOLS/PROCEDURES.

P. CAL ISO:
   1. METERING (REVENUE)
   2. REMOTE INTELLIGENT GATEWAY (RIG)
   3. AUTOMATED DISPATCH SYSTEM (ADS)
   4. APPROVED COMMUNICATIONS
Q. SDG&E:
   1. VENDOR
   2. IT
   3. SERIAL
   4. TCP/IP
   5. INTERNET
   6. GRID OPS TELEMETRY
   7. METERING (REVENUE)
   8. ELECTRIC METERING
   9. INFORMATION SECURITY (IS)

**BILL OF MATERILS:** NONE

**NOTES:**

I. TRAYER 4 WAY SCADA HIGH SPEED CLOSE COIL SWITCH(S) SPECIFICALLY DESIGNED FOR BLACKSTARTING AND ISLANDING CAPABILITIES.
II. FOR OVERHEAD SECTIONALIZING APPLICATIONS, USE ANY APPROVED SCADA RECLOSERS.
III. HYS TRANSFORMER(S) WILL BE REQUIRED FOR ALL NON-PRIMARY METERED INTERCONNECTIONS.

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| C | REVISED TO 3D FORMAT | ARC | JIK | - | - | 03/14/2022 |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | DG | JS | MDJ | 04/01/2018 |

SDG&E
A Sempra Energy utility®

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**ENERGY STORAGE INTERCONNECTION**

SCALE: NOT TO SCALE

DRAWING NO: OH1920.2 UG4720.2

SHEET: 2 OF 3

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

**REFERENCE:**

a. ELECTRIC DISTRIBUTION OVERHEAD CONSTRUCTION STANDARDS
HTTP://SEMPRA.SHAREPOINT.COM/SITES/SDGE-POWERUP/EDE/EDE%20MANUALS/OVERHEAD%20CONSTRUCTION%20STANDARDS.PDF

b. ELECTRIC DISTRIBUTION UNDERGROUND CONSTRUCTION STANDARDS
HTTP://SEMPRA.SHAREPOINT.COM/SITES/SDGE-POWERUP/EDE/EDE%20MANUALS/UNDERGROUND%20CONSTRUCTION%20STANDARDS.PDF

c. ELECTRIC DISTRIBUTION DESIGN MANUAL (INTERNAL SDG&E ONLY)
HTTP://SEMPRA.SHAREPOINT.COM/SITES/SDGE-POWERUP/EDE/EDE%20MANUALS/ELECTRIC%20DISTRIBUTION%20DESIGN%20MANUAL.PDF

d. ELECTRIC SERVICE STANDARDS
HTTP://SEMPRA.SHAREPOINT.COM/SITES/SDGE-POWERUP/EDE/EDE%20MANUALS/SERVICE%20STANDARDS%20AND%20GUIDE.PDF

e. ELECTRIC STANDARD PRACTICES (INTERNAL SDG&E ONLY)
HTTP://SEMPRA.SHAREPOINT.COM/SITES/SDGE-POWERUP/EDE/EDE%20MANUALS/ELECTRIC%20STANDARD%20PRACTICES.PDF

f. GO 95 LINK
HTTP://WWW.CPUC.CA.GOV/GOS/GO95/GO_95_STARTUP_PAGE.HTML

g. GO 128 LINK
HTTP://WWW.CPUC.CA.GOV/GOS/GO128/GO_128_STARTUP_PAGE.HTML

h. CAL ISO LINK - RESOURCE INTERCONNECTION GUIDE
HTTP://WWW.CAISO.COM/PARTICIPATE/PAGES/RESOURCEINTERCONNECTIONGUIDE/DEFAULT.ASPX

i. CAL ISO LINK - NEW RESOURCE INTERCONNECTION GUIDE
HTTP://WWW.CAISO.COM/PARTICIPATE/PAGES/NEWRESOURCEIMPLEMENTATION/DEFAULT.ASPX

TABLE OF CONTENTS

| REV | CHANGE | DRWN | BY | CHKD | APVD | DATE |
|---|---|---|---|---|---|---|
| C | REVISED TO 3D FORMAT | ARC | JIK | - | - | 03/14/2022 |
| B | FORMATTING | EDM | JIK | - | - | 10/26/2021 |
| A | ORIGINAL ISSUE | - | DG | JS | MDJ | 04/01/2018 |

SDGE — A Sempra Energy utility

© 1998 - 2022 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SDG&E ELECTRIC OVERHEAD AND UNDERGROUND CONSTRUCTION STANDARDS

**ENERGY STORAGE INTERCONNECTION**

SCALE: NOT TO SCALE

DRAWING NO: OH1920.3 UG4720.3

SHEET: 3 OF 3

X Indicates Latest Revision | Completely Revised | New Page | Information Removed

# 4800 - VAULT STANDARDS

# 4800 - VAULT STANDARDS

# Table of Contents

1. *TRANSFORMER VAULT* ..... 3
2. *PERSONNEL ACCESS DOOR (MAN DOOR)* ..... 3
3. *EQUIPMENT OPENINGS* ..... 4
4. *PULLING INSERT REQUIREMENTS* ..... 6
5. *VENTILATION SYSTEM* ..... 7
6. *VAULT LIGHTING SYSTEM* ..... 8
7. *ENERGIZING VAULT VENTILATION AND LIGHTING SYSTEM* ..... 8
8. *VAULT DRAINAGE SYSTEM: (CHECK WITH CITY IF REQUIRED)* ..... 8
9. *VAULT GROUNDING SYSTEM* ..... 9
10. *PRIMARY CONDUIT, EXTERIOR and INTERIOR:* ..... 9
11. *CUSTOMER SERVICE CONDUIT* ..... 11
12. *SERVICE ENTRANCE, BUS DUCT* ..... 11
13. *CUSTOMER'S METERING FACILITIES* ..... 12
14. *COMMUNICATIONS CONDUIT* ..... 12
15. *CABLE TRAY* ..... 12
16. *UNISTRUT HANGERS:* ..... 12
17. *SDG&E WILL FURNISH AND INSTALL* ..... 13
18. *BUS DUCT INTO PAD-MOUNTED TRANSFORMER:* ..... 14
19. *COPPER BRAID SIZING CHART:* ..... 16
20. *LOW VOLTAGE TERMINALS:* ..... 17
21. *INTERNAL VAULT WIRING* ..... 19
22. *EQUIPMENT OPENINGS IN VAULT WALL* ..... 21
23. *ELECTRIC VAULT LOCATION & ACCESSIBILITY* ..... 22
24. *VAULT INTERNAL DIMENSIONS: BELOW GRADE & STREET LEVEL VAULTS* ..... 24
25. *LADDER INSTALLATION FOR VAULTS GREATER THAN 12ft (Below Grade)* ..... 25
26. *VAULT EQUIPMENT COVER and PERSONNEL ACCESS OPENING (Below Grade)* ..... 26
27. *TYPICAL VAULT CONFIGURATIONS (AT & BELOW GRADE)* ..... 28
28. *CONSTRUCTION & MAINTENANCE RESPONSIBILITIES:* ..... 31

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

The following specifications have been compiled for the installation of SDG&E distribution facilities in a customer-owned vault. The information provides requirements to be followed for the construction of the vault and installation of electrical equipment per SDG&E standards. Consult the appropriate regional Project Management Office/service center for approval whenever any alteration to or deviation from these plans and specifications are contemplated. See service center and phone number listed below.

This installation must comply with all applicable rules of the Electrical Safety Orders of the Division of Industrial Safety, Department of Industrial Relations, State of California, National Electric Code, California Code of Regulations Title 8, CPUC General Order 128 and other governing codes and ordinances.

TABLE OF CONTENTS

PROJECT TITLE: ^ _____

PROJECT LOCATION: ^ _____

PROJECT NUMBER: ^ _____

SERVICE CENTER: ^ _____

PHONE NUMBER: ^ _____

PLANNER: ^ _____ DATE: ^ _____ APPROVAL: _____

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

**CUSTOMER SHALL FURNISH, INSTALL, OWN, AND MAINTAIN:**

## 1. TRANSFORMER VAULT:

1.1. Walls, roof, and floor shall be of assemblies of materials approved for three-hour non-combustible fire resistive construction (California Code of Regulations, Title 8, section 2806). All walls to be solid or solid filled. All concrete block or brick joints to be solid mortared. All floor-to-wall joints, wall-to-wall joints and wall-to-ceiling joints to be sealed water-tight with water and oil resistant materials. Street grade vaults only require seam sealing of floor-to-wall joints and wall-to wall joints to a height of 6 inches above floor, with water and oil resistant materials.

1.2. A 6 inch threshold for oil retention shall be provided at all vertical access openings into vault. See section 22.

1.3. Vault size _____ (inside dimensions). See section 24 for dimension table.

1.4. Whenever a vault is constructed over sublevels of a structure, the customer is to provide SDG&E with a certificate from a civil engineer registered in the State of California verifying the structural adequacy of the building to support the transformers and the fire withstanding capabilities of the structure's floor, ceiling and walls. Vault floor to be capable of supporting combined equipment weight of_____pounds.

1.5. Any vault construction below finished grade is to be considered a dry vault. The exterior surfaces of a dry vault which are exposed to surrounding earth conditions shall be sealed water-tight with an impermeable seal so as to prevent water entry through any portion of the vault. See section 1.1 above for sealing requirement for wall, floor and ceiling joints.

1.6. No ducts, pipes or conduits, except those which are a part of the electrical installation shall be installed in or through the vault. Sprinklers and smoke detectors shall not be installed in the vault room.

1.7. Any and all conduits passing through vault floor or walls (see section 1.6 above) shall be sealed water-tight with water and oil resistant materials on exterior surface. In addition, customer must apply a one inch thick and one inch wide layer of sealant mastic around the conduit in the center of the form before concrete is poured. See **SDG&E Underground Construction Standard page 3960** for illustration of required technique, recommended materials and required spacing between conduits. Contact SDG&E inspector at least one (1) day in advance of concrete pour to schedule inspection of construction of vault walls through which electric conduit pass.

1.8. Any and all spare conduits between the vault and a substructure located outside the vault shall be plugged at both ends with expandable duct plugs.

1.9. Customer shall inform SDG&E when any pre stressed concrete portions of vault are proposed for construction.

## 2. PERSONNEL ACCESS DOOR (WALK-THROUGH DOOR):

2.1. Developer / customer is to provide a 3ft x 6ft-8in, three-hour fire-rated self-closing personnel access door equipped with panic hardware, and should be located as shown in section 22 or 23.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

2.2. Developer / customer to provide light switch, with lighted switch plate, inside vault and adjacent to door.

2.3. Developer / customer to install **weather strips on all door edges** to prevent excessive air intake around door edges when vault ventilation is operating, and to limit fresh air intake in case of fire.

2.4. Developer / customer shall provide and install a Schlage VTQP section MA series key section in a storeroom function (self locking) Rhodes series lever action lockset. SDG&E will replace the MA series cylinder with an electric series cylinder prior to energizing the service. The developer is required to notify SDG&E's inspector when the lockset is installed.

2.5. Personnel access door shall open into a clear area that will allow manual carry-in of small tools and equipment. Personnel access doors in garage areas shall open into a designated no-parking zone and have permanent unobstructed access to door.

2.6. Door threshold to be 6 inches above vault floor for oil retention. All threshold seams, if any, to be sealed with water and oil resistant materials. See "Equipment Openings in Vault Wall" illustration in section 22.

2.7. Developer/customer to attach sign/placard to door stating the following:

"SDG&E Electric Vault", "Danger – High Voltage – Keep Out."

2.8. Developer to provide SDG&E with an approved route with 24 hour access easement to the personnel access door in the vault. If an electrically operated gate is installed restricting SDG&E vehicle access to the walk-through door, developer shall install a Schlage VTQP quad section cylinder in a key switch wired to the gate controller. A list of locksmiths authorized to sell SDG&E approved locks is available on request. The developer will install a means of opening the gate from the inside without the use of a vehicle to activate the controller. This will require the installation of an additional key switch inside the gate if there is no unsecured switch available. Door to have 24-hour direct ingress and egress for SDG&E personnel.

## 3. EQUIPMENT OPENINGS:

3.1. **Below Grade Vaults**

3.1.1. 10 ft. X 10 ft. Equipment opening through vault ceilings. Customer / developer shall provide removable three-hour fire rated 3 part concrete cover with wheel load factor HS-20 (per AASHTO). Customer to submit drawings approved by civil engineer registered in the State of California verifying HS-20 wheel loading for each equipment opening cover. No section of covers to exceed 4,800 lbs. Both opening and cover/s shall have matching beveled edges, with 30° vertical deflection. Four lifting coil inserts to be provided for removal of each section of cover. Lifting inserts shall be 1-inch threaded coil inserts with 4,500 lbs safe working load tension. See **SDG&E Underground Construction Standards** for illustrative details for equipment opening three piece cover. The equipment opening must be kept clear and unobstructed by customer-installed equipment both above and below the opening. A minimum vertical clearance of 30ft - for operation of heavy equipment including cranes - must be provided above the equipment opening – see illustration in section 23. Customer shall seal the cover to prevent water entry following installation of equipment. Repair, maintenance or replacement of any old or new, damaged covers is the responsibility of the customer / developer. SDG&E to determine when replacement is necessary.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

3.1.2. Customer to provide personnel access opening with 30-inch cast-in-frame ring and a 34-inch cast iron cover. Opening to be adjacent to equipment opening and at final grade. No coverings are permitted over this opening. Locate opening as shown in Sections 22.2 & 25. See SDG&E Underground Standards page 3332.

3.2. **At Grade Vaults**:

3.2.1. 10 ft. X 10 ft. Equipment opening through exterior vault wall. Equipment access door shall be Three-hour fire rated and have 24-hour direct access for SDG&E personnel. Developer shall provide and install a Schlage VTQP quad section MA series key section. SDG&E will replace the MA series cylinder with an electric series cylinder prior to energizing the service. A permanent and level six-foot clear working area, at least as wide as the door, is required outside of the equipment access door and at the same grade as the vault floor.

3.2.2. Customer to install removable 6-inch oil retention sill at equipment opening floor level when there is no other access for installing or removing transformers or other vault equipment. Sill construction to be 6-inch steel box beam. Bolts to pass through beam and align with inserts embedded in base of equipment opening. The beam must align with floor base and vertical edge to provide close fit for sealant compression to retain oil inside vault. Sealant to be oil and water resistant. See section 22.

TABLE OF CONTENTS

3.3. Truck Access on Private Property: If both the equipment opening and access route to equipment opening is located on private property, customer will provide permanent “all weather” drivable access route to equipment opening. This permanent access route shall be of sufficient strength to support truck weight class HS20 (20 tons per axel), be a minimum of 16ft wide and 13ft-6in high, with permanent turnaround having 20ft minimum turning radius – as measured from inside radius edge. Customer may provide permanent drive through access route in lieu of turnaround if so desired. Customer to install “Permanent SDG&E Truck Access Route” placard along access route with a minimum of one placard every 25ft. If heavier duty equipment is used to install facilities, such as a large crane, permanent access shall be maintained.

3.4. Truck Work Area on Private Property: If equipment opening is located on private property and area in immediate vicinity of equipment opening is also located on private property, customer will provide clear and permanent truck work area at least 50ft long x 16ft wide, centered on equipment opening.

3.5. Truck Access in Public Right-of-Way: If equipment opening is adjacent to public right-of-way, or in public right-of-way, it shall be located such that it provides the same truck access as for private property.

3.6. Truck Work Area in Public-Right-of-Way: If equipment opening is adjacent to public right-of-way, or in public right-of-way, it shall be located such that it provides the same truck work area as for private property.

3.7. Boom Clearance: Customer will provide permanent overhead boom clearance at equipment access opening as shown in “Electric Vault Location and Accessibility” illustration in section 23.

3.8. Restrictions: customer is not permitted to install tables, chairs, partitions, posts, signs, screens, walls, fences, railings, or barriers of any nature above or in front of SDG&E equipment opening or personnel access opening into electric vault.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

## 4. PULLING INSERT REQUIREMENTS

4.1. Transformer/switch/equipment moving inserts (A) – ____(no.) 1-inch diameter galvanized pulling irons located 48-inch up from vault floor, per attached SDG&E sketch. The coil insert strength shall be 10,000 pounds minimum with a working load safety factor 3. The concrete vault shall have a safety factor of 2 for these loads.

4.2. Cable pulling insert (B) (below grade vaults) – One (1) 7/8 inch diameter galvanized pulling iron(s) located in the opposite wall and at same height as incoming conduits. Pulling iron(s) to be designed to provide a minimum pulling tension of 12,000 lbs. The concrete vault to have a safety factor of 2 for these loads. A clear and unobstructed path must be provided and maintained between the conduit opening (into the vault) and the pulling eye on the opposite wall.

4.3. Cable pulling insert (C) (below grade vaults) – One 1-inch diameter galvanized pulling iron in same wall as cable pulling insert required in section 4.2 above, located directly opposite equipment opening, 48-inch above the vault floor. Pulling iron to provide a minimum pulling tension of 12,000 lbs. The concrete vault to have a safety factor of 2 for these loads. A clear and unobstructed path must be provided and maintained between cable pulling insert in section 4.2 and this cable pulling insert.

4.4. Cable pulling insert (E) (on grade vaults) – One 1-inch diameter galvanized pulling iron located in vault ceiling directly above incoming conduits in vault floor. Pulling iron to provide a minimum pulling tension of 12,000 lbs. The concrete vault to have a safety factor of 2 for these loads.

4.5. Optional cable and/or transformer insert – may be located in the vault floor a minimum of 9-inch from any wall face, and located per attached work order sketch.





**Figure 1 - Typical coil insert for use into thin slabs or small sections.**

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 5. VENTILATION SYSTEM:

5.1. Ventilation openings shall be located as far away as practicable from building doors, windows, fire escapes and combustible material. (California Code of Regulations, Title 8, section 2806). Openings inside the vault shall be located so as to direct the air stream over and around the transformer/s.

5.2. Supply Air (Intake) Opening for supply air shall be provided from a source of clean outside air or garage air. Intake louver(s) shall be provided on the outside of the building or in the garage, located a minimum of 18 inches above grade and per local codes. Intake louver(s) shall be sized per the louver manufacturer's recommendations to minimize entrainment of water into the air stream. Intake louver(s) shall be provided with bird screens. Three hour fire-rated ductwork shall connect the intake louver(s) to the vault. Ductwork shall be sized and designed per SMACNA, ASHRAE, and industry standards. Ductwork sizing shall consider pressure drop, air velocity and noise. Supply air opening(s) shall be located away from exhaust louver(s) and at least 18 ft above the floor of the vault and positioned to promote good cross ventilation/distribution of supply air across the entire vault. Supply air openings shall be constructed with a ½ inch mesh hardware cloth and sized for a maximum face velocity of 800 feet per minute. In addition, the foregoing installation is to comply with all local codes and ordinances.

5.3. Exhaust Air (Discharge): Ventilation and cooling air from the vault shall be discharged to the outside of the building or garage through exhaust louver(s). Exhaust louver(s) shall be located a minimum of 18 inches above street grade, away from intake louver(s) and building openings and per local codes. Exhaust louver(s) shall be sized per the louver manufacturer's recommendations. Exhaust louver(s) shall be provided with bird screens. Three hour fire-rated ductwork shall connect the exhaust louver(s) to the vault. Ductwork shall be sized and designed per SMACNA, ASHRAE, and industry standards. Ductwork sizing shall consider pressure drop, air velocity and noise. Exhaust opening(s) shall be located near the ceiling of the vault and positioned to promote good cross ventilation and/or distribution of supply air across the entire vault. Exhaust openings shall be constructed with a ½in mesh hardware cloth and sized for a maximum face velocity of 800 feet per minute. In addition, the foregoing installation is to comply with all local codes and ordinances.

5.4. Ventilation fan motor may be located inside or outside transformer vault. Coordinate with SDG&E to determine acceptable location prior to purchase of equipment. Ventilation fan motor installation is to comply with all local codes and ordinances.

5.5. Ventilation fan motor inside transformer vault shall have a disconnect device located (and marked) inside the vault adjacent to personnel access door. Customer to provide thermostat control, with a range of 70°F to 140°F located inside the vault mounted away from intake and exhaust vents in easily accessible location ("Minneapolis – Honeywell thermostat model or equivalent"). **Customer to provide regular scheduled maintenance for ventilation fan motor. Coordinate with SDG&E for access to transformer vault.**

5.6. Ventilation fan motor outside transformer vault shall have a lockable disconnect located outside the vault in the immediate vicinity of fan motor. Appropriate permanent signage is to be posted adjacent to outside lockable disconnect warning against tampering or disconnecting the vault ventilation. Customer to provide thermostat control, with a range of 70°F to 140°F located inside the vault mounted away from intake and exhaust vents in easily accessible location ("Minneapolis – Honeywell thermostat model or equivalent"). Thermostat shall have alarm monitoring and temperature reset controls and 2-way communication or remote control capability. **Customer to**

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

**provide regular scheduled maintenance for ventilation fan motor. Coordinate with SDG&E for access to transformer vault.**

5.7. Fire dampers shall be installed as required by local and State governing agencies having jurisdiction for the Occupancy type for the building. Any required fire dampers are to be located within vault. Provide adequate clearance for fire damper installation on supply & exhaust vent openings if dampers are required.

5.8. One continuous_____CFM (minimum) exhaust fan direct driven by a_____3-phase, sealed ball bearing motor. Fan to be mounted as close to the ceiling as practicable when located inside vault.

5.9. Vents, Ducts and flues shall not be connected with any other ventilation or air distribution system and must be for exclusive use of electric (transformer) vault.

5.10. See Section 21 for Internal Vault Wiring Diagrams.

5.10.1. Note - No gas meter set assemblies are allowed within 10ft of intake or discharge vents.

## 6. VAULT LIGHTING SYSTEM:

6.1. Vault light switch and 120v power receptacle. A 277V vault lighting system may be installed if available.

6.2. EXO switch complete with protection. Ventilation blower motor and vault lighting system to be separately protected. See attached detail____for diagram schematic.

6.3. Customer to wire out per authority having jurisdiction (AHJ) from point adjacent to secondary side of transformer to EXO switch and interconnect vault lights, switch and receptacle, exhaust fan and thermostat control as required.

6.4. Four-foot double fluorescent lamp fixture with minimum 40-watt bi-fin lamps to be mounted on ceiling or maximum height of 9 feet above floor level, at locations as specified on SDG&E drawing.

6.5. See Section 21 for Internal Vault Wiring diagrams.

## 7. ENERGIZING VAULT VENTILATION AND LIGHTING SYSTEM

7.1. When initially energizing the vault ventilation and lighting system a joint meeting with the customer electrician and SDG&E crews shall be scheduled to ensure wiring is correct and all motors/lighting are working properly. For services using three-phase motors, proper rotation should be confirmed.

## 8. VAULT DRAINAGE SYSTEM: (CHECK WITH CITY IF REQUIRED)

8.1. When Governmental or Municipal authority requires a vault drainage system, the customer is to install a standard floor drain connected to a dry sump located outside of the vault. Slope the floor gently to this drain and cover with standard grating. Customer will be responsible for maintaining all components of drainage system in good working condition.

8.2. The design and installation of vault drainage system (provided by the customer) must be approved by the appropriate inspection authority and must meet all local, state and federal environment requirements for all components.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

8.3. Customer is responsible for proper environmental disposal of any and all liquids recovered by vault drainage system.

8.4. Waste collection container must be capable of containing the total volume of oil for projected maximum size transformer/s (based on panel size/s) that can be used in vault. Contact SDG&E for volume requirement.

8.5. Regardless of whether Governmental or Municipal authorities require a vault drainage system, customer will install a sump hole directly below street level personnel access opening - in below grade vaults only.

## 9. VAULT GROUNDING SYSTEM:

9.1. Trench grounding is the preferred method for providing grounds for all vaults. Customer to install 30 ft of 4/0 bare stranded copper wire in the primary trench closest to building and encase the 4/0 bare copper wire in the base of the trench using Ground Enhancement Material (GEM). See SDG&E UG Standard 4510. Customer to insert 4/0 ground wire into 1inch PVC conduit for transition through vault/building wall. See SDG&E UG Standard 3960.2 for required technique and materials to transition PVC conduit through concrete. Ground wire inside vault to reach vault floor + 24 inch additional length.

9.2. As an alternative method, only when the approaching primary trench is less than 30 ft in length, customer to install 2 - 5/8 in X 10 ft long copper clad steel ground rods at minimum 6 ft interval in the primary trench. Install 4/0 bare stranded copper wire ground wire. Rods to be interconnected with 4/0 bare strand copper wire. See SDG&E UG Standard 4510. Customer to insert 4/0 ground wire into 1 inch PVC conduit for transition through vault/building wall. See SDG&E UG Standard 3960.2 for required technique and materials to transition PVC conduit through concrete. Ground wire inside vault to reach vault floor + 24 inch additional length.

9.3. Customer to provide individual equipment grounds within the vault for all transformers, capacitors, cable taps and fuse cabinets as specified by SDG&E. Customer to install/embed 1-#2/7 bare strand copper wire into vault floor for each transformer, capacitor, fuse cabinet and set of cable taps. Equipment ground wire to run from primary side of each transformer or capacitor, from below middle cable tap, and from below fuse cabinet, to a position just below entry point where 4/0 bare stranded copper trench ground wire transitions through vault wall – see 9.1 or 9.2 above. Customer to provide 24 inch (minimum) tail at each end of (each) equipment ground wire embedded in the floor of the vault.

9.4. Contact SDG&E inspector at least one (1) day in advance to schedule inspection of installation of trench ground outside vault (prior to backfill) and/or equipment ground embedded in vault floor. Customer to provide ladder access and a safe temporary access path (plywood or planks) within the vault for SDG&E inspector to make the inspection.

9.5. SDG&E will install required interior grounding for switches inside the vault.

## 10. PRIMARY CONDUIT, EXTERIOR and INTERIOR:

10.1. Primary exterior conduit trench shall be slurry backfilled, concrete encased or as specified by SDG&E.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

10.2. Primary exterior conduits shall terminate in corner of vault as specified by SDG&E Project Management Dept. Top of conduit package shall terminate no less than 60 inch below interior surface of vault ceiling.

10.3. Any and all conduits passing through vault exterior wall (see section 1.6 & 1.7 above) shall be water-tight with water and oil resistant materials. Conduit must be sealed on vault exterior surface. In addition customer must apply a one inch thick and one inch wide layer of sealant mastic around each conduit in the center of the form before concrete is poured. See SDG&E Underground Construction Standard page 3960 for illustration of required technique, recommended materials and required spacing between conduits. Contact SDG&E inspector at least one (1) day in advance to schedule inspection of vault floor through which conduits pass.

10.4. Any and all conduits passing through vault floor (see section 1.6 & 1.7 above) shall be sealed water-tight with water and oil resistant materials. If possible, conduit may be sealed on vault interior surface. In addition, customer must apply a one inch thick and one inch wide layer of sealant mastic around the conduit in the center of the form before concrete is poured. See SDG&E Underground Construction Standard page 3960.2 for illustration of required technique, recommended materials and required spacing between conduits. Contact SDG&E inspector at least one (1) day in advance to schedule inspection of construction of vault floor through which conduits pass.

10.5. All primary exterior conduits shall be installed such that they are free and clear of dirt, rocks, or other obstructions. Customer/developer shall install ¾in pulling and measuring tape rated at 2,500 pound tensile strength in all conduit runs over 10ft. Each conduit will have at least a two-foot measuring tape coil securely tied at each terminating end of conduit run. Horizontal conduit bends shall be 25ft radius of curvature.

10.6. Contact SDG&E inspector at least one (1) day in advance to schedule inspection of installation of primary exterior conduit system (prior to backfill) Note: service conduits not included in this section

10.6.1. _____(#. Conduits),_____In. Size,_____Type

10.6.2. _____(#. Conduits),_____In. Size,_____Type

10.6.3. _____(#. Conduits),_____In. Size,_____Type

10.6.4. _____(#. Conduits),_____In. Size,_____Type

10.7. Primary interior conduit may be installed beneath the vault floor provided vault floor is located at street level and is completely resting on earth.

10.8. Cable troughs may be installed in vault floor as substitute for primary interior conduits. Customer to submit specification to SDG&E for approval prior to fabrication. Allow 6 inches of width for each set of distribution cables and 7in of width for each set of feeder cables. The maximum width of any trough will be 30in.

10.9. Trough covers will be designed to withstand a minimum of 20,600 lbs traffic loading capacity (AASHTO H20 and ASTM C 857). Trough cover surfaces must be smooth textured to allow easy pass-over by small roller wheels. Trough covers will be flush mounted and have flush mounted

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

lifting handles on each end, or 1in lifting hole on both ends. Trough cover sections will be limited to a maximum weight of 80 lbs.

10.10. Cable troughs may not pass beneath floor mounted electric equipment. Troughs may terminate beneath floor mounted electric equipment.

10.11. Cable trays may be installed as substitute for primary interior conduits. See section 15.

## 11. CUSTOMER SERVICE CONDUIT:

11.1. Service conduits are only permitted when transformer vault is located at street level and vault floor is resting on earth. Combinations of 3 or 4 inch service conduits may be used provided they do not exceed 6 conduits total. A maximum of 5 - 5 inch service conduits may serve commercial & industrial boards up to 2,000 Amps. A maximum of 5 - 5 inch service conduits may serve residential & multifamily boards up to 3,500 Amps.

11.2. In addition to truck access required in section 3 above, line truck access is to be provided as indicated in SDG&E Service Standards & Guide, pg 16, when service conduits will be installed.

11.3. Service conduit requirements exceeding quantities stated above will require bus duct, rather than conduit, between secondary side of transformer and customer service equipment. When transformer vault is not on street level, and is not resting on earth, bus duct is required between secondary side of transformer and customer service equipment.

11.4. Install_____conduits from secondary side of transformer to customers pull section as indicated on sheet **XX** of **YY**. Terminate primary and service conduits at least 2in above floor to permit sealing (see section 1.6 & 1.7 above)

11.5. When more than one pull-section is served by the same transformer and the total number of conduits exceeds those listed above, bus duct will be required.

11.6. Any and all electric service conduits passing through vault floor shall be sealed water-tight with water and oil resistant materials. See SDGE Underground Standard 3960 for required spacing and specifications to be provided between conduits to allow use of sealing tools. See section 1.9 above for additional requirements

## 12. SERVICE ENTRANCE, BUS DUCT:

12.1. Service bus way from customer's service equipment to transformer. The design and location must be approved by SDG&E prior to fabrication. Refer to attached enclosure for straight bus section and bus entrance box. For attachment to transformer housing, bus bar configuration and transformer housing see illustrations in section 18 for details/specifications. Bus and entrance box to be permanently supported as required. Horizontal bus sections within vault to maintain 7ft-6in vertical clearance above vault floor. Where bus enters vault room, opening to be sealed following bus installation. Bus ampacity to match or exceed panel rating.

12.2. Customer service entrance installation to comply with all local codes and ordinances.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 13. CUSTOMER'S METERING FACILITIES:

13.1. Customer's meter board shall be constructed in accordance with SDG&E's service guide requirements. Manufacturer shall submit drawings to SDG&E Service Standards group for approval prior to fabrication.

## 14. COMMUNICATIONS CONDUIT:

14.1. SCADA (Supervisory Control and Data Acquisition): One 4 inch communications conduit shall be extended from customer vault to closest SDG&E substructure (for supervisory cable). Or one 4 inch conduit shall be extended to anticipated/future SCADA antenna location (for coax cable). And one 1 inch conduit shall be extended from customer vault to project telephone equipment area (telephone line). Coordinate with SDG&E Project Management department to determine specific requirement.

## 15. CABLE TRAY:

15.1. Cable trays are **not** preferred; however, the installation of cable trays may be necessary when circumstances prevent the installation of either (primary) conduit or trough, such as structurally thin floors. Customer to submit specifications to SDG&E for approval prior to fabrication.

15.2. Refer to Article 392 of the National Electric Code (NEC) for guidelines in selecting the proper cable tray type. (The type of cable to be installed in the tray will dictate the type of cable tray needed).

15.3. Refer to Article 392 of the National Electric Code (NEC) for guidelines in calculating the cable tray depth and width. (The type and number of cables to be installed will dictate the depth and width).

15.4. Cable tray side rail height should be at least 1in higher than the load depth (the depth of the largest cable).

15.5. Cable tray radius: The nominal (inside) bending radius for curved sections of cable trays shall not be less than the minimum allowable bending radius for the largest (triplexed) cable to be installed in the tray. Refer to SDG&E Underground Standard pg. 4004 for a listing of minimum cable bending radius.

15.6. Cable tray load/span classification describes the cable tray's load carrying capability for a specific support span. A classification should be selected that reflects the actual working load for each application. Refer to SDG&E Underground Standard pg. 4003.1 for a listing of SDG&E cable weights.

15.7. Cable trays shall hang not less than 7 ft-6 in above the vault floor.

## 16. UNISTRUT HANGERS:

16.1. Unistrut hangers shall be used to support cable trays and shall be suspended from ceiling of vault. Each unistrut hanger shall be capable of supporting 500 lbs. Unistruts will be spaced such that the maximum load at each unistrut hanger is no more that 250 lbs.

16.2. Sufficient unistrut hangers shall be installed such that not more than one cable tray splice plate connection is located between hangers. Curved sections shall have at least one unistrut hanger at the center of the curved section.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

# 17. SDG&E WILL FURNISH AND INSTALL:

## 17.1. Transformers

17.1.1. _____Transformer(s)_____kV._____/_____volt connected for three-phase 4-wire service (weight_____lbs)

17.1.2. _____Transformer(s)_____kV._____/_____volt connected for three-phase 4-wire service (weight_____lbs)

17.1.3. _____Transformer(s)_____kV. 120/240 volt connected for 1 -phase 3 -wire service (weight_____lbs)

## 17.2. 12KV Distribution Cable and Connectors

17.2.1. **Distribution Equipment:** SDG&E will furnish and install in vault (a) cable taps, (b) transformers, (c)_____-way switch (_____lbs), (d) wall-mounted fuse cabinet/s and fuses, (e) capacitor (2,000 lbs), (f) SCADA and communication equipment.

**17.2.1.1. Equipment Dimensions**

**17.2.1.1.1. Cable Taps**

**17.2.1.1.2. Transformers**

**17.2.1.1.3. Switches**

**17.2.1.1.4. Fuse Cabinets**

**17.2.1.1.5. Capacitors**

**17.2.1.1.6. SCADA and Communication Equipment**

17.2.2. **Service Conductors:** SDG&E will furnish and install service entrance conductors from transformer secondary terminals to customer's service pull section only when criteria in section 10.1 (above) are satisfied. Otherwise customer will install bus duct.

**NOTE -** CUSTOMER SERVICE ENTRANCE DESIGN AND LOCATION TO BE APPROVED BY SDG&E PRIOR TO FABRICATION

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 18. 18. BUS DUCT INTO PAD-MOUNTED TRANSFORMER:





Figure 2 - Typical bus duct configuration for pad-mounted transformer.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law

TABLE OF CONTENTS

TABLE OF CONTENTS





**Figure 3** - Typical service entrance configuration for various sizes of transformers.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 19. COPPER BRAID SIZING CHART:

19.1. Three-phase padmount transformers (number of 600 amp secondary braided jumpers per phase to be used)

| | SECONDARY VOLTAGE | | |
|---|---|---|---|
| KVA | 208Y/120 | 240 DELTA | 480Y/277 |
| 75 | 1 | 1 | 1 |
| 150 | 1 | 1 | 1 |
| 225 | 2 | 2 | 1 |
| 300 | 2 | 2 | 1 |
| 500 | 4 | 3 | 2 |
| 750 | 6 | — | 3 |
| 1000 | 7 | — | 3 |
| 1500 | 11 | — | 5 |
| 2000 | — | — | 6 |
| 2500 | — | — | 8 |
| 3000 | — | — | 9 |

**Table 1** - Number of 600A secondary braided jumpers based on transformer kVA size and secondary voltage.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 20. LOW VOLTAGE TERMINALS:

LOW VOLTAGE TERMINALS

| KVA X –6 HOLES | KVA X –6 HOLES | KVA X –6 HOLES | KVA X –6 HOLES | VOLTAGE |
|---|---|---|---|---|
| | 500 | 750 | 1000 | 208Y/120 |
| 750 | 1000 | 1500 | 2000 – 3000 | 480Y/277 |

**Table 2** - Number of "T" spade terminal holes based on transformer kVA size and secondary terminal voltages.





**Figure 4** - "T" Spade terminal dimensions.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

| A<br>MIN. | KVA | B<br>MIN. | E |
|---|---|---|---|
| 5±1/4” | 75 | 6±1/4” | 27±1/2” |
| 5±1/4” | 150 | 6±1/4” | 27±1/2” |
| 6±1/4” | 225 | 8±1/4” | 31±1/2” |
| 6±1/4” | 300 | 8±1/4” | 31±1/2” |
| 6±1/4” | 500 | 8±1/4” | 31±1/2” |
| 6±1/4” | 750 | 8±1/4” | 46±1/2” |
| 6±1/4” | 1000 - 3000 | 8±1/4” | 46±1/2” |

**Table 3** - Secondary bushing spatial dimensions.






**Figure 5** - Secondary bushing spatial diagram.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

## 21. INTERNAL VAULT WIRING

21.1. **120 – 208V Vault** (Alternate, only use if 277-480V not present)




**120-208V Vault**

* THERMOSTAT TO BE MOUNTED AWAY FROM INTAKE AND EXHAUST VENTS IN ANY EASILY ACCESSILBLE LOCATION.


** LIGHT SWITCH WITH LIGHTED SWITCH PLATE REQUIRED INSIDE VAULT (A) ADJACENT TO PERSONNEL ACCESS DOOR AND (B) BELOW 34" CAST IRON COVER/PERSONNEL ACCESS OPENING, 48" ABOVE THE FLOOR.

NOTE: ANY MODIFICATIONS OR ADDITIONS TO THESE SPECIFICATIONS SHALL COMPLY WITH ALL APPLICABLE NEC AND LOCAL CODES.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law

21.2. **277 – 480V Vault** (Preferred)




## 120V Vault Power from 277-480 Y Transformer

* THERMOSTAT TO BE MOUNTED AWAY FROM INTAKE AND EXHAUST VENTS IN ANY EASILY ACCESSILBLE LOCATION.

** LIGHT SWITCH WITH LIGHTED SWITCH PLATE REQUIRED INSIDE VAULT (A) ADJACENT TO PERSONNEL ACCESS DOOR AND (B) BELOW 34" CAST IRON COVER/PERSONNEL ACCESS OPENING, 48" ABOVE THE FLOOR.

NOTE: ANY MODIFICATIONS OR ADDITIONS TO THESE SPECIFICATIONS SHALL COMPLY WITH ALL APPLICABLE NEC AND LOCAL CODES.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law

## 22. EQUIPMENT OPENINGS IN VAULT WALL:

22.1. 10ft X 10ft Door required for equipment opening. May be a roll-up door or conventional.

22.2. Either style door must be Three-Hour Fire Rated. See section 3.1 and 3.2.





**Figure 6** - At Grade vault equipment and personnel access door.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

## 23. ELECTRIC VAULT LOCATION & ACCESSIBILITY:

23.1. At Grade Vault (Preferred):





**Figure 7** - Access to equipment openings for At Grade Vaults.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

23.2. Below Grade Vault (Alternate):





**Figure 7** - Access to equipment for Below Grade vaults.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

## 24. VAULT INTERNAL DIMENSIONS: BELOW GRADE & STREET LEVEL VAULTS

| Customer Type | Number of Transformers (26.1) | | Clear and unobstructed space (26.1/.2 /.3 /.5) | Equipment opening & personnel access opening |
|---|---|---|---|---|
| | 1Ø | 3Ø | | |
| **Residential Only** | 1 | 1 | 18' X 16' (at grade) | (not required at grade) |
| | 1 | 1 | 18' X 16' (below grade) | 17' X 12' (min) |
| **Commercial or Combination w/ Residential** | | 1 | 20' X 44' (26.4) | 17' X 12' (min)<br>(not required at grade) |
| | | 2 | 36½' X 29' or 20' x 57' | 17' X 12' (min)<br>(not required at grade) |
| | | 3 | 20' x 70' | 17' X 12' (min)<br>(not required at grade) |

**Table 4** – Vault dimensions based on type of service and equipment needs.

24.1. Customer must contact SDG&E Project Management department to determine dimensions for transformer combinations not listed. Contact SDG&E prior to submitting architectural building plans for Municipal approval.

24.2. Customer desiring deviation from standard vault dimensions must make formal written request to SDG&E Project Management department for consideration. Requests must be submitted to SDG&E prior to submitting architectural building plans for Municipal approval.

24.3. If customer is not able to provide clear & unobstructed space (no columns) in the dimensions specified above, please contact SDG&E Project Management department to determine acceptable alternative to prescribed dimensions above. Customer must coordinate with SDG&E prior to submitting architectural building plans for Municipal approval.

24.4. Customer may use 36½ft x 29ft dimensions if convenient.

24.5. Customer may provide larger vault than minimum dimensions listed above.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 25. LADDER INSTALLATION FOR VAULTS GREATER THAN 12ft (Below Grade)

25.1. Minimum Vault Depth 12ft, Maximum Vault Depth 20ft.

25.2. Sump hole required, centered directly below personnel access opening

25.3. Installation of permanent ladder not required in personnel access opening. SDG&E will supply ladder when needed.





**Figure 8** - Ladder installation details.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 26. VAULT EQUIPMENT COVER and PERSONNEL ACCESS OPENING (Below Grade)

26.1. Inside dimension of equipment opening shall measure 10ft x 10ft. Customer shall provide removable three-hour fire rated three-part concrete equipment opening covers. No coverings or facades are permitted over these covers unless an integral part of the covers themselves. Maximum weight of each section is not to exceed 4,800 lbs.

26.2. Customer to provide 4 lifting inserts with removable plugs (to keep out debris) near each corner of each equipment opening cover/section. Lifting inserts shall be 1in threaded coil inserts with 4,500 lbs safe working load tension – see section 3 & 4.

26.3. Personnel access opening (manhole) shall measure 30 inches in diameter with 34 inch diameter cast iron cover and recessed stainless steel penta-head bolts (4 total). See SDG&E Underground Standards page 3332. Personnel access opening to be at final grade. No coverings are permitted over this opening.

26.4. Customer to submit plans approved by a civil engineer registered in the State of California verifying the structural integrity of equipment opening covers and personnel access opening cover to withstand (AASHTO) HS-20 loading. Equipment opening cover shall be designed in accordance with SDG&E Underground Construction Standards. Plans to be submitted to SDG&E prior to construction/manufacture of vault roof and sectioned equipment opening.

26.5. Café fences, railings, partitions, enclosures, screens, barriers, walls, tables, chairs, umbrellas, podiums, or any other miscellaneous structures or furniture are not permitted above equipment opening cover or personnel access opening cover, temporarily or otherwise. Twenty four hour access for emergency and/or routine removal of covers is to be maintained at all times.

26.6. Equipment opening covers and personnel access open cover to sit flush with and at same grade as surrounding sidewalk.

26.7. Customer shall install felt insulation between concrete equipment opening covers and metal side rails/struts - to prevent surface vacuum buildup between covers and side rails. Install felt insulation such that top horizontal surface of insulation is ½ inch – 1inch below top surface of covers. Customer to seal perimeter of equipment opening covers with removable ultraviolet/water/oil resistant caulking.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

26.8. Equipment Opening & Personnel Access Opening shall be no more than 2 ft from edge of curb*.





**Figure 9** - Proximity of Below Grade Vault equipment and personnel access opening to street.

*Note: Customer is not permitted to install tables, chairs, partitions, posts, signs, screens, walls, fences, railings or barriers of any nature above or in front of SDG&E equipment opening or personnel access opening.

26.9. The following depiction shows typical arrangements of the “Clear& Unobstructed Space” (vault space for equipment) to the “Equipment and Personnel Access Opening”.





**Figure 10** - Typical arrangement of vault room in relation to equipment and personnel access opening.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

## 27. TYPICAL VAULT CONFIGURATIONS (AT & BELOW GRADE)





**Figure 11** - Typical below grade residential vault configuration for one transformer.





**Figure 12** - Typical at grade residential vault configuration for one transformer

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS





**Figure 13** - Typical below grade commercial vault configuration for one transformer.





**Figure 14** - Typical below grade commercial vault configuration for two transformers.

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS





**Figure 15** - Typical (square) below grade commercial vault configuration for two transformers.

TABLE OF CONTENTS

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

## 28. CONSTRUCTION & MAINTENANCE RESPONSIBILITIES:

The customer / owner shall furnish, construct and own the transformer vault facilities as specified. The customer / owner will be responsible for the maintenance of the vault facilities installed for the duration of service. This includes any portion of the vault structure extending into the public right-of-way, or outside of the project boundary.

The customer, owner or authorized representative agrees to provide, construct and maintain permanent truck & equipment access, and boom clearance for SDG&E's use at any equipment access opening located within the customer /owner's land. See sections 3.3 - 3.8 for specific requirements. Customer, owner or authorized representative also agrees to position equipment access opening that is adjacent to public right-of-way or in public right-of-way such that it provides the same access as when located within customer / owner's land. Access route shall be capable of supporting truck weight class H20 (20 tons per axel).

SDG&E will be represented in the field by an inspector and all work and material shall be subject at all times to inspection. Our inspector may be contacted prior to the start of your construction to answer any question you may have concerning your project. Final acceptance by SDG&E will be made when you have completed all work to the satisfaction of our inspector. The meters can only be set after final acceptance of your work, completion of our work, application for service, and receipt of final building inspection clearance.

All materials, work and work areas shall comply with the CAL-OSHA, Federal OSHA, and all other applicable federal, state, or local safety laws or rules that are necessary to protect applicant's and utility's employees, the public, and workers during the time of construction.

By proceeding with this installation, it is understood that you agree to all the stipulations set forth in these specifications and drawings indicated herein.

Customer / Owner_____Date_____

Customer (print name) _____

Authorized customer representative_____Date_____

Authorized customer representative (print name) _____

SDG&E representative_____Date_____

SDG&E representative (print name) _____

© 1998 – 2018 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without expressed written consent is not permitted under law.

TABLE OF CONTENTS

# 5000- TRENCHLESS CONSTRUCTION

# 5000- TRENCHLESS CONSTRUCTION

| PAGE | SUBJECT |
|---|---|
| 5001 | TABLE OF CONTENTS |
| 5010 | TRENCHLESS CONSTRUCTION - GENERAL |
| 5020 | TRENCHLESS CONSTRUCTION - JACK & BORE - REQUIREMENTS |
| 5030 | TRENCHLESS CONSTRUCTION - JACK & BORE - LAYOUT |
| 5040 | TRENCHLESS CONSTRUCTION - HORIZONTAL DIRECTIONAL DRILLING - REQUIREMENTS |
| 5050 | TRENCHLESS CONSTRUCTION - HORIZONTAL DIRECTIONAL DRILLING - LAYOUT |
| 5060 | TRENCHLESS CONSTRUCTION - SECTION VIEWS - CASING BORE |
| 5070 | TRENCHLESS CONSTRUCTION - SECTION VIEWS - EARTH BORE |

MAIN TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed

SHEET 1 OF 1

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRENCHLESS CONSTRUCTION
TABLE OF CONTENTS

UG5001.1

**SCOPE:** THE SCOPE OF THIS STANDARD IS TO PROVIDE GENERAL REQUIREMENTS FOR TRENCHLESS CONSTRUCTION METHODS USED TO CONSTRUCT UNDERGROUND ELECTRIC DISTRIBUTION FACILITIES.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. POLICY:

a. A QUALIFIED ELECTRICAL WORKER (QEW) SHALL BE PRESENT DURING ALL TRENCHLESS OPERATIONS.

b. REFER TO UG3002 FOR SAFETY, PEDESTRIAN CONTROL PLANS, BARRICADING, ACCESSIBILITY AND OTHER APPLICABLE POLICIES.

c. REFER TO UG3370 AND UG3371 FOR HORIZONTAL AND VERTICAL UTILITY SEPARATION AND DEPTH REQUIREMENTS.

d. THE TRENCHLESS CONTRACTOR MUST ATTEND THE PRECONSTRUCTION MEETING.

II. **RESPONSIBILITIES & QUALIFICATIONS:**

a. **TRENCHLESS CONTRACTOR** SHALL HAVE A MINIMUM OF 5 YEARS EXPERIENCE OF SUCCESSFUL TRENCHLESS CONSTRUCTION. ADDITIONALLY, THIS CONTRACTOR SHALL ENSURE THAT THE END ELEVATIONS OF THE NEW TRENCHLESS ALIGNMENT MATCH THE UNDERGROUND SEGMENTS TO WHICH THEY ARE TO BE CONNECTED.

b. **DISTRIBUTION DISTRICTS** ARE RESPONSIBLE FOR THE IMPLEMENTATION OF THIS DOCUMENT.

c. **ENGINEER** IS RESPONSIBLE FOR THE DESIGN OF CASING AND/OR EARTH BORES AS WELL AS THE CONDUIT CONFIGURATION IN CONFORMANCE WITH THIS STANDARD. THE ENGINEER WILL PROVIDE THE FOLLOWING DELIVERABLES: DRAWINGS, SPECIFICATIONS AND CALCULATIONS. CERTAIN PROJECTS WILL REQUIRE ADDITIONAL DELIVERABLES AT THE DETERMINATION OF THE DISTRIBUTION ENGINEER/CSE: GEOTECHNICAL INVESTIGATION, SWPPP, WPCP AND/OR DEWATERING PLAN.

d. **DISTRIBUTION ENGINEER/CSE** IS RESPONSIBLE FOR REVIEW OF DESIGN AND SUBMITTALS FOR CONFORMANCE WITH THIS STANDARD.

e. **FIELD EMPLOYEES** ARE RESPONSIBLE FOR ADHERENCE TO THIS STANDARD REGARDING SAFETY AND CONSTRUCTION QUALITY.

f. REFER TO UG3002 FOR ADDITIONAL EMPLOYEE DUTIES AND RESPONSIBILITIES.

III. **DEFINITIONS:**

**CARRIER PIPE** - THESE ARE THE ELECTRICAL CONDUITS INSTALLED IN A CASING PIPE OR AN EARTH BORE.

**CASING PIPE** - THE OUTERMOST PIPE WHICH CARRIES THE LOADING FROM VERTICAL LIVE AND DEAD LOADING AS WELL AS LOADING DURING INSTALLATION.

**GOVERNING AGENCY/RESPONSIBLE AUTHORITY** - THE AGENCY OR OWNER WHICH IS RESPONSIBLE FOR THE LOCATION IN WHICH THE WORK WILL BE PERFORMED. THIS INCLUDES BUT IS NOT LIMITED TO COUNTIES, CITIES, RAILWAY AGENCIES, HIGHWAY AGENCIES AND OWNERS OF BELOW GRADE UTILITIES.

**"GREENBOOK"** - STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, LATEST EDITION.

**JACK & BORE** - A METHOD OF TRENCHLESS CONSTRUCTION BY WHICH A TUNNEL IS DRILLED BY A BORING UNIT AND A CASING PIPE IS JACKED FORWARD WITHIN THE TUNNEL.

**HORIZONTAL DIRECTIONAL DRILLING (HDD)** - A METHOD OF TRENCHLESS CONSTRUCTION THAT INVOLVES DRILLING A PILOT HOLE, REAMING THE PILOT HOLE TO A LARGER SIZE AND PULLING A CARRIER PIPE THROUGH.

**PORTAL STABILIZATION** - WHERE THE NEW TUNNELED PIPELINE ENTERS OR EXITS A STABILIZED SHAFT.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed

## NOTES (CONT.):

### IV. ABBREVIATIONS:

| | |
|---|---|
| BNSF | BURLINGTON NORTHERN SANTA FE RAILWAY |
| CLSM | CONTROLLED LOW STRENGTH MATERIAL |
| CSE | SDG&E CIVIL/STRUCTURAL ENGINEERING DEPARTMENT |
| DR | PIPE DIMENSION RATION (OUTSIDE DIAMETER/WALL THICKNESS) |
| HDPE | HIGH DENSITY POLYETHYLENE |
| MTS | METROPOLITAN TRANSIT SYSTEM |
| OD | OUTER DIAMETER |
| PE | POLYETHYLENE |
| ROW | RIGHT OF WAY |
| SWPPP | STORM WATER POLLUTION PREVENTION PLAN |
| t | PIPE WALL THICKNESS |
| WPCP | WATER POLLUTION CONTROL PLAN |

### V. GEOTECHNICAL INVESTIGATION:

a. GEOTECHNICAL INVESTIGATIONS SHALL BE CONDUCTED AT THE DISCRETION OF THE CONTRACTOR OR WHEN DIRECTED BY SDG&E. WHETHER INVESTIGATIONS ARE CONDUCTED OR NOT, THE CONTRACTOR TAKES FULL RESPONSIBILITY FOR THE GEOTECHNICAL CONDITIONS. IF A GEOTECHNICAL INVESTIGATION IS PERFORMED IT SHALL BE INCLUDED AS A BID ITEM.

b. WHEN A GEOTECHNICAL INVESTIGATION IS WARRANTED IT SHALL INCLUDE THE FOLLOWING: GRADATION CURVES FOR GRANULAR SOIL, STANDARD PENETRATION TEST VALUES, CORED SAMPLES OF ROCK WITH LITHOLOGIC DESCRIPTION ROCK QUALITY DESIGNATION, UNCONFINED COMPRESSIVE STRENGTH OF ROCK, MOHS HARDNESS FOR ROCK SAMPLES, UNIT WEIGHT, ATTERBERG LIMITS, COHESION COEFFICIENT, SOIL FRICTION ANGLE, SOIL CONTAMINATIONS, AND RECOMMENDATIONS.

### VI. GROUNDWATER ELEVATION:

a. IF THE GROUNDWATER ELEVATION IS WITHIN TWO (2) FEET OF THE BOTTOM OF THE CASING PIPE OR DRILLED HOLE, THE CONTRACTOR WILL BE REQUIRED TO PERFORM DEWATERING PROCEDURES

### VII. PERMITTING:

a. REQUIRED RAILWAY CROSSING (MTS/BNSF) PERMITS INCLUDE BUT ARE NOT LIMITED TO TTRAFFIC CONTROL, ENCROACHMENT, SWPPP, ENVIRONMENTAL, AND THIRD-PARTY UTILITIES. FOLLOW MTS/BNSF REQUIREMENTS.

b. REQUIRED SIDEWALK/ROADWAY CROSSING PERMITS INCLUDE BUT ARE NOT LIMITED TO TTRAFFIC CONTROL, ENCROACHMENT, SWPPP, ENVIRONMENTAL, AND THIRD-PARTY UTILITIES. FOLLOW GOVERNING AGENCY REQUIREMENTS.

c. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING PERMITTING PACKAGE(S) TO GOVERNING AGENCIES FOR REVIEW AND APPROVAL.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed

## NOTES (CONT.):

VIII. **INSPECTION REQUIREMENTS:**

a. JACK & BORE: PUSH AN INSPECTION CAMERA THROUGH THE ENTIRE INSERTED CASING PIPE. ALL POTENTIAL OBSTRUCTIONS SHALL BE REMOVED PRIOR TO INSERTION OF THE CARRIER PIPE.

b. STANDBY REQUIREMENTS APPLY TO TRENCHLESS ALIGNMENTS THAT CROSS ELECTRIC AND/OR GAS LINES.

c. CONTRACTOR SHALL COORDINATE INSPECTION REQUIREMENTS WITH GOVERNING AGENCIES, UTILITY OWNERS, ROAD AND RAILWAY AGENCIES.

d. AN MTS REPRESENTATIVE SHALL BE PRESENT AT ALL TIME DURING CONSTRUCTION IN MTS ROW. WORK PERFORMED WITHOUT AN MTS INSPECTOR OR WITHOUT WRITTEN APPROVAL FROM MTS WILL NOT BE ACCEPTED.

IX. **WELDING:**

a. ANY AND ALL WELDING SHALL BE PERFORMED IN ACCORDANCE WITH STRUCTURAL WELDING CODE AWS D1.1 AND GREENBOOK SECTION 304-1.

b. WELDERS SHALL BE QUALIFIED IN ACCORDANCE WITH AWS QC7.

XI. **MANDREL TESTING:**

a. PERFORM MANDREL TESTING ON ALL PLASTIC PIPES TO CONFIRM DEFLECTION HAS NOT EXCEEDED 5% OF TOTAL LENGTH.

XII. **CASING PIPE MATERIAL:**

a. CASING PIPE SHALL BE STEEL MANUFACTURED IN ACCORDANCE WITH ASTM A53, GRADE A OR B.

b. PIPE CONNECTIONS SHALL BE WELDED CONNECTIONS.

c. COATINGS FOR CORROSION OR ABRASION RESISTANCE MAY BE REQUIRED BASED ON GEOTECHNICAL INVESTIGATION AT THE DETERMINATION OF THE ENGINEER.

XIII. **CARRIER PIPE MATERIALS:**

a. ACCEPTABLE MATERIALS INCLUDE PVC, PE OR HDPE.

b. PLASTIC PIPE SHALL BE DR 11 OR GREATER.

c. ALL JOINTS FOR HDD SHALL BE FUSHION TYPE

d. FOR APPLICATIONS WITHOUT A STEEL CASING, A CONDUCTIVE TRACER WIRE SHALL BE INSTALLED.

XIV. **BORING UNIT:**

a. BORING UNIT MUST BE OF SUFFICIENT SIZE TO MEET TORQUE REQUIREMENTS FOR TRENCHLESS INSTALLATION.

XV. **GROUT:**

a. VOID SPACE BETWEEN CASING AND CARRIER PIPE SHALL BE FILLED WITH CLSM PER SECTION 201-6 OF THE GREENBOOK.

XVI. **SUBMITTALS:**

a. WHEN A GEOTECHNICAL INVESTIGATION IS PERFORMED IT SHALL BE SUBMITTED TO SDG&E FOR RECORD PURPOSES.

b. DESIGN PLANS, SPECIFICATIONS AND CALCULATIONS FOR TEMPORARY SHORING AND SUB STRUCTURES SHALL BE SUBMITTED FOR REVIEW BY DISTRIBUTION ENGINEERING. ALL SUBMITTALS SHALL BE STAMPED BY A REGISTERED CIVIL ENGINEER WITH A MINIMUM 5 YEARS EXPERIENCE IN SIMILAR STRUCTURAL DESIGN.

1. INDICATE LOCATIONS OF ENTRY AND EXIT POINT, LAYDOWN AREAS, PROPOSED DRILL PATH ALIGNMENT (PLAN & PROFILE), LOCATION/ELEVATION OF PROPOSED CLEARANCES OF EXISTING UTILITIES AND STRUCTURES, PROPOSED COVER DEPTH, PRODUCT MATERIAL, ROW LINES, PROPERTY AND OTHER UTILITY ROW AND/OR EASEMENT LINES.
2. ESTABLISH SURVEY GRID FOR MONITORING GROUND SURFACE MOVEMENT DUE TO DRILLING OPERATIONS.

c. CONTRACTOR SHALL SUBMIT FOR REVIEW SHOP DRAWINGS FOR ALL PIPE AND FITTINGS TO BE USED ON THE PROJECT.

d. WELDING PROCEDURES FOR STEEL PIPE AND WELDER QUALIFICATIONS

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

| | Indicates Latest Revision | | Completely Revised | X | New Page | | Information Removed |
|---|---|---|---|---|---|---|---|

## NOTES (CONT.):

e. CONTRACTOR SHALL SUBMIT SCHEDULE OF ACTIVITY FOR REVIEW 15 DAYS PRIOR TO COMMENCEMENT OF WORK.

1. BORING ACTIVITIES WITHIN BNSF ROW SHALL CONTINUE 24 HOURS A DAY UNTIL THE WORK WITHIN ROW IS COMPLETED.

f. DETAILED AS-BUILT DRAWINGS INCLUDING THE MATERIAL, SIZE AND DEPTH OF THE PIPE ALONG THE ENTIRE TUNNEL SHALL BE RECORDED AND SUBMITTED BY THE CONTRACTOR TO SDG&E.

XVI. **SETTLEMENT MONITORING:**

a. SETTLEMENT SHALL MONITORED DURING TUNNELING PROCEDURES FOR THE PIPE ALIGNMENT AS WELL AS NEARBY STRUCTURES. SETTLEMENT MONITORING READINGS SHALL BE TAKEN PRIOR TO THE ZONE OF ACTIVE EXCAVATION, WHEN THE TUNNEL FACE REACHES THE MONITORING POINT, AND WHEN THE ZONE OF ACTIVE EXCAVATION HAS PASSED AND NO FURTHER MOVEMENT IS DETECTED.

b. IF SETTLEMENT IS DETECTED, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY, AND THE TUNNELING ACTIVITY SHALL BE HALTED UNTIL THE CAUSE OF THE SETTLEMENT CAN BE IDENTIFIED AND ADDRESSED.

XVIII. **UTILITY CROSSINGS:**

a. CONTACT DIG ALERT TWO (2) WORKING DAYS PRIOR TO BEGINNING INSTALLATION.

b. THE CONTRACTOR SHALL CHECK THE ENTIRE AREA OF THE INTENDED BORE BY SWEEPING AND/OR DIRECT CONNECTION WITH A PIPE LOCATOR TO VERIFY KNOWN SUBSTRUCTURES AND DETECT ANY UNKNOWN FACILITIES.

1. IDENTIFIED UTILITY CROSSINGS SHALL BE POTHOLED TO CONFIRM LOCATION, DEPTH AND PIPE SIZE.

XIX. **CLEANUP:**

a. THE CONTRACTOR SHALL REMOVE ALL TEMPORARY FACILITIES CONSTRUCTED ON PUBLIC ROW IN ADDITION TO DEBRIS, TRASH AND OTHER DELETERIOUS MATERIAL. CONTRACTOR SHALL NOTIFY THE GOVERNING AGENCY WITHIN 24 HOURS THAT ALL CONSTRUCTION HAS BEEN COMPLETED.

b. ENSURE THAT ALL DRILLING FLUIDS ARE DISPOSED OF IN A MANNER ACCEPTABLE TO THE GOVERNING AGENCIES.

## REFERENCE:

a. BNSF UTILITY ACCOMMODATION POLICY

b. MTS JACK AND BORE DESIGN CRITERIA, STANDARD CONSTRUCTION NOTES

c. ASTM A53, A716, F1962

d. AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

e. ASCE MANUAL NO. 27, MANUAL NO. 108

f. AWWA M11 STEEL PIPE DESIGN & INSTALLATION GUIDE

g. AWS WELDING STANDARDS D1.1, QC7

h. PLASTIC PIPE INSTITUTE: CH. 12 HDD

i. SDG&E EMPLOYEE HANDBOOK FOR PERSONAL PROTECTIVE EQUIPMENT

j. REFER TO GAS STANDARD D7255 FOR RAILWAY CROSSING REQUIREMENTS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed

**SCOPE:** THE SCOPE OF THIS STANDARD IS TO DETAIL THE REQUIREMENTS FOR THE JACK & BORE METHOD OF TRENCHLESS CONSTRUCTION.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

I. **VENT REQUIREMENTS:**

a. PROVIDE, OPERATE AND MAINTAIN AN OSHA-COMPLIANT VENTILATION SYSTEM FOR THE DURATION OF THE CASING PROJECT.

II. **CONTROLLING LINE AND GRADE:**

a. CONTINUOUSLY MONITOR LINE AND GRADE DURING INSTALLATION OF THE CASING PIPE.

b. MAXIMUM ALLOWABLE DEVIATION FROM LINE AND GRADE IS 1" PER 100'.

III. **ANNULAR SPACE:**

a. CONTRACTOR SHALL BE RESPONSIBLE FOR GROUTING THE ANNULAR SPACE BETWEEN SOIL AND THE CASING PIPE.

IV. **CARRIER PIPE:**

a. SPACERS SHALL BE NON-METALLIC, HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI. CONTRACTOR SHALL PROVIDE SPACERS AT REGULAR INTERVALS NOT TO EXCEED 5'.

V. **JACKING AND RECEIVING PIT:**

a. BRACING AND SUPPORT SYSTEM SHALL BE CONSTRUCTED OF DRIVEN STEEL SHEET PILINGS, STEEL SOLDIER BEAMS AND/OR STEEL PLATES.

b. CONTRACTOR'S WORK PLAN SHALL INCLUDE PROVISIONS FOR KEEPING WATER, ANIMALS AND OTHER UNWANTED THINGS FROM ENTERING THE PITS AND/OR CASING PIPE WHEN WORK IS AND IS NOT BEING PERFORMED.

c. PLACEMENT

1. LOCATION TO BE COORDINATED WITH SDG&E AND GOVERNING AGENCY.
2. ALL JACKING PITS FOR RAILWAY CROSSINGS SHALL BE SET-UP OUTSIDE OF RAILROAD ROW UNLESS OTHERWISE APPROVED BY BNSF/MTS.
3. JACKING PITS ARE PREFERRED TO BE LOCATED AS FAR AWAY FROM TRAVELED WAY AS FEASIBLE AND ARE TO BE COORDINATED WITH RESPONSIBLE/GOVERNING AGENCY.
4. ALL SHORING AND EQUIPMENT NEAR ROADWAYS AND RAILWAYS SHALL BE FENCED OFF AND CLEARLY MARKED WITH REFLECTORS.
5. CONTRACTOR TO PROVIDE ADEQUATE FENCING OR TYPE-K BARRIER (K RAILS).

VI. **BACKFILL:**

a. BACKFILL SHALL BE IN ACCORDANCE WITH GREENBOOK SECTION 300-4.

VII. **BACKSTOP PLATE:**

a. BACKSTOP PLATE DIMENSIONS SHOWN ON UG5030.2 ASSUME A MINIMUM OF 3' COVER OVER THE CASING PIPE, 30° INTERNAL SOIL FRICTION, NO COHESION, 125 POUNDS PER CUBIC FOOT (PCF) SOIL, AND A SKIN FRICTION OF 0.2, IF A GEOTECHNICAL REPORT IS PERFORMED, THE BACKSTOP DESIGN CAN BE OPTIMIZED BY THE ENGINEER.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed


SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1


TRENCHLESS CONSTRUCTION
JACK & BORE - REQUIREMENTS

UG5020.1

**SCOPE:** THIS STANDARD SHOWS THE HORIZONTAL AND VERTICAL LAYOUT OF JACK & BORE CONSTRUCTION.




PLAN VIEW




PROFILE VIEW

**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) MINIMUM COVER SHALL BE 3' UNLESS THERE IS A CONFLICT WITH OTHER REQUIREMENTS. (a)

(II) ALTERNATIVE BACKSTOP MATERIALS MAY BE SELECTED AT THE DISCRETION OF THE ENGINEER AND PENDING SDG&E APPROVAL.

**REFERENCE:**

(a) SEE REFERENCES ON UG5010.5

(b) SEE UG5060 FOR CASING BORE SECTION VIEWS.

(c) SEE DETAIL ON UG5030.2 FOR STANDARD BACKSTOP PLATE DIMENSIONS.

(d) REFER TO UG5020.5 FOR DESIGN ASSUMPTIONS.

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRENCHLESS CONSTRUCTION
JACK & BORE - LAYOUT

UG5030.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS TYPICAL BACKSTOP PLATE DIMENSIONS.





**FIGURE 1**
SIDE VIEW
BACKSTOP PLATE





**FIGURE 1**
TOP VIEW
BACKSTOP PLATE

**TABLE 1**

| BACKSTOP PLATE DIMENSIONS | | |
|---|---|---|
| **CASING NOMINAL DIAMETER** | **PLATE THICKNESS "Y"** | **PLATE HEIGHT & WIDTH "Z"** |
| 12" | 1 1/4" | 6'-0" |
| 16" | 1 3/8" | 6'-6" |
| 18" | 1 1/2" | 7'-0" |
| 20" | 1 5/8" | 7'-6" |
| 24" | 1 3/4" | 7'-9" |

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:** NONE

**REFERENCE:**

a. REFER TO UG5020 FOR UNDERLYING ASSUMPTIONS.

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised | X New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRENCHLESS CONSTRUCTION
JACK & BORE - LAYOUT

UG5030.2

TABLE OF CONTENTS

**SCOPE:** THE SCOPE OF THIS STANDARD IS TO DETAIL THE REQUIREMENTS FOR THE HORIZONTAL DIRECTIONAL DRILLING (HDD) METHOD OF TRENCHLESS CONSTRUCTION.

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

**I. SET-UP:**

a. IF PRACTICAL, ALL DRILLING EQUIPMENT SHALL BE SET-UP OUTSIDE OF RAILROAD OR ROADWAY ROW.

b. ALL SHORING AND EQUIPMENT NEAR ROADWAYS AND RAILWAYS SHALL BE FENCED OFF AND CLEARLY MARKED WITH REFLECTORS.

**II. DRILLING PILOT HOLE:**

a. CONTROLLING LINE AND GRADE

1. LINE AND GRADE SHALL BE VERIFIED AT A MINIMUM OF ONCE EACH DRILL ROD ADDITION AND ANY DEVIATIONS FROM THE PROPOSED LINE AND GRADE SHALL BE CORRECTED IMMEDIATELY.

b. DRILLING FLUID

1. DRILLING FLUID SHALL BE USED TO STABILIZE HOLE DURING DRILLING AND REAMING
2. DRILLING FLUID ADDITIVE MATERIALS SHALL BE CHEMICALLY INERT, BIODEGRADABLE AND NON-TOXIC SO AS TO NOT POLLUTE GROUNDWATER DURING THE TUNNELING PROCESS.
3. USE OF DRILLING FLUID SHALL BE MONITORED TO ENSURE FLUID IS NOT BEING LOST DURING DRILLING. IF THE RETURN OF FLUID IS MEASURED LESS THAN 95%, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND INVESTIGATE THE CAUSE OF FLUID LOSS.
4. PROPER DISPOSAL OF DRILLING FLUID SHALL BE THE RESPONSIBILITY OF THE TRENCHLESS CONTRACTOR. DEPENDING ON THE MIX IT MAY NEED TO BE DISPOSED OF AT A HAZARDOUS WASTE FACILITY.

c. BEND RADIUS

1. MINIMUM RADIUS OF CURVATURE FOR STEEL PIPE SHALL BE EQUAL TO 100 FEET PER INCH OF DIAMETER OF THE PIPE TO BE INSTALLED. FOR INSTANCE, A 24-INCH DIAMETER PIPE WOULD REQUIRE A MINIMUM RADIUS OF 2,400 FEET.
2. ALLOWABLE RADIUS OF CURVATURE FOR HDPE PIPE SHALL BE PROVIDED BY THE MANUFACTURER.

**III. REAM PILOT HOLE:**

a. PRE-REAMING BEFORE INSTALLATION OF THE CARRIER PIPE MAY NOT BE NECESSARY FOR SMALLER DIAMETER PIPES IN SOFT SOIL AT THE DETERMINATION OF THE ENGINEER.

b. THE REAMED HOLE SHALL BE SIZED TO APPROXIMATELY 1.5 TIMES THE DIAMETER OF THE CASING PIPE.

**IIV. CARRIER PIPE:**

a. PROVIDE AXIAL TENSION FORCE MONITORING. UTILIZE A "WEAK LINK" BREAKAWAY PULLER. AXIAL TENSION FORCE SHALL NOT EXCEED VALUES SHOWN IN TABLE 1.

b. PULL BACK OF THE CARRIER PIPE SHOULD BE DONE IN A SINGLE UNINTERRUPTED OPERATION. IF SPACE PERMITS, ALL SECTIONS OF HDPE SHOULD BE PRE-FUSED TO AVOID HALTING OF OPERATION FOR JOINT FUSING.

c. IF THE CARRIER PIPE IS HDPE, A STEEL CASING SHALL BE INSTALLED AT RAILWAY CROSSINGS.

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised [X] | New Page | Information Removed



SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRENCHLESS CONSTRUCTION
HDD - REQUIREMENTS

UG5040.1

## NOTES (CONT.):

### V. HDD PIPE MATERIALS AND CHARACTERISTICS:

a. CSE IS RESPONSIBLE FOR DESIGNING THE PIPE TO WITHSTAND PULLBACK LOADS WHICH INCLUDE TENSILE PULL FORCES, EXTERNAL HYDROSTATIC PRESSURE, TENSILE BENDING STRESSES, EXTERNAL SERVICE LOADS (POST-INSTALLATION SOIL, GROUNDWATER, AND SURCHARGE LOADS OCCURRING OVER THE LIFE OF THE PIPELINE).

b. SEE TABLE 1 FOR VALUES OF A716 DUCTILE IRON AND DR11 HDPE.

1. THE ALLOWABLE TENSILE FORCES FOR HDPE IN TABLE 1 ARE BASED ON DR11, 3XXX PE MATERIAL. THE VALUES ARE GIVEN FOR A DURATION OF CONTINUOUS LOADING OVER 12 HOURS AND FOR A PIPE TEMPERATURE OF 73°F. FOR OTHER TEMPERATURES, A TEMPERATURE COMPENSATING MULTIPLIER WILL BE REQUIRED. OTHER PE PIPE DESIGNATIONS AND MATERIALS MAY BE SELECTED BY THE CSE DURING THE PIPE DESIGN PROCESS.

**TABLE 1**

| DUCTILE IRON AND HDPE ALLOWABLE TENSILE FORCES | | |
|---|---|---|
| NOMINAL PIPE SIZE (INCHES) | ALLOWABLE TENSILE FORCE | |
| | DUCTILE IRON A716, Fy=42kips (KIPS) | HDPE (VI) DR11 12 HOUR PULL (KIPS) |
| 12 | N/A | 46 |
| 16 | 550 | 73 |
| 18 | 640 | 92 |
| 20 | 733 | 114 |
| 24 | 930 | 164 |
| 26 | N/A | 193 |

(VI) PE 3XXX STANDARD PE CODE DESIGNATION.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed




SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS


TRENCHLESS CONSTRUCTION
HDD - REQUIREMENTS

UG5040.2

**SCOPE:** THIS STANDARD SHOWS THE HORIZONTAL AND VERTICAL LAYOUT OF HORIZONTAL DIRECTIONAL DRILLING (HDD) CONSTRUCTION.




PLAN VIEW




PROFILE VIEW

**FIGURE 1**

**INSTALLATION:** NONE

**BILL OF MATERIALS:** NONE

**NOTES:**

(I) MINIMUM COVER SHALL BE 3' BELOW BASE OF PAVEMENT UNLESS THERE IS A CONFLICT WITH OTHER REQUIREMENTS. (b)

**REFERENCE:**

(a) FOR SECTION VIEWS, SEE UG5060 FOR CASING BORES OR UG5070 FOR EARTH BORES.

(b) SEE REFERENCES ON UG5010.5.

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| | Indicates Latest Revision | | Completely Revised | X New Page | Information Removed |

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

TRENCHLESS CONSTRUCTION
HDD - LAYOUT

UG5050.1

TABLE OF CONTENTS

**SCOPE:** THIS STANDARD SHOWS EXAMPLES OF CONDUIT CONFIGURATIONS THAT ARE ACCEPTABLE FOR CASING BORES.





**FIGURE 1**





**FIGURE 2**

## INSTALLATION:

(A) INSTALL PER SPACER MANUFACTURER'S REQUIREMENTS.
(B) INSTALL ONE SPACER EVER FIVE FEET OF TRENCHLESS ALIGNMENT.
(C) INSTALL TWO BANDS FOR EVERY SPACER (ONE ON EACH SIDE).

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | BORE SPACER, UNDERGROUND DEVICES CAT. NO. BS3509W2 | (B) | - | - | - |
| 2 | BORE SPACER, UNDERGROUND DEVICES CAT. NO. BS3926W2 | (B) | - | - | - |
| 3 | 5/8" WIDE X 0.03" THICK BANDS & BUCKLES | (C) | - | - | - |

## NOTES:

(I) MATERIAL SHALL BE MANUFACTURED BY UNDERGROUND DEVICES OR APPROVED EQUAL.
(II) CASING PIPE DIMENSIONS APPLY TO A 2- 4" CONDUIT CONFIGURATION.
(III) CASING PIPE DIMENSIONS APPLY TO A 4- 5" CONDUIT CONFIGURATION.
(IV) BANDS & BUCKLES SHALL BE 201 STAINLESS STEEL WITH ALUMINUM BREAKING STRENGTH = 1,875 POUNDS.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

SHEET 1 OF 1

TRENCHLESS CONSTRUCTION
SECTION VIEWS - CASING BORES

UG5060.1

**SCOPE:** THIS STANDARD SHOWS EXAMPLES OF CONDUIT CONFIGURATIONS THAT ARE ACCEPTABLE FOR EARTH BORES (NO CASING PIPE).





**FIGURE 1**
1 CONDUIT





**FIGURE 2**
2 CONDUITS

## INSTALLATION:

(A) INSTALL PER SPACER MANUFACTURER'S REQUIREMENTS.
(B) INSTALL ONE SPACER EVER FIVE FEET OF TRENCHLESS ALIGNMENT.
(C) INSTALL TWO BANDS FOR EVERY SPACER (ONE ON EACH SIDE).

## BILL OF MATERIALS:

| ITEM | DESCRIPTION | QUANTITY | STANDARD PAGE | STOCK NUMBER | DESIGN UNITS |
|---|---|---|---|---|---|
| 1 | CONDUIT SPACER (EARTH BORE) | (B) | - | - | - |
| 2 | 5/8" WIDE X 0.03" THICK BANDS & BUCKLES | (C) | - | - | - |

## NOTES:

(I) MATERIAL SHALL BE MANUFACTURED BY UNDERGROUND DEVICES OR APPROVED EQUAL.
(II) BANDS & BUCKLES SHALL BE 201 STAINLESS STEEL WITH ALUMINUM BREAKING STRENGTH = 1,875 POUNDS.

**REFERENCE:** NONE

TABLE OF CONTENTS

© 1998 - 2020 San Diego Gas & Electric Company. All Rights Reserved. Removal Of This Copyright Notice Without Permission Is Not Permitted Under Law.

| REV | CHANGE | DR | BY | DSN | APV | DATE | REV | CHANGE | DR | BY | DSN | APV | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C | | | | | | | F | | | | | | |
| B | | | | | | | E | | | | | | |
| A | ORIGINAL ISSUE | EDM | ARW | JES | CZH | 2/29/2020 | D | | | | | | |

Indicates Latest Revision | Completely Revised X | New Page | Information Removed

SHEET
1 OF 1

SDG&E ELECTRIC UNDERGROUND CONSTRUCTION STANDARDS

TRENCHLESS CONSTRUCTION
SECTION VIEWS - EARTH BORES

UG5070.1