2025 SERVICE STANDARDS & GUIDE

Historical Record: 6/2/2025 External Version



GENERAL INFORMATION	000
RESIDENTIAL, COMMERCIAL & INDUSTRIAL OVERHEAD	100
CUSTOMER-OWNED METER POLES	200
UNDERGROUND ELECTRIC SERVICE	300
ELECTRIC SERVICE & METERING EQUIPMENT	500
MEDIUM VOLTAGE ELECTRIC SERVICE & METERING EQUIPMENT	600
ELECTRIC TERMINATING ENCLOSURES, 0-600 VOLTS	700
CUSTOMER GENERATION	800
GAS	1000
DISCLAIMER & CONTACTS	
SUMMARY OF CHANGES	
DETAILED TABLE OF CONTENT	s
SERVICE ORDER TEAMS & REGIO PROJECT MANAGEMENT OFFICE	
PROJECT MANAGEMENT REGION BOUNDARY MAP	IAL
FREQUENTLY REFERENCED STANDARDS	
ALPHABETICAL SUBJECT INDE	X
SIGNIFICANT REVISION LIST	
SAN DIEGO AREA ELECTRICAI NEWSLETTER	

ATTENTION:

THESE STANDARDS WERE DEVELOPED FOR MAINTAINING SAFETY AND RELIABILITY OF THE ELECTRIC DISTRIBUTION AND SERVICE SYSTEMS.

THE INTENT OF THIS STANDARD IS TO GUIDE ENGINEERS, DESIGNERS/PLANNERS AND CONSTRUCTION PERSONNEL AND PROVIDE TYPICAL CONSTRUCTION METHODS FOR ELECTRIC DISTRIBUTION. NOT ALL ARRANGEMENTS ARE DEPICTED AND IT IS THE USER'S RESPONSIBILITY TO APPLY THESE STANDARDS APPROPRIATELY. ALL USERS MUST USE GOOD JUDGMENT. STANDARDS ARE UPDATED AS NEEDED. CONSULT EDE FOR LATEST VERSION. SDG&E STANDARDS MUST BE APPLIED. PRE-CONSTRUCTION APPROVAL OF A "DEVIATION REQUEST" IS REQUIRED FOR ANY EXCEPTION TO THESE STANDARDS. ANY ALTERATIONS, MODIFICATIONS OR IMPROVEMENTS TO THIS AND ALL STANDARDS MUST BE REVIEWED, APPROVED AND DOCUMENTED BY EDE-CONSTRUCTION STANDARDS AND DISTRICT C&O'S.

THE CPUC'S GENERAL ORDER 95 RULES/REQUIREMENTS ARE NOT INTENDED FOR USE AS COMPLETE CONSTRUCTION SPECIFICATIONS BUT EMPLOY ONLY THE MINUMUM REQUIREMENTS WHICH ARE MOST IMPORTANT FROM THE STANDPOINT OF **SAFETY AND RELIABILITY.** SDG&E MAY IMPOSE STRICTER RULES AND REQUIREMENT IN THE INTREST MAINTANANING SAFETY AND RELIABILITY OF OUR ELECTRICAL SYSTEM.

CONSTRUCTION SHALL BE ACCORDING TO ACCEPTED GOOD PRACTICE FOR GIVEN LOCAL CONDITIONS IN ALL SITUATIONS NOT SPECIFIED IN THE STANDARD.

SDG&E WILL NOT ACCEPT ANY SYSTEM DESIGN OR INSTALLATION WHICH DOES NOT CONFORM TO THESE STANDARDS DEVIATIONS CANNOT BE GRANTED WHICH CONFLICT WITH THE CPUC GENERAL ORDERS OR OTHER GOVERNING AGENCIES. THESE MAY INCLUDE SEPARATION FROM ENERGIZED FACILITIES AND WORKING CLEARANCES.

BASED ON UNUSUAL OR UNSAFE SITE CONDITIONS SDG&E MAY IN THE INTEREST OF SAFETY OR RELIABILITY REQUIRE CONSTRUCTION MEASURES BEYOND THOSE SPECIFICALLY STATED IN THIS MANUAL.

EXCEPT FOR A REQUIREMENT TO IMMEDIATELY ADOPT NEWLY PUBLISHED STANDARDS, THE APPLICATION OF NEWLY PUBLISHED STANDARDS IS REQUIRED FOR ALL WORK UP TO THE 30% PROJECT DESIGN APPROVAL LEVEL. ALL DESIGN AND CONSTRUCTION WORK AFTER 30% PROJECT DESIGN APPROVAL MAY USE CONSTRUCTION STANDARDS THAT IMMEDIATELY PRECEDE THE NEWLY UPDATED STANDARD, UNLESS THE IMMEDIATE ADOPTION OF NEWLY PUBLISHED STANDARDS IS MANDATED.

USE OF "BLOCK STOCK" MUST BE COORDINATED WITH INVENTORY & LOGISTICS AND IS GENERALLY ONLY APPLIED AS A "LAST RESORT" AFTER CONSULTATION AND AGREEMENT WITH STAKEHOLDERS AND AN ALTERNATE SOLUTION, SUPPLIER, MATERIAL OR METHOD IS DEEMED ACCEPTABLE AND AVAILABLE.

IF YOU HAVE ANY QUESTIONS REGARDING THE CONTENT OF THESE MANUALS, PLEASE EMAIL CONSTRUCTIONSTANDARDSADMINISTRATORS@SEMPRAUTILITIES.COM OR CONTACT:

SUMMARY OF CHANGES

DATE	STANDARD PAGES	QTY	FILE NAME
01/24/20	NEW FORMAT RELEASE	1	SG2020v0124.pdf
02/19/20	002	1	SG2020v0219.pdf
04/24/20	301, 320	2	SG2020v0424.pdf
05/22/20	001, 021, 022, 023, 024, INTERNAL SERVER UPGRADE	6	SG2020v0522.pdf
12/18/20	201, 202, 203, 204, 205, 206, 207, 208, 209, 210	10	SG2020v1218.pdf
01/22/21	COVER PAGE, DISCLAIMER	2	SG2021v0122.pdf
02/19/21	24, 301, (308 MOVED TO FMO)	3	SG2021v0219.pdf
07/23/21	301, 302, 303, 304, 305, 306, 307, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320	19	SG2021v0723.pdf
01/21/22	Cover Page	1	SG2022v0121.pdf
04/22/22	SG1, SG6	2	SG2022v0422.pdf
10/14/22	003, 524	2	SG2022v1014.pdf
12/22/22	005	1	SG2022v1222.pdf
01/20/23	COVER PAGE, DISCLAIMER, 006, 019, 806	5	SG2023v0120.pdf
04/21/23	004, 009, 011, 012	4	SG2023v0421.pdf
05/19/23	101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112	12	SG2023v0519.pdf
		4	SG2023v0623.pdf
06/23/23	013, 015, 016, Electrical Newsletter		•
08/25/23	311	1	SG2023v0825.pdf
09/22/23	306, 309	2	SG2023v0922.pdf
10/20/23	103, 303	2	SG2023v1020.pdf
11/22/23	104, 106, 109	3	SG2023v1122.pdf
12/21/23	019, 319	2	SG2023v1221.pdf
02/23/24	312, 315	2	SG2024v0223.pdf
06/07/24	018	1	SG2024v0607.pdf
11/22/24	DISCLAIMER, 018, 601, 602, 603, 604, 605, 606, 607, 608, 609, 701, 702, 703, 704, 705, 706, 707, 708, 709	20	SG2024v1122.pdf
01/24/25	107, 112, 303, 309, 320, 523	6	SG2025v0124.pdf
02/21/25	801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 522, 524, 525	34	SG2025v0221.pdf
03/21/25	001, 002, 003, 004, 005, 007, 008, 009, 010, 011, 012, 013, 014, 015, 016, 017, 020, 023, 024	19	SG2025v0321.pdf
04/25/25	1001, 1002, 1003, 1004, 1005, 1006, 1007, 1008, 1009, 1010, 1011, 1012, 1013, 1014, 1015		SG2025v0425.pdf
05/23/25	506	1	SG2025v0523.pdf
06/02/25	1005	1	SG2025v0602.pdf

INTRODUCTION

STANDARDS MANUAL OWNER CONTACT INFORMATION, TABLE OF CONTENTS, SERVICE ORDER TEAMS & REGIONAL PROJECT MANAGEMENT OFFICES, PROJECT MANAGEMENT REGIONAL BOUNDARY MAP, ALPHABETICAL SUBJECT INDEX, SIGNIFICANT REVISIONS LIST

SECTION 000 – GENERAL INFORMATION

DEFINITIONS OF TERMS, GENERAL INFORMATION, LINE TRUCK ACCESS

<u>SECTION 100 – RESIDENTIAL, COMMERCIAL & INDUSTRIAL OV</u>ERHEAD

OVERHEAD SERVICE INFORMATION

SECTION 200 – CUSTOMER-OWNED METER POLES

CUSTOMER-OWNED METER POLES & TEMPORARY SERVICE INSTALLATIONS

SECTION 300 – UNDERGROUND ELECTRIC SERVICE

UNDERGROUND ELECTRIC SERVICE INFORMATION

SECTION 500 – ELECTRIC SERVICE & METERING EQUIPMENT

GENERAL REQUIREMENTS, LOW VOLTAGE SERVICE & METERING REQUIREMENTS

SECTION 600 - MEDIUM VOLTAGE ELECTRIC SERVICE & METERING EQUIPMENT

SERVICE & METERING REQUIREMENTS FOR MEDIUM VOLTAGE SERVICE

<u>SECTION 700 – ELECTRIC TERMINATING ENCLOSURES, 0 – 600V</u>

GENERAL REQUIREMENTS FOR TERMINATING ENCLOSURES, CONDUCTOR IDENTIFICATION, PHASE ARRANGEMENT

<u>SECTION 800 – CUSTOMER GENERATION</u>

STAND-BY & DISTRIBUTED GENERATION

SECTION 1000 - GAS

GENERAL INFORMATION, GAS SERVICE & METERING EQUIPMENT, GAS SERVICE POLICIES & METER LOCATIONS, BARRICADES, GAS FACILITIES NEAR UG SUBSTRUCTURES

UG – UNDERGROUND CONSTRUCTION STANDARDS

PADS, GROUNDING, CONNECTORS, RETAINING WALLS & CLEARANCES, WIRELESS COMMUNICATIONS ATTACHMENT TO DISTRIBUTION POLE

ELECTRICAL NEWSLETTERS

INTERNATIONAL CODE COUNCIL (ICC) SAN DIEGO AREA ELECTRICAL NEWSLETTERS

	© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	С	IAH:	NGE	DR	BY	DSN	APV	DATE
С									F								
В	FORMAT	TINC	3	EDM	JIK	-	-	03/29/2022	Е								
Α	EDITORIAL (CHAN	NGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates Latest Revision Completely Revised New Page Information Removed																
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																

SHEET 1 OF 1

SG1

SCOPE: THIS STANDARD DETAILS SG SIGNIFICANT REVISIONS LIST.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. ENTIRE MANUAL
 - a. REVISED INFORMATION IN THE PAGE FOOTER TO INCLUDE DOCUMENT CHANGE HISTORY AND NUMBER OF SHEETS IN A SPECIFIC STANDARD.
 - b. ADDED A NEW TABLE OF CONTENTS AT THE BEGINNING OF EACH SECTION.
 - c. REPLACED EXISTING INDEX SECTIONS WITH NEW ALPHABETICAL SECTION INDEXES AT THE BEGINNING OF EACH SECTION.
 - d. ADDED STANDARD REFERENCES AT THE BOTTOM LEFT SIDE OF EACH PAGE, WHEN APPLICABLE.
 - e. INCREASED THE NUMBER OF PAGES NEEDED TO IMPROVE READABILITY.
 - f. CHANGED STANDARD TITLES WHEN NEEDED TO MORE ACCURATELY REFLECT THE SUBJECT.
- II. INTRODUCTION SECTION
 - a. ADDED SG6, SIGNIFICANT REVISIONS LIST.
- III. SECTION 000 GENERAL INFORMATION
 - a. DIVIDED "ELECTRIC SERVICE POLICIES NEW AND EXISTING CUSTOMER" (OLD PAGES 013.1 013.12) INTO FOUR NEW STANDARDS, AS FOLLOWS:
 - 1. "ELECTRIC SERVICE POLICIES NEW & EXISTING CUSTOMERS" (SG011)
 - 2. "ELECTRIC SERVICE POLICIES NEW PROJECT TYPES" (SG012)
 - 3. "ELECTRIC SERVICE POLICIES EXISTING CUSTOMER" (SG013)
 - 4. "ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS" (SG014)
 - b. ON PAGES SG012.1 AND SG013, TO ASSIST SDG&E PLANNERS AND CUSTOMERS IN THE PLANNING PHASE OF THEIR PROJECT, ADDED A NEW PARAGRAPH AS FOLLOWS:
 - 1. GENERAL SERVICE REQUIREMENT TO MULTIPLE MULTI-UNIT BUILDINGS ON A SINGLE PREMISES WHEN THERE IS MORE THAN ONE MULTI-UNIT BUILDING ON A SINGLE PREMISES, AN INDIVIDUAL SDG&E SERVICE IS GENERALLY REQUIRED TO EACH OF THE MULTI-UNIT BUILDINGS. BOTH RESIDENTIAL AND NON-RESIDENTIAL APPLICATIONS ARE SUBJECT TO THIS REQUIREMENT. REFER TO SG014 FOR FURTHER DETAIL.
- IV. SECTION 100 RESIDENTIAL, COMMERCIAL & INDUSTRIAL OVERHEAD
 - a. MOVED OLD PAGE 123 TO SG107.3 AND REVISED CONTENT TO CLARIFY THE 8-FOOT SERVICE DROP CLEARANCE AS SPECIFIED IN G.O. 95 THAT IS REQUIRED ABOVE BUILDINGS ON ADJACENT PREMISES EXCEPT AS DEFINED IN NOTES ON PAGE SG107.7.
- V. SECTION 200 CUSTOMER-OWNED METER POLES
 - a. NO SIGNIFICANT CHANGES.
- VI. SECTION 300 UNDERGROUND ELECTRIC SERVICE
 - a. NO SIGNIFICANT CHANGES.
- VII. SECTION 500 ELECTRIC SERVICE & METERING EOUIPMENT (NEW SECTION)
 - a. DIVIDED EXISTING SECTION 600 INTO TWO SECTIONS BY CREATING NEW SECTION 500 FOR LOW VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT AND CHANGING TERMINOLOGY FROM "HIGH" TO "MEDIUM" VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT IN SECTION 600.
 - b. HOUSEKEEPING PAD WITHIN A BUILDING MUST BE FLUSH WITH THE SERVICE EQUIPMENT. ADDED A NEW REQUIREMENT "WORKING SPACE FOR NON-RESIDENTIAL SERVICE PANELS REQUIRES A PERMANENT CONCRETE SLAB" ON PAGE SG504.5. THIS NEW REQUIREMENT REPLACES NOTE 5 ON OLD PAGE 604.1.
 - c. OLD PAGE 604.2 IS NOW NEW PAGE SG506.1. UNDER "DOORS", THE CALIFORNIA ELECTRIC CODE CHANGED THE REQUIREMENT FOR SERVICES RATED 1200A, OR MORE, TO NOW APPLY TO SERVICES RATED 800A, OR MORE.

	© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	CHANGE DR B				BY	DSN	APV	DATE	
С									F									
В	FORMAT	TING	3	EDM	JIK	-	-	03/29/2022	Е									
Α	EDITORIAL C	CHAN	IGES	-	LSM	LSM	TPM	11/01/2017	D									
	X Indicates Latest Revision Completely Revised New Page Information Removed																	
	SHEET SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	
	1 OF 2					CIC	NITE	TO A NIT D		~T/	NIC LICT	_					SG6	.1
	1 01 2					SIG	JIIL	TCAN L R	(FAT;	21(ons list							

- d. OLD PAGE 604.2, NEW PAGE SG506.1, UNDER "DEDICATED ELECTRICAL SPACE", EXCEPTION 2, HAS BEEN REVISED AS, "DRY PIPES AND/OR DUCTS NOT CONTAINING FLUIDS, AND INSTALLED FOR THE SOLE PURPOSE OF VENTING ARE PERMITTED WITHIN THE 6-FOOT (1.8M) ZONE."
- e. REMOVED THE COMMUNICATIONS INFORMATION FROM THE ILLUSTRATION ON PAGE SG510.3, OLD PAGE 607.3, REMOVED NOTE 6 FROM OLD PAGE 607.4, NEW PAGE SG510.4, AND ADDED "METERING COMMUNICATIONS" INFORMATION REFERENCING NEW PAGE SG525 AT THE BOTTOM OF PAGE SG510.4.
- f. REVISED THE HEADING "BUS TAP DRAWINGS FOR APPROVAL" ON PAGE SG517.1, OLD PAGE 623, TO "SWITCHBOARD BUS/WIRE TAP DRAWINGS FOR APPROVAL." ADDED A REQUIREMENT FOR BUS TAP DRAWINGS PREPARED BY A QUALIFIED ENGINEER WHENEVER MECHANICAL LUGS ARE BEING ADDED TO EXISTING BUS, OR MANUFACTURER INSTALLED WIRE CONDUCTORS ARE TO BE TAPPED.
- g. ADDED NEW PAGES SG524.8–10, "UNMETERED ELECTRIC SERVICE", TO PROVIDE A STANDARD FOR INSTALLATION OF A CUSTOMER-OWNED AND INSTALLED WIRELESS COMMUNICATIONS ANTENNA ATTACHMENT ON A DIRECT BURIAL OR FOUNDATION POLE WITH CONVENTIONAL LUMINAIRE FOR ROADWAY LIGHTING OWNED BY SDG&E.
- ADDED NEW PAGE SG525, "METERING COMMUNICATIONS", TO PROVIDE DIRECTION FOR ESTABLISHING EFFECTIVE METERING COMMUNICATIONS WHEN A METER LOCATION DOES NOT FACILITATE STANDARD "SMART METER" COMMUNICATION METHODS.

VIII. SECTION 600 - MEDIUM VOLTAGE ELECTRIC SERVICE & METERING EQUIPMENT

a. DIVIDED EXISTING SECTION 600 INTO TWO SECTIONS BY CREATING NEW SECTION 500 FOR LOW VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT AND CHANGING TERMINOLOGY FROM "HIGH" TO "MEDIUM" VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT IN SECTION 600.

IX. SECTION 700 - ELECTRIC TERMINATING ENCLOSURES, 0 - 600V

- a. REVISED "PHASE ARRANGEMENT" INFORMATION ON OLD PAGE 700, NEW PAGE, SG703, TO REQUIRE THE HIGH LEG TO BE IN THE "C" PHASE POSITION.
- b. EXPANDED OLD PAGE 707 INTO NEW PAGES SG707.1–2, "RESIDENTIAL SINGLE-PHASE MULTI-METER STACK". REVISED THE DESCRIPTION AT THE TOP OF THE PAGE BY ADDING "FACTORY-MANUFACTURED PULL CAN AND METER STACK(S)" AND, "THIS STANDARD DOES NOT APPLY TO FIELD INSTALLED PULL CANS WITH RACEWAYS AND CABLING TO INDIVIDUAL METER PANELS." ADDED A NEW NOTE 10 TO PAGE SG707.2, AS FOLLOWS:
 - 1. THE SDG&E PLANNER SHALL PROVIDE THE CUSTOMER WITH A COPY OF THIS STANDARD WITH THE ELECTRIC METER & SERVICE LOCATION FORM BECAUSE IT IS A SPECIAL APPLICATION. IT IS IMPORTANT FOR THE CUSTOMER TO UNDERSTAND THE EQUIPMENT MUST BE FACTORY-MANUFACTURED WITH HORIZONTAL BUSSING FROM THE PULL CAN TO THE METERING SECTION(S).

XI. SECTION 800 - CUSTOMER GENERATION

a. MODIFIED PAGE SG806.13 PER NEW 36-INCH CLEARANCE REQUIREMENTS SPECIFIED ON PAGES SG1007.1-4.

XII. SECTION 1000 - GAS

2 OF 2

- a. ADDED A DEFINITION FOR LARGE GAS FIELD SERVICE VEHICLE ACCESS ON PAGE SG1003.1.
- b. ADDED "SIGNAGE REQUIREMENTS FOR GAS SERVICE LOCATIONS ON MULTI-TENANT BUILDINGS" ON PAGES SG1003.2-3.
- c. CHANGED "WELD HOLE" TO "TIE-IN HOLE" ON PAGES SG1004.1-2.
- d. CHANGED "NUMBER OF SERVICES ALLOWED TO A BUILDING NEW PROJECTS" TO "GAS SERVICE POLICY FOR NEW PROJECTS NUMBER OF SERVICES ALLOWED", ON PAGES SG1006.2–3 (OLD PAGE 1007), REFORMATTED THIS SECTION, AND CHANGED THE TITLES OF SUBSECTIONS 1, 3, AND 4.
- e. OLD PAGES 1008.1-2 ARE NOW PAGES SG1007.1-5, WITH NEW 36-INCH CLEARANCE REQUIREMENTS FROM GAS RISER.
- f. OLD PAGES 1008.3–4 ARE NOW PAGES SG1008.1–3, WITH THE LATEST PRODUCT INFORMATION, ILLUSTRATIONS AND MANUFACTURER'S CONTACT INFORMATION. ON PAGE SG1008.1, THE NEW 36-INCH CLEARANCE REQUIREMENTS FROM GAS RISER ARE SPECIFIED.
- g. TABLES ON OLD PAGES 1010 AND 1011 HAVE BEEN REVISED AND ARE NOW ON PAGES SG1009.2 AND SG1009.3.
- h. OLD PAGES 1241-1243 ARE NOW PAGES SG1012.1-4.
- . ADDED NEW PAGE SG1010.8, "ADEQUATE SUPPORT FOR WALL-MOUNTED METER HEADERS", TO THE "GAS METERS GROUPED ON METER HEADERS" STANDARD.

	© 1998 - 2022 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHANGE			DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С									F						
В	FORMAT	TING	j .	EDM	JIK	-	-	03/29/2022	Е						
Α	EDITORIAL C	CHAN	NGES	-	LSM	LSM	TPM	11/01/2017	D						
	X Indicates Latest Revision Completely Revised New Page Information Removed														
	CHEET				SDG	&E E	LECT	RIC SERVIC	E STA	ANDARDS & GUIDES					
SHEET SHOULD SHANDARD & GOIDES											Ī	SG6 2			

SIGNIFICANT REVISIONS LIST

<u>PAGE</u>	SUBJECT
002	GENERAL INFORMATION ALPHABETICAL SUBJECT INDEX
003	DEFINITIONS OF TERMS
004	GENERAL INFORMATION
005	LISTING OF LOCKSMITHS AUTHORIZED TO SELL SCHLAGE RESTRICTED VTQP QUAD SECTION KEYWAYS AND THE SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY
006	UTILITY'S CONTRIBUTION TO FAULT CURRENT
007	SDG&E TRANSFORMER FUSING INFORMATION
008	UTILITY'S CONTRIBUTION TO FAULT CURRENT – SECONDARY VOLTAGE SERVICE EXAMPLES
009	TRANSFORMER VAULTS
010	TESTING REQUIREMENTS FOR METAL-ENCLOSED SERVICE ENTRANCE AND UNMETERED FEEDER BUSWAYS
011	ELECTRIC SERVICE POLICIES - NEW AND EXISTING CUSTOMERS
012	ELECTRIC SERVICE POLICIES - NEW PROJECT TYPES
013	ELECTRIC SERVICE POLICIES – EXISTING CUSTOMER
014	ELECTRIC SERVICE POLICIES – EXISTING CUSTOMER FEEDER EXCEPTIONS
015	LINE TRUCK ACCESS REQUIREMENTS
016	PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES
017	PLAQUE SPECIFICATIONS AND EXAMPLES
018	MEDIUM-VOLTAGE CONDUCTOR CLEARANCES FOR NON-UTILITY WORKERS AND EQUIPMENT
019	CLEARANCES OF OVERHEAD FACILITIES FROM TANKS CONTAINING $\frac{A}{A}$ FLAMMABLE OR EXPLOSIVE MIXTURE
020	PRODUCT DISTRIBUTORS
021	SERVICE ORDER TEAMS AND REGIONAL PROJECT MANAGEMENT OFFICES
022	PROJECT MANAGEMENT REGIONAL BOUNDARY MAP
023	FREQUENTLY REFERENCED STANDARDS
024	ALPHABETICAL SUBJECT INDEX

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F						
В	FORMATTING	EDM	JIK	-	-	05/22/2020	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/1/2017	D						·

SHEET 1 OF 1 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GENERAL INFORMATION TABLE OF CONTENTS

SG001.1

<u>s</u>	UBJECT													<u>P</u>	PAGE
Α	CCESSIBILITY														004.4
Α	CCESSIBLE METER	R LOCATIONS													005.1
Α	DDING LOAD TO E	EXISTING METE	R PAI	IELS .											004.2
Α	DDRESSING CONV	ENTIONS													004.5
В	ILLING ACCOUNT	ESTABLISHMEN	IT – A	PPLIC	CATIO	N FO	R A BILLIN	G ACC	COUNT				0	03.1,	004.2
С	HARACTER OF SEI	RVICE													004.3
С	LEARANCES OF O	VERHEAD FACIL	ITIES	FRO	IAT M	NKS C	ONTAININ	G FLA	MMABLE OR EX	(PLOSIVE MIXTURE	·				019
С	LEARANCES, MED	IUM-VOLTAGE (COND	исто	R CLE	EARAN	NCES FOR I	NON-l	JTILITY WORK	ERS & EQUIPMENT					018
C	CONNECTION OR D	DISCONNECTION	N OF	SERVI	ICE										004.4
D	EFINITIONS OF T	ERMS													003
		ELECTRIC SERV	ICE P	OLIC:	IES –	EXIS ⁻	TING CUST	OMER	REQUESTING	ADDITIONAL SERV	ICES	OR			
R	EMOTE METER LC	CATIONS													013
	GENERAL SER	VICE REQUIREN	1ENT	то м	ULTIF	PLE M	ULTI-UNIT	BUIL	DINGS ON A SI	NGLE PREMISES					013.1
	MULTI-FAMILY	RESIDENTIAL	BUILI	DINGS	5 – LE	SS TH	HAN 3 STO	RIES	HIGH						013.1
	RESIDENTIAL	CONTIGUOUS I	OWEL	LINGS	5 – TC	OWNH	IOUSES (RO	H WC	OMES)						013.1
	RESIDENTIAL	OR MIXED USE	BUIL	DING	S – 3	STOR	IES OR GR	EATE	R						013.1
	SINGLE PREMI	SES – MULTIPL	E NO	N-RES	SIDEN	TIAL	ENTERPRI	SES							013.2
	SINGLE PREMI	SES – MULTIPL	E RES	SIDEN	ITIAL	CUST	OMERS								013.3
	SINGLE PREMI	SES - SINGLE N	NON-F	RESID	ENTI	AL EN	TERPRISE								013.2
	SINGLE PREMI	SES – SINGLE F	RESID	ENTI	AL CU	STOM	1ER WITH	OTHE	R ELECTRIC US	ES					013.3
Е	LECTRIC SERVICE	POLICIES – EX	ISTIN	G CU	STOM	ER FE	EDER EXC	EPTIC	NS						014
Е	LECTRIC SERVICE	POLICIES - NE	W AN	D EXI	ISTIN	G CUS	STOMERS .								011
	ALTERNATE SE	ERVICE DELIVE	RY PO	INT F	REQUE	STS									011.2
	GENERAL INFO	DRMATION													011.1
	GENERAL REQ	UIREMENTS													011.1
	© 1998 - 2025 Sa	an Diego Gas & Ele	ectric C	ompai	ny. All	rights r	eserved. Rei	moval o	of this copyright no	tice without permission	is not	permit	ted und	der law	
C C	CHAN	GE	DR	ВҮ	DSN	APV	DATE	REV	Cl	HANGE	DR	BY	DSN	APV	DATE
В	FORMAT	TING	EDM	JIK	JTM	KRG	02/26/2025								
Α	EDITORIAL (CHANGES	-	LSM	LSM		11/01/2017								
•		X Indicates La	atest R				npletely Rev		New Page	Information Re	moved			'	
	SHEET			SDC	S&E E	LECTI	RIC SERVIC	CE STA	ANDARDS & GU	IDES			_		2.4
	1 OF 3								MATION JECT INDEX	(S	G00	2.1

RIGHTS OF WAY	<u>SUBJECT</u>	<u>PAGE</u>
SERVICE LOCATIONS	RIGHTS OF WAY	011.2
ELECTRIC SERVICE POLICIES – NEW PROJECT TYPES	SECONDARY SERVING VOLTAGES AND CLASSIFICATION OF SERVICE INFORMATION	011.3
GENERAL SERVICE REQUIREMENT TO MULTIPLE MULTI-UNIT BUILDINGS ON A SINGLE PREMISES	SERVICE LOCATIONS	011.2
MULTI-FAMILY RESIDENTIAL BUILDINGS – LESS THAN 3 STORIES HIGH	ELECTRIC SERVICE POLICIES – NEW PROJECT TYPES	012
RESIDENTIAL CONTIGUOUS DWELLINGS – TOWNHOUSES (ROW HOMES)	GENERAL SERVICE REQUIREMENT TO MULTIPLE MULTI-UNIT BUILDINGS ON A SINGLE PREMISES	012.1
RESIDENTIAL OR MIXED USE BUILDINGS – 3 STORIES OR GREATER	MULTI-FAMILY RESIDENTIAL BUILDINGS - LESS THAN 3 STORIES HIGH	012.1
SINGLE PREMISES – MULTIPLE RESIDENTIAL CUSTOMERS	RESIDENTIAL CONTIGUOUS DWELLINGS - TOWNHOUSES (ROW HOMES)	012.1
SINGLE PREMISES – SINGLE NON-RESIDENTIAL ENTERPRISE	RESIDENTIAL OR MIXED USE BUILDINGS – 3 STORIES OR GREATER	012.1
SINGLE PREMISES – SINGLE RESIDENTIAL CUSTOMER WITH OTHER ELECTRIC USES	SINGLE PREMISES – MULTIPLE RESIDENTIAL CUSTOMERS	012.3
SINGLE-PREMISES – MULTIPLE NON-RESIDENTIAL ENTERPRISES	SINGLE PREMISES – SINGLE NON-RESIDENTIAL ENTERPRISE	012.2
EQUIPMENT RESPONSIBILITIES – CUSTOMER AND SDG&E	SINGLE PREMISES – SINGLE RESIDENTIAL CUSTOMER WITH OTHER ELECTRIC USES	012.3
FAULT CURRENT, UTILITY'S CONTRIBUTION — SECONDARY VOLTAGE SERVICE EXAMPLES	SINGLE-PREMISES – MULTIPLE NON-RESIDENTIAL ENTERPRISES	012.2
FAULT CURRENT, UTILITY'S CONTRIBUTION – SECONDARY VOLTAGE SERVICE EXAMPLES	EQUIPMENT RESPONSIBILITIES - CUSTOMER AND SDG&E	004.4
GAS AND ELECTRIC METER ACCESS	FAULT CURRENT, UTILITY'S CONTRIBUTION	006
GENERAL INFORMATION	FAULT CURRENT, UTILITY'S CONTRIBUTION – SECONDARY VOLTAGE SERVICE EXAMPLES	008
INACCESSIBLE METER LOCATIONS	GAS AND ELECTRIC METER ACCESS	005.1
LINE TRUCK ACCESS REQUIREMENTS	GENERAL INFORMATION	004
LOCKSMITHS, LISTING OF	INACCESSIBLE METER LOCATIONS	005.1
MARKOUT SERVICE	LINE TRUCK ACCESS REQUIREMENTS	015
MEDIUM-VOLTAGE CONDUCTOR CLEARANCES FOR NON-UTILITY WORKERS AND EQUIPMENT	LOCKSMITHS, LISTING OF	005.1 – 005.2
PERMIT AND INSPECTION	MARKOUT SERVICE	004.5
	MEDIUM-VOLTAGE CONDUCTOR CLEARANCES FOR NON-UTILITY WORKERS AND EQUIPMENT	018
PLAQUE SPECIFICATIONS AND EXAMPLES	PERMIT AND INSPECTION	004.2
	PLAQUE SPECIFICATIONS AND EXAMPLES	017

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

					_								
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						·
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 2 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GENERAL INFORMATION ALPHABETICAL SUBJECT INDEX

SG002.2

SUBJECT	<u>PAGE</u>
PRODUCT DISTRIBUTORS	020
PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES	016
PURPOSE	004.1
REQUEST FOR SERVICE	004.2
SAMPLE PLAQUE FOR ELECTRICAL EQUIPMENT LABELS	017.1
SCOPE	004.1
SDG&E TRANSFORMER FUSING INFORMATION	007.1
SEALING OF METER AND SERVICE FACILITIES	004.4
SECONDARY FAULT CURRENT CALCULATIONS	006.1 – 006.2
SECONDARY SERVING VOLTAGES AND CLASSIFICATION OF SERVICE INFORMATION	011.3
SERVICE DELIVERY POINT POLICY	011.1
SERVICE PLANNING	004.1
TESTING REQUIREMENTS FOR METAL-ENCLOSED SERVICE ENTRANCE AND UNMETERED FEEDER BUSWAYS	010
TRANSFORMER FUSING INFORMATION, SDG&E	007
TRANSFORMER VAULTS	009
TRENCH INSPECTIONS	004.5
TYPICAL PLAQUE FOR EXISTING BUILDINGS WITH INTERMIXED SERVICES	017.3
TYPICAL PLAQUE FOR NEW BUILDINGS OR EXISTING BUILDINGS WITH SEPARATE SERVICE AREAS	017.2
UTILITY'S CONTRIBUTION TO FAULT CURRENT	006.1 – 006.2
UTILITY'S CONTRIBUTION TO FAULT CURRENT – SECONDARY VOLTAGE SERVICE EXAMPLES	008
WORK ON UTILITY-OWNED POLES	004.4

@ 1009 2025 San Diogo Goo & Electric Company	All rights reserved. Removal of this copyright notice without	permission is not permitted under law
© 1990 - 2020 San Diego Gas & Electric Company	All rights reserved. Removal of this copyright hotice without	permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е			•			
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GENERAL INFORMATION ALPHABETICAL SUBJECT INDEX

SG002.3

SCOPE: THIS STANDARD DEFINES THE VARIOUS TERMS USED IN THE SERVICE STANDARDS AND GUIDE MANUAL.

DEFINITIONS:

- APPROVED: ACCEPTABLE AND IN CONFORMANCE WITH SDG&E'S (UTILITY'S) RULES AND POLICIES AND GOVERNMENTAL AUTHORITIES' HAVING JURISDICTION (AHJ'S) LAWS, CODES, AND ORDINANCES.
- **BILLING ACCOUNT ESTABLISHMENT:** A REQUEST TO THE UTILTY FOR ELECTRIC AND/OR GAS SERVICE AS DISTINGUISHED FROM AN INQUIRY AS TO THE AVAILABILITY OF OR CHANGES FOR SUCH SERVICE. CONTACT THE UTILITY'S CUSTOMER CONTACT CENTER AT 1-800-411-7343, TO "MAKE APPLICATION" FOR A BILLING ACCOUNT AS SOON AS THE STREET ADDRESS HAS BEEN ASSIGNED BY THE AHJ.
- **BUILDING:** NORMALLY A STRUCTURE WHICH STANDS ALONE AND IS USED OR INTENDED FOR SUPPORTING OR SHELTERING ANY USE OR OCCUPANCY. WHENEVER THERE IS A QUESTION WHETHER OR NOT THE STRUCTURE IS A SEPARATE BUILDING, THE APPROPRIATE AHJ SHALL MAKE THAT DETERMINATION.
- CUSTOMER GENERATION: PRODUCTION OF ELECTRICAL ENERGY NOT GENERATED BY THE UTILITY.
- FINAL GRADE: THE GRADE AFTER PAVING OR IMPROVEMENTS HAVE BEEN COMPLETED.
- GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ): SEE INSPECTION AUTHORITY.
- INSPECTION AUTHORITY: AN AGENCY RESPONSIBLE FOR ISSUING PERMITS, MAKING INSPECTIONS OF THE CUSTOMER'S ELECTRICAL WIRING SYSTEM (PREMISES WIRING), AND NOTIFYING THE UTILITY THAT SUCH WIRING AND SYSTEM COMPONENTS MEET THE CRITERIA ENFORCED BY THE AGENCY. INSPECTION AUTHORITIES INCLUDE CITY, COUNTY, STATE, AND FEDERAL AGENCIES, INDIAN RESERVATIONS AUTHORIZED TO MAKE ELECTRICAL INSPECTIONS, APPROPRIATE SECTIONS OF SCHOOL, PORT, TRANSIT, AND WATER DISTRICTS AND OTHER ENTITIES WITH LEGAL JURISDICTION OVER PREMISES WIRING.
- METER ROOM: A WEATHERPROOF, ILLUMINATED ROOM PROVIDED BY THE CUSTOMER AT THEIR OPTION AND APPROVED BY SDG&E FOR THE LOCATION OF ELECTRIC METERING EQUIPMENT.
- METER SEQUENCE: THE SEQUENTIAL RELATIONSHIP BETWEEN THE SERVICE SWITCH AND THE UTILITY'S BILLING METER IN A SERIES ARRANGMENT.
- HOT SEQUENCE: A METER-SWITCH-FUSE SEQUENCE.
- **COLD SEQUENCE:** A SWITCH-FUSE-METER-SEQUENCE.
- **METERED CIRCUITS:** THOSE CONDUCTORS EXTENDED FROM THE METER AND OTHER SERVICE EQUIPMENT TO THE LOADS OR OUTLETS CONNECTED TO SUCH CIRCUITS. METERED CIRCUITS ARE NOT PERMITTED TO SERVCE ANOTHER PREMISE.
- **PREMISES:** ALL OF THE REAL PROPERTY AND APPARATUS EMPLOYED IN A SINGLE ENTERPRISE ON AN INTEGRAL PARCEL OF LAND UNDIVIDED, EXCEPT IN THE CASE OF INDUSTRIAL, AGRICULTURAL, OIL FIELDS, RESORT ENTERPRISES AND PUBLIC OR QUASI-PUBLIC INSTITUTIONS DIVIDED BY A DEDICATED STREET, HIGHWAY, OR OTHER PUBLIC THOROUGHFARE, OR A RAILWAY. AUTOMOBILE PARKING LOTS CONSITUTING A PART OF, AND ADJACENT TO, A SINGLE ENTERPRISE MAY BE SEPARATED BY AN ALLEY FROM THE REMAINDER OF THE PREMISES SERVED.
- **PREMISES AGRICULTURAL:** REAL PROPERTY USED FOR AGRICULTURAL PURPOSES WHERE SPRINKLERS, SPRAYERS, PORTABLE IRRIGATION PIPE, ETC. ARE USED, INCLUDING PROPERTY IN AN AGRICULTURAL AREA NOT UNDER CULTIVATION, WHICH IS CAPABLE OF BEING TRAVERSED BY VEHICLES OR AGRICULTURAL EQUIPMENT.
- **PREMISES COMMERCIAL:** REAL PROPERTY FROM WHICH SERVICES ARE OFFERED AND RENDERED TO THE PUBLIC, OR FROM WHICH PRODUCTS ARE SOLD AND DISTRIBUTED FOR GAIN, INCLUDING PREMISES WHERE RESIDENTIAL UNITS ARE COMBINED WITH COMMERCIAL ENTERPRISES. FOR RESIDENTIAL LIVING UNITS EXCEEDING TWO IN NUMBER ON THE SAME PREMISES, SEE "PREMISES-RESIDENTIAL."
- **PREMISES IDENTIFICATION:** APPROVED NUMBERS OR ADDRESSES TO BE PLACED FOR ALL NEW BUILDINGS OR STRUCTURES IN SUCH A POSITION AS TO BE PLAINLY VISIBLE AND LEGIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY.
- PREMISES INDUSTRIAL: REAL PROPERTY UPON WHICH AN ENTERPRISE IS ENGAGED IN PROCESSSING OR MANUFACTURING
 RAW OR UNFINISHED MATERIALS INTO ANOTHER FORM OR PRODUCT.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	C	HAN	IGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGE	EDM	IWA	JTM	KRG	02/26/2025	F								
В	2022 FORMAT UPDATE	ARC	JIK	IPJ	KRG	09/29/2022	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates	Latest F				npletely Revi		New Page	IIDE	Information Re	moved				
	SHEET		SDC	3&E E	LECTI	RIC SERVIC	LE STA	NDARDS & GL	וחונ	<u> </u>			_	C001	
	1 OF 3	DEFINITIONS OF TERMS													3.1

- PREMISES RESIDENTAL: REAL PROPERTY USED SOLEY FOR RESIDENTIAL PURPOSES AND COMPLYING WITH THE FOLLOWING PROVISIONS:
 - I. PREMISES FROM WHICH SERVICES ARE NOT OFFERED OR RENDERED TO THE PUBLIC, OR FROM WHICH PRODUCTS ARE NOT COMMERCIALLY PRODUCED, SOLD, OR DISTRIBUTED FOR GAIN.
 - II. PREMISES UPON WHICH ANY COMBINATION OF RESIDENTIAL LIVING UNITS DOES NOT EXCEED TWO IN NUMBER, WHETHER ON ONE LEVEL OR MORE.

RESIDENTIAL LIVING UNITS EXCEEDING TWO IN NUMBER ON THE SAME PREMIS ES ARE CLASSIFIED AS A COMMERICAL ENTERPRISE AND COMMERCIAL PREMISES REQUIRING COMMERICAL SERVICE DROP CLEARANCES: HOWEVER, METERING PROVISIONS FOR INDIVIDUAL LIVING UNITS SHALL COMPLY WITH RESIDENTIAL REQUIREMENTS. (a)

- PULL BOX: A SUBSURFACE BOX, USUALLY CONCRETE, USED FOR PULLING OR SPLICING UTILITY CABLES. ALSO KNOWN AS A HANDHOLE. (NOT TO BE USED TO TERMINATE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS.)
- PULL CAN: A WALL-MOUNTED ENCLOSURE USED FOR PULLING, ROUTING, OR CONNECTING THE UTILITY'S SERVICE CONDUCTORS TO THE CUSTOMER'S SERVICE EQUIPMENT.
- PULL SECTION: AN UNDERGROUND PULL SECTION (UGPS) IS A SEPARATE COMPARTMENT OF A FREESTANDING, METAL OR METALCLAD SWITCHBOARD, WHICH IS USED FOR CONNECTING THE UTILITY'S SERVICE CONDUCTORS TO THE CUSTOMER'S SERVICE EOUIPMENT.
- READILY ACCESSIBLE: CAPABLE OF BEING REACHED QUICKLY AND CONVENIENTLY 24 HOURS A DAY FOR CONSTRUCTION, OPERATION, MAINTENANCE, INSPECTION, TESTING, OR READING, WITHOUT REQUIRING THOSE SEEKING ACCESS TO CLIMB OVER OR REMOVE OBSTACLES, OR TO OBTAIN SPECIAL PERMISSION OR SECURITY CLEARANCES.
- SERVICE DELIVERY POINT: THE POINT OF CONNECTION OF THE UTILITY'S SERVICE CONDUCTORS AND THE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS.
- SERVICE DROP CONDUCTORS: THE UTILITY'S OVERHEAD CONDUCTORS EXTENDING FROM ITS POLE LINE TO THE POINT OF SERVICE DROP SUPPORT ON A BUILDING OR STRUCTURE.
- SERVICE ENTRANCE CONDUCTORS OVERHEAD: THE CUSTOMER'S CONDUCTORS OR BUS BARS EXTENDING FROM THE SERVICE EQUIPMENT TO THE POINT OF CONNECTION TO THE UTILITY'S SERVICE DROP CONDUCTORS.
- SERVICE ENTRANCE CONDUCTORS UNDERGROUND: ALL CONDUCTORS OR BUS BARS INSTALLED BY THE CUSTOMER BEYOND AND INCLUDING THE POINT OF CONNECTION TO THE UTILITY'S SERVICE LATERAL CONDUCTORS.
- SERVICE LATERAL: THE UNDERGROUND SERVICE LATERAL CONDUCTORS IN THE CUSTOMER'S CONDUIT, INSTALLED BY THE UTILITY FROM THE DESIGNATED SOURCE TO THE POINT OF CONNECTION WITH THE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS.
- SERVICE POINT: THE POINT OF CONNECTION BETWEEN THE FACILITIES OF THE SERVING UTILITY AND THE PREMISES WIRING.
- SHALL AND WILL: THROUGHOUT THIS SERVICE STANDARDS & GUIDES, "SHALL" AND "WILL" ARE USED TO INDICATE THE MORE RIGID REQUIREMENTS OF THE UTILITY OR AHJ.
- SHOULD AND MAY: THROUGHOUT THIS SERVICE STANDARDS & GUIDES, "SHOULD" AND "MAY" ARE USED TO INDICATE RECOMMENDATIONS, OR THAT WHICH IS ADVISED BUT NOT NECESSARILY REQUIRED.
- SINGLE ENTERPRISE: A SEPARATE BUSINESS OR OTHER INDIVIDUAL ACTIVITY CARRIED ON BY A CUSTOMER. THE TERM DOES NOT APPLY TO ASSOCIATIONS OR COMBINATIONS OF CUSTOMERS. ONE PERSON MAY BE CONDUCTING SEVERAL ACTIVITES OF WHICH ONE ACTIVITY MAY BE A SINGLE ENTERPRISE.
- SUBMETERS: CUSTOMER-FURNISHED, -INSTALLED, -OWNED, AND -MAINTAINED METERS BEHIND A MASTER UTILITY METER. RESIDENTIAL SUBMETERS MAY BE PERMITTED IN CERTAIN SPECIAL CIRCUMSTANCES. SUBMETERING OF NON-RESIDENTIAL SERVICE IS PROHIBITED.
- TERMINATING ENCLOSURE: A UTILITY-APPROVED PULL CAN OR PULL SECTION AT THE SERVICE DELIVERY POINT FOR CONNECTING THE UTILITY'S UNDERGROUND SERVICE LATERAL CONDUCTORS AND THE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS. (b) (c)

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights r	eserved. Rer	noval o	of th	is copyright no	tice	without permission	is not	permit	ted und	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	IAN	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F									
В	2022 FORMA	T UPI	DATE	ARC	JIK	IPJ	KRG	09/29/2022	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Rea	moved				
	SHEET				SDC	S&E E	LECTI	RIC SERVIC	E STA	ANE	ARDS & GL	IDI	ES					
	2 OF 3							INITION	C 01		EDMC					S	G00	3.2

DEFINITIONS OF TERMS

- UTILITY METERS: UTILITY-FURNISHED, -INSTALLED, -OWNED, AND -MAINTAINED METERS USED TO MEASURE CONSUMPTION FOR BILLING PURPOSES.
- UTILITY'S OPERATING CONVENIENCE: THE UTILIZATION, UNDER CERTAIN CIRCUMSTANCES, OF FACILITIES OR PRACTICES NOT ORDINARILY EMPLOYED WHICH CONTRIBUTE TO THE OVERALL EFFICIENCY OF THE UTILITY'S OPERATIONS.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES: NONE **REFERENCE:**

- a) FOR UTILITY'S CONTRIBUTION TO FAULT CURRENT VALUES, SEE SG006.
- (b) FOR 0-600V TERMINATING ENCLOSURES, SEE SG703.
- (c) for switchgear underground service terminating pull sections, see SG608.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F						
В	2022 FORMAT UPDATE	ARC	JIK	IPJ	KRG	09/29/2022	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision		Completely Revised		New Page		Information Removed					
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES											

DEFINITIONS OF TERMS

SG003.3

SCOPE: THIS STANDARD PROVIDED GENERAL INFORMATION REGARDING THE SERVICE STANDARDS AND GUIDE MANUAL.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

PURPOSE:

- SAN DIEGO GAS ELECTRIC COMPANY (SDG&E) IS AN INVESTOR-OWNED UTILITY COMMITTED TO BUILDING THE CLEANEST, SAFEST AND MOST RELIABLE ENERGY COMPANY IN AMERICA AND PROVIDING THE BEST POSSIBLE SERVICE TO ITS CUSTOMERS IN THE COMPANY'S 4,105 SQUARE MILE SERVICE AREA.
- II. THE SERVICE STANDARDS & GUIDE CONTAINS INFORMATION ESSENTIAL TO THE ESTABLISHMENT OF SERVICE TO NEW FACILITIES, OR TO REMODELED OR EXPANDED FACILITIES WHERE LOAD HAS BEEN ADDED. THIS INFORMATION IS INTENDED FOR USE BY ALL INTERESTED CUSTOMERS AND PARTICULARLY BY MEMBERS OF TECHNICAL AND PROFESSIONAL TRADES CONCERNED WITH THE DESIGN AND BUILDING OF FACILITIES TO RECEIVE SERVICE FROM SDG&E'S SYSTEM.

SCOPE:

- III. THE SERVICE STANDARDS & GUIDE PRESENTS GENERAL AND DETAILED INFORMATION TO HELP ENSURE THAT A SERVICE INSTALLATION WILL BE ADEQUATE FOR PRESENT AND FUTURE POWER NEEDS. THE MANUAL SEEKS TO OUTLINE SERVICE REQUIREMENTS IN ACCORDANCE WITH THE REGULATIONS OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) WHO WILL INSPECT THE SERVICE CONNECTION PRIOR TO PERMITTING THE UTILITY TO ESTABLISH SERVICE.
- IV. THE SERVICE STANDARDS ARE BASICALLY FOUNDED UPON STANDARDS OF GOOD SAFETY PRACTICES AND ELECTRICAL CODES ENFORCED BY THE AHJ'S IN THE UTILITY'S SERVICE AREA. WE HAVE ENDEAVORED TO BRING THEM ALL TOGETHER IN A SINGLE, CONVENIENT FORM FOR EASY USE.
- V. REFERENCES ON WHICH THIS MANUAL IS BASED: (a) b) c) d) e)
- VI. THE CONTENTS OF THE SERVICE STANDARDS & GUIDE ARE TAKEN FROM A NUMBER OF AUTHORITATIVE SOURCES, AND SINCE THEY ARE COMPILED IN A FORM WE BELIEVE WILL BEST SUIT YOUR INTERESTS, WE HAVE AVOIDED PRECISE FOOTNOTING OF REFERENCES.
- VII. WHEN AN UNUSUAL SITUATION CONFRONTS YOU, ONE THAT DOES NOT APPEAR TO BE SPELLED-OUT SPECIFICALLY IN THIS MANUAL, PLEASE CONTACT YOUR PROJECT PLANNER OR SERVICE STANDARDS FOR CLARIFICATION.
- VIII. DESIGN AND PROJECT MANAGEMENT AND THE SERVICE ORDER TEAMS ARE THE SPECIAL DEPARTMENTS THAT WILL ANSWER YOUR INDIVIDUAL QUESTIONS AND AID YOU IN THE DESIGN AND CONSTRUCTION OF SERVICE CONNECTIONS. (f)
- IX. THE PROJECT PLANNER WILL MEET WITH YOU TO DISCUSS YOUR PARTICULAR PROJECT, AND WORK OUT A SOLUTION WHICH WILL BE SATISFYING FOR YOU AND FOR THE FUTURE CUSTOMERS THE UTILITY WILL SERVE WITH SAFE AND RELIABLE ENERGY.

SERVICE PLANNING:

- XI. PLEASE BE ADVISED THAT WHENEVER DESIGN OF ELECTRICAL PLANS IS CONSIDERED FOR A COMMERCIAL, INDUSTRIAL OR RESIDENTIAL STRUCTURE. CONTACT THE UTILITY AS SOON AS POSSIBLE FOR THE FOLLOWING REASONS:
 - a. THE UTILITY WILL WORK WITH YOU TO ESTABLISH THE SERVING VOLTAGE AND AN ACCEPTABLE METER AND SERVICE LOCATION.
 - b. EARLY DISCUSSION OF THE PROJECT WILL ENABLE THE UTILITY TO DETERMINE THE MOST FAVORABLE RATE SCHEDULE FOR THE CUSTOMER, AND PROVIDE THE UTILITY THE ABILITY TO MEET YOUR CONSTRUCTION SCHEDULE.
 - c. YOU CAN PREVENT THE UNNECESSARY EXPENSE OF REDESIGN, CONSTRUCTION CHARGES, OR DELAYS BY NOT ASSUMING THE TYPE OF SERVICE THE UTILITY WILL PROVIDE.

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		Cl	IAN	GE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F									
В	EDITORIAL C	CHANGES	IPJ	IPJ	KRG	12/06/2022	Е										
Α	EDITORIAL C	CHANGES	-	LSM	LSM	TPM	11/01/2017	D									
		X Indicates Latest Revision Completely Revised New Page X Information Removed															
SDC&E ELECTRIC SERVICE STANDARDS & CHIDES																	
SHEET SDGQL ELECTRIC SERVICE STANDARDS & GOLDES													S	G00 ⁴	4.1		
1 OF 6 GENERAL INFORMATION													_				

GENERAL INFORMATION

REQUEST FOR SERVICE: (g) (h)

- XII. AT THE TIME OF THIS INITIAL CONTACT, SIMPLY PROVIDE THE FOLLOWING INFORMATION:
 - a. STREET ADDRESS AND LEGAL DESCRIPTION OF THE PROPERTY, AND
 - b. PLOT, GRADING, ELEVATION, AND SITE IMPROVEMENT PLANS
- XIII. AVAILABLE FORMS INCLUDE THE FOLLOWING:
 - a. REQUEST FOR SERVICE RESIDENTIAL SINGLE-FAMILY DWELLING
 - b. REQUEST FOR SERVICE RESIDENTIAL SUBDIVISION/DEVELOPMENT
 - c. REQUEST FOR SERVICE RESIDENTIAL COMMERCIAL/INDUSTRIAL DEVELOPMENT
- XIV. ALSO, YOU MAY UTILIZE THE REGIONAL SDG&E CONTACTS.(f)

ADDING LOAD TO EXISTING METER PANELS:(i)

- XV. EXISTING CUSTOMERS RECEIVING ELECTRIC SERVICE AT 480V, OR LESS, SHALL PROVIDE WRITTEN NOTIFICATION TO THE UTILITY A MINIMUM OF 30 DAYS IN ADVANCE OF CONNECTING ALL NEW ELECTRIC LOADS WITH A RATING OF 20KW, OR GREATER, OR SMALLER LOADS ADDED OVER A 12-MONTH PERIOD OF TIME WITH AGGREGATE RATINGS TOTALING 20KW, OR GREATER.
- XVI. EXISTING CUSTOMERS RECEIVING ELECTRIC SERVICE AT OVER 480V SHALL PROVIDE WRITTEN NOTIFICATION TO THE UTILITY A MINIMUM OF 30 DAYS IN ADVANCE OF CONNECTING ALL NEW ELECTRIC LOADS WITH A RATING OF 200KW, OR GREATER, OR SMALLER LOADS ADDED OVER A 12-MONTH PERIOD OF TIME WITH AGGREGATE RATINGS TOTALING 200KW, OR GREATER.
- XVII. IT IS THE CUSTOMER'S RESPONSIBILITY TO NOTIFY THE UTILITY, IN WRITING, WITHIN 15 DAYS IF THE CUSTOMER MAKES ANY CHANGE IN THE CONNECTED LOAD, OR THE SIZE OR CHARACTER OF THEIR APPLIANCES OR APPARATUS. SUCH CHANGES MAY REQUIRE A NEW APPLICATION FOR SERVICE AND/OR A CHANGE IN THE UTILITY'S SERVICE FACILITIES.

APPLICATION FOR A BILLING ACCOUNT:

XVIII. THE INITIAL CONTACT WITH THE UTILITY FOR METER AND SERVICE REQUIREMENTS IS NOT AN APPLICATION FOR SERVICES. THERE IS ANOTHER SIMPLE STEP WHICH IS TAKEN CARE OF THROUGH A SEPARATE CHANNEL AT SDG&E. AN APPLICATION FOR A BILLING ACCOUNT MUST BE MADE BEFORE SERVICE CAN BE ESTABLISHED. APPLICATIONS CAN USUALLY BE MADE BY TELEPHONE. THIS SHOULD BE DONE AT THE TIME OF INITIAL CONTACT OR SHORTLY THEREAFTER TO AVOID DELAYS IN ESTABLISHING SERVICE.

PERMIT & INSPECTION:

- XIX. PRIOR TO SERVICE BEING ENERGIZED, AN INSPECTION BY THE AHJ IS REQUIRED. ALL ENERGY CONSUMPTION MUST BE METERED.
- XX. BRIEFLY, THE STEPS ARE:
 - a. AN ELECTRICAL PERMIT IS OBTAINED FROM THE APPROPRIATE AHJ BY THE CONTRACTOR OR OTHER QUALIFIED PERSON.
 - WIRING FOR THE FACILITY IS COMPLETED BY AN ELECTRICIAN OR OTHER QUALIFIED PERSON.
 - c. INSPECTION OF THE INSTALLATION IS MADE BY THE AHJ WHO NOTIFIES THE UTILITY OF ACCEPTANCE.
 - d. THE INSTALLATION IS CLEARED TO THE UTILITY.
 - e. THE UTILITY CONNECTS TO THE CUSTOMER'S SERVICE EQUIPMENT AND SETS THE METER.
- XXI. MODIFICATIONS, ALTERATIONS, OR RE-ESTABLISHMENT OF ELECTRIC SERVICE MAY REQUIRE AN INSPECTION CLEARANCE BY THE AHJ.

	© 1998 - 2025 Sa	an Di	iego Gas & Ele	ectric C	Compa	ny. All	rights r	reserved. Rer	moval o	of th	nis copyright not	tice	without permission	is not	permit	ted und	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		СН	IAI	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDIT	ORIA	AL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F									
В	EDITORIAL (CHAN	NGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е									
Α	EDITORIAL (CHAN	NGES	-	LSM	LSM	TPM	11/01/2017	D									
	X Indicates Latest Revision							npletely Revi	ised		New Page		Information Rei	moved				
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	

SHEET 2 OF 6

GENERAL INFORMATION

SG004.2

CHARACTER OF SERVICE:

- XXII. SERVICE SUPPLIED THROUGHOUT THE UTILITY'S SERVICE AREA IS ALTERNATING CURRENT AT A FREQUENCY OF APPROXIMATELY 60 CYCLES PER SECOND, AND AT THE NORMAL VOLTAGE AVAILABLE AT ANY SPECIFIC LOCATION ON THE DISTRIBUTION SYSTEM. A DETAILED DESCRIPTION OF SERVICE IS OUTLINED IN RULE 2 OF THE COMPANY'S RULES FOR THE SALE OF ELECTRIC ENERGY, AS FILED WITH THE CALIFORNIA PUBLIC UTILITIES COMMISSION. (k)
- XXIII. SINGLE-FAMILY RESIDENCES ON INDIVIDUAL LOTS AND MOST SMALL COMMERCIAL LOADS ARE NORMALLY SERVED BY A 3-WIRE, SINGLE-PHASE, 120/240V SERVICE. MULTI-FAMILY RESIDENTIAL DEVELOPMENTS, INDUSTRIAL LOADS, SUBSTANTIAL COMMERCIAL LOADS AND THREE-PHASE LOADS USUALLY REQUIRE SPECIAL ENGINEERING STUDIES TO ESTABLISH THE SERVING VOLTAGE, AND SHOULD BE REFERRED TO THE NEAREST SDG&E OFFICE AT AN EARLY PLANNING STAGE.
- XXIV. SERVICE STANDARDS AND THE APPROPRIATE AHJ MAY APPROVE A 2-WIRE, SINGLE-PHASE, 120V WHERE THE LOAD DOES NOT EXCEED ONE 15A AND ONE 20A BRANCH CIRCUIT.
- XXV. A 4-WIRE, THREE-PHASE, 208Y/120V SERVICE MAY BE PROVIDED TO MULTI-FAMILY BUILDINGS; HOWEVER, THE INDIVIDUAL OCCUPANCIES MUST BE SERVED AND METERED SINGLE-PHASE, 200A MAXIMUM. IN MIXED-USE BUILDINGS, COMMERCIAL SERVICE MAY BE METERED SINGLE-PHASE, 200A MAXIMUM.
- XXVI. THREE-PHASE, 480V SERVICE FROM AN <u>OVERHEAD</u> TRANSFORMER STATION, WHERE AVAILABLE, IS SUPPLIED 3-WIRE, DELTA-CONNECTED, WITH B-PHASE GROUNDED AND A SEPARATE 4TH WIRE SERVICE GROUND CONDUCTOR (REDUNDANT GROUND, NOT A "NEUTRAL").
- XXVII. ALL CUSTOMER REQUESTS FOR 480V SERVICE FROM A PADMOUNT TRANSFORMER WILL BE SERVED THREE-PHASE, 4-WIRE, 480Y/277V.
- XXVIII. THREE-WIRE, SINGLE-PHASE 240/480V SERVICE IS AVAILABLE, 200A MAXIMUM. THIS IS TYPICALLY PROVIDED FOR HIGH-POWER LIGHTING LOADS, SUCH AS CALTRANS HIGHWAY LIGHTING SYSTEMS.
- XXIX. ALL CUSTOMERS ON THE UTILITY'S ELECTRIC DISTRIBUTION SYSTEM ARE OCCASIONALLY SUBJECTED TO MOMENTARY FLUCTUATIONS IN SERVING VOLTAGE. THESE ARE CAUSED BY DISTURBANCES SUCH AS LIGHTING SURGES AND SHORT CIRCUITS, AND ARE IMPOSSIBLE TO PREVENT. ANY CUSTOMER HAVING OR PLANNING TO INSTALL VOLTAGE-SENSITIVE EQUIPMENT (SUCH AS SOLID-STATE CONTROLS) WHICH CANNOT OVERRIDE MOMENTARY VOLTAGE FLUCTUATIONS SHOULD CONSIDER INSTALLING SPECIALLY DESIGNED PROTECTIVE APPARATUS AS PART OF THEIR OWN ELECTRICAL SYSTEM.
- XXX. MAXIMUM SERVICE PANEL SIZE ALLOWED TO BE SERVED BY A 120/240V, 3-PHASE DELTA TRANSFORMER INSTALLATION (OVERHEAD OR UNDERGROUND) IS 600A.
- XXXI. MAXIMUM SERVICE PANEL SIZE ALLOWED TO BE SERVED BY AN OVERHEAD 480V, 3-PHASE DELTA TRANSFORMER INSTALLATION IS 600A.

EQUIPMENT RESPONSIBILITIES:

- XXXII. CUSTOMER: THE CUSTOMER IS TO PROVIDE AND INSTALL THEIR OWN SERVICE EQUIPMENT. THIS INCLUDES, BUT IS NOT LIMITED TO, THE FOLLOWING EQUIPMENT:
 - a. SERVICE ENTRANCE CONDUCTORS (NO. 8 AWG MINIMUM FOR OVERHEAD SERVICES)
 - b. SERVICE TERMINATING EQUIPMENT
 - c. SERVICE SWITCHES AND CIRCUIT BREAKERS
 - d. FUSES
 - e. METER SOCKETS AND A STAINLESS STEEL OR ALUMINUM RETAINER (FLIMSY) RING FOR EACH SOCKET
 - f. METER AND INSTRUMENT TRANSFORMER HOUSINGS
 - g. SERVICE SWITCHBOARDS AND ASSOCIATED DEVICES
 - h. OTHER RELATED EQUIPMENT AS REQUIRED BY THE UTILITY

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CI	IAH	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F									
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е									
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D									
	X Indicates Latest Revision				Con	npletely Revi	sed		New Page		Information Rer	noved				

SHEET 3 OF 6 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG004.3

EQUIPMENT RESPONSIBILITIES (CONT'D):

- XXXIII. AFTER THE CUSTOMER HAS INSTALLED THEIR EQUIPMENT IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPROPRIATE AHJ AND THE UTILITY, THE CUSTOMER WILL BE RESPONSIBLE FOR ITS MAINTENANCE.
- XXXIV. UTILITY: ALL METERS, METERING TRANSFORMERS, TEST SWITCHES, AND OTHER ASSOCIATED METERING EQUIPMENT WILL BE PROVIDED, INSTALLED, OWNED, AND MAINTAINED BY THE UTILITY IN ACCORDANCE WITH OUR FILED RULE 16.
- XXXV. CUSTOMER RESPONSIBILITY TO MEET SERVICE STANDARDS REQUIREMENTS: MEETING THE SERVICE EQUIPMENT REQUIREMENTS SET BY THE SDG&E SERVICE STANDARDS & GUIDE IS A CONDITION OF RECEIVING SERVICE. AVOID TURN DOWNS THAT COST THE BUILDER EXTRA TIME AND RESOURCES. IF SERVICE EQUIPMENT MEETING STANDARD CANNOT BE FOUND TO COMPLETE A PROJECT AND ALTERNATIVES THAT DO NOT MEET STANDARD ARE BEING CONSIDERED, CONSULT WITH YOUR SDG&E PROJECT PLANNER FIRST.

CONNECTION OR DISCONNECTION OF SERVICE:

XXXVI. THE UTILITY WILL BE RESPONSIBLE FOR ANY CONNECTION OR DISCONNECTION OF SERVICE BETWEEN COMPANY POWER LINES AND CUSTOMER-OWNED FACILITIES. ONLY AUTHORIZED EMPLOYEES OR AGENTS OF THE COMPANY ARE PERMITTED TO DO THIS WORK. ARRANGEMENTS MAY BE MADE FOR THIS WORK TO BE DONE ON A SPECIFIC DAY. IT IS ADVISED TO GIVE AS MUCH ADVANCE NOTICE AS POSSIBLE FOR A TURN-ON OR SHUT-OFF OF SERVICE.

WORK ON UTILITY-OWNED POLES:

XXXVII. BECAUSE OF SAFETY RULES AND SPECIAL TRAINING REQUIRED, PROPERLY QUALIFIED UTILITY LINEMEN ARE THE ONLY PERSONS PERMITTED TO CLIMB THE UTILITY'S POLES.

SEALING OF METER & SERVICE FACILITIES:

- XXXVIII.THE UTILITY WILL SEAL ALL SERVICE RACEWAYS, PULL CANS, PULL SECTIONS, METERING COMPARTMENTS WITH DOORS OR REMOVABLE COVERS, METERS, TEST SWITCHES, AND OTHER FACILITIES FOR SERVICE AND METERING INSTALLATIONS. THE SEAL IS A BOND OF MUTUAL PROTECTION FOR THE UTILITY AND FOR THE CUSTOMER. AS SUCH, IT MAY NOT BE BROKEN BY ANYONE BUT AN AUTHORIZED REPRESENTATIVE OF THE UTILITY. (m)
- XXXIX. IF IT BECOMES NECESSARY FOR ANY PERSON TO BREAK A SEAL FOR ANY LEGITIMATE REASON, THEY SHALL SECURE PERMISSION TO DO SO BY CALLING THE NEAREST DESIGN & PROJECT MANAGEMENT REGIONAL OFFICE. (f)

ACCESSIBILITY:

4 OF 6

- XL. IN THE EXPRESS INTERESTS OF PROVIDING THE BEST POSSIBLE ELECTRIC SERVICE TO ALL CUSTOMERS, THE UTILITY MUST HAVE IMMEDIATE 24-HOUR ACCESS TO THEIR FACILITIES LOCATED ON THE CUSTOMER'S PREMISES. THE UTILITY MAKES EVERY EFFORT TO DO OUR WORK WITH THE LEAST INCONVENIENCE TO THE CUSTOMER.
- XLI. WHEN A SERVICE CONNECTION IS TERMINATED, THE UTILITY MUST REMOVE ITS PROPERTY FROM THE PREMISES.
- XLII. ELECTRICALLY OPERATED GATES, WHICH DO NOT PERMIT IMMEDIATE 24-HOUR ACCESS TO ELECTRIC AND GAS FACILITIES FOR SDG&E AND LOCAL FIRE DEPARTMENT PERSONNEL, COULD POSE A SAFETY HAZARD. IF AN ELECTRICALLY OPERATED SECURITY GATE IS TO BE INSTALLED, THE CUSTOMER IS RESPONSIBLE FOR INSTALLING AN SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY IN A KEY SWITCH WIRED TO THE GATE CONTROLLER. THE KEY SWITCH SHOULD BE LOCATED IN A HOUSING THAT ALLOWS AN AUTHORIZED UTILITY EMPLOYEE, OR AUTHORIZED AGENT, TO DRIVE UP AND INSERT THEIR KEY IN THE CYLINDER TO ACTIVATE THE GATE CONTROLLER WITHOUT HAVING TO LEAVE THEIR VEHICLE. IF SITE CONDITIONS MAKE THIS REQUIREMENT IMPRACTICAL, CONTACT SDG&E'S PROJECT PLANNER FOR APPROVAL OF AN ALTERNATE LOCATION. YOU SHOULD CONTACT THE FIRE DEPARTMENT WHICH SERVICES YOUR AREA TO OBTAIN THEIR REQUIREMENTS. THE CUSTOMER IS ALSO REQUIRED TO PROVIDE A MEANS OF OPENING THE GATE FROM THE INSIDE WITHOUT THE USE OF A VEHICLE TO ACTIVATE THE CONTROLLER. THIS MAY REQUIRE THE INSTALLATION OF AN ADDITIONAL KEY SWITCH INSIDE THE GATE IF THERE IS NOT AN UNSECURED SWITCH AVAILABLE FOR THE UTILITY'S USE. (n)

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	НΑ	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F									
В	EDITORIAL (CHAN	GES	ARC	IPJ	IPJ	KRG	12/06/2022	Е									
Α	EDITORIAL C	GES	-	LSM	LSM	TPM	11/01/2017	D										
		Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Re	moved					
	SHEET				SDC	S&E E	LECTI	RIC SERVIC	E STA	NE	DARDS & GL	JID	ES					
l	31 ILL 1															S	G00	4.4

GENERAL INFORMATION

MARKOUT SERVICE:

XLIII. BEFORE YOU BEGIN DIGGING AT YOUR BUILDING SITE, CALL DIGALERT AT 811 (UNDERGROUND SERVICE ALERT OF SOUTHERN CALIFORNIA [USA]) FOR MARKOUT SERVICE. BY CONTACTING DIGALERT, YOU CAN AVOID CONFLICT WITH EXISTING UNDERGROUND FACILITIES. (0)

TRENCH INSPECTIONS:

XLIV. TO REQUEST INSPECTIONS FOR GAS AND/OR ELECTRIC TRENCHES, SEE $\frac{SG021}{FOR}$ FOR CONTACT INFORMATION. (f)

EXISTING NONCONFORMING CONDITIONS:

XLV. REWIRES OF EXISTING METER AND SERVICE LOCATIONS THAT HAVE EXISTING NONCONFORMING CONDITIONS SHALL REQUIRE CORRECTIVE MEASURES TO BRING THE CONDITIONS UP TO STANDARD AS PART OF THE REWIRE.

TABLE 1

	ADDRESSING CONVENTIONS
ACRONYM	SUBSTITUTION FOR
AL	ALARM
CG	CUSTOMER GENERATION (GENERATOR OUTPUT METER)
СР	CONTROL POWER (FOR PRIMARY SERVICES)
CS	CELL SITE
EL	ELEVATOR
EV	ELECTRIC VEHICLE
FA	FIRE ALARM
FC	FUEL CELL (FOR GAS)
FM	FACILITY METER
FP	FIRE PUMP
НМ	HOUSE METER
IR	IRRIGATION
MC	METER CABINET
ND	NETWORK DEVICE
PS	PUMP SERVICE (DOMESTIC, AGRICULTURAL OR COMMERCIAL)
REC	RECREATION ROOM
RR	RAILROAD
SPK	SPRINKLER
SL	STREET LIGHT
TEL	TELEPHONE
TP	TEMPORARY POWER
TR	TROLLEY
TS	TRAFFIC SIGNAL
TV	CABLE TV

REFERENCE:

- (a) RULES FOR OVERHEAD ELECTRIC LINE CONSTRUCTION: GENERAL ORDER 95 OF THE PUBLIC UTILITIES COMMISSION, STATE OF CALIFORNIA
- (b) RULES FOR CONSTRUCTION OF UNDERGROUND ELECTRICAL SUPPLY AND COMMUNICATION SYSTEMS: GENERAL ORDER 128 OF THE PUBLIC UTILITIES COMMISSION, STATE OF CALIFORNIA

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 5 OF 6

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG004.5

GENERAL INFORMATION

REFERENCE (CONT'D):

- TITLE 24. STATE BUILDING STANDARDS ELECTRICAL CODE, FORMERLY KNOWN AS ELECTRICAL SAFETY ORDERS OF THE DIVISION OF INDUSTRIAL SAFETY, DEPARTMENT OF INDUSTRIAL RELATIONS, STATE OF CALIFORNIA.
- $(\mathtt{d}^{'})$ NATIONAL ELECTRICAL CODE (NFPA 70), AN ANSI STANDARD, PUBLISHED BY THE NATIONAL FIRE PROTECTION ASSOCIATION, $\mathtt{1}$ BATTERYMARCH PARK, QUINCY, MA 02169-7471.
- APPLICABLE LAWS AND ORDINANCES OF THE COUNTY OR CITY WHERE THE SERVICE CONNECTION IS INSTALLED.
- (f) FOR A LIST OF OFFICES WHERE REPRESENTATIVES MAY BE REACHED, SEE <mark>SG021</mark>.
- FOR ANY BUILDING PROJECT NEEDS, BROCHURES AND FORMS CAN BE FOUND AT SDG&E'S BUILDER SERVICES RESOURCES PAGE ONLINE AT HTTP://WWW.SDGE.COM/BUILDER-SERVICES.
- (h) SDG&E TARIFFS INCLUDING RULE 15 CAN BE ACCESSED AT HTTP://WWW.SDGE.COM/RATES-REGULATIONS/CURRENT-AND-**EFFECTIVE-TARIFFS.**
- $ar{}$ i $\,$ RULE 2, B.9 AND B.10 AND RULE 3, C. SDG&E TARIFFS, INCLUDING RULES 2 AND 3, CAN BE ACCESSED AT HTTP://WWW.SDGE.COM/RATES-REGULATIONS/CURRENT-AND-EFFECTIVE-TARIFFS.
- (j) FOR ADDITIONAL INFORMATION, SEE "BILLING ACCOUNT ESTABLISHMENT" IN SG003.
- (k) SEE RULE 2.
- I) FOR DEFINITION OF "UTILITY METERS", SEE SG003.
- (m) FOR ADDITIONAL SEALING REQUIREMENTS, SEE SG503.

Indicates Latest Revision

- $(\mathsf{n}\,)$ for a list of Locksmiths authorized to sell utility-approved locks, see SG005.
- o) YOU MAY CALL DIGALERT AT 811, OR VISIT THEIR WEBSITE AT HTTP://WWW.DIGALERT.ORG.

	© 1998 - 2025 San Diego Gas & Ele	ectric (Compa	ny. All	rights	reserved. Rei	moval	of this copyright notice without permission	is not	permit	ted un	der law	1.
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 6 OF 6

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Completely Revised

GENERAL INFORMATION

New Page X

Information Removed

SG004.6

SCOPE: THIS STANDARD SHOWS THE LISTING OF LOCKSMITHS TO SELL SCHLAGE RESTRICTED VTQP QUAD SECTION KEYWAYS AND THE SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. GAS & ELECTRIC METER ACCESS IN ORDER TO PROVIDE THE BEST POSSIBLE GAS AND ELECTRIC SERVICE TO ALL OUR CUSTOMERS, SDG&E (UTILITY) MUST HAVE IMMEDIATE 24-HOUR ACCESS TO OUR METERS LOCATED ON THE CUSTOMER'S PREMISES. WE MAKE EVERY EFFORT TO DO OUR WORK WITH THE LEAST INCONVENIENCE TO YOU, OUR CUSTOMER. THE UTILITY MAY ALSO REQUIRE LINE TRUCK ACCESS TO LARGER SERVICES AND DISTRIBUTION FACILITIES ON THE CUSTOMER'S PROPERTY. CONSULT WITH THE UTILITY'S PROJECT PLANNER TO DETERMINE IF LINE TRUCK ACCESS IS REQUIRED. SEE PAGE SG021 FOR DESIGN & PROJECT MANAGEMENT CONTACT INFORMATION.
- II. **ACCESSIBLE METER LOCATION** AN ACCESSIBLE METER LOCATION IS CAPABLE OF BEING REACHED QUICKLY 24-HOURS A DAY FOR INSTALLATION, READING, TESTING, INSPECTION, MAINTENANCE, OR IN THE EVENT OF AN EMERGENCY. LOCKED DOORS AND GATES WHICH THE UTILITY'S EMPLOYEES MUST PASS THROUGH FOR ACCESS TO OUR FACILITIES MUST UTILIZE THE SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY.
- III. **INACCESSIBLE METER LOCATION** AN INACCESSIBLE METER LOCATION REFERS TO A METER IN A LOCATION WHERE THE UTILITY'S EMPLOYEE/AGENT DOES NOT HAVE 24-HOUR ACCESS TO INSTALL, READ, TEST, INSPECT, MAINTAIN, OR RESPOND IN THE EVENT OF AN EMERGENCY.
- IV. BELOW IS A LIST OF LOCKSMITHS AUTHORIZED BY THE UTILITY TO SELL THE SCHLAGE RESTRICTED VTQP QUAD SECTION KEYWAYS AND THE SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY THAT WILL ALLOW THE UTILITY'S PERSONNEL ACCESS TO ITS FACILITIES:

TABLE 1

	SAN DIEGO AREA	
A-ADVANCED LOCKSMITHS 8280 CLAIREMONT MESA BLVD #135 SAN DIEGO, CA 92111 858-277-4358	ACCURATE SECURITY PROS 9919 HIBERT ST #D SAN DIEGO, CA 92131 858-271-1155	ADAMS AVENUE LOCK & KEY 2948 IMPERIAL AVE SAN DIEGO, CA 92102 619-280-0800
BUSY BEES LOCKS & KEYS 1747 KETTNER BLVD SAN DIEGO, CA 92101 619-733-0172	CALIFORNIA COMMERCIAL SECURITY 9560 RIDGEHAVEN CT #C SAN DIEGO, CA 92123 800-286-2555 / 858-503-7500	COMMERCIAL LOCK & SAFE 7094 MIRAMAR RD #118 SAN DIEGO, CA 92121 858-566-6065
CONVOY STREET LOCKSMITH SHOP 4204 CONVOY ST SAN DIEGO, CA 92111 858-715-8533	CORONADO LOCK AND KEY 1016 9 TH ST SAN DIEGO, CA 92118 619-435-5363	GRAH SAFE & LOCK 939 UNIVERSITY AVE #100 SAN DIEGO, CA 92103 619-234-4829
LA JOLLA LOCKSMITH CORPORATION 8677 VILLA LA JOLLA DR #1140 SAN DIEGO, CA 92037 858-453-6868	LABANN LOCK & SAFE 2038 HANCOCK ST SAN DIEGO, CA 92110 619-291-2038 (SERVES ALL AREAS)	
	SOUTH BAY AREA	
BUSY BEES LOCKS & KEYS 386 EAST H ST STE 209 SAN DIEGO, CA 91910 619-271-6364	CHULA VISTA SECURITY CENTER CHULA VISTA, CA 91909 619-476-1333 (ALSO SERVES SAN DIEGO AREA)	PROFESSIONAL LOCKSMITH SERVICES 1111 SEACOAST DR IMPERIAL BEACH, CA 91932 619-429-0813

© 1998 - 2025 San Diego Gas & Elec	Tric C	ompa	лу. Ан і	rignts re	eservea. Rer	novai	of this copyright notice without permission is	s not p	permitte	ea uno	aer iaw.	

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/04/2022	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

LISTING OF LOCKSMITHS AUTHORIZED TO SELL SCHLAGE RESTRICTED VTQP QUAD SECTION KEYWAYS AND THE SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY SG005.1

TABLE 1 (CONT'D)

	EAST COUNTY AREA	
A AARON LOCK & KEY 3027 LEMON GROVE AVE LEMON GROVE, CA 91945 619-462-3381	A GARAGE DOOR & GATE STORE 9901 MAINE AVE LAKESIDE, CA 92040 619-561-9370	KWIK-KEY LOCKSMITHS 7368 EL CAJON BLVD LA MESA, CA 91941 619-667-5120
LYNN'S LOCKSMITH SERVICE 1380 EAST MAIN ST EL CAJON, CA 92021 619-447-7332		
	NORTH COUNTY AREA	
A-1 LOCK & SAFE 6020-B PASEO DEL NORTE CARLSBAD, CA 92011 760-431-5397 (ALSO SERVES SAN DIEGO & SOUTH BAY AREAS)	ADOBE LOCK & SAFE 184 SOUTH RANCHO SANTA FE RD SAN MARCOS, CA 92078 760-727-5470	B&B LOCK & SAFE 250 WOODWARD AVE #C ESCONDIDO, CA 92025 760-746-8060
CARLSBAD VILLAGE LOCK & KEY 3138 ROOSEVELT ST #E CARLSBAD, CA 92008 760-434-6600	FOOTHILL LOCK & SECURITY 1650 ORD WAY OCEANSIDE, CA 92056 760-806-9000 / 858-999-4400	PRO-TEC LOCK & SAFE 601 OCEANSIDE BLVD #A OCEANSIDE, CA 92056 760-722-1479
QUALITY LOCK & SAFE 340 EAST BROADWAY VISTA, CA 92084 760-945-4545 (ALSO SERVES ORANGE COUNTY)	RAMONA LOCKSMITH 811 ½ D ST RAMONA, CA 92065 760-789-4189 (SERVES JULIAN, RAMONA, SANTA YSABEL)	RL HELMS LOCK & DOOR 4140 OCEANSIDE BLVD UNIT 159-406 OCEANSIDE, CA 92056 760-685-2794
SUPERIOR LOCKSMITH ESCONDIDO, CA 760-580-8777 (MOBILE)	VISTA LOCK & SAFE CO 1025 SOUTH SANTA FE AVE #A VISTA, CA 92083 760-726-0310 (ALSO SERVES SAN DIEGO AREA)	
	ORANGE COUNTY AREA	
CAPISTRANO LOCK AND SAFE 32118 PASEO ADELANTO, #5AR SAN JUAN CAPISTRANO, CA 92675 949-496-5625	CONTROLLED KEY SYSTEMS, INC. 17248 RED HILL AVE IRVINE, CA 92614 949-756-1121	CUSTOM LOCK & KEY SERVES ALL ORANGE COUNTY 714-788-9660 / 949-233-4422
MARIN LOCK & SAFE COMPANY 26072 MERIT CIR #108 LAGUNA HILLS, CA 92653 949-582-5652 (SERVES SOUTH ORANGE COUNTY)	TONY'S LOCKSMITH & SAFE SERVICE 429 AVE DE LA ESTRELLA SAN CLEMENTE, CA 92672 949-492-5700 (SERVES SOUTH ORANGE COUNTY)	

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/04/2022	Е						
A	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 2 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

LISTING OF LOCKSMITHS AUTHORIZED TO SELL SCHLAGE RESTRICTED VTQP QUAD SECTION KEYWAYS AND THE SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY

SG005.2

SCOPE: THE CALIFORNIA ELECTRICAL CODE REQUIRES THE INSTALLATION OF SERVICE EQUIPMENT WITH OVERCURRENT PROTECTIVE DEVICES WITH A SHORT CIRCUIT CURRENT RATING EQUAL TO, OR NOT LESS THAN, THE AVAILABLE FAULT CURRENT PROVIDED BY SDG&E (UTILITY), AND WHEN APPLICABLE, THE CONTRIBUTION TO FAULT CURRENT FROM CUSTOMER'S MOTOR

INSTALLATION: NONE

BILL OF MATERIALS: NONE

CONTRIBUTION.

NOTES:

- I. THE UTILITY'S MAXIMUM CONTRIBUTION TO FAULT CURRENT IS STATED AS FOLLOWS:
 - a. RESIDENTIAL APPLICABLE TO A SINGLE-FAMILY RESIDENCE OR DUPLEX AS DEFINED IN RULE 1 (WHICH MAY INCLUDE A HOUSE METER FOR A TOTAL OF 3 METERS), MULTI-FAMILY RESIDENTIAL SERVICE CONSISTING OF 3 OR MORE DWELLING UNITS, OR A MOBILE HOME; ALSO APPLICABLE TO SERVICE USED IN COMMON FOR RESIDENTIAL PURPOSES IN A MULTI-FAMILY DWELLING, ON A SINGLE PREMISES, WHETHER SEPARATELY METERED OR COMBINED WITH SERVICE TO AN INDIVIDUAL DWELLING UNIT. THE UTILITY'S CONTRIBUTION TO THE AVAILABLE FAULT CURRENT AT THE POINT OF CONNECTION OF SERVICE CONDUCTORS TO THE CUSTOMER'S FACILITIES WILL NOT EXCEED THE VALUES LISTED IN TABLE 1.

TABLE 1:

PHASE	SERVING VOLTAGE (VOLTS)	SERVICE ENTRANCE AMPACITY (AMPS)	UTILITY'S CONTRIBUTION TO FAULT CURRENT WILL NOT EXCEED (AMPS)
1Ø	120/240	225 OR LESS	10,000
1Ø	120/240	226 – 600	22,000
1Ø	120/208	200 OR LESS	42,000
1Ø (Ib)	120/240	800	42,000
3Ø	120/240	600 OR LESS (SEE ITEM 4)	42,000
3Ø	208Y/120	3,000 OR LESS	42,000
3Ø	208Y/120	3,001 – 4,000	65,000

- BY EXCEPTION ONLY: 800 AMPS AND ABOVE SINGLE PHASE RESIDENTIAL MAY BE CONSIDERED ONLY ON A CASE BY CASE BASIS WHEN THE SDG&E DISTRIBUTION SYSTEM SERVING THE AREA IS ONLY SINGLE PHASE AND 3 PHASE DISTRIBUTION IS A CONSIDERABLE DISTANCE AWAY. THIS EXCEPTION REQUIRES REVIEW AND DEVIATION APPROVAL BY SDG&E SERVICE STANDARDS IN ELECTRIC DISTRIBUTION ENGINEERING.
- NON-RESIDENTIAL APPLICABLE TO ALL NON-RESIDENTIAL OCCUPANCIES SUCH AS, BUT NOT LIMITED TO, COMMERCIAL, INDUSTRIAL, AGRICULTURAL, GOVERNMENTAL, EDUCATIONAL INSTITUTIONS, HOSPITALS, MEDICAL CLINICS, ETC. THE UTILITY'S CONTRIBUTION TO THE AVAILABLE FAULT CURRENT AT THE POINT OF CONNECTION OF THE UTILITY'S SERVICE CONDUCTORS TO THE CUSTOMER'S FACILITIES WILL NOT EXCEED THE VALUES LISTED IN TABLE 2.

TABLE 2:

PHASE	SERVING VOLTAGE (VOLTS)	SERVICE ENTRANCE AMPACITY (AMPS)	UTILITY'S CONTRIBUTION TO FAULT CURRENT WILL NOT EXCEED (AMPS)
1Ø	120/208	200 OR LESS	42,000
1Ø	120/240	400 OR LESS	42,000
1Ø	240/480	200 OR LESS	10,000
3Ø	120/240	600 OR LESS (SEE Ie)	42,000
3Ø	208Y/120	3,000 OR LESS	42,000
3Ø	208Y/120	3,001 – 4,000	65,000
3Ø	480	600 OR LESS (SEE If)	30,000

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/07/22	Е						
A	EDITORIAL CHANGES		LSM	LSM	TPM	11/01/17	D						

SHEET 1 OF 2 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY'S CONTRIBUTION TO FAULT CURRENT

SG006.1

TABLE 2 (CONT'D):

PHASE	SERVING VOLTAGE (VOLTS)	SERVICE ENTRANCE AMPACITY (AMPS)	UTILITY'S CONTRIBUTION TO FAULT CURRENT WILL NOT EXCEED (AMPS)
3Ø	480Y/277	2,000 OR LESS	30,000
3Ø	480Y/277	2,001 – 3,000	45,000
3Ø	480Y/277	3,001 – 4,000	65,000

- d. SDG&E'S AVAILABLE FAULT CURRENT FOR MEDIUM AND HIGH VOLTAGE SERVICES WILL BE CALCULATED ON AN INDIVIDUAL BASIS AND WILL BE QUOTED FOR BOTH THE INITIAL AND ULTIMATE THREE-PHASE, LINE-TO-LINE, AND LINE-TO-GROUND FAULT CURRENT VALUES.
- e. MAXIMUM SERVICE PANEL SIZE ALLOWED TO BE SERVED BY A 120/240 VOLT, THREE-PHASE DELTA-CONNECTED TRANSFORMER INSTALLATION, OVERHEAD OR UNDERGROUND, IS 600 AMPS.
- f. MAXIMUM SERVICE PANEL SIZE ALLOWED TO BE SERVED BY AN OVERHEAD 480 VOLT, THREE-PHASE DELTA-CONNECTED TRANSFORMER INSTALLATION IS 600 AMPS.

REFERENCE:

a. REFER TO DM6142

© 1998 - 2023 San Diego Gas & Flectric Company	All rights reserved. Removal of this copyright notice without	permission is not permitted under law
e 1000 E0E0 Can Blogo Cao a Elocato Company	7 th rights received. I terrieval of the copyright hotice without	pormisorom to not pormittod andor law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/07/22	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/17	D						

SHEET 2 OF 2 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG006.2

SCOPE: THIS STANDARD PROVIDES PRIMARY FUSING INFORMATION FOR SDG&E DISTRIBUTION TRANSFORMERS.

TABLE 1

			REPLACEM	IENT FUSE FOR BA	Y-O-NET	
	TRANSFOR	MER		CA	TALOG NUMBER	
KV	KVA	FUSE SIZE (AMPS)	KEARNEY	RTE	VOLTAGE	IMPEDANCE (%)
	25	15	124080-15	4038105C07		1.2
2.4	50	35	124080-35	-		1.8
	30	40	-	4038105C11		1.0
	75	15	124080-15	4038105C07		1.3
4.16	150	30	124080-30	-		1.5
	500	100	-	4000353C16	-	3.5
	25	6	124080-6	4038105C04		1.2
6.9	50	12	124080-12	4038105C06		1.8
	75	15	124080-15	4038105C07		1.0
	75	6	124080-6	4038105C04		1.3
	150	12	124080-12	4038105C06		1.5
	225	15	124080-15	4038105C07	2400/4160Y/2400 OR 2400/4160GrdY/2400	4.63
	-	-			240/120 3Ø 4W	1.6
	300	25	124000 25	4020105600	208Y/120	2.2
	-	-	124080-25	4038105C09	480Y/277	1.3
12.0	500	40			2400/4160Y/2400 OR 2400/4160GrdY/2400	4.63
	-	-		4000353C12	208Y/120	3.5
	-	-			480Y/277	2.2
	750		-	400005004.4		
	1000	65		4000353C14		
	1500	100		4038361C04CB	-	5.32
	2000	125		403036460565		
	2500	125		4038361C05CB		

	© 1998 - 2025 San Diego Gas & Ele	ectric C	ompai	ny. All	rights r	eserved. Rer	noval (of this copyright notic	e without permission	is not	permit	ted und	der law.	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	СНА	NGE	DR	BY	DSN	APV	DATE
С							F							
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е							
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							
	Y - " - " - " - " - " - " - " - " - " -													

SHEET 1 OF 2

X Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E TRANSFORMER FUSING INFORMATION

SG007.1

TABLE 2

LIVE FRONT TRANSFORMER FUSING TABLE, THREE-PHASE, 12KV TYPE SM-4 RATED 14.4KV											
NOMINAL VOLTAGE (kV)	TRANSFORMER RATING (KVA)	FUSE SIZE (AMPS)	S&C CATALOG NO.	IMPEDANCE (%)							
	1500	125	122200R4								
14.4	2000	150	122250R4	5.32							
	2500, 3000	200	122300R4								

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. THIS INFORMATION MAY BE USED BY THE CUSTOMER'S ENGINEERS WHEN CALCULATING THE INCIDENT ENERGY LEVELS FOR ARC FLASH CONDITIONS, OR PERFORMING PROTECTION COORDINATION STUDIES FOR SECONDARY VOLTAGE SERVICES.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	СНА	NGE	DR	BY	DSN	APV	DATE
С							F							
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е							
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							
	X Indicates La	atest R	evision	า	Con	npletely Revi	ised	New Page	Information Re	moved				

SHEET 2 OF 2

Revision		Completely Revised		New Page		mormation Removed
SDC8	FF	LECTRIC SERVICE ST	V VIL	VDDC & CI	IID	EC

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E TRANSFORMER FUSING INFORMATION

SG007.2

SCOPE: THIS STANDARD ILLUSTRATES THE UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE. (B)(a)(1) C **GRADE LEVEL** (4) **FIGURE 1 EXAMPLE 1** APPLIES TO TWO DWELLING UNITS WITH GROUPED METERS WITH (D) I (IV) V (VI) (WI) A COMBINED SERVICE RATING OF 225A MAXIMUM SEE TABLES 1 AND 2 ΑXΕ (5) F 18" MAX. 2 X 3 \bigcirc **GRADE LEVEL FIGURE 2 EXAMPLE 2** APPLIES TO MULTI-FAMILY RESIDENTIAL BUILDINGS WITH 3 OR MORE (D) G VII VIII (IX) XI) RESIDENTIAL DWELLING UNITS WITH GROUPED METERS SEE TABLES 1 AND 2 © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV REV** DSN APV DSN APV DATE **CHANGE** DR BY DATE **CHANGE** DR BY С F В FORMATTING/EDITORIAL CHANGES **EDM IWA** JTM KRG 02/26/2025 Ε **EDITORIAL CHANGES** LSM BRB TPM 11/01/2017 Α Completely Revised New Page X Information Removed **Indicates Latest Revision** SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG008.1 1 OF 6 UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE SERVICE EXAMPLES




FIGURE 3

EXAMPLE 3

APPLIES TO <u>ADDING ONE NEW RESIDENTIAL METER SET TO TWO EXISTING</u> DVIII XXI XII XIII DWELLING UNITS WITH GROUPED METERS 600A OR LESS SERVICE AMPACITY. SEE TABLES 1 AND 2




FIGURE 4

EXAMPLE 4

APPLIES TO MULTI-FAMILY RESIDENTIAL BUILDINGS WITH 3 OR MORE (D) G (VIII) (IX) XI (XIV) RESIDENTIAL UNITS WITH GROUPED METERS SEE TABLES 1 AND 2

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 2 OF 6 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE SERVICE EXAMPLES




FIGURE 5

EXAMPLE 5

APPLIES TO RESIDENTIAL UNITS (3 OR MORE) WITH GROUPED METERS (D)(G)(IX)(XI) IN A METER CABINET (DOORS NOT SHOWN) WITH A SERVING VOLTAGE OF SINGLE-PHASE, 3-WIRE, 120/240V, 600A MAXIMUM SEE TABLES 1 AND 2




FIGURE 6 EXAMPLE 6

APPLIES TO COMMERCIAL OR INDUSTRIAL GROUPED METERING (D) G (II) (XI) (XV)

SEE TABLES 1 AND 2

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						
		•									•		

SHEET 3 OF 6 Indicates Latest Revision | Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE SERVICE EXAMPLES




FIGURE 7 EXAMPLE 7

APPLIES TO TEMPORARY SERVICE – OVERHEAD OR UNDERGROUND TO SERVE
RESIDENTIAL AND COMMERCIAL/INDUSTRIAL PREMISES WITH A 200A MAXIMUM, D II XI XV
SINGLE-PHASE OR THREE-PHASE SERVICE
SEE TABLES 1 AND 2

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 4 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE SERVICE EXAMPLES

TABLE 1

	FIGURE ITEMS	
ITEM	DESCRIPTION	COMMENT
$\langle 1 \rangle$	RISER AND WEATHERHEAD, NEW	DECHIDED
\1/	GUTTER, LINE, NEW	REQUIRED
2	METER, PROPOSED NEW	
(3)	DISCONNECT, SERVICE, PROPOSED NEW	
4	METER, EXISTING	
	RISER AND WEATHERHEAD, NEW	SHOWN ON FIGURE
(5)	GUTTER, LINE, NEW	IF REQUIRED
	TAPPING FROM EXISTING GUTTER, LINE	
6	DISCONNECT, SERVICE, METER	
7	SOCKET, METER	
8	EQUIPMENT, SERVICE, RATED 600A, 3-WIRE, SINGLE-PHASE, 120/240V	
9	DISCONNECT, MAIN	
$\langle 10 \rangle$	FACILITIES, TEST-BYPASS (IN THIS COMPARTMENT)	
(11)	EQUIPMENT, SERVICE, RATED 400A MAXIMUM	
(12)	EQUIPMENT, SERVICE, RATED 200A MAXIMUM	
(13)	LATERAL, SERVICE UNDERGROUND (OPTIONAL)	

TABLE 2

	UTILITY FAULT CURRENT CONTRIBUTION													
ITEM	PANEL (AMPS)	UTILITY'S MAXIMUM CONTRIBUTION TO FAULT CURRENT (AMPS)												
$\hat{\Lambda}$	-	10,000												
Δ	-	22,000												
/2∖	-	42,000												
<u></u>	-	22,000												
\wedge	226-600	22,000												
/4\	800	42,000												
<u>/</u> 5\	-	42,000												

INSTALLATION:

- (A) service riser to be located on wall facing utility pole line or within 18 inches of building corner.
- (B) EXCEPTION AS PERMITTED ON SG103, FIGURES 1-3
- (C) residential clearances required
- (D) ELECTRICIAN SHALL PROVIDE EQUIPMENT RATED FOR THE FAULT CURRENT OF THE SYSTEM.
- (E) NO EXCEPTIONS PERMITTED PER GO95.
- (F) COMMERCIAL CLEARANCES REQUIRED
- (G) A MAIN DISCONNECT IS REQUIRED AHEAD OF 7 OR MORE METER SERVICE DISCONNECTS.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 5 OF 6

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE SERVICE EXAMPLES

INSTALLATION (CONT'D):

- (H) MAXIMUM OF 3 PARALLEL RUNS OF OVERHEAD SERVICE ENTRANCE CONDUCTORS PER PHASE TO SUPPLY THE LOAD FOR ONE SERVICE.
- METER SERVICE DISCONNECT IF SERVED OVERHEAD. IF SERVED UNDERGROUND, METER SERVICE DISCONNECT TO BE LOCATED IMMEDIATELY ADJACENT TO SERVICE AND METER PANEL.

BILL OF MATERIALS: NONE

NOTES:

- $\left(
 m I\left.
 ight)$ exception: Two main service disconnects rated 125A each is permissible.
- (II) FACTORY-INSTALLED TEST-BYPASS FACILITIES ARE REQUIRED FOR 100 AND 200A COMMERCIAL/INDUSTRIAL SERVICE EQUIPMENT.
- m (III) TEST-BYPASS FACILITIES ARE REQUIRED FOR ALL 200A OR LESS TEMPORARY SERVICES.

CONCLUSIONS:

- (IV) RESIDENTIAL METERING EQUIPMENT IS ACCEPTABLE.
- (V) UTILITY CONTRIBUTION TO FAULT CURRENT WILL NOT EXCEED 10,000A. (b)
- (VI) RESIDENTIAL CLEARANCES APPLY PER G.O. 95.
- $(\! ext{VII}\!)$ NEW DWELLING UNIT METER MUST NOT EXCEED 225A MAXIMUM, SINGLE-PHASE, 120/240V.
- (VIII) TEST-BYPASS FACILITIES ARE NOT REQUIRED.
- (IX) UTILITY'S CONTRIBUTION TO FAULT CURRENT WILL NOT EXCEED THE VALUES SHOWN ON SG006, TABLE 1 AND ARE BASED ON THE SERVICE AMPACITY. (b)
- (XI) COMMERCIAL CLEARANCES APPLY PER G.O. 95. (c)
- (XII) 600A MAXIMUM SERVICE SIZE, SINGLE-PHASE, 120/240V
- (XIII) IF SERVICE AMPERAGE EXCEEDS 600A, SEE SG006, TABLE 1 FOR UTILITY'S MAXIMUM CONTRIBUTION TO FAULT CURRENT. (b)
- (XIV) NEW HOUSE METER 225A MAXIMUM, 1-PHASE, 120/240V
- UTILITY CONTRIBUTION TO FAULT CURRENT WILL NOT EXCEED THE VALUES SHOWN ON SG006, TABLE 2 AND ARE BASED ON THE SERVICE AMPACITY. (d)
- (XVI) NEW DWELLING UNIT METER PLUS EXISTING MUST NOT EXCEED 225A MAXIMUM, SINGLE-PHASE, 120/240V.

REFERENCE:

- (a) SEE SG103, FIGURES 1-3.
- (b) SEE SG006, TABLE 1.
- (c) SEE G.O. 95.
- (d) SEE SG006, TABLE 2.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.	
--	--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 6 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY'S CONTRIBUTION TO FAULT CURRENT SECONDARY VOLTAGE SERVICE EXAMPLES

SCOPE: THIS STANDARD HAS BEEN COMPILED AS A GUIDE FOR A TYPICAL INSTALLATION OF UTILITY DISTRIBUTION FACILITIES IN A CUSTOMER-OWNED VAULT. THE INFORMATION IS TO BE USED ONLY AS A GUIDELINE AND NOT FOR THE DESIGN OR CONSTRUCTION OF THE VAULT, OR INSTALLATION OF ELECTRICAL EQUIPMENT.

INSTALLATION:

CUSTOMER SHALL FURNISH, INSTALL, OWN, AND MAINTAIN:

A. VAULT:

- 1. THE WALLS AND ROOF SHALL BE CONSTRUCTED OF 6 INCHES MINIMUM REINFORCED CONCRETE, REINFORCED CONCRETE BLOCK, OR 8 INCHES MINIMUM REINFORCED BRICK. ALL CONCRETE BLOCK OR BRICK JOINTS ARE TO BE MORTARED SOLID. A 6-INCH THRESHOLD FOR OIL RETENTION IS REQUIRED AT ALL ACCESS OPENINGS INTO THE VAULT. THE VAULT FLOOR IS TO BE CAPABLE OF SUPPORTING COMBINED EQUIPMENT WEIGHT AS REQUIRED.
- 2. WHEREVER A VAULT IS CONSTRUCTED OVER SUB LEVELS OF A STRUCTURE, THE CUSTOMER IS TO PROVIDE SDG&E WITH A CERTIFICATE FROM A REGISTERED CIVIL ENGINEER VERIFYING THE STRUCTURAL ADEQUACY OF THE BUILDING TO SUPPORT THE TRANSFORMERS UNDER NORMAL AND STRUCTURAL FIRE CONDITIONS AS WELL AS FIRE WITHSTANDING CAPABILITIES OF THE STRUCTURE FLOOR, CEILING, AND WALLS.
- 3. ANY VAULT CONSTRUCTION BELOW FINISHED GRADE IS TO BE CONSIDERED A DRY VAULT. THE EXTERIOR SURFACES OF A DRY VAULT WHICH ARE EXPOSED TO SURROUNDING EARTH CONDITIONS WILL BE MOISTURE-PROOFED AGAINST WATER ENTRY. A VAULT MUST BE CONNECTED TO THE BUILDING OR STRUCTURE WITH A MAIN DOOR FOR ENTRANCE AND EXIT.
- 4. NO DUCTS, PIPES, OR CONDUITS, EXCEPT THOSE WHICH ARE A PART OF THE ELECTRICAL INSTALLATION, SHALL BE INSTALLED IN OR THROUGH THE VAULT. WATER-TYPE FIRE SPRINKLER SYSTEMS ARE PROHIBITED IN ANY VAULT. CUSTOMER MUST INFORM THE UTILITY WHEN ANY PRE-STRESSED CONCRETE PORTIONS OF A VAULT ARE PROPOSED FOR CONSTRUCTION.

B. CONDUIT AND BUS DUCT:

- 1. PRIMARY CONDUITS SHALL BE EITHER DIRECT-BURIED OR CONCRETE-ENCASED AS SPECIFIED BY SDG&E.
- 2. THERE ARE NO RESTRICTIONS ON THE APPLICATION OF CUSTOMER-SUPPLIED BUS DUCT. ANY SIZE PANEL MAY BE FED BY BUS DUCT, AT THE OPTION OF THE CUSTOMER. THE ONLY EXCEPTION IS BUS DUCT <u>CANNOT BE APPLIED IN CASES WHERE MORE THAN ONE SERVICE POINT WILL BE SERVED BY A SINGLE TRANSFORMER.</u>
- 3. CUSTOMERS MAY ELECT THE OPTION OF HAVING THE UTILITY INSTALL AND MAINTAIN SERVICE LATERAL CONDUCTORS, REGARDLESS OF BOARD SIZE, GIVEN THE REQUIRED CRITERIA ARE MET TO THE SATISFACTION OF THE UTILITY.
- 4. THE TRANSFORMER TO THE TERMINATING ENCLOSURE DISTANCE IS LIMITED TO 75 CONDUIT FEET, WHICH INCLUDES THE ELBOWS.

C. CUSTOMER'S METERING FACILITIES:

SERVICE EQUIPMENT IS TO BE INSTALLED IN ACCORDANCE WITH SDG&E'S SERVICE STANDARDS & GUIDE. METERS AND SERVICE EQUIPMENT ARE NOT PERMITTED IN THE VAULT.

D. <u>DRAINAGE SYSTEM:</u>

STANDARD FLOOR DRAINS MUST DRAIN TO A DRY SUMP LOCATION AS DETERMINED AND APPROVED BY THE APPROPRIATE INSPECTION AUTHORITY. FLOOR DRAINS ARE NOT TO BE CONNECTED TO THE SEWER OR DRAIN SYSTEM.

E. EQUIPMENT OPENINGS:

1. BELOW GRADE: WHEN THE EQUIPMENT OPENING IS TO BE THROUGH A VAULT CEILING, THE CUSTOMER SHALL PROVIDE A REMOVABLE 3-HOUR FIRE APPROVED CONCRETE COVER. BOTH OPENING AND COVER SHALL HAVE MATCHING BEVELED EDGES, WITH MINIMUM 1/2-INCH VERTICAL DEFLECTION. FOUR LIFTING INSERTS ARE TO BE PROVIDED FOR REMOVAL OF THE COVER. LIFTING INSERTS ARE TO BE 1-INCH MINIMUM COIL, WITH SLOTTED SETTING STUDS, AS SUPPLIED BY A PROFESSIONAL CONCRETE ACCESSARY PRODUCTS COMPANY. THE EQUIPMENT OPENING INSIDE AND OUT MUST BE KEPT CLEAR AND UNOBSTRUCTED BY CUSTOMER-INSTALLED EQUIPMENT. PROPER CLEARANCE FOR OPERATION OF HEAVY EQUIPMENT, INCLUDING CRANES, MUST BE PROVIDED ABOVE THE OPENING FOR INSTALLATION AND REMOVAL OF MATERIAL AND EQUIPMENT IN AND OUT OF THE VAULT. CONTACT THE UTILITY FOR REQUIRED CLEARANCES. CUSTOMER SHALL SEAL THE COVER TO PREVENT WATER ENTRY FOLLOWING INSTALLATION OF EQUIPMENT.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

			-		•	•	-					· · · · · · · · · · · · · · · · · · ·		•			
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		СНА	NGE	DR	BY	DSN	APV	DATE
С									F								
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е								
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D								
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed	New Pag	е	Information Re	moved	ı			
	CHEET				SDC	3&E E	LECTI	RIC SERVIC	E STA	Andards &	GUID	ES					

SHEET 1 OF 3

TRANSFORMER VAULTS

SG009.1

INSTALLATION (CONT'D):

CUSTOMER SHALL FURNISH, INSTALL, OWN, AND MAINTAIN (CONT'D):

E. EQUIPMENT OPENINGS (CONT'D):

2. ON GRADE: EQUIPMENT OPENING IS TO BE THROUGH AN EXTERIOR VAULT WALL, AND THE EQUIPMENT DOOR IS TO BE 3-HOUR FIRE APPROVED. CUSTOMER IS TO PROVIDE AND INSTALL A SCHLAGE VTQP QUAD SECTION MA SERIES KEY SECTION IN A STOREROOM FUNCTION (SELF-LOCKING) RHODES SERIES LOCKSET. SDG&E WILL REPLACE THE MA SERIES CYLINDER WITH AN ELECTRIC SERIES CYLINDER PRIOR TO ENERGIZING EQUIPMENT IN THE VAULT. THE CUSTOMER IS REQUIRED TO NOTIFY SDG&E'S INSPECTOR WHEN THE LOCKSET IS INSTALLED. THE UTILITY WILL REPLACE THE MA SERIES CYLINDER PRIOR TO ENERGIZING THE SERVICE. A PERMANENT 6-FOOT CLEAR AND LEVEL WORKING AREA IS REQUIRED AT THE VAULT FLOOR LEVEL OUTSIDE THE ACCESS DOOR. DOOR SHALL PROVIDE 24-HOUR DIRECT ACCESS FOR UTILITY PERSONNEL.

F. GROUNDING SYSTEM:

A GROUND GRID WILL BE REQUIRED WITHIN THE VAULT, AND THE REQUIREMENTS WILL BE AS SPECIFIED ON THE DRAWINGS PROVIDED BY SDG&E.

G. LIGHTING:

THE VAULT IS TO BE ILLUMINATED. THE VENTILATION BLOWER MOTOR AND VAULT LIGHTING SYSTEM ARE TO BE SEPARATELY PROTECTED.

H. PERSONNEL ACCESS DOOR:

- 1. A MINIMUM 3-FOOT WIDE X 6'-8" HIGH, 3-HOUR FIRE RATED, SELF-CLOSING PERSONNEL ACCESS DOOR IS REQUIRED. (a)
- 2. ACCESS MUST BE THROUGH A DOOR ON AN EXTERIOR WALL OF THE BUILDING TO PROVIDE IMMEDIATE 24-HOUR-A-DAY ACCESS. THE DOOR MUST SWING OUT OF THE ROOM IN THE DIRECTION OF EGRESS, AND IT MUST BE EQUIPPED WITH PANIC HARDWARE. IF THE DOOR IS TO BE LOCKED DURING CONSTRUCTION AND PRIOR TO ENERGIZING ELECTRICAL EQUIPMENT IN THE VAULT, THE CUSTOMER IS REQUIRED TO PROVIDE AND INSTALL A SCHLAGE VTQP QUAD SECTION MA SERIES KEY SECTION IN A STOREROOM FUNCTION (SELF-LOCKING) RHODES SERIES LOCKSET. THE CUSTOMER IS REQUIRED TO NOTIFY SDG&E'S INSPECTOR WHEN THE LOCKSET IS INSTALLED. SDG&E WILL REPLACE THE MA SERIES CYLINDER WITH AN ELECTRIC SERIES CYLINDER PRIOR TO ENERGIZING EQUIPMENT IN THE VAULT.
- 3. THE DOOR THRESHOLD IS TO BE 6 INCHES ABOVE THE VAULT FLOOR FOR OIL RETENTION.
- 4. THE CUSTOMER SHALL PROVIDE SDG&E WITH AN APPROVED ROUTE AND ACCESS EASEMENT TO THE PERSONNEL ACCESS DOOR IN THE VAULT. THE DOOR SHALL PROVIDE DIRECT 24-HOUR ACCESS FOR UTILITY PERSONNEL.

J. PICK UP INSERTS AND PULLING EYES:

PICK UP INSERTS AND PULLING EYES ARE REQUIRED FOR INSTALLATION OF THE TRANSFORMER, AND THE PULLING AND TRAINING OF THE CABLES.

K. <u>VENTILATION SYSTEMS:</u>

- 1. THE CUSTOMER SHALL PROVIDE FOR ADEQUATE VENTILATION, ALL VENTS OR DUCTING, AND RELATED FACILITIES AS REQUIRED BY SDG&E.
- 2. INSTALLATION IS TO COMPLY WITH ALL LOCAL CODES AND ORDINANCES.
- 3. FIRE DAMPERS MAY BE REQUIRED BY THE APPROPRIATE INSPECTION AUTHORITY.

WHEN TRANSFORMER VAULTS ARE IMPROPERLY CONSTRUCTED BECAUSE THE UTILITY WAS NOT CONTACTED IN ADVANCE, THE CUSTOMER WILL BE RESPONSIBLE FOR ALL MODIFICATIONS.

SDG&E WILL FURNISH, INSTALL, OWN, AND MAINTAIN:

- L. TRANSFORMERS
- M. PRIMARY DISTRIBUTION CABLE AND EQUIPMENT

	© 1998 - 2025 Sa	an D	iego Gas & Ele	ectric C	ompa	ny. All	rights r	reserved. Rer	moval o	of th	is copyright no	tice	without permission	is not	permit	ted und	der law.	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	HAN	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	ORI/	AL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е									
Α	EDITORIAL C	CHAI	NGES	-	LSM	IPJ	TPM	11/01/2017	D									
		Χ	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Ren	noved				
	SHEET				SDC	&E E	LECTI	RIC SERVIC	E STA	١N	DARDS & GL	IIDI	ES					
				•				•								S	G00	9.2
	2 OF 3						TRA	NSFORM	1ER	V٨	AULTS						230	·-

INSTALLATION (CONT'D):

SDG&E WILL FURNISH, INSTALL, OWN, AND MAINTAIN (CONT'D):

- N. SERVICE LATERAL CONDUCTORS (IN CUSTOMER'S CONDUIT) FROM TRANSFORMER SECONDARY TERMINALS TO THE CUSTOMERS TERMINATING ENCLOSURE (UNDERGROUND PULL SECTION)
- O. SERVICE LATERAL CONDUCTORS FROM THE TRANSFORMER SECONDARY TERMINALS TO THE BUS STUBS WHERE THE CUSTOMER PROVIDES A BUS DUCT SERVICE

BILL OF MATERIALS: NONE

NOTES:

- I. ALL REQUESTS FOR VAULT DESIGN MUST BE REVIEWED AND APPROVED BY SDG&E (UTILITY) DURING THE ARCHITECTURAL DESIGN PHASE OF THE PROJECT. A MEETING WITH UTILITY REPRESENTATIVES IS BENEFICIAL TO ALL PARTIES EARLY IN THE DESIGN PHASE TO ENSURE PROPER COMPLIANCE WITH VAULT STANDARDS. THE MAIN ELEMENTS THAT WILL BE REVIEWED DURING THE MEETING INCLUDE THE FOLLOWING:
 - a. ACCESS FOR TRANSFORMER INSTALLATION AND MAINTENANCE
 - b. ACCESS TO INSTALL AND MAINTAIN THE SERVICE LATERAL CONDUCTORS
 - OTHER REQUIREMENTS APPLICABLE TO VAULT INSTALLATIONS SUCH AS POWER VENTILATION, LIGHTING, PERSONNEL ACCESS, ETC.
- II. THE DIMENSIONS WILL VARY IN SIZE DEPENDING UPON THE BUS AMPACITY OF THE CUSTOMER SERVICE ENTRANCE EQUIPMENT, SERVING VOLTAGE AND SIZE OF THE TRANSFORMER TO BE INSTALLED BY SDG&E. A TYPICAL VAULT SIZE COULD RANGE ANYWHERE FROM 13'-6" X 9'-6" X 8'-0" HIGH (FOR A 400A SERVICE) TO 20'-0" X 16'-6" X 12'-0" HIGH (FOR A 4,000A SERVICE) PROVIDED NO EQUIPMENT OTHER THAN THE TRANSFORMER IS REQUIRED IN THE VAULT.
- III. VAULT INSTALLATIONS MUST BE IN COMPLIANCE WITH ALL APPLICABLE RULES OF THE ELECTRICAL SAFETY ORDERS OF THE DIVISION OF INDUSTRIAL SAFETY, DEPARTMENT OF INDUSTRIAL RELATIONS, STATE OF CALIFORNIA, NATIONAL ELECTRICAL CODE, OTHER GOVERNING CODES AND ORDINANCES, AND COMPLY WITH REQUIREMENTS OF THE UTILITY.

REFERENCE:

(a) REFER TO THE SDG&E ELECTRIC VAULT REQUIREMENTS AND SPECIFICATIONS DOCUMENT.

	© 1998 - 2025 S	an Diego Gas & Ele	ectric C	ompa	ny. All	rights r	eserved. Rer	noval (of this copyright no	otice	without permission	is not	permit	ted und	der law.	
REV	CHAN	IGE	DR	BY	DSN	APV	DATE	REV	CI	HAN	IGE	DR	BY	DSN	APV	DATE
С								F								
В	FORMATTING/EDIT	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е								
Α	EDITORIAL (CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
		X Indicates La	atest R	evisio	n	Con	npletely Revi	sed	New Page		Information Rea	noved				
	SHEET			SDC	S&E E	LECTI	RIC SERVIC	E STA	Andards & Gl	JIDE	ES					

SHEET 3 OF 3

TRANSFORMER VAULTS

SG009.3

SCOPE: THIS STANDARD OUTLINES THE SDG&E (UTILITY) REQUIREMENT FOR THIRD-PARTY TESTING OF METAL-ENCLOSED SERVICE ENTRANCE AND UNMETERED FEEDER BUSWAYS.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. THE UTILITY REQUIRES THE INSPECTION AND TESTING OF METAL-ENCLOSED "SERVICE ENTRANCE AND UNMETERED FEEDER BUSWAYS" IN ACCORDANCE WITH THE LATEST EDITION OF THE INTERNATIONAL ELECTRICAL TESTING ASSOCIATION, INC. (NETA), ACCEPTANCE TESTING SPECIFICATIONS FOR ELECTRICAL POWER DISTRIBUTION EQUIPMENT AND SYSTEMS AS SHOWN IN TABLE 1.

TABLE 1

	NETA SPECIFICATIONS REQUIRED INSPECTION AND TESTING INFORMA	TION
SECTION	TOPIC	REQUIREMENTS
3	QUALIFICATIONS OF TESTING ORGANIZATION AND PERSONNEL	-
3.1	TESTING ORGANIZATION (II)	AS PUBLISHED
3.2	TESTING PERSONNEL	AS PUBLISHED
7.4	METAL-ENCLOSED BUSWAYS	-
7.4.1	VISUAL AND MECHANICAL INSPECTION	AS PUBLISHED
7.4.2	ELECTRICAL TESTS	AS PUBLISHED
7.4.3	TEST VALUES	AS PUBLISHED

- (II) A TESTING ORGANIZATION THAT DOES NOT HAVE A "FULL MEMBERSHIP" IN NETA BUT MEETS ALL OTHER REQUIREMENTS OF SECTION 3.1 AND 3.2, AND TESTS IN COMPLIANCE WITH NETA SPECIFICATIONS NOTED BELOW, MAY BE ALLOWED TO PERFORM THE TESTING IF ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION (AHJ) AND THE UTILITY.
- III. THE INSTALLER OF THE SYSTEM SHALL PROVIDE A WRITTEN TEST REPORT TO THE AHJ AND THE UTILITY'S INSPECTOR. THE AHJ WILL NOT RELEASE AN INSPECTION CLEARANCE TO THE UTILITY, NOR WILL THE UTILITY ENERGIZE ITS TRANSFORMER AND SERVICE UNTIL RECEIPT, REVIEW, AND ACCEPTANCE OF THE WRITTEN TEST REPORT.

REFERENCE: NONE

	© 1998 - 2025 Sa	an Diego Gas & El	ectric C	Compa	ny. All	rights ı	reserved. Rer	moval o	of th	nis copyright no	tice	without permission	is not	permit	ted und	der law	
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CH	IAI	NGE	DR	BY	DSN	APV	DATE
С								F									
В	FORMAT	TING	EDM	JIK	JTM	KRG	02/26/2025	Е									
Α	EDITORIAL (CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X Indicates L	atest R	Revisio	n	Con	npletely Revi	ised		New Page		Information Re	moved				
	CHEET			SDC	G&E E	LECTI	RIC SERVIC	E STA	٩NI	DARDS & GU	ID	ES					

SHEET 1 OF 1

TESTING REQUIREMENTS FOR METAL-ENCLOSED SERVICE ENTRANCE AND UNMETERED FEEDER BUSWAYS

SG010.1

SCOPE: THIS STANDARD DESCRIBES SDG&E ELECTRIC SERVICE POLICIES FOR NEW AND EXISTING CUSTOMERS.

DEFINITIONS:

- **PRACTICABLE:** IN REFERENCE TO THE SERVICE DELIVERY POINT, PRACTICABLE IS DEFINED AS ANY BUILDING SURFACE, OTHER THAN THE BUILDING ENTRANCE (DOORS), GLASS WALLS, OR WINDOWS, WHICH IS ACCESSIBLE. DECORATIVE WALLS WILL BE CONSIDERED AS A PRACTICABLE LOCATION FOR THE PURPOSE OF LOCATING SERVICE TERMINATING ENCLOSURES.
- ACCESSIBLE: IN REFERENCE TO TERMINATING ENCLOSURES, ACCESSIBLE IS DEFINED AS BEING READILY AND PERMANENTLY LOCATED ON OR RECESSED IN AN EXTERIOR WALL OF THE BUILDING SERVED, FACING OUTWARD.

ATTENTION:

* A TERMINATING ENCLOSURE SHALL BE PERMANENTLY ACCESSIBLE WITHOUT ENTERING THE BUILDING, SHALL NOT PROJECT INTO ANY DRIVEWAY, WALK OR PUBLIC WAY, AND SHALL PROVIDE ACCESS AND WORKING SPACE IN COMPLIANCE WITH ALL SERVICE STANDARDS & GUIDE REQUIREMENTS. BY SPECIAL PERMISSION, THE TERMINATING ENCLOSURE MAY BE INSTALLED IN AN ELECTRIC METER ROOM OR IN A PARKING STRUCTURE WHEN APPROVED BY THE UTILITY AND INSTALLED PER THE UTILITY'S APPLICABLE STANDARDS. (a) (b)

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. SDG&E (UTILITY) WILL NOT NORMALLY PROVIDE MORE THAN ONE ELECTRIC SERVICE EXTENSION FOR ANY ONE BUILDING OR GROUP OF BUILDINGS, FOR A SINGLE ENTERPRISE ON A SINGLE PREMISE, EXCEPT:
 - a. TARIFF SCHEDULES WHERE OTHERWISE ALLOWED OR REQUIRED UNDER THE UTILITY'S TARIFF SCHEDULES, OR
 - b. **UTILITY CONVENIENCE** AT THE OPTION OF, AND AS DETERMINED BY THE UTILITY, FOR ITS OPERATING CONVENIENCE, CONSISTENT WITH ITS ENGINEERING DESIGN FOR DIFFERENT VOLTAGE AND PHASE CLASSIFICATION, OR WHEN REPLACING AN EXISTING SERVICE, OR
 - c. **ORDINANCE** WHERE REQUIRED BY ORDINANCE OR OTHER APPLICABLE LAW, FOR SUCH THINGS AS FIRE PUMPS, FIRE ALARM SYSTEMS, ETC.

GENERAL INFORMATION:

II. SERVICE DELIVERY POINT POLICY:

NEW UNDERGROUND ELECTRIC SERVICE INSTALLATIONS SHALL COMPLY WITH THE UTILITY'S SERVICE DELIVERY POINT POLICY.

GENERAL REQUIREMENTS:

- III. ONE SERVICE DELIVERY POINT WILL NORMALLY BE ESTABLISHED AS NEAR AS PRACTICABLE TO THE CLOSEST CORNER OF THE BUILDING WALL WHICH IS ACCESSIBLE, WITH A MINIMUM LENGTH OF SERVICE LATERAL CONDUCTORS FROM THE UTILITY'S SOURCE. AESTHETICS WILL NOT BE CONSIDERED WHEN DETERMINING THE SERVICE DELIVERY POINT.
 - a. ALL UTILITY METERS AND ASSOCIATED METERING EQUIPMENT SHALL BE LOCATED AT SOME PROTECTED LOCATION ON APPLICANT'S PREMISES AS APPROVED BY THE UTILITY.
 - b. IN A BUILDING WITH TWO OR MORE TENANTS, OR WHERE THE UTILITY FURNISHES MORE THAN ONE METER ON THE SAME PREMISES, UTILITY'S METERS NORMALLY SHALL BE GROUPED AT ONE CENTRAL LOCATION.
 - c. MORE THAN ONE GROUP OF METERS MAY BE ESTABLISHED WHERE ACCEPTABLE TO THE UTILITY, PROVIDED THE APPLICANT INSTALLS, OWNS, AND MAINTAINS THE SERVICE ENTRANCE CONDUIT(S) AND CONDUCTORS FROM THE SERVICE DELIVERY POINT (TERMINATING ENCLOSURE) TO EACH METER LOCATION IN COMPLIANCE WITH THE UTILITY'S REQUIREMENTS AND RECEIVES PRIOR APPROVAL FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		C	HAN	IGE	DR	BY	DSN	APV	DATE
С								F									
В	FORMAT	TING	EDM	JIK	JTM	KRG	02/26/2025	Е									
Α	EDITORIAL C	CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X Indicates L	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Re	moved				
	SHEET	•		SDC	S&E E	LECTI	RIC SERVIC	E STA	١ND	ARDS & GL	JIDE	ES					
		·													S	G01	1.1
	1 OF 3				EL	ECT	RIC SER	VICE	P	OLICIES					3	GUI	1.1

NEW AND EXISTING CUSTOMERS

NOTES (CONT'D):

GENERAL REQUIREMENTS (CONT'D):

III. (CONT'D):

d. FOR SINGLE- AND MULTI-FAMILY RESIDENTIAL BUILDINGS, AND SINGLE- AND MULTI-OCCUPANCY COMMERCIAL AND INDUSTRIAL BUILDINGS, METERS MAY BE INSTALLED:

OUTDOOR-MOUNTED ON OR RECESSED IN AN EXTERIOR BUILDING WALL.

IN AN APPROVED METER ROOM. (a)

METER LOCATIONS ARE NOT REQUIRED TO BE AT OR NEAR THE SERVICE DELIVERY POINT, BUT ARE TO BE LOCATED IN ACCORDANCE WITH THE UTILITY'S RULES AND SERVICE STANDARDS. \bigcirc

- IV. TWO SERVICE DELIVERY POINTS TO A SINGLE BUILDING OR PREMISES MAY BE ESTABLISHED AT THE UTILITY'S OPTION IF <u>ALL</u> OF THE FOLLOWING REQUIREMENTS ARE MET:
 - a. ALL ELECTRIC SERVICE POLICIES FOR NEW PROJECTS & EXISTING CUSTOMERS AS OUTLINED IN THIS STANDARD ARE MET; AND
 - b. METERS ARE GROUPED AT OR NEAR EACH SERVICE DELIVERY POINT OR AT A LOCATION APPROVED BY THE UTILITY; AND
 - c. THE APPROPRIATE AHJ APPROVES THE INSTALLATION.

ALTERNATE SERVICE DELIVERY POINT REQUESTS:

V. AN APPLICANT MAY REQUEST AN ALTERNATE SERVICE DELIVERY POINT THAT IS NOT NECESSARILY THE CORNER OF THE BUILDING WALL CLOSEST TO THE UTILITY'S UNDERGROUND OR OVERHEAD SOURCE. THE REQUEST MAY BE APPROVED PROVIDED THE REQUESTED LOCATION IS ACCEPTABLE TO THE UTILITY'S PROJECT PLANNER, AND THE APPLICANT AGREES TO PAY FOR THE ADDITIONAL FACILITIES REQUIRED PER THE PROVISIONS OF RULE 2, I. SPECIAL FACILITIES AND MAINTENANCE. CONSULT WITH THE UTILITY'S PROJECT PLANNER FOR APPROVAL OF AN ALTERNATE SERVICE DELIVERY POINT IN THE PROJECT'S DESIGN PHASE TO AVOID PROJECT DELAYS AND TO OBTAIN COST INFORMATION. (d)

SERVICE LOCATIONS:

- VI. THE SERVICE DELIVERY POINT MUST BE CONFIRMED IN WRITING BY THE UTILITY'S PROJECT PLANNER. IT IS IMPORTANT TO CONTACT THE UTILITY'S SERVICE PLANNING OR DESIGN & PROJECT MANAGEMENT REGIONAL OFFICE AND REQUEST AN ELECTRIC METER & SERVICE LOCATION FORM FOR THE FOLLOWING: (e)
 - a. A NEW SERVICE CONNECTION IS BEING CONSIDERED FOR ANY TYPE OF PROJECT.
 - b. ADDITIONS, ALTERATIONS, RENEWALS, OR A CHANGE IN THE ELECTRIC SERVICE DELIVERY POINT LOCATION IS BEING PROPOSED TO AN EXISTING SERVICE. THIS INCLUDES, BUT IS NOT LIMITED TO, REPLACEMENT OF CUSTOMER-OWNED SERVICE ENTRANCE CONDUITS, CONDUCTORS, SERVICE EQUIPMENT, OR METERING ENCLOSURES.

RIGHTS OF WAY:

- VII. THE UTILITY WILL OWN, OPERATE AND MAINTAIN DISTRIBUTION LINE EXTENSION FACILITIES ONLY AS FOLLOWS:
 - a. ALONG PUBLIC STREETS, ALLEYS, ROADS, HIGHWAYS AND OTHER PUBLICLY DEDICATED WAYS AND PLACES WHICH THE UTILITY HAS THE LEGAL RIGHT TO OCCUPY (FRANCHISE AREAS); AND
 - b. ON PUBLIC LANDS AND PRIVATE PROPERTY ACROSS WHICH RIGHTS OF WAY AND PERMITS SATISFACTORY TO THE UTILITY MAY BE OBTAINED WITHOUT COST TO OR CONDEMNATION BY THE UTILITY.

VIII.THE CUSTOMER IS RESPONSIBLE FOR PROVIDING A CLEAR ROUTE, FREE OF OBSTRUCTIONS, WHICH WOULD INHIBIT THE CONSTRUCTION OF EITHER UNDERGROUND OR OVERHEAD SERVICE EXTENSIONS ON THEIR PROPERTY.

	DR	BY	DSN	APV	DATE	REV	СН	ANGE	DR	BY	DSN	APV	DATE
						F							
ORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е							
ORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							
X Indica	tes Latest F	Revisio	n	Con	npletely Revi	sed	New Page	Information Re	emoved	ı			
		SDO	G&E E	LECT	RIC SERVIC	E STA	NDARDS & GUI	DES					
											S	G01	1.2
_	FORMATTING FORIAL CHANGES X Indica	TORIAL CHANGES - X Indicates Latest F	TORIAL CHANGES - LSM X Indicates Latest Revision SD0	TORIAL CHANGES - LSM IPJ X Indicates Latest Revision SDG&E E	TORIAL CHANGES - LSM IPJ TPM X Indicates Latest Revision Cor SDG&E ELECTION	CORIAL CHANGES - LSM IPJ TPM 11/01/2017 X Indicates Latest Revision Completely Revi SDG&E ELECTRIC SERVICE	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING - LSM IPJ TPM 11/01/2017 D X Indicates Latest Revision Completely Revised SDG&E ELECTRIC SERVICE STA	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORIAL CHANGES - LSM IPJ TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUI	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING TOWN TOWN TOWN TOWN TOWN TOWN TOWN TOWN	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING CHANGES - LSM IPJ TPM 11/01/2017 D X	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORIAL CHANGES - LSM IPJ TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING EDM JTM JTM JTM JTM JTM JTM JTM JTM JTM JT	FORMATTING EDM JIK JTM KRG 02/26/2025 E FORMATTING EDM JIK JTM

NOTES (CONT'D):

RIGHTS OF WAY (CONT'D):

- IX. THE UTILITY CANNOT BE RESPONSIBLE FOR CORRECTING ANY PORTION OF THE CUSTOMER'S SERVICE INSTALLATION NECESSITATED BY THE CUSTOMER'S OR THEIR CONTRACTOR'S DEVIATION FROM THE UTILITY'S SERVICE STANDARDS & GUIDE REQUIREMENTS, OR WHERE THE SERVICE EQUIPMENT LOCATION WAS ASSUMED AND CONFLICTS WITH THE LOCATION APPROVED BY THE UTILITY'S PROJECT PLANNER.
- XI. A SERVICE LOCATION DOES NOT CONSTITUTE AN "APPLICATION FOR SERVICE". ENSURING AN APPLICATION FOR SERVICE HAS BEEN MADE FOR THE BILLING ACCOUNT CAN HELP AVOID DELAYS IN ESTABLISHING NEW ELECTRIC SERVICE. $\binom{f}{f}$

SECONDARY SERVING VOLTAGES & CLASSIFICATION OF SERVICE INFORMATION:

- XII. THE FOLLOWING ARE THE UTILITY'S STANDARD SECONDARY SERVING VOLTAGES:
 - a. SINGLE-PHASE 120/240V, 120/208V, AND 240/480V (FOR HIGHWAY LIGHTING) VOLTS
 - b. THREE-PHASE DELTA SERVING VOLTAGES 120/240V AND 480V (CORNER-GROUNDED) VOLTS
 - c. THREE-PHASE WYE SERVING VOLTAGES 208Y/120V AND 480Y/277V
 - d. A DIFFERENT CLASS OF SERVICE SHALL BE CONSIDERED TWO SERVICES WITH EACH HAVING A DIFFERENT "PHASE-TO-NEUTRAL"OR "PHASE-TO-GROUND" VOLTAGE.

XIII. THE FOLLOWING THREE-PHASE VOLTAGES ARE CONSIDERED DIFFERENT CLASSES OF SERVICE BY THE UTILITY:

- a. 208Y/120V OR 120/240V
- b. 480V (CORNER-GROUNDED)
- c. 480Y/277V
- d. "SINGLE-PHASE 120/208V AND THREE-PHASE 208Y/120V" ARE THE SAME CLASS OF SERVICE AND ARE NOT CONSIDERED BY THE UTILITY AS A DIFFERENT CLASS OF SERVICE THAN "SINGLE-PHASE OR THREE-PHASE 120/240V". THIS IS BECAUSE THE PHASE-TO-NEUTRAL VOLTAGE IS THE SAME FOR ALL OF THEM (120V).

REFERENCE:

- (a) SEE SG506: ELECTRIC METER ROOM.
- $(\,{}_{
 m b})\,$ SEE SG016: PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES.
- $(\ c\)\$ SEE SG510: ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS.
- (d) SEE RULE 2, I.
- (e) SEE LISTING ON SG021.
- (f) FOR "APPLICATION FOR A BILLING ACCOUNT" INFORMATION, SEE SG004.

	© 1998 - 2025 San Diego Gas & Ele	ectric C	Compa	ny. All	rights r	eserved. Re	moval o	of this copyright notice without permission	is not	permit	ted un	der law.	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	ī

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	1	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES NEW AND EXISTING CUSTOMERS

SG011.3

SCOPE: THIS STANDARD IS INTENDED TO PROVIDE GUIDANCE TO DEVELOPERS, ARCHITECTS, ENGINEERS, ELECTRICAL CONTRACTORS, AND CONSULTANTS PLANNING CUSTOMERS' NEW ELECTRICAL SERVICE NEEDS.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. GENERAL SERVICE REQUIREMENT TO MULTIPLE MULTI-UNIT BUILDINGS ON A SINGLE PREMISES:

WHEN THERE IS MORE THAN ONE MULTI-UNIT BUILDING ON A SINGLE PREMISES, AN INDIVIDUAL SDG&E SERVICE IS GENERALLY REQUIRED TO EACH OF THE MULTI-UNIT BUILDINGS. BOTH RESIDENTIAL AND NON-RESIDENTIAL APPLICATIONS ARE SUBJECT TO THIS REQUIREMENT. (a)

II. MULTI-FAMILY RESIDENTIAL BUILDINGS – LESS THAN 3 STORIES HIGH:

ONE SERVICE PER BUILDING WILL BE GRANTED, UNLESS THE DISTANCE BETWEEN SERVICE POINTS AND METER LOCATIONS IS 300 FEET OR GREATER. IF THE SERVICE SIZE EXCEEDS 4,000A AND A SECOND SERVICE OF THE SAME CLASS IS REQUIRED, THE SERVICE POINTS WILL BE GROUPED AT ONE LOCATION UNLESS THE DISTANCE BETWEEN SERVICE POINTS IS 300 FEET OR GREATER. A SEPARATE SERVICE OF A DIFFERENT CLASS, NORMALLY 480Y/277V FOR SERVING HOUSE LOADS, MAY BE GRANTED AND GROUPED WITH THE SERVICE(S) FOR THE MULTI-FAMILY DWELLING UNITS OR LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO SDG&E'S (UTILITY'S) PROJECT PLANNER BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY, AND WITH APPROVAL FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ). THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 WILL APPLY, AND THE RULE 15 RESIDENTIAL AND NON-RESIDENTIAL ALLOWANCES WILL BE APPLIED TO THE COST OF ALL SERVICES MEETING THE CRITERIA ABOVE. (b) (c)

III. RESIDENTIAL OR MIXED USE BUILDINGS – 3 STORIES OR GREATER:

THE CUSTOMER MAY RECEIVE AS MANY 3-PHASE, 208Y/120V SERVICES AS REQUIRED, NORMALLY GROUPED AT ONE LOCATION, TO SERVE THE DWELLING UNITS THAT MUST BE INDIVIDUALLY METERED BY THE UTILITY. THE PLANNER MAY APPROVE MORE THAN ONE SERVICE POINT AND METER LOCATION FOR SERVICES OF THE SAME CLASS IF THE DISTANCE BETWEEN THEM IS 300 FEET OR GREATER, OR WHEN IT IS IN THE BEST INTEREST OF THE UTILITY TO PROVIDE MULTIPLE SERVICE POINTS AND METER LOCATIONS. A SEPARATE SERVICE OF A DIFFERENT CLASS, NORMALLY 480Y/277V, MAY BE GRANTED FOR HOUSE LOADS AND MAY BE GROUPED WITH THE SERVICE(S) FOR THE MULTI-FAMILY DWELLING UNITS OR LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO THE PROJECT PLANNER BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY, AND WITH APPROVAL FROM THE AHJ. THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 WILL APPLY AND THE RULE 15 RESIDENTIAL AND NON-RESIDENTIAL ALLOWANCES WILL BE APPLIED TO THE COST OF ALL SERVICES MEETING THE CRITERIA ABOVE. (b) (c)

IV. RESIDENTIAL CONTIGUOUS DWELLINGS - TOWNHOUSES (ROW HOMES):

EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON <u>A PARCEL OF LAND BOUNDED BY LEGAL PROPERTY LINES</u> MUST BE PROVIDED WITH AN INDIVIDUAL ELECTRIC SERVICE AND METER(S) LOCATED ON THE PROPERTY SERVED. EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A <u>SINGLE PARCEL OF PROPERTY DIVIDED WITH "ASSUMED PROPERTY LINES"</u> MAY BE:

a. PROVIDED WITH AN INDIVIDUAL ELECTRIC SERVICE AND METER(S) LOCATED ON THE TOWNHOUSE BOUNDED BY ASSUMED PROPERTY LINES, OR

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		Cl	IAN	NGE	DR	BY	DSN	APV	DATE
С								F									
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е									
Α	EDITORIAL (HANGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X Indicates La	atest R	levisio	n	Con	npletely Revi	sed		New Page		Information Re	moved				
	SHEET	1		SDC	S&E E	LECTI	RIC SERVIC	E STA	NDA	ARDS & GU	IDE	ΞS					
															S	G012	2.1
	1 OF 3				EL		RIC SER								J	C012	
	1 01 3						W PROJ										

NOTES (CONT'D):

IV. RESIDENTIAL CONTIGUOUS DWELLINGS - TOWNHOUSES (ROW HOMES)(CONT'D):

b. Served through a single service point, with meters grouped at one location in a common area remote from the buildings. Easements will be required to be established and recorded in the deed of every townhouse allowing for privately-owned electric lines to cross assumed property lines. The utility is not involved in the easement process, but it is important for developers to understand this requirement. Main electric service disconnects (maximum of six) may be grouped at one location to accommodate grouping of the electric service and of the electric service and metering equipment. If the number of service disconnects exceeds six, a main disconnect will be required ahead of all meters and their related meter service disconnect. The meter service disconnect must be located at or immediately adjacent to the meter. A 3/4-inch or larger electrical conduit must be installed, per the requirements of the california electrical code and approved by the Ahj, between the grouped meter location and each individual townhouse. This conduit will provide access for future installation of alternative energy sources, such as photovoltaic systems.

V. SINGLE PREMISES – MULTIPLE NON-RESIDENTIAL ENTERPRISES (SUCH AS SHOPPING CENTERS AND OFFICE BUILDINGS):

ONE SERVICE PER BUILDING WILL BE GRANTED, UNLESS THE DISTANCE BETWEEN METER LOCATIONS IS GREATER THAN 300 FEET OR THE CUSTOMER IS REQUESTING TWO CLASSES OF SERVICE. IN THE CASE OF TWO CLASSES OF SERVICE, THE SERVICES MAY BE GROUPED AT THE SAME LOCATION, OR LOCATED AT TWO SEPARATE MORE CONVENIENT LOCATIONS ACCEPTABLE TO THE UTILITY'S PROJECT PLANNER BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY, AND WITH APPROVAL FROM THE AHJ. THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 FOR SERVICE EXTENSIONS WILL APPLY, AND THE NON-RESIDENTIAL ALLOWANCES PER RULE 15 WILL BE APPLIED TO THE COST OF ALL SERVICES MEETING THE CRITERIA ABOVE. $\begin{pmatrix} b \\ c \end{pmatrix}$

SINGLE PREMISES - SINGLE NON-RESIDENTIAL ENTERPRISE (CUSTOMER):

- VI. NORMALLY, ONE SERVICE PER PREMISES SERVING A SINGLE ENTERPRISE WILL BE GRANTED, FOR EXAMPLE, SCHOOLS, CHURCH COMPLEXES, MANUFACTURING PLANTS, HOSPITALS, ETC.
- VII. IF THE PLANNED SECONDARY VOLTAGE SERVICE EXCEEDS 4,000A, THE UTILITY WILL PROVIDE A MAXIMUM OF 3 SECONDARY VOLTAGE SERVICES RATED AT NOT MORE THAN 4,000A EACH, AND THEY SHALL BE GROUPED TOGETHER AT A SINGLE LOCATION OR AT A LOCATION APPROVED BY THE PROJECT PLANNER AND THE AHJ, BASED ON THE CONFIGURATION AND CAPACITY OF THE UTILITY DISTRIBUTION SYSTEM AND GOOD ENGINEERING PRACTICE. LOADS GREATER THAN 3 AT 4,000A (MAXIMUM 12,000A AT SECONDARY VOLTAGE) WILL REQUIRE THE CUSTOMER TO INSTALL A MEDIUM VOLTAGE SERVICE AND PRIMARY METERING EOUIPMENT.
- VIII. IF MORE THAN ONE SECONDARY VOLTAGE SERVICE IS REQUIRED BECAUSE THE SERVICE SIZE EXCEEDS 4,000A, RULE 16 FOR SERVICE EXTENSIONS WILL APPLY AND RULE 15 NON-RESIDENTIAL ALLOWANCES WILL BE APPLIED TO THE COST OF ALL SERVICES GROUPED AT ONE LOCATION. WHEN THE UTILITY DETERMINES IT IS IN THE CUSTOMER'S BEST INTEREST FOR THE UTILITY TO APPROVE A SECOND OR THIRD SECONDARY VOLTAGE SERVICE OF THE SAME CLASS NOT GROUPED AT ONE LOCATION, THE CUSTOMER WILL PAY FOR ONLY THE ADDITIONAL FACILITIES REQUIRED PER THE PROVISIONS OF RULE 2, SPECIAL FACILITIES, UNLESS THE MINIMUM DISTANCE BETWEEN ALL SERVICES IS AS FOLLOWS: (b) (c) (d)
 - a. 120/240V OR 208Y/120V 500 FEET MINIMUM SEPARATION BETWEEN SERVICES OF THE SAME CLASS IS REQUIRED.
 - b. 480Y/277V 1,000 FEET MINIMUM SEPARATION BETWEEN SERVICES OF THE SAME CLASS IS REQUIRED.
- IX. IF THE CUSTOMER REQUESTS A SECOND CLASS OF SECONDARY VOLTAGE SERVICE, ALL SERVICES MAY BE GROUPED AT THE SAME LOCATION, OR THE SERVICE OF A DIFFERENT CLASS MAY BE LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO THE PROJECT PLANNER AND THE AHJ BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY. THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 FOR SERVICE EXTENSIONS WILL APPLY AND THE NON-RESIDENTIAL ALLOWANCES PER RULE 15 WILL BE APPLIED TO THE COST OF THE SECOND SERVICE OF A DIFFERENT CLASS. (b) (c)

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights	reserved. Rer	moval o	of th	is copyright n	otice	without permission	is not	permit	ted und	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		С	HAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	NG/EDITORIAL CHANGES EDM IWA JTM KRG 02/26/2025 E TORIAL CHANGES - LSM IPJ TPM 11/01/2017 D																
Α	EDITORIAL C	CHAN	NGES - LSM IPJ TPM 11/01/2017 D															
		X	ANGES - LSM IPJ TPM 11/01/2017 D Indicates Latest Revision Completely Revised New Page Information Removed															
	SHEET	,			SDO	G&E E	LECTI	RIC SERVIC	E STA	ANE	DARDS & GL	JIDI	ES					
	· · · ·						ГСТ	חזכ כבם	. /т.СГ	- n						S	G01	2.2
	2 OF 3					EL		RIC SER W PROJ			OLICIES (PES							

XI. SINGLE PREMISES – SINGLE RESIDENTIAL CUSTOMER WITH OTHER ELECTRIC USES:

ONE SERVICE PER PREMISES WILL BE GRANTED. A SECOND SERVICE MAY BE APPROVED FOR OTHER ELECTRIC USES SUCH AS AN ACCESSORY DWELLING UNIT (ADU), WELLS, BARNS, GARAGES, ETC., PROVIDED THE LOCATION IS MORE THAN 150 FEET FROM THE EXISTING SERVICE AND METER LOCATION AT THE RESIDENCE, AND THE AHJ APPROVES A SECOND SERVICE AND METER ON THE PROPERTY. WHEN BOTH OF THESE CONDITIONS ARE MET, RULE 16 WILL APPLY, AND THE RULE 15 NON-RESIDENTIAL ALLOWANCE WILL BE APPLIED TO THE COST OF THE SECOND SERVICE. (b)(c)

XII. SINGLE PREMISES - MULTIPLE RESIDENTIAL CUSTOMERS:

EACH SEPARATE STRUCTURE CONTAINING MORE THAN SIX LEGAL DWELLING UNITS, OR MORE THAN FIVE LEGAL DWELLING UNITS AND A HOUSE METER, MUST BE INDIVIDUALLY SERVED BY THE UTILITY. EACH DWELLING UNIT MUST BE INDIVIDUALLY METERED BY THE UTILITY. RULE 16 FOR SERVICE EXTENSIONS AND THE RESIDENTIAL ALLOWANCES PER RULE 15 FOR EACH DWELLING UNIT WILL APPLY TO EACH SERVICE. APPROVAL BY THE AHJ IS REQUIRED. (b)(c)

REFERENCE:

- (a) FOR FURTHER DETAILS, SEE SG014.
- (b) SEE RULE 16.
- (c) SEE RULE 15.
- d) SEE RULE 2.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES NEW PROJECT TYPES

SG012.3

SCOPE: THIS STANDARD IS INTENDED TO PROVIDE GUIDANCE TO DEVELOPERS, ARCHITECTS, ENGINEERS, ELECTRICAL CONTRACTORS, AND CONSULTANTS WORKING WITH AN EXISTING CUSTOMER PLANNING FOR ADDITIONS TO THEIR ELECTRICAL SERVICE(S) OR REMOTE METER LOCATIONS.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. GENERAL SERVICE REQUIREMENT TO MULTIPLE MULTI-UNIT BUILDINGS ON A SINGLE PREMISES:

WHEN THERE IS MORE THAN ONE MULTI-UNIT BUILDING ON A SINGLE PREMISES, AN INDIVIDUAL SDG&E SERVICE IS GENERALLY REQUIRED TO EACH OF THE MULTI-UNIT BUILDINGS. BOTH RESIDENTIAL AND NON-RESIDENTIAL APPLICATIONS ARE SUBJECT TO THIS REQUIREMENT. (a)

II. MULTI-FAMILY RESIDENTIAL BUILDINGS – LESS THAN 3 STORIES HIGH:

- a. CUSTOMER REQUESTS FOR A SECOND SERVICE OF THE SAME CLASS WILL NOT BE GRANTED UNLESS THE SERVICE SIZE EXCEEDS 4,000A. WHEN THE SERVICE SIZE WILL EXCEED 4,000A, A SECOND SERVICE OF THE SAME CLASS MAY BE GROUPED AS CLOSE AS PRACTICAL TO THE EXISTING SERVICE OR A SECOND SERVICE A MINIMUM OF 300 FEET APART MAY BE GRANTED. RULE 16 WILL APPLY, AND RULE 15 ALLOWANCES MAY BE GRANTED FOR THE SECOND SERVICE REQUEST BASED ON THE TYPE OF LOAD ADDITIONS. FOR EXAMPLE, IF THE LOAD ADDITIONS ARE IN THE EXISTING DWELLING UNITS ONLY, NO ALLOWANCES WILL BE GIVEN. IF HOUSE LOADS ARE BEING ADDED THROUGH A NEW SERVICE AND METER, ALLOWANCES FOR THE INCREMENTAL LOAD INCREASE WILL BE GRANTED. $\begin{pmatrix} b \\ b \end{pmatrix}$ $\begin{pmatrix} c \\ c \end{pmatrix}$
- b. A SEPARATE SERVICE OF A DIFFERENT CLASS, NORMALLY 480Y/277V, MAY BE GRANTED FOR HOUSE LOADS AND MAY BE GROUPED WITH THE SERVICE(S) FOR THE MULTI-FAMILY DWELLING UNITS OR LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO THE PROJECT PLANNER BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY AND WITH APPROVAL FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ). THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 FOR SERVICE EXTENSIONS AND THE NON-RESIDENTIAL ALLOWANCES FOR THE INCREMENTAL LOAD INCREASE PER RULE 15 WILL APPLY TO THE SECOND SERVICE. (b) (c)

III. RESIDENTIAL OR MIXED USE BUILDINGS – 3 STORIES OR GREATER:

THE CUSTOMER MAY RECEIVE AS MANY 3-PHASE, 208Y/120V SERVICES AS REQUIRED, NORMALLY GROUPED AT ONE LOCATION, TO SERVE THE DWELLING UNITS THAT MUST BE INDIVIDUALLY METERED BY THE UTILITY. THE PROJECT PLANNER MAY APPROVE MORE THAN ONE SERVICE POINT AND METER LOCATION FOR SERVICES OF THE SAME CLASS IF THE DISTANCE BETWEEN THEM IS 300 FEET OR GREATER, OR WHEN IT IS IN THE BEST INTEREST OF THE UTILITY TO PROVIDE MULTIPLE SERVICE POINTS AND METER LOCATIONS. A SEPARATE SERVICE OF A DIFFERENT CLASS, NORMALLY 480Y/277V, MAY BE GRANTED FOR HOUSE LOADS AND MAY BE GROUPED WITH THE SERVICE(S) FOR THE MULTI-FAMILY DWELLING UNITS OR LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO THE PROJECT PLANNER BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY, AND WITH APPROVAL FROM THE AHJ. THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 WILL APPLY AND THE RULE 15 RESIDENTIAL AND NON-RESIDENTIAL ALLOWANCES WILL BE APPLIED TO THE COST OF ALL SERVICES MEETING THE CRITERIA ABOVE.

IV. RESIDENTIAL CONTIGUOUS DWELLINGS - TOWNHOUSES (ROW HOMES):

EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A PARCEL OF LAND BOUNDED BY LEGAL PROPERTY LINES MUST BE PROVIDED WITH AN INDIVIDUAL ELECTRIC SERVICE AND METER(S) LOCATED ON THE PROPERTY SERVED. EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A SINGLE PARCEL OF PROPERTY DIVIDED WITH "ASSUMED PROPERTY LINES" MAY BE:

 a. PROVIDED WITH AN INDIVIDUAL ELECTRIC SERVICE AND METER(S) LOCATED ON THE TOWNHOUSE BOUNDED BY ASSUMED PROPERTY LINES, OR

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CH	AN	GE	DR	BY	DSN	APV	DATE
С								F									
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е									
Α	EDITORIAL (CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X Indicates La	atest R	evisio	n	Con	npletely Revi	ised	N	New Page		Information Re	moved				
	SHEET	•		SDC	S&E E	LECTI	RIC SERVIC	E STA	NDAF	RDS & GUII	DE:	S					
	1 OF 3				EL		RIC SER								S	G01	3.1

NOTES (CONT'D):

IV. RESIDENTIAL CONTIGUOUS DWELLINGS - TOWNHOUSES (ROW HOMES) (CONT'D):

b. Served through a single service point, with meters grouped at one location in a common area remote from the buildings. Easements will be required to be established and recorded in the deed of every townhouse allowing for privately-owned electric lines to cross assumed property lines. The utility is not involved in the easement process, but it is important for developers to understand this requirement. Main electric service disconnects (maximum of six) may be grouped at one location to accommodate grouping of the electric service and of the electric service and metering equipment. If the number of service disconnects exceeds six, a main disconnect will be required ahead of all meters and their related meter service disconnect. The meter service disconnect must be located at or immediately adjacent to the meter. A 3/4-Inch or larger electrical conduit must be installed, per the requirements of the california electrical code and approved by the Ahj, between the grouped meter location and each individual townhouse. This conduit will provide access for future installation of alternative energy sources, such as photovoltaic systems.

V. SINGLE PREMISES-MULTIPLE NON-RESIDENTIAL ENTERPRISES (SUCH AS SHOPPING CENTERS & OFFICE BUILDINGS):

- a. CUSTOMER REQUESTS FOR A SECOND SERVICE OF THE SAME CLASS TO SERVE AN EXISTING BUILDING WILL NOT BE GRANTED UNLESS THE SERVICE SIZE EXCEEDS 4,000A. WHEN THE SERVICE SIZE WILL EXCEED 4,000A, A SECOND SERVICE OF THE SAME CLASS MAY BE GROUPED AS CLOSE AS PRACTICAL TO THE EXISTING SERVICE OR A SECOND SERVICE A MINIMUM OF 300 FEET APART MAY BE GRANTED. RULE 15 ALLOWANCES WILL BE GRANTED FOR THE SECOND SERVICE REQUEST BASED ON THE INCREMENTAL LOAD INCREASE. (C)
- b. REQUESTS FOR A SECOND CLASS OF SERVICE WILL BE GRANTED AND MAY BE GROUPED WITH THE EXISTING SERVICE(S) OR LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO THE PLANNER AND THE AHJ BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY. THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. THIS APPLIES TO AN EXISTING PRIMARY METERED CUSTOMER WHO IS ALLOWING A NEW SEPARATE ENTERPRISE TO OPERATE A BUSINESS ON THE SINGLE PREMISES. A SECONDARY VOLTAGE SERVICE WILL BE GRANTED AT A LOCATION APPROVED BY THE PROJECT PLANNER AND THE AHJ. RULE 16 FOR SERVICE EXTENSIONS AND THE NON-RESIDENTIAL ALLOWANCES PER RULE 15 WILL APPLY TO THE SECOND SERVICE.
- c. AREA SEPARATION WALLS CONSTRUCTED AS PART OF A TENANT IMPROVEMENT MAY RESULT IN THE CREATION OF A SEPARATE BUILDING CONTIGUOUS WITH THE EXISTING BUILDING. WHEN THE BUILDING OFFICIAL CONFIRMS IN WRITING A NEW SEPARATE BUILDING HAS BEEN CREATED, A NEW GAS AND/OR ELECTRIC SERVICE IS ALLOWED PROVIDED THERE IS SPACE ON THE BUILDING FOR THE SERVICE AND METERING EQUIPMENT. RULE 16 FOR SERVICE EXTENSIONS WILL APPLY AND THE NON-RESIDENTIAL ALLOWANCES PER RULE 15 MAY BE GRANTED FOR THE NEW SERVICE REQUEST IF THERE IS AN INCREMENTAL LOAD INCREASE. (b) (c)

VI. SINGLE PREMISES – SINGLE NON-RESIDENTIAL ENTERPRISE (CUSTOMER):

- a. THE CUSTOMER WILL NOT BE GRANTED BOTH A PRIMARY METERED SERVICE AND A SECONDARY VOLTAGE SERVICE, EVEN THOUGH THE SERVICES ARE TECHNICALLY A DIFFERENT CLASS. IF A CUSTOMER'S LOAD REQUIREMENTS EXCEED 3 AT 4,000A SECONDARY VOLTAGE SERVICE, THE CUSTOMER WILL BE REQUIRED TO TAKE SERVICE AT A PRIMARY VOLTAGE LEVEL AND INSTALL PRIMARY METERING MEDIUM VOLTAGE SWITCHGEAR.
- EXCEPTION: WHEN AN EXISTING PRIMARY METERED CUSTOMER REQUESTS A NEW SECONDARY VOLTAGE SERVICE WITH THE INTENT OF REMOVING THEIR EXISTING PRIMARY METERED SERVICE, WE WILL PROVIDE UP TO 3 SECONDARY VOLTAGE SERVICES, NOT EXCEEDING 3 AT 4,000A EACH. RULE 15, SECTION I, ITEM 1, FACILITY RELOCATION OR REARRANGEMENT, WILL APPLY. THE CUSTOMER IS RESPONSIBLE FOR THE TOTAL ESTIMATED INSTALLED COST OF THE NEW FACILITIES AND REMOVAL OF THE EXISTING PRIMARY METERED SERVICE, INCLUDING THE METERING. IF THE CUSTOMER IS ADDING LOAD AND THE EXISTING PRIMARY METERED SERVICE WAS ADEQUATE TO SERVE THE LOAD ADDITIONS, THE CUSTOMER WILL NOT BE GRANTED RULE 15 ALLOWANCES FOR THE INCREMENTAL LOAD INCREASE. THE CUSTOMER IS ALLOWED TO CONTINUE RECEIVING PRIMARY METERED SERVICE AND THE NEW SECONDARY VOLTAGE SERVICE FOR A MAXIMUM OF FIVE YEARS AND SHALL PROVIDE THE PLANNER WRITTEN CONFIRMATION OF THEIR ACCEPTANCE OF THE MAXIMUM TIMEFRAME FOR REMOVAL OF THE EXISTING PRIMARY METERED SERVICE. THIS WILL ALLOW THE CUSTOMER ADEQUATE TIME TO RE-FEED THEIR ELECTRICAL LOADS FROM THE NEW SECONDARY VOLTAGE SOURCE(S) AND FACILITATE A PHASED APPROACH WHEN MORE THAN ONE SECONDARY VOLTAGE SERVICE IS NEEDED. TYPICALLY, PLANNERS WILL RECEIVE THIS TYPE OF REQUEST FROM SCHOOL DISTRICTS OR CAMPUS TYPE FACILITIES. (C) (d)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. DR BY DSN APV **REV** DATE REV **CHANGE** DR BY DSN APV DATE **CHANGE** С F JTM В FORMATTING/EDITORIAL CHANGES EDM IWA KRG 02/26/2025 Ε **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 Α D Completely Revised New Page Information Removed **Indicates Latest Revision**

SHEET 2 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER

SG013.2

NOTES (CONT'D):

VI. SINGLE PREMISES – SINGLE NON-RESIDENTIAL ENTERPRISE (CUSTOMER) (CONT'D):

c. WHEN THE UTILITY DETERMINES IT IS IN THE CUSTOMER'S BEST INTEREST FOR THE UTILITY TO APPROVE A SECOND OR THIRD SECONDARY VOLTAGE SERVICE OF THE SAME CLASS NOT GROUPED WITH THE EXISTING SERVICE AT ONE LOCATION, THE CUSTOMER WILL PAY FOR ONLY THE ADDITIONAL FACILITIES REQUIRED PER THE PROVISIONS OF RULE 2, SECTION I, ITEM 1, SPECIAL FACILITIES AND MAINTENANCE, UNLESS THE MINIMUM DISTANCE BETWEEN THE EXISTING AND ALL PROPOSED NEW SERVICES ARE AS FOLLOWS: (e)

TABLE 1

REQUIRED MINIMUM S SERVICES OF TH	
SERVICE (V)	MINIMUM SEPARATION (FT)
120/240 208Y/120	500
480Y/277	1,000

- d. RULE 16 FOR SERVICE EXTENSIONS WILL APPLY WHEN THE ABOVE CRITERIA IS MET, AND THE NON-RESIDENTIAL ALLOWANCES PER RULE 15 MAY BE GRANTED FOR THE NEW SERVICE REQUEST IF THERE IS AN INCREMENTAL LOAD INCREASE. (b)(c)
- e. REQUESTS FOR A SECOND CLASS OF SECONDARY VOLTAGE SERVICE WILL BE GRANTED AND MAY BE GROUPED WITH THE EXISTING SERVICE(S) OR LOCATED AT A MORE CONVENIENT LOCATION ACCEPTABLE TO THE PROJECT PLANNER AND THE AHJ BASED ON THE DESIGN OF THE CUSTOMER'S ELECTRICAL SYSTEM AND THE UTILITY'S SERVICE DELIVERY POINT POLICY. THERE IS NO MINIMUM DISTANCE REQUIRED BETWEEN SERVICES OF A DIFFERENT CLASS. RULE 16 FOR SERVICE EXTENSIONS AND THE NON-RESIDENTIAL ALLOWANCES PER RULE 15 WILL APPLY TO THE SECOND SERVICE. (b) C

VII. SINGLE PREMISES - SINGLE RESIDENTIAL CUSTOMER WITH OTHER ELECTRIC USES:

ONE SERVICE PER PREMISES WILL BE GRANTED. A SECOND SERVICE MAY BE APPROVED FOR OTHER ELECTRIC USES SUCH AS $\frac{AN}{AN}$ ACCESSORY DWELLING UNIT (ADU), WELLS, BARNS, GARAGES, ETC., PROVIDED THE LOCATION IS MORE THAN 150 FEET FROM THE EXISTING SERVICE AND METER LOCATION AT THE RESIDENCE, AND THE AHJ APPROVES A SECOND SERVICE AND METER ON THE PROPERTY. WHEN BOTH OF THESE CONDITIONS ARE MET, RULE 16 WILL APPLY, AND THE RULE 15 NON-RESIDENTIAL ALLOWANCE WILL BE APPLIED TO THE COST OF THE SECOND SERVICE. $\frac{1}{D}$ $\frac{1}{C}$

VIII. SINGLE PREMISES – MULTIPLE RESIDENTIAL CUSTOMERS:

EACH SEPARATE STRUCTURE CONTAINING MORE THAN SIX LEGAL DWELLING UNITS, OR MORE THAN FIVE LEGAL DWELLING UNITS AND A HOUSE METER, MUST BE INDIVIDUALLY SERVED BY THE UTILITY. EACH DWELLING UNIT MUST BE INDIVIDUALLY METERED BY THE UTILITY. RULE 16 FOR SERVICE EXTENSIONS AND THE RESIDENTIAL ALLOWANCES PER RULE 15 FOR EACH DWELLING UNIT WILL APPLY TO EACH SERVICE. APPROVAL BY THE AHJ IS REQUIRED. $\begin{pmatrix} b \\ b \end{pmatrix}$ $\begin{pmatrix} c \\ c \end{pmatrix}$

REFERENCE:

- (a) SEE SG014: ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS.
- (b) SEE RULE 16.
- (c) SEE RULE 15.
- (d) SEE RULE 15, SECTION 1, ITEM 1: FACILITY RELOCATION OR REARRANGEMENT.
- (e) SEE RULE 2, SECTION 1, ITEM 1: SPECIAL FACILITIES AND MAINTENANCE.


© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV DSN APV **CHANGE** DR DATE REV **CHANGE** DR BY DATE C F В FORMATTING/EDITORIAL CHANGES **EDM IWA** JTM KRG 02/26/2025 Ε **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 Α **Indicates Latest Revision** Completely Revised New Page Information Removed

SHEET 3 OF 3

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG013.3






FIGURE 2

SERVICE AND METERING REQUIREMENT
SINGLE PREMISES WITH MULTIPLE BUILDINGS (Ib) (III) VII
POSSIBLE EXCEPTION SCENARIO
SEE TABLE 1

© 1998 – 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS




FIGURE 3

SERVICE AND METERING REQUIREMENT
SINGLE PREMISES WITH MULTIPLE BUILDINGS (Ib) (IV) (VII)
POSSIBLE EXCEPTION SCENARIO
SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS




FIGURE 4 SERVICE AND METERING REQUIREMENT SINGLE PREMISES WITH MULTIPLE BUILDINGS SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS

TABLE 1

	FI	GURE ITEMS
ITEM	DESCRIPTION	DETAILS
<u>(1)</u>	METER, NEW	FOR REAR BUILDING
(2)	METER, ONE	
(3)	METERS, GROUP	FOR FRONT BUILDING
<u>4</u>	METERS, GROUP	2 NEW
(5)	METERS, GROUP	2 OR MORE
6	METERS, GROUP	4 NEW
(7)	METERS, GROUP, NEW	FOR 2 UNITS AND 1 UNIT IN ADJACENT BUILDING (SOUTH)
8	METERS, GROUP, NEW	FOR 2 UNITS
9	METER LOCATION, GROUPED, EXISTING	FOR ALL UNITS ON PARCEL
(10)	CONDUCTORS, FEEDER, NEW METERED CUSTOMER	
(11)	CONDUCTORS, SERVICE ENTRANCE	UNDERGROUND OR OVERHEAD, WITH AHJ APPROVAL
(12)	CONDUCTORS, SERVICE ENTRANCE, NEW	BY CUSTOMER EITHER UNDERGROUND OR OVERHEAD WITH AHJ APPROVAL
(13)	CONDUCTORS, SERVICE ENTRANCE, NEW	BY CUSTOMER - SEALABLE JUNCTION/TAP ENCLOSURE
(14)	CONDUCTORS, SERVICE ENTRANCE, NEW CUSTOMER	
(15)	POINT OF ATTACHMENT (POA), EXISTING	
(16)	POINT OF ATTACHMENT (POA), NEW	
(17)	SERVICE, UNDERGROUND OR OVERHEAD, NEW	DIRECT FROM SDG&E SOURCE
(18)	SPACE	ADEQUATE TO RUN SERVICE BETWEEN PROPERTY LINE AND EXISTING BUILDING

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. SINGLE PREMISES WITH MULTIPLE BUILDINGS - SERVICE & METERING REQUIREMENTS:

- a. FOR COMPLIANCE WITH THE CALIFORNIA ELECTRICAL CODE, ARTICLE 225.30, AN INDIVIDUAL SDG&E (UTILITY) SERVICE DROP OR SERVICE LATERAL WILL BE PROVIDED TO EACH BUILDING CONTAINING 2 OR MORE RESIDENTIAL OR NON-RESIDENTIAL UNITS LOCATED ON A SINGLE PARCEL OF LAND. EACH BUILDING WILL HAVE THE METERS FOR THE UNITS WITHIN THAT BUILDING GROUPED AT ONE CENTRAL LOCATION. THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) SHALL APPROVE AND INSPECT THE CUSTOMER'S PREMISES WIRING SYSTEM.
- (b) EXCEPTION: FOR REWIRES OR CONVERSION OF SERVICE FROM OVERHEAD TO UNDERGROUND ON EXISTING PARCELS WITH 2 OR MORE MULTI-UNIT BUILDINGS, IT IS SOMETIMES IMPRACTICABLE TO ESTABLISH A DIRECT SERVICE FROM THE UTILITY SOURCE TO REAR OR REMOTELY LOCATED BUILDINGS ON THE PARCEL. FOR EXAMPLE, IF THERE IS A STRUCTURE BUILT LOT LINE TO LOT LINE BETWEEN THE UTILITY SOURCE AND ANOTHER MULTI-UNIT BUILDING ON THE SAME PARCEL, AN INDIVIDUAL UTILITY SERVICE TO THE OTHER MULTI-UNIT BUILDING WOULD BE CONSIDERED IMPRACTICABLE. CUSTOMER-OWNED AND -INSTALLED SERVICE ENTRANCE CONDUCTORS OR UNMETERED FEEDER WILL BE ALLOWED BETWEEN BUILDINGS IN THESE SITUATIONS BY DEVIATION ONLY. THIS IS BY EXCEPTION AND APPLIES ONLY WHEN APPROVED IN ADVANCE BY SDG&E SERVICE STANDARDS.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																		
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	HAI	NGE		DR	BY	DSN	APV	DATE
С									F										
В	FORMATTING/EDIT	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/26/2025	Е										
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D										
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Iı	nformation Rer	noved				
Ì	CHEET				SDG	&E E	LECTF	RIC SERVIC	E STA	NE	DARDS & GL	JIDI	ES						

SHEET 5 OF 6

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS

NOTES (CONT'D):

- (II) THIS STANDARD APPLIES ONLY WHEN STANDARD OH OR UG SERVICE CANNOT BE ESTABLISHED TO BOTH BUILDINGS DUE TO PHYSICAL CONSTRUCTION LIMITATIONS. A DEVIATION IS REQUIRED FROM SERVICE STANDARDS BEFORE NEGOTIATING THIS METHOD OF SERVICE WITH THE CUSTOMER OR THEIR CONTRACTOR, OR ON A CONVERSION PROJECT.
- THIS STANDARD APPLIES ONLY WHEN STANDARD OH OR UG SERVICE CANNOT BE ESTABLISHED TO ALL BUILDINGS DUE TO PHYSICAL CONSTRUCTION LIMITATIONS. A DEVIATION IS REQUIRED FROM SERVICE STANDARDS BEFORE NEGOTIATING THIS METHOD OF SERVICE WITH THE CUSTOMER OR THEIR CONTRACTOR, OR ON A CONVERSION PROJECT.
- (IV) THIS STANDARD APPLIES ONLY WHEN STANDARD OH OR UG SERVICE CANNOT BE ESTABLISHED TO ALL BUILDINGS WITH MULTIPLE TENANTS DUE TO PHYSICAL CONSTRUCTION LIMITATIONS. A DEVIATION IS REQUIRED FROM SERVICE STANDARDS BEFORE NEGOTIATING THIS METHOD OF SERVICE WITH THE CUSTOMER OR THEIR CONTRACTOR, OR ON A CONVERSION PROJECT.
- V. SDG&E SOURCE IN ALLEY AND NO SDG&E SOURCE ON STREET SIDE OF PARCEL.
- VI. A PLAQUE IS REQUIRED AT EACH METER LOCATION CONNECTED TO THE SERVICE IDENTIFYING THE LOCATION OF ALL METER LOCATIONS SERVED. (b)
- SERVICE ENTRANCE CONDUITS INSTALLED UNDERGROUND BETWEEN BUILDINGS SHALL BE CONCRETE-ENCASED (ONE SACK SLURRY).
- (VIII) EXCEPTION NOT GRANTED IN THIS SCENARIO

REFERENCE:

- (a) SEE CALIFORNIA ELECTRIC CODE, ARTICLE 225.30.
- (b) FOR PLAQUE SPECIFICATIONS AND EXAMPLES, SEE SG017.

	© 1998 - 2025 San Diego Gas & Ele	ectric C	Compa	ny. All	rights r	reserved. Rei	moval	of this copyright notice without permission	is not	permit	ted und	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	D

 REV
 CHANGE
 DR
 BY
 DSN
 APV
 DATE
 REV
 CHANGE
 DR
 BY
 DSN
 APV
 DATE

 C
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S
 S<

SHEET 6 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE POLICIES EXISTING CUSTOMER FEEDER EXCEPTIONS

SCOPE: THIS STANDARD PROVIDES SDG&E (UTILITY) LINE TRUCK ACCESS REQUIREMENTS TO TERMINATING ENCLOSURES.

DEFINITIONS:

- LINE TRUCK ACCESS: A MINIMUM 16-FOOT WIDE "ALL WEATHER" DRIVEN WAY OF SUFFICIENT STRENGTH TO SUPPORT A TRUCK WEIGHT CLASS H20 (20 TONS), WITH A CLEAR HEIGHT OF 13'-6" AND A 40-FOOT MINIMUM TURNING RADIUS MEASURED FROM INSIDE CURB.
- PICK-UP TRUCK ACCESS: A MINIMUM 8-FOOT HEIGHT CLEARANCE, 14-FOOT MINIMUM TURNING RADIUS MEASURED FROM INSIDE CURB, AND 14-FOOT WIDE ALL WEATHER DRIVEN WAY OF SUFFICIENT STRENGTH TO SUPPORT A MINIMUM TRUCK WEIGHT OF 4,000 POUNDS.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE MAXIMUM DISTANCE FROM LINE TRUCK ACCESS TO AN ELECTRIC METER ROOM DOOR APPLIES WHEN THE TERMINATING ENCLOSURE IS LOCATED IN THE ELECTRIC METER ROOM DIRECTLY IN FRONT OF THE ACCESS DOOR, OR WHEN THE TERMINATING ENCLOSURE IS LOCATED ON AN EXTERIOR BUILDING WALL. THE MAXIMUM DISTANCE IS DEPENDENT UPON THE SIZE OF THE ELECTRIC SERVICE. LARGER SERVICES REQUIRE LARGER DIAMETER AND GREATER NUMBER OF CONDUITS TO SERVE THE CUSTOMER'S ULTIMATE ELECTRICAL NEEDS.
 - a. IF THE TERMINATING ENCLOSURE IS WITHIN A METER ROOM AND LOCATED OTHER THAN DIRECTLY IN FRONT OF THE ACCESS. DOOR, PULLING EYE HOOKS AND COIL INSERTS MAY BE REQUIRED TO RIG CABLE PULLING OPERATIONS. CONSULT WITH THE UTILITY'S PROJECT PLANNER IF THIS IS PROPOSED. (a)
- II. THE MAXIMUM SIZE CONDUCTOR THE UTILITY INSTALLS IS 1,000 KCMIL ALUMINUM CONDUCTORS IN A 5-INCH CONDUIT. THE MAXIMUM DISTANCES SHOWN IN TABLE 1 HAVE BEEN ESTABLISHED TO HELP ENSURE A SAFE INSTALLATION AND TO SHORTEN RESTORATION TIME SHOULD A CABLE FAILURE OCCUR DURING THE LIFE OF THE SERVICE.
- III. ALL ELECTRIC METER ROOMS <u>WITHOUT THE TERMINATING ENCLOSURE LOCATED INSIDE THE ELECTRIC METER ROOM</u> SHALL BE A MAXIMUM OF 100 FEET FROM PICK-UP TRUCK ACCESS.
- IV. IT IS THE CUSTOMER'S RESPONSIBILITY TO PROVIDE AND MAINTAIN THE REQUIRED TRUCK ACCESS FOR THE LIFE OF THE ELECTRICAL SYSTEM.

TABLE 1

MAXIMUM DISTANCE FROM LINE ELECTRIC METER ROOM DOOI ENCLOSURE LOCATED ON EXT	R OR TERMINATING
SIZE OF ELECTRIC CONDUIT ENTERING TERMINATING ENCLOSURE (IN)	MAXIMUM DISTANCE (FT)
LESS THAN 4	30
4	20
5	10

REFERENCE:

a) SEE SG016.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1

Completely Revised New Page Information Removed Indicates Latest Revision SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

LINE TRUCK ACCESS REQUIREMENTS

SG015.1


SCOPE: THIS STANDARD PROVIDES AN ALTERNATIVE TO LINE TRUCK ACCESS TO THE EXTERIOR OF AN ELECTRIC METER ROOM DOOR FOR INSTALLATION AND REMOVAL OF SERVICE LATERAL CONDUCTORS IN THE UNDERGROUND TERMINATING ENCLOSURE (UGPS) LOCATED IN A PARKING STRUCTURE.

ATTENTION:

* THIS STANDARD MAY BE USED WHEN ALL OF THE REQUIREMENTS CAN BE MET.

DEFINITIONS:

• TRUCK ACCESS (FOR THIS STANDARD): A MINIMUM 8-FOOT HEIGHT CLEARANCE AND 14-FOOT MINIMUM TURNING RADIUS MEASURED FROM INSIDE CURB



NOT DRAWN TO SCALE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C FORMATTING EDM JIK JTM KRG 02/26/2025 F	REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
	С	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	F						
B EDITORIAL CHANGES ARC IPJ IPJ KRG 12/06/2022 E	В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е						
A EDITORIAL CHANGES - LSM LSM TPM 11/01/2017 D	Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES

SG016.1




FIGURE 2

INSTALLATION:

- A CUSTOMER TO PROVIDE PULLING EYE HOOK STRUCTURALLY IN THE CEILING WITH A LOAD CAPACITY OF 8,000 POUNDS. LOCATE EYE HOOK IN FRONT OF, AND CENTERED TO, THE UGPS. CUSTOMER TO SUBMIT THE STRUCTURAL ENGINEER'S APPROVED DRAWING(S) TO SDG&E'S (UTILITY) PROJECT PLANNER PRIOR TO INSTALLATION OF THE EYE HOOK AND COIL INSERT. COORDINATE THE INSTALLATION WITH THE UTILITY'S INSPECTOR. (B)
- B CUSTOMER TO PROVIDE A 1" X 4 1/2" DAYTON/RICHMOND FLARED THIN SLAB COIL INSERT (F-63), OR EQUIVALENT, WITH A SAFE WORKING LOAD TENSION OF 4,750 POUNDS. AND A LOAD OF 8,000 POUNDS. WHEN USED IN COMBINATION WITH THE COIL INSERT SPECIFIED ABOVE. INSTALL THE COIL INSERT AND SWIVEL LIFTING PLATE DIRECTLY BELOW THE PULLING EYE HOOK. COORDINATE THE INSTALLATION WITH THE UTILITY'S INSPECTOR. TO ENSURE SAFETY, INSTALLATION OF THE COIL INSERT AND SWIVEL LIFTING PLATE SHALL BE IN COMPLIANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. (A)
- C THE RIGGING PATH THROUGH THE METER ROOM DOOR IS TO BE DIRECTLY IN LINE FROM TRUCK ACCESS TO THE FLOOR-MOUNTED COIL INSERT AND SWIVEL LIFTING PLATE THROUGH THE METER ROOM DOOR.
- THE PULLING EYE HOOK, THE FLOOR-MOUNTED COIL INSERT AND SWIVEL LIFTING PLATE ARE TO BE POSITIONED AT A DISTANCE OUT FROM THE UGPS SUCH THAT ANGLE Z IS NOT GREATER THAN 15 DEGREES. THE RIGGING PATH THROUGH THE FRONT OF THE UGPS IS TO BE UNOBSTRUCTED, AND THE RIGGING IS TO HAVE NO CONTACT WITH THE TOP, BOTTOM, OR SIDES OF THE PULL SECTION OPENING. MAXIMUM ALLOWABLE HEIGHT OF TOP PULLING EYE IS 14 FEET. $(A \setminus B)$
- (E) customer to provide the utility 24-hour direct access to within 5 feet of the meter room door(s).
- (F) RIG THROUGH METER ROOM DOOR.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	F						
В	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	12/06/2022	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 2 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E ELECTRIC SERVICE STANDARDS & GUIDE

SG016.2

PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES


BILL OF MATERIALS: NONE **NOTES:** I. PRECAST CONCRETE COMPANIES STOCK THE PULLING DEVICES SPECIFIED ABOVE. II. UPON COMPLETION OF INSTALLATION OF PULLING DEVICES, CERTIFICATION OF COMPLIANCE WITH THIS STANDARD IS REQUIRED UNDER STRUCTURAL/MECHANICAL ENGINEER'S SEAL. (III) TRUCK ACCESS REQUIRED. UTILITY MUST BE ABLE TO POSITION PICKUP TRUCK PERPENDICULAR TO ACCESS DOOR. **REFERENCE: NONE** © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV DSN APV **DATE CHANGE** DR DATE REV **CHANGE** DR BY С **FORMATTING EDM** JIK JTM KRG 02/26/2025 F В **EDITORIAL CHANGES** ARC IPJ IPJ KRG 12/06/2022 Ε **EDITORIAL CHANGES** LSM LSM TPM 11/01/2017 Α

SHEET 3 OF 3 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES

SG016.3



© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PLAQUE SPECIFICATIONS AND EXAMPLES




FIGURE 2 TYPICAL PLAQUE FOR NEW BUILDINGS OR EXISTING BUILDINGS (V) WITH SEPARATE SERVICE AREAS

	© 1998 - 2025 San Diego Gas & El	ectric C	Compa	ny. All	rights ı	reserved. Rer	moval o	of th	nis copyright notic	e wit	hout permission	is not	permit	ted und	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		СНА	NGE		DR	BY	DSN	APV	DATE
С							F									
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е									
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
	X Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Rer	noved				

SHEET 2 OF 4

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PLAQUE SPECIFICATIONS AND EXAMPLES




FIGURE 3 TYPICAL PLAQUE FOR EXISTING BUILDINGS WITH (II) INTERMIXED SERVICES

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CHAI	NGE	DR	BY	DSN	APV	DATE
С							F								
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
X Indicates L			evisio	n	Con	npletely Revi	ised		New Page	Information Re	moved	1			

SHEET 3 OF 4 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PLAQUE SPECIFICATIONS AND EXAMPLES

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE PLAQUE OR DIRECTORY REQUIRED BY SECTION 230.2 OF THE NATIONAL ELECTRICAL CODE SHALL BE MANUFACTURED IN METAL OR PLASTIC WITH ENGRAVED OR MACHINE-PRINTED LETTERING, OR ELECTRO-PHOTO-PLATING, IN A CONTRASTING COLOR. (a)
- (II) THE PLAQUE SHALL INCLUDE A FOOTPRINT OF THE ENTIRE BUILDING.
- III. THE PLAQUE SHALL BE ATTACHED TO THE SERVICE DISCONNECTING MEANS SECURELY BY A MEANS ACCEPTABLE TO THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).
- IV. EPOXY IS NO LONGER AN ACCEPTABLE METHOD OF SECURING.
- (\mathtt{v}) the plaque shall include a footprint of the entire building with the area served by each service clearly DELINEATED.

REFERENCE:

(a) SEE NEC, SECTION 230.2.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	02/26/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 4 Indicates Latest Revision Completely Revised New Page X Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PLAQUE SPECIFICATIONS AND EXAMPLES

SCOPE: THESE CLEARANCES APPLY TO ALL UNQUALIFIED PERSONS WHO ARE WORKING IN PROXIMITY TO VOLTAGES UP TO 50KV.






FIGURE 1
10'-0" MINIMUM RADIAL CLEARANCE (I)(II)

FIGURE 2
10'-0" MINIMUM RADIAL CLEARANCE (I)(II)




FIGURE 3
20'-0" MINIMUM RADIAL CLEARANCE

REV	CHANGE	DRWN	ВҮ	CHKD	APVD	DATE				
Е	EDITORIAL CHANGES	EDM	JAC	MRF	KRG	10/22/2024	CDCE			
D	REVISED TO 3D FORMAT	NV5	JIK	-	-	04/15/2024	SDGE			
С	DRAWING UPDATE	EDM	JAC	MRF	KRG	11/28/2023				
©	© 1998 - 2024 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.									



INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) WORKERS OR OBJECTS NOT SUPPORTED BY BOOM TYPE EQUIPMENT MUST MAINTAIN A 10-FOOT RADIAL CLEARANCE FROM LINE **VOLTAGES UP TO 50KV CONDUCTORS.**
- SCAFFOLDS AND ANY CONDUCTIVE MATERIAL HANDLED ON THEM MUST HAVE A MINIMUM RADIAL CLEARANCE OF 10 FEET FROM UNINSULATED VOLTAGES UP TO 50KV AND A MINIMUM OF 3 FEET FROM INSULATED LINE VOLTAGES LESS THAN 300 VOLTS.
- BOOM TYPE LIFTING OR HOSTING EQUIPMENT, INCLUDING LOAD, MUST MAINTAIN A 20-FOOT MINIMUM WORKING RADIUS DISTANCE FROM LINE VOLTAGES UP TO 50KV CONDUCTORS.
- TO REDUCE MINIMUM DISTANCE TO 10-FOOT, ALL CAL/FED OSHA APPLICABLE RULES APPLY.
- V. CAL/OSHA ELECTRICAL SAFETY ORDER 2948 MAKES THE CUSTOMER RESPONSIBLE FOR NOTIFYING SDG&E IF ADJUSTMENTS NEED TO BE MADE IN THE ELECTRICAL SYSTEM TO COMPLY WITH TITLE 8. CUSTOMER SHOULD CONTACT APPROPRIATE SDG&E CUSTOMER PROJECT PLANNER FOR AVAILABLE OPTIONS.

REFERENCE:

- a. SEE CALIFORNIA ADMINISTRATIVE CODE TITLE 8 INDUSTRIAL RELATIONS ELECTRICAL SAFETY ORDER 2946.
- SEE FED/OSHA 1926.1408.
- SEE CALIFORNIA ADMINISTRATIVE CODE TITLE 8 INDUSTRIAL RELATIONS ELECTRICAL SAFETY ORDER 2948.
- SEE FED/OSHA 1926.451

SDG&E ELECTRIC OVER	SCA	SCALE: NOT TO SCALE												
MEDIUM VOLT	MEDIUM VOLTAGE CONDUCTOR CLEARANCES FOR									DRAWING NO				SHEET:
NON-UTL	NON-UTILITY WORKERS AND EQUIPMENT													
Indicates Latest Revision	atest Revision Completely Revised New Page Information Removed													

SCOPE: THIS STANDARD DESCRIBES HORIZONTAL AND VERTICAL CLEARANCES OF SUPPLY CONDUCTORS FROM BUILDINGS, BRIDGES AND OTHER STRUCTURES.




FIGURE 1 NEAR BUILDINGS, BRIDGES, AND OTHER STRUCTURES




FIGURE 2 UNDER OR THRU BRIDGES, VIADUCTS OR SIMILAR STRUCTURES

INSTALLATION: NONE BILL OF MATERIALS: NONE

NOTES:

- (I) HORIZONTAL CLEARANCE OF 750V-7.5KV CONDUCTORS FROM BUILDING WALLS MAY BE REDUCED TO FOUR FEET WHERE CONDUCTORS ARE IN EXCESS OF THIRTY FIVE FEET ABOVE GROUND. REDUCED CLEARANCE DOES NOT APPLY TO BRIDGES, FIRE ESCAPES, WINDOWS, BALCONIES OR STRUCTURES WHERE HUMAN CONTACT MAY BE EXPECTED
- (II) NO LIMIT REQUIRED BUT THE GREATEST PRACTICABLE CLEARANCE SHOULD BE MAINTAINED. PROVIDE MECHANICAL (PHYSICAL) CLEARANCE FOR CABLE PROTECTION.

REFERENCE:

- FOR 0-300V SERVICE DROP CLEARANCES, SEE UG262.3-4.
- SEE G.O. 95 RULE 54.4I FOR SIGN REQUIREMENTS ON BRIDGES, VIADUCTS ETC., WHEN ATTACHING CONDUCTORS 750V-22.5KV BENEATH OR THRU SAME.
- DATA TAKEN FROM G.O. 95 TABLE I, CASE 6 AND 7 AND RULE 54.4H AND I.

CHANGE **CHKD APVD** DATE BY **EDITORIAL CHANGES** KRG MRF KRG 11/03/2023 07/20/2023 G REVISED TO 3D FORMAT/DRAWING UPDATE KRG EDM JAC MRF 12/12/2021 **EDITORIAL CHANGES GLW** JES

© 1998 - 2023 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.



SCOPE: THIS STANDARD DESCRIBES MINIMUM CLEARANCES OF WIRES FROM ILLUMINATED AND NON-ILLUMINATED SIGNS.





FIGURE 1 CLEARANCES FROM WALKABLE ILLUMINATED SIGNS



CLEARANCES FROM NON-WALKABLE ILLUMINATED SIGNS

	SDG&E ELECTRIC OVER	SCALE: NOT TO SCALE			
	HORIZONTAL AND VER	TICAL CLEARANCES OF	SUPPLY CONDUCTOR	DRAWING NO:	SHEET:
	FROM BUILDINGS, I	OH229.1	1 OF 4		
	ILLUMINATED A	AND NON-ILLUMINATED	SIGNS	SG019.1	1 05 4
X	Indicates Latest Revision	Completely Revised	Information Removed		




FIGURE 3
CLEARANCES FROM WALKABLE NON-ILLUMINATED SIGNS




FIGURE 4
CLEARANCES FROM NON-WALKABLE NON-ILLUMINATED SIGNS

REV	CHANGE	DRWN	BY	СНКД	APVD	DATE					
Ξ	EDITORIAL CHANGES	EDM	KRG	MRF	KRG	11/03/2023	CDCE				
G	REVISED TO 3D FORMAT/DRAWING UPDATE	EDM	JAC	MRF	KRG	07/20/2023	SDGE				
F	EDITORIAL CHANGES	EDM	GLW	JES	CZH	12/12/2021					
©	© 1998 - 2023 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.										

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) THESE CLEARANCES DO NOT APPLY TO SERVICE DROPS ATTACHED TO AND SERVING THESE SIGNS.
- (II) MAY BE REDUCED TO SIX INCHES MINIMUM IF ILLUMINATED SIGN IS GROUNDED.
- (III) CLEARANCES SPECIFIED MAY VARY NO MORE THAN 10% DUE TO TEMPERATURE OR WIND LOADING.
- WHEN CONDUCTORS OF MORE THAN 750V ARE AT A LEVEL OF EIGHT FEET OR MORE BELOW THE LEVEL OF THE LOWEST PORTION OF THE SIGN BUT NOT VERTICALLY UNDER THE SIGN, NO HORIZONTAL CLEARANCE IS REQUIRED BETWEEN THE VERTICAL PLANES THROUGH THE CONDUCTOR NEAREST THE SIGN AND THE VERTICAL PROJECTION OF THE EXTREMITIES OF THE SIGN. (a)

REFERENCE:

- a) SEE G.O. 95, RULE 39.
- b. DATA TAKEN FROM G.O. 95 TABLE 2-A.
- (c) SEE G.O. 95 RULES 57.4-A2 & 57.8.

SDG&E ELECTRIC OVE	SCALE: NOT TO SCALE				
LIODIZONITAL AND VE	DTTCAL CLEADANCES OF	CURRLY CONDUCTOR	DRAWING NO:	SHEET:	
HORIZONTAL AND VE	OH229.2	2.05.4			
FROM ILLUMINAT	TED AND NON-ILLUMINA	IED SIGNS	SG019.2	2 OF 4	
Y Indicates Latest Revision	Completely Revised	New Page	Information R	emoved	

SCOPE: THIS STANDARD DESCRIBES MINIMUM HORIZONTAL AND VERTICAL CLEARANCES WHERE LINE STRUCTURES ARE SET IN PROXIMITY TO RAILROAD TRACKS.





FIGURE 1 (I)



INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) IF VERTICAL CLEARANCE OF 22'-6" IS NOT ENCROACHED IN FROM NEAREST PART OF STRUCTURE TO CENTERLINE OF TRACK, THEN MINIMUM HORIZONTAL CLEARANCE IS ALLOWED TO BE MEASURED FROM FACE OF POLE.
- (II) IF VERTICAL CLEARANCE OF 22'-6" IS ENCROACHED IN BY ANY PORTION OF STRUCTURE, THEN MINIMUM HORIZONTAL CLEARANCE MUST BE MEASURED FROM THE NEAREST PART OF STRUCTURE TO CENTERLINE OF TRACK.
- (III) NO PART OF STRUCTURE ALLOWED IN THIS AREA.

REFERENCE:

a. FOR VERTICAL CLEARANCES, SEE OH220.

RE	CHANGE	DRWN	BY	CHKD	APVD	DATE	
Н	EDITORIAL CHANGES	EDM	KRG	MRF	KRG	11/03/2023	CDCE
G	REVISED TO 3D FORMAT/DRAWING UPDATE	EDM	JAC	MRF	KRG	07/20/2023	JOUR
F	EDITORIAL CHANGES	EDM	GLW	JES	CZH	12/12/2021	

RE	V CHANGE	DRWN	BY	CHKD	APVD	DATE		SDG&E ELECTRIC OVER	SCALE: NOT TO	SCALE			
-	EDITORIAL CHANGES	EDM	KRG	MRF	KRG	11/03/2023	CDCE	HODIZONTAL AND VED	DRAWING NO:	SHEET:			
(REVISED TO 3D FORMAT/DRAWING UPDATE	EDM	JAC	MRF	KRG	07/20/2023	SDGE		HORIZONTAL AND VERTICAL CLEARANCES OF SUPPLY CONDUCTOR FROM RAILROAD TRACKS				
F	EDITORIAL CHANGES	EDM	GLW	JES	CZH	12/12/2021		FR	SG019.3	3 OF 4			
	© 1998 - 2023 San Diego Gas and Electric Company. All rights rese	f this copyri	ght notice v	without peri	mission is no	ot permitted under law.	Indicates Latest Revision	Completely Revised	New Page	Information R	emoved		

SCOPE: THIS STANDARD DESCRIBES MINIMUM CLEARANCE AND SEPARATION REQUIREMENTS OF ENERGIZED OVERHEAD CONDUCTORS FROM CONTAINERS OF FLAMMABLE OR EXPLOSIVE MIXTURES.




FIGURE 1 PLAN VIEW




FIGURE 1 ELEVATION

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. ALL ENERGIZED OVERHEAD FACILITIES OVER 600V SHALL HAVE A MINIMUM CLEARANCE OF 6 FEET MEASURED HORIZONTALLY AND A RECOMMENDED RADIUS OF 25 FEET FROM ANY EXPOSED TANK, VENT OR FILL TUBE CONTAINING FLAMMABLE OR EXPLOSIVE
- II. THIS STANDARD DOES NOT APPLY TO FACILITIES INSTALLED PRIOR TO NOVEMBER 15, 1983. (a)
- (III) 10 FEET RECOMMENDED

REFERENCE:

a. SEE NFPA 58-6.5.3.13, 2020 EDITION.

REV	CHANGE	DRWN	BY	CHKD	APVD	DATE							
Η	EDITORIAL CHANGES	EDM	KRG	MRF	KRG	11/03/2023	CDCE	ı					
G	REVISED TO 3D FORMAT/DRAWING UPDATE	EDM	JAC	MRF	KRG	07/20/2023	JOUGE	•					
F	EDITORIAL CHANGES	EDM	GLW	JES	CZH	12/12/2021							
©	© 1998 - 2023 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.												



	SDG&E ELECTRIC OVER	SCALE: NOT TO SCALE						
	LIODIZONTAL AND VED	FICAL CLEADANCES OF	_	UDDLY CONDUCTOR		DRAWING NO:		SHEET:
	HORIZONTAL AND VER		OH229.4					
	FROM TANKS CONTAIN	PLOSIVE MIXTURE		SG019.4	4 OF 4			
<	Indicates Latest Revision	Completely Revised		New Page		Informatio	n Re	moved

SCOPE: THIS STANDARD LISTS VARIOUS PRODUCT DISTRIBUTORS UTILIZED BY SDG&E.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. CONDUIT PULLING TAPE, CONCRETE PRODUCTS, AND WOOD POLES PURCHASED FOR USE ON SDG&E'S DISTRIBUTION SYSTEM AND CUSTOMER-OWNED METER POLES MUST MEET THE AMERICAN SOCIETY FOR TESTING & MATERIALS (ASTM) INTERNATIONAL STANDARDS. TABLE 1 IS A CURRENT LISTING OF SUPPLIERS THAT CARRY PRODUCTS APPROVED BY SDG&E. PRIOR TO PURCHASE, IT IS ADVISED THAT YOU VERIFY WITH THE SUPPLIER THAT THE PRODUCTS YOU ARE PROCURING MEET ASTM INTERNATIONAL STANDARDS.

TABLE 1

	SDG&E SUPPLIER LIST												
SUPPLIER	PHONE NUMBER	CONDUIT (II)	CONCRETE PRODUCTS	POLES	PULLING TAPE								
Brooks Products – Ontario	909-947-7470		Х										
California Electric Supply													
Chula Vista	619-427-2370	Χ											
El Cajon	619-579-0711												
Consolidated Electric Distributors													
Carlsbad	760-438-9691												
Escondido	760-747-2900												
Ramona	760-788-6112	X											
San Clemente	949-492-5161	^											
San Diego	858-268-1020												
Santee	619-562-3004												
Temecula	951-296-9555												
Crescent Electric Supply Company	855-999-2372	X	Х	Х	X								
CSC (Communications Supply Corporation/WESCO Distribution)	858-279-0233	Х											
Grand Electric Supply – Vista	760-727-0400	Х											
Graybar Electric Company													
San Diego	858-547-6550	Χ											
San Marcos	760-591-4788												
Jensen Precast – Fontana	909-350-4111		Х										
Oldcastle Precast													
Escondido	760-737-8590		Χ										
Fontana	800-626-3860												
One Source Distributors													
El Centro	760-352-1015												
Garden Grove	714-685-5340												
Oceanside	760-966-4500				X								
San Diego – Miramar	858-452-9001												
San Diego – Kearny Mesa	858-565-8866												
Pine Tree Lumber – Escondido	760-745-0411			X									
ProGlass, Inc. – Gig Harbor (WA)	253-884-4008		X										
Rexel													
El Cajon	619-442-9255												
Escondido	760-747-2211	X											
San Diego	858-636-4400												

(II) CONDUIT MUST BE GRAY

REFERENCE:

a. SEE AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) INTERNATIONAL STANDARDS.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV REV** DR BY DSN APV DR BY DSN APV DATE CHANGE DATE **CHANGE** С F В **FORMATTING EDM** JIK JTM KRG 02/26/2025 Ε **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 Α

SHEET 1 OF 1 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG020.1

PRODUCT DISTRIBUTORS

SCOPE: THIS SERVICE GUIDE EXPLAINS HOW TO OBTAIN A SERVICE AND METER LOCATION FOR NEW ELECTRIC SERVICES, SERVICE RELOCATIONS, AND SERVICE UPGRADES.

TABLE 1:

SERVICE ORDER TEAMS FOR RESIDENTIAL CUSTOMERS UP TO 400 AMPS AND NON-RESIDENTIAL CUSTOMERS UP TO 200 AMPS												
BEACH CITIES	METRO	NORTH COAST										
4848 SANTE FE ST	701A 33RD ST	4940 CARLSBAD BLVD										
SAN DIEGO, CA 92109	SAN DIEGO, CA 92102	CARLSBAD, CA 92008										
(858) 581-7544	(619) 230-7800	(760) 476-5621										
NORTHEAST	EASTERN	ORANGE COUNTY										
571 ENTERPRISE ST	904 WEST MAIN ST	662 CAMINO DE LOS MARES										
ESCONDIDO, CA 92029	EL CAJON, CA 92020	SAN CLEMENTE, CA 92673										
(760) 480-7745	(619) 441-3969	(949) 361-8066										

TABLE 2:

PROJECT MANAGEMENT OFFICES FOR RESIDENTIAL CUSTOMERS UP TO 400 AMPS AND NON-RESIDENTIAL CUSTOMERS UP TO 200 AMPS											
SOUTHERN REGION (METRO)	NORTHERN REGION	ORANGE COUNTY REGION									
8315 CENTURY PARK CT, STE 210	571 ENTERPRISE ST	662 CAMINO DE LOS MARES									
SAN DIEGO, CA 92123-1550	ESCONDIDO, CA 92029	SAN CLEMENTE, CA 92673									
(858) 636-6805	(760) 480-7603	(949) 361-8028									

IN ALL CASES, YOU MAY ALSO CONTACT SDG&E BY CALLING (877) 789-9866 OR VIA THE INTERNET AT: https://www.sdge.com/businesses/savings-center/services/service-planning-for-expansionrelocation/service-and-meter-request-form

TO REQUEST A **TRENCH INSPECTION**, CONTACT ONE OF THE FOLLOWING NUMBERS BETWEEN 7:00 A.M. AND 2:00 P.M. BASED ON THE LOCATION OF YOUR PROJECT.

TABLE 3:

SAN DIEGO GAS & ELECTRIC TRENCH INSPECTIONS												
SOUTHERN REGION (METRO)	NORTHERN REGION	ORANGE COUNTY REGION										
(877) 610-2948	(760) 432-5805	(949) 361-8061										

FOR SERVICE STANDARDS INTERPRETATIONS OR TO PURCHASE A SERVICE STANDARDS & GUIDE, CONTACT:

ISRAEL JUAREZ SERVICE STANDARDS TEAM LEAD <u>ijuarez@sdge.com</u> (858) 636-3941



© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.	
--	--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			5/22/2020	F						
В	EDITORIAL CHANGES		CSE	IPJ	CZH	2/10/2020	Е						
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/1/2017	D						


SHEET 1 OF 1

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE ORDER TEAMS & REGIONAL PROJECT MANAGEMENT OFFICES

SG021.1



SHEET 1 OF 1

PROJECT MANAGEMENT REGIONAL BOUNDARY MAP SG022.1

<u> </u>	SUBJECT – ELEC	CTRIC										<u>P</u>	PAGE
C	CONDUITS, CUSTON	MER-OWNED & -IN	ISTA	LLED									309
0	EFINITIONS OF TE	ERMS											003
E	LECTRIC METER C	ABINETS											509
Е	LECTRIC METER R	OOMS											506
Е	LECTRIC SERVICE	POLICIES										.011	- 014
F	AULT CURRENT, U	TILITY'S CONTRIB	BUTI	ON & E	XAMPLE	ĒS						00€	5, 008
L	OCKSMITHS, LISTI	NG OF											005
N	1ETER ACCESS												004.4
N	TETER POLES, CUS	TOMER-OWNED SE	ERV	ICE & M	IETER F	POLES						.204	– 205
N	1ETER TYPE & SOC	KET CLIP ARRANG	SEME	ENT									516
S	ERVICE LATERAL,	underground ei	LEC	TRIC SE	RVICE	LATERAL F	RESIDI	ENTIAL OR COMMERCIAL					309
Т	ERMINATING ENC	LOSURES											
	PULL CAN, 0-6	00 VOLTS										.705	- 706
	PULL SECTION	, 0-600 VOLTS											708
	PULL SECTION	, MEDIUM-VOLTAG	GE S	WITCH	GEAR								608
Т	RENCH INSPECTIO	NS										021,	004.5
Т	RUCK ACCESS											.015	- 016
ι	INACCEPTABLE ME	TER LOCATIONS											504.3
٧	VORKING SPACE												504.1
<u>s</u>	SUBJECT – GAS												
G	GAS METER CAPACI	TY & SELECTION											1005
C	SAS SERVICE RISER	R & HOUSELINE SP	PACI	NG, CLI	EARANC	CES, & MIN	IMUM	WORKING SPACE					1009
C	SAS TRENCH ONLY	FOR SAN DIEGO C	COUI	NTY									. 1004
N	1ETER CABINET FO	R SINGLE RESIDE	NTI	AL GAS	METER								. 1008
ι	TILITY PLACEMEN	T IN JOINT TRENC	CH &	GAS M	ETER S	SET ASSEM	BLY IN	NSTALLATION					. 1007
	© 1998 - 2025 Sa	an Diego Gas & Electri	ic Co	mpany. /	All rights	reserved. Re	moval	of this copyright notice without permission	_				
C C	CHAN EDITORIAL			BY DS	_	DATE 02/26/2025	REV	CHANGE	DR	BY	DSN	APV	DATE
В	FORMAT		DM		-	05/22/2020							
Α	NEW P					11/01/2017	1						
	SHEET	X Indicates Lates				mpletely Rev RIC SERVI		New Page Information Ren	noved		C	G02:	3 1
	1 OF 1		F	REQL	IENTL	Y REFER	RENC	CED STANDARDS			3	JUZ.	J. 1

ELECTRIC SECTIONS

SUBJECT	<u>PAGE</u>
ACCESSIBILITY	004.4
ACCESSIBLE/INACCESSIBLE METER LOCATION	005.1
ADDING LOAD TO EXISTING METER PANELS	004.2
ADDITIONS, ALTERATIONS OR RENEWAL OF EXISTING SERVICE AND METERING EQUIPMENT	504.2
ADDRESSING CONVENTIONS	004.5
ALTERNATE SERVICE DELIVERY POINT REQUESTS	011.2
APPLICATION FOR A BILLING ACCOUNT	004.2
BARRIERS FOR ELECTRIC SERVICE AND METERING EQUIPMENT	505
BIL RATING	603.4
BUS TAP DRAWINGS FOR APPROVAL	517.1, 603.3
BUSWAY SERVICE HEADS	110
CABLE POLE QUADRANT AND RISER IDENTIFICATION	314
CABLE POLE RISER INSTALLATION	315
CABLE POLE RISER POSITION USING LADDER ARM BRACKET AND SINGLE RISER	313
CABLE TERMINATION BUS STUBS	709
CHARACTER OF SERVICE	004.3
CLEARANCES OF OVERHEAD FACILITIES FROM TANKS CONTAINING FLAMMABLE OR EXPLOSIVE MIXTURE	019
CLEARANCES, MEDIUM-VOLTAGE CONDUCTORS	018
CONDUIT BEND AND RISER AT BUILDING	312
CONNECTION OR DISCONNECTION OF SERVICE	004.4
CONTROL POWER TRANSFORMER METERING	605
CONVERSIONS	303 – 305
CURRENT TRANSFORMER DIMENSIONS	606

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	SG308 MOVED TO FMO	EDM	JIK	IPJ	CZH	02/08/2021	F						
В	FORMATTING	EDM	JIK	-		05/22/2020	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D	EDITORIAL CHANGES	EDM	JIK	JTM	KRG	02/26/2025

SHEET 1 OF 9 Indicates Latest Revision Completely Revised New Page X Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG024.1

ALPHABETICAL SUBJECT INDEX

SUBJECT PAGE **CUSTOMER GENERATION** CLEARANCE REQUIREMENTS FROM SDG&E-OWNED ELECTRIC METER AND SERVICE AND GAS METER ASSEMBLY810 VOLTAGE STANDARDS 807.5 CUSTOMER-OWNED SERVICE AND METER POLES © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. REV DR BY DSN APV DR BY DSN APV DATE **CHANGE** DATE REV **CHANGE** С SG308 MOVED TO FMO EDM JIK IPJ CZH 02/08/2021 В **FORMATTING** EDM JIK 05/22/2020 E LSM LSM TPM 11/01/2017 D **NEW PAGE** EDM | JIK | JTM | KRG | 02/26/2025 Α **EDITORIAL CHANGES Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG024.2 2 OF 9 ALPHABETICAL SUBJECT INDEX

<u>s</u>	<u>UBJECT</u>												<u> </u>	PAGE
El	LECTRIC METER A	ND SERVICE LO	CATION	- COMI	MERC:	ial and ri	ESIDE	NTIAL PREMISES						
	COMMERCIAL A	AND INDUSTRIA	L, METE	r loca	TION	S								504.3
	GENERAL INFO	RMATION											503	3, 504
	INACCESSIBLE													005.1
	MID-RISE AND HIGH-RISE BUILDINGS													510
	REQUESTS, ELECTRIC METER AND SERVICE LOCATION													503
	RESIDENTIAL, METER LOCATIONS													
	SINGLE OR MULTIPLE METER INSTALLATIONS													
	SINGLE OR MULTIPLE METER INSTALLATIONS													504.3
El														
	ELECTRIC METER CABINET – COMMERCIAL OR RESIDENTIAL MULTI-METER INSTALLATIONS													
	ELECTRIC METER ROOM													
	·													
	ELECTRIC SERVICE POLICIES													
L	ELECTRIC TERMINATING ENCLOSURES, 0–600V													
GENERAL INFORMATION														,
_														
	QUIPMENT PROVII													
	XISTING CUSTOME													
E	XISTING GAS MET	er below elec	TRIC SE	RVICE	AND N	METERING	EQUI	PMENT						504.2
F)	ield heating sep	RVICE LATERAL (CONDUI	ΓS										306
G	AS AND ELECTRIC	METER ACCESS												005.1
G	ENERAL INFORMA	TION												004
G	ROUNDING AND B	ONDING												112.6
IN	ngress and egre	SS TO ELECTRI	C SERVI	CE AND	METI	ering Equ	JIPME	NT						504.2
	© 1998 - 2025 Sa	an Diego Gas & Elec	ctric Comp	any. All	rights r	eserved. Rer	moval (of this copyright notice	e without permission	is not p	ermitt	ed und	der law	
REV	CHAN	IGE	DR B	-			REV	СНА	NGE	DR	BY	DSN	APV	DATE
C B	SG308 MOVE FORMAT		EDM JI	-		02/08/2021 05/22/2020								
A	NEW P		+ +	M LSM		11/01/2017		EDITORIA	L CHANGES	EDM	JIK	JTM	KRG	02/26/2025
		X Indicates Lat				pletely Revi		New Page	Information Ren	noved				
	SHEET		SI	G&E E	LECT	RIC SERVIC	E ST	Andards & Guid	ES			c	CU2	4 3
	3 OF 9 ALPHABETICAL SUBJECT INDEX SG024.3													

F

<u>s</u>	SUBJECT												<u> </u>	PAGE
II	NSPECTION AUTHO	ORITY												003.1
II	NSTRUMENT TRAN	SFORMER MOUN	TING	SPE	CIFIC	CATIO	NS							607
L	OCKSMITHS, LISTI	ING OF										00	5.1 –	005.2
M	ianufacturer's i	DRAWINGS FOR A	APPR	OVAL								5	17.1,	603.1
M	IARKOUT SERVICE													004.5
M	IEDIUM-VOLTAGE	CONDUCTOR CLE	EARAI	NCES	FOR	NON-	-UTILITY W	/ORK	ERS AND EQUIPMENT					018
M	IEDIUM VOLTAGE I	METERING CUBIO	CLE											604
M	IEDIUM VOLTAGE :	SERVICE AND ME	TERI	NG E	EQUIF	PMENT	Γ							603
					_									
									DN - COMMERCIAL AND RESIDENTI					
		•							CONTRENENT AND RESIDENT			,		
	METER PEDESTAL FOUNDATION DETAILS													
	METER PEDESTAL, FIELD REPLACEMENT OF EXISTING 120-VOLT METER PEDESTAL													
	·													
M	ietered and unm	1ETERED CONDU	CTOF	S										503
M	IETERING COMMU	NICATIONS												525
M	IID-RISE AND HIG	H-RISE BUILDING	3S											510
M	OBILE HOME PARI	K SERVICE AND I	METE	R PE	DEST	ALS								518
M	MULTI-FAMILY RESIDENTIAL BUILDINGS – LESS THAN 3 STORIES HIGH													
С	VERHEAD ELECTR	IC CLEARANCES	OVER	SW	IMMI	NG PC	OOLS							108
Р	ERMIT AND INSPE	CTION												004.2
Р	LAQUE SPECIFICA	TIONS AND EXAM	1PLES	S										017
				_					of this copyright notice without permission is			_		
REV	SG308 MOVE		DR EDM		IPJ	APV CZH	DATE 02/08/2021	REV F	CHANGE	DR	ВҮ	DSN	APV	DATE
В	FORMAT		EDM			-	05/22/2020							
Α	NEW P	AGE	-	LSM	LSM	TPM	11/01/2017	D	EDITORIAL CHANGES	EDM	JIK	JTM	KRG	02/26/2025
		X Indicates Late	est Re				npletely Revi		New Page Information Rem	oved	_			
	SHEET			SDG	i&E E	LECT	KIC SERVIC	ESI	ANDARDS & GUIDES			C	G02	44
	4 OF 9				ALP	HAB	ETICAL	SUB	JECT INDEX			3	J UZ	ıı f

<u> </u>	SUBJECT												<u> </u>	PAGE
F	PRODUCT DISTRIBL	JTORS												020
F	PULLING DEVICES F	OR INSTALLATIO	O NC	F SEI	RVICE	E LATI	ERAL CONE	OUCTO	DRS IN PARKING STRUCTURES					016
F	PURPOSE													004.1
F	READILY ACCESSIB	LE DEFINITION												503
F	REQUEST FOR SERN	/ICE											021,	004.2
F	RESIDENTIAL OR M	IXED USE BUILD	INGS	- 3	STOR	IES C	OR GREATE	R				0	12.1,	013.1
F	RESIDENTIAL SING	LE-PHASE MULTI	-MET	ER S	TACK	SPEC	CIAL APPLI	CATIO	DN					707
F	RESIDENTIAL CONT	IGUOUS DWELLI	INGS	– TC)WNF	IOUSE	ES (ROW H	OMES	s)			0	12.1,	013.1
F	RIGHTS OF WAY													011.2
F	RISERS													
	METALLIC CON	NDUIT RISERS												105
	SOLID WOOD	RISERS												106
9	SAFETY SOCKET ME	TER CANS												514
9	Sample plaque FC	OR ELECTRICAL E	QUIP	MEN	T LAE	BELS.								017.1
Ş	SCOPE													004.1
Ş	SDG&E TRANSFORM	MER FUSING INFO	ORMA	TIOI	١									007.1
9	SDG&E WILL FURNI	SH, INSTALL, OV	VN, A	ND I	MAIN ⁻	TAIN								009.2
9	SEALING OF METER	AND SERVICE F	ACILI	TIES	S								004.4	1, 503
9	SECONDARY SERVII	ng voltages an	ND CI	_ASS	IFICA	TION	OF SERVIO	CE IN	FORMATION					011.3
Ş	SERVICE DROPS													
	ATTACHMENTS	S										10	3, 105	5, 106
	CLEARANCES													107
	CLEARANCES (OVER SWIMMING	POC	LS										108
	GENERAL INFO	ORMATION												103.4
	LENGTH													
	SUPPORTS													104
	© 1998 - 2025 Sa	an Diego Gas & Elec	tric Co	mpar	ny. All	rights ı	reserved. Rei	moval	of this copyright notice without permission	is not p	ermitt	ed und	ler law	
REV C	CHAN SG308 MOVE		DR EDM		DSN IPJ	APV C7H	DATE 02/08/2021	REV	CHANGE	DR	BY	DSN	APV	DATE
В	FORMAT		EDM	JIK	-	-	05/22/2020	E						
Α	NEW P	AGE Indicates Late	- oct D -				11/01/2017		EDITORIAL CHANGES New Page Information Ren		JIK	JTM	KRG	02/26/2025
	SHEET 5 OF 9	indicates Late	est KE	SDG	&E E	LECTI		E ST	New Page Information Ren	ioveu		S	G02	4.5
	·				ALP.	i iAD	LIICAL	500	DECT TINDEY					

<u>s</u>	<u>SUBJECT</u>												<u> </u>	PAGE
S	SERVICE AND METE	RING EQUIPMEN	NT, RES	IDENTI.	AL SEI	_F-CONTAI	NED							
	COMBINATION	I PULL AND METI	ER CAN:	5										512
	EQUIPMENT CO	ONNECTED AHEA	AD OF A	MAIN :	SERVI	CE DISCO	NNECT	Γ						512.1
	METER SOCKE	T CLOSING DEVI	ICES											512.1
	METER SOCKE	T CONNECTIONS	5											512.1
	SELF-CONTAIN	IED METER SOCK	KETS											512.1
S	SERVICE ENTRANCE	E CONDUCTORS,	0–600\	′										112
		RANCE CONDUCTORS, 0–600V												
S	SERVICE ENTRANCE	E RACEWAYS	CEWAYS											111
S	SERVICE HEADS													109
S	SERVICE LOCATION	IS												011.2
													,	
													,	
													,	
		LE PREMISES – SINGLE RESIDENTIAL CUSTOMER WITH OTHER ELECTRIC USES												
									D FEEDER BUSWAYS					
- 1									tice without permission					
REV	CHAN			Y DSN		DATE	REV		HANGE	DR		DSN		DATE
С	SG308 MOVE	D TO FMO	EDM J	K IPJ	CZH	02/08/2021	F							
В	FORMAT		EDM J	-		05/22/2020	-			_	_			
Α	NEW P			M LSM		11/01/2017			IAL CHANGES	1	JIK	JTM	KRG	02/26/2025
		X Indicates Lat				pletely Rev		New Page ANDARDS & GU	Information Ren	noved	4			
	SHEET		3	JUKE E	LLCIF	TC DEKAI	JL 31/	א כעוואטויר	IDLJ		\dashv	c	G02	4.6
	6 OF 9			ALF	НАВ	ETICAL	SUB	JECT INDEX	(3	UU Z	ייר

F

<u>s</u>	SUBJECT												<u>P</u>	AGE
Т	RUCK ACCESS REQ	UIREMENTS, LIN	IE											015
Т	YPICAL PLAQUE FC	OR EXISTING BUI	LDIN	igs v	NITH	INTE	RMIXED SE	RVIC	ES				(017.3
Т	YPICAL PLAQUE FC	OR NEW BUILDIN	GS O	R EX	(ISTI)	NG BU	JILDINGS V	VITH	SEPARATE SERVICE AREAS				(017.2
U	INACCEPTABLE MET	TER LOCATIONS.											!	504.3
U	JNDERGROUND ELE	ECTRIC SERVICE	LATE	RAL	CLEA	RANC	ES							
	GASOLINE DIS	PENSING AND SE	ERVIC	JE S7	ΓΑΤΙC)NS							316	, 318
	LEACH FIELDS													319
	PROPANE TANK	KS											. 317	- 318
U	INDERGROUND ELE	ECTRIC SERVICE	LATE	RAL	CONI	TIUC	REQUIREM	ENTS						309
U	Inderground Pul	LL CAN WITH CAE	BLE T	FERM	IINAT	TON E	BUS STUBS							706
U	Inderground Pul	LL CAN WITH OR	. WIT	HOU	T ME	CHAN	ICAL LUGS							705
U	INDERGROUND PUL	LL SECTION (SEE	ELEC	CTRI	C TEF	≀MIN <i>F</i>	ATING ENC	LOSU	RES, 0-600V) SHEET 3					
U	UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE)310													
							•	•						
U	UNDERGROUND SERVICE FROM OVERHEAD FACILITIES-PADMOUNT TRANSFORMER													
U	JTILITY METERS													003.3
U	JTILITY'S CONTRIB	UTION TO FAULT	r cuf	REN	ĮΤ		•••••							006
U	JTILITY'S CONTRIB	UTION TO FAULT	r cuf	REN	IT SE	COND	ARY VOLTA	AGE S	ERVICE EXAMPLES					008
٧	'ENTILATION											5	17.2, (503.4
٧	VIRELESS COMMUN	ICATIONS ON PF	RIVA ⁻	ΓΕ ΡΙ	ROPE	RTY								522
٧	VIRELESS COMMUN	NICATIONS PROV	IDER	. – M	ETER	.ED EL	LECTRIC SE	RVIC	E					523
٧	VORK ON UTILITY-	OWNED POLES											(004.4
٧	VORKING SPACE													
	LOW VOLTAGE	(0–600V)											!	504.1
	MEDIUM-VOLT	AGE SWITCHGEA	۱R										(603.3
	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.													
REV	CHAN SG308 MOVE		DR EDM	-		APV CZH	DATE 02/08/2021	REV F	CHANGE	DR	BY	DSN	APV	DATE
В	FORMAT		EDM		-	-	05/22/2020							
Α	NEW PA			l			11/01/2017	L	EDITORIAL CHANGES	_	JIK	JTM	KRG (02/26/2025
	CHEET	X Indicates Late					npletely Revis		New Page Information Rei	noved	\dashv			
	SHEET 7 OF 9				ALP	HAB	ETICAL	SUB	JECT INDEX			S	G02 [,]	4.7

F

GAS SECTION

SUBJECT	<u>PAGE</u>
BARRICADES FOR GAS METER SETS	1014
BILLING ACCOUNT ESTABLISHMENT	1003.2
BUILDING RECESS FOR GAS SERVICE AND METERS	1012
CUSTOMER RESPONSIBILITY FOR APPLIANCES	1003.2
DEFINITIONS OF TERMS	1003
ELECTRIC BONDING AND GROUNDING OF GAS PIPE	1003.4
ESTABLISHING GAS METER LOCATION AND LOCATION OF CUSTOMER'S HOUSELINE	1003.2
EXISTING GAS SERVICE - CUSTOMER REQUESTS FOR ADDITIONAL SERVICES	1006.3
GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES	1015
GAS METER CAPACITY AND SELECTION	1005
GAS METERS GROUPED ON METER HEADERS	1010.1
GAS SERVICE AND METERING	1003.1
GAS SERVICE AND METER BEHIND WING WALLS	1011
GAS SERVICE RISER AND HOUSELINE SPACING, CLEARANCES, AND MINIMUM WORKING SPACE	1009
GAS TRENCH ONLY FOR SAN DIEGO COUNTY	1004
HOUSELINE MODIFICATIONS	1003.3
MARKOUT SERVICE	1003.4
METER AND SERVICE LOCATION	1006
METER CABINET FOR SINGLE RESIDENTIAL GAS METER	1008
METER LOCATIONS	1006
MOBILE HOME METER PAD	1013
NUMBER OF SERVICES ALLOWED TO A BUILDING	1006.2
OWNERSHIP AND MAINTENANCE OF UTILITY'S FACILITIES	1003.3

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

				-	_								
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	SG308 MOVED TO FMO	EDM	JIK	IPJ	CZH	02/08/2021	F						
В	FORMATTING	EDM	JIK	-	-	05/22/2020	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D	EDITORIAL CHANGES	EDM	JIK	JTM	KRG	02/26/2025

SHEET 8 OF 9 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ALPHABETICAL SUBJECT INDEX

SG024.8

SUBJECT	<u>PAGE</u>
PURPOSE	
RESALE OF NATURAL GAS	
SCOPE	
SERVICE LOCATIONS	1006.4
SIGNAGE REQUIREMENTS FOR GAS SERVICE LOCATIONS ON MULTI-TENANT BUILDINGS	
TERRITORY SERVED	
UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION	1007
UTILITY'S RIGHT OF ACCESS TO CUSTOMER'S PREMISES	1003

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C SG308 MOVED TO FMO EDM JIK IPJ CZH 02/08/2021 F B FORMATTING EDM JIK - - 05/22/2020 E	REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
B FORMATTING EDM JIK 05/22/2020 E	С	SG308 MOVED TO FMO	EDM	JIK	IPJ	CZH	02/08/2021	F						
	В	FORMATTING	EDM	JIK	-	-	05/22/2020	Е						
A NEW PAGE - LSM LSM TPM 11/01/2017 D EDITORIAL CHANGES EDM JIK J	Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D	EDITORIAL CHANGES	EDM	JIK	JTM	KRG	02/26/2025

SHEET 9 OF 9

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ALPHABETICAL SUBJECT INDEX

SG024.9

100 - RESIDENTIAL, COMMERCIAL & INDUSTRIAL OVERHEAD

100 - RESIDENTIAL, COMMERCIAL & INDUSTRIAL OVERHEAD

<u>PAGE</u>	<u>SUBJECT</u>
102	RESIDENTIAL, COMMERCIAL AND INDUSTRIAL OVERHEAD ALPHABETICAL SUBJECT INDEX
103	SERVICE DROPS – OVERHEAD ELECTRIC
104	SERVICE DROP SUPPORTS
105	OVERHEAD SERVICE ATTACHMENT FOR METALLIC CONDUIT RISERS
106	OVERHEAD SERVICE ATTACHMENT FOR SOLID WOOD RISERS
107	SERVICE DROP CONDUCTOR CLEARANCES, 0-600V
108	OVERHEAD ELECTRIC CLEARANCES OVER SWIMMING POOLS
109	SERVICE HEADS
110	BUSWAY SERVICE HEADS
111	SERVICE ENTRANCE RACEWAYS
112	SERVICE ENTRANCE CONDUCTORS, 0-600V

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

RESIDENTIAL, COMMERCIAL, AND INDUSTRIAL OVERHEAD TABLE OF CONTENTS

SG101.1

<u>s</u>	<u>SUBJECT</u>												<u>F</u>	PAGE
Α	LUMINUM SERVIC	E ENTRANCE CONDU	CTOR	S										112.6
В	USWAY SERVICE H	HEADS												110
C	LEARANCES													
	ABOVE COMMI	ERCIAL OR INDUSTR	IAL B	UILDI	NGS A	AND STRUC	CTURE	S, SERVICE ENT	RANCE CONDUCT	ORS,	0-600	ον		112.6
	ABOVE GROUN	ID, THOROUGHFARE	S, DR	IVEW.	AYS A	and Public	C/PRI\	/ATE PROPERTY.						107.8
	COMMERCIAL	OR INDUSTRIAL PRE	MISE	S SER	VICE	DROP CON	IDUCT	OR, 0-600V						107.6
	FROM BUILDIN	NGS AND STRUCTUR	ES, RI	SIDE	NTIA	L, COMMER	CIAL/	INDUSTRIAL PRE	MISES			10	7.11,	112.6
	FROM DOORS,	EXITS, WINDOWS,	FIRE I	ESCAF	PES, E	BALCONIES	, ETC.							107.4
	FROM OTHER	CONDUCTORS												107.9
	FROM SIGNS												1	07.10
		AND VERTICAL CLEA OTHER STRUCTURE									•			107.7
	OVER BUILDINGS AND STRUCTURES													
	OVER THOROL	JGHFARES, FROM BU	ILDIN	IGS A	ND A	T POINT OF	= ATT	ACHMENT TO BU	ILDING					
	RESIDEN ⁻	TIAL PREMISES												107.5
	COMMERC	CIAL OR INDUSTRIAI	. PREI	MISES	5									107.6
	SWIMMING PO	OLS												108
C	ONNECTION OF SI	ERVICE ENTRANCE C	ONDU	JCTOF	RS TO	SERVICE I	DROP	CONDUCTORS						112.4
D	RIP LOOPS									103.	4, 10	4.5, 1	12.4,	112.6
		CONDUIT RISER OF RVICE ATTACHMENT												105
G	ENERAL INFORMA	TION												
	BUSWAY SERV	ICE HEADS												110
	OVERHEAD EL	ECTRIC CLEARANCES	OVE	R SW	IMMI	NG POOLS.								108
	SERVICE DROP	PS, OVERHEAD ELEC	TRIC.									1	03.1,	103.4
	SERVICE DROP	P SUPPORT												104
	SERVICE DROP	P CONDUCTOR CLEA	RANC	ES, 0-	600V							1	07.1,	107.8
-\/		an Diego Gas & Electric (-							-			
E V	CHAN	GE DR	ВҮ	DSN	APV	DATE	REV	СНА	NGE	DR	BY	DSN	APV	DAT
3	FORMAT		JIK	-	-	04/24/2023	Е							
4	EDITORIAL (l	<u>' </u>		11/01/2017			T		<u> </u>			
		X Indicates Latest F				npletely Revi		New Page ANDARDS & GUID	Information Reports	moved	1			
	SHEET 1 OF 3	RESIDEN		_, cc	MMC	ERCIAL	AND	INDUSTRIA	L OVERHEAD			S	G10	2.1
	_ 0. 0			ALP	HAB	ETICAL	SUB.	JECT INDEX	_					

<u>s</u>	SUBJECT .													<u> </u>	PAGE
	SERVICE ENTR	ANCE CONDUC	TORS	, 0-60	00V							112	.1, 11	2.3 –	112.4
	SERVICE ENTR	ance racewa	YS												111
	SERVICE HEAD	S													109
G	ROUNDING AND B	ONDING													112.6
II	DENTIFICATION, S	ERVICE ENTRA	NCE C	OND	исто	RS, 0	–600V								112.4
Ιſ	NSTALLATION MET	HOD, SERVICE	ENTR	ANCE	RAC	EWA	′S								111
0	VERHEAD ELECTR	IC CLEARANCES	OVE	R SW	IMMI	NG P	OOLS								108
	MINIMUM VER	TICAL AND RAD	IAL C	LEAR	ANCE	S OV	ER SWIMM	ING P	00LS						108
0	VERHEAD SERVIC	E ATTACHMENT	FOR	META	ALLIC	CONI	OUIT RISEF	RS							105
0	VERHEAD SERVIC	E ATTACHMENT	FOR	SOLI	D WO	OD R	ISERS								106
R	ISERS														
	CLEARANCE RI	SERS OR STRU	CTUR	ES											104
	METALLIC CON	IDUIT RISERS													105
	SOLID WOOD	RISERS													106
S	EALING SERVICE E	NTRANCE RACI	EWAY	s ani	D MET	TERIN	ig enclos	URES							111
S	ERVICE DROPS														103
	ATTACHMENTS	S											10	3, 105	, 106
	COMMERCIAL	AND INDUSTRI	AL BU	ILDIN	NGS O	R STI	RUCTURES						10	3.2 –	103.4
	CONDUCTOR O	CLEARANCES													107
	GENERAL INFO	RMATION													103.4
	IMPAIRED CLE	ARANCES													103.5
	LENGTH														103.1
	RESIDENTIAL	BUILDINGS OR	STRU	CTUR	RES						103.1	., 103	.2 – 1	03.4,	103.5
	SUPPORTS														104
	SWIMMING PC	OLS													108
REV	© 1998 - 2023 Sa	_	ectric C		ny. All DSN		reserved. Rei	moval o	of this copyright notice		is not	1	ted und		DATE
С	CHAIN	UL.	DK	D 1	DON	AI V	DAIL	F	CHAI	101	DIC	<u> </u>	DOIN	AI V	DAIL
В	FORMAT		EDM		-		04/24/2023								
Α	EDITORIAL (X Indicates La	- tost D		<u>' </u>		11/01/2017	1	New Page	Information Re	movoc				
	SHEET	A Indicates La	icsi K	CVISIUI			· · ·		ARDS & GUIDES	Information Re	HOVEL				
	2 OF 3	RESI	DEN.	TIAL	_, CC	MMC	ERCIAL	AND	INDUSTRIAL JECT INDEX	OVERHEAD			S	G10	2.2
					ALL	ПAD	FITCAL	SUD	DECT TINDEY			1			

<u>SUBJECT</u> P	<u>AGE</u>
SERVICE DROP SUPPORTS	104
ATTACHMENT RISER, ANGLE IRON RACK	104.1
BUILDINGS OTHER THAN WOOD	L04.4
CLEARANCE RISERS OR STRUCTURES	L04.4
GENERAL INFORMATION	l04.1
INSTALLATION	104.5
MAINTENANCE RESPONSIBILITY AND LIABILITY	L04.5
WOOD BUILDINGS	L04.4
WOOD-REINFORCING BLOCK	L04.4
SERVICE ENTRANCE CABLE	12.5
SERVICE ENTRANCE CONDUCTORS, 0-600V	112
CONNECTION OF SERVICE ENTRANCE CONDUCTORS TO SERVICE DROP CONDUCTORS	12.4
DEFINITIONS	12.1
IDENTIFICATION	12.4
MAXIMUM LENGTH OF SERVICE ENTRANCE CONDUCTORS	12.4
OTHER CONDUCTORS IN SERVICE ENTRANCE RACEWAYS	12.5
SERVICE ENTRANCE CABLE	12.5
SIZE AND CAPACITY	12.5
TAPS AND SPLICES IN SERVICE RACEWAYS	12.5
SERVICE ENTRANCE RACEWAYS	111
SERVICE HEADS	. 109
LOCATION	109.1
MULTIPLE SERVICE HEAD INSTALLATIONS	109.2

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

RESIDENTIAL, COMMERCIAL AND INDUSTRIAL OVERHEAD ALPHABETICAL SUBJECT INDEX

SG102.3

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR OVERHEAD ELECTRIC SERVICE DROPS FOR RESIDENTIAL AND COMMERCIAL BUILDINGS OR STRUCTURES.

ATTENTION:

- WHERE SDG&E'S DISTRIBUTION POLE LINE IS LOCATED ON THE CUSTOMER'S PREMISES, OR ON A STREET, HIGHWAY, LANE, ALLEY, ROAD, OR PRIVATE EASEMENT CONTIGUOUS THERETO, SDG&E (UTILITY) WILL, AT ITS OWN EXPENSE, FURNISH AND INSTALL A SERVICE DROP (SINGLE SPAN OF SERVICE WIRES) FROM ITS POLE LINE TO THE CUSTOMER'S PERMANENT SERVICE DROP SUPPORT. UPON THE UTILITY'S RECEIPT OF APPROVAL FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ), THE UTILITY WILL CONNECT TO THE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS PROVIDED SUCH SUPPORT IS OF A TYPE ACCEPTABLE TO THE UTILITY.
- THE CUSTOMER IS REQUIRED TO PROVIDE, OR PAY FOR, A CLEAR ROUTE ON ANY PRIVATE PROPERTY THAT IS CLEAR OF OBSTRUCTIONS WHICH WOULD INHIBIT THE CONSTRUCTION OF OVERHEAD SERVICE FACILITIES. THIS INCLUDES TREE TRIMMING, OR TREE REMOVAL, IF REQUIRED.
- *** THE MAXIMUM LENGTH OF SERVICE DROP NORMALLY SHALL NOT EXCEED 100 FEET. IN ORDER TO MINIMIZE SERVICE DROP STRESS ON THE BUILDING, THE POINT OF ATTACHMENT SHALL BE LOCATED AS NEAR AS PRACTICABLE TO THE UTILITY'S SERVICE POLE. WHERE THE CHARACTER OF LOAD NECESSITATES HEAVY SERVICE DROP CONDUCTORS WITH EXCESSIVE SAG AND STRESS, THE MAXIMUM LENGTH OF SERVICE DROP SHALL BE SUBJECT TO APPROVAL OF THE UTILITY'S SERVICE PLANNER.




FIGURE 1 RESIDENTIAL BUILDINGS OR STRUCTURES PLAN VIEW SEE TABLE 1


© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	05/09/2023	F						
В	FORMATTING	EDM	JIK	-	1	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 6


Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROPS - OVERHEAD ELECTRIC



TO SERVICE DROP ATTACHMENT RISER PLAN VIEW SEE TABLE 1

PLAN VIEW SEE TABLE 1



EXAMPLE 1 WALL FACING AND NEAREST LINE AFFORDING (B) ADEQUATE CLEARANCE PLAN VIEW

EXAMPLE 2 PLAN VIEW(J)

EXAMPLE 3 LOW SHED-TYPE (K)XII) **BUILDING WALLS** PLAN VIEW


EXAMPLE 4 INADEQUATE (K)(XIII) **CLEARANCES**

FIGURE 4 COMMERCIAL AND INDUSTRIAL BUILDINGS OR STRUCTURES SEE TABLE 1

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. DATE **REV** DSN APV DR DSN APV **CHANGE** DR BY DATE **REV CHANGE** BY C **EDITORIAL CHANGES ARC** IPJ IPJ KRG 05/09/2023 F В **FORMATTING EDM** JIK 04/24/2023 Ε **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 Α

SHEET 2 OF 6 **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROPS - OVERHEAD ELECTRIC



EXAMPLE 5
SERVICE DROP OVER
INTERVENING LOT B M
NOT PERMITTED
PLAN VIEW

EXAMPLE 6
SERVICE DROP CLEARANCE OVER
STAIRWAYS AND SHED-TYPE
BUILDING PROJECTIONS
PROFILE VIEW

EXAMPLE 7
MAXIMUM HEIGHT
SERVICE DROP ATTACHMENT
PROFILE VIEW

FIGURE 4 (CONT'D)

COMMERCIAL AND INDUSTRIAL BUILDINGS OR STRUCTURES SEE TABLE 1

TABLE 1

	SERVICE DROPS DESCRIPTION LIST
ITEM	DESCRIPTION
1	ATTACHMENT, SERVICE DROP
2	SERVICE DROP
3	RISER, SERVICE DROP ATTACHMENT
4	BUILDING PROJECTIONS, SHED-TYPE, LOW
5	STAIRWAYS, ETC.
6	BUILDING PROJECTIONS, SHED-TYPE
7	SERVICE DROP CROSSING OVER ROOF PROJECTION TO NEAREST WALL

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	05/09/2023	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 6

 Indicates Latest Revision
 Completely Revised
 New Page
 Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROPS - OVERHEAD ELECTRIC

INSTALLATION:

SERVICE DROP ATTACHMENT

- A. THE POINT OF SERVICE DROP ATTACHMENT SHALL NORMALLY BE LOCATED ON THAT PORTION OF A BUILDING OR STRUCTURE FACING AND NEAREST THE STREET, ALLEY, EASEMENT, OR PUBLIC WAY ON WHICH THE UTILITY'S POLE LINE IS LOCATED, AND INSTALLED AT A HEIGHT NOT LESS THAN SPECIFIED HEREIN FOR RESIDENTIAL, COMMERCIAL AND INDUSTRIAL BUILDINGS (SEE SG107). THIS IS TO PERMIT THE SERVICE DROP CONDUCTORS TO BE:
 - 1. INSTALLED AND MAINTAINED IN ACCORDANCE WITH VERTICAL, HORIZONTAL AND RADIAL CLEARANCES REQUIRED ABOVE GROUND AND FROM ROOFS, OBSTRUCTIONS, WINDOWS, DOORWAYS, OPENINGS, BALCONIES, FIRE ESCAPES, SWIMMING POOLS AND OTHER CONDUCTORS.
 - 2. RUN FREE OF OBSTRUCTION FROM TREES, STRUCTURES, POLES, MASTS, ANTENNAS, VENTS, FLOOD LIGHTS, ETC. AN 18-INCH RADIAL CLEARANCE IS REQUIRED FROM ELECTRIC RISERS SUPPORTING SERVICE CONDUCTORS TO VENTS OR CHIMNEYS CONVEYING PRODUCTS OF COMBUSTION TO THE OUTSIDE ATMOSPHERE, SUCH AS A WATER HEATER VENT OR WOOD BURNING STOVE VENT. A VENT SHALL NOT BE INSTALLED WITHIN THE WORKING SPACE OF THE ELECTRICAL EQUIPMENT. 12-INCH MINIMUM RADIAL CLEARANCE IS REQUIRED FROM VENTS TO SERVICE DROP CONDUCTORS CROSSING OVER A STRUCTURE TO WITHIN 18 INCHES OF THE RISER.
 - 3. INSTALLED AT AN APPROACH ANGLE OF NOT LESS THAN 30 DEGREES WITH THE BUILDING WALL WHEN SERVICE ATTACHES BELOW ROOFLINE.
 - 4. READILY ACCESSIBLE FOR INSTALLATION, INSPECTION AND MAINTENANCE.
 - 5. INSTALLED AT A LOCATION WHERE THE WEATHERHEAD AND POINT OF ATTACHMENT ARE SAFELY ACCESSIBLE FROM A LADDER PLACED ON THE GROUND. DISTANCE FROM THE LADDER TO THE WEATHERHEAD AND POINT OF ATTACHMENT IS NOT TO EXCEED 24 INCHES.
 - ATTACHED AT ONLY ONE POINT ON THE BUILDING AND WITHOUT INTERMEDIATE SUPPORT.
 - 7. ATTACHED IN THE PROXIMITY OF THE SERVICE ENTRANCE SO THAT THE OPEN WIRING BETWEEN THE SERVICE DROP AND THE SERVICE HEAD (DRIP LOOP) DOES NOT EXCEED 3 FEET.
 - 8. ATTACHED AT NOT MORE THAN 30 FEET ABOVE THE GROUND.
 - 9. SO ARRANGED AS NOT TO HAMPER OR ENDANGER WORKERS AND FIREMEN IN THE PERFORMANCE OF THEIR DUTIES.
 - 10. SUBSTANTIALLY SUPPORTED AT THE BUILDING.
- B THE SERVICE DROP WILL NORMALLY BE RUN TO THE BUILDING OR STRUCTURE FROM THE UTILITY'S NEAREST POLE ADJACENT TO THE PREMISES. UNDER THIS CONDITION THE SERVICE DROP MAY, WHERE APPROVED BY THE UTILITY, CROSS AN ADJOINING PREMISES PROVIDED THE NECESSARY RIGHTS-OF-WAY CAN BE OBTAINED AT NO COST TO THE UTILITY. IN EVERY CASE, THE POINT OF SERVICE DROP ATTACHMENT SHALL BE LOCATED ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE OR WITHIN 18 INCHES OF THAT POINT TO PERMIT THE UTILITY, AS NECESSITATED FOR ITS OPERATING CONVENIENCE, TO INSTALL A SERVICE DROP FROM SOME POINT ALONG ITS LINE PASSING THE PREMISES SERVED WHETHER OR NOT A POLE EXISTS. SEE FIGURE 1 EXAMPLE 3, AND FIGURE 3 EXAMPLES 1 AND 5.

RESIDENTIAL BUILDINGS OR STRUCTURES

(C) THE POINT OF SERVICE DROP ATTACHMENT ON A RESIDENTIAL BUILDING OR STRUCTURE SHALL NORMALLY BE LOCATED ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE, AND SO LOCATED THAT THE SERVICE HEAD, SERVICE DROP AND OPEN WIRES BETWEEN THE SERVICE HEAD AND POINT OF CONNECTION TO THE SERVICE DROP (DRIP LOOP) WILL HAVE NOT LESS THAN 12-FOOT CLEARANCE ABOVE FINAL GRADE ON RESIDENTIAL PREMISES, AND WHENEVER NECESSARY, BE LOCATED AT A GREATER HEIGHT TO OBTAIN REQUIRED CLEARANCES. THE 12-FOOT CLEARANCE MAY BE REDUCED FOR INSULATED SERVICES (SSC) TO NOT LESS THAN 10 FEET. SEE FIGURE 1 – EXAMPLE 1.

RESIDENTIAL DWELLING UNITS EXCEEDING TWO IN NUMBER ON THE SAME PREMISES ARE CLASSIFIED AS A COMMERCIAL ENTERPRISE AND PREMISES, REQUIRING THE SERVICE DROP ATTACHMENT TO BE LOCATED AT A POINT AFFORDING COMMERCIAL SERVICE DROP CLEARANCES.

	© 1998 - 2023 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights r	reserved. Rer	noval c	of this	s copyright no	otice	e without permission	is not	permit	ted und	der law.	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	HAI	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL C	CHAN	IGES	ARC	IPJ	IPJ	KRG	05/09/2023	F									
В	FORMAT	TING	ì	EDM	JIK	-	-	04/24/2023	Е									
Α	EDITORIAL C	CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X	Indicates La	atest R				npletely Revi			New Page		Information Re	moved				
	SHEET				SDC	S&E E	LECTI	RIC SERVIC	E STA	AND	ARDS & GL	JID	ES					

4 OF 6

SERVICE DROPS - OVERHEAD ELECTRIC

INSTALLATION (CONT'D):

- D THE POINT OF SERVICE DROP ATTACHMENT MAY BE SELECTED ON A RESIDENCE SIDE WALL WHICH IS AT RIGHT ANGLES TO THE UTILITY'S POLE LINE, WHERE THE WALL OF THE RESIDENCE FACING AND NEAREST THE UTILITY'S POLE LINE DOES NOT AFFORD SUFFICIENT SERVICE DROP CLEARANCE ABOVE GROUND OR FROM OBSTRUCTIONS. SUCH A LOCATION IS SUBJECT TO APPROVAL BY THE SERVICE PLANNER, AND TO CONFORMANCE WITH PROVISIONS OF THE FOLLOWING EXCEPTIONS:
 - (1) EXCEPTION FOR OBTAINING GROUND CLEARANCE

WHERE THE HEIGHT OF A RESIDENCE WALL FACING AND NEAREST THE UTILITY'S POLE LINE IS INSUFFICIENT TO OBTAIN SERVICE DROP CONDUCTOR CLEARANCE WITHOUT THE INSTALLATION OF A CLEARANCE RISER OR STRUCTURE ON THE FRONT OF THE RESIDENCE, A POINT OF SERVICE DROP ATTACHMENT MAY BE LOCATED UP THE GABLE WALL NOT FARTHER BACK THAN IS NECESSARY TO OBTAIN SERVICE DROP CLEARANCE, BUT IN NO CASE MORE THAN 12 FEET BACK FROM THE WALL FACING THE UTILITY'S POLE LINE NOR FURTHER BACK THAN THE PEAK OF A GABLE ROOF. SEE FIGURE 1 – EXAMPLE 2. THE SERVICE DROP CONDUCTORS MAY NOT PASS OVER THE ROOF (EXCLUDING EAVES) OF THE RESIDENCE SERVED.

2. EXCEPTION FOR CLEARING WINDOWS AND OBSTRUCTIONS

WHERE WINDOWS OR OTHER BUILDING COMPONENTS CONFLICT WITH PROVIDING AN ACCEPTABLE POINT OF SERVICE DROP ATTACHMENT ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE, OR WITHIN 18 INCHES OF THAT POINT, A RISER OR STRUCTURE MAY BE LOCATED ON A RESIDENCE SIDE WALL. THIS LOCATION MAY NOT BE FARTHER BACK THAN IS NECESSARY TO OBTAIN SERVICE DROP CLEARANCES, BUT IN NO CASE MORE THAN 7 FEET BACK FROM THE WALL FACING THE POLE LINE. SERVICE DROP CONDUCTORS MAY NOT PASS OVER THE ROOF (EXCLUDING EAVES) OF THE RESIDENCE SERVED.

IN EITHER EXCEPTION, THE SERVICE DROP ATTACHMENT SHALL BE LOCATED AT A POINT WHICH WILL NOT REQUIRE THE SERVICE DROP TO PASS OVER AN ADJACENT LOT OR A BUILDING SITE ON THE SAME PREMISES.

(E) WHERE THE HEIGHT OF A RESIDENCE WILL NOT AFFORD SUFFICIENT SERVICE DROP CLEARANCE ABOVE GROUND OR FROM OBSTRUCTIONS, A SERVICE DROP SUPPORT RISER OR STRUCTURE SHALL BE INSTALLED ON THE WALL FACING, OR WITHIN 18 INCHES OF THAT POINT, AND NEAREST THE UTILITY'S POLE LINE TO PROVIDE CLEARANCE. SEE FIGURE 1 – EXAMPLES 3 AND 4.

IMPAIRED CLEARANCES

- F. WHEN ANY OF THE SERVICE DROP CLEARANCES REQUIRED BY THE UTILITY, OR THE AHJ, BECOME IMPAIRED BECAUSE OF CHANGES CREATED BY THE TENANT OR OWNER OF THE PREMISES, IT IS INCUMBENT UPON THE CUSTOMER, AT THEIR EXPENSE, TO PROVIDE A MEANS TO CORRECT THE INFRACTION.
- (G) TO OBTAIN PROPER CLEARANCES, THE POINT OF SERVICE DROP ATTACHMENT MAY BE SELECTED NOT MORE THAN 12 FEET BACK FROM WALL FACING UTILITY'S POLE LINE TO AVOID INSTALLATION OF RISER ON FACE OF RESIDENCE.

ATTENTION:

* WHEN THE DISTANCE FROM BUILDING TO AN OBSTRUCTION WILL NOT ACCOMMODATE SAFE USE OF A LADDER FOR ACCESS, BUCKET TRUCK ACCESS IS REQUIRED.

COMMERCIAL – INDUSTRIAL BUILDINGS OR STRUCTURES

- H. THE POINT OF SERVICE DROP ATTACHMENT ON A COMMERCIAL OR INDUSTRIAL BUILDING SHALL NORMALLY BE LOCATED ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE, AND SO LOCATED THAT THE SERVICE HEAD, SERVICE DROP AND THE OPEN WIRES BETWEEN THE SERVICE HEAD AND POINT OF CONNECTION TO THE SERVICE DROP WILL HAVE NOT LESS THAN 16 FEET OF CLEARANCE ABOVE FINISHED GRADE, AND WHENEVER NECESSARY BE LOCATED AT A GREATER HEIGHT TO OBTAIN REQUIRED CLEARANCES. THE 16-FOOT CLEARANCE MAY BE REDUCED FOR INSULATED SERVICES (SSC) TO NOT LESS THAN 10 FEET IN AREAS ACCESSIBLE TO PEDESTRIANS ONLY. (a)
- (J) WHERE THE SERVICE DROP WILL PASS OVER ONLY THE PREMISES SERVED, THE POINT OF SERVICE DROP ATTACHMENT MAY BE ON ANY WALL OF THE BUILDING FACING AND PARALLEL TO THE UTILITY'S POLE LINE. SEE FIGURE 4 EXAMPLE 2.
- WHERE THE BUILDING WALL FACING AND NEAREST THE UTILITY'S POLE LINE IS ON A SHED OR SIMILAR BUILDING PROJECTION, WHICH DOES NOT AFFORD SUFFICIENT SERVICE DROP CLEARANCE WITHOUT THE INSTALLATION OF A SERVICE DROP SUPPORT RISER OR STRUCTURE, AND THERE IS ANOTHER WALL OF ADEQUATE HEIGHT FACING THE UTILITY'S POLE LINE, THE POINT OF SERVICE DROP ATTACHMENT MAY BE LOCATED ON SUCH WALL, PROVIDED APPLICABLE CLEARANCES CAN BE OBTAINED. SEE FIGURE 4 EXAMPLE 3. THIS OPTION DOES NOT APPLY TO A BUILDING OF NORMAL HEIGHT OR CONSTRUCTION HAVING A

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHA	AN	GE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	05/09/2023	F								
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates La	itest R	evision	ı	Con	npletely Revi	sed	New Page		Information Rer	noved				

SHEET 5 OF 6 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

INSTALLATION (CONT'D):

HIGHER SECTION SET BACK FROM THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE, SUCH AS A HIP ROOF. WHEN SERVICE DROP CLEARANCES CANNOT BE MET, A SERVICE DROP SUPPORT RISER OR STRUCTURE SHALL BE PROVIDED ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE TO OBTAIN REQUIRED CLEARANCES. SEE FIGURE 4 – EXAMPLE 4.

- L BUCKET TRUCK ACCESS REQUIRED IF DISTANCE FROM LADDER TO WEATHERHEAD AND POINT OF ATTACHMENT EXCEEDS 24 INCHES OR REQUIRED WORKING SPACE FOR A LADDER IS NOT MET.
- (M) service drop attachment to be located where directed by the utility.
- (N) roof clearance applies to all commercial and industrial buildings and to metal roofs.

BILL OF MATERIALS: NONE

NOTES:

- $(\ { t I}\)$ nearest wall height
- ${
 m (II)}$ SERVICE DROP ATTACHMENT RISER IS REQUIRED.
- $\left(ext{III}
 ight)$ SERVICE DROP ATTACHMENT NOT PERMITTED WHEN SERVICE DROP CROSSES ADJOINING PREMISES.
- (IV) SERVICE DROP ATTACHMENT NOT PERMITTED.
- (V) MAXIMUM LENGTH OF SERVICE DROP OVER ROOF.
- (VI) OVER ROOF AND OVERHANG LIMITED TO 6 FEET OF CONDUCTOR.
- (VII) MAXIMUM EAVE OVERHANG (FOR LADDER ACCESS TO WEATHERHEAD AND POINT OF ATTACHMENT)
- (VIII) LOCATION OVER SHED-TYPE PROJECTIONS NOT RECOMMENDED DUE TO CLEARANCE REQUIREMENTS.
- (IX) LOCATION NOT APPROVED. SERVICE DROP CROSSES ADJOINING PREMISES.

Indicates Latest Revision

- (XI) ANOTHER WALL FACING LINE. SERVICE DROPS PERMITTED ONLY ACROSS PREMISES SERVED.
- (XII) DO NOT PROVIDE CLEARANCE WITHOUT INSTALLATION OF A RISER. OPTIONAL SERVICE DROP ATTACHMENT LOCATION PERMITTED ON HIGHER PART OF BUILDING.
- FOR A WALL WITH INADEQUATE SERVICE DROP CLEARANCE, RISER IS REQUIRED. WHEN NEAREST WALL DOES NOT AFFORD CLEARANCE, SERVICE DROP SUPPORT RISER REQUIRED.

REFERENCE:

(a) SEE SG107.

© 1998 - 2023 San Diego Gas & Electric Compa	ny All rights reserved. Removal of this conv	yright notice without permission is not permitted under law.
9 1990 - 2023 San Diego Gas & Liectific Compa	ny. An ngma reserved, Nemovai or uns copy	yrigint notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	05/09/2023	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 6 OF 6

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page


Information Removed

Completely Revised

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR SERVICE DROP SUPPORTS.

ATTENTION:

- * A SERVICE DROP WILL BE ATTACHED AT ONLY ONE POINT OF SUPPORT ON A BUILDING. AT THIS POINT OF SUPPORT, THE BUILDING SHALL HAVE ADEQUATE STRENGTH TO SAFELY WITHSTAND THE STRESS OF THE SERVICE DROP CONDUCTORS.
- ** WHERE, IN THE OPINION OF SDG&E (UTILITY), A BUILDING DOES NOT AFFORD SUFFICIENT STRENGTH TO SAFELY SUPPORT SERVICE DROP CONDUCTORS, AN UNDERGROUND SERVICE OR A CUSTOMER-OWNED SERVICE AND METER POLE SHOULD BE INSTALLED.
- *** WHERE THE SIZE OF SERVICE ENTRANCE CONDUCTORS INDICATES UNUSUALLY HEAVY SERVICE DROP CONDUCTORS WILL BE REQUIRED, CONTACT THE UTILITY'S NEAREST DESIGN AND PROJECT MANAGEMENT REGIONAL OFFICE. (a)



SEE TABLE 1
© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CI	IAH	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F								
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates La	atest R	evisio	n	Con	npletely Revi	ised	New Page		Information Re	moved				

S	HEE	T
1	OF	5

ICVISION		completely revised		nen rage		Information Removed
SDG&	ΕE	LECTRIC SERVICE STA	AND	DARDS & GL	JID	ES

SDOGE ELECTRIC SERVICE STANDARDS & GOIDES

SG104.1

SERVICE DROP SUPPORTS






FIGURE 2 TYPICAL INSTALLATION SERVICE HEAD IS BELOW POINT OF ATTACHMENT



NON-METALLIC ROOF

EXAMPLE 2 UN-ENCLOSED EAVE OR ROOF OVERHANG



EXAMPLE 3 FASCIA BOARD-ENCLOSED OR **UN-ENCLOSED EAVES**


FIGURE 3 SEE TABLE 1

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


C EDITORIAL CHANGES ARC IPJ IPJ KRG 11/02/2023 F		BY	DSIN	APV	DATE
B FORMATTING EDM JIK - - 04/24/2023 E					
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D					

SHEET 2 OF 5 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP SUPPORTS



EXAMPLE 5 CONCEALED STUDS OR TIMBERS



EXAMPLE 6 WOOD REINFORCING BLOCK

FIGURE 3 (CONT'D) SEE TABLE 1

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C EDITORIAL CHANGES ARC IPJ IPJ KRG 11/02/2023 F		BY	DSIN	APV	DATE
B FORMATTING EDM JIK - - 04/24/2023 E					
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D					

SHEET 3 OF 5

Completely Revised Indicates Latest Revision New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP SUPPORTS

TABLE 1:

	SERVICE DROP SUPPORT ITEM DESCRIPTIONS						
ITEM	DESCRIPTION						
$\langle 1 \rangle$	HOLES, 5/16" DIA., FOR 1/4" X 3" LAG SCREWS						
2 HOLES, 5/16" DIA., FOR 1/4" DIAMETER GALV. BOLTS							
3	SERVICE HEAD, PREFERRED POSITION						
4	BARGEBOARD, 2" NOMINAL THICKNESS						
(5)	FASCIA BOARD, 2" NOMINAL THICKNESS						
$\langle 6 \rangle$	INSULATOR, SERVICE, SCREWED INTO STUDS						
$\langle 7 \rangle$	SCREWS, LAG, 3/8" X 5", MIN. 2						
\'/	WASHER, LARGE, ROUND FLAT						
8 SERVICE HEAD, ALTERNATE POSITION							
9	BOARD, PRESSURE TREATED, 2" X 4"						

INSTALLATION:

WOOD BUILDINGS:

- A. THE UTILITY WILL FURNISH, AT THE CONTRACTOR'S REQUEST, A SERVICE BRACKET OR INSULATORS TO SUPPORT SERVICE DROP CONDUCTORS ON A WOOD FRAME OR STUCCO BUILDING, PROVIDED THE WOOD BUILDING MEMBERS HAVE NOT LESS THAN A 2-INCH NOMINAL THICKNESS AND ARE PROPERLY LOCATED WITH RESPECT TO A POINT OF SERVICE DROP ATTACHMENT ACCEPTABLE TO THE UTILITY. THE FOLLOWING WOOD STRUCTURAL MEMBERS ARE APPROVED FOR SUPPORTING SERVICE DROP CONDUCTORS:
 - 1. AN UN-ENCLOSED, NON-METALLIC ROOF OVERHANG, EAVE OR RAFTER END PROJECTING OUTSIDE AN EXTERIOR WALL.
 - 2. A FASCIA, BARGEBOARD, OR AN UN-ENCLOSED EAVE PROJECTING OUTSIDE AN EXTERIOR WALL.

WOOD REINFORCING BLOCK:

- B. WHERE THE WOOD ROOF OR EAVE OVERHANG MEMBERS AT THE POINT OF SERVICE DROP SUPPORT HAVE LESS THAN A 2-INCH NOMINAL THICKNESS, OR ARE OTHERWISE CONSIDERED TO BE INADEQUATE TO WITHSTAND THE PULL OF THE SERVICE DROP CONDUCTORS, A 2" X 4" MINIMUM WOOD REINFORCING BLOCK OF SUFFICIENT LENGTH SHALL BE LAGGED OR BOLTED TO THE ROOF RAFTERS TO PROVIDE A SAFE ANCHORAGE FOR INSTALLATION OF SERVICE INSULATORS BY THE UTILITY.
- C. SERVICE INSULATORS OR WOOD REINFORCING BLOCKS FOR THE SUPPORT OF SERVICE INSULATORS SHALL NOT BE INSTALLED IN ANY ROOF SECTION INSIDE THE OUTER FACE OF AN EXTERIOR WALL OR ROOF SURFACE OF AN ENCLOSED CORNICE OR WITHIN A SOFFIT. SEE FIGURE 3 EXAMPLE 6.

BUILDINGS OTHER THAN WOOD:

D. THE CONTRACTOR SHALL INSTALL BOLTS, SERVICE INSULATORS OR OTHER SUITABLE MEANS OF SERVICE DROP CONDUCTOR SUPPORT ON BUILDINGS CONSTRUCTED OF TILE, BRICK, CONCRETE, ADOBE, STONE, METAL OR SIMILAR MATERIAL. THE UTILITY WILL FURNISH, AT THE CONTRACTOR'S REQUEST, BOLTS OR INSULATORS NECESSARY TO SUPPORT THE SERVICE DROP CONDUCTORS.

CLEARANCE RISERS OR STRUCTURES:

E. WHERE A SERVICE DROP RISER OR STRUCTURE IS NECESSARY ON A BUILDING TO OBTAIN SERVICE DROP CLEARANCE, A GALVANIZED RIGID CONDUIT RISER, INTERMEDIATE METALLIC CONDUIT, OR UN-SPLICED TIMBER SHALL BE SECURELY LAGGED OR BOLTED TO THE BUILDING TO SUPPORT SERVICE INSULATORS FURNISHED AND INSTALLED BY THE UTILITY. GALVANIZED CONDUIT RISERS ARE PREFERRED. (b)

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 5 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP SUPPORTS

- (F) WELD OR BOLT KNEE BRACES.
- (G) service head to be located within 24 inches from the point of attachment. Drip loop not to exceed 3 feet.
- (H) install 2" X 4" pressure treated board lagged to rafters. Nailing is not acceptable.
- (J) WOOD BLOCKS FOR SERVICE INSULATOR SUPPORT, OR SERVICE INSULATORS, SHALL NOT BE INSTALLED IN ANY ROOF SECTION INSIDE THE OUTER FACE OF AN EXTERIOR WALL OR ROOF SURFACE OF AN ENCLOSED CORNICE OR WITHIN A SOFFIT.
- K. SERVICE DROP ATTACHMENT SHOULD NORMALLY BE LOCATED ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE.
- L. IT IS RECOMMENDED THAT SERVICE HEADS BE INSTALLED 1-FOOT ABOVE THE POINT OF SERVICE DROP ATTACHMENT TO PREVENT SIPHONING OF MOISTURE INTO THE SERVICE CONDUIT. WHERE SERVICE HEADS ARE INSTALLED BELOW THE POINT OF SERVICE DROP ATTACHMENT, DRIP LOOPS SHALL BE FORMED IN OPEN SERVICE ENTRANCE CONDUCTORS. TO PREVENT WATER FROM SIPHONING INTO THE SERVICE RACEWAY AND EQUIPMENT, AN INVERTED "V" NOTCH SHOULD BE CUT THROUGH THE INSULATION TO THE CURRENT-CARRYING STRAND(S) AT THE LOWEST POINT ON THE BOTTOM SIDE OF EACH SERVICE ENTRANCE DRIP LOOP.
- (M) insulators will be provided by the utility and installed by the contractor or customer.
- N. COMMUNICATION DROPS, ATTACHMENT SUPPORTS AND ANTENNAE ARE TO HAVE A MINIMUM 12-INCH RADIAL CLEARANCE FROM THE SDG&E SERVICE DROP AND SERVICE DROP SUPPORT.

BILL OF MATERIALS: NONE

NOTES:

MAINTENANCE RESPONSIBILITY AND LIABILITY:

- I. ANY SERVICE DROP CLEARANCE RISER OR STRUCTURE INSTALLED SHALL BE PROPERLY MAINTAINED AT THE EXPENSE OF THE PROPERTY OWNER OR CUSTOMER.
- II. THE UTILITY WILL NOT ASSUME LIABILITY FOR ANY DAMAGE CAUSED BY:
 - a. ROOF LEAKAGE AROUND A RISER OR ANY OTHER TYPE OF SERVICE DROP SUPPORT.
 - b. MECHANICAL FAILURE OF A RISER OR ANY OTHER TYPE OF SERVICE DROP SUPPORT.
 - c. FAILURE OF ANY PART OF THE BUILDING AT THE POINT WHERE A RISER OR ANY OTHER TYPES OF SERVICE DROP SUPPORT IS ATTACHED.
- m (III) all angle iron is to be 1 1/4" x 1 1/4" x 1/8".
- $\overline{ ext{(IV)}}$ length of brace varies with height of rack and pitch of roof.
- V. ANGLE IRON RACK FOR ATTACHMENT OF UTILITY SERVICE DROP PROVIDED AND INSTALLED BY CUSTOMER.
- VI. STEEL CLEARANCE STRUCTURES SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION.

REFERENCE:

- (a) SEE SG021.
- (b) FOR METHODS OF ATTACHING SERVICE DROPS TO GALVANIZED CONDUIT AND SOLID WOOD SERVICE DROP SUPPORT RISERS, SEE SG105 SG106.
- c. FOR SERVICE DROP CLEARANCES, SEE SG107.
- d. SEE OH229.

	© 1998 - 2023 San Diego Gas & El	ectric (Compa	ny. All	rights	eserved. Rer	moval	of th	nis copyright noti	ice	without permission	is not	permit	ted un	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CH	A۱	IGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F									
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е									
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
	X Indicates La	atest R	evision	n	Con	npletely Revi	ised		New Page		Information Rea	noved				

SHEET 5 OF 5 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR OVERHEAD SERVICE ATTACHMENT FOR METALLIC CONDUIT RISERS.




FIGURE 1

GALVANIZED RIGID CONDUIT RISER OR INTERMEDIATE METALLIC CONDUIT FOR OVERHEAD SERVICE ATTACHMENT SEE TABLES 1, 2 AND 3

TABLE 1

	STANCE MEASURED FROM VY DUTY PIPE STRAPS
CONDUIT SIZE (IN)	Z (IN)
1 1/4	12
1 1/2	15
2	22
2 1/2	30

TABLE 2

	F CENTERLINE OF LOAD E ROOF
CONDUIT SIZE (IN)	Y (IN)
1 1/4	30
1 1/2	40
2	60
2 1/2	96

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 2 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG105.1

OVERHEAD SERVICE ATTACHMENT FOR METALLIC CONDUIT RISERS

TABLE 3

RISER I	TEM DESCRIPTIONS
ITEM	DESCRIPTION
1	RAFTER
2	STUD
3	JOIST, CEILING

INSTALLATION:

- A. SDG&E (UTILITY) WILL NOT BE RESPONSIBLE FOR ANY DAMAGE TO THE BUILDING CAUSED BY RAIN OR STRUCTURAL FAILURE.
- B. THESE METHODS ARE SUGGESTED TO OBTAIN THE REQUIRED GROUND AND ROOF CLEARANCES AS REQUIRED BY THE GOVERNMENTAL AUTHORITIES HAVING JURISDICTION (AHJ). WHEN THIS METHOD IS USED, IT WILL BE ACCEPTABLE TO THE UTILITY PROVIDED THE DIMENSIONS AND CONSTRUCTION DETAILS ARE IN COMPLIANCE WITH THIS STANDARD.
- C. NO COUPLINGS WILL BE PERMITTED BETWEEN, OR ABOVE, THE TOP TWO PIPE STRAP SUPPORTS FOR CONDUIT SIZES 1 1/4 TO 2 INCHES INCLUSIVE. IF A COUPLING IS NECESSARY IN THE 2 1/2-INCH SIZE CONDUIT TO OBTAIN THE MAXIMUM POINT OF ATTACHMENT OF 8 FEET ABOVE THE TOP SUPPORT OR ROOFLINE, THE COUPLING SHALL BE INSTALLED AT THE UPPER END NEAR THE WEATHERHEAD.
- D. SERVICE DROP ATTACHMENT SHALL NORMALLY BE LOCATED ON THE WALL FACING AND NEAREST SDG&E'S POLE LINE. (e)
- E HEAVY DUTY TWO-HOLE PIPE STRAPS. UPPER STRAP MUST BE DIRECTLY BELOW SOFFIT (SEE FIGURE 1-EXAMPLE 2) OR SCREWED WITH 3/8" X 3" LAG SCREWS INTO PLATE (SEE FIGURE 1-EXAMPLE 3). 1/4-INCH TOGGLE BOLTS MAY BE USED IN LIEU OF LAG SCREWS. ZANAC NAIL HEADS 1/4" X 1 7/8" (MUSHROOM) MAY BE USED IN PLACE OF LAG SCREWS WHEN ATTACHING TO CINDER BLOCK OR CONCRETE WALLS.
- F HEAVY DUTY ONE-HOLE PIPE STRAPS ARE ACCEPTABLE IF USED WITH 3/8" X 3" LAG CREW (MIN. SIZE) INTO WALL STUD OR PLATE. ZANAC NAIL HEADS 1/4" X 1 7/8" (MUSHROOM) MAY BE USED IN PLACE OF LAG SCREWS WHEN ATTACHING TO CINDER BLOCK OR CONCRETE WALLS.
- (G) enclosed risers must be securely supported at the plate and immediately above the meter socket enclosure.
- (H) THE UTILITY WILL PROVIDE THE CLAMP AND INSULATOR FOR ATTACHMENT OF THE SERVICE DROP TO THE CUSTOMER'S RISER.
- (J) ONLY THE UTILITY'S SERVICE DROP CONDUCTORS SHALL BE PERMITTED TO BE ATTACHED TO THE SERVICE RISER. THIS IS A UTILITY AND CALIFORNIA ELECTRICAL CODE REQUIREMENT.
- (K) BUCKET TRUCK ACCESS REQUIRED IF DISTANCE FROM LADDER TO WEATHERHEAD AND POINT OF ATTACHMENT EXCEEDS 24 INCHES.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

- a. FOR RECESSED RESIDENTIAL METER INSTALLATION, SEE SG507.
- b. FOR SINGLE RESIDENTIAL METER INSTALLATION ENCLOSED IN A METER CABINET, SEE SG508.
- c. FOR COMMERCIAL OR RESIDENTIAL MULTI-METER ENCLOSED IN A CABINET, SEE SG509.
- d. FOR COMMERCIAL OR RESIDENTIAL MULTI-METER LOCATED IN A METER ROOM, SEE SG506.
- (e) for exceptions to obtain service drop clearances on residential buildings or structures, see SG103.
- f. SEE OH641.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						


SHEET 2 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD SERVICE ATTACHMENT FOR METALLIC CONDUIT RISERS

SG105.2





				0 ./ = ./ = 0	_							
EDITORIAL C	CHANGES	- LSM	IPJ	TPM 11/01/20	7 D							
	X Indicates La	atest Revisio	n	Completely R	vised	New Page		Information Re	moved			
CHEET		SD	G&E E	LECTRIC SERV	ICE STA	ANDARDS & GL	UIDES	S				
SHEET 2 OF 4		(RHEAD SER FOR SOLID			NT			S	G10	6.2

TABLE 1:

IABLE	<u> </u>	
	OVERHEAD SERVICE ATTACHMENT ITEM DESCRIPT	TIONS
ITEM	DESCRIPTION	
1	BOLT AND WASHER, 1/2", (QTY 2)	
2	RISER, SOLID WOOD, 4" X 4" (PRESSURE TREATED)	
3	RISER, SOLID WOOD, 4" X 6" (PRESSURE TREATED)	
4	RISER, SOLID WOOD, 6" X 6" (PRESSURE TREATED)	
5	BOLTS, 1/2" DIA. OR LAG SCREWS	
6	SERVICE CAP	
7	DICED COLID WOOD DESCRIPE TREATED	4" X 4"
7	RISER, SOLID WOOD, PRESSURE TREATED	4" X 6"
		4" X 4"
$\langle 8 \rangle$	RISER, SOLID WOOD, PRESSURE TREATED	4" X 6"
		6" X 6"
9	SERVICE KNOB	
(10)	E.M.T., I.M.T. OR SCH 40 PVC	
(11)	FLASHING	
(12)	PLATES	
(13)	STRAPS, ON PLATES	
(14)	SOCKET BOX, METER, FLUSH TYPE	
(15)	METER	
(16)	SCREW, LAG, 1/4" X 4"	
(17)	RISER, WOOD	
(18)	BOLT, MACH., 1/2" DIA.	
19	2" X 4"	
$\overline{\langle 20 \rangle}$	SOCKET BOX, METER, SURFACE MOUNTED TYPE	

INSTALLATION:

- (A) BOLT HEAD TO BE RECESSED IN 2 X 4. BOLT 2 X 4 TO WOOD RISER BEFORE INSTALLING.
- (<code>B</code>) SERVICE DROP ATTACHMENT SHALL NORMALLY BE LOCATED ON THE WALL FACING AND NEAREST THE UTILITY'S POLE LINE. (<code>c</code>)
- C. WOOD RISERS SHALL NOT BE SPLICED OR OF LAMINATED CONSTRUCTION, 2 X 4'S, 2 X 6'S, ETC. NAILED OR BOLTED TOGETHER RISERS ARE NOT ACCEPTABLE.
- D. BUCKET TRUCK ACCESS IS REQUIRED IF THE DISTANCE FROM LADDER TO WEATHERHEAD AND POINT OF ATTACHMENT EXCEEDS 24 INCHES.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 4

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD SERVICE ATTACHMENT FOR SOLID WOOD RISERS

SG106.3

- E. ONLY THE UTILITY'S SERVICE DROP CONDUCTORS SHALL BE PERMITTED TO BE ATTACHED TO THE SOLID WOOD RISER STRUCTURE. THIS IS A UTILITY AND CALIFORNIA ELECTRICAL CODE REQUIREMENT.
- (F) SERVICE KNOBS TO BE INSTALLED ON 4-INCH FACE OF TIMBER ONLY.
- G SECURE RISER TO STUD.

BILL OF MATERIALS: NONE

NOTES:

- (I) SDG&E (UTILITY) WILL NOT BE RESPONSIBLE FOR ANY DAMAGE TO THE BUILDING CAUSED BY RAIN OR STRUCTURAL FAILURE.
- (II) WOOD RISER TO EXTEND TO TOP OF FOUNDATION.
- (III) FURNISHED AND INSTALLED BY SDG&E

REFERENCE:

- a. SEE OH641.
- b. FOR SERVICE DROP CLEARANCES, SEE SG107.
- (c) for exceptions to obtain service drop clearances on residential buildings or structures, see SG103.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD SERVICE ATTACHMENT FOR SOLID WOOD RISERS

SG106.4

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR 0-600V SERVICE DROP CONDUCTOR CLEARANCES.

ATTENTION:

- * THE VERTICAL, HORIZONTAL AND RADIAL SERVICE DROP CONDUCTOR (INCLUDING THE DRIP LOOP) CLEARANCES TABULATED AND ILLUSTRATED THROUGHOUT THIS MANUAL ARE MINIMUM REQUIREMENTS OF STATE, COUNTY OR MUNICIPAL CODES, LAWS AND ORDINANCES. DEVIATION FROM THESE MINIMUM CLEARANCE REQUIREMENTS CANNOT BE GRANTED BY SDG&E (UTILITY).
- ** THE UTILITY PRIMARILY USES INSULATED ABRASION-RESISTANT SELF-SUPPORTING CABLE (SSC) FOR SERVICE DROP CONDUCTORS. HOWEVER, THE UTILITY USED TO INSTALL OPEN-WIRE WEATHERPROOF (WP) UNINSULATED SERVICE DROP CONDUCTORS. THE OLDER WP SERVICE DROPS STILL EXIST, THOUGH THEY ARE NOT COMMON.
- *** THE USE OF OPEN-WIRE SERVICE DROP CONDUCTORS IN COMMERCIAL/INDUSTRIAL APPLICATIONS MAY OCCUR TODAY WHEN THE ESTIMATED LOAD REQUIRES A HIGHER AMPACITY RATING FOR THE SERVICE DROP CONDUCTORS THAT ARE ONLY AVAILABLE IN OPEN-WIRE CONDUCTOR SIZES. THE ABBREVIATIONS SSC AND WP ARE COMMONLY USED THROUGHOUT THIS SECTION.




FIGURE 1 CLEARANCE ABOVE RESIDENTIAL, COMMERCIAL, OR INDUSTRIAL BUILDINGS ON PREMISES SERVED OTHER THAN THE BUILDING SERVED


FIGURE 2
REDUCED 0-300V WP SERVICE DROP
CLEARANCE ABOVE A RESIDENTIAL
ROOF OR EAVE ON THE BUILDING
SERVED

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice w	


	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE UPDATE	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 12 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP CONDUCTOR CLEARANCES 0-600V



EXAMPLE 1 EXAMPLE 2



EXAMPLE 3 (II)

FIGURE 3 EXCEPTIONS FOR REDUCED CLEARANCE ABOVE (G2)(XIV) COMMERCIAL AND INDUSTRIAL BUILDINGS

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DSN APV DSN APV **DATE** DR BY **CHANGE** DR BY **CHANGE** DATE **REV** С FIGURE UPDATE **EDM IWA** JTM KRG 01/02/2025 В Ε **FORMATTING EDM** JIK 04/24/2023

0-600V

TPM 11/01/2017

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET 2 OF 12 SERVICE DROP CONDUCTOR CLEARANCES

IPJ

LSM

Α

EDITORIAL CHANGES

SG107.2

1'-0" MIN.




FIGURE 3 (CONT'D)
EXCEPTIONS FOR REDUCED CLEARANCE ABOVE G2 XIV
COMMERCIAL AND INDUSTRIAL BUILDINGS

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

EXAMPLE 5

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE UPDATE	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						
_				_			_						

SHEET 3 OF 12 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP CONDUCTOR CLEARANCES 0-600V




FIGURE 4

SERVICE DROP CONDUCTOR CLEARANCES, 0-600V, FROM DOORS, EXITS, WINDOWS, FIRE ESCAPES, BALCONIES, ETC. II V VII SEE TABLE 1

TABLE 1

VERTICAL, HORIZONTAL, AND RADIAL SERVICE DROP CONDUCTOR (INCLUDING THE DRIP LOOP) CLEARANCES												
CONDITION	MINIMUM	CLEARANCE										
CONDITION	Z (FT)	Y (FT)										
VERTICALLY ABOVE WALKABLE SURFACES OF FIRE ESCAPES, BALCONIES, STAIRWAYS AND WALKWAYS	8											
HORIZONTALLY AND RADIALLY FROM FIRE ESCAPES, EXITS, OPENABLE WINDOWS, DOORS, AND OTHER POINTS AT WHICH HUMAN CONTACT MIGHT BE EXPECTED		3										

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV DATE** DSN APV **CHANGE** DR BY DSN APV **CHANGE** DR BY DATE **REV** С FIGURE UPDATE **EDM IWA** JTM KRG 01/02/2025 В JIK Ε **FORMATTING EDM** 04/24/2023 TPM 11/01/2017 Α **EDITORIAL CHANGES** LSM IPJ

SHEET 4 OF 12 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP CONDUCTOR CLEARANCES 0-600V




FIGURE 5

RESIDENTIAL PREMISES


MINIMUM CLEARANCES REQUIRED FOR SERVICE DROP CONDUCTORS OVER THOROUGHFARES, FROM BUILDINGS, AT POINT OF ATTACHMENT TO BUILDING, AND CROSS REFERENCE PAGES

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE UPDATE	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 5 OF 12 Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SERVICE DROP CONDUCTOR CLEARANCES 0-600V




A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D

SHEET
6 OF 12

| SERVICE DROP CONDUCTOR CLEARANCES 0-600V | SG107.6



EXAMPLE 1 BUILDINGS, BRIDGES, AND OTHER STRUCTURES



EXAMPLE 2 UNDER OR THRU BRIDGES, VIADUCTS OR SIMILAR STRUCTURES

FIGURE 7

HORIZONTAL AND VERTICAL CLEARANCES OF SUPPLY AND SERVICE DROP (g) (h) CONDUCTORS FROM BUILDINGS, BRIDGES, AND OTHER STRUCTURES SEE TABLE 2

TABLE 2

	APPURTENANCE LIST
ITEM	DESCRIPTION
1	WALKABLE SURFACE
2	NEAREST PROJECTING SURFACE (R)
(3)	CLEARANCE ZONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE UPDATE	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						
_				_			_						

SHEET 7 OF 12 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP CONDUCTOR CLEARANCES 0-600V

INSTALLATION:

- A. WEATHER AND TIME ADVERSELY AFFECT SERVICE DROP CONDUCTORS AND THE SERVICE SUPPORT, RESULTING IN ULTIMATE SERVICE DROP CONDUCTOR SAG GREATER THAN THE INITIAL SAG OBTAINED AT THE TIME OF INSTALLATION. ACCORDINGLY, WHEN SELECTING A POINT OF ATTACHMENT METHOD PROVIDE A HEIGHT THAT WILL PERMIT THE SERVICE DROP CONDUCTORS TO BE MAINTAINED IN COMPLIANCE WITH APPLICABLE CLEARANCE REQUIREMENTS FOR THE ULTIMATE SAG.
- B. A SERVICE DROP SUPPORT RISER OR RACK SHALL NOT BE LOCATED MORE THAN 18 INCHES BACK FROM THE FRONT FACE OF THE BUILDING WALL FACING THE UTILITY'S POLE LINE, EXCEPT AS PERMITTED FOR RESIDENTIAL BUILDINGS.
- C. SERVICE SUPPORT INSULATORS OR BRACKET SHALL NOT BE INSTALLED ON THE TOP OF ANY CORNICE, APPENDAGE, EAVE, ROOF OR PARAPET WALL OF A BUILDING, EXCEPT AS ALLOWED ON SG104. (d)
- D. WHERE NON-INSULATED (WP) OPEN WIRE SERVICE DROP CONDUCTORS APPROACH A BUILDING WALL AT ANY ANGLE OF LESS THAN 60 DEGREES, THE SPACING OF THE INSULATORS IN HORIZONTAL CONFIGURATION AT THE POINT OF ATTACHMENT SHALL BE INCREASED TO PROVIDE AT LEAST 8 INCHES CONDUCTOR SEPARATION. VERTICAL CONFIGURATION IS PREFERABLE WHERE THE ANGLE BETWEEN THE SERVICE DROP AND THE WALL IS LESS THAN 60 DEGREES AND IS ACCEPTABLE FOR ANY ANGLE.
- E. SERVICE DROPS SHOULD BE ARRANGED SO AS NOT TO HINDER OR ENDANGER WORKERS AND FIREFIGHTERS WHILE PERFORMING THEIR DUTIES.
- (F) CLEARANCES ABOVE GROUND, THOROUGHFARES, DRIVEWAYS, AND PUBLIC/PRIVATE PROPERTY:

VERTICAL CLEARANCES ABOVE GROUND FOR SERVICE DROP CONDUCTORS CROSSING OVER PUBLIC OR PRIVATE THOROUGHFARES, DRIVEWAYS, AND PROPERTIES SHALL BE NOT LESS THAN THOSE SPECIFIED IN TABLE 3. THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) MAY IN SOME INSTANCES REQUIRE GREATER CLEARANCES THAN THOSE SHOWN. (i)

TABLE 3

VERTICAL CLEARANCES ABOVE GROUND FOR SERVICE DROP CONDUCTORS	
CONDITION	MINIMUM VERTICAL CLEARANCE (FT)
CROSSING RAILROAD TRACKS	25
CROSSING PUBLIC THOROUGHFARES (PUBLIC OR PRIVATELY OWNED ROADWAYS MAINTAINED BY A PUBLIC AGENCY, I.E. COUNTY SERVICE AREA)	18
EXCEPTION: THIS CLEARANCE MAY BE REDUCED FROM 18 FEET AT A POSITION NOT MORE THAN 12 FEET HORIZONTALLY FROM THE CURB LINE TO A CLEARANCE AT THE CURB LINE OF NOT LESS THAN (WHERE NO CURB EXISTS, THE OUTER LIMITS OF POSSIBLE VEHICULAR MOVEMENT SHALL BE USED IN LIEU OF A CURB LINE)	16
CROSSING PRIVATE DRIVEWAYS, LANES, OR OTHER PRIVATE PROPERTY AREAS ACCESSIBLE TO VEHICLES ON COMMERCIAL OR INDUSTRIAL PREMISES (INCLUDES PRIVATELY-OWNED ROADWAYS NOT MAINTAINED BY A PUBLIC AGENCY)	16
CROSSING PREMISES ACCESSIBLE TO AGRICULTURAL EQUIPMENT	15
CROSSING PRIVATE DRIVEWAYS, LANES, OR OTHER AREAS ACCESSIBLE TO VEHICLES ON RESIDENTIAL PREMISES	12
EXCEPTION: THIS CLEARANCE MAY BE REDUCED FOR INSULATED SERVICES (SSC) TO NOT LESS THAN	10
CROSSING AREAS ON RESIDENTIAL, COMMERCIAL OR INDUSTRIAL PREMISES THAT ARE ACCESSIBLE ONLY TO PEDESTRIANS	12
EXCEPTION: THIS CLEARANCE MAY BE REDUCED FOR INSULATED SERVICES (SSC) TO NOT LESS THAN	10
CROSSING OVER OR IN PROXIMITY TO SWIMMING POOLS AND/OR RELATED DIVING BOARDS, DIVING PLATFORMS, SLIDES, ETC.	a

C FIGURE UPDATE EDM IWA JTM KRG 01/02/2025 F B FORMATTING EDM JIK - - 04/24/2023 E - - - 04/24/2023 E - <th></th> <th colspan="13">© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.</th>		© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
B FORMATTING EDM JIK - - 04/24/2023 E - - - 04/24/2023 E - - - LSM IPJ TPM 11/01/2017 D -	REV	CHANG	E		DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed	O	FIGURE UPD	Έ	EDM	IWA	JTM	KRG	01/02/2025	F							
X Indicates Latest Revision Completely Revised New Page Information Removed	В	FORMATTI	i	EDM	JIK	-	-	04/24/2023	Е							
X	Α	EDITORIAL CH	GES	-	LSM	IPJ	TPM	11/01/2017	D							
CDC0 F FLECTDIC CEDVICE CTANDADDC 0 CLIDEC)	X	Indicates La	atest Revision Completely Revised New Page Information Removed								d			
SHEET SUGAE ELECTRIC SERVICE STANDARDS & GUIDES		SHFFT	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES													

SHEET 8 OF 12

SERVICE DROP CONDUCTOR CLEARANCES 0-600V

(G) CLEARANCES OVER BUILDINGS AND STRUCTURES:

0–600V SERVICE DROP CONDUCTORS SHALL BE MAINTAINED AT A VERTICAL CLEARANCE OF NOT LESS THAN 8 FEET IF WP, OR 2 FEET IF SSC, ABOVE ANY PORTION OF A METALLIC OR NON-METALLIC RESIDENTIAL, COMMERCIAL OR INDUSTRIAL BUILDING OR STRUCTURE, INCLUDING ANY OTHER BUILDING OR STRUCTURE ON THE PREMISES EXCEPT THAT 0–300V SERVICE DROP CONDUCTORS MAY BE REDUCED IN ACCORDANCE WITH THE FOLLOWING:

(1)EXCEPTION FOR WP REDUCED CLEARANCE ABOVE RESIDENTIAL BUILDING SERVED (SEE TABLE 6):

0–300V WP SERVICE DROP CONDUCTORS MAY BE LESS THAN 8 FEET, BUT SHALL BE MAINTAINED AT A CLEARANCE OF NOT LESS THAN 12 INCHES ABOVE A METALLIC OR NON-METALLIC RESIDENTIAL ROOF OR EAVE OF THE BUILDING SERVED, PROVIDED:

- THE SERVICE DROP CONDUCTORS ARE SUPPORTED ON A RISER OR RACK LOCATED NOT MORE THAN 18 INCHES BACK FROM THE WALL FACING THE UTILITY'S POLE LINE, AND
- THE POINT OF SERVICE SUPPORT IS LOCATED NOT MORE THAN 4 FEET BACK FROM THE OUTER EDGE OF THE ROOF EAVES EXTENDING BEYOND THE WALL FACING THE UTILITY'S POLE LINE.

(2) EXCEPTION FOR REDUCED CLEARANCE ABOVE COMMERCIAL AND INDUSTRIAL BUILDINGS:

SERVICE DROP CONDUCTORS MAY BE LESS THAN 8 FEET, BUT NOT LESS THAN 1 FOOT ABOVE A METALLIC OR NON-METALLIC ROOF, EAVE, PARAPET WALL, CORNICE, OR DECORATIVE APPENDAGE OF THE BUILDING SERVED PROVIDED:

- ANY CORNICE OR DECORATIVE APPENDAGE DOES NOT EXTEND MORE THAN 1 FOOT FROM THE FRONT FACE OF THE BUILDING WALL FACING THE UTILITY'S POLE LINE, AND
- THE POINT OF ATTACHMENT OF THE SERVICE DROP IS NOT MORE THAN 18 INCHES BACK FROM THE FRONT FACE OF THE BUILDING WALL FACING THE UTILITY'S POLE LINE, AND
- THE SERVICE DROP CONDUCTORS ARE INSULATED (SSC) FOR THE VOLTAGE BEING SUPPLIED.

H. CLEARANCES FROM OTHER CONDUCTORS:

THE VERTICAL CLEARANCE OF SERVICE DROP CONDUCTORS FROM OTHER CONDUCTORS AT CROSSINGS AND RADIALLY WHERE APPROACHING CROSSINGS SHALL NOT BE LESS THAN THE MINIMUM CLEARANCES SPECIFIED:

TABLE 4

VERTICAL CLEARANCES OF SERVICE DROP CONDUCTORS FROM OTHER CONDUCTORS										
CONDITION	MINIMUM VERTICAL CLEARANCE (FT)									
BELOW TELEPHONE CABLE SUPPORTED ON A MESSENGER	4									
BELOW OPEN-WIRE TELEPHONE AND FIRE ALARM	2									
ABOVE TELEPHONE CABLE, OPEN-WIRE TELEPHONE AND FIRE ALARM CONDUCTORS	2									
RADIAL FROM TELEPHONE SERVICE DROPS	2									
EXCEPT WHERE WITHIN 15' OF THE POINT OF ATTACHMENT ON A BUILDING THIS CLEARANCE MAY BE REDUCED TO	1									
FROM OTHER ELECTRIC SERVICE DROPS	2									

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under													ler law.		
REV	CHAN	CHANGE			BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE U	PDAT	ΓΕ	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMAT	ì	EDM	JIK	-	-	04/24/2023	Е							
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D						
X Indicates Latest Revision Completely Revised New Page Information Rem									noved						
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															

SHEET 9 OF 12

SERVICE DROP CONDUCTOR CLEARANCES 0-600V

J. CLEARANCES FROM SIGNS:

THE VERTICAL AND HORIZONTAL SERVICE DROP CONDUCTOR CLEARANCE FROM SIGNS, WHETHER MOUNTED ON A BUILDING, ISOLATED STRUCTURES, OR OTHERWISE CONSTRUCTED, SHALL NOT BE LESS THAN THE MINIMUM CLEARANCES SPECIFIED:

TABLE 5

CLEARANCES OF SERVICE DROP CONDUCTORS FROM SIGNS										
CONDITION	MINIMUM CLEARANCE (IV) (FT)									
VERTICAL CLEARANCE ABOVE SIGNS UPON WHICH A PERSON CAN WALK	8									
VERTICAL CLEARANCE ABOVE SIGNS UPON WHICH A PERSON CANNOT WALK	2									
VERTICAL CLEARANCE UNDER SIGNS WHICH ARE ILLUMINATED	2									
VERTICAL CLEARANCE UNDER SIGNS WHICH ARE NON-ILLUMINATED	1									
HORIZONTAL CLEARANCE FROM SIGNS WHICH ARE ILLUMINATED	3									
HORIZONTAL CLEARANCE FROM SIGNS WHICH ARE NON-ILLUMINATED	1									

(K) CLEARANCES FROM BUILDINGS AND STRUCTURES, RESIDENTIAL, COMMERCIAL/INDUSTRIAL PREMISES:

TARIF 6

G.O. 95 TABLE 10: MINIMUM ALLOWABLE CLEARANCE OF SERVICE DROPS OF 0-750V FROM BUILDINGS (G1) (VIII)											
	MINIMUM CLEARANCE FROM BUILDINGS (FT)										
	WEATHER RESISTANT COVERED CONDUCTORS 0-750V	INSULATED CONDUCTORS (RULE 20.8-G) 0-750V									
VERTICAL CLEARANCE ABOVE:											
1) ALL PORTIONS OF BUILDINGS INCLUDING METALLIC OR NON-METALLIC CORNICE, DECORATIVE APPENDAGE, EAVES, ROOF OR PARAPET WALL OF THE BUILDING SERVED.		(K1)(K2)									
2) METALLIC OR NON-METALLIC NON-WALKABLE OVERHANG, PATIO COVER, OR OTHER STRUCTURE.	8	(12)(12)									
3) OTHER BUILDINGS ON THE SAME PREMISES.		2 (L)									
4) BUILDINGS ON OTHER PREMISES.		(K3) (M)									
HORIZONTAL AND RADIAL CLEARANCES:											
1) FROM FIRE ESCAPES, EXITS, WINDOWS AND DOORS.	3	3									

- $(\,1\,)$ no limit is specified but the greatest practicable clearance should be obtained. SDG&E minimum requirement IS 1 FOOT.
- $(\,2\,)$ the point of attachment of the service drop for industrial and commercial premises is not to be more than 18 INCHES BACK OF THE FRONT FACE OF THE BUILDING WALL FACING THE POLE LINE FROM WHICH THE SERVICE DROP ORIGINATES.

© 1998 - 2025 San Diego Gas & Electric Company.		


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE UPDATE	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 10 OF 12 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE DROP CONDUCTOR CLEARANCES 0-600V

- (K) CLEARANCES FROM BUILDINGS AND STRUCTURES, RESIDENTIAL, COMMERCIAL/INDUSTRIAL PREMISES (CONT'D):
 - 3 REDUCE TO 2 FEET FOR NON-METALLIC ROOFS, MORE THAN 3/8 PITCH (APPROXIMATELY 37 DEGREES FROM HORIZONTAL).

 RUN=12"



- L THE AHJ MAY ENFORCE THE MORE RESTRICTIVE CALIFORNIA ELECTRICAL CODE REQUIREMENT OF 8 FEET MINIMUM CLEARANCE, OR 3 FEET MINIMUM CLEARANCE WHEN THE VOLTAGE BETWEEN CONDUCTORS DOES NOT EXCEED 300V AND THE ROOF HAS A SLOPE OF NOT LESS THAN 4 INCHES IN 12 INCHES. IT IS THE CUSTOMER'S RESPONSIBILITY TO VERIFY THE LOCAL AHJ'S REQUIREMENTS BEFORE START OF CONSTRUCTION.
- (M) NON-WALKABLE DEFINITION THOSE SURFACES NOT NORMALLY INTENDED TO SUPPORT HUMANS, SUCH AS BUT NOT LIMITED TO: HANDRAILS, FENCES, WALLS, CHIMNEYS, PARAPET WALLS, CORNICES, ALUMINUM OR LATH PATIO COVERS AND DECORATIVE APPENDAGES OR OTHER LIGHT WEIGHT MATERIAL USED FOR PATIO COVERS. HOWEVER, SUCH SURFACES, WHEN USED FOR A DUAL PURPOSE AS IN THE CASE OF A WIDE SURFACE USED AS A PLATFORM TO WORK ON LIGHTS, SIGNS, ETC., MUST BE CONSIDERED AS A SURFACE THAT A PERSON MIGHT NORMALLY WALK UPON. ALL CLEARANCES OF THIS TYPE MUST BE MEASURED FROM THE WALKABLE SURFACE.
- N CLEARANCE MAY BE REDUCED FOR INSULATED SERVICES (SSC) TO NOT LESS THAN 10 FEET. CLEARANCE IS MEASURED FROM THE LOWEST POINT, WHICH INCLUDES THE DRIP LOOP, TO FINISHED GRADE.
- ① THE POINT OF SERVICE DROP ATTACHMENT ON ANY RISER SHALL IN NO CASE BE MORE THAN 18 INCHES BACK OF THE FRONT FACE OF THE WALL FACING THE POLE LINE TO WHICH THE SERVICE DROP ORIGINATES, EXCEPT AS PERMITTED ON SG103. (c)
- (P) HORIZONTAL CLEARANCE OF 750–7,500V CONDUCTORS FROM BUILDING WALLS MAY BE REDUCED TO 4 FEET WHERE CONDUCTORS ARE IN EXCESS OF 35 FEET ABOVE GROUND. REDUCED CLEARANCE DOES NOT APPLY TO BRIDGES, FIRE ESCAPES, WINDOWS, BALCONIES, OR STRUCTURES WHERE HUMAN CONTACT MAY BE EXPECTED.
- Q NO LIMIT REQUIRED BUT THE GREATEST PRACTICABLE CLEARANCE SHOULD BE MAINTAINED. PROVIDE MECHANICAL (PHYSICAL) CLEARANCE FOR CABLE PROTECTION.
- (R) INCLUDES CORNICES, BALCONIES, EXITS, FIRE ESCAPES, BAY WINDOWS, CATWALKS, ETC.

BILL OF MATERIALS: NONE

NOTES:

- (I) ONLY IF THIS BUILDING IS ON THE PREMISES SERVED
- (II) NO SUPPLY SERVICE WIRES PERMITTED WITHIN SHADED ZONE.

Indicates Latest Revision

A WALKABLE MARQUEE, BUILDING PROJECTION, CANOPY, ROOF SECTION, OR EAVES EXTENDED FROM A BUILDING WALL TO FORM A SHELTER OVER A WALKWAY, DRIVEWAY, PASSENGER LOADING AREA, ETC., OUTSIDE THE BUILDING FIRE WALL REQUIRES 8 FEET MINIMUM CLEARANCE. IF NON-WALKABLE, MAY REDUCE TO 2 FEET PROVIDED SERVICE DROP IS INSULATED (SSC).

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV **CHANGE** BY DSN APV DATE **REV CHANGE** DR DATE DR C FIGURE UPDATE **IWA** JTM KRG 01/02/2025 F **FDM** В **FORMATTING FDM** JIK 04/24/2023 Ε **EDITORIAL CHANGES** TPM 11/01/2017 Α LSM IPJ

Completely Revised

SHEET 11 OF 12 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

SERVICE DROP CONDUCTOR CLEARANCES 0-600V

NOTES (CONT'D):

- (IV) THESE CLEARANCES DO NOT APPLY TO SERVICE DROP CONDUCTORS WHICH ARE ATTACHED TO SIGNS FOR THE PURPOSE OF SERVING SUCH SIGN. ALL CLEARANCES OF MORE THAN 6 INCHES SHALL BE APPLICABLE FROM THE CENTERLINE OF THE CONDUCTORS CONCERNED. LESSER CLEARANCES SHALL BE APPLICABLE FROM THE CONDUCTOR SURFACE. (f)
- (V) service drop conductors are not permitted within shaded zones.
- (VI) CLEARANCE REQUIREMENT FOR RESIDENTIAL, COMMERCIAL, OR INDUSTRIAL 0-600V SERVICE DROPS ABOVE BUILDINGS OTHER THAN SERVED (G)
- (VII) THE PORCH RAIL ILLUSTRATED IS NOT CONSIDERED A WALKABLE SURFACE. THE CLEARANCE WILL BE MEASURED FROM THE PORCH DECK.
- CLEARANCE REQUIREMENTS FOR NON-WALKABLE SURFACES ARE 2 FEET, AND FOR WALKABLE SURFACES ARE 8 FEET. SEE TABLE 6 FOR WALKABLE SURFACE CLEARANCES AND DEFINITION OF "NON-WALKABLE". (M)
- (IX) HORIZONTAL ANGLE SERVICE MAKES WITH BUILDING MUST NOT BE LESS THAN 30 DEGREES.
- (XI) 3-FOOT MINIMUM RADIAL CLEARANCE ABOVE OPENABLE WINDOWS (SEE SHEET 4)
- $\overline{ ext{(XII)}}$ 24 Inches minimum radially where more than 15 feet from point of attachment of either service
- (XIII) 12 INCHES MINIMUM RADIALLY WHERE 15 FEET OR LESS FROM POINT OF ATTACHMENT OF EITHER SERVICE
- (XIV) BUCKET TRUCK ACCESS IS REQUIRED IF THE DISTANCE FROM A LADDER TO THE WEATHERHEAD AND POINT OF ATTACHMENT EXCEEDS 24 INCHES.

REFERENCE:

- (a) SEE SG108.
- b. SEE OH220 AND OH225.
- (c) for residential, commercial, or industrial service drops, see SG103.
- (d) SEE SG104.
- e. FOR RADIAL CLEARANCES FROM OTHER CONDUCTORS, SEE 0H225.

Indicates Latest Revision

- (f) FOR MINIMUM CLEARANCES OF WIRES (0-750V SERVICE DROPS AND 750V-300KV SUPPLY CONDUCTORS AND CABLES) TO ILLUMINATED AND NON-ILLUMINATED SIGNS, SEE OH229.
- (9) FOR SIGNAGE REQUIREMENTS ON BRIDGES, VIADUCTS, ETC., WHEN ATTACHING CONDUCTORS 750-22,500V BENEATH OR THROUGH SAME, SEE G.O. 95 RULE 54.4I.
- (h) SEE G.O. 95, TABLE 1, CASES 6 AND 7 AND RULE 54.4H.
- (i) SEE CPUC GENERAL ORDER 95.
- (j) for 0-300V service drop clearances, see 0H262.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.												
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FIGURE UPDATE	EDM	IWA	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 12 OF 12 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed


Completely Revised

SERVICE DROP CONDUCTOR CLEARANCES 0-600V

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR OVERHEAD ELECTRIC CLEARANCES OVER SWIMMING POOLS.

DEFINITIONS:

• THE STATE OF CALIFORNIA GENERAL ORDER 95 DEFINES SWIMMING POOL AS "THAT PORTION OF ANY NATURAL OR ARTIFICIALLY CONTAINED BODY OF WATER WHICH IS 24 INCHES OR MORE IN DEPTH AT ANY POINT BELOW THE HIGHEST WATER LEVEL, WHICH IS INTENDED FOR USE FOR SWIMMING, BATHING OR OTHER SIMILAR RECREATIONAL PURPOSES, AND WHICH HAS A SURFACE AREA EXCEEDING 100 SQUARE FEET." (b)






TABLE 1

CLEARANCES OVER SWIMMING POOLS												
MINIMUM VERTICAL AND RADIAL CLEARANCES OVER SWIMMING POOLS $\overbrace{ m III}$ $\overbrace{ m IV}$	Z MINIMUM VERTICAL (FT)	Y MINIMUM RADIAL (FT)										
UNPROTECTED LINE CONDUCTORS (VERTICAL OVER HIGHEST WATER LEVEL AND RADIAL FROM TOP EDGE OF POOL WALLS) 1. 0-750V 2. 750-22,500V 3. 22.5-300KV	20 25 30	20 25 30										
SERVICE DROPS (VERTICAL OVER HIGHEST WATER LEVEL AND RADIAL FROM TOP EDGE OF POOL WALLS) 4. POOLS PUBLIC AND COMMERCIAL 5. POOLS RESIDENTIAL SERVICE DROPS (OVER DIVING BOARDS OR PLATFORMS) 6. PORTION OF BOARD OR PLATFORM THAT IS OVER WATER SURFACE 7. PORTION OF BOARD OR PLATFORM THAT IS NOT OVER WATER SURFACE	16 12 16 12	16 12 8 3										

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD ELECTRIC CLEARANCES
OVER SWIMMING POOLS

SG108.1

TABLE 1 (CONT'D)

CLEARANCES OVER SWIMMING POOLS												
MINIMUM VERTICAL AND RADIAL CLEARANCES OVER SWIMMING POOLS (III) (IV)	Z MINIMUM VERTICAL (FT)	Y MINIMUM RADIAL (FT)										
GUYS (UNGROUNDED PORTIONS) 8. OVER HIGHEST WATER LEVEL AND FROM TOP EDGE OF POOL WALLS 9. OVER DIVING BOARD OR PLATFORM (THE PORTION THAT IS OVER THE WATER SURFACE) 10. OVER DIVING BOARD OR PLATFORM (THE PORTION THAT IS NOT OVER THE WATER SURFACE)	18 18 12	18 8 6										
GUYS (GROUNDED PORTIONS) 11. OVER THE HIGHEST WATER LEVEL 12. OVER DIVING BOARD OR PLATFORM (THE PORTION THAT IS OVER THE WATER SURFACE) 13. OVER DIVING BOARD OR PLATFORM (THE PORTION THAT IS NOT OVER THE WATER SURFACE)	16 16 8	- 8 3										

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. CONTACT SDG&E (UTILITY) TO OBTAIN AN ACCEPTABLE POINT OF SERVICE DROP ATTACHMENT WHENEVER A SWIMMING POOL IS PROPOSED TO BE CONSTRUCTED IN AN AREA BETWEEN THE UTILITY'S POLE LINE AND THE BUILDING TO BE SERVED, OR A SWIMMING POOL HAS BEEN CONSTRUCTED CREATING A G.O. 95 OVERHEAD ELECTRIC CLEARANCE INFRACTION.
- II. INSTALLATION of 0–600V SERVICE DROP CONDUCTORS ABOVE A PUBLIC OR PRIVATE SWIMMING POOL AND ADJACENT RECREATIONAL AREA SHALL BE AVOIDED. SERVICE CONDUCTORS SHALL BE ROUTED AROUND THESE AREAS AT A HORIZONTAL CLEARANCE SUFFICIENT TO PROVIDE FOR HUMAN SAFETY, AND TO AVOID CONTAMINATION AND NUISANCE CAUSED BY "DROPPINGS" FROM BIRDS RESTING ON CONDUCTORS. SUFFICIENT HORIZONTAL CLEARANCE IS DEFINED AS A CLEARANCE DIMENSION AS CONDITIONS WARRANT TO PREVENT PERSONS IN THE POOL AREA FROM COMING INTO ACCIDENTAL CONTACT WITH SERVICE CONDUCTORS, OR BRINGING CONDUCTING MATERIALS INTO CONTACT WITH SERVICE CONDUCTORS BY USE OF POOL CLEANING OR MAINTENANCE EQUIPMENT.
- (III) SWIMMING POOLS SHALL NOT BE PLACED UNDER EXISTING OVERHEAD CONDUCTORS, INCLUDING SERVICE DROPS AND ANY OTHER OPEN OVERHEAD WIRING, UNLESS THE UTILITY DETERMINES ANY NECESSARY EASEMENTS HAVE BEEN GRANTED TO THE UTILITY, AND ALL MINIMUM CLEARANCES ARE MET.
- (IV) WHERE IT IS NOT PRACTICABLE TO CLEAR A SWIMMING POOL AND RECREATIONAL AREA AT A HORIZONTAL CLEARANCE AS SPECIFIED, SERVICE DROP CONDUCTORS SHALL BE MAINTAINED AT A RADIAL AND VERTICAL CLEARANCE OF NOT LESS THAN SHOWN.
 - a. PRACTICABLE AS DEFINED BY THE RULES FOR OVERHEAD LINE CONSTRUCTION MEANS CAPABLE OF BEING ACCOMPLISHED BY REASONABLY AVAILABLE AND ECONOMIC MEANS.
- V. CLEARANCE REQUIREMENTS FOR SPAS, HOT TUBS, ETC. MAY VARY ACCORDING TO THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ). MOST AHJS REQUIRE SWIMMING POOL CLEARANCES BE MET OVER ALL OUTDOOR SPAS, REGARDLESS OF SIZE.
- VI. UNDERGROUND ELECTRIC SERVICE CONDUIT AND GAS SERVICES ARE TO MAINTAIN A MINIMUM 5-FOOT SEPARATION FROM THE OUTSIDE WALL OF SWIMMING POOLS AND SPAS.

REFERENCE:

- a. SEE G.O. 95 RULE 54.4-A3.
- (b) SEE G.O. 95 RULE 23.6.

	© 1998 - 2023 San Diego Gas & Ele	ectric C	Compa	ny. All	rights r	eserved. Re	moval	of this copyright notice without permission	is not	permit	ted und	der law.	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	ī

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	1	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD ELECTRIC CLEARANCES OVER SWIMMING POOLS SG108.2

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR SERVICE HEADS.

ATTENTION:

* A SERVICE HEAD OF A TYPE APPROVED BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) SHALL BE PROVIDED ON THE SUPPLY END OF EVERY SERVICE RACEWAY TERMINATED ABOVE GROUND FOR AN OVERHEAD SERVICE CONNECTION.




FIGURE 1 (B)

INSTALLATION:

A. LOCATION:

THE SERVICE HEAD SHALL NORMALLY BE LOCATED ABOVE OR ON THE WALL OF THE BUILDING FACING AND NEAREST THE UTILITY'S POLE LINE. IT MAY BE LOCATED BELOW THE ROOF OF THE BUILDING SERVED UNDER THE CONDITIONS OUTLINED BELOW. (A2) IN ANY CASE, IT SHALL BE LOCATED SO THE SERVICE HEAD AND POINT OF CONNECTION TO THE SERVICE DROP CONDUCTORS WILL COMPLY WITH CLEARANCES REQUIRED BY APPLICABLE ELECTRICAL CODES AND ORDINANCES ENFORCED BY THE AHJ, AS WELL AS PROVISIONS SPECIFIED ON OTHER PAGES OF THIS SERVICE STANDARDS & GUIDE AND THE FOLLOWING:

1. THE SERVICE HEAD SHALL BE LOCATED SO THAT ONLY ONE POINT OF ATTACHMENT IS REQUIRED TO SUPPORT THE SERVICE DROP ON A BUILDING OR STRUCTURE AND SHOULD, WHERE PRACTICABLE, BE AT LEAST ONE FOOT ABOVE THE LEVEL OF THE POINT OF SERVICE DROP SUPPORT.

	© 1998 - 2023 San Diego Gas & El	ectric (Compa	ny. All	rights i	reserved. Rer	moval o	of th	is copyright no	tice	without permission	is not	permit	ted und	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CH	IAI	IGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F									
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е									
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
	X Indicates La	evisio	n	Con	npletely Revi	ised		New Page		Information Rer	noved					

SHEET 1 OF 2 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG109.1

SERVICE HEADS

- WHERE IT IS IMPRACTICAL TO LOCATE THE SERVICE HEAD ABOVE THE POINT OF ATTACHMENT, THE SERVICE HEAD MAY BE LOCATED NOT MORE THAN 24 INCHES RADIALLY FROM THE POINT OF ATTACHMENT. THE SERVICE HEAD SHALL BE LOCATED SO THE LENGTH OF OPEN SERVICE ENTRANCE CONDUCTORS BETWEEN THE SERVICE HEAD AND THE POINT OF CONNECTION OF THE UTILITY'S SERVICE DROP CONDUCTORS (DRIP LOOP) WILL NOT EXCEED 3 FEET.
- 3. WHERE MORE THAN ONE SERVICE HEAD FOR THE SAME PHASE AND VOLTAGE IS INSTALLED ON A BUILDING OR STRUCTURE, ALL SUCH SERVICE HEADS SHALL BE LOCATED SO THEY MAY BE SERVED THROUGH A SINGLE SERVICE DROP. THE MAXIMUM NUMBER OF SERVICE HEADS PERMITTED IS THREE. SEE INSTALLATION NOTE B FOR MULTIPLE SERVICE HEAD INSTALLATIONS.
- 4. WHERE SERVICE HEADS FOR DIFFERENT PHASE OR VOLTAGE ARE INSTALLED ON A BUILDING FOR WHICH A SINGLE POINT OF DELIVERY IS ESTABLISHED, SUCH SERVICE HEADS SHALL BE LOCATED AS CLOSE TOGETHER AS PRACTICABLE OR AS OTHERWISE DIRECTED BY THE SDG&E SERVICE PLANNER.
- 5. A SERVICE HEAD SHALL NOT BE LOCATED ON ANY WALL OR STRUCTURE WHICH FACES AND IS LESS THAN 3 FEET FROM A COMMON PROPERTY LINE.
- 6. A RADIAL DISTANCE OF NOT LESS THAN 3 FEET SHALL BE MAINTAINED FROM A SERVICE HEAD, SERVICE ENTRANCE CONDUCTORS AND SERVICE DROP TO ANY OPEN LOAD CONDUCTORS OR YARD LIGHTING.
- 7. A SERVICE HEAD SHALL NOT BE LOCATED MORE THAN 30 FEET ABOVE GRADE LEVEL MEASURED FROM THE STANDING SURFACE NEAREST SUCH HEAD.
- (B) NUMBER OF SERVICE HEADS PERMITTED:

MORE THAN ONE SERVICE HEAD MAY BE INSTALLED ON A BUILDING UP TO A MAXIMUM OF THREE PROVIDED THE INSTALLATION CONFORMS TO APPLICABLE ELECTRICAL CODES AND ORDINANCES ENFORCED BY THE AHJ PERTAINING TO THE PERMISSIBLE NUMBER OF SERVICES TO A BUILDING, AND CONFORMS TO ALL METER LOCATION AND ACCESS REQUIREMENTS FOR THEIR LOCATION IN ACCORDANCE WITH THE PROVISIONS OF THE SERVICE STANDARDS & GUIDE.

- C) THE POINT OF ATTACHMENT IS TO BE ON THE CENTER RISER, WHICH IS TO MEET ALL STANDARD REQUIREMENTS FOUND ON SG105. (a)
- D. DRIP LOOPS ARE NOT TO EXCEED 3 FEET IN OVERALL CABLE LENGTH PER SERVICE HEAD. (b)
- E. THE UTILITY SERVICE DROP IS NOT TO CROSS OVER MORE THAN 6 FEET OF ROOF TO REACH THE POINT OF ATTACHMENT. (c)

BILL OF MATERIALS: NONE

NOTES:

I. ACTUAL CONFIGURATION WILL VARY BASED ON SITE CONDITIONS.

Indicates Latest Revision

- II. THE BUILDER'S ACTUAL DESIGN AND INSTALLATION ARE SUBJECT TO ALL APPROVALS, PERMITS, AND INSPECTIONS REQUIRED BY THE AHJ.
- III. ALL PROPOSED METER LOCATIONS FOR THIS APPLICATION REQUIRE UTILITY APPROVAL AND A "METER & SERVICE LOCATION" FORM FROM AN SDG&E SERVICE PLANNER PRIOR TO CONSTRUCTION.

REFERENCE:

- (a) SEE SG105.
- (b) SEE SG112.
- (c) SEE SG103.

	© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE		
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F								
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								

SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed


Completely Revised

SG109.2

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR BUSWAY SERVICE HEADS.

ATTENTION:

BUSWAY TYPE SERVICE ENTRANCE SHALL BE LIMITED TO 600V MAXIMUM AND IS A REQUIREMENT WHEN MORE THAN THREE PARALLELED OVERHEAD SERVICE ENTRANCE CONDUCTORS PER PHASE ARE NECESSARY TO SUPPLY THE LOAD FOR ONE METERING LOCATION.




© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 3 Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG110.1

BUSWAY SERVICE HEADS




				•	_					•			
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						
	X Indicates L	atest R	evision	n	Con	npletely Revi	ised	New Page Information Re	moved				


SHEET 2 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG110.2

BUSWAY SERVICE HEADS





DETAIL 1DRILLING DETAILS FOR STUBOUTS

DETAIL 2DRILLING DETAILS FOR STUBOUTS

TABLE 1

MINIMUM DISTANCE FROM NEAREST OBSTRUCTION/WALL Z (IN) TO NEUTRAL CONNECTION 7											
TO NEUTRAL CONNECTION	7										
TO LINE CONNECTION	12										

INSTALLATION:

A. BUS STUBS SHALL BE DRILLED AS SHOWN IN DETAILS 1 AND 2.

BILL OF MATERIALS: NONE

NOTES:

- I. MANUFACTURER SHALL PROVIDE AN INSULATED BARRIER TO SHIELD THE BUS BARS. ONLY THE STUBS ARE TO BE EXPOSED FOR CONNECTION OF SERVICE DROP CONDUCTORS BY SDG&E'S CREW.
- II. ALL NEUTRAL AND DELTA POWER LEG BUS STUBS SHALL BE PERMANENTLY IDENTIFIED (MARKED) IN A MANNER CONFORMING TO THE REQUIREMENTS OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) AND SDG&E. (a)
- III. SDG&E WILL FURNISH LUGS AND INSULATE THE CONNECTIONS BELOW THE BARRIER.
- IV. CONTACT THE APPROPRIATE PROJECT MANAGEMENT REGIONAL OFFICE FOR VAULT INSTALLATIONS. (b)

REFERENCE:

- (a) FOR IDENTIFICATION, SEE SG112.
- (b) SEE SG<mark>021</mark>.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

atest Revision		Completely Revised		New Page		Information Removed
SDG&	F F	FCTRIC SERVICE ST	ΔΝΓ	VABDS & CI	IID	FS

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

BUSWAY SERVICE HEADS

SG110.3

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR SERVICE ENTRANCE RACEWAYS.

INSTALLATION:

A. GENERAL INFORMATION:

FOR EACH OVERHEAD SERVICE CONNECTION, THE CONTRACTOR FURNISHES AND INSTALLS AN APPROVED RAINTIGHT SERVICE ENTRANCE RACEWAY, INCLUDING ALL FITTINGS, FROM THE SERVICE EQUIPMENT TO THE POINT OF SERVICE DROP ATTACHMENT. SUCH A SERVICE RACEWAY MAY BE CONCEALED OR EXPOSED. THE INSTALLATION MUST COMPLY WITH ALL APPLICABLE ELECTRICAL CODES AND ORDINANCES OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).

B. INSTALLATION METHOD:

THE SERVICE ENTRANCE RACEWAY SHOULD BE CONTINUOUS AND WITHOUT CONDULET OR JUNCTION BOX. HOWEVER, WITH THE PRIOR APPROVAL OF THE AHJ AND SDG&E (UTILITY), SUCH DEVICES MAY BE INSTALLED WHEN EXCESSIVE LENGTH AND BENDS IN THE SERVICE ENTRANCE RACEWAY MAKE A CONTINUOUS RUN IMPRACTICAL.

- 1. IF EXPOSED TO WEATHER, THE DEVICES SHALL BE RAINTIGHT.
- 2. IF A CONDULET OR JUNCTION BOX IS APPROVED IN THE SERVICE ENTRANCE RACEWAY, IT WILL NEED TO BE EQUIPPED WITH ACCESSORIES TO PERMIT SEALING.
- 3. BETWEEN THE METERING EQUIPMENT AND THE SERVICE ENTRANCE CONNECTION, THE DEVICES SHALL BE LOCATED SO THAT THEY ARE PLAINLY VISIBLE FOR PERPETUAL INSPECTION BY THE UTILITY.

C. SEALING SERVICE ENTRANCE RACEWAYS AND METERING ENCLOSURES:

THE UTILITY WILL SEAL AUXILIARY RACEWAYS, GUTTERS, OR METER TROUGHS CONTAINING SERVICE ENTRANCE CONDUCTORS (UNMETERED CONDUCTORS), INCLUDING METER ENCLOSURES, METER SOCKET BOXES AND SIMILAR ENCLOSURES WHICH FORM A PART OF THE SERVICE ENTRANCE INSTALLATION THAT IS ON THE SUPPLY (LINE) SIDE OF THE METERING EQUIPMENT. IT IS NOT ACCEPTABLE TO INSTALL THE CUSTOMER'S FEEDER (METERED) CONDUCTORS IN A SERVICE ENTRANCE RACEWAY, LINE GUTTER OR METER TROUGH, OR IN A METERING ENCLOSURE AHEAD (ON THE LINE SIDE) OF THE OVERCURRENT PROTECTIVE DEVICE. ELECTRICALLY PROTECTED (FUSED) AND UNPROTECTED (UNFUSED) CONDUCTORS ARE NOT ALLOWED TO OCCUPY THE SAME RACEWAY OR LINE GUTTER. (a)

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

(a) FOR SEALING OF METERS AND METERING EQUIPMENT AND SEALING REQUIREMENTS, SEE SG503.

	© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	HAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMAT	TING	3	EDM	JIK	-	-	04/24/2023	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Rer	noved				
					SDC	%F F	I FCTI	RIC SERVIC	F ST	ΔΝΓ	DARDS & GI	IID	FS					

SHEET 1 OF 1

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SERVICE ENTRANCE RACEWAYS

SG111.1

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR 0-600V SERVICE ENTRANCE CONDUCTORS.

DEFINITIONS:

- **SERVICE ENTRANCE CONDUCTORS (OVERHEAD):** CUSTOMER-OWNED CONDUCTORS EXTENDING FROM THE SERVICE EQUIPMENT TO THE POINT OF CONNECTION TO THE UTILITY SERVICE DROP CONDUCTORS.
- SERVICE DROP CONDUCTORS: SDG&E (UTILITY'S) OVERHEAD CONDUCTORS EXTENDING FROM ITS POLE LINE TO THE POINT OF SERVICE DROP SUPPORT ON A BUILDING OR STRUCTURE.






FIGURE 1 DRIP LOOPS (U) DETAIL 1 DRIP LOOP

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--


	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	PS	JTM	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 7


Indicates Latest Revision		Completely Revised		New Page		Information Removed				
SDG&F FLECTRIC SERVICE STANDARDS & GUIDES										

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SERVICE ENTRANCE CONDUCTORS 0-600V



EXAMPLE 1 DECORATIVE APPENDAGE AND/OR ROOF



EXAMPLE 2 FLAT OR SLOPING EAVE OR ROOF



EXAMPLE 3 PARAPET WALL

FIGURE 2 0-600V CLEARANCE ABOVE A METALLIC OR NON-METALLIC DECORATIVE APPENDAGE, EAVE, ROOF OR PARAPET WALL F G II (III) (IV) a

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C EDITORIAL CHANGES PS JTM JTM KRG 01/02/2025 F				BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
B FORMATTING FDM 11K 04/24/2023 F	С	EDITORIAL CHANGES	PS	JTM	JTM	KRG	01/02/2025	F						
	В	FORMATTING E	EDM	JIK	-	-	04/24/2023	Е						
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D	Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 7

Information Removed Indicates Latest Revision | Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE ENTRANCE CONDUCTORS 0-600V




FIGURE 2 (CONT'D)

0-600V CLEARANCE ABOVE A METALLIC OR
NON-METALLIC DECORATIVE APPENDAGE, EAVE, ROOF OR PARAPET WALL (F)(G)(II)(III)(IV)(a)

INSTALLATION:

GENERAL INFORMATION:

- A. FOR EACH OVERHEAD SERVICE CONNECTION, THE CONTRACTOR FURNISHES AND INSTALLS SERVICE ENTRANCE CONDUCTORS FROM THE SERVICE EQUIPMENT TO THE POINT OF CONNECTION TO THE UTILITY'S SERVICE DROP CONDUCTORS. THESE CONDUCTORS MAY BE AN INDIVIDUAL SET OR PARALLEL SETS IN CONDUIT RACEWAYS, BUSWAY OR SERVICE ENTRANCE CABLE OF TYPES APPROVED BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).
- B. BUSWAY TYPE SERVICE ENTRANCE SHALL BE REQUIRED WHERE MORE THAN THREE PARALLELED OVERHEAD SERVICE ENTRANCE CONDUCTORS PER PHASE ARE NECESSARY TO SUPPLY THE LOAD FOR ONE METERING LOCATION. (b)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	PS	JTM	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						
												*	

SHEET 3 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE ENTRANCE CONDUCTORS 0-600V

GENERAL INFORMATION (CONT'D):

- C. IN GENERAL, A BUILDING SHOULD HAVE ONLY ONE SET OF SERVICE ENTRANCE CONDUCTORS, EXCEPT AS FOLLOWS:
 - 1. WHERE PERMITTED BY THE AHJ, BUILDINGS WITH MULTIPLE TYPES OF OCCUPANCY MAY HAVE TWO OR MORE SEPARATE SETS OF SERVICE ENTRANCE CONDUCTORS WHICH ARE TAPPED FROM A SINGLE POINT OF SERVICE DELIVERY. UP TO SIX SETS OF SERVICE ENTRANCE CONDUCTORS MAY BE TAPPED FROM A SINGLE SET OF MAIN SERVICE ENTRANCE CONDUCTORS PROVIDED THE PHASE-TO-PHASE VOLTAGE BETWEEN THE CONDUCTORS DOES NOT EXCEED 300V. WHERE MAIN SERVICE ENTRANCE CONDUCTORS SUPPLY SEVERAL UNITS OF A MULTIPLE OCCUPANCY BUILDING, THE JUNCTION BOXES IN WHICH SUB-SERVICE ENTRANCE CONDUCTORS ARE CONNECTED TO THE MAIN SERVICE NEED TO BE IN A READILY ACCESSIBLE AND VISIBLE LOCATION ON THE EXTERIOR OF THE BUILDING OR IN A PUBLIC AREA. THEY MUST BE SEALABLE AND IF EXPOSED TO WEATHER, RAINTIGHT.
 - 2. BUILDINGS OF UNUSUALLY LARGE AREA MAY HAVE MORE THAN ONE POINT OF SERVICE DELIVERY. (c)
 - 3. A SEPARATE SET OF SERVICE ENTRANCE CONDUCTORS MAY BE INSTALLED IF REQUIRED FOR FIRE PUMPS OR FOR EMERGENCY LIGHTING PURPOSES.
 - 4. ADDITIONAL SERVICE ENTRANCE CONDUCTORS MAY BE INSTALLED FOR A SECOND CLASS OF SERVICE (DIFFERENT VOLTAGE) WHEN APPROVED BY THE UTILITY.

SIZE AND CAPACITY:

D. THE CAPACITY OF SERVICE ENTRANCE CONDUCTORS SHALL COMPLY WITH ELECTRICAL CODES AND ORDINANCES ENFORCED BY THE AHJ. THE SMALLEST SIZE SHOULD NOT BE LESS THAN 6 AWG, EXCEPT THAT 8 AWG MAY BE USED IN EITHER TWO-WIRE, OR THREE-WIRE SERVICE ENTRANCE INSTALLATIONS WHICH SUPPLY NOT MORE THAN TWO 2-WIRE BRANCH CIRCUITS, WITH A MAXIMUM OF ONE 15A AND ONE 20A CIRCUIT.

IDENTIFICATION:

E. ALL NEUTRAL CONDUCTORS SHALL BE PERMANENTLY IDENTIFIED WHITE OR GRAY IN COLOR IN A MANNER ACCEPTABLE TO THE AHJ. FOR THREE-PHASE DELTA-CONNECTED SERVICES, THE POWER LEG SHALL BE PERMANENTLY IDENTIFIED ORANGE IN COLOR IN A MANNER ACCEPTABLE TO THE AHJ. THE IDENTIFICATION FOR BOTH NEUTRAL AND POWER LEG CONDUCTORS SHALL BE APPLIED ON THE OPEN CONDUCTORS (DRIP LOOP) EXTENDED FROM A SERVICE HEAD OR ON THE BUS STUBS OF A BUSWAY SERVICE HEAD, WHICHEVER IS APPLICABLE, AND THROUGHOUT THE METER AND SERVICE EQUIPMENT. THE UTILITY DOES NOT REQUIRE OTHER CONDUCTORS TO BE IDENTIFIED.

MAXIMUM LENGTH OF SERVICE ENTRANCE CONDUCTORS EXTENDED FROM SERVICE HEAD AND THE DRIP LOOP:

- F THE LENGTH OF OPEN SERVICE ENTRANCE CONDUCTORS BETWEEN THE SERVICE HEAD AND THE POINT OF CONNECTION TO THE UTILITY'S SERVICE DROP (DRIP LOOP) SHALL NOT EXCEED 3 FEET.
- G THE CONTRACTOR SHOULD ENSURE THAT THE SERVICE ENTRANCE CONDUCTORS EXTENDED FROM THE SERVICE HEAD HAVE SUFFICIENT LENGTH TO BE CONNECTED TO THE UTILITY'S SERVICE DROP CONDUCTORS. SPLICES ARE NOT PERMITTED IN THE CUSTOMER-OWNED SERVICE ENTRANCE CONDUCTORS. WHEN THE ACTUAL LENGTH REQUIRED IS NOT KNOWN, 3 FEET WILL BE SUFFICIENT.
- H. SEE DRIP LOOP INSTALLATION INSTRUCTIONS WHEN, BY NECESSITY, A SERVICE HEAD IS INSTALLED BELOW THE POINT OF SERVICE DROP ATTACHMENT. (U)

CONNECTION OF SERVICE ENTRANCE CONDUCTORS TO SERVICE DROP CONDUCTORS:

- J. THE UTILITY WILL COMPLETE THE SERVICE CONNECTION BY:
 - 1. CONNECTING THE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS TO ITS SERVICE DROP CONDUCTORS, OR

	© 1998 - 2025 Sa	an Diego Gas & E	lectric C	Compa	ny. All	rights i	reserved. Rer	noval c	f this copyright not	ice	without permission	is not	permit	ted und	ler law.	
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV	СН	ΑN	IGE	DR	BY	DSN	APV	DATE
С	EDITORIAL C	CHANGES	PS	JTM	JTM	KRG	01/02/2025	F								
В	FORMAT	TING	EDM	JIK	-	-	04/24/2023	Е								
Α	EDITORIAL (CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
X Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																
													SG112.4			
SHEET 4 OF 7 SERVICE ENTRANCE CONDUCTORS 0-600V																

CONNECTION OF SERVICE ENTRANCE CONDUCTORS TO SERVICE DROP CONDUCTORS (CONT'D):

2. CONNECTING ITS SERVICE DROP CONDUCTORS TO BUSWAY SERVICE HEAD BUS-DUCT STUBS, EXCEPT WHEN VOLTAGE RATED INSULATED SERVICE ENTRANCE CONDUCTORS ARE REQUIRED BETWEEN BUSWAY BUS-DUCT STUBS AND SERVICE DROP CONDUCTORS AT LOCATIONS WHERE SERVICE ENTRANCE CONDUCTORS WILL PASS ABOVE ANY PORTION OF A BUILDING AT THE REDUCED CLEARANCE PERMITTED BY SOME EXCEPTIONS. INSULATED SERVICE ENTRANCE CONDUCTORS, IN SUCH A CASE, SHALL BE FURNISHED AND CONNECTED TO BUS-DUCT STUBS BY THE CONTRACTOR AND BE OF SUFFICIENT LENGTH FOR CONNECTION TO THE UTILITY'S SERVICE DROP CONDUCTORS. (W)

SERVICE ENTRANCE CABLE:

- K. WHERE PERMITTED BY THE AHJ, STANDARD TYPES OF SERVICE ENTRANCE CABLE WITH APPROVED RAINTIGHT FITTINGS MAY BE FURNISHED AND INSTALLED BY THE CONTRACTOR IN LIEU OF SERVICE ENTRANCE CONDUCTORS IN RACEWAYS.
- L. SERVICE ENTRANCE CABLES SHALL BE INSTALLED ON THE SURFACE OF THE BUILDING.

TAPS AND SPLICES IN SERVICE RACEWAYS:

- M. THE CONDUCTORS SHALL BE CONTINUOUS WITHOUT TAPS OR SPLICES, EXCEPT AS FOLLOWS:
 - 1. APPROVED CLAMPED OR BOLTED CONNECTIONS MAY BE MADE IN JUNCTION BOXES OR APPROVED DEVICES. (d)
 - 2. TAPS MAY BE MADE IN APPROVED JUNCTION BOXES WHERE SUBSETS OF INDIVIDUAL SERVICE ENTRANCE CONDUCTORS ARE PERMITTED TO BE EXTENDED FROM MAIN BUS SERVICE ENTRANCE CONDUCTOR RUN.
 - 3. TAPS MAY BE MADE IN AUXILIARY GUTTERS OR METER TROUGHS WHERE INDIVIDUAL SETS OF SERVICE ENTRANCE CONDUCTORS ARE PERMITTED TO BE TAPPED TO AN APPROVED GROUP OF INDIVIDUAL SERVICE SWITCHES.
 - 4. THE NEUTRAL SHALL BE CONTINUOUS WITHOUT SPLICE UNTIL TERMINATED AT THE GROUNDING BUS. TAPS MAY BE MADE AS INDICATED PREVIOUSLY. NEUTRAL CONDUCTORS BROKEN AT AN APPROVED LANDING BLOCK OR BUS SHALL BE CONSIDERED AS CONTINUOUS.

OTHER CONDUCTORS IN SERVICE ENTRANCE RACEWAYS:

- N. NO CONDUCTORS OTHER THAN SERVICE ENTRANCE CONDUCTORS ARE PERMITTED IN THE SERVICE ENTRANCE RACEWAY, EXCEPT WHEN CONTINUOUS BONDING WIRES ARE REQUIRED BY THE APPROPRIATE INSPECTION AUTHORITY TO CONNECT MULTIPLE SECTIONS OF THE CUSTOMER'S SERVICE EQUIPMENT. WHERE A MAIN DISCONNECT IS INSTALLED ON THE LINE SIDE OF A GROUP OF METERS AND SERVICE SWITCHES, THE CONDUCTORS ON THE LINE SIDE OF THE MAIN DISCONNECT, AND ANY UNMETERED CONDUCTORS (FEEDERS) ON THE LOAD SIDE OF THE MAIN DISCONNECT TO THE METERS WILL BE TREATED AS SERVICE ENTRANCE CONDUCTORS. THE PURPOSE OF THIS RULING IS TO PROHIBIT METERED AND UNMETERED CONDUCTORS IN THE SAME RACEWAY.
- O. LINE SIDE (UNMETERED) AND LOAD SIDE (METERED) CONDUCTORS ARE PROHIBITED FROM OCCUPYING THE SAME RACEWAY, EXCEPT IN METER SOCKETS AND TERMINATING ENCLOSURES.
- P. NO CONDUCTORS FROM THE LOAD SIDE OF ANY OR FROM A SIMILAR SOURCE MAY RE-ENTER AN AUXILIARY GUTTER OR METER TROUGH CONTAINING UNMETERED FEEDER OR SERVICE ENTRANCE CONDUCTORS, EXCEPT IN A SEPARATELY BARRIERED SECTION.
- Q. A MAIN GROUNDING CONNECTION FROM THE GROUNDING ELECTRODE OR WATER PIPE TO A NEUTRAL CONDUCTOR OF THE SERVICE MAY BE IN AN AUXILIARY GUTTER OR METER TROUGH WHERE MORE THAN ONE METER IS INVOLVED, PROVIDED THE INSTALLATION IS MADE SO AS TO MINIMIZE INTERFERENCE AND APPROVED BY THE AHJ.

REV CHANGE DR BY DSN APV DATE REV CHANGE DR BY DSN														1			
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	С	IAH	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL C	CHAN	IGES	PS	JTM	JTM	KRG	01/02/2025	F								
В	FORMAT	TING	i	EDM	JIK	-	-	04/24/2023	Е								
Α	EDITORIAL C	CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates Latest Revisio					n	Completely Revised New Page Information Removed										

SERVICE ENTRANCE CONDUCTORS

0-600V

SG112.5

SHEET 5 OF 7

GROUNDING AND BONDING:

- R. THE SERVICE RACEWAY, METERING ENCLOSURE AND SERVICE EQUIPMENT FOR ALL CLASSES OF SERVICE, INCLUDING ANY NEUTRAL SERVICE ENTRANCE CONDUCTOR, NEEDS TO BE BONDED AND GROUNDED IN COMPLIANCE WITH ELECTRICAL CODES AND ORDINANCES ENFORCED BY THE AHJ. IN ADDITION, A NEUTRAL BOND CONNECTION SHALL BE MADE BY THE CONTRACTOR, CONNECTING THE NEUTRAL SERVICE ENTRANCE CONDUCTOR TO THE INTERIOR OF THE METER SOCKET ENCLOSURE FOR MULTIPLE SOCKETS, OR SEALED SERVICE GUTTER. IN SUCH CASES, THE COMPLETE NEUTRAL BOND CONNECTION SHALL BE ENTIRELY WITHIN THE PART OF THE ENCLOSURE WHICH IS UNDER THE UTILITY'S SEAL. IN COMBINATION METER SOCKET AND BREAKER ENCLOSURES, THE NEUTRAL BOND CONNECTION SHALL BE ENTIRELY ON THE SUPPLY SIDE OF THE BARRIER BETWEEN THE UPPER PART OF THE DEVICE AND THE BREAKER COMPARTMENT.
- S. ELECTRIC BONDING TO, OR USE OF SDG&E GAS SERVICE PIPING, GAS RISERS OR GAS METER FACILITIES FOR ELECTRIC BONDING AND GROUNDING IS NOT PERMITTED.

ALUMINUM SERVICE ENTRANCE CONDUCTORS:

T. ALUMINUM SERVICE ENTRANCE CONDUCTORS MAY BE USED PROVIDED THE TERMINALS AND CONNECTORS MAKING CONNECTIONS, TAPS OR SPLICES IN METER AND SERVICE DEVICES ARE OF A TYPE SUITABLE FOR RECEIVING ALUMINUM CONDUCTORS AND ARE FURNISHED AND INSTALLED BY THE CONTRACTOR IN ACCORDANCE WITH APPLICABLE ELECTRICAL CODES ENFORCED BY THE AHJ.

DRIP LOOPS:

WHERE BY NECESSITY A SERVICE HEAD IS INSTALLED BELOW THE POINT OF SERVICE DROP ATTACHMENT, DRIP LOOPS SHOULD BE FORMED IN THE OPEN SERVICE ENTRANCE CONDUCTORS. TO PREVENT SIPHONING OF WATER INTO SERVICE RACEWAY OR EQUIPMENT, AN INVERTED "V" NOTCH SHOULD BE CUT THROUGH THE INSULATION ON THE CURRENT CARRYING STRANDS AT THE LOWEST POINT ON THE BOTTOM SIDE OF EACH SERVICE ENTRANCE CONDUCTOR DRIP LOOP AS SHOWN IN FIGURE 1.

CLEARANCES ABOVE COMMERCIAL OR INDUSTRIAL BUILDINGS AND STRUCTURES:

- (W) THE LEGAL REQUIREMENT FOR 0-600V OPEN WIRE SERVICE ENTRANCE CONDUCTORS IS A VERTICAL CLEARANCE OF NOT LESS THAN 8 FEET ABOVE ANY PORTION OF A METALLIC OR NON-METALLIC BUILDING OR STRUCTURE SERVED, EXCEPT:
 - 1. 0–300V SERVICE ENTRANCE CONDUCTORS MAY BE LESS THAN 8 FEET BUT NOT LESS THAN 12 INCHES ABOVE A NON-METALLIC DECORATIVE APPENDAGE, EAVE, ROOF, OR PARAPET WALL, PROVIDED THE SERVICE HEAD IS LOCATED NOT MORE THAN 18 INCHES BACK OF THE EXTERIOR FACE OF THE BUILDING WALL.
 - 2. 0–300V SERVICE ENTRANCE CONDUCTORS MAY BE LESS THAN 8 FEET BUT NOT LESS THAN 12 INCHES ABOVE A METALLIC EAVE, ROOF OR PARAPET WALL, PROVIDED THE SERVICE HEAD IS NOT MORE THAN 18 INCHES BACK OF THE OUTER EDGE OF THE EAVE, ROOF, OR PARAPET WALL.
 - 3. 0-600V SERVICE ENTRANCE CONDUCTORS MAY BE LESS THAN 8 FEET BUT NOT LESS THAN 12 INCHES ABOVE A METALLIC OR NON-METALLIC EAVE, ROOF, OR PARAPET WALL, PROVIDED THE SERVICE HEAD IS NOT MORE THAN 18 INCHES BACK OF THE OUTER EDGE OF THE EAVE, ROOF, OR PARAPET WALL.

BILL OF MATERIALS: NONE

NOTES:

- (1) FORM DRIP LOOPS IN SERVICE ENTRANCE CONDUCTORS WHERE SERVICE HEAD IS BELOW SERVICE DROP ATTACHMENT. 3 FEET MAXIMUM LENGTH
- (II) NO SUPPLY SERVICE WIRES PERMITTED WITHIN SHADED ZONE.
- (III) SERVICE ENTRANCE CONDUCTORS AND SERVICE DROP CONDUCTORS ARE NOT PERMITTED WITHIN THE SHADED ZONES ILLUSTRATED.
- (IV) 0-600V SERVICE DROP CONDUCTORS AND SUPPORTING SERVICE INSULATOR MAY BE ATTACHED TO A CONDUIT RISER IN LIEU OF THE SUPPORT RACK PROVIDED THE SERVICE ENTRANCE CONDUCTORS AND SERVICE DROP CONDUCTORS DO NOT PASS THROUGH THE SHADED ZONES ILLUSTRATED.

 $@ 1998 - 2025 \ San \ Diego \ Gas \ \& \ Electric \ Company. \ All \ rights \ reserved. \ Removal \ of this \ copyright \ notice \ without \ permission \ is \ not \ permitted \ under \ law.$

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	PS	JTM	JTM	KRG	01/02/2025	F						
В	FORMATTING	EDM	JIK	-	-	04/24/2023	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						
							L .						

SHEET 6 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE ENTRANCE CONDUCTORS 0-600V

REFERENCE: (a) FOR SERVICE DROP CLEARANCES ABOVE BUILDINGS, A CORNICE OR APPENDAGE, SEE SG107. (b) SEE SG109 AND SG110. (c) FOR ELECTRIC SERVICE POLICIES, SEE SG013. (d) SEE SG111. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV DR BY DSN APV DATE DATE **REV CHANGE** CHANGE С **EDITORIAL CHANGES** PS JTM JTM KRG 01/02/2025 В Ε **FORMATTING EDM** JIK 04/24/2023 LSM TPM 11/01/2017 Α **EDITORIAL CHANGES** IPJ **Indicates Latest Revision** Completely Revised New Page Information Removed

SHEET 7 OF 7

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SERVICE ENTRANCE CONDUCTORS 0-600V

200 104 103

<u>62</u>

200 104 103

<u>62</u>

<u>PAGE</u>	<u>SUBJECT</u>
202	ALPHABETICAL SUBJECT INDEX
203	GENERAL INFORMATION
204	CUSTOMER-OWNED SERVICE & METER POLE PERMANENT/CLIMBABLE, 0 - 600 VOLTS
205	CUSTOMER-OWNED SERVICE & METER POLES TEMPORARY/NON-CLIMBABLE, 0 – 600 VOLTS
206	CUSTOMER-OWNED SERVICE & METER POLE WITH MULTIPLE METERS PERMANENT OR TEMPORARY INSTALLATION
207	CUSTOMER-OWNED SERVICE WITH MULTIPLE METERS FOR UNDERGROUND PERMANENT OR TEMPORARY INSTALLATION
208	TEMPORARY SERVICE FROM SDG&E HANDHOLE TO CUSTOMER-OWNED SERVICE & METER INSTALLATION
209	TEMPORARY SERVICE FROM SDG&E POLE OR PADMOUNT TRANSFORMER TO CUSTOMER-OWNED SERVICE & METER INSTALLATION
210	TEMPORARY SERVICE TO PERMANENT SERVICE & METERING ENCLOSURE (TSPB)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK			12/07/2020	Е						
Α	NEW PAGE		LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1 Indicates Latest Revision Completely Revised New Page X Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG201.1

<u>SUBJECT</u> <u>PAGI</u>	<u>E</u>
ADDRESS MARKING	2
AVAILABLE SECONDARY FAULT CURRENT	2
CUSTOMER-OWNED SERVICE & METER POLE FOR PERMANENT OR TEMPORARY SERVICE, 0 - 600 VOLTS203.1 - 203.2	2
CUSTOMER-OWNED SERVICE & METER POLES PERMANENT/CLIMBABLE, 0 – 600 VOLTS	3
CUSTOMER-OWNED SERVICE & METER POLES TEMPORARY/NON-CLIMBABLE, 0 – 600 VOLTS	4
CUSTOMER-OWNED SERVICE & METER POLE WITH MULTIPLE METERS PERMANENT OR TEMPORARY INSTALLATION 200	6
CUSTOMER-OWNED SERVICE WITH MULTIPLE METERS FOR UNDERGROUND PERMANENT OR TEMPORARY INSTALLATION 202	7
GENERAL INFORMATION	1
GENERAL REQUIREMENTS	1
MARKING, ADDRESS	2
MULTIPLE METER INSTALLATION	7
PERMANENT POLES 204.1 – 204.1	3
PERMANENT OR TEMPORARY SERVICE INSTALLATIONS	7
SERVICE & METER POLE SPECIFICATIONS	1
SERVICE DROP CLEARANCES	3
STEEL SERVICE & METER POLES	2
TEMPORARY POLES	4
TEMPORARY SERVICE FROM AN OVERHEAD SOURCE	2
TEMPORARY SERVICE FROM AN UNDERGROUND SOURCE	9
TEMPORARY SERVICE FROM SDG&E HANDHOLE TO CUSTOMER-OWNED SERVICE & METER INSTALLATION	2
TEMPORARY SERVICE FROM SDG&E POLE OR PADMOUNT TRANSFORMER TO CUSTOMER-OWNED SERVICE & METER INSTALLATION	2
TEMPORARY SERVICE TO PERMANENT METERING ENCLOSURE (TSPB)	0

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK			12/07/2020	Е						
Α	EDITORIAL CHANGES		LSM	LSM	TPM	11/01/2017	D			·			

SHEET 1 OF 1 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Indicates Latest Revision | Completely Revised | New Page |

CUSTOMER-OWNED METER POLES ALPHABETICAL SUBJECT INDEX

SG202.1

Information Removed

SCOPE: THIS SERVICE GUIDE PROVIDES GENERAL INFORMATION REGARDING SERVICE AND METER POLES OR POLE-TYPE STRUCTURES.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. ALL PERMANENT CUSTOMER-OWNED SERVICE AND METER POLES OR POLE-TYPE STRUCTURES ON WHICH SDG&E (UTILITY) OVERHEAD SERVICE DROP CONDUCTORS ARE TO BE SUPPORTED ARE DEFINED BY THE CALIFORNIA PUBLIC UTILITIES COMMISSION AS BEING CLIMBABLE. FOR THIS REASON, THEY ARE SUBJECT TO COMPLIANCE WITH CALIFORNIA PUBLIC UTILITIES COMMISSION RULES FOR OVERHEAD ELECTRIC LINE CONSTRUCTION, GENERAL ORDER 95. EXCEPTED ARE POLES OR WOODEN TIMBERS PERMANENTLY ATTACHED TO BUILDINGS IN SUCH A MANNER THAT THEY ARE CONSIDERED TO BE NON-CLIMBABLE AND PART OF THE BUILDING STRUCTURE, IN WHICH CASE THEY ARE TREATED AS A SERVICE DROP ATTACHMENT RISER AND ARE SUBJECT TO COMPLIANCE WITH APPLICABLE STRENGTH AND CLEARANCE REQUIREMENTS. THE UTILITY HAS DETERMINED TEMPORARY CUSTOMER-OWNED SERVICE AND METER POLES WILL NOT BE CLIMBED.

II. MINIMUM REQUIREMENTS FOR CUSTOMER-OWNED SERVICE AND METER POLES ARE SPECIFIED AND ILLUSTRATED ON THE FOLLOWING PAGES. COMPLIANCE WITH THESE MINIMUM REQUIREMENTS IS THE RESPONSIBILITY OF THE CUSTOMER OR CONTRACTOR. SERVICE CANNOT BE ESTABLISHED TO ANY INSTALLATION NOT COMPLYING WITH THESE MINIMUM REQUIREMENTS, OR WHERE PERMIT AND INSPECTION CLEARANCE FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) HAS NOT BEEN OBTAINED. THE FOLLOWING INFORMATION PROVIDES ASSISTANCE IN DETERMINING A CORRECT AND UNIFORM INTERPRETATION OF REQUIREMENTS FOR CUSTOMER-OWNED PERMANENT OR TEMPORARY SERVICE AND METER POLES.

III. GENERAL REQUIREMENTS

THE REQUIREMENTS ON DIMENSIONS PERTAINING TO SEPARATION, ELEVATION, LOCATION OF CONSTRUCTION UNITS, DESCRIPTION OF APPROVED MATERIALS, CONSTRUCTION METHODS AND CLEARANCES ARE BASIC MINIMUMS SPECIFIED BY LOCAL CODES AND ORDINANCES, STATE OF CALIFORNIA BUILDING STANDARDS, CALIFORNIA ELECTRICAL CODE AND CALIFORNIA PUBLIC UTILITIES COMMISSION RULES FOR OVERHEAD ELECTRIC LINE CONSTRUCTION, GENERAL ORDER 95. DEVIATION FROM THESE MINIMUM REQUIREMENTS, OR SUBSTITUTION OF MATERIAL OTHER THAN SPECIFIED, CANNOT BE GRANTED BY THE UTILITY.

IV. SERVICE DROP CLEARANCES

SERVICE DROP CLEARANCES ABOVE GROUND ARE SHOWN ON THE ACCOMPANYING SPECIFICATIONS AND DRAWINGS. FOR SERVICE DROP CLEARANCE REQUIRED OVER ROOFS, FROM BUILDINGS, STRUCTURES, OBSTRUCTIONS, AND OTHER CONDUCTORS, REFER TO SG112. (a)

V. SERVICE & METER POLE SPECIFICATIONS

SEE DRAWINGS AND GENERAL NOTES IN SG204 AND SG205 FOR PERMANENT AND TEMPORARY SERVICE AND METER POLE REQUIREMENTS.(b)(c)

VI. STEEL SERVICE & METER POLE

- a. A STEEL POLE MAY BE USED FOR BOTH A TEMPORARY OR PERMANENT SERVICE AND METER POLE, PROVIDED ITS STRENGTH IS ADEQUATE AND IS APPROVED BY THE UTILITY. SUCH POLE SHALL BE SELF-SUPPORTING AND IN OTHER RESPECTS COMPLY WITH SPECIFICATIONS AND DRAWINGS ILLUSTRATING PERMANENT OR TEMPORARY CUSTOMER-OWNED SERVICE AND METER POLE AS APPLICABLE FOR ITS INTENDED USE.
- b. THE COVERING OF METALLIC CONDUIT RISERS AND WOOD BLOCKS OVER THE TOPS OF THE RISERS WILL NOT BE REQUIRED, PROVIDED THE POLE IS GROUNDED IN ACCORDANCE WITH GOVERNING CODES AND TITLE 24, STATE BUILDING STANDARDS; AND PROVIDED ALL METALLIC CONDUITS ARE ADEQUATELY BONDED TO THE POLE MECHANICALLY WITH APPROVED CLAMPS OR CONNECTORS.
- c. A STEEL POLE SHALL BE SET IN AN ADEQUATE CONCRETE FOUNDATION TO ENSURE THE SELF-SUPPORTING CONDITION. THE POLE SHALL BE PAINTED OR, PREFERABLY, GALVANIZED TO PREVENT CORROSION. STEEL POLES SHALL BE OF HEAVY WALL PIPE 3 INCHES OR LARGER IN DIAMETER.

REV	CHAN	IGE		DR	BY	DSN	APV	DATE	REV		CI	1AH	NGE	DR	BY	DSN	APV	DATE	
С									F										
В	FORMAT	ΓΤΙΝ	G	EDM	JIK			12/07/2020	Е										
Α	EDITORIAL	CHA	NGES		LSM	IPJ	TPM	11/01/2017	D										
		Indicates Lat	est Re	vision		Completely Revised New Page Information Removed													
	SHEET				SDG	&E El	ELECTRIC SERVICE STANDARDS & GUIDES												
																SG203.1			
	1 OF 2				(GEN	ERAL IN	FOR	MA	ATION					30203.1				

- THE CUSTOMER-OWNED STEEL SERVICE AND METER POLE MUST BE LOCATED WITHIN A 20' RADIUS FROM A ROAD OR OTHER DRIVABLE SURFACE SO THE UTILITY CAN CONNECT AND MAINTAIN THE SERVICE DROP FROM A BUCKET TRUCK. IF THE SERVICE AND METER POLE CANNOT BE LOCATED WITHIN THE 20' RADIUS, A PERMANENT/CLIMBABLE POLE MUST BE INSTALLED. (b)
- e. CONSULT THE UTILITY FOR APPROVAL IN ALL CASES WHERE A STEEL POLE IS PROPOSED TO BE USED.

ADDRESS MARKING VII.

ALL METER POLES, TEMPORARY OR PERMANENT, MUST HAVE THE NUMERIC PORTION OF THE ADDRESS PERMANENTLY MARKED ON THE POLE OR SERVICE EQUIPMENT.

AVAILABLE SECONDARY FAULT CURRENT VIII.

THE UTILITY'S CONTRIBUTION TO SECONDARY FAULT CURRENT INFORMATION MAY BE FOUND IN SG006. FOR SHORT CIRCUIT CURRENT AND OVERLOAD PROTECTION REQUIREMENTS, CONSULT WITH THE AHJ. (d)

REFERENCE:

- REFER TO SG112.
- REFER TO SG204.
- REFER TO SG205.
- REFER TO SG206.

© 1000 2020 San Diago Cas & Floatric Compar	 All rights reserved. Removal of this copyright notice witho 	ut parmission is not parmitted under law
© 1990 - 2020 Sali Diego Gas & Electric Compar	y. Ali rigitis reserveu. Nemovai oi uns copyrigiti nouce wilho	ut permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK			12/07/2020	Е						
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 2

Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GENERAL INFORMATION

SG203.2



INSTALLATION:

- EXTEND PROTECTIVE COVERING OVER METALLIC CONDUIT TO BOTTOM OF SERVICE HEADS. DO NOT LEAVE CONDUITS EXPOSED.
- (B) SERVICE GROUND TO COMPLY TO CALIFORNIA ELECTRIC CODE AND BE MECHANICALLY PROTECTED IN COMPLIANCE WITH G.O. 95 PER ONE OF THE FOLLOWING METHODS:
 - ENCASED IN RIGID STEEL CONDUIT.
 - 2. MINIMUM NO. 8 AWG ARMORED COPPER GROUND WIRE.
 - 3. COVERED BY A MINIMUM OF:

HARDWOOD MOULDING (OF OAK OR ROCK ELM) 3/8-INCH THICKNESS, OR

DOUGLAS FIR MOULDING 1/2-INCH THICKNESS, OR

RIGID CONDUIT OR RIGID U-SHAPED MOULDING OF A MINIMUM SCHEDULE 40 PVC, OR

POLY PROTECTED GROUND WIRE.

- CUSTOMER TO WIRE OUT 3 FEET BELOW TOP OF POLE.
- WHEN CUSTOMER'S LOAD CONDUCTORS ARE UNDERGROUND, INSTALL CONDUIT AS INDICATED BY DASHED LINES.
- PROVIDE AT LEAST 18 INCHES OF WIRE OUTSIDE OF SERVICE HEAD.
- E F G H J COVERING TO BE STRAPPED TO POLE WITH GALVANIZED TWO-HOLE PIPE STRAPS SPACED NOT TO EXCEED 3 FEET APART.
- COVER TO BE NAILED TO SIDE PIECES.
- INSTALL STRAPS BELOW FIBER CONDUITS TO PREVENT SLIPPING.
- CAP ON BOTTOM AND STRAP TO POLE.
- POLE SETTING DEPTH

TABLE 1

POLE SETTING DEPTH												
HEIGHT	SETTING DEPTH											
25′-0″	5′-0″											
30'-0"	5′-6″											
35′-0″	5′-6″											

- CUSTOMER TO DIG POLE HOLE IN NATURAL SOIL. BACKFILL MUST BE COMPACTED TO 90% MINIMUM WITHIN A 5-FOOT RADIUS OF THE POLE. POLE DEPTH WILL BE CONFIRMED BY INSERTION OF A GROUND ROD OR SIMILAR PROBE INTO THE PCV DEPTH CONDUIT ATTACHED TO CLIMBABLE POLE. INSTALL REMOVABLE CAP ON TOP OF CONDUIT TO PREVENT FALLING DEBRIS ENTERING CONDUIT. GUY WIRES ARE NOT PERMITTED AS A MEANS OF SUPPORTING A METER POLE.
- (M)ALL METER POLES MUST HAVE THE NUMERIC PORTION OF THE STREET ADDRESS FIRMLY ATTACHED AND FACING THE STREET OR DRIVABLE SURFACE. PLASTIC OR METALLIC NUMBERS OF THE TYPE USED FOR HOUSE ADDRESSES ARE ACCEPTABLE.
- (N)ALL CONDUIT FITTINGS MUST BE RAINTIGHT. APPROVED WIRE, NOT LESS THAN NO. 8 AWG, SHALL BE USED IN THE SERVICE ENTRANCE CONDUIT.
- (0)BOLTED TO POLE IN 1/2-INCH GAINS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK			12/07/2020	Е						
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 5

Completely Revised Indicates Latest Revision New Page Information Removed SDG&E SERVICE STANDARDS & GUIDES

CUSTOMER-OWNED SERVICE & METER POLE PERMANENT/CLIMBABLE, 0 - 600V

SG204.2

BILL O	<u>F MATERIALS:</u>							
ITEM		DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS		
1	POLE, TREATED, FULL LENGTH RO	DUND, 25'-0", CLASS 5 MIN.	1					
2	CUSTOMER LOAD CONDUCTORS		AS REQ'D					
2	HOLDER, SERVICE DROP & WIRE		AC DECID					
3	RACK, SERVICE		AS REQ'D					
4	WOOD BLOCK, 4" X 4" X 6"		AS REQ'D					
		PVC, SCHEDULE 40, PLASTIC (PREFERRED)						
5	CONDUIT, SERVICE ENTRANCE	IRON, RIGID, GALV., 3/4" MIN. WITH PROTECTIVE COVERING (ALTERNATE)	AS REQ'D					
6	STRAP, PIPE		AS REQ'D					
7	METER		AS REQ'D					
8	SAFETY SOCKET CAN WITH BYPA	SS TEST FACILITIES (IF REQUIRED)	AS REQ'D					
9	SERVICE GROUND		AS REQ'D					
10	REMOVABLE CAP		AS REQ'D					
11	CONDUIT, PVC, SCHEDULE 40, 6'-	0", 3/4", POLE DEPTH	AS REQ'D					
12	CONDUIT CAP		AS REQ'D					

NOTES:

- (I) MAXIMUM LENGTH OF SERVICE DROP SPAN SHALL BE 100 FEET.
- (II) BLOCK NOT REQUIRED FOR PVC, SCHEDULE 40 PLASTIC CONDUIT RUNS.
- THESE ARE MINIMUM REQUIREMENTS FOR PERMANENT CUSTOMER-OWNED SERVICE AND METER POLES. THEY ARE APPROVED FOR TEMPORARY INSTALLATIONS. (V)

(IV) POLE LOCATION:

- a. POLE SHALL BE SET NOT MORE THAN 100 FEET NOR LESS THAN 10 FEET FROM THE SURFACE OF SDG&E'S SERVICE POLE AND SO LOCATED THAT ALL REQUIRED SERVICE DROP CLEARANCES WILL BE OBTAINED FROM GROUND, BUILDINGS, STRUCTURES AND OTHER CONDUCTORS ON SDG&E'S POLE INCLUDING FOREIGN COMMUNICATION AND SUPPLY CONDUCTORS. IN SELECTING THE POLE LOCATION, CONSIDERATION SHOULD BE GIVEN TO PROVIDING ADEQUATE CLEARANCE IN AREAS WHERE:
 - CONSTRUCTION EQUIPMENT WILL BE OPERATED.
 - CHANGES IN GRADE OF STREETS, DRIVEWAY, AND OTHER LANDS ARE PROPOSED.
 - BUILDINGS OR STRUCTURES ARE PROPOSED TO BE ADDED DURING THE PERIOD OF PERMANENT OR TEMPORARY SERVICE
- b. ADEQUATE CLEARANCE SHALL BE PROVIDED, WHETHER OR NOT SUCH AREAS OF CONFLICT OR OBSTRUCTION ARE ON THE PREMISES SERVED.
- c. Contact SDG&E at any regional project management office and request an electric meter and service location form. (b)

	© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		С	HA	NGE	DR	BY	DSN	APV	DATE
С							F									
В	FORMATTING	EDM	JIK			12/07/2020	Е									
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D									
X Indicates La			evision		Com	pletely Revis	sed		New Page		Information Rer	noved				

SHEET 3 OF 5

CUSTOMER-OWNED SERVICE & METER POLE PERMANENT/CLIMBABLE, 0 – 600V

SDG&E SERVICE STANDARDS & GUIDES

SG204.3

(V)

SERVICE DROP MINIMUM CLEARANCES:

TABLE 2

SERVICE DROP MINIMUM CLEARANCES (VII)												
LOCATION	MIN. CLEARANCE (FT)											
AT CENTER OF STREET OR 12'-0" FROM CURB, WHICHEVER IS LESS	18											
AT CURB LINE	16											
OVER COMMERCIAL OR INDUSTRIAL DRIVEWAYS, PARKING AREAS OR AREAS CAPABLE OF BEING TRAVERSED BY VEHICLES	16											
OVER RESIDENTIAL DRIVEWAYS	12 (VI)											
OVER AGRICULTURAL AREAS	15											
OVER RAILROADS OR FOR OTHER SPECIAL CONDITIONS	CONSULT YOUR SDG&E PROJECT PLANNER											

- MAY BE REDUCED TO 10 FEET IF SELF-SUPPORTING CABLE (SSC) SERVICE. SERVICE DROP CABLE (SSC) SHALL BE USED BY SDG&E. THE TYPE OF CONSTRUCTION USED BY THE CUSTOMER IS THEIR OPTION.
- (VII) WHERE CLEARANCES CANNOT BE OBTAINED WITH THE 25-FOOT POLE SHOWN, A 35-FOOT MAXIMUM POLE SHALL BE USED.
- SAFETY SOCKET CAN WITH TEST-BYPASS FACILITIES IS REQUIRED WHEN POLE IS TO BE USED FOR TEMPORARY SERVICE OR PERMANENT NON-RESIDENTIAL SERVICE. SERVICE EQUIPMENT AND RECEPTACLES MUST BE RAINTIGHT, PROPERLY RATED FOR THE LOAD TO BE SERVED, AND SHALL BE ADEQUATELY BONDED AND GROUNDED.
- RECEPTACLES USED TO CONNECT PORTABLE TOOLS SHALL BE 3-POLE TYPE FOR SINGLE-PHASE MOTORS AND 4-POLE TYPE IX. FOR THREE-PHASE MOTORS, ONE CONTACT TO BE USED FOR GROUNDING CONNECTION. WHERE MORE THAN ONE VOLTAGE TYPE IS USED, RECEPTACLES SHALL BE NON-INTERCHANGEABLE.
- PERMIT AND INSPECTION MUST BE OBTAINED FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) BEFORE XI. SERVICE WILL BE CONNECTED AND A METER SET BY SDG&E
- XII. CONSULT SDG&E FOR SERVICE REQUIREMENTS WHENEVER THREE-PHASE SERVICE IS DESIRED.
- XIII. SDG&E WILL FURNISH AND INSTALL THE METER, SERVICE DROP AND SERVICE DROP RACK OR WIRE HOLDERS, ALL OTHER EQUIPMENT, INCLUDING THE POLE, SHALL BE FURNISHED AND INSTALLED BY THE CUSTOMER.
- XIV. FLOOD LIGHTS, SIGNS, ROPES AND ANY SIMILAR EQUIPMENT SHALL NOT BE ATTACHED TO SERVICE AND METER POLES.
- XV. A TELEPHONE AND/OR CABLE TV SERVICE DROP MAY ATTACH TO A METER POLE PROVIDED:
 - a. THE ATTACHMENT IS OUTSIDE THE CLIMBING SPACE,
 - b. A MINIMUM RADIAL CLEARANCE OF 12 INCHES IS MAINTAINED FROM ANY PORTION OF THE DRIP LOOP, AND
 - c. IT MEETS ALL G.O. 95 REQUIREMENTS.
- XVI. REQUIRED WORK AREA AROUND CLIMBABLE METER AND SERVICE POLES: 8 FEET OF UNOBSTRUCTED RADIAL CLEARANCE AROUND THE POLE IS REQUIRED.
- XVII. REQUIRED WORKING SPACE IN FRONT OF THE METER PANEL: A MINIMUM OF 3-FOOT BY 3-FOOT CLEAR AND LEVEL WORKING SPACE IS REQUIRED IN FRONT OF THE METER PANEL MEASURED FROM FACE OF PANEL.
- XVIII. TO MAINTAIN SAFE, CLEAR AND LEVEL WORKING SPACE IN FRONT OF NEW OR EXISTING NON-RESIDENTIAL METER AND SERVICE EQUIPMENT, A CONCRETE SLAB IS REQUIRED FOR THE FULL WORKING SPACE.(c)

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK			12/07/2020	Е						
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 5

Completely Revised Indicates Latest Revision New Page Information Removed SDG&E SERVICE STANDARDS & GUIDES


CUSTOMER-OWNED SERVICE & METER POLE PERMANENT/CLIMBABLE, 0 - 600V

SG204.4

REFERENCE: REFER TO OH645. (b) REFER TO SG021. REFER TO SG504.5. © 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** CHANGE DR BY DSN APV DATE REV **CHANGE** DR BY DSN APV DATE F **FORMATTING** -- 12/07/2020 Ε В EDM JIK TPM 11/01/2017 **EDITORIAL CHANGES** LSM IPJ **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E SERVICE STANDARDS & GUIDES SHEET SG204.5

5 OF 5

CUSTOMER-OWNED SERVICE & METER POLE PERMANENT/CLIMBABLE, 0 – 600V



INSTALLATION:

- A. NO SDG&E EMPLOYEE SHALL PLACE A LADDER AGAINST OR OTHERWISE CLIMB THE TEMPORARY POLE FOR THE PURPOSE OF INSTALLING, REPAIRING, OR REMOVING THE ELECTRIC SERVICE CONNECTIONS.
- B. TEMPORARY SERVICE OR METER POLES SHALL NOT BE SET AT ANY LOCATION WHERE A CHANGE TO PERMANENT STATUS IS PLANNED.
- C. THE TEMPORARY/NON-CLIMBABLE POLE MUST BE LOCATED WITHIN A 20-FOOT RADIUS FROM A ROAD OR OTHER DRIVABLE SURFACE SO SDG&E CAN CONNECT AND MAINTAIN THE SERVICE DROP FROM A BUCKET TRUCK. TRUCK ACCESS MUST BE MAINTAINED DURING THE PERIOD OF TEMPORARY SERVICE. (1)
- D. ANY SERVICE OR METER POLES THAT CANNOT BE LOCATED WITHIN THE 20-FOOT RADIUS MUST BE BUILT TO THE STANDARD OF A PERMANENT/CLIMBABLE POLE.
- (E) CUSTOMER TO WIRE OUT 3 FEET BELOW TOP OF POLE.
- (F) PROVIDE AT LEAST 18 INCHES OF WIRE OUTSIDE OF SERVICE HEAD.
- (G) WOOD BLOCKS TO BE BOLTED TO POLE WITH 1/2-INCH GAINS. BLOCK NOT REQUIRED FOR SCHEDULE 40 PVC PLASTIC CONDUIT RUNS.
- (H) EXTEND PROTECTIVE COVERING OVER METALLIC CONDUIT TO BOTTOM OF SERVICE HEADS. DO NOT LEAVE CONDUITS EXPOSED.
- (J) INSTALL STRAPS BELOW FIBER CONDUITS TO PREVENT SLIPPING.
- K SERVICE GROUND TO COMPLY TO CALIFORNIA ELECTRIC CODE AND BE MECHANICALLY PROTECTED IN COMPLIANCE WITH G.O. 95 PER ONE OF THE FOLLOWING METHODS:
 - 1. ENCASED IN RIGID STEEL CONDUIT.
 - 2. MINIMUM NO. 8 AWG ARMORED COPPER GROUND WIRE.
 - 3. COVERED BY A MINIMUM OF:
 - HARDWOOD MOULDING (OF OAK OR ROCK ELM) 3/8-INCH IN THICKNESS, OR
 - DOUGLAS FIR MOULDING 1/2-INCH IN THICKNESS, OR
 - RIGID CONDUIT OR RIGID U-SHAPED MOULDING OF A MINIMUM SCHEDULE 40 PVC.
- (L) WHEN CUSTOMER'S LOAD CONDUCTORS ARE UNDERGROUND, INSTALL CONDUIT AS INDICATED BY DASHED LINES.
- (M) COVERING TO BE STRAPPED TO POLE WITH GALVANIZED TWO-HOLE PIPE STRAPS SPACED NOT TO EXCEED 3 FEET APART.
- (N) COVER TO BE NAILED TO THE SIDE PIECES.

Indicates Latest Revision

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	HOLDER, WIRE	AS REQ'D			
1	RACK, SERVICE	AS REQ D	1	1	
	TIMBER, SELF-SUPPORTING, 6" X 6" X 20'-0"				
2	POLE, ROUND, 20'	1			
	POLE, SELF-SUPPORTING, METER, 20'-0"				
3	CONDUCTOR, LOAD, CUSTOMER-OWNED	AS REQ'D			
4	WOOD BLOCK, 4" X 4" X 6"	AS REQ'D		-	
-	CONDUIT, PVC, SCHEDULE 40, PLASTIC (SERVICE ENTRANCE – PREFERRED)	AC DEO/D			
5	CONDUIT, IRON, RIGID, GALV. 3/4" MIN. (SERVICE ENTRANCE – ALTERNATE)	AS REQ'D	-	-	

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	-	-	12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED		JC	TPM	MDJ	08/06/2015	D						

SHEET 2 OF 4 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

CUSTOMER-OWNED SERVICE & METER POLE TEMPORARY/NON-CLIMBABLE, 0 – 600V

Completely Revised

SG205.2

BILL OF MATERIALS (CONT'D):

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
6	STRAP, PIPE	AS REQ'D		1	
7	METER	AS REQ'D			
8	SAFETY SOCKET CAN WITH BYPASS TEST FACILITIES	AS REQ'D			
9	BOXES AND RECEPTACLES, WEATHERPROOF	AS REQ'D		-	
10	SERVICE GROUND	AS REQ'D			

NOTES:

- THESE ARE MINIMUM REQUIREMENTS FOR ALL TEMPORARY SERVICES. TEMPORARY SERVICE IS FOR A PERIOD OF ONE YEAR, OR LESS.
- (II) POLE LOCATION:
 - a. MAXIMUM LENGTH OF SERVICE DROP SHALL BE 100 FEET. POLE SHALL BE SET NOT MORE THAN 100 FEET, NOR LESS THAN 10 FEET, FROM THE SURFACE OF SDG&E'S SERVICE POLE AND SO LOCATED THAT ALL REQUIRED SERVICE DROP CLEARANCES WILL BE OBTAINED FROM GROUND, BUILDINGS, STRUCTURES, AND OTHER CONDUCTORS ON SDG&E'S POLE INCLUDING FOREIGN COMMUNICATION AND SUPPLY CONDUCTORS. IT ALSO MUST BE LOCATED WITHIN A 20-FOOT RADIUS FROM A ROAD OR OTHER DRIVABLE SURFACE SO SDG&E CAN CONNECT AND MAINTAIN THE SERVICE DROP FROM A BUCKET TRUCK. IN SELECTING THE POLE LOCATION, CONSIDERATION SHOULD BE GIVEN TO PROVIDING ADEQUATE CLEARANCE IN AREAS WHERE:
 - CONSTRUCTION EQUIPMENT WILL BE OPERATED.
 - CHANGES IN GRADE OF STREETS, DRIVEWAY, AND OTHER LANDS ARE PROPOSED.
 - BUILDINGS OR STRUCTURES ARE PROPOSED TO BE ADDED DURING THE PERIOD OF PERMANENT OR TEMPORARY SERVICE.
 - b. ADEQUATE CLEARANCE SHALL BE PROVIDED, WHETHER OR NOT SUCH AREAS OF CONFLICT OR OBSTRUCTION ARE ON THE PREMISES SERVED.
 - CONTACT SDG&E AT ANY REGIONAL PROJECT MANAGEMENT OFFICE AND REQUEST AN ELECTRIC METER & SERVICE LOCATION FORM. (b)
- (III) SERVICE DROP MINIMUM CLEARANCES:

TABLE 1

SERVICES DROP MINIMUM CLEAR	ANCES
LOCATION	MIN. CLEARANCE (FT)
AT CENTER OF STREET OR 12'-0" FROM CURB, WHICHEVER IS LESS	18
AT CURB LINE	16
OVER COMMERCIAL OR INDUSTRIAL DRIVEWAYS, PARKING AREAS OR AREAS CAPABLE OF BEING TRAVERSED BY VEHICLES	16
OVER RESIDENTIAL DRIVEWAYS	12 (IV)
OVER AGRICULTURAL AREAS	15
OVER RAILROADS OR FOR OTHER SPECIAL CONDITIONS	CONSULT YOUR SDG&E PROJECT PLANNER

- MAY BE REDUCED TO 10 FEET IF SELF-SUPPORTING CABLE (SSC) SERVICE. SERVICE DROP CABLE (SSC) SHALL BE USED BY SDG&E. THE TYPE OF CONSTRUCTION USED BY THE CUSTOMER IS THEIR OPTION.
- (V) WHERE CLEARANCES CANNOT BE OBTAINED WITH THE 20-FOOT POLE SHOWN, A PERMANENT/CLIMBABLE POLE IS REQUIRED.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			12/07/2020	F						
В	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED	-	JC	TPM	MDJ	08/06/2015	D						

SHEET 3 OF 4

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CUSTOMER-OWNED SERVICE & METER POLE TEMPORARY/NON-CLIMBABLE, 0 – 600V

SG205.3

NOTES (CONT'D.):

- ALL CONDUIT FITTINGS MUST BE RAINTIGHT. APPROVED WIRE, NOT LESS THAN NO. 8 AWG, SHALL BE USED IN THE SERVICE ENTRANCE CONDUIT. SEE FIGURE 2 FOR RIGID IRON PROTECTIVE COVERING.
- VII) FURNISHED & INSTALLED BY SDG&E.
- SAFETY SOCKET CAN WITH TEST-BYPASS FACILITIES IS REQUIRED WHEN POLE IS TO BE USED FOR TEMPORARY/
 CONSTRUCTION POWER. SERVICE EQUIPMENT AND RECEPTACLES MUST BE RAINTIGHT, PROPERLY RATED FOR THE LOAD TO
 BE SERVED, AND SHALL BE ADEQUATELY BONDED AND GROUNDED.
- (IX) RECEPTACLES USED TO CONNECT PORTABLE TOOLS SHALL BE 3-POLE TYPE FOR SINGLE-PHASE MOTORS AND 4-POLE TYPE FOR THREE-PHASE MOTORS, ONE CONTACT TO BE USED FOR GROUNDING CONNECTION. WHERE MORE THAN ONE VOLTAGE TYPE IS USED, RECEPTACLES SHALL BE NON-INTERCHANGEABLE.
- XI. PERMIT AND INSPECTION MUST BE OBTAINED FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) BEFORE SERVICE WILL BE CONNECTED AND A METER SET BY SDG&E.
- XII. CONSULT SDG&E FOR SERVICE REQUIREMENTS WHENEVER THREE-PHASE SERVICE IS DESIRED.
- XIII. FLOOD LIGHTS, SIGNS, ROPES AND ANY SIMILAR EQUIPMENT SHALL NOT BE ATTACHED TO SERVICE AND METER POLES.
- XIV. COVERING OF METALLIC CONDUIT WILL NOT BE REQUIRED ON METAL POLES, PROVIDED THE METAL POLE IS EFFECTIVELY GROUNDED AND PROVIDED ALL METALLIC CONDUITS ARE ADEQUATELY BONDED TO THE METAL POLE WITH APPROVED CLAMPS OR CONNECTORS.
- ALL METER POLES MUST HAVE THE NUMERIC PORTION OF THE STREET ADDRESS FIRMLY ATTACHED AND FACING THE STREET OR DRIVABLE SURFACE. PLASTIC OR METALLIC NUMBERS OF THE TYPE USED FOR HOUSE ADDRESSES ARE ACCEPTABLE.
- XVI. A TELEPHONE AND/OR CABLE TV SERVICE DROP MAY ATTACH TO A METER POLE PROVIDED:
 - a. THE ATTACHMENT IS OUTSIDE THE CLIMBING SPACE,
 - b. A MINIMUM RADIAL CLEARANCE OF 12 INCHES IS MAINTAINED FROM ANY PORTION OF THE DRIP LOOP, AND
 - c. IT MEETS ALL G.O. 95 REQUIREMENTS.
- XVII. REQUIRED WORKING SPACE IN FRONT OF THE METER PANEL: A MINIMUM 3-FOOT BY 3-FOOT CLEAR AND LEVEL WORKING SPACE IS REQUIRED IN FRONT OF THE METER PANEL MEASURED FROM FACE OF PANEL.
- XVIII. TO MAINTAIN SAFE, CLEAR AND LEVEL WORKING SPACE IN FRONT OF NEW OR EXISTING NON-RESIDENTIAL METER AND SERVICE EQUIPMENT, A CONCRETE SLAB IS REQUIRED FOR THE FULL WORKING SPACE. (C)
- XIX SELF-SUPPORTING METER POLE SHALL MEET EQUIVALENT STRENGTH REQUIREMENTS.

REFERENCE:

- a. REFER TO OH646 TEMPORARY SERVICE AND METER POLES.
- (b) REFER TO SG021.
- (c) REFER TO SG504.5.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	-		12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED		JC	TPM	MDJ	08/06/2015	D						

SHEET 4 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CUSTOMER-OWNED SERVICE & METER POLE TEMPORARY/NON-CLIMBABLE, 0 – 600V

SG205.4

SCOPE: THIS SERVICE GUIDE DESCRIBES PERMANENT OR TEMPORARY INSTALLATION OF CUSTOMER-OWNED SERVICE OR METER POLE WITH MULTIPLE METERS.



INSTALLATION: NONE

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	LINE GUTTER, SEALABLE	AS REQ'D			
2	POLE, SERVICE & METER, APPROVED	AS REQ'D			
3	BACKBOARD, PLYWOOD, EXTERIOR GRADE, 3/4" MIN	AS REQ'D			
4	THRU BOLT, NUT & BOLT ASSY, 1/2" (TYP)	AS REQ'D			
5	METER	AS REQ'D			
6	METER SERVICE DISCONNECTS	AS REQ'D			
7	TREATED WOOD, 4" X 4"	AS REQ'D		-	

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED		JC	TPM	MDJ	08/06/2015	D						

SHEET 1 OF 2 Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CUSTOMER-OWNED SERVICE & METER POLE WITH MULTIPLE METERS PERMANENT OR TEMPORARY INSTALLATION SG206.1

Information Removed

NOTES:

- I. A LINE GUTTER IS REQUIRED WHEN SERVING FOUR OR MORE METERS. A SECOND RISER FOR TWO METERS, OR A THIRD RISER FOR THREE METERS, MAY BE INSTALLED IN PLACE OF A LINE GUTTER. VERIFY METHOD OF INSTALLATION WITH THE SDG&E PLANNER AND THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) PRIOR TO START OF CONSTRUCTION.
- II. THIS APPLICATION IS LIMITED TO A SINGLE-PHASE OR THREE-PHASE SERVICE, 600 AMPS MAXIMUM. A MAIN SWITCH IS REQUIRED AHEAD OF MORE THAN 6 METER SERVICE DISCONNECTS. THERE IS NO LIMIT TO THE NUMBER OF METERS THAT CAN BE INSTALLED PER THIS STANDARD.
- III. WHEN THE INSTALLATION IS PERMANENT, NO RISERS, WIRE, OR EQUIPMENT ARE PERMITTED ON THE REAR HALF OF THE METER POLE IN ORDER TO PROVIDE THE LEGALLY REQUIRED CLIMBING SPACE.
- (IV) BUS DUCT OR CABLE MAY BE USED FOR SERVICE ENTRANCE CONDUCTORS IN LINE GUTTER.
- (V) DISTANCE BETWEEN POLE AND POST AS REQUIRED.

REFERENCE:

- (a) REFER TO SG503 FOR SEALING REQUIREMENTS.
- (b) REFER TO SG204 OR SG205, WHICHEVER IS APPLICABLE.

@ 1000 2020 Can Diago Cao 9 Floatrio Company	All rights recomined Democral of this constricts notice without	· naumicaian ia nat naumittadndau la
(C) 1998 - 2020 San Diego Gas & Flectic Company	All rights reserved. Removal of this copyright notice without	permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED		JC	TPM	MDJ	08/06/2015	D						·

New Page

Information Removed

SHEET 2 OF 2

CUSTOMER-OWNED SERVICE & METER POLE
WITH MULTIPLE METERS
PERMANENT OR TEMPORARY INSTALLATION

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Completely Revised

SG206.2

SCOPE: THIS SERVICE GUIDE DESCRIBES THE INSTALLATION OF CUSTOMER OWNED PERMANENT OR TEMPORARY UNDERGROUND SERVICE WITH MULTIPLE METERS.




FIGURE 1

INSTALLATION: NONE

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	PLYWOOD BACKBOARD, EXTERIOR GRADE, 3/4" MIN.	AS REQ'D			
2	THRU BOLT, NUT & BOLT ASSY, 1/2" (TYP)	AS REQ'D			
3	PULL CAN	AS REQ'D			
4	STRAP, PIPE	AS REQ'D			
5	WOOD, TREATED, 4" X 4"	AS REQ'D			
6	CONDUIT, PVC, SCHEDULE 80	AS REQ'D			
7	METER	AS REQ'D			

NOTES:

- I. CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE:
 - a. POST, TERMINATING AND METER ENCLOSURE, TRENCH, CONDUIT AND CONDUIT RISER TO SDG&E'S EQUIPMENT, OR AS DIRECTED BY THE SDG&E INSPECTOR.
 - b. PROVIDE SHADE MATERIAL AND BACKFILL TO FINISHED GRADE AFTER CONDUIT HAS BEEN INSTALLED, INSPECTED, AND APPROVED BY THE SDG&E INSPECTOR.

REFERENCE:

- (a) REFER TO SECTION 700; ELECTRIC TERMINATING ENCLOSURES.
- (b) REFER TO SG309; UNDERGROUND ELECTRIC SERVICE LATERAL CONDUIT REQUIREMENTS.

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK		-	12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED		JC	TPM	MDJ	08/06/2015	D						

SHEET 1 OF 1 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CUSTOMER-OWNED SERVICE WITH MULTIPLE METERS FOR UNDERGROUND PERMANENT OR TEMPORARY INSTALLATION

SG207.1

SCOPE: THIS SERVICE GUIDE DESCRIBES THE INSTALLATION OF TEMPORARY SERVICE FROM SDG&E HANDHOLES TO CUSTOMER-OWNED SERVICE AND METERS.




FIGURE 1

INSTALLATION:

- A. CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE:
 - (1) POST, TERMINATING AND METER ENCLOSURE, TRENCH, CONDUIT AND CONDUIT RISER TO SDG&E'S SECONDARY HANDHOLE AS ILLUSTRATED ABOVE.
 - 2 PROVIDE SHADE MATERIAL AND BACKFILL TO FINISHED GRADE AFTER CONDUIT HAS BEEN INSTALLED, INSPECTED AND APPROVED BY SDG&E'S INSPECTOR.
- B. SDG&E WILL FURNISH AND INSTALL AT CUSTOMER'S EXPENSE:
 - SERVICE LATERAL CONDUCTORS FROM CUSTOMER'S METER PANEL ON POST TO SDG&E'S SECONDARY HANDHOLE AND REMOVE SERVICE LATERAL CONDUCTORS AT DISCONTINUANCE OF SERVICE.
- C. SERVICE AND METER INSTALLATION SHALL COMPLY WITH LOCAL CODES AND STATE OF CALIFORNIA DIVISION OF INDUSTRIAL SAFETY REGULATIONS, AND SHALL BE SUBJECT TO INSPECTION CLEARANCE BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK		-	12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES		JC	BRB	MDJ	08/06/2015	D						
						•			•				

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TEMPORARY SERVICE FROM SDG&E HANDHOLE TO CUSTOMER-OWNED SERVICE & METER INSTALLATION SG208.1

BILL OF MATERIALS: STANDARD STOCK **DESIGN** ITEM DESCRIPTION QUANTITY **PAGE** NUMBER UNITS POST, 4" X 4" MIN. 1 AS REQ'D STRAP, PIPE AS REQ'D 2 ------3 SERVICE GROUND AS REQ'D --4 CONDUIT, BEND AND RISERS AS REQ'D --5 CONDUCTOR, LOAD, CUSTOMER OWNED AS REQ'D 6 HANDHOLE, SECONDARY, SDG&E OWNED AS REQ'D 7 SAFETY SOCKET CAN WITH TEST-BYPASS FACILITIES AS REQ'D MATN AS REQ'D

NOTES:

- (I)FOR SINGLE-PHASE, 2" CONDUIT WITH 2'-0" MIN. RADIUS REQUIRED. FOR THREE-PHASE, 3" CONDUIT WITH 3'-0" RADIUS REQUIRED. (a)
- (II)REQUIRED FOR ALL TEMPORARY SERVICE UP TO 200A.(b)
- III. SERVICE METHOD SHOWN IS FOR A MAXIMUM OF 200A. FOR GREATER CAPACITY, CONTACT THE SDG&E PLANNER.
- CONTACT THE PLANNER AT THE NEAREST SDG&E REGIONAL PROJECT MANAGEMENT OFFICE FOR AN ELECTRIC METER AND IV. SERVICE LOCATION FORM AND NEGOTIATION OF TEMPORARY SERVICE CHARGES. (d)
- ٧. WHERE THE CUSTOMER PROPOSES TO EXTEND TEMPORARY OVERHEAD CONDUCTORS VIA CUSTOMER-OWNED LINES, A 6" X 6" X 20'-0" MINIMUM SELF-SUPPORTING POLE SHALL BE SUBSTITUTED FOR THE 4" X 4" MINIMUM POST SHOWN.

REFERENCE:

- REFER TO SG309 NOTE C. (a)
- REFER TO SG210 FOR TSPB AND SG513.1 FOR TSPB EXCEPTION.

Indicates Latest Revision

- SERVICE GROUND TO COMPLY WITH CALIFORNIA ELECTRICAL CODE.
- REFER TO SG021.

Completely Revised

				•						•			
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
A	EDITORIAL CHANGES		JC	BRB	MDJ	8/06/2015	D						•

SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


New Page

Information Removed

TEMPORARY SERVICE FROM SDG&E HANDHOLE TO CUSTOMER-OWNED SERVICE & METER INSTALLATION

SG208.2

SCOPE: THIS SERVICE GUIDE DESCRIBES INSTALLATION OF TEMPORARY SERVICE FROM AN SDG&E POLE OR PADMOUNT TRANSFORMER TO CUSTOMER-OWNED SERVICE AND METER.



INSTALLATION:

- A. CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AT THEIR EXPENSE:
 - (1) POST, SAFETY SOCKET METER CAN, TRENCH, CONDUIT AND CONDUIT RISER AS ILLUSTRATED ABOVE.
 - (2) SHADING MATERIAL AND BACKFILL TO FINISHED GRADE AFTER CONDUIT HAS BEEN INSTALLED, INSPECTED AND APPROVED BY SDG&E'S INSPECTOR.
- B. SDG&E WILL FURNISH AND INSTALL AT CUSTOMER'S EXPENSE:
 - 1 SERVICE LATERAL CONDUCTORS FROM CUSTOMER'S METER PANEL ON POST TO SDG&E'S POLE OR PADMOUNT TRANSFORMER. SDG&E WILL REMOVE SERVICE LATERAL CONDUCTORS AT DISCONTINUANCE OF SERVICE.
- C. THE SERVICE AND METER INSTALLATION SHALL COMPLY WITH LOCAL CODES AND STATE OF CALIFORNIA DIVISION OF INDUSTRIAL SAFETY REGULATIONS, AND SHALL BE SUBJECT TO INSPECTION CLEARANCE BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).

© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES		JC	BRB	MDJ	08/06/2015	D						
				_									

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TEMPORARY SERVICE FROM SDG&E POLE OR PADMOUNT TRANSFORMER TO CUSTOMER-OWNED SERVICE & METER INSTALLATION

SG209.1

- ALTERNATE DIRECTION OF SERVICE TRENCH. TERMINATE TRENCH AT LOCATION THAT WILL PERMIT SERVICE TO ENTER SIDE OF SECONDARY COMPARTMENT.
- (E) 24-INCH MINIMUM RADIUS BEND REQUIRED.

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	POST, 4" X 4" MIN.	AS REQ'D			
2	DEADFRONT SINGLE-PHASE PADMOUNT TRANSFORMER SECONDARY AREA	AS REQ'D			
3	LIVEFRONT OR THREE-PHASE PADMOUNT TRANSFORMER SECONDARY AREA	AS REQ'D			
4	SERVICE GROUND	AS REQ'D			
5	COMPARTMENT, SECONDARY	AS REQ'D			
6	PADMOUNT TRANSFORMER OR POLE, SDG&E-OWNED	AS REQ'D			
7	CONDUCTOR, LOAD, CUSTOMER-OWNED	AS REQ'D			
8	STRAP, PIPE	AS REQ'D			
9	CONDUIT, 2", BEND AND RISER	AS REQ'D			
10	MAIN	1			
11	SAFETY SOCKET CAN WITH TEST BY-PASS FACILITIES	AS REQ'D			

NOTES:

- (I)SAFETY SOCKET CAN WITH TEST BY-PASS FACILITIES REQUIRED FOR ALL TEMPORARY SERVICES.
- II. THE SERVICE METHOD SHOWN IS FOR A MAXIMUM OF 200 AMPS. FOR GREATER CAPACITY, CONTACT THE SDG&E PLANNER.
- III. WHERE THE CUSTOMER PROPOSES TO EXTEND TEMPORARY OVERHEAD CONDUCTORS VIA CUSTOMER-OWNED LINES, A 6-INCH X 6-INCH X 20-FOOT MINIMUM SELF-SUPPORTING POLE SHALL BE SUBSTITUTED FOR THE 4-INCH X 4-INCH MINIMUM POST SHOWN.
- IV. CONTACT THE PLANNER AT THE NEAREST SDG&E REGIONAL PROJECT MANAGEMENT OFFICE FOR AN ELECTRIC METER AND SERVICE LOCATION FORM AND NEGOTIATION OF TEMPORARY SERVICE CHARGES. (b)

REFERENCE:

- SERVICE GROUND TO COMPLY WITH CALIFORNIA ELECTRICAL CODE.
- (b) REFER TO SG021.
- WHEN SERVICE IS PROVIDED FROM AN OVERHEAD POLE, SEE SG315 FOR CABLE POLE RISER INSTALLATION.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DA
0	FORMATTING	FDM	ПК			12/07/2020	F						

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK			12/07/2020	F						
В	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES		JC	BRB	MDJ	08/06/2015	D						


© 1998 - 2020 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

SHEET 2 OF 2

Completely Revised New Page Information Removed Indicates Latest Revision SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TEMPORARY SERVICE FROM SDG&E POLE OR PADMOUNT TRANSFORMER TO CUSTOMER-OWNED SERVICE & METER **INSTALLATION**

SG209.2



1 OF 2

TEMPORARY SERVICE TO PERMANENT SERVICE & METERING EQUIPMENT (TSPB)

INSTALLATION:

- A. FOUNDATION TO BE INSTALLED PRIOR TO SERVICE CONNECTION AND METER SET.
- B. THE TERMINATING ENCLOSURE SHALL BE MOUNTED ON PERMANENT STUDDING OR ON TEMPORARY 2" X 4" SUPPORTING STRUCTURE. BRACES SHOWN, AND ANY ADDITIONAL BRACES, SHALL BE PROVIDED AS NECESSARY TO SUBSTANTIALLY SUPPORT THE PERMANENT FACILITIES. SERVICE CONNECTION AND METER SET IS SUBJECT TO THE AHJ'S (AUTHORITIES HAVING JURISDICTION) AND SDG&E'S APPROVAL OF THE SUITABILITY OF THE SUPPORTING STRUCTURE AND BRACING.
- C. SERVICE LATERAL CONDUIT TO BE CONNECTED TO TERMINATING ENCLOSURE WITH HUB OR SUPPORTED WITH REINFORCEMENT PLATE TO PREVENT BREAK AWAY OF KNOCKOUT RINGS.
- D. BONDING AND GROUNDING PROVISIONS SHALL BE INSTALLED PRIOR TO INSTALLATION OF UNDERGROUND SERVICE LATERAL CONDUCTORS. (c)

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	FOUNDATION AREA	AS REQ'D			
2	CONDUIT, SERVICE, PERMANENT	AS REQ'D			
3	SILL	AS REQ'D			

NOTES:

- I. RESIDENTIAL METER PANEL IS ACCEPTABLE FOR USE IN TSPB APPLICATIONS.
- (II) VARIABLE FOUNDATION DETAILS NOT SHOWN.
- III. THIS INSTALLATION IS SUBJECT TO THE APPROVAL OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).
- IV. TEMPORARY SERVICE SUPPLIED IN ACCORDANCE WITH THIS STANDARD IS SUBJECT TO THE CONTINUING APPROVAL OF THE AHJ THROUGHOUT THE BUILDING CONSTRUCTION PERIOD.
- V. USE OF THIS SERVICE IS NOT INTENDED FOR DWELLING OR COMMERCIAL PURPOSES PRIOR TO FINAL INSPECTION CLEARANCE. SERVICE IS SUBJECT TO DISCONNECTION AND METER REMOVAL IF USED FOR OTHER THAN TEMPORARY CONSTRUCTION POWER.
- VI. THE UTILITY WILL FURNISH AND INSTALL THE SERVICE LATERAL CONDUCTORS AND CONNECT DIRECTLY TO THE LANDING LUGS.
- VII. CONTACT THE PLANNER AT THE NEAREST SDG&E REGIONAL PROJECT MANAGEMENT OFFICE TO THE JOB LOCATION FOR AN ELECTRIC METER AND SERVICE LOCATION FORM. (d)
- VIII. TEMPORARY SERVICE ON A PERMANENT BASE (TSPB) IS NOT PERMITTED WHEN THE METER PANEL IS TO BE LOCATED IN A METER CABINET, METER ROOM OR NON-RESIDENTIAL INSTALLATIONS.

REFERENCE:

- (a) SEE SECTION 500 FOR APPROVED COMBINATION PULL AND METER CANS.
- (b) REFER TO SG309 FOR CUSTOMER-OWNED RIGID SERVICE CONDUIT REQUIREMENTS.
- (c) REFER TO CALIFORNIA ELECTRICAL CODE.
- (d) SEE SG021.
- e. FOR TRENCH INFORMATION, SEE UG3370 FOR SAN DIEGO COUNTY AND UG3371 FOR ORANGE COUNTY.

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CH	IAN	IGE	DR	BY	DSN	APV	DATE
С	FORMAT	TING	EDM	JIK			12/07/2020	F									
В	EDITORIAL C	CHANGES		LSM	IPJ	TPM	11/01/2017	Е									
Α	NO CHANGES-R	EAFFIRMED		JC	BRB	MDJ	08/06/2015	D									
		X Indicates Latest Revision Completely Revised New Page Information Removed															
	SHEET		SDG&E ELECTRIC SERVICE STANDARDS & GUIDES														
															S	G21	0.2
	2 OF 2			TEI	MPO	rar	Y SERVI	CE T	О	PERMAN	ΕN	ΙΤ			•		

SERVICE & METERING EQUIPMENT (TSPB)

PAGE #	SUBJECT
302	ALPHABETICAL SUBJECT INDEX
303	CUSTOMER AND UTILITY RESPONSIBILITIES FOR UNDERGROUND INSTALLATION TO REPLACE OVERHEAD ELECTRIC SERVICE
304	ACCEPTABLE METHODS FOR RESIDENTIAL ELECTRIC SERVICE CONVERSION
305	OVERHEAD TO UNDERGROUND SERVICE CONVERSION – CONTRACTOR AND SDG&E CREW COORDINATION METHODS
306	FIELD HEATING SERVICE LATERAL CONDUITS
307	SAFETY OVERFLOW FITTING FOR INDOOR USE ONLY ON WALL-MOUNTED SERVICE EQUIPMENT
309	UNDERGROUND ELECTRIC SERVICE LATERAL CONDUIT REQUIREMENTS
310	UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE)
311	PRIMARY AND SECONDARY VOLTAGE UNDERGROUND SYSTEM ON CUSTOMER PREMISES FROM CABLE POLE
312	CUSTOMER-OWNED CONDUIT BEND AND RISER AT BUILDING
313	STANDARD JOINT CABLE POLE RISER POSITION USING LADDER ARM BRACKE AND SINGLE RISER
314	CABLE POLE QUADRANT AND RISER IDENTIFICATION
315	UNDERGROUND ELECTRIC CABLE POLE RISER INSTALLATION
316	UNDERGROUND ELECTRIC SERVICE LATERAL GASOLINE DISPENSING AND SERVICE STATIONS
317	UNDERGROUND ELECTRIC SERVICE LATERAL AND METER PANELS IN PROXIMITY TO PROPANE TANKS
318	UNDERGROUND ELECTRIC SERVICE NEAR GASOLINE DISPENSING EQUIPMENT AND PROPANE TANKS
319	UNDERGROUND ELECTRIC SERVICE LATERAL FROM LEACH FIELDS
320	EXISTING SIDA SERVICE FOR PANEL REWIRES, UPGRADES, AND RELOCATIONS

© 1998 – 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	SG308 MOVED TO FMO	EDM	JIK	IPJ	CZH	02/08/2021	F						
В	ADDED SG 320	-	CSE	IPJ	CZH	04/13/2020	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D	FORMATTING	EDM	JIK	-	-	07/19/2021

SHEET 1 OF 1 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC SERVICE TABLE OF CONTENTS

SG301

SUBJECT	<u>PAGE</u>
ACCEPTABLE METHODS FOR RESIDENTIAL ELECTRIC SERVICE CONVERSION	304.1 – 304.2
CABLE POLE QUADRANT AND RISER IDENTIFICATION	314.1 – 314.3
CABLE POLE RISER INSTALLATION	315.1 – 315.5
CABLE POLE RISER POSITION USING LADDER ARM BRACKET AND SINGLE RISER	313.1 – 313.2
CONDUIT BEND AND RISER AT BUILDING, CUSTOMER-OWNED	312.1 – 312.2
CONDUIT SEALING	308.1 – 308.2
CONDUIT, SAFETY OVERFLOW FITTING	307
CONVERSIONS	2, 305.1 – 305.2
CUSTOMER AND UTILITY RESPONSIBILITIES FOR UNDERGROUND INSTALLATION TO REPLACE OVERHEAD ELECTRIC SERVICE	303
CUSTOMER-OWNED CONDUIT BEND AND RISER AT BUILDING	312.1 – 312.2
FIELD HEATING SERVICE LATERAL CONDUITS	306
GASOLINE DISPENSING AND SERVICE STATIONS, UNDERGROUND ELECTRIC SERVICE LATERAL CLEARANCES	316, 318
LEACH FIELDS, UNDERGROUND ELECTRIC SERVICE LATERAL CLEARANCES	319
OVERHEAD TO UNDERGROUND SERVICE CONVERSION CONTRACTOR AND SDG&E CREW COORDINATION METHODS	305.1 – 305.2
PRIMARY AND SECONDARY VOLTAGE UNDERGROUND SYSTEM ON CUSTOMER PREMISES FROM CABLE POLE	311.1 – 311.2
PROPANE TANKS, UNDERGROUND ELECTRIC SERVICE LATERAL AND METER PANEL CLEARANCES	'.1 – 317.2, 318
RESIDENTIAL ELECTRIC SERVICE CONVERSION	304.1 – 304.2
SAFETY OVERFLOW FITTING FOR INDOOR USE ONLY ON WALL-MOUNTED SERVICE EQUIPMENT	307
STANDARD JOINT CABLE POLE RISER POSITION USING LADDER ARM BRACKET AND SINGLE RISER	313.1 – 313.2
UNDERGROUND ELECTRIC CABLE POLE RISER INSTALLATION	315.1 – 315.5
UNDERGROUND ELECTRIC SERVICE LATERAL AND METER PANELS IN PROXIMITY TO PROPANE TANKS	317.1 – 317.2
UNDERGROUND ELECTRIC SERVICE LATERAL FROM LEACH FIELDS	319

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
A	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D		·				

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC SERVICE ALPHABETICAL SUBJECT INDEX

SG302.1

<u>SUBJECT</u>	<u>PAGE</u>
UNDERGROUND ELECTRIC SERVICE LATERAL GASOLINE DISPENSING AND SERVICE STATIONS	316
UNDERGROUND ELECTRIC SERVICE LATERAL RESIDENTIAL OR COMMERCIAL	309.1 – 309.3
UNDERGROUND ELECTRIC SERVICE NEAR GASOLINE DISPENSING EQUIPMENT AND PROPANE TANKS	318
UNDERGROUND PRIMARY SYSTEM FROM CABLE POLE TO PADMOUNT TRANSFORMER	311.1 – 311.2
UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE)	310.1 – 310.2

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

								17 0 1					
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	1	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 2 OF 2

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC STANDARDS & GUIDES


UNDERGROUND ELECTRIC SERVICE ALPHABETICAL SUBJECT INDEX

SG302.2

SCOPE: THIS STANDARD DESCRIBES CUSTOMER AND UTILITY RESPONSIBILITIES FOR AN UNDERGROUND INSTALLATION TO REPLACE AN OVERHEAD ELECTRIC SERVICE.

ATTENTION:

* BEFORE STARTING CONSTRUCTION, OBTAIN AN "ELECTRIC METER & SERVICE LOCATION" FORM FROM SDG&E DESIGN & PROJECT MANAGEMENT. APPLY ONLINE ON THE SDG&E BUILDER SERVICES PORTAL AT: https://www.sdqe.com/apply-service.



INSTALLATION:

- (A) TO BE REMOVED BY CUSTOMER.
- (B) TO BE REMOVED BY UTILITY.
- (c) conduit, elbow, pull can or utility pull section, and wiring on building to be installed by customer.
- (D) CUSTOMER TO PROVIDE TRENCH, BACKFILL AND PAVEMENT REPAIR.

CUSTOMER TO FURNISH, INSTALL, OWN AND MAINTAIN:

- (E) CONDUIT AS SPECIFIED BY SDG&E ON THE CONVERSION SERVICE ORDER.
- (F) TRENCH PER SDG&E STANDARDS. BACKFILL SHALL BE COMPACTED IN ACCORDANCE WITH SDG&E AND LOCAL GOVERNMENTAL REQUIREMENTS.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															<i>I</i> .		
REV	CHAN	CHANGE			BY	DSN	APV	DATE	REV		CH	A۱	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES				IPJ	IPJ	KRG	08/31/2023	F									
В	FORMA ⁻	FORMATTING			JIK	-	-	07/19/2021	Е									
Α	EDITORIAL CHANGES				LSM	IPJ	TPM	11/01/2017	D		TABLE	· U	PDATE	PS	JTM	JTM	KRG	01/03/2025
X Indicates Latest Revision Com								npletely Revi	sed		New Page		Information Rem	oved				
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																		

SHEET 1 OF 2

CUSTOMER & UTILITY RESPONSIBILITIES FOR UNDERGROUND INSTALLATION TO REPLACE OVERHEAD ELECTRIC SERVICE

SG303.1

INSTALLATION (CONT'D):

TABLE 1:

CONDUIT RISER BEND	MINIMUM BENDING RADII							
BEND SIZE (IN)	RADIUS (IN)							
2	24							
3	36							
4	36							
5	48							

- (G) CONDUIT RISER BENDS SIZE AND MINIMUM BENDING RADIUS SHOWN IN TABLE 1. MINIMUM SCHEDULE 40 PVC REQUIRED. **DO NOT CUT BENDS.**
- (H) TYPE & SCHEDULE OF CONDUIT PER THE BUILDING INSPECTOR'S REQUIREMENTS. NORMALLY, SCHEDULE 40 PVC IS ALLOWED INSIDE THE BUILDING WALL, AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH THE APPROPRIATE BUILDING INSPECTOR. FLEX CONDUIT IS NOT PERMITTED. (b)

BILL OF MATERIALS: NONE

NOTES:

- $oxed{(\mathrm{I})}$ depth of trench is determined by type of substructure at source, verify with SDG&E inspector prior to excavation.
- $\left(ext{II} \;
 ight)$ Customer or utility depending on conversion rule. Consult with Planner.
- (III) SOURCE: MANHOLE, HANDHOLE OR PADMOUNT TRANSFORMER.

Indicates Latest Revision

REFERENCE:

- $\left(\mathsf{a} \;
 ight)$ see SG304 installation notes A-F for cable and conduit responsibilities between property line and structure.
- (b) SEE SG306 FOR FIELD HEATING SERVICE LATERAL CONDUIT, AND CONSULT WITH THE SDG&E TRENCH INSPECTOR.

0 4000 000E 0 B: 0 0 E: 1: 0		
© 1998 - 2025 San Diego Gas & Electric Company	All rights reserved. Removal of this copyright notice without	permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/31/2023	F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D	TABLE UPDATE	PS	JTM	JTM	KRG	01/03/2025

New Page

Information Removed


SHEET 2 OF 2

CUSTOMER & UTILITY RESPONSIBILITIES FOR UNDERGROUND INSTALLATION TO REPLACE OVERHEAD ELECTRIC SERVICE

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Completely Revised

SG303.2



INSTALLATION:

- A. THE CUSTOMER WILL PROVIDE A SUITABLE TRENCH FROM THE CONDUIT RISER TO THE PROPERTY LINE, OR SOURCE. CONSULT WITH A PLANNER. (a)
- B. THE CUSTOMER WILL PROVIDE AND INSTALL A SUITABLE CONDUIT FROM THE ELBOW TO THE PROPERTY LINE, OR SOURCE. CONSULT WITH A PLANNER.
- C. THE CUSTOMER WILL PROVIDE AND INSTALL ALL EQUIPMENT NEEDED TO MODIFY THE SERVICE ENTRANCE WHEN CHANGING FROM OVERHEAD TO UNDERGROUND SERVICE. THE CUSTOMER WILL ALSO REMOVE ALL THEIR EXISTING SERVICE EQUIPMENT NO LONGER REQUIRED UPON COMPLETION OF SERVICE CONVERSION TO UNDERGROUND.
- D. SDG&E (UTILITY) WILL FURNISH AND INSTALL UG SERVICE LATERAL CONDUCTORS AND MAKE CONNECTIONS AT THE SERVICE PULL CAN.
- E. THE METER ADAPTER SHOWN IN FIGURE 2 IS APPROVED FOR SINGLE-METER RESIDENTIAL EQUIPMENT INSTALLATIONS ONLY. MULTIPLE METER CONVERSIONS WILL REQUIRE USE OF A LINE GUTTER OR MULTIPLE METER SERVICE EQUIPMENT
- (F) IF SERVICE ENTRANCE CONDUCTORS ARE ENERGIZED, THE CONTRACTOR IS RESPONSIBLE TO IDENTIFY AS ENERGIZED OR "HOT".
- METER ADAPTER INSTALLATIONS REQUIRE THE RISER TO BE SECURED TO THE WALL WITH A HEAVY DUTY TWO-HOLE PIPE STRAP PLACED 3 INCHES BELOW BOTTOM OF METER ADAPTER WITH 3/8" X 3" LAG SCREWS INTO PLATE. 1/4-INCH TOGGLE BOLTS MAY BE USED IN LIEU OF LAG SCREWS. A ZANAC NAIL HEAD 1/4" X 1 7/8" (MUSHROOM) MAY BE USED IN PLACE OF A LAG SCREW WHEN ATTACHING IT TO A CINDER BLOCK OR CONCRETE WALL. INSTALL CROSS-BRACING (UNISTRUT) AS REQUIRED TO FIT TO WALL STUDS. TIGHTEN THE PIPE STRAP FIRMLY OVER THE RISER TO SECURE IT FROM SHIFTING DOWNWARD AS THE TRENCH SETTLES OVER TIME.
- H. AN INSPECTION AND RELEASE FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) IS NOT REQUIRED FOR INSTALLATION OF A METER ADAPTER. WHEN THE METER ADAPTER IS INSTALLED, THE ELECTRICAL CONTRACTOR MUST REROUTE THE EXISTING NEUTRAL CONDUCTOR INTO THE METER ADAPTER AND CONNECT TO THE NEUTRAL LUG SUPPLIED BY THE MANUFACTURER. THE UTILITY'S SERVICE CREW WILL CHECK THE NEUTRAL CONNECTIONS IN THE NEW METER ADAPTER AND IN THE EXISTING SERVICE EQUIPMENT FOR TIGHTNESS.

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	RISER, CONDUIT	AS REQ'D			
2	PULL CAN, UNDERGROUND SERVICE	AS REQ'D			
3	ELBOW, 90°, 24" MIN. RADIUS	AS REQ'D			
4	STRAP, PIPE	AS REQ'D			
5	COVER, GASKETED (SEALABLE)	AS REQ'D			
6	RING, ADAPTER	AS REQ'D			
7	HUB, 3"	AS REQ'D			

NOTES:

- (I) EXISTING SURFACE-MOUNT METER SOCKET CAN.
- (II)CONDUIT RISER SIZE BASED ON SERVICE EQUIPMENT AMPACITY. (2" MIN.)
- (III) EXISTING SEMI-FLUSH METER SOCKET.

REFERENCE:

(a) SEE UG3370 (SAN DIEGO COUNTY) OR UG3371 (ORANGE COUNTY) FOR TRENCH AND UTILITY POSITIONING DETAILS.


	© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		СН	IAN	IGE	DR	BY	DSN	APV	DATE
С							F									
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е									
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
	X Indicates L	n	Con	npletely Revi	ised		New Page		Information Ren	noved						

SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ACCEPTABLE METHODS FOR RESIDENTIAL ELECTRIC SERVICE CONVERSION

SG304.2



INSTALLATION:

- A THE CONTRACTOR COMPLETES INSTALLATION OF UG PULL CAN, UG RISER, RISER, CONDUIT, JUNCTION BOX, WIRE FROM JUNCTION BOX TO PULL CAN, AND CONNECTS TEMPORARY JUMPERS TO SERVICE DROP AND LANDING LUGS. IF THE SERVICE ENTRANCE CONDUCTORS ARE ENERGIZED, THE CONTRACTOR IS TO IDENTIFY THEM AS ENERGIZED OR "HOT".
- B) SDG&E (UTILITY) INSTALLS NEW UG SERVICE LATERAL CONDUCTORS TO THE PULL CAN. ON INSPECTION, THE UTILITY REMOVES TEMPORARY JUMPERS AND THE OH SERVICE DROP, CONNECTS WIRES IN THE PULL CAN, SEALS THE PULL CAN AND JUNCTION BOX, AND RESETS OR RESEALS THE METER AS REQUIRED.
- C THE CONTRACTOR INSTALLS THE NEW METER PANEL, UG RISER, WIRE AND NIPPLE FROM THE BREAKER PANEL TO THE SERVICE SWITCH. THE NEW CIRCUIT BREAKER IS TO BE LOCKED OR TAPED IN THE OFF POSITION.
- D THE UTILITY WILL INSTALL UG SERVICE LATERAL CONDUCTORS. ON INSPECTION AND RELEASE BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ), THE UTILITY DISCONNECTS THE OH SERVICE AT THE WEATHERHEAD, CONNECTS NEW CONDUCTORS TO THOSE ON THE LOAD-SIDE OF SERVICE SWITCH, CONNECTS THE NEW UG SERVICE, AND SETS THE METER.
- (E) THE CONTRACTOR IS TO FOLLOW UP WITH THE REMOVAL OF THE SERVICE CONDUIT, METER BASE, SERVICE SWITCHBLADES, ETC.
- F THE METER ADAPTER MAY BE INSTALLED EITHER FOR LEFT OR RIGHT HAND FEED BY SIMPLY REVERSING THE DIRECTION OF INSERTION INTO THE EXISTING METER SOCKET.
- G ON REQUEST, PERMISSION IS GRANTED BY THE PLANNER FOR THE CONTRACTOR TO BREAK THE METER SEAL, PULL METER AND INSERT IN THE ADAPTER. THE METER ADAPTER IS BUSSED THROUGH SO THE UNIT MAY BE INSERTED INTO THE EXISTING METER SOCKET, THE SCREW TYPE SEALING RING FURNISHED WITH THE UNIT INSTALLED IN THE GROOVE OF THE ADAPTER RING AND OVER THE EXISTING SOCKET RING, AND WHEN SECURELY IN PLACE, THE EXISTING METER INSERTED IN THE ADAPTER WILL OPERATE CORRECTLY STILL CONNECTED TO THE OVERHEAD SERVICE. (a)
- (H) AFTER THE CONTRACTOR INSTALLS THE UNDERGROUND SERVICE LATERAL CONDUIT AND TRENCH, AND THE UTILITY'S INSPECTOR APPROVES, A JOINT MEET WILL BE SCHEDULED AND THE FOLLOWING WORK IS TO BE PERFORMED:
 - 1. **UTILITY CREW WILL:** PULL THE METER AND INSTALL SERVICE LATERAL CONDUCTORS INTO THE PULL BOX OF THE METER ADAPTER. CUT OVERHEAD SERVICE AT THE DRIP LOOP. SWING THE METER ADAPTER OUT FROM THE METER SOCKET.
 - 2. **CONTRACTOR WILL:** PULL ENOUGH NEUTRAL SERVICE ENTRANCE CONDUCTOR DOWN FROM THE SERVICE CONDUIT RISER TO REACH THROUGH THE SLOT IN THE METER SOCKET TO THE NEUTRAL LUG LANDING IN THE PULL BOX OF THE METER ADAPTER (APPROXIMATELY 18 INCHES). REMOVE THE PHASE WIRES FROM THE EXISTING METER SOCKET LINE TERMINALS.
 - 3. **UTILITY CREW WILL:** RE-INSERT THE METER ADAPTER INTO THE EXISTING METER SOCKET (FEEDING THE NEUTRAL CONDUCTOR THROUGH THE SLOT IN THE ADAPTER RING).
 - 4. **CONTRACTOR WILL:** CONNECT THE NEUTRAL CONDUCTOR TO THE NEUTRAL TERMINAL IN THE PULL BOX OF THE METER ADAPTER.
 - 5. **UTILITY CREW WILL:** CONNECT THE UNDERGROUND PHASE WIRES TO THE UPPER TERMINALS OF THE METER ADAPTER SOCKET (NO CONNECTION IS MADE TO THE LOWER TERMINALS). INSERT THE METER IN THE METER ADAPTER AND ENERGIZE UNDERGROUND SERVICE. RESEAL THE METER AND SEAL THE METER ADAPTER.
- THE CONVERSION IS COMPLETED WITH THE UTILITY'S REMOVAL OF THE OVERHEAD SERVICE DROP AND THE CONTRACTOR'S REMOVAL OF THE OVERHEAD SERVICE ENTRANCE CONDUCTORS AND CONDUIT RISER.
- (K) THE METER ADAPTER INSTALLATIONS REQUIRE THE RISER TO BE SECURED TO THE WALL WITH A HEAVY DUTY TWO-HOLE PIPE STRAP PLACED 3 INCHES BELOW THE BOTTOM OF THE METER ADAPTER WITH 3/8-INCH X 3-INCH LAG SCREWS INTO THE PLATE. 1/4- INCH TOGGLE BOLTS MAY BE USED IN LIEU OF LAG SCREWS. A ZANAC NAIL HEAD 1/4-INCH X 1 7/8-INCH (MUSHROOM) MAY BE USED IN PLACE OF A LAG SCREW WHEN ATTACHING IT TO A CINDER BLOCK OR CONCRETE WALLS. INSTALL CROSSBRACING (UNISTRUT) AS REQUIRED TO FIT TO THE WALL STUDS. TIGHTEN THE PIPE STRAP FIRMLY OVER THE RISER TO SECURE IT FROM SHIFTING DOWNWARD AS THE TRENCH SETTLES OVER TIME.

REV	CHAN	GE DR BY DSN APV DATE REV CHANGE DR BY													BY	DSN	APV	DATE
С			F															
В	FORMAT	FORMATTING EDM JIK - - 07/19/2021 E																
Α	EDITORIAL (_ CHANGES																
	X Indicates Latest Revision Completely Revised New Page Information Removed																	
	SHEET		SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															
	2 OF 3		OVERHEAD TO UNDERGROUND SERVICE CONVERSION – CONTRACTOR & SDG&E													S	G30!	5.2

CREW COORDINATION METHODS

BILL OF MATERIALS: STANDARD STOCK DESIGN ITEM DESCRIPTION **QUANTITY** NUMBER UNITS **PAGE** CONDUCTORS, SERVICE ENTRANCE, NEW 1 AS REQ'D CAN, PULL 2 ----AS REQ'D --RISER, SERVICE, U.G. 3 AS REQ'D 4 OPEN LOOP AND BOND OR JUNCTION BOX, WITH SEALING SCREWS AS REQ'D 5 CAN, METER SOCKET, FLUSH MOUNTED AS REQ'D CAN, NEW U.G. COMBINATION PULL AND METER, WITH CIRCUIT BREAKER 6 AS REQ'D DISTRIBUTION SECTION 7 SOCKET, METER, OLD AS REQ'D SWITCH, SERVICE 8 AS REQ'D 9 STRAP, PIPE AS REQ'D

NOTES:

- (I) CONNECTIONS BY CONTRACTOR.
- (II) BY CUSTOMER.
- (III) SIZED PER CODE AND BONDED TO OLD RISER.
- (IV) SDG&E MAY INSTALL TEMPORARY SERVICE DROP CONDUCTORS FOR JOB COORDINATION.

Indicates Latest Revision

- (V) EXISTING.
- (VI) PULL BOX AREA OF METER ADAPTER.

REFERENCE:

a SEE SG304.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

OVERHEAD TO UNDERGROUND SERVICE CONVERSION – CONTRACTOR & SDG&E CREW COORDINATION METHODS


Completely Revised

SG305.3

SCOPE: THIS STANDARD PROVIDES THE REQUIREMENTS AND CONDITIONS ALLOWING FIELD HEATING OF SERVICE LATERAL CONDUITS INSTALLED ABOVE GRADE ONLY.

ATTENTION:

- THIS STANDARD PROVIDES A MEANS TO AVOID EXCAVATING INTO AN EXISTING BUILDING FOOTING WHEN CONVERTING EXISTING OVERHEAD SERVICES TO UNDERGROUND (SEE FIGURE 1). IT ALSO APPLIES TO EXISTING OR NEW SERVICES WHEN A HORIZONTAL OFFSET IS REQUIRED DUE TO FIELD CONDTIONS (SEE FIGURE 2).
- THIS STANDARD IS NOT INTENDED TO CORRECT POOR WORKMANSHIP.
- CARE SHOULD BE TAKEN TO INSTALL SERVICE EQUIPMENT IN A MANNER ALLOWING THE SERVICE LATERAL CONDUIT RISER TO EXIT THE GROUND AND RUN STRAIGHT UP INTO THE TERMINATING ENCLOSURE EXCEPT WHERE PRE-EXISTING FIELD CONDITIONS EXIST.



INSTALLATION:

- (A) this standard applies to 2-inch, 3-inch and 4-inch conduit sizes only.
- (B) only manufacturer's recognized field conduit heating equipment shall be used. Degradation of the conduit's SHAPE, WRINKLES, DISCOLORATION, BURN MARKS, OR PAINT ARE NOT ALLOWED. SDG&E'S INSPECTOR WILL DETERMINE IF THE HEATED CONDUIT IS ACCEPTABLE.

C EDITORIAL CHANGES ARC IPJ IPJ KRG 08/31/2023 F IPJ IPJ	REV	EV CHANGE DR BY DSN APV DATE REV CHANGE DR I													BY	DSN	APV	DATE
A EDITORIAL CHANGES LSM IPJ TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed	С	EDITORIAL CHANGES ARC IPJ IPJ KRG 08/31/2023 F																
X Indicates Latest Revision Completely Revised New Page Information Removed	B FORMATTING				JIK	-	-	07/19/2021	Е									
SDG&E ELECTRIC SERVICE STANDARDS & CLITTES	Α	A EDITORIAL CHANGES LSM IPJ TPM 11/01/2017 D																
SDG&F ELECTRIC SERVICE STANDARDS & GUIDES	X Indicates Latest Revision Completely Revised New Page Information Removed																	
CULLT		SHEET	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															
	1	$\cap E$	FIELD HEATING SERVICE LATERAL CONDUITS													SG306.1		

FIELD HEATING SERVICE LATERAL CONDUITS

INSTALLATION (CONT'D):

- $(\mathsf{C}$) 45 degrees is the maximum allowable deflection on the Riser. The deflection in the Riser is included in the MAXIMUM 270 DEGREE TOTAL DEFLECTION IN THE SERVICE LATERAL CONDUIT RUN. (b)
- (D) when converting an existing service to underground, mandrel new conduit to the top of the elbow extending TO GRADE PRIOR TO CONNECTING THE RISER CONDUIT. ALLOW ENOUGH PULL ROPE TO EXTENDED THROUGH THE RISER, WITH A MINIMUM 12-INCH TAIL TO BE LEFT IN THE TERMINATING ENCLOSURE.
- (E) NEW SERVICES REQUIRE MANDRELING OF ALL NEW CONDUITS, INCLUDING THE CONDUIT RISER.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

- a. REFER TO UG3950.
- (b) REFER TO SG309, INSTALLATION ITEM B, FOR ADDITIONAL INFORMATION.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/31/2023	F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
A	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 2 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


FIELD HEATING SERVICE LATERAL CONDUITS

SG306.2

SCOPE: THIS STANDARD PROVIDES INSTRUCTIONS FOR INSTALLING A SAFETY OVERFLOW FITTING FOR FLUSH OR SEMI-FLUSH MOUNTED SERVICE EQUIPMENT WHERE THE SDG&E SOURCE IS AT A HIGHER ELEVATION THAN THE SERVICE EQUIPMENT.

ATTENTION:

- THIS FITTING IS RECOMMENDED, BUT NOT REQUIRED BY SDG&E.
- THE PURPOSE OF INSTALLING THIS DEVICE IS THAT IT MAY HELP PREVENT WATER ENTRY INTO THE SERVICE EQUIPMENT.
- *** THIS FITTING IS FOR INDOOR USE ONLY.






FIGURE 1

INSTALLATION:

- A. THIS FITTING IS FOR CONDUITS INSTALLED INSIDE BUILDING WALLS ONLY. USE LISTED ELECTRICAL RIGID PVC SCHEDULE 40. CONDUIT AND FITTINGS FOR EXTENDING THE DRAIN FITTING OUTSIDE THE WALL OR FOUNDATION. IT IS THE INSTALLER'S RESPONSIBILITY TO COMPLY WITH ALL APPLICABLE BUILDING AND ELECTRICAL CODES.
- B. ASSEMBLE THE DRAIN BY MEANS OF CEMENT THAT IS, OR CONTAINS, A SOLVENT FOR POLYVINYL CHLORIDE.
- C. ENSURE THE ARROW ON THE 2-INCH FITTING IS POINTING "UP" WHEN INSTALLING, DO NOT CUT OR MODIFY THE SAFETY OVERFLOW FITTING.
- D. CLEAN THE SAFETY OVERFLOW FITTING APPROXIMATELY 2 INCHES FROM EACH END THOROUGHLY WITH CLEANING FLUID. LET THE FITTING DRY COMPLETELY.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 2

Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SAFETY OVERFLOW FITTING FOR INDOOR USE ONLY ON WALL-MOUNTED SERVICE EQUIPMENT

SG307.1

INSTALLATION (CONT'D):

- E. THE DRAIN MUST BE FULLY INSERTED INTO THE BODY AND EXTENDED IN THE DOWNWARD POSITION.
- F. AFTER USING THE CEMENT SOLVENT, MAKE A QUARTER TURN AND THEN LET DRY COMPLETELY.
- G. REPEAT THE CLEANING AND GLUING PROCESS AT EACH JOINT.
- $(\mathsf{H}\,)$ EXTEND THE 1-INCH FITTING UNTIL IT IS OUTSIDE THE WALL OR FOUNDATION AT LEAST 1 1/2 INCHES TO 2 INCHES.
- AFTER EXTENDING THE CONDUIT OUTSIDE THE WALL OR FOUNDATION, INSTALL A 90-DEGREE ELBOW POINTING DOWN AND A MINIMUM OF 18 INCHES ABOVE GROUND. INSTALL A MESH SCREEN TO PREVENT DIRT OR INSECTS FROM ENTERING CONDUIT. DO NOT CONNECT THE 1-INCH FITTING TO ANY OUTSIDE WATER DRAINS.
- (K) USE THE PROPER END COUPLING AND LOCKING NUT INSIDE THE CABLE TERMINATION CAN.
- (L) SDG&E CREW WILL SEAL THE SERVICE LATERAL CONDUIT IN THE TERMINATING ENCLOSURE.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

a. REFER TO UG3960 FOR REQUIREMENTS RELATING TO ELEVATION OF CUSTOMER FACILITIES AND WATER ENTRY PREVENTION.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
A	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 2

Completely Revised New Page

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SAFETY OVERFLOW FITTING FOR INDOOR USE ONLY ON WALL-MOUNTED SERVICE EQUIPMENT

SG307.2


SCOPE: THIS STANDARD PROVIDES INSTRUCTIONS FOR COSTUMER-INSTALLED CONDUIT AND ADDITIONAL REQUIREMENTS FOR A RESIDENTIAL OR COMMERCIAL SERVICE LATERAL.

TABLE 1:

CUSTOMER-INSTALLE	SERVICE EQU	IPMENT, BUS	AND ASSOCIA	TED CONDUITS									
	SERVICE RISER BEND AND SERVICE LATERAL CONDUIT S FOR 3- OR 4- WIRE RUN 3 6 7												
SERVICE EQUIPMENT OR BUS AMPACITY (AMPS)	RESIDENT MULTI-FAMI		COMMERCIAL AND INDUSTRIAL SERVICE										
	QTY.	SIZE (IN)	QTY.	SIZE (IN)									
0 -200 I	1	3 (C)	1	3 C									
201 – 400 (SINGLE-PHASE)	1	3 (IV)	1	3									
201 – 400 (THREE-PHASE)	1	4	1	4									
401 – 800	2	4 (V) j	2	4									
801 – 1,200	3	4	3	5									
1,201 – 1,600	3	4	4	5									
1,601 – 2,000	4	4	5	5									
2,001 – 2,500	5	4	6	5									
2,501 – 3,000	4	5	7	5									
3,001 – 3,500	5	5	8	5									
3,501 – 4,000	7	5	10	5									

TABLE 2:

CONDUIT BENDS												
CONDUIT RISER BEND SIZE (IN)	MINIMUM BENDING RADIUS (IN) 6 7											
2 (C)	24											
3	36											
4	36											
5	48											



© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under lav	Ν.
---	----

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	-	F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е	TABLE UPDATE	PS	JTM	JTM	KRG	01/03/2024
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/31/2023

SHEET 1 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG309.1

UNDERGROUND ELECTRIC SERVICE LATERAL CONDUIT REQUIREMENTS

TABLE 3:

ITEM	DESCRIPTION	RESPONSIBLE PARTY
1	SOURCE: MANHOLE, HANDHOLE OR PADMOUNT TRANSFORMER.	SDGE WILL FURNISH, INSTALL, OWN AND
2	SERVICE LATERAL CONDUCTORS AND CONNECTORS FROM SDG&E UNDERGROUND DISTRIBUTION SYSTEM ITEM 1 TO CUSTOMER'S SERVICE TERMINATING FACILITY ITEM 8. SDG&E WILL MAKE CONNECTIONS.	MAINTAIN, SUBJECT TO INSTALLATION CHARGES.
3	A CLEAR ROUTE ON ANY PRIVATE PROPERTY, THAT IS CLEAR OF OBSTRUCTIONS WHICH WOULD INHIBIT THE CONSTRUCTION OF SERVICE FACILITIES. SERVICE LATERAL CONDUIT FROM SOURCE ITEM 1 TO TERMINATING FACILITY ITEM 8. CONDUIT SIZE SHALL BE BASED ON THE NAMEPLATE RATING OF THE SERVICE EQUIPMENT AND DISTANCE FROM TRANSFORMER TO THE TERMINATING FACILITY. CONDUIT MATERIAL FROM ITEM 1 TO ITEM 8 SHALL BE APPROVED NON-METALLIC CONDUIT IN ACCORDANCE WITH UG3373. BETWEEN ITEM 6 AND ITEM 8, THE CONDUIT INSTALLER MUST PROVIDE A 3/4-INCH PULLING AND MEASURING TAPE IN EACH CONDUIT. THE PULLING TAPE MUST BE APPROVED BY SDG&E, HAVE A MINIMUM AVERAGE TENSILE STRENGHT OF 2,500 POUNDS AND BE WOVEN POLYESTER HIGH STRENGTH, CONTINUOUS FILAMENT, PRE-LUBRICATED WITH FOOTAGE MARKING. PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF THE CONDUIT, THE PULLING TAPE SHALL BE PULLED IN BEHIND THE MANDREL. WHEN THE PULLING AND MEASURING TAPE IS INSTALLED, IT SHALL BE ONE CONTINUOUS LENGTH WITHOUT KNOTS FOR THE ACCURATE MEASUREMENT FOR CONDUCTOR INSTALLATION AND THE PULLING OF CONDUCTORS OR WINCH LINES. LEAVE AT LEAST 2 FEET BEYOND EACH END OF CONDUIT RUN. FLEX CONDUIT IS NOT PERMITTED.	
4	TRENCH, BACKFILL, PAVEMENT REPAIR, AND STRUCTURES SHALL BE IN ACCORDANCE WITH SDG&E AND THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) REQUIREMENTS. IF THE CUSTOMER INSTALLS A SECONDARY HARDHOLE ON PRIVATE PROPERTY, THE LID SHALL BE MARKED "SDG&E". THE CUSTOMER IS TO OBTAIN AN EXCAVATION PERMIT FOR TRENCHING IN STREET RIGHT-OF-WAY AS REQUIRED BY THE GOVERNMENTAL AHJ. SDG&E INSPECTION IS REQUIRED PRIOR TO SHADING AND BACKFILLING	CUSTOMER SHALL FURNISH, INSTALL, OWN
5	ADAPTER COUPLINGS FOR CONNECTING BENDS TO STRAIGHT CONDUIT.	AND MAINTAIN AT THEIR EXPENSE
6	CONDUIT RISER BEND. (SEE TABLE 2)	
7	SIZE AND NUMBER OF CONDUIT RUNS TO BE DESIGNATED BY SDG&E. (SEE TABLE 1)	
8	SERVICE TERMINATING ENCLOSURE PER SG700.	
9	TYPE AND SCHEDULE OF CONDUIT ON OR WITHIN A BUILDING OR STRUCTURE TO BE INSTALLED PER BUILDING INSPECTOR'S REQUIREMENTS AND MUST BE LISTED AND LABELED. NORMALLY SCHEDULE 40 PVC IS ALLOWED INSIDE A BUILDING WALL AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH THE APPROPIATE AHJ. FLEX CONDUIT IS NOT PERMITTED.	
(10)	CONDUIT MANUFACTURER AND MATERIAL MUST BE SDG&E-APPROVED, ASBESTOS-CONTAINING MATERIAL (ACM) IS NOT APPROVED.	

INSTALLATION:

- A. CONTACT DESIGN & PROJECT MANAGEMENT AT THE NEAREST SDG&E REGIONAL OFFICE CLOSEST TO THE JOB SITE FOR AN ELECTRIC METER & SERVICE LOCATION FORM PRIOR TO THE START OF CONSTRUCTION, SEE SG2.
- (B) THE SERVICE LATERAL CONDUIT SPECIFIED IN THE CONDUIT TABLE IS LIMITED TO 150 FEET IN LENGTH, WITH NOT MORE THAN THREE 90 DEGREE HORIZONTAL OR VERTICAL BENDS OR 270 DEGREES TOTAL DEFLECTION THROUGH THE SERVICE RUN. IF GREATER THAN 150 FEET, REFER TO UG4005-UG4007. PLANNER AND ELECTRIC CONSTRUCTION SUPERVISOR APPROVAL IS REQUIRED IF LIMITATIONS ARE EXCEEDED.
- (C) A 3-WIRE, 100A, SINGLE-PHASE SERVICE AND METER PANEL CAN BE SERVED BY A 2-INCH CONDUIT. A 3-WIRE, 200A, OR LESS, SINGLE-PHASE SERVICE AND METER PANEL FOR TEMPORARY CONSTRUCTION POWER CAN BE SERVED BY A 2-INCH CONDUIT. ITEM 3 SHALL BE THE SAME SIZE AND TYPE MATERIAL STOCKED BY SDG&E AS SHOWN ON UG3373.
- D. ENGINEERS' AND ARCHITECTS' PROPOSALS FOR ALL SWITCHBOARDS RATED 801 AMPERES, OR LARGER, SHALL BE SUBMITTED BY THE MANUFACTURER TO THE SDG&E SERVICE STANDARDS SECTION FOR REVIEW AND APPROVAL. REFER TO SG517 FOR FURTHER INFORMATION ON THE MANUFACTURER'S DRAWINGS FOR APPROVAL PROCESS.
- E. REPLACEMENT OR ENLARGEMENT OF SERVICE LATERAL CONDUITS DUE TO RELOCATION OR INCREASED LOAD WILL BE ACCOMPLISHED BY THE CUSTOMER UNDER THE PROVISIONS OF TABLE 3, ITEMS 3 THROUGH 10. CONSULT WITH THE SDG&E PROJECT PLANNER.
- F CONDUITS SHALL BE SEALED PER UG3948. (e) (k)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	-	F						
В	FORMATTING	EDM	JIK		-	07/19/2021	Е	TABLE UPDATE	PS	JTM	JTM	KRG	01/03/2025
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/31/2023

SHEET 2 OF 4

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Indicates Latest Revision | Completely Revised | New Page |

UNDERGROUND ELECTRIC SERVICE LATERAL CONDUIT REQUIREMENTS

SG309.2

Information Removed

INSTALLATION (CONT'D):

- (G) A 24-INCH MINUMUM COVER OVER THE CONDUIT IS REQUIRED FOR ALL NORMAL INSTALLATIONS ON PRIVATE PROPERTY AND A 30-INCH MINIMUM COVER IS REQUIRED IN RIGHT-OF-WAY OR PUBLIC PROPERTY. IN ALL INSTALLATIONS WHERE THE MINIMUM COVER CANNOT BE MET, G.O. 128 REQUIRES ONE OF THE FOLLOWING:
 - 1. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 1/8-INCH.
 - 2. AT LEAST A 3-INCH LAYER OF CONCRETE ABOVE (2 SACK 3/8-INCH ROCK) AND 2 INCHES ON EACH SIDE OF THE CONDUIT, REDUCED DEPTHS MUST BE APPROVED BY THE SDG&E'S PROJECT PLANNER AND INSPECTOR.
- (H) THE TRENCH MUST HAVE AN EVEN SLOPING GRADE TO ALLOW ROOM FOR A 90-DEGREE BEND INTO THE BOTTOM OF ANY CUSTOMER-OWNED OR SDG&E FACILITY. DO NOT CUT BENDS. THE TRENCH DEPTH IS TO BE DETERMINED AT THE PRECONSTRUCTION MEETING.
- (J) WHEN TRENCHING TO AN EXISITING SDG&E FACILITY, THE APPLICANT/CONTRACTOR SHALL COMPLETE THE TRENCH AND INSTALLATION OF CONDUIT UP TO THE EXISTING FACILITY UNLESS IT IS DETERMINED BY AN AUTHORIZED SDG&E EMPLOYEE THAT SUCH AN INSTALLATION PERFORMED BY THE APPLICANT/CONTRACTOR WOULD EXPOSE WORKERS TO, OR CREATE, A HAZARD. IN THIS CASE, SDG&E WOULD PERFORM TRENCHING AS INDICATED ON THE CONSTRUCTION WORK ORDER. DIGGING UNDER ENERGIZED PAD MOUNTED EQUIPMENT AND INSTALLATION OF CONDUIT INTO ENERGIZED PAD MOUNTED EQUIPMENT WILL ALWAYS BE THE RESPONSIBILITY OF SDG&E.
- (K) A SERVICE CONDUIT WILL ONLY BE ALLOWED UNDERNEATH THE BUILDING BEING SERVED BY THE CABLE IN THE CONDUIT. NO CONDUIT IS ALLOWED UNDER ONE BUILDING TO SERVE ANOTHER BUILDING.
- (L) DEPTH OF TRENCH IS DETERMINED BY TYPE OF SUBSTRUCTURE AT SOURCE. VERIFY WITH SDG&E INSPECTOR PRIOR TO EXCAVATION.
- (M) install conduit on even sloping grade from conduit riser bend to SDG&E source.

BILL OF MATERIALS: NONE

NOTES:

- (I)225A RESIDENTIAL SERVICE EQUIPMENT.
- II. AMPACITY RANGE BASED IN 75 DEGREES CELSIUS ALIMINUM WIRE.
- (III) THESE ARE MINIMUM REQUIREMENTS. CONDUIT REQUIREMENTS MAY INCREASE WITH DIFFERENT ESTIMATED DEMANDS AND LENGTH OF SERVICE, DUE TO VOLTAGE DROP AND/OR FLICKER (INRUSH CURRENT). FUTURE LOADS SHOULD ALSO BE CONSIDERED.
- (IV) INCLUDES 300A RESIDENTAIL SERVICE EQUIPMENT. (i)
- $\left(\,\mathsf{V}\,
 ight)$ 2-3-inch conduits minimum for multi-family 600A services.

REFERENCE:

- a. SEE UG3367 FOR TRENCH PARALLELING FOUNDATIONS.
- b. SEE UG3372 FOR CONDUIT SIZING AND UG3373 FOR CONDUIT AND FITTINGS.
- c. SEE UG3376 FOR CONCRETE SLURRY REQUIREMENTS.
- d. SEE UG3421, UG3425, UG3426 AND UG3427 FOR CONDUIT PLACEMENT.
- $(\,\mathsf{e}\,)$ see ug3941 for residential riser and conduit and ug3948 for conduit sealing.
- f. SEE UG3944 FOR MATERIAL REQUIREMENTS OF AN UG SERVICE FROM OH FACILITIES.
- g. SEE OH1404, UG4204 FOR CABLE POLE CONDUIT REQUIREMENTS.
- h. SEE UG3942.
- i SEE SG512.6

© 1998 - 2025 San Diego Gas & Electric Company	All rights reserved. Removal of this copyright notice without	it permission is not permitted under law

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	-	F						
В	FORMATTING	EDM	JIK		-	07/19/2021	Е	TABLE UPDATE	PS	JTM	JTM	KRG	01/03/2025
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/31/2023

SHEET 3 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Ren

UNDERGROUND ELECTRIC SERVICE LATERAL CONDUIT REQUIREMENTS

SG309.3

REFERENCE (CONT'D): (j) SEE SG707 FOR SPECIAL APPLICATION. (k) SEE G.O. 128, RULE 31.6. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV DR BY DSN APV DATE DATE **CHANGE REV CHANGE EDITORIAL CHANGES** ARC IPJ KRG В 07/19/2021 E **FORMATTING** EDM JIK TABLE UPDATE PS JTM JTM KRG 01/03/2025 **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 D IPJ **EDITORIAL CHANGES** IPJ KRG 08/31/2023 **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG309.4 4 OF 4 UNDERGROUND ELECTRIC SERVICE LATERAL **CONDUIT REQUIREMENTS**

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR INSTALLATION, OWNERSHIP AND MAINTENANCE OF A SINGLE LOW-VOLTAGE UNDERGROUND SERVICE FED FROM OVERHEAD FACILITIES.

ATTENTION:

- * CONTACT THE SDG&E INSPECTOR FOR INSTRUCTIONS ON TRENCHING NEAR THE POLE.
- ** SDG&E INSPECTION IS REQUIRED PRIOR TO BACKFILLING TRENCH.




FIGURE1

TABLE 1

ITEM	DESCRIPTION	RESPONSIBLE PARTY
<u>(1)</u>	SOURCE POLE AS DESIGNATED BY SDG&E PLANNER. CONTACT PROJECT MANAGEMENT AT THE NEAREST SDG&E REGIONAL OFFICE CLOSEST TO THE JOB SITE FOR AN ELECTRIC METER & SERVICE LOCATION FORM PRIOR TO THE START OF CONSTRUCTION.	SDG&E OVERHEAD DISTRIBUTION SYSTEM
2	SERVICE LATERAL CONDUCTORS AND CONNECTORS	SDG&E TO FURNISH, INSTALL, OWN AND MAINTAIN, SUBJECT TO INSTALLATION CHARGES
3	SCHEDULE 40 PVC CONDUIT	CUSTOMER TO PROVIDE, SDG&E TO
4	SCHEDULE 80 PVC CONDUIT	INSTALL, OWN AND MAINTAIN
(5)	SCHEDULE 80 PVC CONDUIT BEND. THE LARGER RADIUS AT THE POLES IS NECESSARY TO ALLOW FOR VERTICAL CABLE PULLING TENSION. (SEE TABLE 2)	
(6)	A CLEAR ROUTE ON ANY PRIVATE PROPERTY, THAT IS CLEAR OF OBSTRUCTIONS WHICH WOULD INHIBIT THE CONSTRUCTION OF SERVICE FACILITIES. SERVICE LATERAL CONDUIT FROM SOURCE (ITEM 1) TO TERMINATING FACILITY (ITEM 11). CONDUIT SIZE SHALL BE BASED ON THE NAMEPLATE RATING OF THE SERVICE EQUIPMENT AND DISTANCE FROM TRANSFORMER TO THE TERMINATING FACILITY.	CUSTOMER SHALL FURNISH, INSTALL,
7	SECONDARY HANDHOLE. VERIFY IF IT IS REQUIRED WITH THE SDG&E PLANNER. IF A HANDHOLE IS REQUIRED, THE LID SHALL BE MARKED "SDG&E".	OWN AND MAINTAIN AT THEIR EXPENSE
8	TRENCH, BACKFILL, PAVEMENT REPAIR AND STRUCTURES SHALL BE IN ACCORDANCE WITH SDG&E'S AND THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION'S (AHJ) REQUIREMENTS. SPECIAL NOTE: CONTACT THE SDG&E INSPECTOR FOR INSTRUCTIONS FOR TRENCHING NEAR THE SDG&E POLE. THE CUSTOMER IS TO OBTAIN AN EXCAVATION PERMIT FOR TRENCHING IN THE STREET RIGHT-OF-WAY AS REQUIRED BY THE AHJ. SDG&E INSPECTION IS REQUIRED PRIOR TO SHADING AND BACKFILLING THE TRENCH.	

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	<u> </u>	CH	HANGE	DR	BY	DSN	APV	DATE
С							F								
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								

SHEET 1 OF 3 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE)

SG310.1

TABLE 1 (CONT'D)

ITEM	DESCRIPTION	RESPONSIBLE PARTY
9	ITEMS 3, 4, 5 AND 6 SHALL BE NON-METALLIC CONDUIT PER UG3373 AND UG4204. BETWEEN ITEM 5 AND ITEM 9 THE CONDUIT INSTALLER SHALL PROVIDE A 3/4-INCH PULLING AND MEASURING TAPE IN EACH CONDUIT. THE PULLING TAPE MUST BE APPROVED BY SDG&E, HAVE A MINIMUM AVERAGE TENSILE STRENGTH OF 2,500 POUNDS AND BE WOVEN POLYESTER HIGH STRENGTH, CONTINUOUS FILAMENT, PRE-LUBRICATED WITH FOOTAGE MARKING. PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF THE CONDUIT. THE PULLING TAPE SHALL BE PULLED IN BEHIND THE MANDREL. WHEN THE PULLING AND MEASURING TAPE IS INSTALLED IT SHALL BE ONE CONTINUOUS LENGTH WITHOUT KNOTS FOR THE ACCURATE MEASUREMENT FOR CONDUCTOR INSTALLATION AND THE PULLING OF CONDUCTORS OR WINCH LINES. LEAVE AT LEAST 2 FEET BEYOND EACH END OF THE CONDUIT RUN. FLEX CONDUIT IS NOT PERMITTED.	CUSTOMER SHALL FURNISH, INSTALL,
(10)	CONDUIT RISER BEND. (j)	OWN AND MAINTAIN AT THEIR EXPENSE
(11)	SERVICE TERMINATING ENCLOSURE PER SECTION 700 REQUIREMENTS.	THEIR EXPENSE
(12)	TYPE AND SCHEDULE OF CONDUIT ON OR WITHIN A BUILDING OR STRUCTURE SHALL BE INSTALLED PER THE AHJ'S REQUIREMENTS AND MUST BE LISTED AND LABELED. NORMALLY SCHEDULE 40 PVC IS ALLOWED INSIDE A BUILDING WALL AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH THE APPROPRIATE AHJ. FLEX CONDUIT IS NOT PERMITTED.	
(13)	CONDUIT MANUFACTURER MUST BE SDG&E-APPROVED.	

TABLE 2

MINIMUM CONI	OUIT BEND RADIUS
CONDUIT SIZE (IN)	MINIMUM BENDING RADIUS (IN)
3	36
4	48
5	48

INSTALLATION:

- (A) A 24-INCH MINIMUM COVER OVER THE CONDUIT IS REQUIRED FOR ALL NORMAL INSTALLATIONS ON PRIVATE PROPERTY, AND A 30-INCH MINIMUM COVER IS REQUIRED IN RIGHT-OF-WAY OR ON PUBLIC PROPERTY. IN ALL INSTALLATIONS WHERE THE MINIMUM COVER CANNOT BE MET, G.O. 128 REQUIRES ONE OF THE FOLLOWING ALTERNATIVES THAT ARE ACCEPTABLE TO SDG&E:
 - 1. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 1/8-INCH.
 - 2. AT LEAST A 3-INCH LAYER OF CONCRETE (2 SACK 3/8-INCH ROCK) ABOVE AND 2 INCHES ON EACH SIDE OF THE CONDUIT. REDUCED DEPTHS MUST BE APPROVED BY THE SDG&E PLANNER AND INSPECTOR.
- (B) THE TRENCH MUST HAVE AN EVEN SLOPING GRADE TO ALLOW ROOM FOR A 90 DEGREE BEND INTO THE BOTTOM OF ANY CUSTOMER-OWNED OR SDG&E FACILITY. DO NOT CUT BENDS. THE TRENCH DEPTH IS TO BE DETERMINED AT THE PRE-CONSTRUCTION MEETING.
- WHEN TRENCHING TO AN EXISTING SDG&E FACILITY, THE APPLICANT/CONTRACTOR SHALL COMPLETE THE TRENCH AND INSTALLATION OF CONDUIT UP TO THE EXISTING FACILITY UNLESS IT IS DETERMINED BY AN AUTHORIZED SDG&E EMPLOYEE THAT SUCH AN INSTALLATION PERFORMED BY THE APPLICANT/CONTRACTOR WOULD EXPOSE WORKERS TO OR CREATE A POTENTIAL HAZARD. IN THIS CASE, SDG&E WOULD PERFORM TRENCHING AS INDICATED ON THE CONSTRUCTION WORK ORDER. DIGGING UNDER ENERGIZED PAD MOUNTED EQUIPMENT AND INSTALLATION OF CONDUIT INTO ENERGIZED PAD MOUNTED EQUIPMENT WILL ALWAYS BE THE RESPONSIBILITY OF SDG&E.

BILL OF MATERIALS: NONE

NOTES: NONE

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
A	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D			·			

SHEET 2 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE)

SG310.2

REFERENCE:

- a. SEE UG3367 FOR TRENCH PARALLELING FOUNDATIONS.
- b. SEE UG3373 FOR SDG&E CONDUIT AND FITTINGS.
- c. SEE UG3376 FOR CONCRETE SLURRY REQUIREMENTS.
- d. SEE UG3941 FOR RESIDENTIAL RISER AND CONDUIT.
- e. SEE UG3944 FOR MATERIAL REQUIREMENTS OF AN UG SERVICE FROM OH FACILITIES.
- f. SEE UG3948 FOR CONDUIT SEALING.
- 9. SEE OH1404UG4204 FOR CABLE POLE CONDUIT REQUIREMENTS.
- h. SEE UG3950 FOR FIELD HEATING SERVICE LATERAL CONDUITS.
- (i) SEE SG3.
- $\left(\ \mathrm{j} \
 ight)$ see SG309.1 for minimum bending radius.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND SERVICE FROM OVERHEAD FACILITIES (LOW VOLTAGE)

SG310.3

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR INSTALLATION, OWNERSHIP AND MAINTANENCE OF A PRIMARY AND SECONDARY VOLTAGE UNDERGROUND SYSTEM FED FROM A NEW CABLE POLE.

ATTENTION:

- * CONTACT THE SDG&E INSPECTOR FOR INSTRUCTIONS ON TRENCHING NEAR THE POLE.
- ** SDG&E INSPECTION IS REQUIRED PRIOR TO BACKFILLING TRENCH.




FIGURE 1

TABLE 1:

IABLE	<u>. 1:</u>	
ITEM	DESCRIPTION	RESPONSIBLE PARTY
1	SOURCE POLE AS DESIGNATED BY SDG&E PLANNER, CONTACT PROJECT MANAGEMENTS AT THE NEAREST SDG&E REGIONAL OFFICE CLOSEST TO THE JOB SITE FOR AN ELECTRIC METER & SERVICE LOCATION FORM PRIOR TO THE START OF CONSTRUCTION.	SDG&E OVERHEAD DISTRIBUTION SYSTEM
2	MEDIUM-VOLTAGE TERMINALS	
3	MEDIUM-VOLTAGE AND LOW VOLTAGE CABLE AND CONNECTIONS	SDG&E TO FURNISH,
4	TRANSFORMER	INSTALL, OWN AND MAINTAIN, SUBJECT TO
5	SCHEDULE 40 PVC CONDUIT	INSTALLATION CHARGES
6	SCHEDULE 80 PVC CONDUIT	

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/07/2023	F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
A	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						·

SHEET 1 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PRIMARY & SECONDARY VOLTAGE UNDERGROUND SYSTEM ON CUSTOMER PREMISES FROM CABLE POLE

SG311.1

<u>TABLE 1 (CONT'D):</u> **DESCRIPTION ITEM RESPONSIBLE PARTY** SCHEDULE 80 PVC CONDUIT BEND. THE LARGER THE RADIUS AT THE POLES IS NECESSARY TO ALLOW FOR VERTICAL CABLE PULLING TENSION. TABLE 2: **SCHEDULE 80 PVC CONDUIT BEND** 7 CONDUIT RADIUS SIZE (IN) (IN) 2, 3 4, 5 48 PRIMARY CONDUIT SIZED AND SPECIFIED BY SDG&E ON THE CONSTRUCTION WORK ORDER. THE CONDUIT MANUFACTURER MUST BE SDG&E-APPROVED. BETWEEN ITEM 7 AND ITEM 12, THE CONDUIT INSTALLER SHALL PROVIDE A 3/4-INCH PULLING AND MEASURING TAPE IN EACH CONDUIT. THE PULLING TAPE MUST BE APPROVED BY SDG&E, HAVE A MINIMUM AVERAGE TENSILE 8 STRENGTH OF 2,500 POUNDS, AND BE WOVEN POLYESTER HIGH STRENGTH, CONTINOUS FILAMENT, PRE-LUBRICATED WITH FOOTAGE MARKING. PULLING TAPE TAILS OF 24 INCHES SHALL BE SECURED AT EACH END OF THE CONDUIT. THE PULLING TAPE SHALL BE PULLED IN BEHIND THE MANDREL. WHEN THE PULLING AND MEASURING A CLEAR ROUTE ON ANY PRIVATE PROPERTY, THAT IS CLEAR OF OBSTRUCTIONS WHICH WOULD INHIBIT THE CONSTRUCTION OF **CUSTOMER SHALL** PRIMARY AND SERVICE FACILITIES. TRENCH, BACKFILL, PAVEMENT REPAIR AND STRUCTURES SHALL BE IN ACCORDANCE WITH FURNISH, INSTALL, OWN SDG&E AND THE LOCAL GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) REQUIREMENTS. AND MAINTAIN AT THEIR 9 **EXPENSE** *CONTACT THE SDG&E INSPECTOR FOR INSTRUCTION ON TRENCHING NEAR THE SDG&E POLE. THE CUSTOMER IS TO OBTAIN AN EXCAVATION PERMIT FOR TRENCHING IN STREET RIGHT-OF-WAY AS REQUIRED BY THE AHJ. SDG&E INSPECTIONS IS REQUIRED PRIOR TO SHADING AND BACKFILLING THE TRENCH. (10) TRANSFORMER PAD AND GROUNDING. THE PAD SIZE IS SPECIFIED ON THE CONSTRUCTION WORK ORDER. f) SERVICE LATERAL CONDUIT SIZED AND SPECIFIED BY SDG&E ON THE CONSTRUCTION WORK ORDER OR ON A SEPARATE g) (11) SERVICE ORDER. CONDUIT MANUFACTURER MUST BE SDG&E APPROVED. TYPE AND SCHEDULE OF CONDUIT ON OR WITHIN A BUILDING OR STRUCTURE SHALL BE INSTALLED PER THE AHJ'S REQUIREMENTS

INSTALLATION:

(12)

13

(14[\]

- A. A 24-INCH MINIMUM COVER OVER THE CONDUIT IS REQUIRED FOR ALL NORMAL INSTALLATIONS ON PRIVATE PROPERTY AND A 30-INCH MINIMUM COVER IS REQUIRED IN RIGHT-OF-WAY OR ON PUBLIC PROPERTY. IN ALL INSTALLATIONS WHERE THE MINIMUM COVER CANNOT BE MET, G.O. 128 REQUIRES ONE OF THE FOLLOWING:
 - 1. STEEL CONDUIT.
 - 2. SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 1/8-INCH.

AND MUST BE LISTED AND LABELED. NORMALLY, SCHEDULE 40 PVC IS ALLOWED INSIDE A BUILDING WALL AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH THE APPROPIATE AHJ. FLEX CONDUIT IS NOT PERMITTED.

IF A SECONDARY HANDHOLE IS REQUIRED BETWEEN THE NEW TRANSFORMER AND THE SERVICE AND METERING EQUIPMENT, THE

SERVICE TERMINATING ENCLOSURE PER SECTION 700 REQUIREMENTS.

LID SHALL BE MARKED "SDG&E". HANDHOLE NOT SHOWN ON FIGURE 1.

- 3. AT LEAST A 3-INCH LAYER OF CONCRETE (2 SACKS 3/8-INCH ROCK) ABOVE AND 2 INCHES ON EACH SIDE OF THE CONDUIT. REDUCED DEPTHS MUST BE APPROVED BY THE SDG&E PROJECT PLANNER AND INSPECTOR.
- B. THE TRENCH MUST HAVE AN EVEN SLOPING GRADE TO ALLOW ROOM FOR A 90 DEGREE BEND INTO THE BOTTOM OF ANY CUSTOMER-OWNED OR SDG&E FACILITY. DO NOT CUT BENDS. THE TRENCH DEPTH IS TO BE DETERMINED AT THE PRE-CONSTRUCTION MEETING.

REV	CHAN	_	DR		DSN		1	REV			e without permission i	DR		DSN		DATE	
KEV	CHAIN	IGE	DK	DI	DSN	APV	DATE	KLV		лА	NGE	DK	DI	DSN	APV	DAIL	
С	EDITORIAL	EDITORIAL CHANGES ARC IPJ IPJ KRG 08/07/2023 F															
В	FORMAT	TTING	EDM	JIK	-	-	07/19/2021	Е									
Α	EDITORIAL	CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X Indicates Lat	est Re	visio	n	Con	pletely Revi	sed	New Page		Information Rem	noved					
	SHEET			SDC	S&E E	LECTF	RIC SERVIC	E ST	ANDARDS & GI	JIDI	ES						
	SHEET													ς	G31	1 2	
	2 OF 3	PF	RIMA	RY	& S	ECO	NDARY \	VOL	TAGE UNDI	ER(GROUND			SG311.2			
	2 01 3								SES FROM								

INSTALLATION (CONT'D):

C. WHEN TRENCHING TO AN EXISTING SDG&E FACILITY, THE APPLICANT/CONTRACTOR SHALL COMPLETE THE TRENCH AND INSTALLATION OF CONDUIT UP TO THE EXISTING FACILITY UNLESS IT IS DETERMINED BY AN AUTHORIZED SDG&E EMPLOYEE THAT SUCH AN INSTALLATION PERFORMED BY THE APPLICANT/CONTRACTOR WOULD EXPOSE WORKERS TO, OR CREATE, A POTENTIAL HAZARD. IN THIS CASE, SDG&E WOULD PERFORM TRENCHING AS INDICATED ON THE CONSTRUCTION WORK ORDER. DIGGING UNDER ENERGIZED PAD MOUNTED EQUIPMENT AND INSTALLATION OF CONDUIT INTO ENERGIZED PAD MOUNTED EQUIPMENT WILL ALWAYS BE THE RESPONSIBILITY OF SDG&E.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

- a. SEE UG3373 FOR SDG&E CONDUIT AND FIITINGS.
- b. SEE UG3376 FOR CONCRETE SLURRY EQUIPMENTS.
- c. SEE UG3941 FOR RESIDENDTILA RISER AND CONDUIT.
- d. SEE UG3948 FOR SEALING CONDUITS.
- e. SEE OH1404UG4204 FOR CABLE POLE CONDUIT REQUIREMENTS.
- (f.) SEE UG4500 FOR GROUNDING SPECIFICATIONS.
- (g.) SEE SG309 FOR ADDITIONAL INFORMATION.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	08/07/2023	F						
В	FORMATTING	EDM	JIK	1	-	07/19/2021	Е						
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D						_

SHEET 3 OF 3


Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

PRIMARY & SECONDARY VOLTAGE UNDERGROUND SYSTEM ON CUSTOMER PREMISES FROM CABLE POLE

SG311.3

SCOPE: THIS STANDARD SHOWS A TERMINATION OF A CUSTOMER-OWNED 2-INCH OR 3-INCH CONDUIT BEND AND RISER AT A BUILDING.



INSTALLATION:

- A. CONTACT DESIGN & PROJECT MANAGEMENT AT THE NEAREST SDG&E REGIONAL OFFICE CLOSEST TO THE JOB SITE FOR AN ELECTRIC METER & SERVICE LOCATION FORM PRIOR TO THE START OF CONSTRUCTION. (g)
- (B) G.O. 128 RULE 33.4-D REQUIRES ONE OF THE FOLLOWING DOWN TO AN 18-INCH DEPTH ON PRIVATE PROPERTY:
 - 1. STEEL CONDUIT
 - 2.SCHEDULE 40 PVC OR SCHEDULE 80 PVC CONDUIT WITH A MINIMUM WALL THICKNESS OF 1/8-INCH
 - 3.AT LEAST A 3-INCH LAYER OF CONCRETE ABOVE AND 2 INCHES ON EACH SIDE OF THE CONDUIT

REV	CHAN	IGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE		
С	EDITORIAL	CHANGES	ARC	IPJ	IPJ	KRG	01/18/2024	F								
В	FORMAT	ITING	EDM	JIK	-	-	07/19/2021	Е								
Α	EDITORIAL	AL CHANGES - LSM IPJ TPM 11/01/2017 D														
	CLIEFT	X Indicates Late	icates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES													
	SHEET 1 OF 2 CUSTOMER – OWNED CONDUIT BEND & RISER AT BUILDING												SG312.1			

INSTALLATION (CONT'D):

- WHEN THE TRENCH IS BUTTED AGAINST THE BUILDING, THE END OF THE TRENCH SHALL BE EXCAVATED AT A ONE-TO-ONE SLOPE IF UNDERMINING IS SUSPECTED AT THE BUILDING.
- (D) THE 90 DEGREE BEND MUST BE INSTALLED DEEP ENOUGH TO CONNECT TO THE CONDUIT ON THE BOTTOM OF THE TRENCH.
- (E) CONDUIT MANUFACTURER MUST BE SDG&E APPROVED.
- F TYPE AND SCHEDULE OF CONDUIT ON OR WITHIN A BUILDING OR STRUCTURE TO BE INSTALLED PER THE BUILDING INSPECTOR'S REQUIREMENTS AND MUST BE LISTED AND LABELED. NORMALLY SCHEDULE 40 PVC IS ALLOWED INSIDE A BUILDING WALL AND SCHEDULE 80 PVC IS REQUIRED WHEN EXPOSED ON AN EXTERIOR WALL. CONSULT WITH THE APPROPRIATE INSPECTION AUTHORITY HAVING JURISDICTION (AHJ). FLEX CONDUIT IS NOT PERMITTED.
- (G) SERVICE LATERAL CONDUIT SIZED AND SPECIFIED BY SDG&E. CONSULT WITH THE SDG&E PLANNER.

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	STUD, 2" X 4" (MIN.)	AS REQ'D			
2	MUDSILL	AS REQ'D			
3	COUPLING, CONDUIT	AS REQ'D			
4	SURFACING MATERIAL, EXTERIOR	AS REQ'D			
5	BEND, RISER	AS REQ'D			
6	BEND, CONDUIT, 3"	AS REQ'D			

NOTES:

- (I) A STRAIGHT PIECE OF 3-INCH CONDUIT AND A 90 DEGREE BEND WITH A 36-INCH MINIMUM RADIUS IS REQUIRED. (f)
- (II) POINT CONDUIT STUB IN THE DIRECTION OF SUPPLY SOURCE NORMALLY AT 45 DEGREE ANGLE FROM OUTER FACE OF BUILDING WALL.

REFERENCE:

- a. SEE UG3367 FOR TRENCH PARALLELING FOUNDATIONS.
- oxt(b) SEE UG3370 (SAN DIEGO COUNTY) OR UG3371 (ORANGE COUNTY) FOR TRENCH DEPTHS, SHADING AND BACKFILL REQUIREMENTS.
- (c) See UG3942 for Minimum Bending Radius.
- d. SEE UG3948 FOR SEALING CONDUITS.
- e. SEE UG3950 FOR FIELD HEATING SERVICE LATERAL CONDUITS.
- (f) SEE UG3942, NOTE C FOR 2-INCH CONDUIT INSTALLATIONS.
- (g) SEE SG2.
- (h) SEE UG3941.
- (i) SEE SG309 FOR ADDITIONAL INFORMATION.

	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																
REV CHANGE DR BY DSN APV DATE REV CHANGE DR BY DSN APV DA															DATE		
С	EDITORIAL	CHANGES	ARC	IPJ	IPJ	KRG	01/18/2024	F									
В	FORMAT	TTING	EDM	JIK	-	-	07/19/2021	Е									
Α	EDITORIAL	CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
X Indicates Latest Revision Completely Revised New Page Information Removed																	
	SHEET SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																

SHEET 2 OF 2

CUSTOMER – OWNED CONDUIT BEND & RISER AT BUILDING SG312.2

SCOPE: THIS STANDARD SHOWS TYPICAL CABLE POLE RISER POSITIONS FOR SDG&E AND COMMUNICATION COMPANIES. **ANCHOR** 1)OR(2) LOCATION (1)OR(2)5 (5) 4 CLIMBING CLIMBING **SPACE SPACE**) OR (2) 6 8 (в) ANCHOR (6)(B)(C **CONFIGURATION 1 CONFIGURATION 2** DEADEND MULTIPLE POWER RISER THROUGH MULTIPLE POWER RISER FIGURE 1 PREFERRED CONSTRUCTION **CLIMBING SPACE ANCHOR** (1)OR(2) OR(2 6 6 FIGURE 3 CLIMBING CLIMBING **NEW CONSTRUCTION SPACE SPACE** WITH EXISTING SDG&E RISER 8 6 DEADEND OR THROUGH CONSTRUCTION MULTIPLE RISER **ANCHOR CONFIGURATION 1 CONFIGURATION 2** DEADEND SINGLE POWER RISER THROUGH SINGLE POWER RISER FIGURE 2 ALTERNATE CONSTRUCTION **INSTALLATION:** f (a f) COMMUNICATIONS ONLY POINT OF ATTACHMENT FOR LADDER ARM BRACKET CONSTRUCTION SHALL BE ON THE BACKSIDE OF LADDER ARM BRACKET ASSEMBLY, GALVANIZED UNISTRUT PIPE CLAMPS SHALL BE USED TO SECURE THE CONDUIT. COMMUNICATIONS MAY ATTACH ON THE BACK OF THE LADDER ARM ASSEMBLY ALONGSIDE SDG&E'S RISER. LADDER ARMS MAY BE INSTALLED BY COMMUNICATIONS COMPANIES PROVIDED THEY ARE INSTALLED PER SDG&E CONSTRUCTION STANDARDS AND MEET SDG&E MATERIAL SPECIFICATIONS. $(\,\mathsf{B}\,)$ for New Construction with an existing SDG&E Riser on the Pole (Figure 3), one 3-inch riser maximum on the Pole AND ONE 3-INCH RISER MAXIMUM ON THE BACKSIDE OF THE LADDER ARM BRACKET ARE PERMITTED BACK-TO-BACK. (C) WHEN A LADDER ARM IS EXISTING, AND THE BACK OF LADDER ARM POSITIONS AND POLE POSITIONS ON COMMUNICATIONS SIDE OF POLE ARE OCCUPIED, ADDITIONAL COMMUNICATIONS RISERS MUST BE PLACED ON ANOTHER POLE. © 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. BY DSN APV **REV** DATE **CHANGE** DR DATE **REV CHANGE** DR BY DSN APV C F В **FORMATTING FDM** JIK 07/19/2021 Ε **EDITORIAL CHANGES** LSM TPM 11/01/2017 Α IPJ **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG313.1 1 OF 2 STANDARD JOINT CABLE POLE RISER POSITION USING

LADDER ARM BRACKET & SINGLE RISER

BILL OF M	ATERIALS:				
ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	RISER, PRIMARY, SDG&E	AS REQ'D		1	
2	RISER, SECONDARY, SDG&E	AS REQ'D		1	
3	RISER, EXISTING, SDG&E	AS REQ'D		-	
4	GROUND, ELECTRIC, SDG&E	AS REQ'D		-	
5	ASSEMBLY, BRACKET, LADDER ARM	AS REQ'D			
6	RISER, POSITION, COMMUNICATION	AS REQ'D		-	
7	TANGENT THROUGH POSITION, COMMUNICATION	AS REQ'D			
8	GROUND, COMMUNICATION	AS REQ'D			

NOTES:

- I. 1/2 POLE CLIMBING SPACE APPLIES TO A LEVEL 4 FEET BELOW THE LOWEST LEVEL OF FACILITIES (COMMUNICATIONS, SECONDARY, PRIMARY, ETC.). (h)
- II. CHANGES TO THESE STANDARD RISER POSITIONS MUST NOT REDUCE THE CLIMBING SPACE TO LESS THAN 1/2 POLE.
- III. CONDUIT RISER AT BASE OF POLE NOT TO INFRINGE ON CURB OR SIDEWALK POSITIONS.
- IV. SPARE CONDUITS ARE NOT CONSIDERED AS RISERS.

REFERENCE:

- a. PVC RISERS ARE NOT PERMITTED WITHIN THE CLIMBING SPACE PER OH1414UG4214.
- b. NO CATV OR TELCO JUMPERS ALLOWED IN CLIMBING SPACE PER G.O. 95 RULE 84.7.
- C. SEE OH225 FOR ALLOWABLE G.O. 95 CLIMBING SPACE OBSTRUCTIONS.
- d. SEE 0H363UG4205 FOR INSTALLATION OF POLE STEPS.
- e. SEE OH1403UG4203 FOR POLE QUADRANT AND RISER IDENTIFICATION.

Indicates Latest Revision

- f. SEE OH1404UG4204 WHEN INSTALLING A SINGLE RISER, MODIFYING EXISTING CABLE POLE TO INCLUDE SECOND RISER, OR FOR MULTIPLE CONDUIT RUNS AND JOINT POLE INSTALLATION.
- 9. SEE UG4620 FOR TELECOMMUNICATIONS INSTALLATION.
- (h) SEE OH430 FOR CLIMBING SPACE REQUIREMENTS.
- (i)SEE UG4202.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 2

Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG313.2

Information Removed

SCOPE: THIS STANDARD SHOWS CABLE POLE RISER LOCATIONS, SDG&E QUADRANT AND SIGN FOR MARKING POLE RISER INSTALLATIONS.




FIGURE 1
DEADEND CONSTRUCTION MULTIPLE POWER RISER




FIGURE 2
THROUGH CONSTRUCTION MULTIPLE POWER RISER




FIGURE 3
THROUGH CONSTRUCTION MULTIPLE POWER RISER




FIGURE 4
DEADEND CONSTRUCTION SINGLE POWER RISER




FIGURE 5THROUGH CONSTRUCTION SINGLE POWER RISER

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 3 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CABLE POLE QUADRANT & RISER IDENTIFICATION

SG314.1

INSTALLATION:

- (A) NAIL THE SIGN TO THE RISER POLE APPROXIMATELY 5 FEET ABOVE GROUND WITH THE PROPER SIDE SHOWING.
- (B) USE ONE MARKER TO SHOW SDG&E RISER LOCATION.

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	SIGN, MARKER, YELLOW PLASTIC	1	1403/4203	S476312	
2	NAILS, GALV. 1 3/4"	AS REQ'D		S492192	
3	BRACKET, LADDER ARM	AS REQ'D			
4	COMMUNICATIONS	AS REQ'D			
5	ANCHOR	AS REQ'D			
6	SDG&E	AS REQ'D			
7	RISER, EXISTING, SDG&E	AS REQ'D			
8	TELCO OR CATV	AS REQ'D			

NOTES:

(I) NO LARGER THAN 3 INCHES.

REFERENCE:

a. SEE OH1402UG4202 FOR STANDARD JOINT CABLE POLE RISER POSITIONS.

Indicates Latest Revision

- b. SEE OH1404UG4204 FOR CABLE POLE RISER INSTALLATION.
- (c) SEE UG4203.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


New Page

Information Removed

SG314.2

Completely Revised

SCOPE: THIS STANDARD SHOWS THE SIGN USED FOR MARKING POLE RISER INSTALLATIONS.



INSTALLATION:

- A. USE THE SIDE OF THE SIGN STATING, "PLACE ELECTRIC RISER HERE" (FRONT), WHEN LADDER ARM BRACKETS ARE INSTALLED.
- B. FOR ALTERNATE CONSTRUCTION, USE THE SIDE OF THE SIGN STATING, "PLACE ELECTRIC RISER HERE 1 IN. CLEAR FROM POLE" (REVERSE), WHEN A SINGLE SDG&E CONDUIT IS INSTALLED.
- C. REMOVE SIGN WHEN POLE RISER(S) IS/ARE INSTALLED.

BILL OF MATERIALS: NONE

NOTES:

- I. A SIGN IS AVAILABLE TO MARK SDG&E RISER LOCATIONS ON THE CABLE POLE. THE SIGN IS MADE OF FLEXIBLE PLASTIC, WITH RAISED LETTERING ON EACH SIDE. SIGNS ARE TO BE ATTACHED TO POLES WITH 1 3/4-INCH NAILS. SEE BILL OF MATERIALS ON PAGE 2 FOR STOCK NUMBERS.
- II. "PLACE ELECTRIC RISER HERE, SDGE" IS PRINTED ON THE FRONT SIDE, SHOWING 3 POLE RISER POSITIONS, with "PLACE ELECTRIC RISER HERE 1 IN. CLEAR FROM POLE, SDGE" PRINTED ON THE REVERSE SIDE.
- III. WHEN THE RISER LOCATION HAS BEEN DETERMINED, THE SIGNS ARE TO BE PLACED ON THE POLE, APPROXIMATELY 5 FEET ABOVE GROUND LEVEL BY THE CUSTOMER PROJECT PLANNER, PROJECT COORDINATOR, ELECTRIC SUPERVISOR, INSPECTOR, OR WORKING FOREMAN SETTING THE POLE.

REFERENCE:

- a. SEE REFERENCES ON PAGE 2.
- b. SEE UG4203.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						


SHEET 3 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CABLE POLE QUADRANT & RISER IDENTIFICATION

SG314.3






FIGURE 5

ALTERNATE NEW CONSTRUCTION
FOR ONE RISER
UP TO 3' CABLE POLE RISER DETAIL K

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	СН	ANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/29/2023	F							
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е							
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							

SHEET 2 OF 5

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC CABLE POLE RISER INSTALLATION

SG315.2

DEFINITIONS:

- **FUTURE SPARE CONDUITS:** THE TERM "FUTURE SPARE CONDUITS" REFERS TO AN EMPTY CONDUIT SPECIFIED BY EITHER THE PROJECT PLANNER OR DISTRIBUTION PLANNING FOR AREAS WITH GROWTH POTENTIAL. FUTURE FEEDER CONDUIT SPECIFIED BY DISTRIBUTION PLANNING MUST BE SUPPORTED BY THE LONG TERM FEEDER ARRANGEMENT PLAN.
- **SPARE CONDUITS:** THE TERM "SPARE CONDUIT" REFERS TO AN EMPTY CONDUIT THAT IS SPECIFIED BY THE PLANNER FOR OPERATING AND MAINTENANCE REQUIREMENTS.

INSTALLATION:

- A) MOUNT FIRST BRACKET LADDER ARM NO LOWER THAN 9 FEET 6 INCHES. IF THE FIRST BRACKET EXTENDS TOWARD A STREET OR DRIVEWAY, OFFSET THE UNISTRUT CHANNEL TO CLEAR LARGE VEHICLES.
- (B) INSTALL AT LEAST ONE LADDER ARM BRACKET FOR EACH COUPLING JOINT OF CONDUIT, WITH A MAXIMUM 10-FOOT DISTANCE BETWEEN BRACKETS. ALL LADDER ARM BRACKETS TO BE ATTACHED TO THE POLE WITH BOLTS, NOT LAG SCREWS.
- (C) refer to individual cable pole standard for correct measurement.
- (D) CENTER CONDUIT POSITION SHALL BE USED FOR MULTIPLE SDG&E SECONDARY RUNS OR SDG&E TELECOMMUNICATION CONDUIT. OTHER CONDUIT POSITIONS ON THE FRONT OF THE BRACKET SHALL BE USED FOR A SINGLE OR DOUBLE CONDUIT. THE 8-INCH UNISTRUT CHANNEL (ITEM 19) MAY BE INSTALLED FOR A SINGLE RISER WHERE NO COMMUNICATIONS ARE ANTICIPATED.
- (E) RISERS OF PLASTIC CONDUIT SHALL BE EPC-80 PVC SCHEDULE 80, FROM THE GROUND LINE TO A LEVEL NOT LESS THAN 8 FEET ABOVE THE GROUND LINE PER G.O. 95 RULE 54.6-E AND SDG&E CONDUIT SIZING REQUIREMENTS.
- (F) FOR SINGLE RISER CONSTRUCTION, SEPARATION OF PIPE STRAPS (ITEM 8) SHALL BE 3 FEET MAXIMUM.
- (G) USE FIGURE 2, PREFERRED CONSTRUCTION FOR A SINGLE RISER WHEN:
 - i. INSTALLING A SINGLE RISER.
 - ii. ADDING A SINGLE RISER TO AN EXISTING RISER POLE. AN EXISTING SINGLE SDG&E RISER WOULD REMAIN ON THE POLE UNLESS IT IS CREATING A G.O. 95 INFRACTION. IF AN INFRACTION EXISTS, MOVE THE EXISTING RISER TO THE LADDER ARM BRACKET ALONG WITH THE NEW RISER SHOWN IN FIGURE 3.
- (H) USE FIGURE 3 WHEN INSTALLING MORE THAN ONE RISER.
- USE FIGURE 4 WHEN ADDING A RISER(S) TO AN EXISTING SDG&E RISER POLE. AN EXISTING SINGLE SDG&E RISER WOULD REMAIN ON THE POLE UNLESS IT IS CREATING A G.O. 95 INFRACTION. IF AN INFRACTION EXISTS, MOVE THE EXISTING RISER TO THE LADDER ARM BRACKET.
- (K) USE FIGURE 5 ALTERNATE CONSTRUCTION FOR A SINGLE RISER WHEN:
 - i. FIELD CONDITION DO NOT ALLOW ROOM FOR LADDER ARM BRACKETS (I.E., CONDUIT WOULD EXTEND INTO THE STREET, SIDEWALK, DRIVEWAY, ETC.). THIS INSTALLATION WOULD BE LIMITED TO ONE SDG&E RISER, UP TO 3 INCHES. (NO OTHER RISER(S) LARGER THAN 3 INCHES WOULD BE ON THE POLE.) ONE HALF OF THE POLE MUST REMAIL CLEAR FOR CLIMBING SPACE, AND G.O. 95 REQUIREMENTS MUST BE FOLLOWED.
 - ii. AN EXISTING RISER IS ALREADY ON THE POLE AND IT MAY BE RE-USED (I.E. REMOVING A STREET LIGHT FUSE BOX FROM A POLE, AND NEW CONDUIT WILL CONNECT TO THE EXISTING CONDUIT WHERE THE FUSE BOX WAS LOCATED, CUSTOMER RE-WIRE JOB, ETC.)
- ONE RISER ON THE POLE 3 INCHES MAXIMUM AND ONE RISER ON THE BACK SIDE OF THE LADDER ARM BRACKET 3 INCHES MAXIMUM ARE PERMITTED BACK-TO-BACK. A MAXIMUM OF TWO 4-INCH COMMUNICATIONS RISERS ARE PERMITTED ON THE BACK SIDE OF A LADDER ARM ASSEMBLY. THE ADJACENT POLE QUADRANT MUST BE VACANT TO INSTALL ANY 4-INCH RISER ON THE BACK OF THE LADDER ARM BRACKET AND MUST REMAIN VACANT AFTER INSTALLATION.
- (M) concrete encasement is required around the elbow(s) for 5-inch primary conduit(s).

	© 1998 - 2023 Sa	an Di	iego Gas & Elec	ctric Co	ompa	ny. All	rights r	reserved. Rer	noval	of th	is copyright no	tice	without permission i	is not p	ermit	ted un	der law	
REV	CHAN	IGE	IGE DR BY DSN APV DATE REV CHANGE DR B												BY	DSN	APV	DATE
С	EDITORIAL CHANGES ARC IPJ IPJ KRG 11/29/2023 F																	
В	B FORMATTING EDM JIK 07/19/2021 E																	
Α	EDITORIAL	CHA	NGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X	Indicates Lat	est Re	visio	n	Com	npletely Revi	sed		New Page		Information Rem	noved				
	SHEET				SDO	S&E E	LECTF	RIC SERVIC	E ST	ANE	ARDS & GU	IDI	ES					
3 OF 5 UNDERGROUND ELECTRIC CABLE POLE RISER INSTALLATION															S	G31	5.3	

INSTALLATION (CONT'D):

- (N) EACH CONDUIT RUN BETWEEN SUBSTRUCTURES, PADS, CUSTOMER SERVICE RISERS, ETC., SHALL BE ONE SIZE CONDUIT CONTINUOUSLY, I.E. NO REDUCERS ARE ALLOWED WITHIN A CONDUIT RUN EXCEPT WHERE THE CONDUIT ENTERS A SUBSTRUCTURE OR ABOVE GROUND LEVEL ON A RISER POLE. IF A 3-INCH RISER IS ALREADY INSTALLED, AND THE GRIP SIZE REQUIRES A 2-INCH RISER, A 2-INCH TO 3-INCH REDUCER MAY BE USED TO ACCOMMODATE THE GRIP. THE SAME WOULD APPLY TO OTHER SIZE CONDUITS AS HAS BEEN DESCRIBED. GRIPS ARE NOT REQUIRED ON SECONDARY RISERS.
- (O) SPARE CONDUITS SHOULD BE CONSIDERED OR INSTALLED WHEN:
 - i. REQUESTED BY A CUSTOMER AT THEIR OWN EXPENSE, BUT NOT EXCEED CONDUIT LIMITATIONS IN THIS STANDARD.
 - ii. IT IS ECONOMICAL TO INSTALL CONDUIT IN LIEU OF CONCRETE, BUT NOT EXCEED CONDUIT LIMITATIONS OF THIS STANDARD.
 - iii. BASED ON FUTURE CONSTRUCTION LIMITATIONS SUCH AS BENEATH BRIDGES, ROADWAYS AND RAILROAD TRACKS, BUT NOT TO EXCEED CONDUIT LIMITATIONS IN THIS STANDARD.
 - iv. IN CONVERSION OR NEW BUSINESS PROJECTS TO ALLOW EASY BYPASS OF THE POLE DURING REMOVAL. CONDUITS INSTALLED FOR THIS PURPOSE SHALL NOT GO UP THE POLE BUT SHALL EXTEND PAST THE POLE A MINIMUM OF 6 INCHES.
- (P) COMMUNICATIONS ONLY POINT OF ATTACHMENT FOR LADDER ARM BRACKET CONSTRUCTION SHALL BE ON THE BACK SIDE OF THE LADDER ARM BRACKET ASSEMBLY. GALVANIZED UNISTRUT PIPE CLAMP SHALL BE USED TO SECURE THE CONDUIT. COMMUNICATIONS MAY ATTACH ON THE BACK OF THE ASSEMBLY ALONGSIDE SDG&E'S RISER.

BILL OF MATERIALS:

ITEM	DESCRIPTION		WIRE SIZE	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
		3"				S279904	
1	COUPLING, SIZE AS REQUIRED	4"				S279936	
	-	5″				S280032	
	CONDUIT DICED DEND, COLIEDIUS 00, CITE AC	3"-36" R				S322472	CP-B
2	CONDUIT RISER BEND, SCHEDULE 80, SIZE AS REQUIRED	4"-48" R				S322480	CP-B
	REQUIRED	5"-48" R				S322488	CP-B
3	REDUCE, PVC, SCHEDULE 80, SIZE AS REQUIRED	4" TO 3"				S573408	4-3RED
3	REDUCE, PVC, SCHEDULE 60, SIZE AS REQUIRED	5" TO 4"				S573424	5-4RED
	CONDUIT DICED DVC CCHEDINE OO CITE AC	3″				S251552	S80
4	CONDUIT RISER, PVC, SCHEDULE 80, SIZE AS REQUIRED	4"				S251584	S80
	REQUIRED	5"				S251592	S80
		3″				S280544	
5	COUPLING, PVC, SCHEDULE 80	4"				S280576	
		5″				S280592	
		3″				S280448	
6	COUPLING, PVC, SCHEDULE 40, AS REQUIRED	4"				S280480	
		5"				S280496	
		3″		AS REQ'D	390	S251360	S40
7	CONDUIT, PVC, SCHEDULE 40, AS REQUIRED	4"				S251392	S40
		5"				S251408	S40
	CTDAD DIDE CALVANIZED 2 16D NATIC	3″				S697920	
8	STRAP, PIPE, GALVANIZED, 2-16D NAILS, GALVANIZED VI	4"				S697952	
	GALVANIZED	5″				S697984	
		3″	1/C# 2 SOL			S393984	2G1#2A
		3"	2-1/C# 2 SOL			S394048	3G2#2A
		3″	3-1/C# 2 SOL			S394048	3G3#2A
		4"	3-1/C# 2 SOL			S394104	4G3#2A
	CDID CADLE CIZE AC DECUIDED FOR DDIMARY	4"	3-1/C# 2 SOL			S394080	4G#2/0
9	GRIP, CABLE SIZE AS REQUIRED FOR PRIMARY RISER ONLY	4"	350 KCMIL			S394100	4G-350
	RISER ONLY N	5″	350 KCMIL			S394102	5G-350
		5″	750 KCMIL			S394096	5G-750
	-	5″	1000 KCMIL			S394098	5G1000
		4" 4/0			S394080	4G4/0C	
		5″	500 KCMIL			S394096	5G500C
10	PROTECTOR, NYLON CABLE					S558720	

	© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE		
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/29/2023	F								
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	V Indicates Late	est Re	visio	n	New Page Information Remo	wed				·					

SHEET 4 OF 5 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC CABLE POLE RISER INSTALLATION

SG315.4

<u>BILL OF MATERIALS (CONT'D):</u> **ITEM** DESCRIPTION WIRE SIZE QUANTITY STANDARD PAGE STOCK NUMBER **DESIGN UNITS** В BRACKET, LADDER ARM S167186 (X) LA-ARM 11 B S216702 (X 12 CHANNEL, DOUBLE GALV., 24 3/4" X 7/8" X 2 3/4" 13 NUT, CLAMPING CHANNEL, W/SPRING, 1/2" S503488 (VII) 14 CLAMP, PIPE, STEEL, GALV., UNISTRUT, 2" S229536 CL-2IN BOLT, MACHINE, GALV., 5/8" X (LENGTH AS REQ'D), В 15 390 1-SQUARE WASHER & DOUBLE COIL SPRING WASHER AS REQ'D 16 CLAMP, PIPE, STEEL, GALV., UNISTRUT, 4" S229664 CL-4IN 17 CLAMP, PIPE, STEEL, GALV., UNISTRUT, 5" S229668 CL-5IN CLAMP, PIPE, STEEL, GALV., UNISTRUT, 3" 18 S229632 CI-3IN D 19 CHANNEL, GALV., 8" S216840 20 COMMUNICATIONS

NOTES:

- I. ALL CABLE POLES RISERS, PRIMARY AND SECONDARY, SHALL BE 3-INCH MINIMUM CONDUIT.
- II. THIS CONSTRUCTION IS LIMITED TO A MAXIMUM OF FOUR SDG&E RISER (NO MORE THAN TWO PRIMARY RISERS).
- III. WHEN POSSIBLE, THE RISER SHOULD BE INSTALLED ON THE SIDE OF THE POLE OPPOSITE TRAFFIC FLOW TOWARDS SIDEWALK. THIS INCLUDES SINGLE RISER INSTALLATIONS.
- IV. SPARE CONDUITS SHALL BE CAPPED JUST ABOVE GROUND LEVEL TO PREVENT MOISTURE OR WIRE ENTRY AND TO KEEP OUT DEBRIS. SPARE CONDUITS ARE NOT TO BE CONSIDERED A RISER.
- (v) slope slurry encasement 1/4-inch above grade of paved area to drain water away from conduit riser.
- (VI) SINGLE RISER CONSTRUCTION, 4-INCH AND SMALLER.
- (VII) NOT SHOWN ON FIGURES.
- (X) THIS ITEM IS EXEMPT.

REFERENCE:

- a. SEE OH363UG4205 FOR POLE STEPS.
- b. SEE UG3944 FOR UG SERVICE FROM OH FACILITIES, MATERIAL REQUIREMENTS, ETC.
- c. SEE OH1402UG4202 FOR POSITIONING OF RISERS INVOLVING MORE THAN ONE UTILITY.
- $^{\prime}$ d $^{\prime}$ SEE OH1440UG4240 FOR NON-PORCELAIN TERMINAL MOUNTING BRACKET INSTALLATION AND MATERIALS.
- (e) SEE OH1414UG4214 FOR 0-750V UNDERGROUND SERVICE FROM AN OVERHEAD LINE.
- f. SEE UG4620 FOR TELECOMMUNICATIONS INSTALLATION.
- q. PVC RISERS ARE NOT PERMITTED WITHIN THE CLIMBING SPACE PER G.O. 95 RULE 22.2C.
- (h) SEE UG4204.
- (i) see ug3370 for depth requirements.

	© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	NGE		DR	BY	DSN	APV	DATE	REV		CI	HAN	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL	CHA	NGES	ARC	IPJ	IPJ	KRG	11/29/2023	F									
В	FORMA	TTIN	G	EDM	JIK	-	-	07/19/2021	Е									
Α	EDITORIAL	CHA	NGES	-	LSM	IPJ	TPM	11/01/2017	D									
	X Indicates Latest Revision Completely Revised New Page Information Removed																	
	CHEET				SDC	3&E El	LECTF	RIC SERVIC	E ST	ANDA	ARDS & GU	IDE	S					

SHEET 5 OF 5

UNDERGROUND ELECTRIC CABLE POLE RISER INSTALLATION

SG315.5

SCOPE: THIS STANDARD SHOWS REQUIREMENTS FOR INSTALLING AN UNDERGROUND ELECTRIC SERVICE LATERAL TO GASOLINE DISPENSING AND SERVICE STATIONS. A GASOLINE DISPENSING AND SERVICE STATION IS DEFINED AS A LOCATION WHERE GASOLINE OR OTHER VOLATILE FLAMMABLE LIQUIDS OR LIQUEFIED FLAMMABLE GASES ARE TRANSFERRED TO FUEL TANKS (INCLUDING AUXILIARY FUEL TANKS) OR SELF-PROPELLED VEHICLES.

TABLE 1

	CLASSIFIED SHADED AREAS												
CLASS/DIVISION	DESCRIPTION	SYMBOL											
CLASS 1, DIVISION 1	FLAMMABLE GASES OR VAPORS, HIGHLY HAZARDOUS, I.E. IGNITABLE CONCENTRATIONS CONFINED IN A PIT.												
CLASS 1, DIVISION 2	LIQUID, VAPOR OR GASES WILL NORMALLY BE CONFINED WITHIN CLOSED CONTAINERS OR CLOSED SYSTEMS.												

ATTENTION:

* UTILITY-OWNED UNDERGROUND FACILITIES ARE NOT ALLOWED BELOW THE SURFACE OF A CLASS 1, DIVISION 1 OR CLASS 1, DIVISION 2 LOCATION. $\stackrel{\frown}{a}$





FIGURE 1
FRONT VIEW



© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


INDEDCROUND ELECTRIC CERVICE LATERA

SG316.1

UNDERGROUND ELECTRIC SERVICE LATERAL GASOLINE DISPENSING & SERVICE STATIONS

NO I II RE	STALLATION: No. LL OF MATERIA OTES:) 5-FOOT RADIUS F) UTILITY UNDERG FERENCE:) SEE SG318 FOR III	L S: NONE FROM TIGHT FI ROUND SERVIC	E LAT	ΓERAL										SION	N 2 LO	CATIO	DNS.
REV	© 1998 - 2021 Sa		ectric (ny. All		eserved. Rei	moval (of this copyri		ice w		n is not p	permit BY	tted und	_	DATE
С								F									
В	FORMAT		EDM		-		07/19/2021										
Α	EDITORIAL C	HANGES Indicates La	-	LSM	IPJ		11/01/2017 pletely Revi	<u> </u>	n. 5		1	Tofarma V					
SHEET 2 OF 2 UNDERGROUND ELECTRIC GASOLINE DISPENSING &							E ST	SERVIC	& GUI	ΛΤΕ	RAL	emoved		S	G31	5.2	

SCOPE: THIS STANDARD SHOWS REQUIREMENTS FOR INSTALLING UNDERGROUND ELECTRIC SERVICE LATERALS AND ELECTRIC METER PANELS IN PROXIMITY TO ABOVE GROUND PROPANE TANKS.






FIGURE 1 FOR TANKS UP TO 500 GALLONS IN SIZE PLAN VIEW

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. UNDERGROUND ELECTRIC SERVICE LATERALS ARE NOT TO PASS WITHIN THE 10-FOOT CLEARANCE AREA AROUND THE PROPANE TANKS UP TO 500 GALLONS WHETHER IT IS ABOVE GROUND OR SUBTERRANEAN (25 FEET FOR ABOVE GROUND TANKS RANGING FROM 501 TO 2,000 GALLONS).

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SPORE ELECTRIC SERVICE STANDARDS & GOIDES

SG317.1

UNDERGROUND ELECTRIC SERVICE LATERAL & METER PANELS IN PROXIMITY TO PROPANE TANKS

NOTES (CONT'D):

- II. FOR TANKS LARGER THAN 2,000 GALLONS, CONSULT SDG&E SERVICE STANDARDS. UTILITY-OWNED UNDERGROUND FACILITIES ARE NOT ALLOWED BELOW THE SURFACE OF A CLASS 1, DIVISION 1 OR CLASS 1, DIVISION 2 LOCATION. (a)
- III. ABOVE GROUND PROPANE TANKS:
 - a. PROPANE TANKS COME IN THREE MAIN SIZES: 330, 500 AND 1,000 GALLONS. THE SIZE SELECTED NORMALLY DEPENDS ON THE PROPANE REQUIREMENTS AND THE SIZE OF THE STRUCTURE USING THE FUEL.
 - b. ELECTRIC METER PANELS ARE A SOURCE OF IGNITION FOR PROPANE GAS AND SHALL BE INSTALLED IN COMPLIANCE WITH THE FOLLOWING CLEARANCE REQUIREMENTS:

TABLE 1

IAPEL I	
	NTAL CLEARANCE S AROUND TANKS
TANK SIZE (GALLONS)	RADIAL CLEARANCE (FEET)
UP TO 500	10 MINIMUM
501 TO 2,000	25 MINIMUM

REFERENCE:

(a)SEE INSTALLATION NOTES ON SG318.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 4 Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC SERVICE LATERAL & METER PANELS IN PROXIMITY TO PROPANE TANKS SG317.2

SCOPE: THIS STANDARD SHOWS REQUIREMENTS FOR INSTALLING UNDERGROUND ELECTRIC SERVICE LATERALS AND ELECTRIC METER PANELS IN PROXIMITY TO SUBTERRANEAN PROPANE TANKS.






FIGURE 2 CLEARANCE REQUIREMENT FOR SUBTERRANEAN TANKS UP TO 2,000 GALLONS PLAN VIEW

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. UNDERGROUND ELECTRIC SERVICE LATERALS ARE NOT TO PASS WITHIN THE 10-FOOT CLEARANCE AREA AROUND THE PROPANE TANK WHETHER IT IS ABOVE GROUND OR SUBTERRANEAN.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	1	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 4

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC SERVICE LATERAL & METER PANELS IN PROXIMITY TO PROPANE TANKS SG317.3

NOTES (CONT'D):

- II. FOR TANKS LARGER THAN 2,000 GALLONS, CONSULT SDG&E SERVICE STANDARDS. (c)
- III. SUBTERRANEAN PROPANE TANKS:
 - a. SUBTERRANEAN TANKS UP TO 2,000 GALLONS REQUIRE A 10-FOOT MINIMUM HORIZONTAL CLEARANCE FROM SOURCES OF IGNITION. THE ONLY VISIBLE PART OF THESE TANKS IS THE RISER COVER, WHICH IS ABOUT 1-FOOT HIGH AND 1-FOOT DIAMETER.
 - b. For the purposes of planning the placement of an underground electric service lateral and meter location, the customer is responsible for providing the tank size and dimension specifications for subterranean tanks, and marking out the footprint of the tank at the job site. The 10-foot clearance requirement will be measured from the outside edge of the marked out footprint.

REFERENCE:

- a. FOR LIQUEFIED PETROLEUM GAS CODE, SEE NFPA 58.
- b. SEE CALIFORNIA FIRE CODE: LIQUEFIED PETROLEUM GASES, CHAPTER 38.
- (c) see installation notes on SG318.

© 1998 - 2021 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 4

Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND ELECTRIC SERVICE LATERAL & METER PANELS IN PROXIMITY TO PROPANE TANKS

SG317.4

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR INSTALLING UNDERGROUND ELECTRIC SERVICE LATERALS AND SERVICE AND METERING EQUIPMENT NEAR GASOLINE DISPENSING EQUIPMENT AND PROPANE TANKS.

INSTALLATION:

- A. IF THE SERVICE LATERAL, USING THE SHORTEST PRACTICABLE ROUTE, WILL NOT EXTEND THROUGH A "HAZARDOUS (CLASSIFIED) LOCATION", THE SERVICE AND METERING EQUIPMENT MAY BE LOCATED ON THE BUILDING.
- B. IF THE SERVICE LATERAL, USING THE SHORTEST PRACTICABLE ROUTE, WOULD EXTEND THROUGH A "HAZARDOUS (CLASSIFIED) LOCATION", THE SERVICE AND METERING EQUIPMENT MUST BE GROUPED AND LOCATED OUTSIDE, AND PRIOR TO, THE "HAZARDOUS (CLASSIFIED) LOCATION". THE CUSTOMER WOULD THEN EXTEND THEIR METERED CONDUCTORS AS PREMISES WIRING IN ACCORDANCE WITH REQUIREMENTS OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).
- C. IF THERE IS AN ACCEPTABLE LOCATION ON THE BUILDING FOR THE SERVICE AND METERING EQUIPMENT WHICH IS "OUTSIDE THE HAZARDOUS (CLASSIFIED) LOCATION", AND ADDITIONAL FACILITIES COULD BE INSTALLED SO THE SERVICE LATERAL WOULD NOT ENCROACH IN THE "HAZARDOUS (CLASSIFIED) LOCATION", BUT WOULD NOT BE THE SHORTEST PRACTICABLE ROUTE FOR THE SERVICE LATERAL FROM THE SDG&E CLOSEST SOURCE, THE CUSTOMER MAY BE GIVEN THE OPTION TO:
 - 1. LOCATE THEIR EQUIPMENT AS STATED IN B, OR
 - 2. PAY THE TOTAL ESTIMATED RULE 2, I, SPECIAL FACILITIES AND MAINTENANCE, CHARGES FOR THE ADDITIONAL SERVICE LATERAL CONDUCTORS REQUIRED TO AVOID THE "HAZARDOUS (CLASSIFIED) LOCATION".

CAUTION:

* CONFIRM THAT THE FUTURE EXPANSION OF TANKS, PUMPS, ETC., WILL NOT ENCROACH INTO THE AREA OF SDG&E'S SERVICE LATERAL CONDUCTORS INSTALLED WITHIN THE CUSTOMER'S CONDUIT.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

a. REFER TO SG019 FOR MINIMUM CLEARANCE AND SEPARATION REQUIREMENTS OF ENERGIZED OVERHEAD CONDUCTORS FROM CONTAINERS OF FLAMMABLE OR EXPLOSIVE MIXTURES, SUCH AS PROPANE TANKS.

	© 1998 - 2021 S	an Diego Gas & El	ectric C	compa	ny. All	rights ı	reserved. Rer	noval	of th	is copyright n	otice	without permission	is not	permit	ted un	der law	
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		С	HAN	IGE	DR	BY	DSN	APV	DATE
С								F									
В	FORMAT	TING	EDM	JIK	-	-	07/19/2021	Е									
Α	EDITORIAL (CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X Indicates L	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Re	moved				
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																


SHEET 1 OF 1

INDEDCEOUND ELECTRIC SERVICE NEAR CASC

SG318.1

UNDERGROUND ELECTRIC SERVICE NEAR GASOLINE DISPENSING EQUIPMENT & PROPANE TANKS

SCOPE: THIS STANDARD PROVIDES CLEARANCE REQUIREMENTS FOR CUSTOMER-OWNED UNDERGROUND ELECTRIC SERVICE LATERAL CONDUIT, AND SUBSTRUCTURE(S) WHEN REQUIRED, FROM LEACH FIELDS.



INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. SAN DIEGO COUNTY DEPARTMENT OF HEALTH SERVICES ESTABLISHES THE STANDARD FOR THE PROXIMITY OF LEACH LINES AND SEEPAGE PITS TO UTILITY TRENCHES. THIS STANDARD MAY AFFECT THE ROUTE AND POSITION OF CUSTOMER GAS AND ELECTRIC SERVICE LATERALS.
- (II) THERE SHALL BE A FIVE (5) TO ONE (1) SETBACK REQUIRED FROM ALL UTILITY TRENCHES TO THE TILE LINES (LEACH LINES) OR SEEPAGE PIT. THE SETBACK SHALL BE MEASURED FROM THE TOP OF THE UTILITY TRENCHES TO THE CLOSEST EDGE OF THE TILE LINE OR SEEPAGE PIT. THE DEPTH OF THE UTILITY TRENCH SHALL BE MEASURED FROM THE GROUND SURFACE TO THE BOTTOM OF THE TRENCH.

© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CI	HA	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	IPJ	IPJ	KRG	11/02/2023	F								
В	FORMATTING	EDM	JIK	-	-	07/19/2021	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates Lat	est Re	evisio	n	Con	pletely Revi	sed	New Page		Information Rem	noved				

SHEET 1 OF 2

ICCVISION		Completely Revised		ivew rage		Iniomation Removed
SDG&	E E	LECTRIC SERVICE STA	ANE	Dards & Gl	JIDI	ES

SG319.1

UNDERGROUND ELECTRIC LATERAL FROM LEACH FIELDS

NOTES (CONT'D):											
III. A 2-FOOT MINIMUM SEPARATIONS IS REQUIRED BETWEEN SERVICE LATERAL CONDUITS AND SEPTIC TANKS AND TIGHT LINES.											
IV.	ALTHOUGH THE C THE PROJECT PLA ROUTES THROUG	INER SHOULD BE AWARE OF T	FOR H HE LO	HAS THE U DCATION (LTIM DF TH	ATE RESPONSIBILITY FOR ADHERIN IE LEACH LINES IN ORDER TO AVOII	G TO	THE	SE RI ISHIN	EQUII IG SE	REMENTS, RVICE
REFERENCE: NONE											
© 1998 - 2023 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.											
REV	CHAN				REV	CHANGE	DR		DSN		DATE
С	EDITORIAL (11/02/2023							
В	FORMAT			07/19/2021							
Α	EDITORIAL (HANGES - LSM IPJ X Indicates Latest Revision		11/01/2017 pletely Revi		New Page Information Remo	nved				
	CHEET					ANDARDS & GUIDES	veu				
	SHEET	UNDERGROUND ELECTRIC								G31	9.2
	2 OF 2	UI LAT	ERA	KGKUU L FROM	IND	ELECTRIC ACH FIELDS					

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR EXISTING SIDA SERVICE FOR PANEL REWIRES, UPGRADES AND RELOCATIONS.

DEFINITIONS:

• **SIDA DESCRIPTION:** SECONDARY-IN-DUCT ALUMINUM (SIDA) AND CABLE IN CONDUIT (CIC) IS A CABLE ASSEMBLY THAT INCLUDED INSULATED CONDUCTORS WITHIN FLEXIBLE DUCT. BOTH NAMES REFER TO THE SAME PRODUCT. THIS PRODUCT WAS PUT IN PRODUCTION IN 1968 AND DISCONTINUED THE USE AROUND 1978.

INSTALLATION:

- A. CUSTOMERS REWIRING, UPGRADING, AND/OR RELOCATING THEIR SERVICE PANEL MUST ADHERE TO CURRENT SDG&E UNDERGROUND CONSTRUCTION STANDARDS (INCLUDING CONDUIT); HOWEVER, IF SIDA SERVICE EXISTS, IT MAY REMAIN PROVIDED THE FOLLOWING CONDITIONS ARE MET:
 - 1. MAXIMUM PANEL SIZE IS NOT EXCEEDED BY SIDA CABLE SIZE AS SHOWN ON THE SIDA TABLE.
 - 2. EXTENDING OR SPLICING FROM EXISTING SIDA IS NOT ALLOWED; NEW TERMINATION POINTS MUST BE AT OR BELOW EXISTING POINTS.
 - 3. THE EXISTING SIDA SERVICE APPEARS TO BE IN GOOD CONDITION, FREE OF DEFECTS AND IMPERFECTIONS WHICH MAY IMPACT SAFETY AND RELIABILITY.
 - 4. IF, FOR ANY REASON, THE EXISTING SIDA SERVICE CANNOT BE UTILIZED, THE CUSTOMER MUST PROVIDE NEW TRENCH AND CONDUIT TO THE EXISTING SOURCE PER CURRENT SDG&E STANDARD SG309.

TABLE 1

SIDA TABLE								
EXISTING SIDA TABLE (AL)	EXISTING CONDUIT SIZE (IN)	MAXIMUM PANEL REPLACEMENT (AMPS)						
#2	1 1/4	125						
1/0	1 1/2	150						
3/0	2	200						
350	2 1/2	225						

BILL OF MATERIALS: NONE

NOTES:

- I. ELECTRIC SERVICE PANEL RELOCATIONS REQUIRE TRENCHING AND NEW CONDUIT FROM **NEW PANEL** LOCATION TO SDG&E SOURCE.
- II. INTERCEPTING SIDA SERVICE WITH A HANDHOLE, OR ANOTHER SUBSTRUCTURE IS NOT ALLOWED FOR A NEW PANEL.
- III. NON-PLASTIC CONDUIT, SUCH AS STEEL CONDUIT, DOES NOT MEET CURRENT SDG&E CONSTRUCTION STANDARDS.
- IV. THE PLANNER WILL DETERMINE WHETHER THE CUSTOMER MUST POTHOLE EXISTING SERVICE TO DETERMINE WHETHER SIDA EXISTS. POTHOLES ARE THE CUSTOMER'S RESPONSIBILITY AND DIGALERT NOTIFICATION IS REQUIRED PRIOR TO DIGGING.

V. SOLAR READY METER PANELS:

SOME MANUFACTURERS MAY MARKET "SOLAR READY" RESIDENTIAL METER PANELS THAT HAVE A 200 AMP BUS RATING BUT LIMIT THE SIZE OF THE MAIN BREAKER FOR UTILITY SERVICE PURPOSES TO 125 AMP MAXIMUM FOR AN EXISTING #2 SIDA SERVICE OR 150 AMP MAXIMUM FOR AN EXISTING 1/0 SIDA SERVICE. THE MANUFACTURER LABELS THE METER PANEL ACCORDINGLY AS A 125 AMP OR A 150 AMP PANEL AND SPECIFIES THE MAXIMUM SIZE OF MAIN BREAKER. THIS ENABLES SDG&E TO CONTINUE SERVING A CUSTOMER WITH AN EXISTING SIDA SERVICE, AND THE CUSTOMER HAS THE BUS CAPACITY TO MEET CODE REQUIREMENTS FOR A LARGER PV INTERCONNECTION.

THIS MANUFACTURER LISTING, LABELING AND THEREBY LIMITING THE SIZE OF THE MAIN BREAKER, IS THE BASIS FOR ALLOWING THE EXISTING SIDA TO REMAIN IN SERVICE. THE DERATING OF THE METER PANEL CAN ONLY BE DONE BY THE MANUFACTURER. DERATING A METER PANEL IS NOT ACCOMPLISHED BY A CUSTOMER OR THEIR AGENT CHANGING OUT THE MAIN BREAKER TO ONE OF LOWER AMPACITY. SDG&E PROJECT PLANNER/SERVICE PLANNER APPROVAL IS REQUIRED PRIOR TO CONSTRUCTION.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	1	-	07/19/2021	F						
В	REVISION	-	CSE	IPJ	CZH	04/13/2020	Е						
Α	NEW PAGE	-	IPJ	SSH	TPM	08/20/2019	D	NOTES UPDATE	PS	JTM	JTM	KRG	01/03/2025

SHEET 1 OF 1 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

EXISTING SIDA SERVICE - PANEL REWIRES, UPGRADES, AND RELOCATIONS

SG320.1

<u>PAGE</u>	<u>SUBJECT</u>
502	ELECTRIC SERVICE AND METERING EQUIPMENT ALPHABETICAL SUBJECT INDEX
503	GENERAL INFORMATION
504	ELECTRIC METER AND SERVICE LOCATION - COMMERCIAL AND RESIDENTIAL PREMISES
505	BARRIERS FOR SERVICE AND METERING EQUIPMENT
506	ELECTRIC METER ROOM
507	SINGLE OR MULTIPLE METER INSTALLATIONS - COMMERCIAL OR RESIDENTIAL APPLICATIONS
508	METER CABINET RECESS FOR SINGLE METER RESIDENTIAL APPLICATION ONLY
509	ELECTRIC METER CABINET - COMMERCIAL OR RESIDENTIAL MULTI-METER INSTALLATIONS
510	ELECTRIC METERING IN MID-RISE AND HIGH-RISE BUILDINGS
511	ELECTRIC SERVICE DISCONNECTS AND METER SERVICE DISCONNECTS
512	RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT
513	TEST-BYPASS FACILITIES FOR SAFETY SOCKETS
514	SAFETY SOCKET METER CANS
515	TRANSFORMER RATED METERS AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT
516	METER TYPE AND SOCKET CLIP ARRANGEMENT
517	STANDARD SWITCHBOARD SERVICE SECTIONS
518	MOBILE HOME PARK SERVICE AND METER PEDESTALS
519	COMMERCIAL METER PEDESTALS
520	FIELD REPLACEMENT OF EXISTING 120V METER PEDESTAL
522	WIRELESS COMMUNICATIONS ON PRIVATE PROPERTY
523	WIRELESS COMMUNICATIONS PROVIDER – METERED ELECTRIC SERVICE
524	UNMETERED ELECTRIC SERVICE
525	METERING COMMUNICATIONS

NOTE: 521 HAS BEEN INTENTIONALLY OMITTED.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	02/07/2025	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1

Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE AND METERING EQUIPMENT TABLE OF CONTENTS

SG501.1

9	<u>SUBJECT</u>													Ē	PAGE
Е	ELECTRIC SERVICE	DISCONNECTS	AND	METE	R SEF	RVICE	DISCONN	ECTS.							511
G	GENERAL INFORMA	TION													503
	ADDITIONS, A	LTERATIONS O	r rei	NEWA	L OF I	EXIST	ING SERVI	CE AI	ND METERING E	QUIPMENT					504.2
	ELECTRIC MET	TER AND SERVI	CE LO	CATIO	ON RE	QUES	ST							.503,	504.2
	EXISTING GAS	METER BELOW	ELEC	CTRIC	: SER\	/ICE A	AND METER	RING.							504.2
	INGRESS AND	EGRESS TO ELI	ECTR1	IC SEI	RVICE	AND	METERING	EQU	IPMENT						504.2
	METER HEIGH	TS													504.1
	METER MARKI	NG													504.1
	METERED AND	UNMETERED (COND	UCTO	RS										503
	METER SOCKE	T SEALING RIN	GS												503
	READILY ACCE	SSIBLE DEFINI	TION												503
	SEALING OF M	IETERS AND ME	TERII	NG EC	QUIPM	IENT .									503
	SEALING REQU	JIREMENTS													503
	SERVICE ENTR	RANCE LIMITAT	IONS.												503
N	METER LOCATIONS														
	BARRIERS FOR	R SERVICE AND	METE	ERING	EQU	IPMEI	NTT								505
	COMMERCIAL	AND INDUSTRI	AL												504.3
	ELECTRIC MET	TER CABINETS													509
	ELECTRIC MET	TER CABINET RI	ECESS	s, SIN	GLE M	1ETER	R RESIDEN	TIAL A	APPLICATION						508
	ELECTRIC MET	TER ROOMS													506
	METER HEIGH	TS													504.1
	METER MARKI	NGS													504.1
	METER PEDES	TAL, COMMERC	IAL 0	-200 <i>A</i>	١										519.1
	METER PEDES	TAL, COMMERC	IAL 6	00A M	1AXIM	IUM, I	MULTI-MET	ER							519.4
	METER PEDES	TAL, FIELD REP	LACE	MENT	OF E	XISTI	NG 120V M	1ETER	R PEDESTAL						520
REV	© 1998 - 2025 Sa		ectric (ny. All DSN		eserved. Rei	moval o		ice without permission	is not	permit BY	ted un		DATE
C	CHAN	GE	DK	БТ	DSN	APV	DATE	F	CH	ANGE	DK	Dĭ	DSN	APV	DATE
В	FORMATTING/EDITO		EDM		JTM		02/07/2025								
Α	EDITORIAL (<u> </u>	<u> </u>	LSM		11/01/2017	D	N -	.					
	CHEET	X Indicates La	atest R				npletely Revi		New Page ANDARDS & GUI	Information Re	moved				
	SHEET												S	G50	2.1
	1 OF 4			CIK.	ALP	EKV) HAB	ETICAL	SUB	TERING EQL JECT INDEX	TEN I					

9	<u>SUBJECT</u>													<u> </u>	PAGE
	METER PEDES	TAL FOUNDATION	ON DI	ETAIL	S										519.6
	METER PEDES	TAL, RESIDENT	IAL												518
	MID-RISE AND	HIGH-RISE BU	ILDIN	IGS											510
	RESIDENTIAL														504.2
	UNACCEPTABL	.e meter loca	TION:	S											504.3
N	METER TYPE AND S	SOCKET OLIP AR	RANC	SEMFI	NT										516
	METERING COMMU														
	MOBILE HOME PAR														
	RESIDENTIAL SELF										•••••				510
							•					512	.1 – 5	12.4.	512.6
														•	
													•		
	-														
S	SAFETY SOCKET ME	ETER CANS	•••••					••••••					•••••		514
	ALUMINUM CC	NDUCTORS IN	SAFE	TY SC	CKET	MET	ER CANS								514.5
	NEUTRAL OR (GROUND COND	UCTO	R IN	SAFET	TY SO	CKET METI	ER CA	NS						514.5
		ETY SOCKET CA													514.3
	SAFETY SOCKE	ET CAN 100A (S	TAND	ARD	DUTY)									514.1
	SAFETY SOCKE	ET CAN 200A (H	IEAVY	DUT	Y)										514.2
	SAFETY SOCKE	ET METER CAN	USED	FOR	UNDE	RGRO	OUND SER\	/ICE							514.4
REV	© 1998 - 2025 Sa	_	ectric C		ny. All DSN		eserved. Rei	moval o		ce without permission	n is not	i -	ted und		DATE
C	CHAN	GL	DK.	10	DSIN	AFV	DAIE	F	СП	7.11UL	DK	<i>•</i> 1	DOIN	AFV	DAIE
В	FORMATTING/EDIT	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е							
Α	EDITORIAL (CHANGES	-	LSM	LSM	TPM	11/01/2017	D							
		X Indicates La	atest R				npletely Rev		New Page	Information Re	emoved	ı			
	SHEET			SDC	S&E E	LECTI	RIC SERVIC	E STA	Andards & Gui	DES		\Box			
	2 OF 4		ELE	CTR:	IC SI	ERV] HAR	CE AND	ME ^T	TERING EQU IFCT INDEX	IPMENT			S	G50	2.2

<u>s</u>	<u>SUBJECT</u>														<u>F</u>	PAGE
S	STANDARD SWITCH	HBOARD SERVIC	E SE	CTION	۱S											517
	SWITCHBOARI	D BUS/WIRE TAP	P DR/	4WIN	GS FC)R AP	PROVAL								5	517.1
	ELECTRIC UTI	LITY SERVICE EC	QUIP	MENT	REQ	UIRE	MENTS CON	MMIT	ΓΕΕ (EUSERC)						5	517.1
	MANUFACTURI	er's drawings	FOR	. APPR	ROVAL										[517.1
	METER SOCKE	ET AND TEST SW	/ITCH	I PANI	EL LA'	YOUT										517.9
	SWITCHBOARI	D SERVICE SECT	TON	DEFIN	NED											517.1
	SWITCHBOARI	D SERVICE SECT	TONS	3 PICT	ΓURΕΓ)								<mark>5</mark>	<mark>17.3-</mark> 5	<mark>517.6</mark>
	STANDARD SV	VITCHBOARD SE	RVIC	E SEC	CTION	1 0–60)0V								[517.3
	STANDARD SV	VITCHBOARD SE	RVIC	E SEC	CTION	1 0–60)OV OUTDC	OR/F	AINTIGHT ENC	LOSUF	RE					517.6
	STANDARD SW	VITCHBOARD SEI	RVIC	E SEC	TION	<mark>, 0-60</mark>	00V METER	SOCI	KET AND TEST	SWITC	CH PANEL LAY	<mark>YOUT.</mark>				<mark>517.9</mark>
		VITCHBOARD SE M METER SOCKE										<mark>/ICE</mark>			5:	17.11
	STANDARD SW INSTRUMENT	VITCHBOARD SEI TRANSFORMER (RVIC COM	e sec Parti	TION MENT	, 0–60 , 201	00V, -400A SING	SLE-PI	HASE SERVICE						5 :	17.14
	STANDARD SW TRANSFORME	VITCHBOARD SE R COMPARTMEN	RVIC IT 20	E SEC 1-1,0(TION T ,AOC	I, 0–6 THREE	00V, INSTF E-PHASE, <mark>3</mark>	RUME AND	NT <mark>4-WIRE SERVI</mark> (CES					5 :	17.15
	STANDARD SW TRANSFORME	VITCHBOARD SE R COMPARTMEN	RVIC	E SEC)01-3,	TION 000A	I, 0-60 , THR)0V, INSTR EE-PHASE,	rumen <mark>3 an</mark>	NT D 4-WIRE SERN	<mark>/ICES</mark> .					 5:	17.17
	STANDARD SW LINK AND CT S	VITCHBOARD SE SUPPORT FOR IN	:RVIC NSTR	E SEC	TION T TR	I, 0-6(ANSF	00V, 1,001- ORMER CO	-3,000 MPAR)A, REMOVABLE TMENTS WITH	<u>=</u> 4-INC∣	H BUS				 5:	17.19
		VITCHBOARD SE R COMPARTMEN								<mark>/ICES</mark> .					 5:	17.21
		VITCHBOARD SE SUPPORT FOR IN													 5:	17.23
	TEST-BYPASS	FACILITIES FOR	SAF	ETY S	OCKE	TS										513
	VENTILATION.														[517.2
Т	RANSFORMER RAT	ΓED METERS <mark>AΝΙ</mark>	D WA	<mark>ALL-M</mark> (OUNT	ED SI	ERVICE AN	D ME	TERING EQUIP	<mark>MENT</mark> [CURRENT TE	RANSF	ORM	ER (CT	¯)]	515
	COMBINATION	N CT AND METER	₹ SO(CKET (CAN-(OH SE	RVICE-WA	LL MC	OUNTED					51	.5.1, !	515.5
	COMBINATION	N CT AND METER	≀ SO(CKET (CAN-l	JG SE	RVICE-WAI	LL MC	UNTED					51	.5.1, 5	515.5
		an Diego Gas & Elec	-									_				
C	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CH	HANGE		DR	BY	DSN A	APV	DATE
В	FORMATTING/EDITO	ORIAL CHANGES	EDM		1	1										
Α	EDITORIAL C					-	11/01/2017		T							
	CHEET	X Indicates Lat	test K				npletely Revi		New Page ANDARDS & GU		nformation Rei	movea	\dashv			
	SHEET 3 OF 4	E	ELE	CTRI	ic si alp	ERVI HAB	CE AND ETICAL	ME ⁻ SUB	TERING EQ JECT INDE	UIPM (ENT			SO	G502	2.3

F

<u>SUBJECT</u> <u>PAGE</u>
CT MOUNTING BASE, 0-400A, 0-600V SERVICE
CT MOUNTING BASE, 201–800A, 0–600V SERVICE
METER SERVICE DISCONNECT
SOCKETS FOR TRANSFORMER RATED METERS
UNMETERED ELECTRIC SERVICE
WIRELESS COMMUNICATIONS ON PRIVATE PROPERTY
WIRELESS COMMUNICATIONS PROVIDER – METERED ELECTRIC SERVICE
WORKING SPACE, ELECTRIC SERVICE AND METERING EQUIPMENT, 0–600V
WORKING SPACE FOR NON-RESIDENTIAL SERVICE PANELS REQUIRES A PERMANENT CONCRETE SLAB

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

	5							., .					
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 4 OF 4 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC SERVICE AND METERING EQUIPMENT ALPHABETICAL SUBJECT INDEX

SG502.4

SCOPE: THIS STANDARD PROVIDES GENERAL INFORMATION ON ELECTRIC SERVICE AND METERING EQUIPMENT.

DEFINITIONS:

• **READILY ACCESSIBLE:** CAPABLE OF BEING REACHED QUICKLY AND CONVENIENTLY 24-HOURS A DAY FOR CONSTRUCTION, OPERATION, MAINTENANCE, INSPECTION, TESTING, OR METER READING WITHOUT REQUIRING THOSE SEEKING ACCESS TO CLIMB OVER OR REMOVE OBSTACLES; OR TO OBTAIN SPECIAL PERMISSION OR SECURITY CLEARANCES. TRUCK ACCESS MAY BE REQUIRED.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. ELECTRIC METER AND SERVICE LOCATION REQUEST:

CONTACT THE SERVICE PLANNER AT THE REGIONAL DESIGN AND PROJECT MANAGEMENT OFFICE CLOSEST TO THE JOB LOCATION FOR AN "ELECTRIC METER & SERVICE LOCATION" FORM BEFORE STARTING CONSTRUCTION. YOU MAY ALSO REQUEST VIA THE INTERNET AT: https://www.sdge.com/apply-service(a)

II. METERED AND UNMETERED CONDUCTORS:

LINE SIDE (UNMETERED) AND LOAD SIDE (METERED) CONDUCTORS ARE PROHIBITED FROM OCCUPYING THE SAME RACEWAY OR ENCLOSURE BY BOTH SDG&E (UTILITY) POLICY AND THE CALIFORNIA ELECTRICAL CODE. EXCEPTION: METER SOCKETS AND SAFETY SOCKET CANS.

III. METER SOCKET SEALING RINGS:

METER SOCKETS SHALL BE EQUIPPED WITH APPROVED SEALING RINGS AS A PART OF THE METER SOCKET INSTALLATION AND SHALL BE PROVIDED BY THE MANUFACTURER. RINGLESS METER SOCKETS ARE NOT ACCEPTABLE.

IV. SEALING OF METERS AND METERING EQUIPMENT:

ALL METERS AND ENCLOSURES FOR METERS, METERING EQUIPMENT, AND SERVICE ENTRANCE EQUIPMENT ON THE LINE SIDE OF THE METER, EXCEPT AS APPROVED FOR ACCESS TO REPLACE FUSES USED FOR OVER-CURRENT PROTECTION, WILL BE SEALED BY THE UTILITY. THE UTILITY SEAL SHALL NOT BE BROKEN EXCEPT BY AN AUTHORIZED REPRESENTATIVE OF THE UTILITY, OR WITH THE UTILITY'S PERMISSION GRANTED IN RESPONSE TO A REQUEST WARRANTING APPROVAL. NO PERSON IS PERMITTED TO TAMPER, OR IN ANY WAY INTERFERE, WITH A METER OR ITS CONNECTIONS AS PLACED BY THE UTILITY. ALL REMOVABLE ACCESS COVERS FOR COMPARTMENTS CONTAINING UNMETERED CONDUCTORS SHALL BE SEALABLE. WHEN A RACEWAY, CONDUIT OR CONDULET IS NECESSARY FOR UNMETERED CONDUCTORS, IT SHALL BE SEALABLE. NO REMOVABLE PANEL OR COVER REQUIRING SEALING SHALL BE LOCATED BEHIND OTHER PANELS, COVERS OR DOORS (EXCEPT NEMA 3R OUTDOOR RAINTIGHT ENCLOSURE DOORS). ALL 400A, AND ABOVE, SERVICE SWITCHES OR BREAKERS SHALL HAVE PROVISIONS FOR LOCKING IN THE OPEN/OFF POSITIONS.

V. SEALING REQUIREMENTS:

SEALING LATCHES, STUD AND WING-NUTS, OR SEALING SCREWS SHALL BE PROVIDED AS THE MEANS OF SEALING REMOVABLE OR HINGED ACCESS COVERS. STUDS AND WING-NUT ASSEMBLIES SHALL CONSIST OF A 1/4-INCH X 20 (MINIMUM) STUD AND AN ASSOCIATED WING-NUT, EACH DRILLED 1/16-INCH (MINIMUM) FOR SEALING PURPOSES. SEALING SCREWS SHALL BE DRILLED 1/16-INCH (MINIMUM) FOR SEALING PURPOSES. LATCHING DEVICES SHALL BE DESIGNED TO PERMIT POSITIVE LOCKING AND BE MADE OF A DURABLE CORROSION RESISTANT MATERIAL.

VI. SERVICE ENTRANCE LIMITATIONS:

SINGLE-PHASE SERVICE IS NORMALLY LIMITED TO 400A MAXIMUM. INDIVIDUAL THREE-PHASE SWITCHBOARDS ARE LIMITED TO 4,000A MAXIMUM. (b)

REFERENCE:

- (a) SEE SG<mark>021</mark>.
- (b) FOR FURTHER INFORMATION, SEE SWITCHBOARD SERVICE SECTION ON SG517.

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights ı	reserved. Rei	noval	of this copyright n	otice	e without permission	is not	permit	ted und	der law.	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	С	HAN	NGE	DR	BY	DSN	APV	DATE
С									F								
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL C	CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D								
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised	New Page		Information Re	moved				
	SHEET				SDC	3&E E	LECTI	RIC SERVIC	E ST	ANDARDS & GI	JIDI	ES					

SHEET 1 OF 1

GENERAL INFORMATION

SG503.1




FIGURE 1
WORKING SPACE – ELECTRIC SERVICE AND METERING EQUIPMENT, 0–600V (VIII)(IX)(XI)(m)

INSTALLATION:

GENERAL INFORMATION:

- (A) ON NEW INSTALLATIONS, IT IS NECESSARY THAT THE LOCATION FOR THE METER AND ITS RELATED SERVICE DISCONNECT BE APPROVED IN WRITING BY AN SDG&E (UTILITY) PROJECT PLANNER. THIS CAN BE ACCOMPLISHED BY THE CUSTOMER OR CONTRACTOR CALLING THE UTILITY'S NEAREST REGIONAL DESIGN AND PROJECT MANAGEMENT OFFICE AND REQUESTING AN ELECTRIC METER & SERVICE LOCATION FORM, OR VIA THE INTERNET AT: https://www.sdge.com/apply-service (a)
- B THE LOCATION FOR THE METER AND SERVICE DISCONNECT SHALL COMPLY WITH APPLICABLE CODES, LAWS AND ORDINANCES OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ), AND WITH THE REQUIREMENTS OF THE UTILITY'S SERVICE STANDARDS & GUIDE.
- © METER HEIGHTS:

1 OF 6

- 1. WHEN METERS ARE LOCATED IN A METER ROOM OR WHEN FULLY ENCLOSED IN A CABINET, THE MINIMUM HEIGHT OF THE METER SOCKET MAY BE 3 FEET, AND THE MAXIMUM HEIGHT SHALL NOT EXCEED 6'-3". THESE HEIGHTS ARE MEASURED FROM THE STANDING SURFACE TO THE CENTERLINE OF THE METER SOCKET, CABINETS SHALL NOT IMPAIR WORKING SPACE.
- 2. WHEN METERS ARE WALL OR SURFACE-MOUNTED, BUT NOT LOCATED IN A METER ROOM OR CABINET, THE MINIMUM HEIGHT OF THE METER SOCKET SHALL BE 4 FEET AND MAXIMUM HEIGHT SHALL NOT EXCEED 6'-3". THESE HEIGHTS ARE MEASURED FROM THE STANDING SURFACE TO THE CENTERLINE OF THE METER SOCKET. EXCEPTION: FOR MULTI-METER PANELS LOCATED ON AN EXTERIOR WALL, THE MINIMUM METER HEIGHT MAY BE REDUCED TO 36 INCHES. (b)

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights	eserved. Rer	noval o	of th	is copyright no	tice	e without permission	is not	permit	ted un	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CH	ΙAΝ	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	GES	-	LSM	BRB	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Cor	npletely Revi	sed		New Page		Information Re	moved	i			
	SHEET				SDC	G&E E	LECTI	RIC SERVIC	E STA	NE	ARDS & GU	IDI	ES					
	3HEE1			_		TDI	- NAE	TED AND	`	Δ,	/ICE OC	۸ -	TON			S	G50	4.1

ELECTRIC METER AND SERVICE LOCATION

COMMERCIAL AND RESIDENTIAL PREMISES

- (D) METER MARKING:
 - 1. EACH METER SOCKET AND ITS RELATED SERVICE DISCONNECT SHALL BE CLEARLY AND PERMANENTLY MARKED WITH MINIMUM 1/2-INCH NUMBER/LETTERS BY THE CONTRACTOR OR CUSTOMER TO INDICATE THE OCCUPANCY OR LOAD SERVED. MARKING WITH FELT PEN, PIGMENTED INK, OR FINGERNAIL POLISH IS NOT ACCEPTABLE.
 - 2. EXAMPLES OF PERMANENT MARKING ARE:

AN IDENTIFICATION PLATE SECURELY FASTENED BY A MEANS ACCEPTABLE TO THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).

COMMERCIALLY AVAILABLE DECALS

- 3. IDENTIFICATION MEANS A STREET, APARTMENT, OR SUITE NUMBER.
- 4. EXCEPTIONS: IN A MULTI-METERING SECTION WHERE THE SERVICE DISCONNECT IS LOCATED IMMEDIATELY ADJACENT TO THE METER SOCKET (TO THE SIDE), IT IS ACCEPTABLE TO MARK ONLY THE SERVICE DISCONNECT. AT THE OPTION OF THE UTILITY, MARKING MAY BE OMITTED OR DONE IN OTHER MANNERS FOR A SINGLE-FAMILY RESIDENCE.
- WHENEVER ANY ADDITION, ALTERATION OR RENEWAL IS CONTEMPLATED IN EXISTING SERVICE LATERAL CONDUITS, SERVICE ENTRANCE CONDUCTORS OR METERING EQUIPMENT, THE CUSTOMER OR CONTRACTOR SHALL CONTACT THE AREA PLANNER FOR AN APPROVED ELECTRIC METER & SERVICE LOCATION FORM. THIS IS IMPERATIVE TO PROVIDE ADVICE REGARDING CORRECTION OF ANY EXISTING UNACCEPTABLE CONDITIONS.
- F. EXISTING ELECTRICAL SERVICE AND METERING EQUIPMENT LOCATED ABOVE AN EXISTING GAS METER SET ASSEMBLY (MSA) IS CONSIDERED NON-COMPLIANT WITH CURRENT STANDARDS BUT MAY REMAIN AS IS. HOWEVER, ANY UPGRADES AND/OR REWIRES OF THE ELECTRICAL SERVICE AND METERING EQUIPMENT WILL REQUIRE THE RELOCATION OF EITHER THE ELECTRIC OR GAS SERVICE.
- (G) ADDITIONAL METERS MAY BE GROUPED WITH THOSE ALREADY IN SERVICE PROVIDED THE EXISTING SERVICE AND METER LOCATION IS ACCEPTABLE TO THE UTILITY. THE ADDED SERVICE EQUIPMENT MUST BE LOCATED AND INSTALLED IN CONFORMANCE WITH APPLICABLE CODES, LAWS AND ORDINANCES ENFORCED BY THE AHJ, AND WITH THE REQUIREMENTS OF THE UTILITY.
- H. ALL METERS SERVING MULTIPLE BUILDINGS OR OTHER REMOTE LOADS MUST BE GROUPED ON OR AT THE BUILDING OR STRUCTURE WHERE THE UTILITY'S SERVICE CONNECTION IS MADE. (c)
- J. METER LOCATIONS AND SERVICE CONNECTIONS ON EXTERIOR WALLS OF BEDROOMS OR NORMALLY OCCUPIED SPACES SHOULD BE AVOIDED WHENEVER POSSIBLE.
- K THE MINIMUM INGRESS AND EGRESS TO SERVICE EQUIPMENT AND METER LOCATIONS IS 24 INCHES IN WIDTH. THIS REQUIREMENT ALLOWS A SAFE ACCESS AND EXIT ROUTE FOR INSTALLATION, TESTING AND MAINTENANCE OF THE SERVICE AND METERING EQUIPMENT.

METER LOCATIONS - RESIDENTIAL:

- (L) for single and multi-family residential buildings, meters and metering equipment may be installed:
 - 1. OUTDOORS AND MOUNTED ON, OR RECESSED IN, AN EXTERIOR BUILDING WALL. $(A \setminus B) (C) (D \setminus E) (G) (b) (d)$
 - 2. IN A ROOM WITHIN A BUILDING, APPROVED BY THE UTILITY FOR THE LOCATION OF ELECTRIC METERS, WITH PROVISION FOR PROPER ILLUMINATION, AND WITH ACCESS ONLY BY A DOOR OPENING TO THE OUTSIDE OF THE BUILDING. (e)
- M. FOR MULTI-FAMILY RESIDENTIAL BUILDINGS LESS THAN THREE FLOORS, METERS AND METERING EQUIPMENT ARE TO BE GROUPED IN ONE CENTRAL LOCATION THAT IS READILY ACCESSIBLE TO THE UTILITY 24-HOURS A DAY IN ACCORDANCE WITH INSTALLATION NOTE L. (L) (f)

REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	CHANGI	E	DR	BY	DSN	APV	DATE
С									F							
В	FORMATTING/EDITO	DITORIAL CHANGES EDM IWA JTM KRG 02/07/2025 E														
Α	EDITORIAL C	CHAN	IGES	-	LSM	BRB	TPM	11/01/2017	D							
		X Indicates Latest Revision Completely Revised New Page X Information Removed														
	SHEET				SDO	S&E E	LECTI	RIC SERVIC	CE STA	NDARDS & GUIDES						
	· · · ·													S	G50	4.2
	2 OF 6									RVICE LOCATION				Ū		
				\mathbf{C}	OMN	1ER(CIAL	AND RE	SIDI	ENTIAL PREMIS	SES					

N. FOR ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS, CONSULT WITH THE UTILITY PROJECT PLANNER FOR APPROVAL OF METER AND METERING EQUIPMENT LOCATIONS IN THE EARLY PLANNING PHASES OF THE PROJECT TO AVOID REENGINEERING AND POSSIBLE DELAYS. (q)

METER LOCATIONS - COMMERCIAL AND INDUSTRIAL:

- O FOR SINGLE-OCCUPANCY BUILDINGS, METERS AND METERING EQUIPMENT MAY BE INSTALLED:
 - 1. OUTDOORS AND MOUNTED ON, OR RECESSED IN, AN EXTERIOR BUILDING WALL. (b)
 - 2. IN A ROOM WITHIN A BUILDING, APPROVED BY THE UTILITY FOR THE LOCATION OF ELECTRIC METERS, WITH PROVISION FOR PROPER ILLUMINATION, AND WITH ACCESS ONLY BY A DOOR OPENING TO THE OUTSIDE OF THE BUILDING. (e)
- P. FOR MULTI-OCCUPANCY BUILDINGS NOT EXCEEDING TWO FLOORS, METERS AND METERING EQUIPMENT ARE TO BE GROUPED IN ONE CENTRAL LOCATION THAT IS READILY ACCESSIBLE 24-HOURS A DAY TO UTILITY PERSONNEL IN ACCORDANCE WITH THE CONDITIONS PRESCRIBED BY INSTALLATION NOTE O. (0) f
- Q. FOR ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS, CONSULT WITH THE UTILITY'S PLANNER FOR APPROVAL OF METER AND METERING EQUIPMENT LOCATIONS IN THE EARLY PLANNING PHASES OF THE PROJECT TO AVOID RE-ENGINEERING AND POSSIBLE DELAYS. (g)
- R. FOR SERVICE STATIONS, THE UTILITY'S UNDERGROUND SERVICE LATERAL CONDUCTORS MAY NOT EXTEND THROUGH A HAZARDOUS (CLASSIFIED) CLASS 1 LOCATION AS DEFINED BY ARTICLE 514 OF THE CALIFORNIA ELECTRICAL CODE. THE UNDERGROUND SERVICE AND METERING EQUIPMENT SHALL BE LOCATED OUTSIDE, AND PRIOR TO, THE HAZARDOUS AREA AT A LOCATION APPROVED BY THE UTILITY'S PLANNER. (h)

UNACCEPTABLE METER LOCATIONS:

- S. FOR REASONS OF PUBLIC SAFETY, MAINTENANCE OF SERVICE, AND RELIABILITY OF METERING, IT IS NOT PERMISSIBLE TO INSTALL METERS AND METERING EQUIPMENT AS FOLLOWS:
 - 1. INSIDE ANY BUILDING, UNLESS LOCATED WITHIN AN ACCEPTABLE ELECTRIC METER ROOM. (e)
 - 2. IN COMMERCIAL OR RESIDENTIAL CARPORTS OR GARAGES, OR UNDER A PATIO COVER.
 - 3. IN A LOCATION NOT READILY ACCESSIBLE 24-HOURS A DAY FOR READING, MAINTENANCE, OR REPLACEMENT OF THE METERING EQUIPMENT BY THE UTILITY. (i)
 - 4. IN A SUBSTATION AREA OR IN A TRANSFORMER VAULT CONTAINING TRANSFORMER(S) OR MEDIUM-VOLTAGE EQUIPMENT.
 - 5. IN ANY LOCATION WHICH IS HAZARDOUS OR UNSUITABLE FOR ENTRY BY METER READERS OR SERVICE PERSONNEL, E.G., UNCONTROLLED OR UNRESTRAINED ANIMALS, ETC.
 - 6. ON ANY SURFACE SUBJECT TO EXCESSIVE VIBRATION.
 - 7. IN REST, BATH, SHOWER, POWDER, OR TOILET ROOM.
 - 8. IN AN ELEVATED AREA (SUCH AS BALCONY OR MEZZANINE) OR A DEPRESSED AREA (SUCH AS A BASEMENT, CELLAR OR UNDERGROUND ROOM) THAT DOES NOT HAVE ACCESS BY MEANS OF A STAIRWAY OF NORMAL RISE (4 TO 7 INCHES) AND RUN (11-INCH MINIMUM) CONFORMING TO BUILDING CODE REQUIREMENTS. SHIPBOARD LADDERS ARE UNACCEPTABLE FOR INGRESS AND EGRESS. MINIMUM HEADROOM OF 6'-6" MUST BE MAINTAINED IN ALL CASES.
 - 9. IN A PLACE WHERE EXCESSIVE MOISTURE, FUMES, DUST OR SIMILAR DETERIORATING AGENTS WILL INTERFERE WITH ITS OPERATION, UNLESS IT IS ENCLOSED IN A MANNER APPROVED BY THE UTILITY. FOR EXAMPLE, AT A CARWASH IN AN AREA EXPOSED TO EXCESSIVE MOISTURE AND DETERIORATING AGENTS, SERVICE AND METERING EQUIPMENT IS NOT ALLOWED.
 - 10. IN A ROOM WHICH DOES NOT MEET THE REQUIREMENTS OF AN ELECTRIC METER ROOM. (e)
 - 11. ON POLES OWNED BY THE UTILITY. (j)

	© 1998 - 2025 S	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights	reserved. Rer	moval	of th	is copyright no	tice	without permission	is not	permi	ted un	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	IAN	IGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDIT	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	BRB	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Cor	npletely Revi	ised		New Page		Information Re	moved	i			
	SHEET				SDC	3&E E	LECT	RIC SERVIC	E ST	AND	DARDS & GL	ID	ES					
				_												S	G50	4.3
	3 OF 6			E	LEC	TRIC	ME	TER ANI	D SE	:R\	/ICE LOC	ΑT	ION					

COMMERCIAL AND RESIDENTIAL PREMISES

UNACCEPTABLE METER LOCATIONS (CONT'D):

- 12. ON BUILDINGS OR OTHER STRUCTURES THAT ARE NOT DIRECTLY SERVED BY THE UTILITY'S SERVICE CONNECTION.
- 13. MEDIUM-VOLTAGE INSTALLATIONS THAT DO NOT HAVE VEHICLE ACCESS TO THE SERVICE AND METERING EQUIPMENT.
- 14. DIRECTLY OVER ANY STAIRWAY, RAMP, OR STEPS.
- 15. IN ANY AREA PROTECTED BY ALARM SYSTEMS, SECURITY GATES OR DOORS, GUARD DOGS, ETC., UNLESS APPROVED BY THE UTILITY. (i)
- 16. ON ANY PORTION OF A BUILDING WHERE FUTURE LANDSCAPING, FENCING OR OTHER BUILDING CONSTRUCTION WILL MAKE THE METER(S) INACCESSIBLE.

BILL OF MATERIALS: NONE

NOTES:

- (I) TO PERMIT ACCESS TO THE METERING INSTALLATION AND TO PROVIDE SAFE WORKING CONDITIONS FOR PERSONNEL, A WORKING AND STANDING SPACE ENTIRELY ON THE PROPERTY OF THE CUSTOMER IS TO BE PROVIDED IN FRONT OF ALL SERVICE AND METERING EQUIPMENT. (k)
- (II) A MINIMUM OF 3 FEET CLEAR AND LEVEL WORK SPACE IS REQUIRED FOR UNDERGROUND PULL SECTIONS, CURRENT TRANSFORMER METERING SECTIONS, AND METERING EQUIPMENT. PULL CANS/SECTIONS REQUIRING 5-INCH CONDUITS MUST ALLOW A MINIMUM OF 6 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE PULL CAN/SECTION. VERIFY LOCATION OF PULL SECTIONS WITH THE SDG&E PLANNER PRIOR TO INSTALLATION. THE WORKING SPACE IS TO BE KEPT CLEAR AND UNOBSTRUCTED.
- (III) THE WIDTH AND DEPTH OF THE WORKING SPACE MUST ALLOW READY ACCESS TO COMPLETE THE SERVICE AND METERING INSTALLATION, AND IN NO CASE BE LESS THAN 3 FEET. (K)
- (IV) METER HEIGHT WILL BE MEASURED FROM THE STANDING SURFACE OF THE WORKING SPACE TO THE CENTERLINE OF THE METER SOCKET. THE HEIGHT CLEARANCES FOR THE WORKING SPACE MUST BE NO LESS THAN 6'-6" AS MEASURED FROM THE CLEAR AND LEVEL WORKING SURFACE TO ANY OVERHEAD OBSTRUCTION. (C)
- (V) EQUIPMENT ASSOCIATED WITH THE ELECTRICAL EQUIPMENT AND INSTALLED BELOW THE METER PANEL(S) MAY EXTEND INTO THE WORKING SPACE UP TO 6 INCHES.
- (VI) WHEN NON-RAINTIGHT SERVICE EQUIPMENT IS INSTALLED WITHIN A BUILDING ON AN ELEVATED PORTION OF THE FLOOR, OR "HOUSEKEEPING PAD", THE PAD MUST BE FLUSH WITH THE SERVICE EQUIPMENT.
 - a. IF A SWITCHBOARD IS INSTALLED ON A HOUSEKEEPING PAD OR SLAB GREATER THAN 2 1/2 INCHES THICK, A METER HEIGHT PROBLEM COULD RESULT. THE 6'-3" MAXIMUM ALLOWABLE METER HEIGHT APPLIES TO ALL INSTALLATIONS.
- WHEN OUTDOOR RAINTIGHT SERVICE EQUIPMENT IS INSTALLED ON A HOUSEKEEPING PAD, THE HOUSEKEEPING PAD MUST BE LEVEL AND EXTEND A MINIMUM OF 3 FEET MEASURED FROM THE FACE OF THE METER PANEL, OR 6 FEET WHEN 5-INCH CONDUIT IS REQUIRED. IF THE ENCLOSURE DOORS ARE WIDER THAN 3 FEET, THE HOUSEKEEPING PAD SHALL EXTEND 1-INCH BEYOND THE OUTER EDGE OF THE EQUIPMENT DOORS WHEN OPENED AT 90 DEGREES.
- (VIII) FOR 480V SERVICE, CONSULT WITH THE AHJ FOR THEIR REQUIREMENTS.
- (IX) TO MAINTAIN A SAFE, CLEAR, AND LEVEL WORKING AREA IN FRONT OF NEW OR EXISTING NON-RESIDENTIAL METER AND SERVICE EQUIPMENT, A CONCRETE SLAB ACCEPTABLE TO THE UTILITY INSPECTOR IS REQUIRED. THIS ALSO APPLIES TO RESIDENTIAL LIVING UNITS EXCEEDING TWO IN NUMBER ON THE SAME PREMISES, WHICH ARE CLASSIFIED AS A COMMERCIAL ENTERPRISE AND PREMISES.

REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	HAN	IGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL C	CHAN	IGES	LSM	BRB	TPM	11/01/2017	D										
		X	Indicates Latest Revision Completely Revised New Page Information Removed															
	SHEET				SDC	S&E E	LECTI	RIC SERVIC	E STA	ND	ARDS & GL	JIDI	ES					
	· · · ·															S	G50	4.4
	4 OF 6		ELECTRIC METER AND SERVICE LOCATION													Ŭ	-50	•••
COMMERCIAL AND RESIDENTIAL PREMISES																		

NOTES (CONT'D):

- (XI) IN ADDITION, THE CONCRETE SLAB IS TO EXTEND A MINIMUM OF 6 FEET CLEAR AND LEVEL FOR WORKING SPACE IN FRONT OF SERVICE CABLE TERMINATING PULL SECTIONS WHEN 5-INCH SERVICE CONDUIT IS REQUIRED. FOR DRAINAGE PURPOSES, THE SLOPE OF THE WORKING SPACE IS NOT TO EXCEED 1/4-INCH PER FOOT SLOPING AWAY FROM THE EQUIPMENT.
- (XII) 3 FEET MINIMUM WIDTH OR LENGTH OF SERVICE EQUIPMENT, WHICHEVER IS GREATER
- (XIII) REQUIRED CLEAR AND LEVEL WORKING SPACE

REFERENCE:

- (a) SEE SG021.
- (b) SEE SG507.
- c SEE SG008.
- (d) SEE SG508.
- (e) FOR ADDITIONAL ELECTRIC METER ROOM AND LOCKING REQUIREMENTS, SEE SG506.
- (f) FOR ELECTRIC SERVICE POLICIES, SEE SG011 AND SG012.
- (g) SEE SG510: ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS.
- (h) SEE SG316 AND SG318.
- (i) FOR DEFINITION OF "READILY ACCESSIBLE", SEE SG503.
- (j) FOR CUSTOMER-OWNED METER POLE REQUIREMENTS, SEE SG203, SG204, AND SG205.
- (k) FOR BARRIER REQUIREMENTS, SEE SG505.
- (|) FOR OUTDOOR RAINTIGHT ENCLOSURE (NEMA 3R) REQUIREMENTS, SEE SG517.
- (m) FOR MEDIUM-VOLTAGE SWITCHGEAR, SEE SG SECTION 600.

© 1998 - 2025 San Diego Gas & Electric Company	. All	-!	

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						


SHEET 5 OF 6

Revision Completely Revised New Page Information Removed
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC METER AND SERVICE LOCATION COMMERCIAL AND RESIDENTIAL PREMISES

SG504.5

SCOPE: THIS IS A CAUTIONARY NOTE FOR THOSE INSTALLING HOUSEKEEPING PADS UNDER FREE STANDING METERING EQUIPMENT WITHIN A METER ROOM.



6'-3" 6'-0 1/2" MAX.

MAX.

2 1/2" MAX. A

WORKING SPACE

B

FIGURE 1
FRONT VIEW
SEE TABLE 1

FIGURE 1 SIDE VIEW

TABLE 1

ı	DESCRIPTION LIST							
ITEM DESCRIPTION								
1	PAD, HOUSEKEEPING							

INSTALLATION:

- A PLACING FREE-STANDING METER PANELS DIRECTLY ON THE FLOOR IS PREFERRED, BUT IF A HOUSEKEEPING PAD IS REQUIRED IT WILL RAISE THE METER HEIGHTS. GENERALLY, EQUIPMENT MANUFACTURERS MAY ALLOW 2 ½ INCHES FOR THIS. HOUSEKEEPING PADS INSTALLED HIGHER THAN 2 ½ INCHES MAY RAISE THE CENTERLINE OF THE METER ON THE PANEL ABOVE THE STANDARD 6 FEET 3 INCHES MAXIMUM. IT IS CUSTOMER RESPONSIBILITY TO ENSURE THE HEIGHT TO CENTERLINE OF METER DOES NOT EXCEED 6 FEET 3 INCHES MEASURED FROM STANDING SURFACE OF THE WORKING SPACE. (C)
- (B) THE FRONT OF THE HOUSEKEEPING PAD SHALL BE FLUSH WITH THE FACE OF THE PANEL. DO NOT EXTEND PAD OUT INTO THE ROOM BEYOND FACE OF PANEL POSING A TRIPPING HAZARD. (C)
- (C) THIS REQUIREMENT IS A CONDITION OF RECEIVING SERVICE AND THE CUSTOMER IS RESPONSIBLE FOR MAKING CORRECTIONS IF THE REQUIREMENT IS NOT MET.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

- a. FOR WORKING SPACE REQUIREMENTS, SEE SHEET 1.
- b. FOR OUTDOOR NEMA 3R RAINTIGHT SWITCHBOARDS, SEE SG517.

Indicates Latest Revision

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
A	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

New Page

Information Removed

SHEET 6 OF 6

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Completely Revised

SG504.6

ELECTRIC METER ROOM HOUSEKEEPING PADS AND METER HEIGHT SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR BARRIERS FOR ELECTRIC SERVICE AND METERING EQUIPMENT.




FIGURE 1

FIGURE 2
NON-REMOVABLE BARRIER POST DETAIL

ATTENTION:

* METERS LOCATED ON A WALL ADJACENT TO ANY PARKING AREA OR AREA ACCESSIBLE TO VEHICULAR TRAFFIC MUST BE PROTECTED BY NON-REMOVABLE BARRIERS. WHEEL STOPS AND REMOVABLE BARRIERS ARE NOT ACCEPTABLE SUBSTITUTES. MAINTAIN A MINIMUM OF 3 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE CABINETS OR ENCLOSURES. BARRIERS MUST BE SO POSITIONED TO ALLOW THE DOORS TO BE OPENED 90 DEGREES.

INSTALLATION:

- (A) USE 4-INCH STEEL PIPE, BLACK OR GALVANIZED STEEL, WITH A MINIMUM WALL THICKNESS OF 3/16-INCH.
- (B) THE CONCRETE ENCASEMENT SHALL BE A MINIMUM OF 6 INCHES THICK IN STABLE SOIL AND 12 INCHES THICK IN SANDY OR UNSTABLE SOIL.
- (C) BARRIERS MUST BE INSTALLED IN LINE WITH EACH END OF SERVICE EQUIPMENT TO PREVENT VEHICLE CONTACT. DISTANCE BETWEEN BARRIERS MAY NOT EXCEED 4 FEET.
- (D) BARRIERS ARE NOT ALLOWED IN THE REQUIRED WORKING SPACE. (a)
- E. BEFORE INSTALLING BARRIERS, CALL DIGALERT AT 811 AND/OR VISIT HTTP://WWW.DIGALERT.ORG/ FOR MARKOUT SERVICE AT LEAST TWO WORKING DAYS PRIOR TO EXCAVATING.

BILL OF MATERIALS: NONE

NOTES:

I. THE CUSTOMER WILL PROVIDE AND INSTALL "NON-REMOVABLE" BARRIERS TO PROVIDE THE CLEARANCES WHERE WORKING SPACE IS EXPOSED TO VEHICLE OR HAZARDOUS CONDITIONS. SERVICE AND METERING EQUIPMENT LOCATED ON PUBLIC OR PRIVATE PROPERTY MUST BE INSTALLED A MINIMUM OF 5 FEET BACK FROM FACE OF CURB OR IS CONSIDERED SUBJECT TO VEHICULAR CONTACT AND REQUIRES BARRIERS. AN SDG&E INSPECTOR WILL DETERMINE IF A BARRIER CAN BE OMITTED WHEN EXISTING STRUCTURES CAN PROTECT PERSONNEL AND EQUIPMENT. METERS WILL NOT BE SET UNTIL THE BARRIERS ARE INSTALLED.

 $@ 1998 - 2025 \ San \ Diego \ Gas \ \& \ Electric \ Company. \ All \ rights \ reserved. \ Removal \ of this \ copyright \ notice \ without \ permission \ is \ not \ permitted \ under \ law.$

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

BARRIERS FOR **ELECTRIC** SERVICE AND METERING EQUIPMENT

SG505.1

<u>NO</u>	TES (CONT'D):												
II.		ACHMENT INTO THE						MENT AND PERSONNEL FROM V E: LOADING ZONES, DRIVEWAY					
RE	FERENCE:												
REI		PACE CLEARANCES, S	SEE SG	5504.									
REV	© 1998 - 2025 Sa			ny. All		eserved. Rer	moval REV	of this copyright notice without permiss CHANGE	on is not	permit BY	ted und		DATE
C	CHAN	SE DK	В.	DSIN	AFV	DAIL	F	CHARGE	- DR	, , , , , , , , , , , , , , , , , , ,	DSIN	AFV	DAIL
В	FORMAT	TING EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL (CHANGES -	LSM	IPJ	TPM	11/01/2017	D						-
		X Indicates Latest R				npletely Revi		New Page Information	Removed	i			
	SHEET		SDG	&E E	LECTE	RIC SERVIC	E ST	ANDARDS & GUIDES		_	_	C Γ Δ	F 2
	2 OF 2	BARRIERS F	OR <mark>E</mark>	ELEC	CTRI	<mark>C</mark> SERVI	CE /	AND METERING EQUIPM	ENT		5	G50	J.∠

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR ELECTRIC METER ROOMS.

DEFINITIONS:

- **ELECTRIC METER ROOM:** AN ELECTRIC METER ROOM IS A WEATHERPROOF, ILLUMINATED ROOM PROVIDED BY THE CUSTOMER AT THEIR OPTION AND APPROVED BY SDG&E (UTILITY) FOR THE LOCATION OF THE ELECTRIC SERVICE AND/OR METERING EQUIPMENT. CHAIN LINK FENCE IS NOT ACCEPTABLE AS A SEPARATING WALL. ALL REQUIREMENTS OF THIS STANDARD SHALL APPLY.
- READILY ACCESSIBLE: CAPABLE OF BEING REACHED QUICKLY AND CONVENIENTLY 24 HOURS A DAY FOR CONSTRUCTION,
 OPERATION, MAINTENANCE, INSPECTION, TESTING OR READING, WITHOUT REQUIRING THOSE SEEKING ACCESS TO CLIMB OVER
 OR REMOVE OBSTACLES; OR TO OBTAIN SPECIAL PERMISSION OR SECURITY CLEARANCES. A STAIRWAY OF NORMAL RISE (4 TO
 7 INCHES) AND RUN (11-INCH MINIMUM) CONFORMING TO BUILDING CODE REQUIREMENTS IS ACCEPTABLE. SHIPBOARD
 LADDERS ARE UNACCEPTABLE.
- STRUCTURAL CEILING: DROP, SUSPENDED AND SIMILAR CEILINGS NOT INTENDED TO ADD STRENGTH TO THE BUILDING STRUCTURE ARE NOT STRUCTURAL CEILINGS.

ELECTRIC METER ROOM

THIS ROOM IS FOR ELECTRICAL AND METERING EQUIPMENT ONLY

STORAGE OF MATERIALS INSIDE IS PROHIBITED

SEE SDG&E TERMS & CONDITION OF SERVICE - STANDARD SG506


REFERENCE:

- STATE FIRE CODE: §8509.1
- CAL OSHA CODE: §2340.16. WORK SPACE ABOUT ELECTRIC EQUIPMENT


FOR ROUTINE WORK, CONTACT THE PROPERTY MANAGER FOR ACCESS.

IN CASE OF EMERGENCY, CONTACT SDG&E AT 1-800-411-7343.

FIGURE 1 EXAMPLE OF IDENTIFICATION PLAQUE (N)



Indicates Latest Revision



Information Removed

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	YZZ	JTM	JTM	KRG	04/23/2025	F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						·


SHEET 1 OF 5 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

ELECTRIC METER ROOM

Completely Revised

SG506.1



INSTALLATION:

A. ACCESS:

ACCESS MUST BE THROUGH A DOOR ON THE BUILDING EXTERIOR TO PROVIDE IMMEDIATE 24 HOUR-A-DAY ACCESS. THE DOOR SHALL OPEN OUT OF THE ELECTRIC METER ROOM IN THE DIRECTION OF EGRESS. IF THE DOOR IS TO BE LOCKED, THE LOCK MUST BE KEYED TO SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY. A LOCKBOX FOR CUSTOMER KEYS IS NOT ACCEPTABLE. IF A SECOND DOOR OR OPENING IN THE ELECTRIC METER ROOM PERMITS ACCESS TO THE BUILDING INTERIOR, THE BUILDING OWNER, AND OTHER PARTIES AS DETERMINED BY THE UTILITY, WILL BE REQUIRED TO SIGN A METER ACCESS EASEMENT WHICH WILL RELEASE THE UTILITY FROM ANY LOSS OR INJURY ARISING FROM THE ACCESS. THIS DOOR SHALL SWING OUT OF THE METER ROOM IN THE DIRECTION OF EGRESS.

(B) COMMUNICATION EQUIPMENT:

TELEPHONE, CATV, DATA PROCESSING EQUIPMENT AND OTHER TYPES OF COMMUNICATION EQUIPMENT ARE NOT PERMITTED IN AN ELECTRIC METER ROOM. A SINGLE CONDUIT CONTAINING COMMUNICATION WIRING OR CABLES MAY BE INSTALLED IN A STRAIGHT, CONTINUOUS SECTION, RUNNING VERTICALLY THROUGH AN ELECTRIC METER ROOM PROVIDED THE CONDUIT IS NOT LOCATED IN THE DEDICATED ELECTRICAL SPACE AND IT DOES NOT ENCROACH INTO THE WORKING SPACE. CONDUIT SHOULD NOT BE RUN HORIZONTALLY THROUGH AN ELECTRIC METER ROOM BECAUSE IT MAY ENCUMBER SPACE NEEDED FOR FUTURE EXPANSION OF THE CUSTOMER'S ELECTRICAL SYSTEM. ACCESS TO COMMUNICATION EQUIPMENT ROOMS OR SPACES THROUGH AN ELECTRIC METER ROOM IS NOT PERMITTED.

1. EXCEPTIONS:

COMMUNICATION EQUIPMENT IS ALLOWED IN A METER ROOM SERVING A SINGLE-FAMILY RESIDENCE.

COMMUNICATION CONDUIT, WIRING AND OTHER RELATED DEVICES FOR AUTOMATED METER READING ARE ALLOWED IN ELECTRIC METER ROOMS.

(C) DEDICATED ELECTRICAL SPACE:

THE SPACE EQUAL TO THE WIDTH AND DEPTH OF THE EQUIPMENT AND EXTENDING FROM THE FLOOR TO A HEIGHT OF 6 FEET ABOVE THE EQUIPMENT OR TO THE STRUCTURAL CEILING, WHICHEVER IS LOWER, SHALL BE DEDICATED TO THE ELECTRICAL INSTALLATION. NO PIPING DUCTS, LEAK PROTECTION APPARATUS, OR OTHER EQUIPMENT FOREIGN TO THE ELECTRICAL INSTALLATION SHALL BE LOCATED IN THIS ZONE.

EXCEPTION: SUSPENDED CEILINGS WITH REMOVABLE PANELS SHALL BE PERMITTED WITHIN THE 6-FOOT ZONE.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV **REV** DR BY DSN APV DATE CHANGE DATE CHANGE C **EDITORIAL CHANGES** JTM KRG 04/23/2025 F Y77 1TM В EDITORIAL CHANGES/FORMATTING EDM IWA JTM KRG 02/07/2025 Ε Α **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017

SHEET 2 OF 5 **Indicates Latest Revision** Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG506.2

ELECTRIC METER ROOM

D. DOORS:

THE ENTRANCE TO THE ELECTRIC METER ROOM SHALL BE THROUGH A VERTICAL DOORWAY NOT LESS THAN 3 FEET WIDE OR THE WIDTH OF THE PULL SECTION, WHICHEVER IS GREATER, AND 6'-6" HIGH. THE DOOR SHALL OPEN OUT IN THE DIRECTION OF EGRESS, AND SHALL UTILIZE LEVER-OPERATED HARDWARE. LEVER-OPERATED HARDWARE IS A TYPE THAT PERMITS THE DOOR TO BE OPENED FROM INSIDE THE ROOM WITHOUT THE USE OF HANDS. FOR ELECTRIC METER ROOMS CONTAINING SERVICES RATED 800A OR MORE, THE DOOR SHALL BE EQUIPPED WITH PANIC BARS, PRESSURE PLATES, OR OTHER DEVICES THAT ARE NORMALLY LATCHED BUT OPEN UNDER SIMPLE PRESSURE. WHEN THE PULL SECTION IS NOT DIRECTLY IN FRONT OF THE METER ROOM DOOR, A DOUBLE-DOOR ASSEMBLY IS REQUIRED. IF TWO DOORS ARE REQUIRED BY CODE FOR EMERGENCY EGRESS, BOTH DOORS MUST BE EQUIPPED WITH PANIC HARDWARE. THE SDG&E PROJECT PLANNER DETERMINES WHICH DOOR WILL BE USED FOR SERVICE CABLE PULLING OPERATIONS AND THAT DOOR SHALL BE A DOUBLE DOOR ASSEMBLY. ON DOUBLE-DOOR ASSEMBLIES, BOTH DOORS MUST BE EQUIPPED WITH PANIC HARDWARE. THE MAXIMUM ALLOWABLE DOORSILL HEIGHT IS 2 INCHES. SECURITY ALARM SYSTEMS MAY BE CONNECTED TO A METER ROOM ACCESS DOOR PROVIDED THE ALARM IS DEACTIVATED MONDAY THROUGH SATURDAY BETWEEN THE HOURS OF 7:00 A.M. AND 9:00 P.M., EXCLUDING HOLIDAYS. THIS WILL ENABLE UTILITY PERSONNEL TO ACCESS UTILITY-OWNED EQUIPMENT DURING OUR NORMAL BUSINESS HOURS WITHOUT ACTIVATING THE ALARM. SHOULD UTILITY EMPLOYEES, OR THEIR AGENTS, ACTIVATE THE ALARM WHILE PERFORMING THEIR DUTIES; THE UTILITY WILL NOT BE RESPONSIBLE FOR THE COST OF LAW ENFORCEMENT OR SECURITY COMPANY RESPONSE CALLS.

(E) FOREIGN SYSTEMS:

THE FOLLOWING EQUIPMENT IS NOT PERMITTED WITHIN THE ELECTRICAL METER ROOM. SUCH EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:

- 1. GAS EQUIPMENT, INCLUDING CUSTOMER GAS PIPING
- 2. WATER HEATERS, BOILERS, AND OTHER MECHANICAL EQUIPMENT
- 3. COMMUNICATIONS EQUIPMENT (B)
- 4. STORAGE OF ANY MATERIALS, LIQUIDS, PAINTS, ETC.
- 5. FIRE AND SECURITY ALARM SYSTEMS
- 6. WET FILLED BATTERIES AND BATTERY CHARGING EQUIPMENT. NOTE: BATTERIES THAT ARE PART OF A UPS SYSTEM THAT ARE A SEALED TYPE, NON-GASSING AND NON-VENTING, ARE ALLOWED IN AN ELECTRIC METER ROOM PROVIDED THEY DO NOT ENCROACH IN THE WORKING SPACE OR THE MINIMUM 24-INCH ACCESS AND EXIT ROUTE.
- IRRIGATION AND SPRINKLER CONTROLLERS
- 8. DIESEL AND COMBUSTIBLE FUEL TANKS
- 9. REFRIGERANT PIPELINES

EXCEPTION: LIGHTING CONTROLLERS ARE ALLOWED IN AN ELECTRIC METER ROOM WHEN THE BRANCH CIRCUIT OVER CURRENT DEVICE FOR THE LIGHTING IS LOCATED IN THE METER ROOM.

F. SPRINKLER PROTECTION:

SPRINKLER PROTECTION SHALL BE PERMITTED FOR THE DEDICATED SPACE WHERE THE PIPING IS INSTALLED IN COMPLIANCE WITH THE "DEDICATED ELECTRICAL SPACE" AND "FOREIGN SYSTEMS" REQUIREMENTS. ONLY SPRINKLER SUPPLY PIPING AND HEADS REQUIRED PER STATE AND LOCAL FIRE AND BUILDING CODES TO PROTECT THE ROOM ITSELF ARE ALLOWED. A "MAIN FIRE SPRINKLER" LINE IS NOT ALLOWED TO PASS THROUGH AN ELECTRIC METER ROOM UNLESS A SPRINKLER HEAD SERVING THE ROOM IS CONNECTED DIRECTLY TO THE MAIN LINE. PLACEMENT OF SPRINKLER HEADS AND SHIELDING REQUIREMENTS ARE THE RESPONSIBILITY OF THE FIRE MARSHALL OR BUILDING INSPECTOR, NOT THE UTILITY. (C) (E)

G. HEADROOM:

THE MINIMUM HEADROOM IN AN ELECTRIC METER ROOM SHALL BE 6'-6" HIGH. THE ACTUAL HEIGHT OF THE ROOM WILL BE DETERMINED BY THE CUSTOMER IN ORDER TO OBTAIN THE 8-INCH CLEARANCE REQUIRED FROM CENTERLINE OF THE HIGHEST METER SOCKET.

	© 1998 - 2025 Sa	an Diego Gas & El	ectric (Compa	ny. All	rights	reserved. Rer	moval o	f this copyright not	ce without permissio	n is not	permi	tted un	der law	
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CH	ANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL C	CHANGES	YZZ	JTM	JTM	KRG	04/23/2025	F							
В	EDITORIAL CHANGE	S/FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е							
Α	EDITORIAL C	CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							
		X Indicates Latest Revision Completely Revised New Page Information Removed										l			
	SHEET		SDG&E ELECTRIC SERVICE STANDARDS & GUIDES												
3 OF 5 ELECTRIC METER ROOM												S	G50	6.3	

H. IDENTIFICATION/MARKING REQUIREMENTS:

EACH METER SOCKET/BASE AND ITS RELATED METER SERVICE DISCONNECT SHALL BE CLEARLY AND PERMANENTLY MARKED BY THE CONTRACTOR OR CUSTOMER TO INDICATE THE OCCUPANCY OR LOAD SERVED, I.E. UNIT OR SUITE NUMBER, FIRE ALARM, HOUSE METER, ETC. EXAMPLES OF PERMANENT MARKING ARE AS FOLLOWS:

- 1. AN IDENTIFICATION PLATE SECURELY FASTENED BY A MEANS ACCEPTABLE TO THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) OR,
- 2. COMMERCIALLY AVAILABLE DECALS.

IDENTIFICATION MEANS A STREET, APARTMENT, OR SUITE NUMBER. FELT PEN, PIGMENTED INK OR FINGERNAIL POLISH IS NOT ACCEPTABLE. AT THE OPTION OF THE UTILITY, MARKING MAY BE OMITTED OR IDENTIFIED DIFFERENTLY FOR A SINGLE-FAMILY RESIDENCE. EXCEPTION: IN A MULTI-METERING SECTION WHERE THE METER SERVICE DISCONNECTS ARE LOCATED IMMEDIATELY ADJACENT TO THE METER SOCKETS (TO THE SIDE, ABOVE OR BELOW) IT IS ACCEPTABLE TO MARK ONLY THE SERVICE DISCONNECTS.

J. ILLUMINATION:

THE LIGHT MUST BE CONTROLLED BY AN ON-OFF WALL SWITCH. TIMERS OR MOTION DETECTORS ARE NOT ALLOWED TO CONTROL THE LIGHT. FOR THE SAFETY OF ELECTRICAL WORKERS, THE UTILITY RECOMMENDS 30 FOOT-CANDLES MEASURED AT THE FLOOR AS THE MINIMUM LIGHTING LEVEL IN AN ELECTRIC METER ROOM.

K. METER HEIGHTS:

THE MINIMUM HEIGHT OF THE METER SHALL BE 3 FEET AND THE MAXIMUM HEIGHT SHALL BE 6'-3" AS MEASURED FROM THE STANDING SURFACE TO THE CENTERLINE OF THE METER SOCKET.

L. ROOF ACCESS LADDER:

LADDERS USED FOR ROOF ACCESS ARE ALLOWED IN A METER ROOM PROVIDED THEY ARE LOCATED OUTSIDE THE REQUIRED WORKING SPACE AREA. THE UTILITY DOES NOT RECOMMEND ROOF ACCESS THROUGH AN OPENING IN AN ELECTRIC ROOM DUE TO ROOF HATCHES BEING INADVERTENTLY LEFT OPEN ALLOWING WATER ENTRY DURING RAIN STORMS.

M. PULL SECTIONS:

THE POSITION OF A PULL SECTION IN A METER ROOM IS SUBJECT TO APPROVAL BY THE UTILITY. (b)

1. PULL SECTIONS SHOULD BE POSITIONED:

OPPOSITE THE ACCESS DOOR TO ALLOW USE OF THE DOORWAY AS ADDITIONAL WORKING SPACE FOR CABLE PULLING EQUIPMENT; OR

ON A WALL PERPENDICULAR TO THE ACCESS DOOR.

NOTE: DO NOT LOCATE ON THE SAME WALL AS THE ACCESS DOOR.

- 2. PULL SECTIONS THAT REQUIRE 2-INCH, 3-INCH OR 4-INCH CONDUITS MUST ALLOW A MINIMUM OF 3 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE SECTION. (a)
- 3. PULL SECTIONS REQUIRING 5-INCH CONDUITS MUST ALLOW A MINIMUM OF 6 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE SECTION.
- 4. ADDITIONAL CLEARANCES MAY BE REQUIRED BY THE LOCAL AUTHORITY HAVING JURISDICTION (AHJ) FOR 480V SERVICES.

(N) **ROOM AND SUITE IDENTIFICATION:**

THE METER ROOM MUST BE PERMANENTLY IDENTIFIED ON THE EXTERIOR OF THE DOOR. DECALS ARE AVAILABLE FROM THE UTILITY BUT MUST BE INSTALLED BY CUSTOMER. WHEN A BUILDING HAS MORE THAN ONE METER ROOM, A PLAQUE IDENTIFYING THE ROOM AND THE SUITES SERVED FROM THE SERVICE IN THE ROOM MUST BE SECURED TO THE EXTERIOR OF THE DOOR. (c)

O. VEHICLE ACCESS:

PERMANENT VEHICLE ACCESS TO THE METER ROOM IS REQUIRED FOR THE INSTALLATION AND MAINTENANCE OF THE SERVICE LATERAL CONDUCTORS AND METERING EQUIPMENT. UNDER SOME CONDITIONS, AS DETERMINED BY THE UTILITY, THE VEHICLE ACCESS REQUIREMENT MAY BE WAIVED. (d)

REV DR DSN APV **REV** DR | BY | DSN | APV DATE CHANGE BY DATE CHANGE C **EDITORIAL CHANGES** JTM KRG 04/23/2025 F Y77 1TM EDITORIAL CHANGES/FORMATTING В EDM IWA JTM KRG 02/07/2025 Ε

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D

X Indicates Latest Revision | Completely Revised | New Page | Information Removed |

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG506.4

ELECTRIC METER ROOM

SHEET 4 OF 5

P. VENTILATION:

THE UTILITY DOES NOT HAVE A REQUIREMENT FOR VENTILATION OF ELECTRIC METER ROOMS. THE AHJ IS RESPONSIBLE FOR ENFORCEMENT OF VENTILATION IN ELECTRICAL METER ROOMS, WHEN REQUIRED, FOR COMPLIANCE WITH THE CALIFORNIA ELECTRIC CODE, BUILDING CODE OR MECHANICAL CODE.

BILL OF MATERIALS: NONE

NOTES:

- (I) 8-INCH MINIMUM CLEARANCE EXTENDS FOR ENTIRE WIDTH AND DEPTH OF THE 3-FOOT WORKING SPACE.
- (II) THE 3-FOOT MINIMUM METER HEIGHT SHOWN IS FOR METER ROOMS, CABINETS, OR EXTERIOR MULTI-METER INSTALLATIONS ONLY.
- (III) THE METER FROM ONE PANEL CANNOT BE IN THE WORKING SPACE OF ANOTHER METER IN A DIFFERENT PANEL.
- (IV) METER CLEARANCES:

ALL METER INSTALLATIONS MUST PROVIDE MINIMUM CLEARANCES AS SHOWN.

REFERENCE:

(a) FOR MEDIUM VOLTAGE PULL SECTION CLEARANCES, SEE SG608.

Indicates Latest Revision

- (b) for required conduit size, see SG309.
- (c) FOR PLAQUE REQUIREMENTS, SEE SG017.
- $(extsf{d}\,)$ SEE SG016: PULLING DEVICES FOR INSTALLATION OF SERVICE LATERAL CONDUCTORS IN PARKING STRUCTURES.

	© 1998 - 2025 San Diego Gas & Ele	ectric (Compa	ny. All	rights	reserved. Rer	noval	of this copyright notice without permission	is not	permit	ted un	der law	<i>1</i> .
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	YZZ	JTM	JTM	KRG	04/23/2025	F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

Completely Revised

SHEET 5 OF 5

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

Information Removed

New Page

ELECTRIC METER ROOM

SG506.5

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR SINGLE OR MULTIPLE METER INSTALLATIONS IN COMMERCIAL OR RESIDENTIAL APPLICATIONS.




FIGURE 1
SEMI-FLUSH EXTERIOR METER INSTALLATION
SEE TABLE 1

TABLE 1

	METER DESCRIPTION LIST
ITEM	DESCRIPTION
1	CLEAR AND LEVEL WORKING SPACE
2	ANY OBSTRUCTION ABOVE METER
3	PROPERTY LINE OR OBSTRUCTION
4	3 FEET MINIMUM OR LENGTH OF EQUIPMENT, WHICHEVER IS GREATER
(5)	SEMI-FLUSH METER INSTALLATION
6	METER SERVICE DISCONNECT
7	MIN. DISTANCE TO NEAREST SIDEWALL OR OTHER OBSTRUCTION

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

		DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
B FC	ORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SINGLE OR MULTIPLE METER INSTALLATIONS COMMERCIAL OR RESIDENTIAL APPLICATIONS

SG507.1




FIGURE 2
MULTIPLE METER INSTALLATION FOR EXTERIOR LOCATIONS COMMERCIAL OR RESIDENTIAL




FIGURE 3
RECESS SINGLE METER "RESIDENTIAL APPLICATION ONLY" (b) c
SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CH	IAI	IGE	DR	BY	DSN	APV	DATE
С							F								
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates La	atest R	evisio	n	Con	npletely Revi	ised	New Page		Information Re	moved				

SHEET 2 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SINGLE OR MULTIPLE METER INSTALLATIONS COMMERCIAL OR RESIDENTIAL APPLICATIONS

SG507.2

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- $\left(ext{ I }
 ight)$ THE 10-INCH AND 2'-2" DIMENSIONS MAY VARY DEPENDING ON SITE CONDITIONS AND EQUIPMENT CONFIGURATION, BUT IN NO CASE SHALL THE LEFT OR RIGHT SIDE CLEARANCE FROM CENTERLINE OF THE METER SOCKET TO AN OBSTRUCTION BE LESS THAN 10 INCHES, AND THE OVERALL WIDTH OF WORKING SPACE MUST BE 36 INCHES MINIMUM.
- (II) RESIDENTIAL EQUIPMENT SHOWN, HOWEVER, THIS STANDARD IS ALSO APPLICABLE TO COMMERCIAL EQUIPMENT (NOT SHOWN).
- (III) THIS STANDARD ALSO APPLIES TO WALL-MOUNTED AND FREE-STANDING SWITCHBOARDS (NOT SHOWN).

REFERENCE:

- (a) FOR HARDSCAPE WORKING SPACE REQUIREMENTS, SEE SG504.
- (b) FOR BARRIER REQUIREMENTS, SEE SG505.
- (c) FOR ADDITIONAL METER CABINET RECESS REQUIREMENTS, SEE SG508.
- (d) FOR 480V SERVICE AND MEDIUM-VOLTAGE SWITCHGEAR, SEE SG504.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SINGLE OR MULTIPLE METER INSTALLATIONS COMMERCIAL OR RESIDENTIAL APPLICATIONS SG507.3




TABLE 1

	METER CABINET DESCRIPTION LIST
ITEM	DESCRIPTION
1	PROPERTY LINE OR OBSTRUCTION
2	SERVICE DISCONNECT
3	EXTERIOR BUILDING WALL
4	METER
(5)	METER SOCKET
6	HINGED DOOR (OPEN)
7	FULL LENGTH DOOR
8	FINAL GRADE
9	ANY OBSTRUCTION ABOVE METER
(10)	CLEAR LEVEL STANDING AND WORKING SURFACE
(11)	WORKING SPACE

INSTALLATION:

- A. GENERAL INFORMATION:
 - 1. A METER CABINET RECESS IS ALLOWED FOR A SINGLE METER RESIDENTIAL APPLICATION ONLY AND IS LIMITED TO SINGLE-PHASE SERVICE.
 - 2. THE METER CABINET RECESS MUST HAVE SUFFICIENT DEPTH TO PROVIDE CLEARANCE FOR THE METER IN ADDITION TO THE DEPTH REQUIRED FOR THE METER PANEL. ALL CLEARANCES MUST BE MET TO ENSURE THE METER CAN BE INSTALLED SAFELY.
- (B) DEPTH OF RECESS:

A 7-INCH MINIMUM, AND 11-INCH MAXIMUM CLEARANCE IS REQUIRED FROM FACE OF METER PANEL TO INSIDE OF CABINET DOOR.

© WIDTH OF RECESS:

A 10-INCH MINIMUM CLEARANCE MEASURED FROM THE VERTICAL CENTERLINE OF THE METER SOCKET TO THE HINGED SIDE OF THE DOOR IS REQUIRED. A 20-INCH MINIMUM CLEARANCE MEASURED FROM THE VERTICAL CENTERLINE OF THE METER SOCKET TO THE SIDE OPPOSITE THE HINGED SIDE OF THE DOOR IS REQUIRED.

- D. DOOR REQUIREMENTS:
 - (1) THE DOOR MUST BE A MINIMUM OF 6'-6" HIGH, FULL LENGTH, SIDE-HINGED, AND DESIGNED TO SECURE IN THE OPEN POSITION AT 90 DEGREES OR MORE. SHOULD THE DOOR, WHEN OPENED TO 90 DEGREES OBSTRUCT THE EXIT ROUTE, IT MUST BE HINGED TO ALLOW THE DOOR TO OPEN BETWEEN 90 AND 180 DEGREES TO OBTAIN THE MINIMUM 24-INCH EXIT ROUTE. IT IS NOT PERMISSIBLE TO CUT AN OPENING IN THE DOOR THROUGH WHICH THE METER WILL PROTRUDE. THE METER COULD BE HIT CAUSING A PERSON TO BE INJURED OR DAMAGE TO THE METER. AN OPENING MAY BE CUT AND COVERED WITH A HINGED POLYCARBONATE VIEWING WINDOW FOR METER READING PURPOSES.
 - 2. FIGURES IN THIS STANDARD ARE FOR 125–225A SOCKET-BASED METER INSTALLATIONS. THIS STANDARD MAY ALSO BE APPLIED TO 400A (CLASS 320) RESIDENTIAL METER PANELS (NOT PICTURED), AND 600A CURRENT TRANSFORMER (CT) RATED COMMERCIAL METER PANELS USED FOR RESIDENTIAL APPLICATION (NOT PICTURED).
- (E) 3 FEET MINIMUM CLEAR AND LEVEL WORKING SPACE REQUIRED. FINAL GRADE OF WORKING SPACE AND THE INSIDE OF THE CABINET MUST BE THE SAME. NO STEPS IN OR OUT OF THE CABINET ARE PERMITTED.


	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE	
С								F							
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е							
Α	EDITORIAL (CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							
		X Indicates L	atest R	Revisio	n	Con	npletely Revi	ised	New Page X Information Rei	noved					
SHEFT SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															

SHEET 2 OF 3

METER CABINET RECESS FOR SINGLE METER RESIDENTIAL APPLICATION ONLY

SG508.2

BII	LL OF MATERIA	LS: NONE														
NO	TES:															
(I) IF THE INTERIOR OF THE METER PA	WIDTH OF TH	E CAE	BINET E GRAI	IS 36 DE DO	INCH DES N	IES, OR GR OT EXCEEI	EATE D A 1	ER, THE WORK /4-INCH DROF	(INC	G SPACE CAN BE	MEAS G AW	URED Y FR	FROI	M THE HE PA	FACE NEL.
RE	FERENCE:															
a.	FOR BARRIER RE	QUIREMENTS, S	SEE S	G505.												
REV	© 1998 - 2025 Sa		ectric (ny. All DSN	_	eserved. Rer	noval REV			e without permissio	n is not		tted und		DATE
C	CHAIN							F						2314		-0:5
В	FORMATTING/EDITO		EDM	IWA			02/07/2025									
A	EDITORIAL C	CHANGES X Indicates La	tost D	LSM	IPJ		11/01/2017	D	Now Page	1	Information	omovos				
	CUEET	A Indicates La	itest R				npletely Revi		New Page ANDARDS & G		Information R DES	emoved				
	SHEET		М						OR SINGL					S	G50	8.3
	3 OF 3		۱۲۱E	- I ER	RESI	DEN	TIAL AP	PLIC	CATION ON	L IV	TIL I EK					



ELECTRIC METER CABINET

THIS SPACE IS FOR ELECTRICAL AND METERING EQUIPMENT ONLY

STORAGE OF MATERIALS INSIDE IS PROHIBITED

SEE SDG&E TERMS & CONDITION OF SERVICE - STANDARD SG509

REFERENCE:

- STATE FIRE CODE: §8509.1
- CAL OSHA CODE: §2340.16. WORK SPACE ABOUT ELECTRIC EQUIPMENT

FOR ROUTINE WORK, CONTACT THE PROPERTY MANAGER FOR ACCESS.


IN CASE OF EMERGENCY, CONTACT SDG&E AT 1-800-411-7343.

FIGURE 3

EXAMPLE OF IDENTIFICATION PLAQUE (H)

TABLE 1

ELECTRIC METER CA	BINET DIMENSIONS
DEPTH OF OBSTRUCTION EXTENDING BEYOND FACE OF PANEL	DISTANCE FROM CENTERLINE OF SOCKET TO SIDE OBSTRUCTION
Z (IN)	Y MIN. (IN)
0 TO LESS THAN 2	4 1/4
2 TO LESS THAN 6	6 1/4
6 OR OVER	10



© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 4

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC METER CABINET – COMMERCIAL OR RESIDENTIAL MULTI-METER INSTALLATIONS

SG509.2

INSTALLATION:

A. GENERAL REQUIREMENTS:

A METER CABINET IS ALLOWED FOR A COMMERCIAL OR RESIDENTIAL MULTI-METERED INSTALLATION PROVIDED IT MEETS ALL OF THE FOLLOWING REQUIREMENTS.

1. NO OBSTRUCTIONS SUCH AS DOOR JAMS, VERTICAL POSTS, ETC. ARE PERMITTED WITHIN THE CABINET OPENING. COMMUNICATION EQUIPMENT IS ALLOWED IN THE SAME CABINET WITH ELECTRICAL BUT MAY NOT ENCROACH IN THE WORKING SPACE. NO OTHER EQUIPMENT FOREIGN TO THE ELECTRICAL OR COMMUNICATION SYSTEMS IS ALLOWED WITHIN THE CABINET.

B. DEPTH OF CABINET:

DEPTH OF CABINET SHALL BE 11 INCHES MINIMUM, 35 INCHES MAXIMUM, MEASURED FROM THE FACE OF METER PANEL TO INSIDE OF CABINET DOOR. THE CHANGE IN ELEVATION WITHIN THE REQUIRED WORKING SPACE SHALL NOT EXCEED 1/4-INCH PER FOOT SLOPING AWAY FROM THE METER PANEL, AND THE ILLUMINATION REQUIREMENTS SHALL BE MET. CABINETS WITH A DEPTH GREATER THAN 35 INCHES WILL BE CONSIDERED A METER ROOM AND ALL REQUIREMENTS FOR ELECTRIC METER ROOMS SHALL BE MET. (E)

C. WIDTH OF CABINET:

A 36-INCH WIDTH IS REQUIRED WITH 10 INCHES MINIMUM SIDE CLEARANCE MEASURED FROM THE VERTICAL CENTERLINE OF THE METER SOCKETS. IF ELECTRICAL EQUIPMENT IS EQUIPPED WITH HINGED DOORS, THE CABINET OPENING MUST ALLOW FOR EQUIPMENT DOORS TO BE OPENED A MINIMUM OF 90 DEGREES.

1. WHEN AN ELECTRIC METER CABINET IS CONSTRUCTED DEEPER THAN 18 INCHES, MEASURED FROM THE FACE OF THE METER PANEL TO THE INSIDE OF THE CABINET DOOR(S), BUT LESS THAN 36 INCHES, THE ILLUMINATION REQUIREMENTS OF AN ELECTRIC METER ROOM SHALL BE MET. IF THE DISTANCE WHEN MEASURED FROM THE FACE OF THE METER PANEL TO THE INSIDE OF THE DOOR(S) IS 36 INCHES OR MORE, THIS IS NO LONGER A METER CABINET, IT IS AN ELECTRIC METER ROOM. (a) (b)

(D) DOOR REQUIREMENTS:

METER CABINET DOORS MUST BE SIDE-HINGED. THE DOOR MUST BE DESIGNED TO SECURE IN THE OPEN POSITION AT 90 DEGREES, OR MORE. SHOULD THE DOORS, WHEN OPENED TO 90 DEGREES, OBSTRUCT THE 24-INCH MINIMUM EXIT ROUTE, THEY MUST BE HINGED TO 180 DEGREES. DOORS MUST BE A MINIMUM OF 6'-6" IN HEIGHT. ROLL UP DOORS AND SLIDING DOORS ARE NOT ACCEPTABLE DUE TO INJURIES TO SDG&E (UTILITY) PERSONNEL RESULTING FROM IMPROPER INSTALLATION AND LACK OF PROPER MAINTENANCE. IF EXISTING ROLL UP OR SLIDING DOORS REQUIRE REPLACEMENT, NEW SIDE HINGED DOORS ARE REQUIRED. THE MAXIMUM ALLOWABLE DOOR SILL HEIGHT IS 2 INCHES.

(E) ILLUMINATION REQUIREMENTS:

ILLUMINATION IS REQUIRED IN METER CABINETS INSTALLED IN MID-RISE AND HIGH-RISE BUILDINGS, AND IN OUTDOOR LOCATIONS WITHOUT DIRECT SUNLIGHT. METER CABINETS CONSTRUCTED WITH A DEPTH OF 18 INCHES, OR GREATER, ARE REQUIRED TO BE ILLUMINATED. METER CABINETS LOCATED OUTSIDE OF A BUILDING IN AN AREA OF DIRECT SUNLIGHT ARE NOT REQUIRED TO HAVE ILLUMINATION.

F. LOCKING REQUIREMENTS:

THE UTILITY DOES NOT REQUIRE METER CABINETS TO BE LOCKED. IF THE CUSTOMER CHOOSES TO LOCK THE DOORS, A LOCKING DEVICE APPROVED BY THE UTILITY IS REQUIRED.

G. MINIMUM CLEAR AND LEVEL STANDING AND WORKING SPACE:

THE FOLLOWING REQUIREMENTS APPLY:

- 1. SHALL NOT BE LESS THAN 6'-6" HIGH MEASURED VERTICALLY FROM THE FLOOR, PERMANENT PLATFORM, OR FINAL GRADE
- 2. SHALL NOT BE LESS THAN 3 FEET MEASURED FROM THE FACE OF THE METER CABINET TO THE NEAREST OBSTRUCTION OR PROPERTY LINE
- 3. SHALL EXTEND THE FULL WIDTH OF THE CABINET OPENING WHICH SHALL NOT BE LESS THAN 3 FEET

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CI	HAN	IGE	DR	BY	DSN	APV	DATE
С								F								
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL CHANGES - LSM				IPJ	TPM	11/01/2017	D								
	X Indicates Latest Revision Completely Revised New Page Information Removed															
	SHEET	•		SDO	G&E E	LECTI	RIC SERVIO	E STA	NDARDS & GL	JIDI	ES					
														S	G50	9.3
3 OF 4 ELECTRIC METER CABINET – COMMERCIAL OR RESIDENTIAL MULTI-METER INSTALLATIONS													30303.3			

(H) CABINET AND SUITE IDENTIFICATION:

THE METER CABINET MUST BE PERMANENTLY IDENTIFIED ON THE EXTERIOR OF THE DOOR AS SHOWN. DECALS ARE AVAILABLE FROM THE UTILITY BUT MUST BE INSTALLED BY CUSTOMER. WHEN A BUILDING HAS MORE THAN ONE METER CABINET, A PLAQUE IDENTIFYING THE CABINET AND THE SUITES SERVED FROM THE SERVICE IN THE CABINET MUST BE SECURED TO THE EXTERIOR OF THE CABINET DOOR. (c)

J. IDENTIFICATION/MARKING REQUIREMENTS:

1. EACH METER SOCKET/BASE AND ITS RELATED METERED SERVICE DISCONNECT SHALL BE CLEARLY AND PERMANENTLY MARKED BY THE CONTRACTOR OR CUSTOMER TO INDICATE THE OCCUPANCY OR LOAD SERVED, I.E. UNIT OR SUITE NUMBER, FIRE ALARM, HOUSE METER, ETC. EXAMPLES OF PERMANENT MARKING ARE:

AN IDENTIFICATION PLATE SECURELY FASTENED BY PERMANENT MEANS ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION (AHJ)

COMMERCIALLY AVAILABLE DECALS

- IDENTIFICATION MEANS A STREET, APARTMENT OR SUITE NUMBER. FELT PEN, PIGMENTED INK, OR FINGERNAIL POLISH ARE
 NOT ACCEPTABLE. AT THE OPTION OF THE UTILITY, MARKING MAY BE OMITTED OR IDENTIFIED DIFFERENTLY FOR A SINGLEFAMILY RESIDENCE.
- 3. <u>EXCEPTION:</u> IN A MULTI-METERING SECTION WHERE THE SERVICE DISCONNECT IS LOCATED IMMEDIATELY ADJACENT TO THE METER SOCKET (TO THE SIDE, ABOVE OR BELOW), IT IS ACCEPTABLE TO MARK ONLY THE SERVICE DISCONNECT OR THE METER SOCKET.

K. VENTILATION:

SDG&E DOES NOT HAVE A REQUIREMENT FOR VENTILATION OF ELECTRIC METER CABINETS. THE AUTHORITY HAVING JURISDICTION (AHJ) IS RESPONSIBLE FOR ENFORCEMENT OF VENTILATION IN ELECTRICAL METER CABINETS, WHEN REQUIRED, FOR COMPLIANCE WITH THE CALIFORNIA ELECTRIC CODE, BUILDING CODE OR MECHANICAL CODE.

L NO OBSTRUCTIONS SUCH AS DOOR JAMS, VERTICAL POSTS, ETC. ARE PERMITTED WITHIN THE CABINET OPENING.

BILL OF MATERIALS: NONE

NOTES:

- (I) PROVIDE CLEAR AND LEVEL STANDING AND WORKING SURFACE.
- $({
 m II})$ Hinged doors when opened, may not block the 24-inch minimum exit route.
- (III) CUSTOMER EQUIPMENT ASSOCIATED WITH ELECTRICAL EQUIPMENT AND INSTALLED BELOW METER PANELS CAN EXTEND INTO WORKING SPACE UP TO 6 INCHES.

REFERENCE:

- (a) FOR ELECTRIC METER ROOM STANDARDS, SEE SG506.
- (b) FOR ADDITIONAL REQUIREMENTS IN MID-RISE AND HIGH-RISE BUILDINGS, SEE SG510.
- (c) FOR PLAQUE REQUIREMENTS, SEE SG017.

	© 1998 – 2025 S	an D	iego Gas & El	lectric (Compa	ıny. All	rights	reserved. Re	moval o	of this copyright notice without permission	n is not	permi	tted un	der law.	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С									F						
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL (CHAN	NGES	-	LSM	IPJ	TPM	11/01/2017	D						
		X	Indicates La	atest R	Revisio	n	Con	npletely Rev	d						
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															

SHEET 4 OF 4

ELECTRIC METER CABINET – COMMERCIAL OR RESIDENTIAL MULTI-METER INSTALLATIONS

SG509.4

SCOPE: THIS STANDARD PROVIDES THE POLICY AND REQUIREMENTS FOR ELECTRIC METERING IN BUILDINGS OR STRUCTURES THREE STORIES, AND ABOVE, IN HEIGHT.

DEFINITIONS:

- **HIGH-RISE BUILDING:** FOR THE PURPOSE OF THIS STANDARD, A HIGH-RISE BUILDING IS A STRUCTURE HAVING FLOORS USED FOR HUMAN OCCUPANCY LOCATED MORE THAN 75 FEET ABOVE THE LOWEST LEVEL OF FIRE DEPARTMENT VEHICLE ACCESS.
- **MID-RISE BUILDING:** FOR THE PURPOSE OF THIS STANDARD, A MID-RISE BUILDING IS A STRUCTURE HAVING A MINIMUM OF THREE FLOORS USED FOR HUMAN OCCUPANCY AND CONSTRUCTED AT A HEIGHT LESS THAN IS REQUIRED TO MEET THE DEFINITION OF A HIGH-RISE BUILDING.




FIGURE 1
MID-RISE AND HIGH-RISE ELECTRIC METERING SCHEMATIC G VII)
SEE TABLE 1

TABLE 1

	METERING SCHEMATIC DESCRIPTION LIST
ITEM	DESCRIPTION
1	OPTIONAL CUSTOMER-OWNED BUS DUCT WITH SDG&E SERVICE POINT AT TRANSFORMER
2	SERVICE POINT IN TERMINATING ENCLOSURE (UGPS)
3	SDG&E OWNED METERS AND CUSTOMER-OWNED ELECTRICAL EQUIPMENT
4	DISTRIBUTION PANELS TYPICAL IN EACH TENANT SPACE
(5)	LOADBREAK DISCONNECT SWITCH AT EACH REMOTE LOCATION
6	SDG&E TRANSFORMER

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	F						
В	NO CHANGES - REAFFIRMED	-	JC	IJ	TPM	10/15/2015	Е						
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	08/06/2015	D	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025

SHEET 1 OF 5

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS

SG510.1

CAUTION: ENERGIZED EQUIPMENT – DO NOT OPEN

THE "SERVICE POINT" IS IN THIS ENCLOSURE AT THE CABLE TERMINATIONS. ALL ELECTRICAL WIRING AND EQUIPMENT BEYOND THE SERVICE POINT, EXCEPT SDG&E SERVICE AND METERING EQUIPMENT, ARE CUSTOMER-OWNED, CONTROLLED, SECURED, SAFEGUARDED AND MAINTAINED BY THE CUSTOMER. ONLY AUTHORIZED SDG&E EMPLOYEES ARE ALLOWED ACCESS INTO UTILITY-SEALED ENCLOSURES OR COMPARTMENTS. ALL UTILITY SEALS ARE TO REMAIN INTACT WITHOUT BEING CUT OR REMOVED.

EXAMPLE 1 PLAQUE

CAUTION: ENERGIZED EQUIPMENT – DO NOT OPEN

THE "SERVICE POINT" IS AT THE SECONDARY OF UTILITY'S TRANSFORMER. ALL CONDUCTORS IN THIS ENCLOSURE ARE CUSTOMER-OWNED. ALL ELECTRICAL WIRING AND EQUIPMENT BEYOND THE SERVICE POINT, EXCEPT SDG&E SERVICE AND METERING EQUIPMENT, ARE CUSTOMER-OWNED, CONTROLLED, SECURED, SAFEGUARDED AND MAINTAINED BY THE CUSTOMER. ONLY AUTHORIZED SDG&E EMPLOYEES ARE ALLOWED ACCESS INTO UTILITY-SEALED ENCLOSURES OR COMPARTMENTS. ALL UTILITY SEALS ARE TO REMAIN INTACT WITHOUT BEING CUT OR REMOVED.

EXAMPLE 2 PLAQUE

FIGURE 2 F F2




FIGURE 3
SAFETY CONE B K

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	F						
В	NO CHANGES - REAFFIRMED	-	JC	IJ	TPM	10/15/2015	Е						
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	08/06/2015	D	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025

SHEET 2 OF 5

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS

Completely Revised

SG510.2

INSTALLATION:

REMOTE ELECTRIC METER ROOM AND CABINET SPECIFICATIONS: (d)

- A. ALL UTILITY-OWNED METERS SHALL BE LOCATED IN AN ELECTRIC METER ROOM APPROVED BY THE UTILITY. ON OCCUPIED FLOORS ONLY, THEY MAY BE IN A METER CABINET APPROVED BY THE UTILITY. IN ADDITION TO THE REQUIREMENTS SHOWN ON SG506 FOR METER ROOMS, OR SG509 FOR METER CABINETS, EACH REMOTE METER ROOM/CABINET SHALL HAVE EMERGENCY LIGHTING, A TELEPHONE WITH A DEDICATED PHONE LINE FOR USE IN AN EMERGENCY, AND AN INFORMATION PLAQUE PLACED AT EYE LEVEL ON THE INSIDE OF THE DOOR CONTAINING THE FOLLOWING INFORMATION: (b) (c)
 - 1. 24-HOUR PROPERTY MANAGEMENT EMERGENCY CONTACT TELEPHONE NUMBER
 - 2. TOTAL NUMBER OF METERS FOR THAT PARTICULAR LOCATION
 - 3. FLOOR NUMBER AND NEAREST ELEVATOR OF ALL OTHER METER ROOM/CABINET LOCATIONS IN THE BUILDING
 - 4. MAP SHOWING THE FOLLOWING:

PRESENT LOCATION

EXITS (ELEVATORS AND STAIRS) FROM PRESENT LOCATION TO THE OUTSIDE OF THE BUILDING

ALL METER ROOMS AND CABINETS IN RELATIONSHIP TO THE ELEVATORS

(B) METER CABINETS NORMALLY REQUIRE TWO SAFETY CONES TO BE PLACED INSIDE THE CABINET FOR USE BY INDIVIDUALS WHEN WORK IS BEING PERFORMED.

C. METER ACCESS EASEMENT:

THE BUILDING OWNER SHALL EXECUTE A "METER ACCESS EASEMENT" PROVIDED BY SDG&E, AT THE OWNER'S EXPENSE, AND RETURN TO THE UTILITY DURING THE PLANNING PHASE OF THE PROJECT.

D. MID-RISE AND HIGH-RISE BUILDING REQUIREMENTS:

- 1. ELECTRIC METER ROOMS OR METER CABINETS MAY BE LOCATED ON EVERY FLOOR. METER ROOMS MUST HAVE STRUCTURAL WALLS AND A STRUCTURAL CEILING. SUBSTITUTES SUCH AS FENCES OR PARTITIONS ARE NOT ACCEPTABLE. ELECTRIC METER CABINETS ARE ALLOWED, BUT MAY ONLY BE LOCATED ON OCCUPIED FLOORS WITHIN THE COMMON CORRIDORS USED TO ACCESS DWELLING UNITS AND OTHER SUITES. ELECTRIC METER CABINETS ARE NOT ALLOWED WITHIN PARKING STRUCTURES OR PARKING GARAGES. THE ELECTRIC METER ROOMS/CABINETS SHALL BE LOCATED AS CLOSE AS PRACTICAL TO THE ELEVATOR THAT WILL BE USED BY SDG&E EMPLOYEES TO ACCESS THE FLOORS, BUT IN NO CASE FURTHER THAN 50 FEET WALKING DISTANCE FROM THE ELEVATOR. THE ELEVATOR MUST BE EQUIPPED WITH AN SDG&E RESTRICTED SCHLAGE PRIMUS VHLK KEYWAY AND KEY SWITCH WIRED TO THE CONTROL PANEL TO ALLOW 24-HOUR ACCESS TO THE FLOORS WHERE UTILITY METERS ARE LOCATED. SDG&E WILL NOT CHECK IN WITH A SECURITY GUARD DURING OUR NORMAL BUSINESS HOURS.
- 2. THE CUSTOMER HAS THE OPTION OF INSTALLING MULTIPLE METER LOCATIONS ON THE SAME FLOOR AND OMITTING METER LOCATIONS ON EVERY FLOOR PROVIDED:

THE TOTAL NUMBER OF METER LOCATIONS DOES NOT EXCEED THE TOTAL NUMBER OF OCCUPIED BUILDING FLOORS.

ALL METER LOCATIONS ARE WITHIN 50 FEET WALKING DISTANCE FROM THE ELEVATOR THAT WILL BE USED BY SDG&E EMPLOYEES TO ACCESS THE FLOORS. METER LOCATION ENTRANCES SHALL BE LOCATED DIRECTLY OFF THE COMMON CORRIDOR USED TO ACCESS THE ELEVATOR. IT IS NOT ACCEPTABLE TO ENTER ANOTHER SPACE OR ROOM BEFORE ENTERING THE METER ROOM/CABINET.

THE CUSTOMER MAY PROVIDE ACCESS TO MULTIPLE METER ROOMS/CABINETS LOCATED ON THE SAME FLOOR FROM DIFFERENT ELEVATORS. THIS IS MORE COMMON IN HIGH-RISE PODIUM CONSTRUCTION PROJECTS.

E. MID-RISE BUILDING EXCEPTION:

AN EXCEPTION MAY BE GRANTED TO ALLOW MULTIPLE METER ROOMS IN A SUBTERRANEAN PARKING STRUCTURE IN LIEU OF METER ROOMS/CABINETS LOCATED ON THE OCCUPIED FLOORS PROVIDED ALL SDG&E APPLICABLE STANDARDS ARE MET. THE CUSTOMER SHOULD CONSULT WITH SDG&E'S PLANNER TO USE THIS EXCEPTION IN THE CONCEPTUAL DESIGN PHASE OF THE PROJECT.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	F						
В	NO CHANGES - REAFFIRMED	-	JC	IJ	TPM	10/15/2015	Е						
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	08/06/2015	D	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025
X Indicates Latest Revision			n	Con	npletely Revi	ised	New Page Information Re	moved	i				

SHEET 3 OF 5

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SOCIE ELLETTIC SERVICE STANDARDS & GOIDES

SG510.3

ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS

- THE MAIN ELECTRIC ROOM SHALL CONTAIN A MASTER DIRECTORY SHOWING ALL METER LOCATIONS WITHIN THE BUILDING. THIS DIRECTORY MAY BE LOCATED ON THE INTERIOR OR EXTERIOR OF THE METER ROOM DOOR, OR MOUNTED ON A WALL WITHIN THE ROOM IN A CONSPICUOUS LOCATION. SEE SG017 FOR PLAQUE SPECIFICATIONS, WITH THE EXCEPTION THAT ALL LETTER SIZES MAY BE REDUCED TO 1/8-INCH. IT IS ACCEPTABLE TO MOUNT A SITE MAP DENOTING THE METER LOCATIONS AND ACCESS ROUTE BETWEEN PLEXIGLAS IN LIEU OF A PLAQUE. (f)
 - 1. EACH MAIN SERVICE DISCONNECT SHALL MEET THE REQUIREMENTS ON SG511. (g)
 - FIGURE 2: EXAMPLE 1 IS REQUIRED AT THE SERVICE POINT AND IS TO BE LOCATED ON THE EXTERIOR PANEL COVER OF THE TERMINATING ENCLOSURE WHERE SDG&E CONDUCTORS TERMINATE. IF THE SERVICE POINT IS AT SDG&E'S TRANSFORMER, FIGURE 2: EXAMPLE 2 SHALL BE INSTALLED ON THE EXTERIOR PANEL COVER AT THE MAIN SERVICE DISCONNECT LOCATION. SEE SG017 FOR PLAQUE SPECIFICATIONS, WITH THE EXCEPTION THAT ALL LETTER SIZES MAY BE REDUCED TO 1/8 INCH.
- (G) FEEDER DISCONNECTS CONTROLLING ELECTRICITY TO REMOTE METER LOCATIONS SHALL HAVE A PERMANENT PLAQUE AFFIXED TO EACH OF THE FEEDER DISCONNECTS STATING:

THIS DISCONNECT CONTROLS POWER TO METERS LOCATED IN REMOTE LOCATIONS ON FLOORS ______. SEE DIAGRAM ON WALL/DOOR INDICATING THE LOCATION AND ACCESS ROUTE TO THE REMOTE METER LOCATIONS.

FIGURE 4 G

- H FEED CONDUCTORS (CABLE OR BUSWAY) SHALL BE INSTALLED PER THE CALIFORNIA ELECTRICAL CODE AND APPROVED BY THE AUTHORITY HAVING JURISDICTION (AHJ). WHEN CABLE IS INSTALLED IN A RACEWAY CONTAINING A CONDULET AND/OR JUNCTION BOX, THEY SHALL BE LOCATED NO HIGHER THAN 9 FEET ABOVE STANDING SURFACE AND SHALL PROVIDE A MEANS FOR INSTALLATION OF UTILITY SEALS. BUS DUCT HOUSING OR CONCEALED RACEWAYS CONTAINING UNMETERED CONDUCTORS ARE NOT REQUIRED TO BE SEALED.
- (J) A LOAD-BREAK DISCONNECT SWITCH, CAPABLE OF BEING LOCKED IN THE OPEN/OFF POSITION, IS REQUIRED WITHIN SIGHT OF EACH GROUP OF METERS CONTROLLED BY A FEED ORIGINATING FROM THE MAIN ELECTRIC METER ROOM.
- (K) SAFETY CONES CONSTRUCTED OF RUGGED PLASTIC ARE REQUIRED FOR ELECTRIC METER CABINETS. THE SAFETY CONES ARE TO BE PLACED INSIDE THE CABINET PRIOR TO THE UTILITY ENERGIZING THE MAIN SERVICE TO THE BUILDING, UNLESS THE CABINET HAS NOT BEEN CONSTRUCTED AT THE TIME THE SERVICE IS ENERGIZED. TWO SAFETY CONES ARE REQUIRED FOR EACH METER CABINET UNLESS THE POSITION OF THE CABINET IS SUCH THAT FOOT TRAFFIC IS LIMITED TO ONE DIRECTION, IN WHICH CASE, UPON APPROVAL BY THE UTILITY'S INSPECTOR, ONLY ONE SAFETY CONE IS REQUIRED.

BILL OF MATERIALS: NONE

NOTES:

GENERAL INFORMATION:

- I. THE PURPOSES OF THE STANDARD ARE TO ESTABLISH REQUIREMENTS FOR AN ELECTRICAL SYSTEM WITH INDIVIDUAL METERING LOCATED ON MULTIPLE FLOORS IN A MANNER THAT WILL PROVIDE FOR SAFE ACCESS, OPERATIONS, AND MAINTENANCE OF THE ELECTRICAL SYSTEM AND HELP ENSURE RELIABLE SERVICE TO THE OCCUPANTS FOR THE LIFE OF THE BUILDING.
- II. THIS STANDARD APPLIES TO BUILDINGS OR STRUCTURES USED FOR COMMERCIAL AND RESIDENTIAL USE, INCLUDING MIXED-USE BUILDINGS, SUCH AS, BUT NOT LIMITED TO, A HOTEL WITH RESIDENTIAL DWELLING UNITS LOCATED ON THE UPPER FLOORS OF THE BUILDING, OR A BUILDING WITH COMMERCIAL SPACE ON THE LOWER FLOORS AND RESIDENTIAL DWELLING UNITS LOCATED ON THE UPPER FLOORS.
- III. EACH DWELLING UNIT IN A MID-RISE OR HIGH-RISE BUILDING MUST BE INDIVIDUALLY METERED BY SDG&E (UTILITY). (a)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DATE **REV** DR BY DSN APV DR BY DSN APV DATE CHANGE CHANGE С **EDITORIAL CHANGES** LSM TPM 11/01/2017 F TP1 NO CHANGES - REAFFIRMED В _ JC 11 TPM 10/15/2015 Ε MDJ 08/06/2015 Α **EDITORIAL CHANGES** JC **BRB** FORMATTING/EDITORIAL CHANGES | EDM | IWA | JTM | KRG | 02/07/2025 **Indicates Latest Revision** New Page Completely Revised Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG510.4 4 OF 5 ELECTRICAL METERING IN

MID-RISE AND HIGH-RISE BUILDINGS

NOTES (CONT'D):

GENERAL INFORMATION (CONT'D):

IV. NON-RESIDENTIAL ENTERPRISES MUST BE INDIVIDUALLY METERED BY THE UTILITY IN MID-RISE BUILDINGS. THE CUSTOMER HAS THE OPTION OF INSTALLING A MASTER METER TO SERVE ALL NON-RESIDENTIAL ENTERPRISES IN HIGH-RISE BUILDINGS WHERE THE NON-RESIDENTIAL ENTERPRISES ARE LOCATED ON OR ABOVE THE SIXTH FLOOR USED FOR HUMAN OCCUPANCY, OR REQUESTING INDIVIDUAL METERS BY THE UTILITY FOR EACH SEPARATE ENTERPRISE. THE UTILITY'S FILED ELECTRIC RULE 19 PROHIBITS SUBMETERING OF NON-RESIDENTIAL SERVICE. A CUSTOMER SHALL NOT CHARGE OTHERS FOR ELECTRICITY RECEIVED THROUGH A SINGLE METER EXCEPT WHERE THE COST OF ELECTRICITY IS ABSORBED IN THE RENT FOR EACH INDIVIDUAL TENANT. THE RENT SHALL NOT VARY WITH ELECTRIC CONSUMPTION. A SEPARATE IDENTIFIABLE CHARGE TO THE TENANTS FOR ELECTRICITY IS NOT ALLOWED.

V. SERVICE STANDARDS REVIEW:

THE SDG&E PLANNER SHALL HAVE SERVICE STANDARDS, IN ELECTRIC DISTRIBUTION ENGINEERING, REVIEW THE BUILDING PROJECT PLANS FOR MID-RISE AND HIGH-RISE BUILDINGS TO ENSURE THE GROUNDING ELECTRODE CONDUCTOR IS APPROPRIATELY PLACED AND OTHER ENGINEERING RELATED ISSUES ARE RESOLVED DURING THE DESIGN PHASE OF THE PROJECT.

VI. APPROVAL PROCESS:

THE LOCAL DESIGN AND PROJECT MANAGEMENT OFFICE SHALL BE CONTACTED TO APPROVE THE MID-RISE OR HIGH-RISE BUILDING MAIN SERVICE AND METER ROOM LOCATION AND THE REMOTE ELECTRIC METER ROOM OR CABINET LOCATIONS. THE UTILITY'S APPROVAL SHALL BE OBTAINED PRIOR TO THE INSTALLATION OF THE ELECTRICAL SERVICE AND METERING EQUIPMENT. ANY SERVICE AND METERING EQUIPMENT THAT HAS BEEN INSTALLED WITHOUT THE UTILITY'S APPROVAL SHALL BE MODIFIED OR RELOCATED AT THE CUSTOMER'S/CONTRACTOR'S EXPENSE AS NECESSARY TO MEET ALL UTILITY STANDARDS.

- (VII) METERING SECTIONS IN MAIN SWITCHBOARD NOT SHOWN.
- (VIII) EACH METER SOCKET AND ITS RELATED METER SERVICE DISCONNECT SHALL MEET ALL OF THE UTILITY'S STANDARDS.

IX. METERING COMMUNICATIONS:

FOR METERING COMMUNICATION REQUIREMENTS, SEE SG525, AND CONSULT WITH SDG&E'S SMART METER OPERATIONS VIA EMAIL: networkdevice@semprautilities.com (d)

- (XI) 10" X 10" DOUBLE-SIDED SIGN SECURELY SNAPPED INTO THE TOP OF CONE
- (XII) 9 POUND WEIGHT REQUIRED FOR EXTRA STABILITY.
- DISCONNECT SHALL BE CAPABLE OF BEING LOCKED IN THE OPEN/OFF POSITION.

REFERENCE:

- (a) SEE PUBLIC UTILITIES CODE SECTION 780.5.
- (${\sf b}$) FOR METER ROOMS, SEE SG506.
- (c) FOR METER CABINETS, SEE SG509.
- (d) FOR METERING COMMUNICATION REQUIREMENTS, SEE SG525.
- e. FOR SERVICE AND METERING POLICIES, SEE ELECTRIC SERVICE POLICIES ON SG011, SG012, AND SG013.
- (f) FOR PLAQUE SPECIFICATIONS, SEE SG017.
- (g) SEE SG511.


	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN		DR	BY	DSN	APV	DATE	REV		CH	ΑN	IGE	DR	BY	DSN	APV	DATE	
С	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	F									
В	NO CHANGES - I	FIRMED	-	JC	IJ	TPM	10/15/2015	Е										
Α	A EDITORIAL CHANGES				JC	BRB	MDJ	08/06/2015	D	FO	RMATTING/ED	TIC	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025
		atest R	evisio	n Completely Revised New Page Information Removed							i							
ı	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	


SHEET 5 OF 5


ELECTRICAL METERING IN MID-RISE AND HIGH-RISE BUILDINGS

SG510.5

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR ELECTRIC SERVICE DISCONNECTS AND METER SERVICE DISCONNECTS.







CONFIGURATION 2
MULTI-METER INSTALLATION, 2 TO 6 METERS
WITHOUT MAIN DISCONNECT

FIGURE 1 SERVICE DISCONNECT LOCATION WITH RESPECT TO METER AND METER SERVICE DISCONNECT




FIGURE 2
MULTI-METER INSTALLATION, 2 TO 6 METERS WITH MAIN DISCONNECT




FIGURE 3
MULTI-METER INSTALLATION, NUMBERING 7 OR MORE METERS

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CH	IAI	IGE	DR	BY	DSN	APV	DATE
С							F								
В	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D								
	X Indicates Latest Revision					npletely Revi	ised	New Page		Information Re	moved				

SHEET 1 OF 3 Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SPORE ELECTRIC SERVICE STANDARDS & GOIDES

ELECTRIC SERVICE DISCONNECTS
AND METER SERVICE DISCONNECTS

SG511.1

INSTALLATION:

A. GENERAL INFORMATION

- 1. A SERVICE DISCONNECT IS A DEVICE, OR GROUP OF DEVICES, OR OTHER MEANS BY WHICH THE CONDUCTORS OF A CIRCUIT CAN BE DISCONNECTED FROM THEIR SOURCE OF SUPPLY.
- 2. ALL SERVICE EQUIPMENT OTHER THAN THAT PROVIDED BY SDG&E (UTILITY) IS TO BE PROVIDED AND INSTALLED BY THE CUSTOMER IN COMPLIANCE WITH THE REQUIREMENTS OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ). (a)

B. DISCONNECT AMPACITY AND AMPERE INTERRUPTING CAPACITY (AIC) RATING:

THE METER SERVICE DISCONNECT AND MAIN SERVICE DISCONNECT SHALL MEET ALL CODE REQUIREMENTS AS DETERMINED BY THE AHJ. (b)

C. METER SERVICE DISCONNECT

1. FOR EACH METER INSTALLED ON A SERVICE OF 600V, OR LESS, A SINGLE FUSIBLE SWITCH, CIRCUIT BREAKER, OR OTHER APPROVED DISCONNECTING MEANS SHALL BE LOCATED ON THE LOAD SIDE OF THE METER AND SHALL CONTROL ALL OF AND ONLY THE ENERGY REGISTERED BY THAT METER.

EXCEPTION 1: TWO METER SERVICE DISCONNECTS ARE ACCEPTABLE IN 300 OR 400A RESIDENTIAL SERVICE EQUIPMENT. 300A SERVICE EQUIPMENT IS LIMITED TO ONE 200A MAIN BREAKER AND ONE 100A MAIN BREAKER. 400A SERVICE EQUIPMENT IS LIMITED TO TWO 200A MAIN BREAKERS.

EXCEPTION 2: MULTIPLE METER SERVICE DISCONNECTS ARE ACCEPTABLE FOR CURRENT TRANSFORMER (CT) METERING APPLICATIONS.

2. THE METER SERVICE DISCONNECT MUST BE LOCATED AT OR IMMEDIATELY ADJACENT TO THE METER. FOR EXAMPLE, THE METER SERVICE DISCONNECT MAY NOT BE LOCATED INSIDE THE BUILDING SERVED IF THE METER IS LOCATED OUTSIDE.

D. MAIN SERVICE DISCONNECT (d)

- 1. FOR MULTI-METER INSTALLATIONS, ELECTRICAL CODES, ENFORCED BY THE AHJ, MAY REQUIRE THE INSTALLATION OF A MAIN SERVICE DISCONNECT LOCATED ON THE SUPPLY (LINE) SIDE OF THE METERS. WHEN A MAIN SERVICE DISCONNECT IS INSTALLED, EACH METER WILL ALSO BE REQUIRED TO HAVE ITS OWN METER SERVICE DISCONNECT.
- 2. IF MULTIPLE METER LOCATIONS WITHIN A BUILDING HAVE BEEN APPROVED BY THE UTILITY AND AHJ, EACH GROUP OF METERS WILL BE REQUIRED TO HAVE A FEEDER DISCONNECT GROUPED WITH THE MAIN SERVICE DISCONNECT(S). A PERMANENT PLAQUE MUST BE AFFIXED TO EACH FEEDER DISCONNECT STATING:

"THIS DISCONNECT SERVES METERS <u>LOCATED ON FLOOR(S)</u> /IN ROOMS .

SEE DIAGRAM ON WALL TO THE LEFT/RIGHT FOR LOCATIONS OF METERS."

- 3. THE DIAGRAM INDICATING THE METER LOCATIONS MUST BE A PERMANENT PLAQUE AFFIXED TO THE WALL. THE MAIN SERVICE WILL NOT BE ENERGIZED UNTIL THIS REQUIREMENT IS COMPLETE. (c)
- 4. FOR SINGLE METER INSTALLATIONS, A MAIN SERVICE DISCONNECT IS NOT PERMITTED ON THE SUPPLY (LINE) SIDE OF THE METER.

BILL OF MATERIALS: NONE

NOTES:

- $ig(\ \mathrm{I} \ ig)$ meter service disconnect(s) on load side of meter
- (II) AMPACITY AND AIC RATINGS OF METER SERVICE DISCONNECT PROPER FOR PROTECTION OF LOAD CONDUCTORS AND AVAILABLE FAULT CURRENT.
- (III) MAIN DISCONNECT AHEAD OF 2 TO 6 METERS, EITHER FUSIBLE SWITCH OR CIRCUIT BREAKER

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		С	HAN	IGE	DR	BY	DSN	APV	DATE
С									F									
В	EDITORIAL (IGES	EDM	IWA	JTM	KRG	02/07/2025	Е										
Α	EDITORIAL (IGES	-	LSM	IPJ	TPM	11/01/2017	D										
		Indicates La	atest R	evisio	n	Completely Revised New Page Information Removed						ı						
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																		

SHEET 2 OF 3

ELECTRIC SERVICE DISCONNECTS AND METER SERVICE DISCONNECTS

SG511.2

NOTES (CONT'D):

- (IV) AMPACITY RATING OF METER SERVICE DISCONNECT PROPER FOR PROTECTION OF LOAD CONDUCTORS; AIC RATING COORDINATED WITH LET-THROUGH CURRENT OF CURRENT-LIMITING FUSE DEVICE AHEAD OF METERS, OR A SERIES-RATED SYSTEM.
- (V) A SAFETY SOCKET CAN WITH TEST-BYPASS FACILITIES IS REQUIRED IN ALL CASES, WHETHER SEPARATELY METERED OR SERVED THROUGH A HOUSE METER. ALARM METER SOURCE MAY BE CONNECTED ON THE LINE SIDE OF THE MAIN DISCONNECT. CONSULT WITH THE AHJ FOR ACCEPTABLE POINT OF CONNECTION.
- (VI) A MAIN DISCONNECT LOCATED AHEAD OF MORE THAN 6 METER SERVICE DISCONNECTS IS REQUIRED PER THE CALIFORNIA ELECTRIC CODE.
- (VII) AMPACITY AND AIC RATINGS OF MAIN SERVICE DISCONNECT AND METER SERVICE DISCONNECTS SHALL MEET ALL ELECTRICAL CODE REQUIREMENTS ENFORCED BY THE AHJ.

REFERENCE:

- (a) FOR EQUIPMENT PROVIDED BY THE CUSTOMER, SEE SG004.
- (b) FOR INFORMATION ON THE UTILITY'S CONTRIBUTION TO FAULT CURRENT WHEN DETERMINING THE NECESSARY SHORT CIRCUIT CURRENT RATING AND AIC RATING FOR A SERVICE OR METER SERVICE DISCONNECT DEVICE, SEE SG006.
- (c) FOR PLAQUE SPECIFICATIONS AND INSTALLATION REQUIREMENTS, SEE SG017.
- (d) FOR SPECIFIC REQUIREMENTS IN MID-RISE AND HIGH-RISE BUILDINGS, SEE SG510.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice w	

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
A	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

ELECTRIC CERVICE DISCONNECTS

Completely Revised

SG511.3

ELECTRIC SERVICE DISCONNECTS AND METER SERVICE DISCONNECTS

SCOPE: THIS STANDARD DESCRIBES GENERAL REQUIREMENTS FOR RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT.

DEFINITIONS:

• **SELF-CONTAINED METERS:** A SELF-CONTAINED METER IS ONE WHICH IS CAPABLE OF CARRYING THE TOTAL CURRENT AND VOLTAGE OF THE ELECTRIC SERVICE SUPPLIED TO THE CUSTOMER. THIS TYPE OF METER IS CONNECTED DIRECTLY TO THE SERVICE ENTRANCE CONDUCTORS WHEN IT IS INSERTED INTO THE METER SOCKET.

INSTALLATION:

A. METER SOCKET CONNECTIONS

- 1. METER SOCKETS FOR ALL SELF-CONTAINED METERS SHALL BE CONNECTED TO THE SERVICE ENTRANCE CONDUCTORS BY THE CONTRACTOR. CONNECTION DIAGRAMS FOR THE VARIOUS TYPES OF SERVICE EQUIPMENT ARE SHOWN ON SHEETS 2 TO 7.
- 2. AN SDG&E (UTILITY) EMPLOYEE WILL PROVIDE AND INSTALL THE WIRING USED IN METER SOCKETS LOCATED IN CURRENT TRANSFORMER (CT) COMPARTMENTS.

B. SELF-CONTAINED METER SOCKETS:

SOCKETS FOR USE WITH SELF-CONTAINED METERS ARE AVAILABLE IN TWO APPROVED RATINGS. WHEN CONNECTED TO PROPERLY SIZED SERVICE ENTRANCE CONDUCTORS, THE APPROVED STANDARD-DUTY SOCKET HAS A NOMINAL CAPACITY OF 100A COMMERCIAL AND 125A RESIDENTIAL. THE APPROVED HEAVY-DUTY SOCKET HAS A NOMINAL CAPACITY OF 200A COMMERCIAL AND RESIDENTIAL.

C. METER SOCKET CLOSING DEVICES:

METER SOCKETS <u>SHALL NOT</u> BE EQUIPPED WITH CIRCUIT CLOSING OR BY-PASS DEVICES WHICH AUTOMATICALLY CLOSE WHEN THE METER IS REMOVED FROM THE METER SOCKET.

D. EQUIPMENT CONNECTED AHEAD OF A MAIN SERVICE DISCONNECT:

CIRCUITS SUPPLYING FIRE ALARMS, FIRE SPRINKLERS, FIRE PUMPS, AND EXIT LIGHTING MAY BE CONNECTED ON THE LINE SIDE OF THE MAIN SERVICE DISCONNECT THROUGH SUITABLE PROTECTION. ALL SUCH CIRCUITS MUST BE METERED, EITHER THROUGH A HOUSE METER OR A SEPARATE METER. (a)

E. COMBINATION PULL AND METER CANS FOR UNDERGROUND OR OVERHEAD RESIDENTIAL SERVICE:

RESIDENTIAL SERVICE EQUIPMENT IS MANUFACTURED WITH A COMBINATION PULL SECTION AND TERMINATING SECTION, DESIGNED FOR THE UTILITY TO INSTALL THEIR SERVICE LATERAL CONDUCTORS AND TERMINATE ON THE FACTORY PROVIDED TERMINATION LUGS, A SELF-CONTAINED METER SOCKET, AND A DISTRIBUTION SECTION FOR THE CUSTOMER'S MAIN BREAKER (ALSO REFERRED TO AS THE METER SERVICE DISCONNECT) AND FEEDER/BRANCH CIRCUIT BREAKERS. SEE FIGURES OF THIS TYPE OF SERVICE EQUIPMENT AND INSTALLATION NOTES ON SHEETS 2 TO 7. (b)

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:


- (a) SEE SG511.
- (b) FOR RESIDENTIAL METER PEDESTALS, SEE SG518.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CH	IAN	IGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDIT	AL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е										
Α	A EDITORIAL CHANGES			-	LSM	IPJ	TPM	11/01/2017	D									
X Indicates Latest Revision Completely Revised New									New Page		Information Re	emoved	ı					
SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																		

SHEET 1 OF 7

RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT GENERAL INFORMATION

SCOPE: THIS STANDARD DESCRIBES 0-600V COMBINATION PULL AND METER CANS FOR RESIDENTIAL SERVICE WITH 225A MAXIMUM, SINGLE-PHASE, 3-WIRE APPLICATIONS.






FIGURE 1

COMBINATION PULL AND METER CANS
FOR UNDERGROUND OR OVERHEAD
RESIDENTIAL SERVICE
225A MAXIMUM, SINGLE-PHASE, 3-WIRE, 0-600V
FRONT VIEW
SEE TABLES 1 AND 2

FIGURE 1

COMBINATION PULL AND METER CANS
FOR UNDERGROUND OR OVERHEAD
RESIDENTIAL SERVICE
225A MAXIMUM, SINGLE-PHASE, 3-WIRE, 0-600V
SIDE VIEW
SEE TABLES 1 AND 2


© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 7

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT 225A MAXIMUM






FIGURE 2

COMBINATION PULL AND METER CANS
FOR UNDERGROUND RESIDENTIAL SERVICE ONLY
225A MAXIMUM, SINGLE-PHASE, 3-WIRE, 0-600V
FRONT VIEW
SEE TABLES 1 AND 2

FIGURE 2

COMBINATION PULL AND METER CANS FOR UNDERGROUND RESIDENTIAL SERVICE ONLY 225A MAXIMUM, SINGLE-PHASE, 3-WIRE, 0-600V SIDE VIEW

SEE TABLES 1 AND 2

TABLE 1

IADEL I											
COMBINATION PULL AND METER CANS RESIDENTIAL SERVICES, 225A MAXIMUM											
SERVICE ENTRANCE NOMINAL CURRENT		LATERAL IT SIZE		INIMUM PU ION DIMENS		UTILITY MAXIMUM WIRE SIZE ALLOWED	UTILITY MAXIMUM WIRE SIZE				
CAPACITY (AMP)	MIN. (IN)	MAX. (IN)	Z (IN)	Y (IN)	X (IN)	WITHOUT PIN ADAPTERS (KCMIL)	ALLOWED WITH PIN ADAPTERS (KCMIL)				
125	2 (a)	3	8	6	4	1/0	3/0				
225	3	3	11	8 1/2	5 1/2	3/0	350				

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT 225A MAXIMUM

TABLE 2

COMBI	INATION PULL AND METER CANS RESIDENTIAL SERVICE, 225A MAXIMUM												
ITEM	DESCRIPTION												
<u>(1)</u>	LUGS, LANDING (OPTIONAL)												
2	CONDUCTORS, SERVICE ENTRANCE												
(3)	LUG FOR UG SERVICE												
4	LUGS, LANDING												
(5)	CIRCUIT BREAKER DISTRIBUTION SECTION												
6	PULL CAN, SEALABLE												
7	CONDUIT, SERVICE LATERAL												

INSTALLATION:

A THIS EQUIPMENT MAY BE CONSTRUCTED FOR OH, UG OR FOR COMBINATION OVERHEAD/UNDERGROUND SERVICE APPLICATIONS. WHEN CONSTRUCTED AS AN OH/UG DEVICE, A YELLOW CAUTION LABEL (2" X 3" MINIMUM) SHALL BE INSTALLED BELOW THE TERMINATIONS IN THE PULL SECTION READING:

"CAUTION: BUS ENERGIZED AT ALL TIMES"

- B TERMINALS FOR SERVICE CONDUCTORS SHALL BE ALUMINUM BODIED RANGE TAKING LUGS WITH A RANGE OF 6 THROUGH 1/0 AWG FOR THE 125A DEVICE AND 4 THROUGH 250 KCMIL FOR THE 225A DEVICE. THE UTILITY MAY INSTALL A MAXIMUM 3/0 KCMIL USING PIN ADAPTERS IN 125A DEVICES AND 350 KCMIL USING PIN ADAPTERS IN 225A DEVICES. THE UTILITY PLANNER SHALL NOTE IF PIN ADAPTERS ARE REQUIRED ON THE ELECTRIC METER AND SERVICE LOCATION FORM AS FOLLOWS: "PIN ADAPTERS REQUIRED PER UG STANDARD 4173."
- (C) BONDING ACCORDING TO THE CALIFORNIA ELECTRICAL CODE SHALL BE INSTALLED PRIOR TO INSTALLATION OF UNDERGROUND SERVICE CONDUCTORS. BONDING CONNECTIONS FOR <u>SERVICE LATERAL CONDUITS</u> ONLY IS PERMITTED AT BOTTOM OF CAN. ANY OTHER BONDING OR GROUNDING CONNECTION MUST BE MADE ABOVE THE PULL CAN AREA AND NO GROUNDING OR BONDING CONDUCTOR IS PERMITTED TO PASS THROUGH THE PULL CAN AREA. THE PULL CAN AREA WILL BE UNDER UTILITY SEAL, THEREFORE, IT IS DEEMED INACCESSIBLE TO THE AUTHORITY HAVING JURISDICTION (AHJ) FOR INSPECTION. PROVIDE A BONDING SCREW OR JUMPER IF THE NEUTRAL IS INSULATED FROM THE ENCLOSURE.

BILL OF MATERIALS: NONE

NOTES:

- (I) BUSSES SHALL BE PROPERLY SUPPORTED
- II. SERVICE LATERAL CONDUIT SHALL ENTER THE BOTTOM OF THE PULL SECTION.
- (III) A MINIMUM RADIAL CLEARANCE OF 1 1/2 INCHES SHALL BE PROVIDED BETWEEN HOT BUS TERMINALS AND GROUNDED SURFACES OR THE NEUTRAL BUS OR TERMINATION LUG.
- IV. RESIDENTIAL PULL CANS SHALL BE ACCESSIBLE WITHOUT ENTERING THE BUILDING, AND WHEN EXPOSED TO THE WEATHER, SHALL BE RAINTIGHT.
- V. THIS DEVICE CANNOT SUPPLY OTHER METERS.

REFERENCE:

- (a) SEE SG309.
- b. SEE UG4173.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С									F						
В	FORMATTING/EDITORIAL CHANGE			EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	A EDITORIAL CHANGES			-	LSM	IPJ	TPM	11/01/2017	D						
		atest R	Revisio	n	Con	npletely Revi									
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES														

SHEET 4 OF 7

RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT 225A MAXIMUM

SCOPE: THIS STANDARD DESCRIBES 120/240V COMBINATION PULL AND METER CANS FOR RESIDENTIAL SERVICE FOR 300-400A, SINGLE-PHASE, 3-WIRE APPLICATIONS. 8 1/2" MIN. 1" MIN. 3 1/4" (2)(VII) MIN. (N) 000 3′-4″ (5) 3 1 1/2" 1 1/2" MIN. 1 1/2" MIN. 8 MÍN. 10 12 1'-3 1/2" 4 10" MIN. 13 14 MIN. 15 16 **ACCESS** 17 18 **OPENING** 19 -20 21 22 -26 $\langle 11 \rangle$ 27 **-28** – 1′-3 1/2″ 6" MIN. (I ` FIGURE 1 **FIGURE 2** COMBINATION PULL AND METER CANS (A)(B)(II)(III)(VI)(VII)(a) FOR UNDERGROUND RESIDENTIAL SERVICE ONLY SEE TABLE 1 300-400A, SINGLE-PHASE, 3-WIRE, 120/240V (A)B)II)III)VI)WII)(a)**SEE TABLE 1** © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR DSN APV DR BY DSN APV **DATE CHANGE** BY DATE **REV CHANGE** С F В FORMATTING/EDITORIAL CHANGES **EDM** IWA JTM KRG 02/07/2025 Ε **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 Α **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG512.5 RESIDENTIAL SELF-CONTAINED 5 OF 7 SERVICE AND METERING EQUIPMENT 300 - 400A

TABLE 1

C	OMBINATION PULL AND METER CANS, 300-400A, DESCRIPTION LIST
ITEM	DESCRIPTION
1	SOCKET, METER, MAIN DISTRIBUTION SECTION
(2)	LUG, MECHANICAL
(3)	SEALING
<u>4</u>	BARRIER
(5)	NEUTRAL, BONDED
6	METER SECTION
7	WIRE, FACTORY INSTALLED
8	SERVICE DISCONNECT UPPER SECTION (200A MAX.)
9	SERVICE DISCONNECT 200A LOWER SECTION
(10)	SUBMAINS
(11)	GROUND, EQUIPMENT




FIGURE 3

COMBINATION PULL AND METER CANS FOR OVERHEAD C D IX XI
RESIDENTIAL SERVICE ONLY
300-400A, SINGLE-PHASE, 3-WIRE, 120/240V
FRONT VIEW

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 6 OF 7

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT 300 - 400A

INSTALLATION:

- (A) TERMINATIONS FOR SERVICE CONDUCTORS SHALL BE ALUMINUM-BODIED MECHANICAL LUGS WITH A RANGE OF 1 AWG THROUGH 600 KCMIL. THE LUGS SHALL BE SECURED TO ASSURE VERTICAL ALIGNMENT. A MINIMUM RADIAL CLEARANCE OF 1 1/2 INCHES SHALL BE PROVIDED BETWEEN HOT BUS TERMINALS AND GROUNDED SURFACES OR NEUTRAL BUS OR TERMINATION LUG. THE 1 1/2-INCH DIMENSION MAY BE LESS IF INSULATING MATERIAL IS PROVIDED.
- (B) WHEN AN OVERHEAD SERVICE DROP WILL SUPPLY POWER TO THIS EQUIPMENT, THE CUSTOMER'S SERVICE ENTRANCE CONDUCTORS MUST ENTER THE LOWER LEFT SIDE OF THE UNDERGROUND SERVICE SECTION AND CONNECT TO THE MECHANICAL LUGS. A CONDULET WILL BE REQUIRED AND SHALL BE VISIBLE AND SEALABLE. SEE FIGURE 3. (A)
- C THE INSTALLATION SHALL BE INSPECTED BY THE AHJ PRIOR TO THE UTILITY ENERGIZING THEIR SERVICE DROP CONDUCTORS AND INSTALLING THE METER. ONCE THE SERVICE IS ENERGIZED, THE PULL CAN COVER WILL BE SEALED BY THE UTILITY AND WILL NO LONGER BE ACCESSIBLE TO THE AHJ INSPECTOR.
- (D) FOR "FLUSH-MOUNTED" INSTALLATIONS, A SOLID ONE-PIECE RISER ACCEPTABLE TO THE UTILITY AND THE AHJ IS REQUIRED.

BILL OF MATERIALS: NONE

NOTES:

- $(\hspace{1mm}\mathrm{I}\hspace{1mm})$ 3-inch minimum, 4-inch maximum conduit in the center position. Utility's maximum conductor size is 500 kcmil.
- (II) THE PANEL SHOWN IS A COMBINATION DEVICE HAVING BOTH A UTILITY SECTION (I.E. PULL SECTION AND METERING SECTION) AND A CUSTOMER SECTION.
- (III) THE PANEL SHALL BE MARKED WITH EITHER A RATING OF "320 AMPERES CONTINUOUS" OR "400 AMPERES MAXIMUM (320 CONTINUOUS)".
- (IV) A RING-TYPE SOCKET IS REQUIRED. THE PANEL SHALL BE PROVIDED WITH A SEALING RING AND THE METER SOCKET SHALL BE RIGIDLY MOUNTED ON A SUPPORT AND ATTACHED TO THE METER PANEL.
- (V) the meter socket may be located above, to the left or right of the terminating pull section.
- (VI) PULL SECTION COVER PANELS SHALL BE REMOVABLE, SEALABLE AND PROVIDED WITH TWO LIFTING HANDLES.
- (VII) THE 10-INCH MINIMUM ACCESS OPENING DIMENSION SHOWN IS MEASURED BETWEEN THE RETURN FLANGES. WHEN VIEWED FROM THE FRONT OF THE PULL SECTION AREA, RETURN FLANGES SHALL NOT EXTEND CLOSER THAN 3/4 INCH FROM THE OUTSIDE EDGE OF THE MECHANICAL LUGS.
- (VIII) This device cannot supply other meters.
- (IX) THIS IS AN ACCEPTABLE METHOD FOR OVERHEAD SERVICE CONNECTION FOR SURFACE-MOUNTED OR SEMI-FLUSH INSTALLATIONS ONLY.
- (XI) USING SERVICE EQUIPMENT PER FIGURES 1 AND 2
- (f XII) service entrance conductors to be connected to the lugs in the pull can by the contractor.
- (\mathbb{H}) a visible and sealable condulet for surface-mounted and semi-flush installations only is required.

REFERENCE:

- (a) FOR METER CABINET RECESS SPECIFICATIONS, SEE SG508.
- $(\,\mathsf{b}\,)$ FOR METALLIC CONDUIT RISER REQUIREMENTS, SEE SG105.

	© 1998 - 2025 Sa	an Di	ego Gas & El	ectric (Compa	ny. All	rights	reserved. Rer	moval	of th	is copyright no	otice	without permission	is not	permit	ted un	der law	-
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	HAN	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDIT	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D									
		X	Indicates La	atest R	Revisio	n	Con	npletely Revi	ised		New Page		Information Re	moved	j			
	CLIEET				SDC	G&E E	LECTI	RIC SERVIC	E ST/	ANE	DARDS & GL	JIDI	ES					

SHEET 7 OF 7

RESIDENTIAL SELF-CONTAINED SERVICE AND METERING EQUIPMENT 300 - 400A

SCOPE: THE GENERAL TEXT AND ILLUSTRATIONS FOR SAFETY SOCKET CANS AND TEST-BYPASS FACILITIES ARE SHOWN IN THIS STANDARD.




FIGURE 1
TEST-BYPASS FACILITIES FOR SAFETY I
SOCKETS 100 AND 200A, 0-600V
FRONT VIEW

FIGURE 1
TEST-BYPASS FACILITIES FOR SAFETY (I)
SOCKETS 100 AND 200A, 0-600V
SIDE VIEW

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG513.1

TEST-BYPASS FACILITIES FOR SAFETY SOCKETS




FIGURE 2

TEST-BYPASS FACILITIES FOR SAFETY SOCKETS (I) 100 AND 200A, 0-600V BUSSED AND/OR CABLE TERMINATIONS FRONT VIEW

FIGURE 2

TEST-BYPASS FACILITIES FOR SAFETY SOCKETS (I) 100 AND 200A, 0-600V **BUSSED AND/OR CABLE TERMINATIONS** SIDE VIEW

INSTALLATION:

TEST-BYPASS REQUIREMENTS:

- A. BUSSED TEST-BYPASS FACILITIES ARE TO BE FACTORY-INSTALLED FOR INSTALLATIONS OF SAFETY SOCKET CANS UP TO 200A.
- THESE DEVICES ISOLATE THE METER SOCKET FROM THE ELECTRIC SOURCE, AND ARE A SAFETY MEASURE TO PROTECT SDG&E PERSONNEL INVOLVED IN METERING WORK.
- C. ADDITIONALLY, THE DEVICES PERMIT TESTING OR REPLACEMENT OF METERS WITHOUT INTERRUPTING THE CUSTOMER'S ELECTRIC SERVICE. THIS AVOIDS PROBLEMS SUCH AS LOSS OF COMPUTER DATA, RESETTING TIME CONTROLS, LOSS OF PERISHABLE FOOD OR MATERIAL PROCESS, ETC.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV DSN APV DATE **CHANGE** DR DATE **REV CHANGE** DR BY C F В **FORMATTING EDM** JIK 02/07/2025 Ε **EDITORIAL CHANGES** LSM TPM 11/01/2017 Α CTG

SHEET 2 OF 4 **Indicates Latest Revision** Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TEST-BYPASS FACILITIES FOR SAFETY SOCKETS

SG513.2

INSTALLATION (CONT'D):

- D. <u>TEST-BYPASS FACILITIES MUST BE INSTALLED FOR ALL NON-RESIDENTIAL METER INSTALLATIONS.</u> MINIMAL LOADS SUCH AS FIRE ALARMS, LANDSCAPE SPRINKLER, CONTROLS OR SIGN BOARDS ARE NOT EXEMPT FROM THIS REOUIREMENT.
- E. TEST-BYPASS FACILITIES ARE REQUIRED ON TEMPORARY SERVICE FOR CONSTRUCTION POWER TO BUILD RESIDENTIAL SINGLE-FAMILY DWELLINGS AND DUPLEXES, ON SINGLE LOTS OR IN SUBDIVISIONS, WITH SINGLE-PHASE, 120/240V, 200A MAXIMUM.
 - 1. EXCEPTION: RESIDENTIAL METER PANELS ARE ACCEPTABLE FOR TEMPORARY SERVICE IN A PERMANENT BASE (TSPB). (a)
- F. A METER AND SERVICE INSTALLATION TO A GATE FOR A SINGLE-FAMILY RESIDENCE ALSO REQUIRES TEST-BYPASS FACILITIES. THIS ALSO APPLIES TO GATES TO ACCESS GATED COMMUNITIES.
- G. SERVICE USED IN COMMON FOR RESIDENTIAL PURPOSES IN A MULTI-FAMILY DWELLING DEVELOPMENT LOCATED ON A SINGLE PARCEL OF LAND QUALIFIES FOR THE DOMESTIC RESIDENTIAL DR RATE SCHEDULE (SEE SPECIAL CONDITION 8). FOR EXAMPLE, SERVICE TO A RECREATION BUILDING IN A CONDOMINIUM OR APARTMENT COMPLEX. TEST-BYPASS FACILITIES ARE NOT REQUIRED. ALL THREE-PHASE INSTALLATIONS MUST BE EQUIPPED WITH TEST-BYPASS FACILITIES. (b)
- H. THE SAFETY SOCKET METER CAN MAY BE USED AS A COMBINATION PULL AND METER CAN FOR UNDERGROUND SERVICE, EITHER RESIDENTIAL OR COMMERCIAL. (c)
- J. AN AGRICULTURAL WELL USED FOR IRRIGATION ONLY REGARDLESS OF TYPE OF OWNERSHIP MAY BE SERVED ON A GENERAL SERVICE "COMMERCIAL" OR "AGRICULTURAL" RATE SCHEDULE REGARDLESS OF THE PHASE OF SERVICE. THIS EQUIPMENT MUST BE EQUIPPED WITH TEST-BYPASS FACILITIES.
- K. AN INDIVIDUAL PRIVATE DOMESTIC WELL WHICH IS SOLELY-OWNED AND PRIMARILY USED FOR DOMESTIC PURPOSES WILL BE SERVED ON THE A OR PA RATE SCHEDULE. TEST-BYPASS FACILITIES ARE REQUIRED.

BILL OF MATERIALS: NONE

NOTES:

- (I) STRIKE DISTANCE BETWEEN UPPER AND LOWER BUS SECTIONS SHALL NOT BE LESS THAN 1/4-INCH WHEN THE CIRCUIT-CLOSING NUT IS BACKED OFF.
- (II) CIRCUIT-CLOSING NUT SHALL BE A HEX NUT 5/8-INCH ACROSS FLATS WITH PLATED COPPER WASHER ATTACHED AND HAVE THREADS COUNTER-BORED AT BOTTOM TO FACILITATE RE-INSTALLATION. BOLT HEAD SHALL BE SECURED IN PLACE TO PREVENT TURNING AND BACKOUT.
- (III) CIRCUIT-CLOSING NUT AND BOLT ASSEMBLY SHALL MAINTAIN THE APPLIED CONTACT PRESSURE BETWEEN THE PLATED COPPER WASHER AND THE BUS MEMBERS OF THE TEST-BYPASS BLOCK.
- IV INSULATING WASHER SHALL BE MADE FROM DIMENSIONALLY STABLE, NON-TRACKING MATERIAL AND SHALL PROVIDE A MINIMUM OF 1/8-INCH CREEP DISTANCE BETWEEN THE BOLT AND THE BUS SECTIONS. BUS SECTIONS SHALL BE PLATED.
- (V) WIRE STOPS ARE NOT REQUIRED IF LINE AND/OR LOADS ARE CONNECTED WITH BUS BAR. IF CABLE TERMINALS ARE USED, FIGURE 1 CONSTRUCTION REQUIREMENTS SHALL APPLY.
- (VI) RIGID INSULATING BARRIERS SHALL PROJECT AT LEAST 1/4-INCH BEYOND ANY ENERGIZED PARTS WHEN THE MAXIMUM WIRE SIZE IS INSTALLED.
- (VII) TERMINATION OF BUS BAR AND CABLE LINE OR LOAD CONDUCTORS MAY BE CABLE OR BUS. IF BUS AND CABLE TERMINATIONS ARE USED TOGETHER, PROPER LOCATIONS AND ALIGNMENT OF STUD "A" MUST BE MAINTAINED TO FACILITATE THE INSTALLATION OF BYPASS JUMPER.
- $(\! ext{ iny III})$ THE TERMINAL SCREW MAY BE ALLEN TYPE (3/16-INCH ACROSS FLATS FOR 100A, 5/16-INCH ACROSS FLATS FOR 200A).
- (IX) STUD "A" MAY BE LOCATED EITHER ON THE TERMINAL BODY, ON THE BUS MEMBER BETWEEN THE CIRCUIT-CLOSING NUT, AND THE WIRE STOP OR INCORPORATED AS PART OF THE WIRE STOP.
- (XI) FOR SERVICEABILITY PURPOSES, THE LINE AND/OR LOAD BUS IS TO BE CONNECTED TO THE BUS BLOCK MEMBER IN A MANNER WHICH WILL ALLOW READY REPLACEMENT OF THE TEST-BYPASS BLOCK ASSEMBLY.

0.4000 0005 0																	
© 1998 - 2025 Sa	n Di	ego Gas & Ele	ectric C	ompa	ny. All	rights r	eserved. Rer	noval o	of this	s copyright not	ice	without permission	is not	permit	ted und	der law.	
CHANG	GE		DR	BY	DSN	APV	DATE	REV		СН	ΑN	IGE	DR	BY	DSN	APV	DATE
								F									
FORMAT	TING	ì	EDM	JIK	-	-	02/07/2025	Е									
EDITORIAL C	HAN	IGES	-	LSM	CTG	TPM	11/01/2017	D									
	X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Rei	noved				
CUEET				SDG	&E E	LECTI	RIC SERVIC	E STA	AND	ARDS & GUI	DE	ES					
		•								•					S	G51	3.3
3 OF 4			TFS	T-BY	PAS	S FA	ACII ITIF	S FC	OR S	SAFFTY S	SO	CKFTS			Ŭ	001	3.3
	FORMAT EDITORIAL C	FORMATTING EDITORIAL CHAN	FORMATTING EDITORIAL CHANGES X Indicates La	FORMATTING EDM EDITORIAL CHANGES - X Indicates Latest R	FORMATTING EDM JIK EDITORIAL CHANGES - LSM X Indicates Latest Revision SHEET	CHANGE DR BY DSN FORMATTING EDM JIK - EDITORIAL CHANGES - LSM CTG X Indicates Latest Revision SDG&E E	FORMATTING EDM JIK EDITORIAL CHANGES - LSM CTG TPM X Indicates Latest Revision Con SDG&E ELECTE	CHANGE DR BY DSN APV DATE FORMATTING EDM JIK 02/07/2025 EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 X Indicates Latest Revision Completely Revision SDG&E ELECTRIC SERVICE COLUMN 1	CHANGE DR BY DSN APV DATE REV F FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised SDG&E ELECTRIC SERVICE STA	CHANGE DR BY DSN APV DATE REV FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised SDG&E ELECTRIC SERVICE STAND	CHANGE DR BY DSN APV DATE REV CH FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUI	CHANGE DR BY DSN APV DATE REV CHAN FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDE SHEET	CHANGE DR BY DSN APV DATE REV CHANGE FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Rer SDG&E ELECTRIC SERVICE STANDARDS & GUIDES	CHANGE DR BY DSN APV DATE REV CHANGE DR FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES	CHANGE DR BY DSN APV DATE REV CHANGE DR BY FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES	CHANGE DR BY DSN APV DATE REV CHANGE DR BY DSN FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES	FORMATTING EDM JIK 02/07/2025 E EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D X Indicates Latest Revision Completely Revised New Page Information Removed SHEET SOF 4 SG51:

NOTES (CONT'D):

- (XII) #12-24 STUD SECURED TO BUS AND HEX NUT 1/2-INCH ACROSS FLATS
- (XIII) STUD "A" #12-24 WITH HEX NUT 1/2-INCH ACROSS FLATS
- (XIV) WIRE STOPS SHALL EXTEND TO CENTER OF TERMINAL OPENING OR BEYOND.
- (XV) TERMINALS SHALL BE ALUMINUM BODIED. THE OPENING SHALL EXTEND THROUGH THE TERMINAL BODY AND, IF WIRE HOLE IS ROUND, SHALL BE CHAMFERED AS NECESSARY TO FACILITATE INSTALLATION OF THE LARGEST SIZE WIRE. (d)
- (XVI) #12-24 STUD AND HEX NUT 1/2-INCH ACROSS FLATS

REFERENCE:

- (a) SEE SG210.
- (b) SEE DOMESTIC RESIDENTIAL DR RATE SCHEDULE, SPECIAL CONDITION 8.
- (c) for Details, see SG514.
- (d) FOR REQUIRED CONDUCTOR RANGE, SEE SG514.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 4 OF 4 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page


Information Removed


Completely Revised

TEST-BYPASS FACILITIES FOR SAFETY SOCKETS

SG513.4

SCOPE: THIS STANDARD PROVIDES INFORMATION ON REQUIREMENTS FOR INSTALLATION OF SAFETY SOCKET METER CANS.








FIGURE 1

SAFETY SOCKET CAN WITH FACTORY-INSTALLED TEST-BYPASS FACILITIES 100A (STANDARD DUTY) FRONT VIEW LOWER COVER REMOVED




FIGURE 1

SAFETY SOCKET CAN WITH FACTORY-INSTALLED TEST-BYPASS FACILITIES 100A (STANDARD DUTY) SIDE VIEW

(V)(VIII)(IX)(XII)(XIII)

FIGURE 1

SAFETY SOCKET CAN WITH FACTORY-INSTALLED TEST-BYPASS FACILITIES 100A (STANDARD DUTY) BOTTOM VIEW

(V) (VIII) (IX) (XII) (XIII)


© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 6 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SAFETY SOCKET METER CANS








FIGURE 2

SAFETY SOCKET CAN WITH FACTORY-INSTALLED TEST-BYPASS FACILITIES 200A (HEAVY DUTY) FRONT VIEW LOWER COVER REMOVED

(VIII)(IX)(XII)(XIII)

FIGURE 2

SAFETY SOCKET CAN WITH FACTORY-INSTALLED TEST-BYPASS FACILITIES 200A (HEAVY DUTY) SIDE VIEW

(VIII)(IX)(XII)(XIII)

FIGURE 2

SAFETY SOCKET CAN WITH FACTORY-INSTALLED TEST-BYPASS FACILITIES 200A (HEAVY DUTY) BOTTOM VIEW

(VIII)(XXXXII)(XIII)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 6


Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SAFETY SOCKET METER CANS




EXAMPLE 1 SIX METERS AND SWITCHES OR LESS



EXAMPLE 2 SIX METERS AND SWITCHES OR LESS



EXAMPLE 3
SELF CONTAINED METERS



EXAMPLE 4
MORE THAN SIX METERS AND SWITCHES

FIGURE 3 TYPICAL MULTIPLE SAFETY SOCKET CAN GROUPING ARRANGEMENTS FOR COMMERCIAL INSTALLATIONS WITH SELF-CONTAINED METERS

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


C										
C							F			
В	FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е			
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D			


SHEET 3 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDOCE ELECTRIC SERVICE STANDARDS & GOIDES

SAFETY SOCKET METER CANS






EXAMPLE 1 NORMAL UG SERVICE CONNECTION FOR STANDARD SAFETY SOCKET METER CAN POST-MOUNTED

EXAMPLE 2 ALTERNATE METHOD FOR UG SERVICE CONNECTION WALL-MOUNTED

EXAMPLE 3 ALTERNATE METHOD FOR UG SERVICE CONNECTION WALL-MOUNTED



EXAMPLE 4 LOAD DISCONNECTS

TABLE 1

SAFET	Y SOCKET METER CAN DESCRIPTION LIST
ITEM	DESCRIPTION
1	MAIN AND LOAD CENTER
2	TEST-BYPASS FACILITIES AREA
3	MAIN BELOW SAFETY SOCKET METER CAN
4	SEALABLE CONDULET
(5)	OPTIONAL
6	MAIN
7	UNDERGROUND PULL CAN
8	METERING SECTION
9	PULL SECTION

FIGURE 4 SAFETY SOCKET METER CAN USED FOR UNDERGROUND SERVICE (D) E (MIII) SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	IWA	JTM	KRG	02/07/2025	Е						
A	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D			·			

SHEET 4 OF 6 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SAFETY SOCKET METER CANS

INSTALLATION:

- (A) WIRING OF SAFETY SOCKET METER CANS:
 - SERVICE ENTRANCE AND <u>LOAD CONDUCTORS INSTALLED IN SEPARATE RACEWAYS</u> MAY ENTER OR EXIT THE SAFETY SOCKET METER CAN AT EITHER THE TOP, BOTTOM, SIDE OR REAR. THE ELECTRICAL CONTRACTOR SHALL CONNECT THOSE CONDUCTORS TO THE FACTORY-INSTALLED TEST-BYPASS FACILITIES.
 - NO CONNECTIONS MAY BE MADE IN A SAFETY SOCKET METER CAN TO SUPPLY ANY OTHER METER, AND NOT MORE THAN ONE LOAD CIRCUIT MAY LEAVE THE CAN.
 - 3. IN MULTI-METER INSTALLATIONS OF SAFETY SOCKET METER CANS, A MAIN SWITCH OR BREAKER CAN ONLY BE INSTALLED ON THE SUPPLY SIDE OF TWO OR MORE METERS, EXCEPT WHEN REQUIRED BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ).
 - 4. WHEN USED TO TERMINATE SDG&E (UTILITY) SERVICE LATERAL CONDUCTORS, THE SERVICE CONDUIT SHALL ENTER THE BOTTOM OF THE CAN. THE LOAD CONDUCTORS MAY NOT EXIT THE REAR OF THE CAN BEHIND THE TEST-BYPASS FACILITIES.
 - 5. THE UTILITY WILL NOT SUPPLY 2-WIRE, 120V SERVICE OR METERING WITHOUT APPROVAL FROM SERVICE STANDARDS. SINGLE-PHASE SERVICE WILL BE 3-WIRE REGARDLESS OF THE VOLTAGE, I.E. 120/208V OR 120/240V. (a)

B. NEUTRAL OR GROUND CONDUCTOR IN SAFETY SOCKET METER CANS:

- 1. THE NEUTRAL SERVICE ENTRANCE CONDUCTOR FOR A SELF-CONTAINED METER SHALL CONNECT IN THE SAFETY SOCKET METER CAN AND MAY BE CONTINUOUS.
- 2. ON OVERHEAD SERVICE INSTALLATIONS THE SERVICE GROUND CONDUCTOR, PROVIDED AS THE REDUNDANT FOURTH WIRE CORNER-GROUND CONDUCTOR OF A 480V DELTA SERVICE, WILL BE CONNECTED TO THE CUSTOMER'S IDENTIFIED EQUIPMENT GROUNDING CONDUCTOR AT THE POINT OF SERVICE CONNECTION (DRIP LOOP). THE CUSTOMER SHALL IDENTIFY B-PHASE RED IN COLOR. (b)

C. ALUMINUM CONDUCTORS IN SAFETY SOCKET METER CANS:

- 1. TEST-BYPASS FACILITIES WITH ALUMINUM BODIED LUGS WILL BE PROVIDED AND INSTALLED BY THE MANUFACTURER. THE CONTRACTOR WILL MAKE THE CONNECTIONS TO THE BYPASS FACILITIES, UNLESS THE EQUIPMENT IS USED AS A PULL CAN, IN WHICH CASE THE UTILITY WILL TERMINATE THEIR SERVICE LATERAL CONDUCTORS TO THE LINE SIDE LUG OF EACH TEST BLOCK.
- 2. CUSTOMER MAXIMUM CONDUCTOR SIZES IN ALUMINUM SHALL NOT EXCEED 1/0 AWG FOR USE IN THE STANDARD DUTY CAN AND 250 MCM IN THE HEAVY DUTY CAN. THE UTILITY MAY USE A MAXIMUM 3/0 AWG IN A STANDARD DUTY CAN AND 350 MCM IN THE HEAVY DUTY CAN USING PIN ADAPTERS.
- 3. THE USE OF A JOINT COMPOUND OR OXIDATION INHIBITOR IS RECOMMENDED FOR ALL ALUMINUM CONNECTIONS. HOWEVER, THE USE OF OXIDATION INHIBITORS IS NO SUBSTITUTE TO HAVING AN APPROVED ALUMINUM WIRE TERMINAL.
- D THE SAFETY SOCKET METER CAN MUST BE SECURELY MOUNTED ON A 3-INCH MINIMUM RIGID METAL PIPE OR 4" X 4" TREATED WOOD POST. THE PIPE OR POST MUST BE FIRMLY SET. THE UNDERGROUND CONDUIT MAY NOT BE UTILIZED AS THE SUPPORT.
- (E) THE SAFETY SOCKET METER CAN MAY BE USED AS A COMBINATION SERVICE TERMINATING PULL AND METER CAN FOR AN UNDERGROUND SERVICE, EITHER RESIDENTIAL OR COMMERCIAL/INDUSTRIAL. THE UNDERGROUND SERVICE RISER SHALL ENTER THE BOTTOM OF THE CAN AS SHOWN IN FIGURE 4, EXAMPLE 1.(A)

BILL OF MATERIALS: NONE

NOTES:

- I ALUMINUM BODIED TERMINALS FOR NO. 6 THROUGH 1/0 MCM CU-AL WIRE. THE UTILITY MAY INSTALL A MAXIMUM 3/0 WIRE USING PIN ADAPTERS.
- (II) HUBS CAPPED OFF IF USED FOR UNDERGROUND FEED.
- (III) RIGID INSULATING BARRIERS (d)

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights ı	reserved. Rer	moval	of th	is copyright no	otice	without permission	is not	permit	ted und	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	IAH	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMAT	TING	3	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Ren	noved				
					CDC	`0. E E	LECTI	OIC CEDVIC	T CT	V VII	VDDC 8. CI	IID	EC					

SHEET 5 OF 6 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SAFETY SOCKET METER CANS

NOTES (CONT'D):

- $\overline{ ext{(IV)}}$ VERTICAL LAY-IN, DOUBLE NEUTRAL LUG WITH 1/0 MCM CU-AL WIRE CAPACITY, MOUNTED ON EITHER SIDEWALL.
- (V) TEST-BYPASS BLOCKS SHALL BE BUSSED OR WIRED TO SOCKET JAWS OR TERMINALS. (b)
- (VI) UPPER TEST CONNECTOR STUDS
- (VII) ALL COVERS SHALL BE INDEPENDENTLY REMOVABLE. UPPER COVER SHALL BE NON-REMOVABLE WHEN METER IS IN PLACE. METER SOCKET SHALL BE MOUNTED ON SUPPORT AND ATTACHED TO PANEL. LOWER COVER SHALL BE SEALABLE AND PERMANENTLY LABELED: "DO NOT BREAK SEALS. NO FUSES INSIDE." (e)
- (VIII) for 3-phase, 4-wire, connect seventh Jaw to Body of Neutral Lug With No. 12 copper wire, white in Color.
- (IX) FOR 3-PHASE, 4-WIRE DELTA, IDENTIFY RIGHT HAND TEST-BYPASS BLOCK (2 POLES) AS POWER LEG, ORANGE IN COLOR (C-PHASE).
- (XI) FOR 3-PHASE, 3-WIRE, INSTALL BUS TO CONNECT LINE AND LOAD POLES TOGETHER AT TOP OF CENTER TEST-BYPASS BLOCK AND CONNECT FIFTH JAW TO THIS BUS USING NO. 12 WIRE, RED IN COLOR.
- (XII) FOR SINGLE-PHASE, 3-WIRE, PROVIDE TWO TEST-BYPASS BLOCKS MOUNTED IN THE OUTER POSITIONS AND A 4-JAW SOCKET.
- FOR SINGLE-PHASE, 3-WIRE, 120/208V, PROVIDE TWO TEST-BYPASS BLOCKS MOUNTED IN THE OUTER POSITIONS AND A 5-JAW SOCKET. CONNECT FIFTH JAW OF METER SOCKET TO BODY OF NEUTRAL LUG WITH NO. 12 COPPER WIRE, WHITE IN COLOR.
- (XIV) PERMANENT LABELS ON INSIDE BACK OF ENCLOSURE IN 3/4-INCH (MINIMUM) HIGH BLOCK LETTERS
- (XV) ALTERNATE NEUTRAL LUG POSITION
- (WI) ALUMINUM BODIED TERMINALS FOR 1/0 THROUGH 250 MCM CU-AL WIRE. THE UTILITY MAY INSTALL A MAXIMUM 350 WIRE USING PIN ADAPTERS.
- (MI) MAIN SERVICE DISCONNECTING MEANS MAY BE REQUIRED PER CODE.
- (MIII) GANGED INSTALLATION OF SAFETY SOCKET METER CANS. MAIN AHEAD OF SEVEN OR MORE METER SERVICE DISCONNECTS IS REQUIRED PER CODE.

REFERENCE:

- (a) SEE CHARACTER OF SERVICE ON SG004.
- (b) SEE SG516<mark>: METER TYPE AND SOCKET CLIP ARRANGEMENT.</mark>
- c. SEE UG4173
- (d) SEE SG513<mark>: TEST-BYPASS FACILITIES FOR SAFETY SOCKETS.</mark>
- (e) FOR SEALING REQUIREMENTS, SEE SG503.

	© 1998 - 2025 Sa	an Di	iego Gas & Ele	ectric C	Compa	ny. All	rights ı	reserved. Rer	moval o	of th	nis copyright no	tice	without permission	is not	permit	ted und	der law.	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		Cl	IAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMAT	TINC	3	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	NGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Re	moved				
	CHEET				SDC	G&E E	LECTI	RIC SERVIC	E STA	ANE	DARDS & GU	ID	ES					

SHEET 6 OF 6

SCOPE: THIS STANDARD PROVIDES GENERAL INFORMATION ON REQUIREMENTS FOR INSTALLATION OF TRANSFORMER RATED METERS, AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT.

INSTALLATION:

A. TRANSFORMER RATED METERS:

- 1. WHEN THE ELECTRICAL SUPPLY NEEDS OF THE CUSTOMER EXCEEDS THE 200A CAPACITY OF THE SELF-CONTAINED METER AND ITS HEAVY DUTY SOCKET, CURRENT TRANSFORMERS (CTS), WHICH CONNECT TO THE SERVICE ENTRANCE CONDUCTORS, MUST BE USED. A TRANSFORMER RATED METER IS INSTALLED TO MEASURE THE ENERGY DELIVERED TO THE CUSTOMER. A CT CAPACITY MULTIPLIER IS APPLIED TO THE BILLING REGISTER ON THE METER. BOTH THE CTS AND THE METER ARE FURNISHED AND INSTALLED BY SDG&E (UTILITY).
- 2. THE TRANSFORMER RATED METER, WHEN INSERTED IN ITS SOCKET, IS WIRED TO THE CT. THE CTS MUST BE LOCATED BEHIND THE METER AND TEST SWITCH PANEL COVER(S). CUSTOMER-OWNED EQUIPMENT AND WIRING IS NOT ALLOWED WITHIN THE UTILITY-SEALED CT AND METERING COMPARTMENT.
- 3. THE CUSTOMER FURNISHES AND INSTALLS AN APPROVED CT ENCLOSURE AND METER SOCKET. (a)

B. SOCKETS FOR TRANSFORMER RATED METERS:

A CT RATED SOCKET IS USED WITH TRANSFORMER RATED METERS. THE SOCKET IS FURNISHED AND INSTALLED BY THE CUSTOMER. THE UTILITY WILL FURNISH, INSTALL, OWN AND MAINTAIN THE NECESSARY INSTRUMENT TRANSFORMERS, TEST FACILITIES AND METERS.

C. COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN - OVERHEAD SERVICE:

- 1. WHEN THE ELECTRIC SERVICE IS 201–800A, A COMBINATION CAN, SHOWN ON SHEET 5, IS ONE TYPE OF APPROVED ENCLOSURE WHICH THE CUSTOMER MAY FURNISH TO HOUSE AND SUPPORT THE CTS AND METER. IN THIS CASE, A CT MOUNTING BASE, WITH AMPERAGE CAPACITY OF 400A, IS ALSO FURNISHED. THE SERVICE ENTRANCE CONDUCTORS ARE CONNECTED TO THE CT MOUNTING BASE BY THE CONTRACTOR.
- 2. NO CONNECTIONS SHALL BE MADE IN THE CT CAN TO SUPPLY ANY OTHER METER.

D. COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN – UNDERGROUND SERVICE:

- 1. WHEN THE ELECTRIC SERVICE IS RATED 201–800A, A COMBINATION CAN, SHOWN ON SHEET 5, MAY BE USED FOR RESIDENTIAL OR COMMERCIAL SERVICE.
- 2. NO CONNECTIONS SHALL BE MADE IN THE CT CAN TO SUPPLY ANY OTHER METER.
- 3. THE CONTRACTOR SHALL FURNISH AND INSTALL A CT MOUNTING BASE AND CONDUCTORS OF THE PROPER TYPE AND SHALL CONNECT THE CONDUCTORS FROM THE TERMINATION SECTION OF THE CT MOUNTING BASE.
- 4. SEE SHEET 8 FOR 400-800A, THREE-PHASE, 4-WIRE, WALL-MOUNTED UNDERGROUND PULL CAN WITH CT, METER SOCKET AND MAIN DISCONNECT(S) IN ADJACENT SECTION.

F. METER SERVICE DISCONNECT:

ALL METER SERVICE DISCONNECTS ON TRANSFORMER RATED METER INSTALLATIONS SHALL HAVE A PROVISION FOR LOCKING IN THE OPEN/OFF POSITION AND SHALL BE IMMEDIATELY ADJACENT TO THE METER PANEL.

BILL OF MATERIALS: NONE

NOTES: NONE REFERENCE:

(a) FOR SPECIAL 400A RESIDENTIAL INSTALLATION, SEE SG512.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	HAN	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDIT	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R	Revisio	n	Con	npletely Revi	ised		New Page		Information Re	moved	ı			
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	

SHEET 1 OF 9

TRANSFORMER RATED METERS AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT GENERAL INFORMATION

SG515.1

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR CURRENT TRANSFORMER MOUNTING BASES FOR INSTALLATION IN CURRENT TRANSFORMER ENCLOSURES. (1A)(III) 1 3/8" 0 7/8" Ν 8 1/8" 1 1/2"- $\langle 2 \rangle$ Q C.T. 0 1 3/8" (3A 8" MIN. 2" MIN. (I)(4)2 1/2" MAX. $\langle 5 \rangle$ 3 5/16" **FIGURE 1** CURRENT TRANSFORMER MOUNTING BASE FOR INSTALLATION IN CURRENT TRANSFORMER ENCLOSURE 0-400A MAXIMUM, 0-600V, SINGLE-PHASE, THREE-WIRE SERVICE SEE TABLE 1 2025 San Diego Gas & Flectric Company. All rights reserved. Removal of this convright notice without permission is not permitted under law

	© 1998 – 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permit													milieu unuer law.				
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CH	IAN	GE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL C	CHAN	IGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R				npletely Revi			New Page	IIDF	Information Re	moved	ı			
	SHEET 2 OF 9		TR		FOR SE	MER RVI(R RA		TERS ERIN	S AN NG E	ID WALI	L-N EN	10UNTED T			S	G51	5.2




FIGURE 2

CURRENT TRANSFORMER MOUNTING BASE FOR INSTALLATION IN CURRENT TRANSFORMER ENCLOSURE 201-800A MAXIMUM, 0-600V, THREE-PHASE, THREE-WIRE OR FOUR-WIRE, WYE OR DELTA CONNECTED-SERVICE SEE TABLE 1

TABLE 1

	CUR	RENT TRANSFORMER MOUNTING BASE DESCRIPTION LIST
ITEM		DESCRIPTION
<u></u>	Α	2 C.T. MOUNTING BOLTS, 4 PLACES (TYP.)
<u>\(1\)</u>	В	2 C.T. MOUNTING BOLTS, 6 PLACES (TYP.)
2	10-	32 MACHINE SCREW AND WASHER DRILLED AND TAPPED INTO BUS
(3)	Α	BUS MARKING "C.T.". 4 LOCATIONS (TYP.)
(3)	В	BUS MARKING "C.T.". 6 LOCATIONS (TYP.)
4	INS	SULATING SUPPORTS
(5)	INS	SULATING BARRIER

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 3 OF 9

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TRANSFORMER RATED METERS AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT CURRENT TRANSFORMER MOUNTING BASE

SG515.3

INSTALLATION: NONE
BILL OF MATERIALS: NONE
NOTES:
I MOUNTING BASE ACCEPTS BAR TYPE CTS ONLY.
II. TWO 1/2-INCH STEEL BOLTS SHALL BE PROVIDED FOR EACH CT MOUNTING POSITION. EACH BOLT SHALL BE SECURED IN PLACE AND FURNISHED WITH A SPRING WASHER AND A NUT. THE SPRING WASHERS MAY BE EITHER A CONE-TYPE (BELLEVILLE) OR A SPLIT-RING WASHER AND A FLAT WASHER. ALL PARTS SHALL BE PLATED TO PREVENT CORROSION.
(III) TERMINATIONS FOR SERVICE CONDUCTORS SHALL BE THREE-POSITION, ALUMINUM-BODIED MECHANICAL LUGS WITH A RANGE ACCEPTING ONE 4 AWG THROUGH 500 KCMIL CONDUCTOR.
IV. FOR APPLICATIONS, SEE SHEETS 5–9.
V CT CENTER PHASE POSITION SHALL BE BUSSED STRAIGHT THROUGH FOR 3-PHASE, 3-WIRE, SERVICE VOLTAGE INSTALLATIONS.
REFERENCE: NONE
© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CH.	AN	GE	DR	BY	DSN	APV	DATE
С							F								
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D								
	X Indicates La	itest R	evision	1	Con	npletely Revi	sed	New Page		Information Re	moved				

SHEET 4 OF 9 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TRANSFORMER RATED METERS AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT CURRENT TRANSFORMER MOUNTING BASE

SG515.4

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR COMBINATION CURRENT TRANSFORMER AND METER SOCKET CANS.





FIGURE 1

COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN FOR
RESIDENTIAL OR COMMERCIAL/INDUSTRIAL USE – OVERHEAD SERVICE ONLY A B C D

SEE TABLES 1 AND 2



COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN
0-600V MAXIMUM, RESIDENTIAL OR COMMERCIAL/INDUSTRIAL USE – UNDERGROUND SERVICE ONLY VIII)
SEE TABLES 1 AND 2

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 5 OF 9

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TRANSFORMER RATED METERS AND WALL-MOUNTED

SERVICE AND METERING EQUIPMENT COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN

SG515.5

1/8"

3 1/2" MAX.

-3 1/2" MAX.

TABLE 1

MINIMUM BOX DIMENSIO	ONS
CONFIGURATION	Z (IN)
3Ø 3-WIRE	
4-WIRE Δ	36
Y	
1Ø	24

TABLE 2

	CT AND METER SOCKET CAN DESCRIPTION LIST
ITEM	DESCRIPTION
1	SEALABLE STUDS (4 PLACES)
2	REMOVABLE TEST PERCH
3	TRANSFORMER MOUNTING BASE FURNISHED AND INSTALLED BY CUSTOMER
4	HANDLES

INSTALLATION:

- (A) SERVICE ENTRANCE CONDUCTORS MUST ENTER ABOVE THE TEST PERCH. LOAD CONDUCTORS MUST EXIT BELOW THE CT MOUNTING BASE. THE CAN MUST BE INSTALLED IN VERTICAL POSITION AS SHOWN.
- B) ON OVERHEAD 3-PHASE, 3-WIRE DELTA SERVICES, THE REDUNDANT GROUND CONDUCTOR, MARKED GREEN, OR GREEN WITH YELLOW STRIPES IN COLOR, SHALL PASS THROUGH THE CT CAN, BE CONTINUOUS AND GROUNDED TO THE CAN.
- © GROUNDING MAY BE ACCOMPLISHED WITH A NO. 8 MINIMUM TAP FROM THE NEUTRAL OR BY REMOVING THE CONDUCTOR INSULATION AND CONNECTING THE CONDUCTOR DIRECTLY TO A LAY-IN GROUNDING LUG IN THE CAN.
- (D) PROVIDE A GROUND CONDUCTOR TERMINATION AT THE SERVICE TERMINATION POINT. A BONDING LUG SHALL BE PROVIDED FOR A MINIMUM 1/0 AWG BONDING CONDUCTOR. A JUMPER SHALL BE PROVIDED FOR CONNECTION TO THE NEUTRAL OR GROUNDED SERVICE TERMINATION LUG.

BILL OF MATERIALS: NONE

NOTES:

- I. MAXIMUM AMPERE CAPACITY:
 - a. 400A FOR SINGLE-PHASE COMMERCIAL
 - b. 600A FOR SINGLE-PHASE RESIDENTIAL
 - c. 800A FOR THREE-PHASE RESIDENTIAL OR COMMERCIAL
- (II) NO CONDUCTORS PERMITTED IN THE SHADED AREA.
- (III) REMOVABLE TEST SWITCH PERCH SHALL BE DRILLED, TAPPED AND INSTALLED ON THE TOP POSITION. (b)
- (IV) TRANSFORMER MOUNTING BASE COVER SHALL HAVE TWO LIFTING HANDLES, BE A MAXIMUM OF 9 SQUARE FEET, AND HAVE A CAUTION SIGN READING:

"DO NOT BREAK SEALS. NO FUSES INSIDE."

- $(\,\mathsf{V}\,)$ PROVISION SHALL BE MADE FOR BONDING THE NEUTRAL TO THE ENCLOSURE.
- (VI) ALL SECURING SCREWS SHALL BE CAPTIVE. ALL PANELS AND COVERS SHALL BE SEALABLE.
- (VII) PROVISION SHALL BE MADE IN THE CT COMPARTMENT FOR A MECHANICAL LUG BONDABLE TERMINATION OF THE SERVING UTILITY'S NEUTRAL. THIS TERMINATION MAY BE INSTALLED ON THE CT MOUNTING BASE AS SHOWN ON SHEETS 2, 3, AND 4.
- THE MINIMUM DISTANCE TO THE LOWEST MECHANICAL LUG IS 22 INCHES. THE HEIGHT OF THE NEUTRAL TERMINATION LUG MAY BE REDUCED TO 20-INCH MINIMUM.
- (IX) the underground service conduit shall enter the bottom of the can.
- (XI) LOAD CONDUCTORS MUST EXIT ABOVE THE CT MOUNTING BASE AND TEST PERCH.
- (XII) SHADED AREA IS FOR UTILITY SERVICE LATERAL CONDUCTORS ONLY.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 6 OF 9

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TRANSFORMER RATED METERS AND WALL-MOUNTED
SERVICE AND METERING EQUIPMENT
COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN

SG515.6

REFERENCE: (a) FOR SIZE AND NUMBER OF CONDUITS, SEE SG309. (b) SEE SG517 (c) FOR METER HEIGHT REQUIREMENTS, SEE SG504. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV DR BY DSN APV DATE CHANGE DATE **REV CHANGE** С F Ε В FORMATTING/EDITORIAL CHANGES EDM | IWA | JTM | KRG |02/07/2025 LSM CTG TPM 11/01/2017 **EDITORIAL CHANGES** Α **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG515.7 TRANSFORMER RATED METERS AND WALL-MOUNTED 7 OF 9 SERVICE AND METERING EQUIPMENT

COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR WALL-MOUNTED UNDERGROUND PULL CANS EQUIPPED WITH MECHANICAL LUGS THAT HAVE A CURRENT TRANSFORMER COMPARTMENT, METER SOCKET AND MAIN DISCONNECT IN AN ADJACENT SECTION.




FIGURE 1

WALL-MOUNTED UNDERGROUND PULL CAN EQUIPPED WITH MECHANICAL LUGS WITH CURRENT TRANSFORMER COMPARTMENT, METER SOCKET AND MAIN DISCONNECT(S) IN ADJACENT SECTION 0-600V, 400-800A MAXIMUM, 3-PHASE, 4-WIRE SERVICE

SEE TABLE 1

TABLE 1

WA	LL-MOUNTED UNDERGROUND PULL CAN DESCRIPTION LIST
ITEM	DESCRIPTION
1	SERVICE CONDUIT AREA
2	WALL-MOUNTED
3	METER DOOR
4	400-800A C.T. COMPARTMENT
(5)	CIRCUIT BREAKERS OR T-FUSEABLE PULLOUTS
6	PULL CAN

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
B F	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 8 OF 9 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

TRANSFORMER RATED METERS AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT WALL-MOUNTED UNDERGROUND PULL CAN

SG515.8

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. SERVICE LATERAL CONDUITS, FIRMLY SECURED WITH LOCKNUT, HUB OR BUSHING, MUST ENTER BOTTOM OF PULL CAN. MAXIMUM CONDUIT INTRUSION INSIDE CAN IS 1-INCH. LOAD CONDUITS MUST EXIT ABOVE SHADED AREA.
- II. BONDING CONNECTION FOR SERVICE LATERAL CONDUITS ONLY IS PERMITTED AT BOTTOM OF CAN. ANY OTHER BONDING OR GROUNDING CONNECTION MUST BE MADE ABOVE THE SHADED AREA AND NO GROUNDING OR BONDING CONDUCTOR IS PERMITTED TO PASS THROUGH SHADED AREA.
- III. REMOVABLE TEST SWITCH PERCH SHALL BE DRILLED AND TAPPED. (a)
- IV. CT COMPARTMENT COVER SHALL HAVE TWO LIFTING HANDLES, BE A MAXIMUM OF 9 SQUARE FEET, AND A CAUTION SIGN READING:

"DO NOT BREAK SEALS, NO FUSES INSIDE."

- V. ALL SECURING SCREWS SHALL BE CAPTIVE. ALL PANELS AND COVERS SHALL BE SEALABLE.
- VI. FOR TRANSFORMER BASE DETAILS, SEE SHEET 3.
- VII. THE MINIMUM DISTANCE FROM BASE OF PULL CAN TO THE LOWEST MECHANICAL LUG IS 26 INCHES.
- VIII. FOR ADDITIONAL TRANSFORMER RATED METERING INFORMATION, SEE SHEET 1.
- (IX) SHADED AREA IS FOR UTILITY SERVICE LATERAL CONDUCTORS ONLY.

REFERENCE:

- (a) SEE SG517
- (b) FOR METER HEIGHT REQUIREMENTS, SEE SG504.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under l															der law	'.	
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CH	AN	GE	DR	BY	DSN	APV	DATE
С								F									
В	FORMATTING/EDIT	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHANGES	-	LSM	CTG	TPM	11/01/2017	D									
		atest R	test Revision Completely Revised New Page Information Removed									I					
	CLIEET	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															

SHEET 9 OF 9

TRANSFORMER RATED METERS AND WALL-MOUNTED SERVICE AND METERING EQUIPMENT WALL-MOUNTED UNDERGROUND PULL CAN

SG515.9

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR METER TYPE AND SOCKET CLIP ARRANGEMENT.

ATTENTION:

* THE METER TYPE AND NUMBER OF SOCKET CLIPS AND THEIR ARRANGEMENT VARIES WITH THE PHASE AND VOLTAGE OF SERVICE SUPPLIED TO THE CUSTOMER. TABLES 2 AND 3 LIST THE REQUIREMENTS.

TABLE 1

	ABBREVIATION LIST
S	SOCKET METER
N	NETWORK 120/208 METER
Р	POLY PHASE AUTORANGING 120-480

TABLE 2

SELF-CONTAINED METER													
TYPE OF SERVICE	METER FORMS	SOCKET (AMPS)	METER CLIPS	SMART METER TYPE									
1 PHASE 2 WIRE 120V (IV)	1S CL200		4	C2SODL1									
1 PHASE 3 WIRE 120/208V (a)	12S NETWORK CL200	200 OR LESS	5	CN2SODL12									
1 PHASE 3 WIRE 120/240V	2S CL200			C2SODL2									
1 PHASE 3 WIRE 120/240V	2S CL320	400	4	C2SOL2E									
1 PHASE 3 WIRE 240/480V	2S CL200			CP2SOL2									
3 PHASE 4 WIRE 120/208V WYE													
3 PHASE 4 WIRE 120/240 DELTA	16S CL200		7	CP1SOL16									
3 PHASE 4 WIRE 277/480V WYE		200 OR LESS											
3 PHASE 3 WIRE (4TH WIRE GROUNDING CONDUCTOR REQUIRED) 240 VOLT CORNER GRD (II) (IV) 480 CORNER GRD (II) (V)	12S CL200		5	CP1SOL12									

TABLE 3

CURRENT TRANSFORMER RATED METER												
TYPE OF SERVICE	METER FORMS	METER CLIPS I	SMART METER TYPE									
1 PHASE 3 WIRE 120/240V	4S	6	C2SOL4									
3 PHASE 4 WIRE 120/208V WYE												
3 PHASE 4 WIRE 120/240 DELTA	9S		CP1SAL9									
3 PHASE 4 WIRE 277/480V WYE												
3 PHASE 3 WIRE (4TH WIRE GROUNDING CONDUCTOR REQUIRED) 240 VOLT CORNER GRD (II) (IV) 480 CORNER GRD (II) (V)	5S	15	CP1SAL5									
3 PHASE 3 WIRE 12KV												
3 PHASE 4 WIRE 12KV	9S		CP1SAL9									

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/NOTES UPDATE	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
												· ·	

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

METER TYPE AND SOCKET CLIP ARRANGEMENT

SG516.1









7 CLIP



8 CLIP



15 CLIP

FIGURE 1

TABLE 4

		CLIPS FO	R METER TYPES			
ТҮРЕ	4 CLIP	5 CLIP SELF-CONTAINED METERS	6 CLIP TRANS RATED METERS	7 CLIP	8 CLIP	15 CLIP
APPLICABLE TO SMART METER TYPES	C2SOL1 C2SODL1 C2SOL2 C2SODL2 C2SOL2E	CNSOL12 CNSODL12 CPSOL12	C2SOL4	CP1SOL16	-	CP1SAL9 CP1SAL5 CP1SOL9 CP1SOL5 CP2SAZ9

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- $(\hspace{1mm} \mathrm{I}\hspace{1mm})$ all meter socket terminal clips must be back connected, except ${ t combination}$ current transformer and meter SOCKET CANS. (b)
- (II) 4TH WIRE (REDUNDANT GROUNDING CONDUCTOR ONLY NOT A NEUTRAL), DELTA-CONNECTED WITH "B" PHASE
- (III) THE REQUIRED POSITION OF THE 5TH CLIP FOR SELF-CONTAINED METER SOCKETS IS 9 O'CLOCK (270 DEGREES).
- (IV) NOT ACCEPTABLE FOR NEW INSTALLATIONS OR OLD SETS, OR FOR ANY VACANT EXISTING SINGLE-PHASE, 2-WIRE 120V METER BASES; FIELD MAINTENANCE ONLY
- (V) only applicable when FED from an overhead transformer station
- VI. EFFECTIVE WITH SMART METER IMPLEMENTATION, FORM 16 METERS WILL ALSO REPLACE ALL FORM 14S AND 15S.
- (VII) NOT FOR NEW INSTALLATIONS. NO LONGER AN ACCEPTABLE METER USE.

REFERENCE:

- a) FOR MULTI-FAMILY RESIDENTIAL REQUIREMENT FOR SINGLE-PHASE METERING, SEE SG004.
- (b) SEE SG515.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/NOTES UPDATE	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 2

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG516.2

METER TYPE AND SOCKET CLIP ARRANGEMENT

SCOPE: THIS STANDARD PROVIDES GENERAL INFORMATION ON STANDARD SWITCH BOARD SERVICE SECTIONS.

DEFINITIONS:

- ELECTRIC UTILITY SERVICE EQUIPMENT REQUIREMENTS COMMITTEE (EUSERC): EUSERC IS AN ORGANIZATION COMPRISED OF UTILITY REPRESENTATIVES FROM THE WESTERN REGION OF THE UNITED STATES WHICH WORKS TO PROMOTE THE STANDARDIZATION OF ELECTRIC SERVICE REQUIREMENTS AND THE DESIGN AND ENGINEERING OF METERING AND SERVICE REQUIREMENT. SWITCHBOARD SERVICE SECTIONS, APPROVED FOR USE IN THE AREA SERVED BY SDG&E (UTILITY), ARE GENERALLY BUILT TO THE REQUIREMENTS DEVELOPED BY EUSERC, AND ARE AVAILABLE TO THE CUSTOMER AND CONTRACTOR THROUGH ELECTRICAL WHOLESALE DISTRIBUTORS.
- SWITCHBOARD SERVICE SECTION: A STANDARD SWITCHBOARD SERVICE SECTION IS A FREE-STANDING UNIT OF SERVICE EQUIPMENT WHICH CONTAINS BUSSING FOR THE TERMINATION OF SERVICE ENTRANCE OR SERVICE LATERAL CONDUCTORS, BUSSING FOR THE CONNECTION AND MOUNTING OF CURRENT TRANSFORMERS (CTS), FACTORY INSTALLED TEST-BYPASS DEVICES, METER SOCKET, AND A SERVICE MAIN DISCONNECT SWITCH OR BREAKER, AND IN MANY CASES, DISTRIBUTION FEEDER BREAKERS OR SWITCHES.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE STANDARD SWITCHBOARD SERVICE SECTION IS USUALLY BUILT TO SERVE THE CUSTOMER WITH HEAVY ELECTRICAL SUPPLY NEEDS, AND IS AVAILABLE WITH SERVICE MAIN SWITCH OR BREAKER RATINGS FROM 201–4,000A.
- II. STANDARDS FOR SERVICE SWITCHBOARDS HAVE ALSO BEEN DEVELOPED FOR SELF-CONTAINED METERS, BOTH RESIDENTIAL AND COMMERCIAL, AND WITH EITHER STANDARD-DUTY OR HEAVY-DUTY METER SOCKETS. THESE SECTIONS OF SWITCHBOARDS ARE NORMALLY BUILT ON SPECIAL ORDER TO MEET THE NEEDS OF THE CUSTOMER'S ELECTRIC SERVICE.

III. MANUFACTURER'S DRAWINGS FOR APPROVAL:

- a. THE MANUFACTURER OF THE SECONDARY (0–600V) ELECTRICAL EQUIPMENT RATED 1,000A AND ABOVE SHALL SUBMIT DRAWINGS ELECTRONICALLY TO SDG&E SERVICE STANDARDS FOR APPROVAL PRIOR TO FABRICATION. SEND DRAWINGS TO: DRAWINGSUBMITTALS@SDGE.COM
- b. The Address of the Job Must be shown on drawings in order to process. Notification will be sent to the sender with approvals or corrections as needed. When a parallel, stand-by or emergency generation system is existing or is to be installed in connection with New Service Equipment, a one-line electrical diagram showing the relationship of the generator with the service Equipment, including the transfer device and its sequence of operation, is to be submitted with the switchboard drawings. The electrical one-line diagram submittal requirement applies to all systems regardless of size.
- c. APPROVALS ARE VALID FOR THREE YEARS. AFTER THREE YEARS, RESUBMITTAL OF SWITCHBOARD DRAWINGS DIRECTLY FROM THE MANUFACTURER WILL BE REQUIRED FOR REVIEW AND APPROVAL.
- d. THIS PRACTICE WILL ENSURE THE UTILITY'S REQUIREMENTS ARE MET AND THE SERVICE EQUIPMENT WILL BE ACCEPTABLE TO THE UTILITY.

IV. SWITCHBOARD BUS/WIRE TAP DRAWINGS FOR APPROVAL:

a. IF THERE ARE ADEQUATE FACTORY-INSTALLED EXISTING CUSTOMER SIDE MECHANICAL LUGS AVAILABLE IN THE UNDERGROUND PULL SECTION (UGPS) FOR NEW SERVICE ENTRANCE CONDUCTORS TO BE ADDED, TAP DRAWINGS ARE NOT REQUIRED. IF MECHANICAL LUGS MUST BE ADDED TO AN EXISTING BUS, OR MANUFACTURER INSTALLED WIRE CONDUCTORS ARE TO BE TAPPED, BUS TAP DRAWINGS PREPARED BY A QUALIFIED ENGINEER ARE REQUIRED. SUBMIT DRAWINGS FOR APPROVAL PRIOR TO FABRICATION. SEND THEM ELECTRONICALLY TO: DRAWINGSUBMITTALS@SDGE.COM.

REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	HAN	GE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	ORIA	AL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL (CHAN	NGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page	Χ	Information Re	moved	ı			
	SHEET				SDO	3&E E	LECTI	RIC SERVIC	E STA	ND	ARDS & Gl	JIDE	S					
																S	G51	7.1
	1 OF 24			STA	AND/							ECT	ΓIONS			3	GJI	/ . I
	1 OF 24 STANDARD SWITCHBOARD SERVICE SECTIONS GENERAL INFORMATION																	

NOTES (CONT'D):

IV. SWITCHBOARD BUS/WIRE TAP DRAWINGS FOR APPROVAL (CONT'D):

b. THE ADDRESS OF THE JOB MUST BE SHOWN ON DRAWINGS IN ORDER TO PROCESS. NOTIFICATION WILL BE SENT TO THE SENDER WITH APPROVALS OR CORRECTIONS AS NEEDED. BOTH THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) AND THE UTILITY WILL INSPECT THE BUS TAP, AND THE UTILITY MUST RECEIVE THE INSPECTION CLEARANCE FROM THE AHJ AS A CONDITION OF ENERGIZING.

V. VENTILATION:

ALL SWITCHBOARD SECTIONS CONTAINING UNMETERED CONDUCTORS SHALL COMPLY WITH UL 891 (8.5.3) FOR PROTECTION OF ENERGIZED PARTS. THE UTILITY'S INSPECTORS DO NOT INSPECT FOR THIS REQUIREMENT. IT IS THE EQUIPMENT MANUFACTURER'S RESPONSIBILITY TO ENSURE COMPLIANCE WITH THE UL STANDARD. (a)

VI. SWITCHBOARD SERVICE SECTIONS OUTLINE:

THE FOLLOWING INFORMATION HAS BEEN INCLUDED TO HELP YOU VISUALIZE THE APPEARANCE OF STANDARD SWITCHBOARD SERVICE SECTIONS.

THE STANDARD SWITCHBOARD SECTIONS AS SHOWN MAY BE USED FOR SINGLE-PHASE SERVICE.

THE SWITCHBOARD BUSSING ARRANGEMENT IN THE INSTRUMENT TRANSFORMER COMPARTMENT FOR SINGLE-PHASE SERVICE CAPACITY IN THE RANGE OF 201–400A IS SHOWN ON SHEET 14.

THE 6-CLIP METER SOCKET FOR A SINGLE-PHASE, 120/240V, 3-WIRE TRANSFORMER RATED METER WILL BE PROVIDED. **b** SEE SHEETS 3-24 FOR STANDARD SWITCHBOARD SECTION DETAILS.

b. THE STANDARD SWITCHBOARD SECTIONS AS SHOWN MAY BE USED FOR THREE-PHASE SERVICE.

THE SWITCHBOARD BUSSING ARRANGEMENT IN THE INSTRUMENT TRANSFORMER COMPARTMENT FOR SERVICE CAPACITY IN THE RANGE OF 201–1,000A IS SHOWN ON SHEET 15.

THE SWITCHBOARD BUSSING ARRANGEMENT IN THE INSTRUMENT TRANSFORMER COMPARTMENT FOR SERVICE CAPACITY IN THE RANGE OF 1,001–3,000A IS SHOWN ON SHEETS 17–20.

THE SWITCHBOARD BUSSING ARRANGEMENT IN THE INSTRUMENT TRANSFORMER COMPARTMENT FOR SERVICE CAPACITY IN THE RANGE OF 3,001–4,000A IS SHOWN ON SHEETS 21–24.

THE 15-CLIP METER SOCKET IS REQUIRED FOR ALL THREE-PHASE TRANSFORMER RATED INSTALLATIONS. (b)

FOR STANDARD SWITCHBOARD SECTION DETAILS, SEE SHEETS 6-8 AND 11-24.

c. MULTIPLE METERING SWITCHBOARDS FOR RESIDENTIAL SERVICE MAY USE EITHER STANDARD-DUTY METER SOCKETS, WITH NOMINAL CAPACITY OF 125A, OR HEAVY-DUTY METER SOCKETS, WITH NOMINAL CAPACITY OF 200A.

WHEN MOUNTED IN SWITCHBOARDS, PREFERABLY ONE BUT NOT MORE THAN TWO METER SOCKETS MAY BE MOUNTED ON ANY SINGLE FRONT PANEL.

WHEN THE INSTALLATION IS COMPLETE, ALL METER PANELS MUST BE REMOVABLE FOR INSPECTION OF WIRING. PANEL DESIGN SHALL PERMIT CONVENIENT REPLACEMENT OF ANY METER SOCKET WITHOUT INTERRUPTION OF SERVICE TO OTHER METERS.


d. MULTIPLE METER SWITCHBOARDS FOR COMMERCIAL SERVICE, EITHER FOR SINGLE OR MULTIPLE METERING, MUST HAVE FACTORY-INSTALLED TEST-BYPASS FACILITIES.

REFERENCE:

- (a) SEE UL 891 (8.5.3).
- (b) SEE SG516.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CHA	١N	GE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDIT	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е										
Α	EDITORIAL (EDITORIAL CHANGES					TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Re	moved				
	SHEET				SDG	3&E E	LECTI	RIC SERVIC	E STA	٩NE	DARDS & GUI	DE	S					
	SHLLH															S	G51	7.2
	2 OF 24		STANDARD SWITCHBOARD SERVICE SECTIONS													_		

GENERAL INFORMATION






TABLE 1

STA	NDARD SWITCHBOARD SERVICE SECTION, 0-600V DESCRIPTION LIST
ITEM	DESCRIPTION
$\langle 1 \rangle$	TEST SWITCH CUTOUT AND REMOVABLE PLATE
2	HANDLE
3	METER PANEL, SEE SHEET 10
4	STUDS AND WING NUTS OR SEALING SCREWS
5	LOCKABLE MAIN SWITCH OR BREAKER
6	HINGE
7	INSTRUMENT TRANSFORMER COMPARTMENT
8	BARRIER
9	BLANK HINGED PANEL
(10)	OPTIONAL BLANK PANEL (SEALABLE)
(11)	FILLER PANEL
(12)	HINGED
(13)	LOCKABLE MAIN
(14)	SEPARATE REMOVABLE PLATE, NOT SEALABLE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 4 OF 24 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V

SG517.4

- (A) FIGURE 3 SHOWS A SEPARATE BARRIER CREATING A LOAD WIREWAY AT THE UPPER RIGHT SIDE OF THE SWITCHBOARD IN ORDER TO ROUTE THE LOAD CONDUCTORS OUT THE TOP. LOAD CONDUCTORS MAY NOT BE ROUTED THROUGH THE INSTRUMENT TRANSFORMER COMPARTMENT IN ORDER TO EXIT THE SWITCHBOARD.
- B PLACING A FREE-STANDING METER PANEL ON A HOUSEKEEPING PAD RAISES THE METER HEIGHTS. GENERALLY, EQUIPMENT MANUFACTURERS MAY ALLOW 2 1/2 INCHES FOR THIS. HOUSEKEEPING PADS INSTALLED HIGHER THAN 2 1/2 INCHES MAY RAISE THE CENTERLINE OF THE METER ON THE PANEL ABOVE 6 FEET 3 INCHES. IT IS THE CUSTOMER'S RESPONSIBILITY TO ENSURE THE CENTERLINE OF METER DOES NOT EXCEED 6 FEET 3 INCHES HIGH, MEASURED FROM STANDING SURFACE OF THE WORKING SPACE.

BILL OF MATERIALS: NONE

NOTES:

- I. THE WIDTH AND DEPTH ARE DETERMINED BY TYPE AND AMPERAGE OF SERVICE.
- II. FOR OUTDOOR/RAINTIGHT (NEMA 3R) ENCLOSURES, SEE SHEETS 6-8.
- III. INSTRUMENT TRANSFORMER COMPARTMENTS SHALL BE BUSSED WITH RECTANGULAR BUS BAR.
- IV. THE GROUNDING CONNECTION SHALL BE MADE IN THE MAIN SWITCH OR BREAKER COMPARTMENT.
- V. METER PANELS SHALL BE CONSTRUCTED OF 12-GAUGE STEEL (MINIMUM) AND SHALL BE REVERSIBLE, SEALABLE, HINGED AND INTERCHANGEABLE.
- VI. THE METER PANEL SHALL BE MOUNTED IN THE UPPER POSITION AND HAVE A HANDLE ATTACHED AT THE UNSUPPORTED END.
- VII. HINGES SHALL BE READILY INTERCHANGEABLE, RIGHT OR LEFT, ON THE JOB SITE.
- VIII. WIDTH OF METER PANELS MAY IN SOME CASES REQUIRE THE SERVICE SECTION TO BE WIDER THAN THE MINIMUM ALLOWABLE WIDTH OF TRANSFORMER COMPARTMENT. FOR MINIMUM DIMENSIONS OF INSTRUMENT TRANSFORMER COMPARTMENTS, SEE SHEET 2, FOR PAGE REFERENCES.
- IX. ALL PANELS AND COVERS SHALL BE SEALABLE.
- (XI) filler panels shall be used where switchboard width exceeds maximum allowable meter panel width.
- (XII) SEE FIGURE 1 FOR ADDITIONAL DIMENSIONS.
- (XIII) ACCESS TO CUSTOMER'S DISTRIBUTION WIREWAYS SHALL NOT REQUIRE OPENING OR REMOVING SEALABLE PANELS.

REFERENCE:

a. FOR WORKING SPACE AND CLEARANCE REQUIREMENTS, 0–600V, SEE SG504.

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CH	IAN	GE	DR	BY	DSN	APV	DATE
С								F									
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL C	CHANGES	-	LSM	CTG	TPM	11/01/2017	D									
		X Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Re	moved				
	SHEET			SDG&E ELECTRIC SERVICE STANDARDS & GUIDES													
															S	G51	7.5
	5 OF 24	ANDA	٩RD	SW:	TCHBO/	٩RD	SEF	RVICE SE	EC	ΓIONS			_				

0-600V

SCOPE: THIS STANDARD SHOWS THE CONSTRUCTION FOR AN OUTDOOR RAINTIGHT UNIT WITH ENCLOSED METER PANELS AND MAIN DISCONNECT SWITCH OR BREAKER. (II) $\langle 6 \rangle$ (4)(C)<mark>III</mark>(a) **B**) **EXAMPLE 1 EXAMPLE 2 FIGURE 1** TOP VIEW SEE TABLE 1 2 11" (II)MIN. V 10" 10" 10" MIN.-MIN. 4" MIN. (XI)(3)(A)(VII)(1)(1)(A)(VII)(VIII)10" MIN.-11" MIN. 12" MAX. 2 (IX) (IX) B 2'-11" MIN. 2'-11" MIN. -(III)(C)(a **EXAMPLE 1 EXAMPLE 2** FIGURE 1 FRONT VIEW SIDE VIEW SEE TABLE 1 © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DSN APV **CHANGE** DR DSN APV **REV** DR BY **DATE** BY DATE **CHANGE** С F Ε В FORMATTING/EDITORIAL CHANGES **EDM** IWA JTM KRG 02/07/2025 TPM 11/01/2017 Α **EDITORIAL CHANGES** LSM CTG **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG517.6 6 OF 24 STANDARD SWITCHBOARD SERVICE SECTIONS

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V, OUTDOOR/RAINTIGHT ENCLOSURE (NEMA 3R)

	STANDARD SWITCHBOARD SERVICE STATION, NEMA 3R, DESCRIPTION LIST
ITEM	DESCRIPTION
$\langle 1 \rangle$	METER PANEL HINGES
2	ENCLOSURE DOOR HINGES
(3)	FACE OF PANEL
4	CLEAR AND LEVEL WORKING SPACE
(5)	HOUSEKEEPING PAD
6	PULL SECTION OR WIREWAY
7	WIREWAY

INSTALLATION:

- (A) HINGED METER PANELS SHALL BE CAPABLE OF BEING OPENED 90 DEGREES WITH METER AND TEST FACILITIES IN PLACE. THE HINGES SHALL BE READILY INTERCHANGEABLE RIGHT OR LEFT ON THE JOB SIGHT. FOR OTHER DETAILS, SEE SHEETS 9 AND 10. ALL METER PANELS MUST BE HINGED FROM THE TEST SWITCH SIDE.
- B THE ENCLOSURE DOOR SHALL BE HINGED OPPOSITE FROM THE METER PANEL DOOR WHEN NECESSARY TO ALLOW 90 DEGREE OPENING OF THE METER PANEL DOOR WITH UTILITY EQUIPMENT IN PLACE. WHEN ENCLOSURE DOOR(S) IS LOCKED, A DOUBLE HASP IS REQUIRED. THE ENCLOSURE DOOR(S) SHALL BE DESIGNED TO SECURE IN THE OPEN POSITION AT 90 DEGREES OR MORE. A FULL HEIGHT HINGED DOOR WITH A THREE-POINT LOCKING MECHANISM AND PROVISION FOR A UTILITY FURNISHED PADLOCK IS REQUIRED.
- © WHEN OUTDOOR RAINTIGHT SERVICE EQUIPMENT IS INSTALLED ON A "HOUSEKEEPING PAD", THAT PAD MUST BE LEVEL AND EXTEND A MINIMUM OF 3 FEET MEASURED FROM THE FACE OF THE METER PANEL, OR A MINIMUM OF 6 FEET WHEN 5-INCH CONDUIT IS REQUIRED. SEE FIGURE 1 ON SHEET 6. IF THE ENCLOSURE DOORS ARE WIDER THAN 3 FEET, THE HOUSEKEEPING PAD SHALL EXTEND 1-INCH BEYOND THE OUTER EDGE OF THE EQUIPMENT DOORS WHEN OPENED AT 90 DEGREES.

BILL OF MATERIALS: NONE

NOTES:

- $\overline{(\mathrm{I})}$ THE METER HEIGHTS SPECIFIED ON SG504 APPLY IN FULL SWITCHBOARD HEIGHT METER ENCLOSURES. $\overline{(\mathsf{a})}$
- (II) WHEN USED AS UNDERGROUND PULL SECTION
- (III) 3 FEET MINIMUM, OR 6 FEET MINIMUM WHEN 5-INCH CONDUIT IS REQUIRED.
- $\overline{(ext{IV})}$ Hinged doors, when opened, may not block the 24-inch minimum exit route.
- (V) the width and depth are determined by type and ampacity of service.
- (VI) FOR METER SOCKET AND TEST SWITCH PANEL LAYOUT, SEE SHEETS 9 AND 10. FOR INSTRUMENT TRANSFORMER COMPARTMENT INFORMATION, SEE SHEETS 14 TO 24.
- (VII) IF PANEL IS HINGED AT THE SIDE WALL OF THE NEMA 3R RECESS, THE EDGE OF THE TEST SWITCH SLOTS SHALL BE 1-INCH PLUS THE DEPTH OF THE RECESS FROM THE HINGED SIDE.
- WHERE AN ADJACENT OBSTRUCTION EXTENDS 11 INCHES OR MORE PERPENDICULAR FROM THE FACE OF THE METER SOCKET, A 10-INCH MINIMUM DIMENSION TO CENTERLINE OF METER IS REQUIRED. THIS ALSO APPLIES TO MULTI-METER INSTALLATIONS. (C)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 7 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS

SG517.7

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V, OUTDOOR/RAINTIGHT ENCLOSURE (NEMA 3R)

NOTES (CONT'D): (IX) ALL PANELS AND COVERS SHALL BE SEALABLE. (XI) THE 11-INCH CLEARANCE FROM METER PANEL TO INSIDE OF DOOR IS REQUIRED FOR ALL TYPES OF METERS. **REFERENCE:** (a) FOR WORKING SPACE AND CLEARANCE REQUIREMENTS, 0–600V, SEE SG504. (b) FOR TERMINATING ENCLOSURE UGPS REQUIREMENTS, SEE SG700. (c) FOR METER CABINET REQUIREMENTS, SEE SG509. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	СН	IAN	IGE	DR	BY	DSN	APV	DATE
С							F								
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D								
	X Indicates La	itest R	evisio	n	Con	npletely Revi	ised	New Page		Information Re	moved				

SHEET 8 OF 24 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V, OUTDOOR/RAINTIGHT ENCLOSURE (NEMA 3R)

SCOPE: THIS STANDARD PROVIDES INFORMATION ON METER SOCKET AND TEST SWITCH PANEL LAYOUT FOR 0-600V STANDARD SWITCHBOARD SERVICE SECTIONS.





FIGURE 1 SEE TABLE 1



DETAIL 1REMOVABLE PLATE

TABLE 1

METER	SOCKET AND TEST SWITCH PANEL DESCRIPTION LIST
ITEM	DESCRIPTION
1	5/16" DRILL, 4 HOLES
2	2 EACH, UPPER AND LOWER FLANGES
3	HANDLE AREA
4	HINGE
(5)	10-32 TAP, 2 HOLES
6	10-32 TAP, 4 HOLES

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 9 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V METER SOCKET AND TEST SWITCH PANEL LAYOUT

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- $oxed{I}$ "Break edges" front and back to remove all burrs.
- II. THE SWITCHBOARD MANUFACTURER SHALL DRILL, TAP AND SLOT THE PANEL AS SHOWN FOR SECONDARY TEST SWITCHES AND SHALL FURNISH AND INSTALL SOCKETS COMPLETE WITH SEALING RINGS.
- III. METER PANELS SHALL BE CONSTRUCTED OF 12-GAUGE STEEL (MINIMUM) AND SHALL BE HINGED AT THE TEST SWITCH SIDE BY THE MANUFACTURER. METER PANELS SHALL BE SEALABLE, AND MUST BE REVERSIBLE AND INTERCHANGEABLE IF FIELD CONDITIONS REQUIRE SUCH CHANGE.
- IV. METER PANELS SHALL HAVE A HANDLE ATTACHED AT THE UNSUPPORTED END.
- V. HINGES MUST SUPPORT A 25-POUND LOAD APPLIED AT THE UNSUPPORTED END WITH 1/8 INCH MAXIMUM SAG WHEN OPEN.
- VI. HINGES SHALL BE READILY INTERCHANGEABLE, RIGHT OR LEFT, ON THE JOB SITE.
- VII. REMOVABLE PLATE SHALL BE SECURED TO REAR OF PANEL BY SCREWS OF SUCH LENGTH SO AS NOT TO PROTRUDE THROUGH FACE OF PANEL.
- VIII.METER PANELS SHALL BE CAPABLE OF BEING OPENED 90 DEGREES WITH METER AND TEST FACILITIES IN PLACE.
- (IX) ALL SECURING SCREWS AND SEALING SCREWS ON PANELS SHALL BE CAPTIVE. STUDS AND WING NUTS SHALL BE SEALABLE WHEN USED.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 10 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V METER SOCKET AND TEST SWITCH PANEL LAYOUT

SCOPE: THIS STANDARD PROVIDES INFORMATION ON 0-600V, SINGLE-PHASE, 3-WIRE AND THREE-PHASE, 4-WIRE, STANDARD SWITCHBOARD SERVICE SECTIONS FOR SELF-CONTAINED METERING WITH 200A MAXIMUM METER SOCKET CAPACITY.




FIGURE 1
SEE TABLE 1

FIGURE 2 SEE TABLE 1




FIGURE 3 SEE TABLE 1

TABLE 1

	SELF-CONTAINED METERING DESCRIPTION LIST
ITEM	DESCRIPTION
1	TEST-BYPASS BLOCK WITH 4 RIGID INSULATING BARRIERS
2	ISOLATING BARRIER
3	SOCKET SUPPORT
4	TEST BYPASS SUPPORT

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SINGLE-PHASE, 3-WIRE AND THREE-PHASE, 4-WIRE SERVICES

SHEET 11 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS

0-600V FOR SELF-CONTAINED METERING,
200A MAXIMUM METER SOCKET CAPACITY

- A TEST-BYPASS FACILITIES WITH RIGID INSULATING BARRIERS SHALL BE FURNISHED, INSTALLED, AND WIRED OR BUSSED TO THE METER SOCKET BY THE MANUFACTURER. BLOCKS AND BARRIERS SHALL CONFORM TO SG513 REQUIREMENTS WITH PHYSICAL ARRANGEMENT CONFORMING TO SG514. CONNECTION SEQUENCE IS LINE-LOAD, LINE-LOAD, LINE-LOAD FROM LEFT TO RIGHT. (a) (b)
- B. SEPARATE LINE AND LOAD CONDUCTORS SHALL BE INSTALLED AND CONNECTED BY THE CONTRACTOR OR MANUFACTURER FOR EACH TEST-BYPASS POSITION.
- C. METERED CONDUCTORS SHALL NOT PASS THROUGH ADJACENT METERING COMPARTMENTS EXCEPT IN CLOSED WIREWAYS. TO ENSURE PROPER IDENTIFICATION OF CABLES IN FACTORY CABLED EQUIPMENT, METERED CABLES (EXCEPT IN THE TEST-BYPASS AREA), SHALL BE EITHER PHYSICALLY BARRIERED OR BUNDLED SO AS TO SEPARATE THEM FROM UNMETERED CABLE OR PERMANENTLY MARKED AND ISOLATED FROM UNMETERED CABLES. PHYSICAL BARRIERS WILL NOT BE REQUIRED IF THE UNMETERED CONDUCTORS ARE BUS.
- D. METER PANELS SHALL BE REMOVABLE, BUT SHALL BE NON-REMOVABLE WHEN THE METER IS IN PLACE. THE METER SOCKET SHALL BE SUPPORTED INDEPENDENT OF, AND ATTACHED TO, THE METER PANEL. WHEN MOUNTED IN SWITCHBOARDS, PREFERABLY ONE BUT NOT MORE THAN TWO SOCKETS MAY BE MOUNTED ON ANY SINGLE FRONT PANEL.
- (E) TEST-BYPASS COVER PANELS SHALL BE SEALABLE AND FITTED WITH A LIFTING HANDLE. ALL PANELS EXCEEDING 16 INCHES IN WIDTH SHALL REQUIRE TWO LIFTING HANDLES.
- F. WHEN A NEUTRAL IS REQUIRED FOR METERING OR TESTING, AN INSULATED NEUTRAL TERMINAL SHALL BE PROVIDED BEHIND EACH TEST-BYPASS COVER PANEL. THE TERMINAL SHALL BE READILY ACCESSIBLE WHEN THE COVER PANEL IS REMOVED AND SHALL BE INDIVIDUALLY CONNECTED TO THE NEUTRAL BUS WITH A MINIMUM NO. 12 COPPER WIRE.
- G FACTORY-INSTALLED FULL-WIDTH INSULATING BARRIERS WITH A MAXIMUM DEFLECTION OF 1/2 INCH FROM AN APPLIED FORCE OF 25 POUNDS DOWNWARD, SHALL BE LOCATED AT THE BOTTOM OF EACH TEST-BYPASS COMPARTMENT. IN ADDITION, A FULL WIDTH AND DEPTH ISOLATING BARRIER SHALL BE LOCATED BELOW THE BOTTOM TEST-BYPASS COMPARTMENTS AND ABOVE THE LOAD TERMINALS OF THE METER DISCONNECT DEVICES. IF A FACTORY-INSTALLED REAR-LOAD WIREWAY IS PROVIDED, THE ISOLATING BARRIER SHALL EXTEND BACK TO THAT WIREWAY. VENTILATION OPENINGS, WHEN PROVIDED, SHALL NOT EXCEED A MAXIMUM DIAMETER OF 3/8 INCH. A SLOT IN THE ISOLATING BARRIER PROVIDED FOR THE LOAD CONDUCTORS SUPPLIED FROM THE TEST-BYPASS BLOCKS SHALL BE A MAXIMUM OF 1 1/2 INCHES IN DEPTH AND MAY EXTEND TO THE WIDTH OF THE METER DISCONNECT DEVICES. THE SLOT MAY NOT BE LOCATED IN THE FRONT 6 INCHES OF THE TEST BY-PASS COMPARTMENT INSULATING BARRIER.
- H. ENCLOSURES MUST ALLOW A MINIMUM OF 11 INCHES TO A MAXIMUM OF 12 INCHES FROM THE FACE OF THE METER PANEL TO THE INSIDE OF THE DOOR, AND 10 INCHES MEASURED FROM THE VERTICAL CENTERLINE OF THE SOCKET TO ANY SIDE OBSTRUCTION INCLUDING THE DOOR-JAMB OR FLANGE. THIS 10-INCH SIDE CLEARANCE EXTENDS A MINIMUM OF 3 FEET FROM THE FACE OF THE METER PANEL. SEE SHEETS 6-8 FOR OUTDOOR/RAINTIGHT ENCLOSURE DETAILS. (d)

BILL OF MATERIALS: NONE

NOTES:

- ${f I}$ field installed conductors may require a greater dimension between test-bypass blocks and barrier.
- II. MINIMUM ACCESS OPENING TO TEST-BYPASS BLOCKS SHALL BE 11" X 10" FOR FIGURE 1 AND 21 1/2" X 10" FOR FIGURE 2.
- III. RIGID INSULATING BARRIERS SHALL BE INSTALLED AS SHOWN.
- IV. UPPER TEST CONNECTOR STUD SHALL BE A MINIMUM OF 3 INCHES BELOW UPPER PANEL.
- V. FOR THREE-PHASE, 4-WIRE, CONNECT 7TH JAW TO NEUTRAL TERMINAL WITH A WHITE NO. 12 COPPER WIRE.
- VI. FOR THREE-PHASE, 4-WIRE, DELTA, IDENTIFY RIGHT HAND TEST-BYPASS BLOCK (2 POLES) AS POWER LEG, ORANGE IN COLOR (C PHASE).
- VII. FOR SINGLE-PHASE, 3-WIRE, OMIT CENTER TEST-BYPASS BLOCK.

	© 1000 2020 G	an Diego Gas & El	ectric (Jompa	ny. All	rights	reserved. Rer	noval d	of this copyright no	otice	without permission	is not	permi	ited und	der law	
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CI	HAN	IGE	DR	BY	DSN	APV	DATE
С								F								
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е								
Α	EDITORIAL (CHANGES	NGES - LSM CTG TPM 11/01/2017 D													
		X Indicates La	Indicates Latest Revision Completely Revised New Page Information Removed													
	CHEET		SDG&E ELECTRIC SERVICE STANDARDS & GUIDES													
	SHEET		STANDARD SWITCHBOARD SERVICE SECTIONS													7.12
-	L2 OF 24		0-600V FOR SELF-CONTAINED METERING,													.12
-	0		200A MAXIMUM METER SOCKET CAPACITY													
SINGLE-PHASE, 3-WIRE AND THREE-PHASE, 4-WIRE SERVICES																

NOTES (CONT'D):

- VIII. FOR SINGLE-PHASE, 3-WIRE, 208Y/120V, OMIT CENTER TEST-BYPASS BLOCK. CONNECT FIFTH JAW TO NEUTRAL TERMINAL WITH A WHITE NO. 12 COPPER WIRE.
- IX. ALL SECURING SCREWS SHALL BE CAPTIVE. ALL PANELS AND COVERS SHALL BE SEALABLE.
- XI. EACH LINE AND LOAD POSITION SHALL BE CLEARLY IDENTIFIED BY 3/4-INCH MINIMUM BLOCK LETTER LABELING.

REFERENCE:


- (a) SEE SG513.
- (b) SEE SG514.
- (c) FOR METER MOUNTING HEIGHTS, SEE SG504.
- (d) FOR METER CABINET DETAILS, SEE SG509.


@ 4000 000F O D! 0 Fl+! - O			!4 !44!! !
(C) 1998 - 2025 San Diego Gas & Electric Company	All rights reserved. Removal of this c	CONTINUI DOTICE WITHOUT DEFMISSIO	in is not nermitted linder law
© 1998 - 2025 San Diego Gas & Electric Company	. 7 th rights reserved. I terrioval of this t	opyright house without permissic	in is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

Indicates Latest Revision | Completely Revised | New Page |

SHEET 13 OF 24 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES
STANDARD SWITCHBOARD SERVICE SECTIONS
0-600V FOR SELF-CONTAINED METERING,
200A MAXIMUM METER SOCKET CAPACITY
SINGLE-PHASE, 3-WIRE AND THREE-PHASE, 4-WIRE SERVICES







INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. BUS ARRANGEMENT AND SUPPORTS ARE REQUIRED AS SHOWN IN FIGURES 1 AND 2, EXCEPT THAT NEUTRAL MAY BE LOCATED ON THE SIDE WALL OR AT EITHER SIDE.

TABLE 1

ITEM

 $\langle 1 \rangle$

 $\langle {}_{2} \rangle$

⟨3⟩

 $\langle 4 \rangle$

 $\langle {\sf 5}
angle$

 $\langle 6 \rangle$

(7)

⟨8⟩

(9)

 $\langle 10 \rangle$

BUS SUPPORT BAR

BARRIER

CENTERI INF

REMOVABLE LINK

ANCHORED TO PREVENT TURNING

9/16" Ø. DRILL 3 HOLES PER BUS

TEST TRANSFORMER SUPPORT BAR

10-32 SCREW AND WASHER, TYPICAL

ALTERNATE LOCATION OF NEUTRAL BUS

BOLT, STEEL, 1/2" (WITH SPRING WASHER AND NUT)

COMPARTMENT INSTRUMENT TRANSFORMER

INSTRUMENT TRANSFORMER COMPARTMENT, 200-1,000A,
DESCRIPTION LIST

DESCRIPTION

- II. COMPARTMENT SHALL BE ON THE SUPPLY SIDE OF THE MAIN SWITCH OR BREAKER.
- III. DIRECTION OF FEED MAY BE FROM TOP OR BOTTOM. NO OTHER CONDUCTORS SHALL PASS THROUGH THIS COMPARTMENT.
- (IV) RETURN FLANGES FOR LOWER AND UPPER METER PANEL SUPPORT SHALL NOT PROJECT MORE THAN 3/4 INCH UP OR DOWN FROM ADJACENT SWITCHBOARD PANELS.
- (V) when a Laminated bus is used, there shall be no space between Laminations in the compartment.
- VI. BUS DIMENSIONS: MAXIMUM 3/4" X 2"; MINIMUM 1/4" X 2".
- (
 m VII) the barrier shall be of insulating material and a have minimum of 24 vent holes of 3/8-inch diameter.
- THE DIRECTION OF FEED MAY BE FROM THE TOP OR BOTTOM. NO OTHER CONDUCTORS SHALL PASS THROUGH THIS COMPARTMENT. A NEUTRAL BUS BAR EXTENSION SHALL BE PROVIDED IN THE INSTRUMENT TRANSFORMER COMPARTMENT ABOVE THE LOWER CT BUS SUPPORT WHEN THE SERVICE SECTION PHASE BUSSES ARE SUPPLIED FROM HORIZONTAL CROSS BUSSING.
- (IX) THE POWER LEG (HIGH LEG) FOR A FOUR-WIRE DELTA SERVICE SHALL BE IDENTIFIED BY AN OUTER FINISH THAT IS ORANGE IN COLOR OR BY TAGGING OR BY OTHER EFFECTIVE MEANS ACCEPTABLE TO THE UTILITY AND THE AHJ ON THE RIGHT OF C-PHASE.
- (XI) a removable link shall be installed in the right side phase bus.
- (XII) BUS UNIT SHALL BE PROVIDED WITH A FIXED STUD/BOLT AS SHOWN FOR MOUNTING THE CURRENT TRANSFORMERS.
 - a. EACH BOLT SHALL CONSIST OF A ½-INCH STEEL BOLT AND SHALL BE PROVIDED WITH A SPRING WASHER AND A NUT. THE SPRING WASHER MAY BE EITHER A CONE-TYPE (BELLEVILLE) WASHER OR A SPLIT-RING WASHER AND FLAT WASHER. ALL PARTS SHALL BE PLATED TO PREVENT CORROSION.
 - b. EACH BOLT SHALL BE SECURED IN PLACE. "SECURED IN PLACE" SHALL MEAN THAT THE STUD WILL NOT TURN, BACK-OUT, OR LOOSEN IN ANY MANNER WHEN TIGHTENING OR LOOSENING THE ASSOCIATED NUTS (INCLUDING CROSS-THREADED SITUATIONS).

REFERENCE:

- a. WHEN MAIN SWITCH IS OVER 400A AND FOR ALL UNDERGROUND SERVICES, SEE SG708 AND CONSULT THE UTILITY'S PLANNER.
- b. FOR CONTACT INFORMATION, SEE SG021.


© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 16 OF 24 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V INSTRUMENT TRANSFORMER COMPARTMENT



IN	STRUMENT TRANSFORMER COMPARTMENT, 1,001-3,000A, DESCRIPTION LIST
ITEM	DESCRIPTION
1	BUS SUPPORT BAR
2	10-32 TAP
3	BUS SUPPORTS
4	10-32 SCREW AND WASHER
(5)	REMOVABLE SECTION B AND C.T. SUPPORT
6	VENTED BARRIER
7	TEST TRANSFORMER SUPPORT BAR
8	NEUTRAL

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE BUS ANCHORAGE SHALL BE SUCH THAT BUSSES WILL REMAIN IN POSITION WHEN REMOVABLE SECTION "B" IS OUT.
- II. THE DIRECTION OF FEED MAY BE FROM THE TOP OR BOTTOM. NO OTHER CONDUCTORS SHALL PASS THROUGH THIS COMPARTMENT.
- III. THE INSTRUMENT TRANSFORMER COMPARTMENT SHALL BE ON THE SUPPLY SIDE OF THE MAIN SWITCH OR BREAKER.
- (IV) ROUND BUS CORNERS AS NECESSARY TO PREVENT DAMAGE TO INSULATION. BUS INSULATION TO BE ADEQUATE FOR THE VOLTAGE INVOLVED.
- V. FOR UNDERGROUND SERVICES INSTALLED BY THE UTILITY, THE BUSSES SHALL EXTEND INTO THE UGPS. CONSULT THE UTILITY'S PLANNER. (a) (b)
- VI. THE MAXIMUM PERMISSIBLE BUS UNIT SHALL CONSIST OF FOUR 1/4" X 4" BARS SPACED 1/4 INCH.
- VII. THE BARRIER SHOULD NOT BE LESS THAN 45 INCHES AND SHALL NOT BE MORE THAN 50 INCHES ABOVE THE STANDING SURFACE.
- VIII.CLEARANCE TO THE SIDE OF THE COMPARTMENT SHALL BE INCREASED BY THE AMOUNT BY WHICH THE CORNER ANGLE EXCEEDS 1 INCH.
- IX. RETURN FLANGES FOR LOWER AND UPPER METER PANEL SUPPORT SHALL NOT PROJECT MORE THAN 3/4 INCH UP OR DOWN FROM ADJACENT SWITCHBOARD PANELS.
- (XI) THE BARRIER SHALL BE OF INSULATING MATERIAL AND A HAVE MINIMUM OF 24 VENT HOLES OF 3/8 INCH DIAMETER.
- XII. ALL BUS SUPPORTS SHALL BE MOUNTED BEHIND THE FACE OF THE BUS.

REFERENCE:

- (a) SEE SG708.
- (b) FOR CONTACT INFORMATION, SEE SG021.

	e 1000 Z0Z0 Gail Blego Gas a El	coulo c	Joinpu	11y . 7 tii	rigino	reserved. I tel	novai	or this copyright hotioc without permission	10 1100	perimi	tou une	JOI IUW	· .
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
C							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this convigant notice without permission is not permitted under law


A EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 D

X Indicates Latest Revision Completely Revised New Page Information Removed

SHEET 18 OF 24

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V INSTRUMENT TRANSFORMER COMPARTMENT 1,001-3,000A THREE-PHASE, 3 AND 4-WIRE SERVICES

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES



REMOV	ABLE LINK AND CT SUPPORT DESCRIPTION LIST									
ITEM DESCRIPTION										
1	INSULATED TRANSFORMER SUPPORT									
2	LINK									
3	WINDOW TYPE CURRENT TRANSFORMER									
4	1/4" X 20 CAPSCREW									

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I THE MANUFACTURER SHALL SECURE THE REMOVABLE BUS LINK TO THE UPPER AND LOWER CT BUS UNITS USING 1/2-INCH HEXHEAD STEEL BOLTS, NUTS (AS SHOWN) WITH A SPRING WASHER AND A NUT. THE SPRING WASHER MAY BE EITHER A CONE-TYPE (BELLEVILLE) OR A SPLIT-RING WASHER WITH A FLAT WASHER. BOLTS SHALL BE GRADE 5 (MINIMUM), AND LONG ENOUGH TO EXTEND A MINIMUM OF 1/2 INCH BEYOND THE NUT. WASHERS (BELLEVILLE OR FLAT) SHALL BE 2 1/4 INCHES (MINIMUM).

(II) THE DRILL AND TAP TWO HOLES AS SHOWN ON THE OUTER UNITS FOR 1/4-INCH X 20 CAPSCREWS.

(III) MATERIAL: INSULATING, NON-TRACKING

(IV) SAME MATERIAL AS BUS

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 20 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V, 1,001-3,000A REMOVABLE LINK AND CURRENT XFMR SUPPORT FOR INSTRUMENT XFMR COMPARTMENTS WITH 4-INCH BUS

SCOPE: THIS STANDARD PROVIDES INFORMATION ON 0-600V, 3,001-4,000A, INSTRUMENT TRANSFORMER COMPARTMENTS ON STANDARD SWITCHBOARD SERVICE SECTIONS.

TABLE 1

MAXIMU	MAXIMUM NUMBER OF BUS BARS											
QUANTITY	BAR SIZE (IN)	SPACED (IN)										
4	1/4 X 4	1/4										
6	1/4 X 5	1/4										
4	3/8 X 5	3/8										
5	3/8 X 5	1/4										




FIGURE 1
TOP VIEW
SEE TABLE 2




FIGURE 1
SIDE VIEW
SEE TABLE 2

FRONT VIEW SEE TABLE 2

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
_													

SHEET 21 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V INSTRUMENT TRANSFORMER COMPARTMENT 3,001-4,000A, THREE-PHASE, 3 AND 4-WIRE SERVICES

IN	STRUMENT TRANSFORMER COMPARTMENT, 3,001-4,000A, DESCRIPTION LIST								
ITEM	DESCRIPTION								
1	BUS SUPPORT BAR								
2	OPTIONAL BUS SUPPORTS								
3	BUS SUPPORTS								
4	10-32 SCREW AND WASHER								
(5)	NEUTRAL								
6	REMOVABLE SECTION B AND C.T. SUPPORT								
7	VENTED BARRIER								
8	TEST TRANSFORMER SUPPORT BAR								
9	10-32 TAP								

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE BUS ANCHORAGE SHALL BE SUCH THAT BUSSES WILL REMAIN IN POSITION WHEN REMOVABLE SECTION "B" IS OUT.
- II. THE DIRECTION OF FEED MAY BE FROM THE TOP OR BOTTOM. NO OTHER CONDUCTORS SHALL PASS THROUGH THIS COMPARTMENT.
- III. THE INSTRUMENT TRANSFORMER COMPARTMENT SHALL BE ON THE SUPPLY SIDE OF THE MAIN SWITCH OR BREAKER.
- (IV) ROUND BUS CORNERS AS NECESSARY TO PREVENT DAMAGE TO INSULATION. BUS INSULATION TO BE ADEQUATE FOR THE VOLTAGE INVOLVED.
- V. FOR UNDERGROUND SERVICES INSTALLED BY THE UTILITY, THE BUSSES SHALL EXTEND INTO THE UGPS. CONSULT THE UTILITY'S PLANNER. (a)(b)
- VI. THE MAXIMUM PERMISSIBLE BUS UNIT SHALL CONSIST OF SIX 1/4" X 5" BARS SPACED 1/4-INCH.
- VII. THE BARRIER SHOULD NOT BE LESS THAN 45 INCHES AND SHALL NOT BE MORE THAN 50 INCHES ABOVE THE STANDING SURFACE.
- VIII.CLEARANCE TO THE SIDE OF THE COMPARTMENT SHALL BE INCREASED BY THE AMOUNT BY WHICH THE CORNER ANGLE EXCEEDS 1 INCH.
- IX. RETURN FLANGES FOR LOWER AND UPPER METER PANEL SUPPORT SHALL NOT PROJECT MORE THAN 3/4 INCH UP OR DOWN FROM ADJACENT SWITCHBOARD PANELS.
- (XI) THE BARRIER SHALL BE OF INSULATING MATERIAL AND A HAVE MINIMUM OF 40 VENT HOLES OF 3/8-INCH DIAMETER.
- (XII) ALL BUS SUPPORTS SHALL BE MOUNTED BEHIND THE FACE OF THE BUS.

REFERENCE:

- (a) SEE SG708.
- (b) FOR CONTACT INFORMATION, SEE <mark>SG021</mark>.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 22 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V INSTRUMENT TRANSFORMER COMPARTMENT 3,001-4,000A THREE-PHASE, 3 AND 4-WIRE SERVICES

SCOPE: THIS STANDARD PROVIDES INFORMATION ON 3,001-4,000A REMOVABLE LINK AND CURRENT-TRANSFORMER SUPPORTS FOR STANDARD SWITCHBOARD SERVICE STATIONS.








FIGURE 1 REMOVABLE LINK ASSEMBLY FURNISHED BY MANUFACTURER SEE TABLE 1

FIGURE 2 DRILLING AND SPACING OF BUS



DETAIL 1 1/4-INCH X 5-INCH LINK (IV)



DETAIL 2 INSULATED SUPPORT FOR CURRENT TRANSFORMER (V)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 23 OF 24 Indicates Latest Revision | Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V 3,001<mark>-4,000A</mark> REMOVABLE LINK AND CURRENT-XFMR SUPPORT FOR INSTRUMENT XFMR COMPARTMENTS WITH 5-INCH BUS

IN	INSTRUMENT TRANSFORMER COMPARTMENT, 3,001-4,000A, DESCRIPTION LIST										
ITEM	DESCRIPTION										
$\langle 1 \rangle$	INSULATED TRANSFORMER SUPPORT										
2	1/4" X 20 CAPSCREW										
3	LINK										
4	WINDOW TYPE CURRENT TRANSFORMER										

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE MANUFACTURER SHALL SECURE THE REMOVABLE BUS LINK TO THE UPPER AND LOWER CT BUS UNITS USING 1/2-INCH HEX-HEAD STEEL BOLTS, NUTS (AS SHOWN) WITH A SPRING WASHER AND A NUT. THE SPRING WASHER MAY BE EITHER A CONE-TYPE (BELLEVILLE) OR A SPLIT-RING WASHER WITH A FLAT WASHER. BOLTS SHALL BE GRADE 5 (MINIMUM), AND LONG ENOUGH TO EXTEND A MINIMUM OF 1/2 INCH BEYOND THE NUT. WASHERS (BELLEVILLE OR FLAT) SHALL BE 2 1/4 INCHES (MINIMUM).
- (II) DRILL AND TAP TWO HOLES AS SHOWN ON THE OUTER UNITS FOR 1/4" X 20 CAPSCREWS.
- (III) CONSULT THE UTILITY FOR THE USE OF BUS BARS LARGER THAN 5 INCHES.
- (IV) SAME MATERIAL AS BUS
- (v) MATERIAL: INSULATING, NON-TRACKING

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 24 OF 24 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG517.24

STANDARD SWITCHBOARD SERVICE SECTIONS 0-600V 3,001<mark>-4,000A</mark> REMOVABLE LINK AND CURRENT-XFMR SUPPORT FOR INSTRUMENT XFMR COMPARTMENTS WITH 5-INCH BUS SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR MOBILE HOME PARK SERVICE AND METER PEDESTALS THAT ARE SINGLE-FAMILY OR MOBILE HOME RESIDENTIAL SERVICES RATED 100A MINIMUM, 225A MAXIMUM, SINGLE-PHASE, 120/208V OR 120/240V.




FIGURE 1 TYPICAL UNDERGROUND SERVICE AND METER POST/PEDESTAL (B)(D)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 3

Indicates Latest Revision

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

Completely Revised

MOBILE HOME PARK SERVICE AND METER PEDESTALS

SG518.1

ELECTRIC SERVICE REQUIREMENTS FOR MOBILE HOME PARKS:

- A. UNDERGROUND ELECTRIC SERVICE TO A MOBILE HOME LOT IS TO BE INSTALLED ALONG THE SHORTEST, MOST PRACTICAL ROUTE FROM THE SDG&E (UTILITY) SOURCE TO THE NEAREST METER AND SERVICE LOCATION ACCEPTABLE TO THE UTILITY. THIS LOCATION MAY BE:
 - 1. ON A PERMANENTLY INSTALLED STRUCTURE LOCATED NEAR THE LOT LINE OF THE MOBILE HOME LOT CLOSEST TO THE UTILITY'S SOURCE.
 - 2. A UTILITY-APPROVED METER POST/PEDESTAL LOCATED AT OR NEAR THE CLOSEST CORNER OF THE MOBILE HOME LOT TO THE UTILITY'S SOURCE.
 - 3. IN ACCORDANCE WITH TITLE 25, ARTICLE 7, SECTIONS 1322, 1333, AND 1333.5, MOBILE HOMES, MANUFACTURED HOMES, OR COMMERCIAL COACHES, INSTALLED ON FOUNDATION SYSTEMS ARE PERMITTED TO BE SERVED BY THE UTILITY IN A MANNER APPLICABLE TO BUILDINGS. THE LOCATION OF THE METER AND SERVICE EQUIPMENT WILL BE DETERMINED BY THE UTILITY'S PLANNER. (b)
 - 4. EACH MOBILE HOME PARK SPACE/UNIT CONSTRUCTED AFTER JANUARY 1, 1997, MUST BE INDIVIDUALLY SERVED BY THE UTILITY.
 - 5. PUBLIC UTILITIES CODE SECTIONS 2791 THROUGH 2799 IS A RESULT OF ASSEMBLY BILL 622 AND OUTLINES THE PROCESS WHEREBY THE OWNER OF A MOBILE HOME PARK MAY TRANSFER OWNERSHIP OF THE PARK'S DISTRIBUTION SYSTEM TO THE UTILITY. CONTACT THE PROJECT MANAGEMENT REGIONAL OFFICE NEAREST TO THE MOBILE HOME PARK LOCATION AND REQUEST INFORMATION FOR TRANSFER OF OWNERSHIP TO THE UTILITY. (a) (c)
- B THE SERVICE AND METERING EQUIPMENT SHALL BE TESTED, LISTED AND LABELED BY A NATIONALLY RECOGNIZED TESTING LABORATORY. THIS SERVICE AND METERING EQUIPMENT SHALL BE INSTALLED PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND UTILITY STANDARDS. AN ELECTRICAL INSPECTION CLEARANCE FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) MUST BE GIVEN TO THE UTILITY BEFORE SERVICE CAN BE ESTABLISHED AND A METER SET.
- (C) THE METER SOCKET SHALL BE PROVIDED WITH A SEALING RING. THE METER SOCKET SHALL BE MOUNTED ON A SUPPORT AND ATTACHED TO THE METER PANEL. THE SOCKET SHALL BE FACTORY-WIRED WITH THE CONDUCTORS IN A SEPARATE OR BARRIERED RACEWAY FROM THE SERVICE TERMINATING LUGS TO THE METER SOCKET. THESE CONDUCTORS SHALL BE INACCESSIBLE FROM THE MAIN DISCONNECT AND POWER OUTLET SECTION. THE CONDUCTORS WHICH EXTEND TO THE METER SOCKET SHALL BE CONNECTED AT THE SERVICE TERMINATING LUGS INDEPENDENTLY OF THE CONNECTION FOR THE SERVICE LATERAL CONDUCTORS. THE MINIMUM METER HEIGHT IS 36 INCHES ABOVE GRADE LINE WHEN THE METER IS ENCLOSED, OR 48 INCHES MINIMUM IF EXPOSED. METER PANELS SHALL BE REMOVABLE, BUT SHALL BE NON-REMOVABLE WHEN THE METER IS IN PLACE. IF THE METER IS ENCLOSED, THE ENCLOSING COVER SHALL BE HINGED AND SELF-SUPPORTING, EQUIPPED WITH A READING WINDOW, AND BE REMOVABLE FOR METER TESTING OR INSPECTION.
- D THE SERVICE MAIN DISCONNECT AND POWER OUTLET SECTION SHALL HAVE BARRIERS INSTALLED TO PREVENT ACCESS TO THE SERVICE CABLE PULL AND TERMINATING SECTION AND TO UNMETERED CONDUCTORS WHICH CONNECT TO THE SOCKET.
- E THE SERVICE CABLE PULL AND TERMINATING SECTION SHALL BE COVERED WITH A SEALABLE AND REMOVABLE PANEL OR PANELS, EXTENDING FROM 2 INCHES TO 6 INCHES ABOVE GRADE, AND WHEN REMOVED, GIVE FULL ACCESS TO THE SERVICE TERMINATING LUGS. ACCESS TO THE SERVICE TERMINATING LUGS MAY BE EITHER THE FRONT OR THE REAR OF THE PEDESTAL. ACCESS SHALL BE UNRESTRICTED BY LOAD CONDUITS OR RACEWAYS.
- F A MINIMUM 12-INCH OPENING SHALL BE MAINTAINED FROM THE TERMINATING LUGS TO ANY FIXED PANEL BELOW THE LUGS. THE MINIMUM LUG HEIGHT IS 17 INCHES ABOVE GRADE LINE, THE MAXIMUM IS 48 INCHES. THE SERVICE TERMINATING LUGS SHALL BE NO. 2 TO 250 KCMIL ALUMINUM BODIED PRESSURE TYPE FOR CONNECTION OF THE SERVICE LATERAL CONDUCTORS. A SINGLE TERMINATING LUG PER PHASE AND NEUTRAL IS PREFERRED. IF TWO TERMINATING LUGS ARE PROVIDED PER PHASE, THE UTILITY REQUIRES ONE OF THE LUG'S SET SCREW TO BE REMOVED AND THE HOLE TO BE FILLED WITH A COMPOUND ACCEPTABLE TO THE MANUFACTURER. THIS REQUIREMENT IS NECESSARY TO AVOID ENERGY DIVERSION. THE SPACE BETWEEN TERMINATING LUGS, FROM LUGS TO SIDES OF POST, OR FROM LUGS TO PANEL ABOVE, SHALL BE 1 1/2 INCHES MINIMUM. RIGID INSULATING BARRIERS ARE REQUIRED AND SHALL PROJECT 1/4 INCH MINIMUM BEYOND ANY ENERGIZED PARTS WHEN THIS SPACE IS REDUCED. TERMINATING LUGS MAY BE POSITIONED EITHER IN-LINE OR STAGGERED, AND ACCESS SHALL BE UNOBSTRUCTED WHEN ALL SERVICE CONDUCTORS ARE IN PLACE. THE NEUTRAL TERMINATING LUG SHALL BE BONDED TO THE POST/PEDESTAL.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. DR BY DSN APV **CHANGE** DR BY DSN APV **REV CHANGE** DATE **REV** DATE С F В **FORMATTING** EDM JIK 02/07/2025 Ε LSM CTG TPM 11/01/2017 Α **EDITORIAL CHANGES** D **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SHEET 2 OF 3

SG518.2

INSTALLATION (CONT'D):

- (G) THE POST/PEDESTAL SHALL HAVE A MINIMUM CROSS SECTIONAL DIMENSION OF 4" X 8" INSIDE DIMENSION. A FIXED PANEL SHALL EXTEND 2 INCHES MINIMUM AND 6 INCHES MAXIMUM ABOVE GRADE AND 18 INCHES MINIMUM BELOW GRADE.
- (H) THE MINIMUM DEPTH OF THE POST/PEDESTAL IN THE GROUND SHALL BE 24 INCHES WITH OPENINGS AT THE BASE TO PERMIT THE SERVICE LATERAL CONDUIT TO ENTER INTO THE POST/PEDESTAL WITHOUT CUTTING THE 24-INCH MINIMUM RADIUS BEND.

BILL OF MATERIALS: NONE

NOTES:

- $\left(ext{ I }
 ight)$ 2-inch service lateral conduit required for 100a. 3-inch service lateral conduit required for 200a.
- (II) AN ACCEPTABLE GROUNDING TERMINAL SHALL BE PROVIDED TO ACCOMMODATE THE RANGE OF GROUNDING CONDUCTOR SIZING AS SPECIFIED BY CALIFORNIA ELECTRICAL CODE FOR THE SIZE OF THE SERVICE EQUIPMENT.
- (III) A MOISTURE BARRIER, LOCATED BELOW ALL TERMINALS AND OTHER LIVE PARTS, OR ADEQUATE VENTILATION, SHALL BE PROVIDED TO INHIBIT THE CONDENSATION OF MOISTURE.
- IV. FOR AUTHORIZATION TO ATTACH TELEPHONE AND CABLE TV TERMINATING FACILITIES, CONSULT THE UTILITY.

REFERENCE:


- (a) FOR A LISTING OF THE REGIONAL OFFICES, SEE $\frac{\mathsf{SG021}}{\mathsf{SG021}}$.
- (b) SEE TITLE 25, ARTICLE 7, SECTIONS 1322, 1333, AND 1333.5.
- (c) SEE PUBLIC UTILITIES CODE, SECTIONS 2791-2799.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		СН	AN	GE	DR	BY	DSN	APV	DATE
С									F									
В	FORMAT	TING		EDM	JIK	-	-	02/07/2025	Е									
Α	EDITORIAL C	CHAN	GES	-	LSM	CTG	TPM	11/01/2017	D									
X Indicates Latest Revision					n	Con	npletely Rev	ised		New Page		Information R	emoved	i				

SHEET 3 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG518.3



MINIMUM DIMENSIONS										
SERVICE	Z (IN)									
1-PHASE	10 1/2									
3-PHASE	12 1/2									

TABLE 2

	COMMERCIAL METER PEDESTALS, 0-200A, ITEM DESCRIPTIONS
ITEM	DESCRIPTION
1	HINGED DEMAND RESET COVER WITH POLYCARBONATE VIEWING WINDOW
2	ENCLOSING COVER
3	WORKING SPACE FROM FACE OF PANEL REQUIRED
4	METER SOCKET
5	TEST-BYPASS SUPPORT
6	LANDING LUGS AND FACTORY INSTALLED CONDUCTORS
7	HANDLE
8	PROTECTIVE METALLIC BARRIER
9	PULL SECTION AND COVER
(10)	HINGED COVER WITH ATTACHED SIDES. SEE NOTE (VI) FOR FIXED TOP AND SIDES.
(11)	HINGED DEMAND RESET COVER
(12)	CUSTOMER SECTION

INSTALLATION:

2 OF 7

- A SERVICE CONDUCTORS ARE TO TERMINATE ON LANDING LUGS. THE SERVICE TERMINATION LUGS SHALL BE NO. 6 THROUGH 250 KCMIL PRESSURE-TYPE, CU-AL LISTED. INSULATED CABLE OR BUS SHALL BE INSTALLED BETWEEN THE LANDING LUGS AND THE TEST-BYPASS FACILITIES.
- B. INTERNAL EQUIPMENT ATTACHED TO THE OUTER WALLS OF THE ENCLOSURE SHALL BE SECURED IN PLACE WITH DEVICES THAT MAY NOT BE LOOSENED FROM THE OUTSIDE. SCREWS OR BOLTS REQUIRING SPECIAL TOOLS FOR INSTALLATION OR REMOVAL ARE NOT ACCEPTABLE.
- C A PROTECTIVE METALLIC BARRIER (16-GAUGE MINIMUM) SHALL BE INSTALLED BETWEEN THE UTILITY TERMINATION SECTION AND THE CUSTOMER DISTRIBUTION SECTION. THERE SHALL BE A 1/4-INCH MINIMUM CLEARANCE BETWEEN THE CUSTOMER SECTION AND PROTECTIVE BARRIER TO PREVENT SCREWS AND BOLTS FROM PROTRUDING INTO THE TERMINATION SECTION.
- D. TEST-BYPASS BLOCKS WITH RIGID INSULATING BARRIER SHALL BE FURNISHED, INSTALLED AND WIRED OR BUSSED TO THE METER SOCKET BY THE MANUFACTURER. CONNECTION SEQUENCE IS LINE-LOAD FROM LEFT TO RIGHT. EACH LINE AND LOAD POSITION SHALL BE CLEARLY IDENTIFIED BY 3/4 INCH MINIMUM BLOCK LETTER LABELING. TEST-BYPASS COVER PANELS SHALL BE SEALABLE AND FITTED WITH A LIFTING HANDLE. ALL PANELS EXCEEDING 16 INCHES IN WIDTH SHALL REQUIRE TWO LIFTING HANDLES.
- E. ALL UTILITY COMPARTMENTS [METER COVER, DEMAND RESET COVER AND UNDERGROUND PULL SECTION (UGPS)] SHALL BE SEALABLE AND PADLOCKABLE.
- F. FOR IDENTIFICATION PURPOSES, THE NUMERIC PORTION OF THE ADDRESS MUST BE PAINTED WITH WEATHERPROOF PAINT OR REFLECTIVE DECALS ON THE EXTERIOR FACE OF THE PORTION OF THE PEDESTAL FACING THE STREET OR DRIVABLE SURFACE IN NUMBERS AT LEAST 1 INCH.
- G. PLASTIC PADS ARE ACCEPTABLE, PROVIDED THE SUPPORTING PULL BOX IS FILLED WITH GRAVEL OR EARTH COMPACTED TO A MINIMUM OF 90 PERCENT. FOR OTHER STRUCTURAL MOUNTING AND SUPPORT OF THE PEDESTAL, CONSULT WITH THE SDG&E TRENCH INSPECTOR.
- H. SDG&E WILL NO LONGER SUPPLY TWO-WIRE, 120V SERVICE OR METERING TO PEDESTALS. SINGLE-PHASE SERVICE WILL BE THREE-WIRE REGARDLESS OF THE VOLTAGE, I.E. 120/208V, 120/240V, OR 240/480V. (b)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. DATE **REV REV** DR | BY | DSN | APV DR | BY | DSN | APV DATE CHANGE CHANGE C В FORMATTING/EDITORIAL CHANGES EDM | IWA | JTM | KRG |02/07/2025 Ε CTG TPM 11/01/2017 Α **EDITORIAL CHANGES** LSM **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG519.2

COMMERCIAL METER PEDESTALS 0-200A

INSTALLATION (CONT'D):

J. TO MAINTAIN A SAFE, CLEAR AND LEVEL WORKING SPACE WHEN A HOUSEKEEPING PAD HAS NOT BEEN INSTALLED, A CONCRETE SLAB ACCEPTABLE TO THE SDG&E INSPECTOR IS REQUIRED. THIS REQUIREMENT IS FOR PEDESTALS ON PRIVATE PROPERTY AND DOES NOT APPLY TO PEDESTALS INSTALLED IN PARKWAY AREAS OF THE STREET WHERE THERE IS A SIDEWALK.

BILL OF MATERIALS: NONE

NOTES:

- I) THE PULL SECTION FOR UTILITY SERVICE MAY BE LOCATED ON THE FRONT, BACK OR SIDE OF A METER PEDESTAL, DEPENDING ON THE MANUFACTURER.
- (II) METER SECTION BARRIER TO EXTEND TO EDGE OF TEST BLOCK BARRIER.
- (III) 400A SINGLE-PHASE IS ACCEPTABLE FOR DUAL PEDESTALS.
- (IV) UTILITY TERMINATION SECTION SHALL BE DIMENSIONED AS SHOWN IN FIGURE 3. THESE DIMENSIONS ARE THE MINIMUM ACCESS OPENINGS ALLOWED FOR THESE TYPES OF TERMINATION SECTIONS. THE DEPTH OF THE WIREWAY SHALL ACCEPT A MINIMUM 3-INCH CONDUIT, AND THE COVER SHALL BE EQUIPPED WITH A LIFTING HANDLE.
- V. PEDESTALS SERVING BOTH METERED AND UNMETERED LOADS, I.E. TRAFFIC SIGNALS AND STREET LIGHTING, MUST HAVE LANDING LUGS, WITH CUSTOMER WIRE FROM LUGS TO TEST BLOCKS (IF NOT BUSSED) TO SERVE METERED LOADS AND FROM LUGS TO BREAKERS TO SERVE UNMETERED LOADS.
- (VI) THE METER SHALL BE ENCLOSED AND THE ENCLOSING COVER SHALL BE HINGED TO ALLOW THE TOP, FRONT AND SIDES TO ROTATE BACK EXPOSING THE METERING COMPARTMENT IN ORDER TO PROVIDE CLEARANCES.
- VII. RESIDENTIAL TYPE PEDESTALS ARE NOT ACCEPTABLE FOR TEMPORARY CONSTRUCTION POWER FOR ANY TYPE OF PREMISES. TO SERVE TEMPORARY POWER, A METER PEDESTAL WITH TEST-BYPASSES, OR A PROPERLY MOUNTED SAFETY SOCKET CAN IS REQUIRED. (a)
- VIII. PHOTOELECTRIC CELLS ARE NOT PERMITTED IN THE UTILITY AREA, I.E. UGPS/METER SECTION.
- IX. FOR METER PEDESTAL FOUNDATION DETAILS, SEE SHEET 6.

REFERENCE:


- (a) SEE SG514
- (b) FOR FIELD REPLACEMENT OF AN EXISTING 120V METER PEDESTAL, SEE SG520.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	HAN	IGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING/EDITO	ORIA	L CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е									
Α	EDITORIAL C	CHAN	IGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Completely Revised New Page Information Removed							ı				
	SHFFT		SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															

SHEET 3 OF 7

COMMERCIAL METER PEDESTALS 0-200A

SG519.3



4 OF 7

SG519.4

COMMERCIAL METER PEDESTALS 600A MAXIMUM

COM	COMMERCIAL METER PEDESTALS, 600A MAXIMUM, ITEM DESCRIPTIONS											
ITEM	DESCRIPTION											
1	METER SOCKET											
2	TEST-BYPASS SUPPORT											
3	HINGE DEMAND RESET COVERS WITH POLYCARBONATE VIEWING WINDOW											

INSTALLATION:

- A. TERMINATING FACILITIES FOR THE UTILITY'S SERVICE LATERAL CONDUCTORS SHALL BE ALUMINUM-BODIED MECHANICAL LUGS WITH A RANGE ACCEPTING A 4 AWG THROUGH 500 KCMIL CONDUCTOR. TWO LUGS PER PHASE SHALL BE PROVIDED FOR TERMINATIONS RATED 401–600A IN THIS METER PEDESTAL APPLICATION.
- B. INTERNAL EQUIPMENT ATTACHED TO THE OUTER WALLS OF THE ENCLOSURE SHALL BE SECURED IN PLACE WITH DEVICES THAT MAY NOT BE LOOSENED FROM THE OUTSIDE. SCREWS OR BOLTS REQUIRING SPECIAL TOOLS FOR INSTALLATION OR REMOVAL ARE NOT ACCEPTABLE.
- C. A PROTECTIVE METALLIC BARRIER (16-GAUGE MINIMUM) SHALL BE INSTALLED BETWEEN THE UTILITY TERMINATION SECTION AND THE CUSTOMER DISTRIBUTION SECTION.
- D. TEST-BYPASS BLOCKS WITH RIGID INSULATING BARRIER SHALL BE FURNISHED, INSTALLED AND WIRED OR BUSSED TO THE METER SOCKET BY THE MANUFACTURER. CONNECTION SEQUENCE IS LINE-LOAD FROM LEFT TO RIGHT. EACH LINE AND LOAD POSITION SHALL BE CLEARLY IDENTIFIED BY 3/4-INCH MINIMUM BLOCK LETTER LABELING. TEST-BYPASS COVER PANELS SHALL BE SEALABLE AND FITTED WITH A LIFTING HANDLE. ALL PANELS EXCEEDING 16 INCHES IN WIDTH SHALL REQUIRE TWO LIFTING HANDLES.
- E. ALL UTILITY COMPARTMENTS (METER COVER, DEMAND RESET COVER AND UGPS) SHALL BE SEALABLE AND PADLOCKABLE.
- F. FOR IDENTIFICATION PURPOSES, THE NUMERIC PORTION OF THE ADDRESSES MUST BE PAINTED WITH WEATHERPROOF PAINT OR REFLECTIVE DECALS ON THE EXTERIOR FACE OF THE PORTION OF THE PEDESTAL FACING THE STREET OR DRIVABLE SURFACE IN NUMBERS AT LEAST 1 INCH HIGH.
- G. WHEN SERVICE EQUIPMENT IS INSTALLED ON A "HOUSEKEEPING PAD", THAT PAD MUST BE LEVEL AND EXTEND A MINIMUM OF 3 FEET MEASURED FROM THE FACE OF THE METER PANEL. SEE THE FIGURES ON SG517 UNDER THE "OUTDOOR/RAINTIGHT ENCLOSER (NEMA 3R) SCOPE, AS THEY ALSO APPLY TO THIS INSTALLATION. (a)

BILL OF MATERIALS: NONE

NOTES:

- $\left(\ \mathrm{I} \
 ight)$ weatherproof door removed meter and test block barriers in place
- II. COMMERCIAL METER PEDESTALS RATED 401–600A REQUIRE THREE-PHASE, 4-WIRE SERVICE. SINGLE-PHASE SERVICE IS NOT AVAILABLE FOR COMMERCIAL APPLICATIONS 401A, AND LARGER.
- III. THIS EQUIPMENT IS DESIGNED FOR A MAXIMUM OF THREE METER SOCKETS.
- IV. PHOTOELECTRIC CELLS ARE NOT PERMITTED IN THE UTILITY AREA, I.E. UGPS/METER SECTION.

REFERENCE:

(a) SEE SG517.


5 OF 7

b. FOR WORKING SPACE AND CLEARANCE REQUIREMENTS, 0-600V, SEE SG504.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.													
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С								F						
В	FORMATTING/EDITO	ORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL (CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
		X Indicates La	ates Latest Revision Completely Revised New Page X Information Removed											
SHEET SDG&E ELECTRIC SERVICE STANDARDS & GUIDES														
SILLI COMMEDIAL METER REDECTALS									SG519.5					

COMMERCIAL METER PEDESTALS

600A MAXIMUM



	METER PEDESTAL FOUNDATION DETAILS								
ITEM	DESCRIPTION								
1	CUSTOMER SECTION								
2	CONCRETE SLAB								
3	CONCRETE FOOTING								
4	ONE SACK SLURRY								
(5)	CONCRETE PRE-CAST BASE								
6	CONCRETE								
7	BASE BRACKET								
8	STRUCTURAL PLASTIC SUPPORT BOX UNDER FRP PADS								
9	FIBERGLASS REINFORCED POLYMER (FRP) PADS								

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

(I) <u>TABLE 2</u>

METER HEIGHT REQUIREMENTS										
TYPE MIN. HEIGHT (IN) MAX. HEIGHT										
ENCLOSED	36	C/ 2//								
EXPOSED	48	6′-3″								

(II) COMPACTED DIRT TO TOP OF THE PLASTIC SUPPORT BOX.

(III) PEDESTAL NOT SHOWN.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 7 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

COMMERCIAL METER PEDESTALS FOUNDATION DETAILS

SG519.7

SCOPE: THIS STANDARD APPLIES TO FIELD REPLACEMENT OF EXISTING 120V METER PEDESTALS FOR RESIDENTIAL SERVICE ONLY.

ATTENTION:

* THE REPLACEMENT OPTION IS NOT AVAILABLE FOR NON-RESIDENTIAL APPLICATIONS IN WHICH CASE A NEW SINGLE-PHASE 3-WIRE, 120/240V COMMERCIAL PEDESTAL IS REQUIRED. (a)




FIGURE 1
METER PEDESTAL (III)
SEE TABLE 1

TABLE 1

	FIGURE ITEMS											
ITEM	DESCRIPTION	DETAILS										
1	ELECTRODE, APPROVED GROUNDING	TYPICAL LENGTH IS 8 FEET.										
2	BREAKER COMPARTMENT (IV)											
3	LUG, PEDESTAL BOND	MAY BE A BAND SCREW IN SOME MODELS										
4	LANDING BLOCK, NEUTRAL, CUSTOMER'S											
(5)	LOAD CONDUCTORS	SHALL NOT BE RUN THROUGH UTILITY'S UGPS										
6	GROUND WIRE, NO. 4 BARE COPPER											

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/INSTALLATION UPDATE	EDM	IWA	JTM	KRG	02/07/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SUGAE ELECTRIC SERVICE STANDARDS & GUIDE

SG520.1

FIELD REPLACEMENT OF EXISTING 120V METER PEDESTAL

- (A) THE METER SOCKET, BREAKER COMPARTMENT AND UNDERGROUND PULL SECTION (UGPS) MUST BE RAINTIGHT EQUIPMENT. METER SOCKET JAWS OR CLIPS SHALL BE FREE OF FOREIGN MATERIAL (MUD, PAINT, PLASTER, ETC.). RINGLESS METER SOCKETS ARE NOT ACCEPTABLE. THE SOCKET SHALL HAVE A MINIMUM RATING OF 100A AND BE FACTORY-WIRED WITH THE CONDUCTORS IN A SEPARATE OR BARRIERED WIREWAY FROM THE SERVICE TERMINATION LUGS TO THE METER SOCKET. THE CONDUCTORS WHICH EXTEND TO THE METER SHALL BE CONNECTED AT THE SERVICE TERMINATION LUGS INDEPENDENT OF THE CONNECTIONS FOR THE SERVICE LATERAL CONDUCTORS. THE MINIMUM METER HEIGHT SHALL BE 48 INCHES, MEASURED FROM THE STANDING SURFACE TO CENTERLINE OF METER SOCKET. IF THE METER IS ENCLOSED, THE MINIMUM HEIGHT MAY BE REDUCED TO 36 INCHES.
- (B) A MINIMUM 12-INCH OPENING SHALL BE MAINTAINED FROM THE TERMINATING LUGS TO ANY FIXED PANEL BELOW THE LUGS. THE MINIMUM LUG HEIGHT IS 17 INCHES ABOVE GRADE LINE, THE MAXIMUM IS 48 INCHES. THE SERVICE TERMINATING LUGS SHALL BE NO. 8 TO NO. 2 ALUMINUM-BODIED PRESSURE TYPE FOR CONNECTION OF THE SERVICE LATERAL CONDUCTORS.
- (C) THE GROUND WIRE SHALL BE CONTINUOUS FROM THE NEUTRAL LANDING BLOCK IN THE BREAKER COMPARTMENT TO A GROUNDING ELECTRODE SYSTEM IN COMPLIANCE WITH NEC ARTICLE 250. THE GROUND WIRE MUST BE PROPERLY SUPPORTED AND ATTACHED TO THE OUTSIDE OF THE PEDESTAL AT 24-INCH INTERVALS. WHEN ATTACHING THE GROUND WIRE TO THE PEDESTAL, THE METHOD OF ATTACHMENT SHALL NOT RESULT IN SHARP PROJECTIONS, SUCH AS METAL SCREWS INTO THE WIRE WAY BELOW THE NEUTRAL LANDING BLOCK. SEE FIGURE 1 FOR THE PREFERRED METHOD OF INSTALLING THE GROUNDING ELECTRODE CONDUCTOR.
- D THE UTILITY'S UGPS SHALL BE COVERED WITH A SEALABLE, REMOVABLE PANEL, EXTENDING FROM AT LEAST 2 INCHES TO 6 INCHES ABOVE THE CONCRETE PAD, AND WHEN REMOVED, ALLOW FULL ACCESS TO THE SERVICE TERMINATION LUGS. ACCESS TO THE UTILITY UGPS SHALL NOT BE BLOCKED IN ANY MANNER. NO CUSTOMER WIRING OR EQUIPMENT IS ALLOWED IN THIS AREA.
- THE PEDESTAL AT GRADE LINE SHALL HAVE A MINIMUM CROSS-SECTIONAL DIMENSION OF 4" X 8" INSIDE DIMENSION. THE FIXED PANEL FOR THE FINAL GRADE AND CONCRETE POUR SHALL EXTEND 2 INCHES TO 6 INCHES ABOVE GRADE AND A MINIMUM OF 18 INCHES BELOW GRADE. THE PEDESTAL SHALL EXTEND 24 INCHES BELOW GRADE. THAT PORTION OF THE PEDESTAL BURIED IN CONCRETE AND EARTH SHALL BE COATED WITH AN APPROVED CORROSION-RESISTANT MATERIAL SUCH AS ZINC, CADMIUM OR ENAMEL TO WITHSTAND DETERIORATION. POURED CONCRETE SLAB SHALL BE 24" X 24" MINIMUM SIZE AND HAVE A 3 1/2-INCH MINIMUM THICKNESS. THE CUSTOMER SHALL BE RESPONSIBLE FOR THE FINAL GRADE OF THE UTILITY ISLAND AND THE INCLUDED METER PEDESTAL.
- (F) THE APPROVED GROUND ELECTRODE CLAMP AND CONDUCTOR SHALL BE BURIED, FLUSH OR SOMEHOW PROTECTED FROM PHYSICAL DAMAGE. THE CLAMP SHALL BE LISTED FOR UNDERGROUND USE. GROUND ROD SHALL NOT BE INSTALLED IN OR BENEATH THE CONCRETE SLAB.
- G. THE NEW PEDESTAL INSTALLATION SHALL BE INSPECTED AND APPROVED BY THE AHJ BEFORE THE UTILITY CAN ENERGIZE AND SET THE METER.

BILL OF MATERIALS: NONE

NOTES:

GENERAL INFORMATION:

- I. SDG&E (UTILITY) PLANNER APPROVAL IS REQUIRED IN ADVANCE OF REPLACING AN EXISTING 120V, SINGLE-PHASE, 2-WIRE METER PEDESTAL.
- II. THE REPLACEMENT PEDESTAL SHALL BE LISTED AS EQUIPMENT SUITABLE FOR USE AS SERVICE EQUIPMENT AND MEET ALL REQUIREMENTS OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) AND UTILITY. THE TOTAL AMPACITY OF THE BREAKERS IS NOT TO EXCEED 30A, WITH NO MORE THAN 2 BREAKERS.
- (III) FIGURE 1 IS AN ILLUSTRATION OF THE PEDESTAL AND A LIST OF MATERIALS FOR A NORMAL METER PEDESTAL REPLACEMENT. THIS IS NOT INTENDED TO BE ALL INCLUSIVE BUT PROVIDES THE MOST COMMON REQUIREMENTS.
- (IV) THE PEDESTAL SHALL HAVE A MINIMUM 10,000A WITHSTAND RATING AND THE BREAKER(S) SHALL HAVE A MINIMUM 10,000A INTERRUPTING CAPACITY (AIC) RATING.

REFERENCE:


(a) SEE SG519: COMMERCIAL METER PEDESTALS.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV DR BY DSN APV CHANGE DATE **REV CHANGE** DATE С F В FORMATTING/INSTALLATION UPDATE EDM | IWA | JTM KRG 02/07/2025 Ε **EDITORIAL CHANGES** LSM CTG TPM 11/01/2017 Α **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET


SHEET 2 OF 2

FIELD REPLACEMENT OF EXISTING 120V METER PEDESTAL SG520.2


SCOPE: THIS STANDARD ESTABLISHES THE REQUIREMENTS FOR INSTALLING NEW ELECTRIC SERVICE AND METERING FOR WIRELESS COMMUNICATION SYSTEMS ON PRIVATE PROPERTY.



SCENARIO I COMMUNICATION SYSTEM LOCATED IN OR ON A BUILDING \overline{D} \overline{E}



SCENARIO II
COMMUNICATION ANTENNAE LOCATED IN OR ON A BUILDING WITH DE
COMMUNICATION EQUIPMENT REMOTE FROM BUILDING



SCENARIO III
COMMUNICATION SYSTEM COMPLETELY SEPARATE FROM A RESIDENTIAL OR
COMMERCIAL/INDUSTRIAL STRUCTURE WITH AN EXISTING ELECTRIC SERVICE

FIGURE 1

EXAMPLES OF ACCEPTABLE METER AND SERVICE LOCATIONS TO COMMUNICATION SYSTEMS (C)

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHANGE			DR	BY	DSN	APV	DATE	REV		С	HAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMATTING				JIK	-	-	02/07/2025	Е									
Α	EDITORIAL (CHAI	NGES	-	LSM	BRB	TPM	11/01/2017	D									
	X Indicates Latest Revision						Completely Revised New Page Information Removed					ı						
	SHEET	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																
	30EE1															S	G52	2.1

WIRELESS COMMUNICATIONS ON PRIVATE PROPERTY

1 OF 2

GENERAL INFORMATION:

- A. A COMMUNICATION SYSTEM INCLUDES A COMMUNICATION EQUIPMENT ENCLOSURE AND COMMUNICATION ANTENNAE.
- B. WHEN AN EXISTING METER ROOM OR CABINET DOES NOT HAVE SPACE REMAINING TO GROUP THE NEW METER PANEL WITH THE EXISTING, SPECIAL PERMISSION MAY BE GRANTED BY THE SDG&E PLANNER AND THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) TO LOCATE THE NEW METER PANEL AND METER SERVICE DISCONNECT AS CLOSE AS PRACTICAL TO THE EXISTING METER LOCATION OUTSIDE THE METER ROOM OR CABINET.
- (C) IT IS IMPORTANT TO NOTE THAT A STRUCTURE INCLUDES A WATER TANK, LIGHT POLE, AND SIMILAR TYPES OF CONSTRUCTION.
- D THE ELECTRIC SERVICE TO THE COMMUNICATION SYSTEM SHALL BE SERVED FROM THE EXISTING BUILDING SERVICE. THE NEW METER SHALL BE GROUPED WITH THE EXISTING METER(S) IN ACCORDANCE WITH ALL OTHER SERVICE STANDARDS REQUIREMENTS.
- (E) THE ANTENNAE LOCATION MAY BE IN OR ON THE BUILDING, OR REMOTELY LOCATED FROM THE BUILDING.

BILL OF MATERIALS: NONE

NOTES:

- $oxed{(\hspace{1pt}\hspace{1pt}\hspace{1pt}\hspace{1pt}}$) a new meter panel and service on the equipment enclosure separate from the building is acceptable.
- (II) A NEW SERVICE AND METER PEDESTAL MAY BE INSTALLED SEPARATE FROM THE BUILDING AND EQUIPMENT ENCLOSURE. THE METER PEDESTAL SHALL NOT BE LOCATED WITHIN THE REQUIRED PROPERTY LINE SETBACKS ESTABLISHED BY THE AHJ. THE CUSTOMER IS TO CONSULT WITH THE AHJ FOR SETBACK REQUIREMENTS.
- m (III) a new meter panel grouped with existing building meter(s) is acceptable.
- IV. THE CALIFORNIA ELECTRICAL CODE REQUIRES THAT GROUNDING SYSTEMS MUST BE ELECTRICALLY BONDED TO ONE ANOTHER WHEN MULTIPLE SERVICES MAINTAIN ELECTRICAL AND/OR COMMUNICATIONS SYSTEMS ON THE SAME STRUCTURE.

REFERENCE: NONE

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHANGE			DR	BY	DSN	APV	DATE	REV		CH	IAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	FORMAT	FORMATTING			JIK	-	-	02/07/2025	Е									
Α	EDITORIAL (CHAN	IGES	-	LSM	BRB	TPM	11/01/2017	D									
	X Indicates Latest Revision						Completely Revised				New Page		Information Removed					
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	


SHEET 2 OF 2

SG522.2

SCOPE: THIS STANDARD SHOWS A CUSTOMER OWNED AND INSTALLED WIRELESS COMMUNICATIONS ANTENNA ATTACHMENT ON AN SDG&E WOOD POLE.

ATTENTION

* THIS CONSTRUCTION IS NOT ALLOWED ON A POLE WITH EQUIPMENT OR SWITCHES INSTALLED. (A)



								_				
RE	CHANGE	DRWN	BY	СНКД	APVD	DATE						
D	EDITORIAL CHANGES	EDM	JIK	JTM	KRG	01/03/2025	SDGE					
С	REVISED TO 3D FORMAT	NV5	JIK	-	-	07/22/2022	SOUL					
В	DRAWING UPDATE	PEI	-	-	-	03/18/2019						
(© 1998 - 2025 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.											

SDG&E ELECTRIC OVERHEAD, UNDERGROUND, AND SERVICE GUIDE CONSTRUCTION STANDARDS

CUSTOMER-OWNED WIRELESS COMMUNICATIONS

PROVIDER ATTACHMENT TO DISTRIBUTION POLE

(METERED SERVICE)

Indicates Latest Revision

Completely Revised

New Page

SCALE: NOT TO SCALE

DRAWING NO:

SHEET:

0H575.1

UG4650.1

SG523.1

- (A) DO NOT INSTALL A TELECOMMUNICATION ANTENNA ON A POLE CONTAINING A SINGLE-PHASE TRANSFORMER, THREE-PHASE TRANSFORMER, BOOSTER, SERVICE RESTORER, CAPACITOR, REGULATOR, PRIMARY METERING, HOOKSTICK OR GANG-OPERATED SWITCH, CUTOUTS OR PRIMARY RISERS.
- (B) A MINIMUM SIX FOOT OF VERTICAL AND RADIAL CLEARANCE MUST BE MAINTAINED FROM THE TELECOMMUNICATIONS ANTENNAS OR SUPPORTING EQUIPMENT TO SDG&E SUPPLY CONDUCTOR LEVEL.
- C ANTENNAS AND SUPPORTING ELEMENTS SHALL MAINTAIN A MINIMUM 24 INCHES OF VERTICAL SEPARATION FROM COMMUNICATION CONDUCTORS AND EQUIPMENT.
- D ANTENNAS SHALL BE INSTALLED ON CROSSARMS AND MAINTAIN 24 INCHES HORIZONTAL CLEARANCE FROM THE CENTERLINE OF POLE.
- (E) ANTENNAS SHALL MAINTAIN 36 INCHES VERTICAL AND RADIAL CLEARANCE FROM STREET LIGHTS AND MAST ARMS.
- F THIS INSTALLATION MUST BE CLEARLY MARKED WITH THE APPROPRIATE SIGNAGE, PER FCC, CPUC AND UTILITY REGULATIONS. SIGNAGE TO BE INSTALLED AND MAINTAINED BY THE TELECOMMUNICATION ANTENNA OWNER. (9)
- (G) THESE ITEMS SUPPLIED AND INSTALLED BY THE TELECOMMUNICATION ANTENNA OWNER.
- A MUNICIPALLY APPROVED RF POWER SHUTOFF DISCONNECT, WITH TEST POINTS, WILL BE INSTALLED AND CLEARLY MARKED BY THE TELECOMMUNICATION ANTENNA OWNER. THIS DISCONNECT, WHEN OPEN, WILL PREVENT THE ANTENNAS FROM GENERATING RADIO FREQUENCY (RF), INCLUDING WHEN ON BATTERY BACK-UP PER NEC. MAINTAIN A MINIMUM OF 36 INCHES DEEP BY 30 INCHES WIDE CLEAR WORKING SPACE. (f)
- (J) A CUT-AWAY LOCK WILL BE PROVIDED BY THE TELECOMMUNICATION ANTENNA OWNER FOR SECURING THE RF POWER SHUTOFF DISCONNECT.
- (K) A CLEAR AND LEVEL WORKING SPACE WITH BOTH A WIDTH AND DEPTH OF 36 INCHES MUST BE MAINTAINED FROM FACE OF METER PANEL.
- (L) MAST MUST BE GROUNDED.

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	CALLOUTS	STANDARD PAGE	STOCK NUMBER	DESIGN UNIT
1	CROSSARM, WD, PENTA, 10', 4 PIN	2	GIII	380	S294128	4-
2	CUSTOMER-OWNED ANTENNA, DIRECTIONAL OR OMNI-DIRECTIONAL	4	(-	-	-
3	TAG, OWNERSHIP I.D.	1	(F)	209	-	-
4	BRACKET, LADDER ARM, STL, GLV	10	(9)	-	S167186	RARM/L
5	CHANNEL, 1-5/8" X 1-5/8" BACK TO BACK	10	(-	S216702	RARM/L
6	NUT, STUD, GLV, 1/2" X 1-3/8"	20	G	-	S507000	LA-ARM
7	WIRE, PVC COVERED, #4 SOL CU	1	GЬ	718	S812490	4POLY
8	GALVANIZED STAPLES FOR PVC COVERED GROUND WIRE	22	<u> </u>	-	S678564	-
9	5/8" GROUND ROD CONNECTOR	1	G	-	S259010	-
10	ROD, GROUND, 5/8" X 8FT, 10 MIL COPPER COATED STEEL	1	G	1002	S603074	GNDPSP
			G			GNDPVC
11	CUSTOMER-OWNED ANCILLARY EQUIPMENT	1	ΊV	-	-	-
12	WASHER 5/8" DOUBLE COIL SPRING TYPE	12	ΊV	-	S798560	-
13	WASHER SQUARE, 2-1/4" X 2-1/4"	3	ΊV	-	S799040	-
14	WASHER, FLAT, SQUARE, 4" X 4" X 3/8", 13/16" HOLE, STEEL GALV	8	ΙV	379	S800070	-
15	BOLT, MACHINE, 5/8" X 16", GALV W/ NUT	4	(11)(11)	-	S154912	-
16	SIGN, "HIGH VOLTAGE", 3", ADHESIVE	4	(II)(IV)	208	S647650	-
17	SIGN, PRINTED "PN" IN 3" X 1-1/8"	2	(II)(IV)	208	S648004	GNDPVC
18	INSULATOR, 25KV, "F" NECK, PIN TYPE 1-3/8"	3	(II)(IV)	-	S429054	-
19	INSULATOR, WHITE, NEUTRAL, 55-5 HENDRIX	1	(II)(IV)	-	S432220	-
20	PIN, INSULATOR, 12KV, FORGED STEEL, GALV	4	(II)(IV)	396	S532450	PS1Z
21	BRACE, CROSSARM, ANGLE, 5FT, 1 1/2" X 3/16", STEEL, GALVANIZED	2	ΊV	390	S164128	-
22	BRACKET, WIREHOLDER, 1-1/4" TO 2-1/2"	1	-	631	S166880	-
23	BRACKET, UPSWEEP, STREET LIGHTING,	1	-	-	S167264	-

BILL OF MATERIALS (CONT'D):

ITEM	DESCRIPTION	QUANTITY	CALLOUTS	STANDARD PAGE	STOCK NUMBER	DESIGN UNIT
24	041320 LUMINAIRE, COBRAHEAD, ST LIGHT	1	-	-	S473400	-
25	CONTROL, PHOTOELECTRIC, SOLID STATE 120 VOLTS, 1800VA LOAD, TURN-ON 1.5 FC,	1	-	-	S273888	-
	TWISTLOCK SOLID BRASS BLADES PER ANSI C-136.10-19 A					
26	CLEVIS DEAD END SECONDARY INSULATOR WITH NEMA TR53-3 GRAY INSULATORS	1	-	-	S235488	-
	ASSEMBLED. STD. PKG. = 15					
27	CONDUIT, ELBOW, PVC, SCH 80, 3", RISER	4	(IV)	-	S322472	3"CP-B
28	COUPLING 3" PVC SCHEDULE 40, PER NEMA	2	(IV)	-	S280448	X-COND
29	GAIN, CROSSARM, 3/4" MAXIMUM BOLT SIZE	2	(IV)	388	S369596	-
30	SCREW, LAG, 1/2" X 4", TWIST DRIVE	2	ΊV	-	S621568	-
31	BOLT, MACHINE, 5/8" X 14", GALV W/ NUT	7	ΙV	390	S154880	-
32	BOLT, MACHINE, 3/4" X 12", GALV W/ NUT	1	(IV)	390	S153408	-
33	BOLT, MACHINE, 1/2" X 8", GALV W/ NUT	4	(IV)	390	S153150	-
34	WASHER, CURVED, RIB, 4" X 4" X 17/32", 13/16" HOLE, FOR 3/4" BOLT, GALV	16	(IV)	-	S797760	RIBWSH
35	WASHER, 3/4", DOUBLE COIL SPRING, TYPE M-W, STEEL, TIN/ZINC COAT	8	(IV)	-	S798496	-
36	NUT, SQUARE, 3/4", GALV	4	ΙV	-	S504768	-
37	WASHER, SPRING LOCK, 1/2", STAINLESS	20	(IV)	-	S796944	-
38	TIE INSUL TOP, FOR USE ON "F" NECK,	4	(IV)	760	S738900	ST336F
39	CONDUIT, PVC, SCH 80, 3" X 10'	2	(IV)	-	S251552	-
40	CLAMP, PIPE, STEEL, GALV., UNISTRUT, 3"	19	ΙV	-	S229632	UPC3IN
41	CONDUIT, PVC, SCH 40, 3" X 10'	8	ΊV	-	S251360	-
42	DO NOT USE-REPLACE WITH S505536 NUT, HEX S/S, 1/2"	20	(IV)	378, 1355	S550536	-
43	NUT, SQUARE, 5/8", GALV	20	(IV)	-	S506880	-
44	BOLT, MACHINE, 5/8" X 12", GALV W/ NUT	3	(IV)	390	S154848	-
45	WASHER, FLAT, ROUND, 1/2" X 1 3/8" OD, GALV	4	ΙV	-	S800192	•
46	WASHER, 1/2", DOUBLE COIL SPRING, TYPE M-W, STEEL, TIN/ZINC COAT	4	ΊV	-	S798464	-
47	SCREW, SELF-TAPPING, #5, 1-1/4", 12-24	11	(IV)	-	S618086	-
48	STRAP, GLV, 3/8", FOR #4	7	ΙV	-	S697304	-
49	PADLOCK, 30 SERIES, ALLOY, ELECTRIC	1	(IV)	-	S514848	-
50	BOLT, MACHINE, 5/8" X 18", GALV W/ NUT	1	(IV)	390	S154944	-

NOTES:

- (I) ANY COMMUNICATION ANTENNA ATTACHMENTS MUST COMPLY WITH SEE THE CPUC, G.O. 95, AND 128 PUBLICATIONS RULES.(d)
- II) ONE TELECOMUNICATION PROVIDERS ATTACHMENT (ANTENNA, ANCILLARY EQUIPMENT) PER POLE.
- (III) SIZE AND/OR TYPE MAY VARY DEPENDING UPON SPECIFIC DESIGN NEEDS.
- (IV) NOT SHOWN ON FIGURES

REFERENCE:


- (a) FOR ALLOWABLE WORKING AND CLIMBING SPACE, SEE 0H251.
- (b) FOR GROUNDING METHODS, SEE OH1002.
- (c) FOR RISER POSITION, SEE OH1402UG4206.
- (d) SEE THE CPUC, G.O. 95, AND 128 PUBLICATIONS RULES.
- (e) FOR RISER CONSTRUCTION, SEE 0H1404UG4204.
- f) SEE ESP124.
- (g) SEE SG209.

RE	CHANGE	DRWN	BY	CHKD	APVD	DATE		SDG&E ELECTRIC OVERHEAD, UNDERGROUND, AND SERVICE GUIDE CONSTRUCTION STANDARDS	SCALE: NOT TO) SCALE
D	EDITORIAL CHANGES	EDM	JIK	JTM	KRG	01/03/2025	CDCE	CUSTOMER-OWNED WIRELESS COMMUNICATIONS	DRAWING NO:	SHEET:
С	REVISED TO 3D FORMAT	NV5	JIK	-	-	07/22/2022	SDGE	PROVIDER ATTACHMENT TO DISTRIBUTION POLE	OH575.2 UG4650.2	2 OE 2
В	DRAWING UPDATE	PEI	-	-	-	03/18/2019		(METERED SERVICE)	SG523.2	2 0
(© 1998 - 2025 San Diego Gas and Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law							Indicates Latest Revision Completely Revised New Page	Information P	2emoved

SCOPE: THIS STANDARD ILLUSTRATES INSTALLATION OF UNMETERED ELECTRIC SERVICE FROM AN UNDERGROUND SOURCE.

ATTENTION:

- * THE INSTALLATION AND ALL MATERIALS SHOWN IN THE ILLUSTRATIONS BELOW ARE PROVIDED BY THE CUSTOMER.
- ** ALL INSTALLATIONS MUST COMPLY WITH THE REQUIREMENTS OF AND BE INSPECTED BY, THE AHJ AND SDG&E (UTILITY).







FIGURE 1 SIDE VIEW



WIRING DIAGRAM INSIDE FUSE SPLICE BOX

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C EDITORIAL CHANGES EDM IWA JTM KRG 02/07/2025 F B EDITORIAL CHANGES PEI/EM IPJ IPJ CZH 08/10/2021 E A EDITORIAL CHANGES - LSM BRB TPM 11/01/2017 D	REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
	С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	F						
A EDITORIAL CHANGES - LSM BRB TPM 11/01/2017 D	В	EDITORIAL CHANGES	PEI/EDM	IPJ	IPJ	CZH	08/10/2021	Е						
	Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 1 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SPORE ELECTRIC SERVICE STANDARDS & GOIDE.

FROM AN UNDERGROUND SOURCE

UNMETERED ELECTRIC SERVICE SG524.1

INSTALLATION:

- (A) mount fuse box securely on supports inside.
- (B) GRAVEL BASE SUITABLE FOR PROPER DRAINAGE REQUIRED.

BILL OF MATERIALS:

ITEM	DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	FUSE BOX				
2	PLAQUE, SUITABLE, FUSE BOX, IDENTIFICATION		SHEET 6		
3	HANDHOLE, CUSTOMER OWNED AND INSTALLED				
4	CABLE AND CONDUIT, CUSTOMER	AS REQ'D			
5	GROUNDING ELECTRODES				
6	GRAVEL BASE				
7	BREAKER				
8	FUSES				

NOTES:

- I. ALTERNATE FUSING METHODS:
 - a. FUSED DISCONNECT SUITABLE FOR UNDERGROUND APPLICATION, OR IN A SUITABLE ENCLOSURE.
- (II) FUSE BOX TO BE LOCKED AND SEALED BY SDG&E.

REFERENCE:

(a) SEE CEC/AHJ REQUIREMENTS

	© 1998 - 2025 San Diego Gas & E	lectric (Compa	ny. All	rights ı	reserved. Rer	noval o	of thi	is copyright notice	e without permission	is not	permi	tted un	der law	' .
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CHAI	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	F								
В	EDITORIAL CHANGES	PEI/EDM	IPJ	IPJ	CZH	08/10/2021	Е								
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D								
	X Indicates L	Revisio	n	Cor	npletely Revi	sed		New Page	Information Re	moved	d				

SHEET 2 OF 7

UNMETERED ELECTRIC SERVICE FROM AN UNDERGROUND SOURCE

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG524.2

SCOPE: THIS STANDARD ILLUSTRATES UNMETERED ELECTRIC SERVICE PLAQUE REQUIREMENTS.




FIGURE 1 TYPICAL PLAQUE CONFIGURATION

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. THE PLAQUE SHALL BE PLASTIC WITH ENGRAVED OR MACHINE PRINTED LETTERS IN CONTRASTING COLOR TO THE PLAQUE AND SHALL BE PERMANENTLY ATTACHED TO THE FUSE BOX WITH POP RIVETS OR SCREWS.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice w	

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	СНА	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	F							
В	EDITORIAL CHANGES	PEI/EDM	IPJ	IPJ	CZH	08/10/2021	Е							
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D							
	X Indicates La	atest R	evision	n	Cor	npletely Revi	ised	New Page	Information Re	emoved	d			

SHEET 3 OF 7

. INCVISION		completely Revised		itew rage		Information Removed
SDG&	ΕE	LECTRIC SERVICE STA	AND	ARDS & GL	JIDI	ES

UNMETERED ELECTRIC SERVICE PLAQUE REQUIREMENTS

SG524.3

SCOPE: THIS STANDARD SHOWS AND DESCRIBES THE INSTALLATION OF A CUSTOMER-OWNED FUSED SERVICE POLE. THIS INSTALLATION IS SUBJECT TO ALL REQUIREMENTS OF AND INSPECTION BY, THE AHJ AND SDG&E (UTILITY). -5" MIN. **T** 1 (F) (K)(P)(B)(C)(I)6'-0" MIN. $oldsymbol{\perp}$ SERVICE POINT OF ATTACHMENT 3 (A (L) 3'-0" (6)(S) (Q)(T) 4 (M) [2)(U) (c)[5] 6'-3" MAX. 4'-0" MIN. GROUND LINE **FIGURE 1 FIGURE 1** POLE DEPTH CONDUIT VIEW A-A © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV DR DSN APV **REV CHANGE** DR **DATE CHANGE** BY DATE С **EDITORIAL CHANGES EDM IWA** JTM KRG 02/07/2025 Ε В **EDITORIAL CHANGES** PEI/EDM IPJ IPJ CZH 08/10/2021 TPM 11/01/2017 Α **EDITORIAL CHANGES** LSM BRB **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG524.4

4 OF 7 UNMETERED ELECTRIC SERVICE ON CUSTOMER-OWNED SERVICE POLE



METHOD 1 IMPREGNATED FIBER CONDUIT OF 1/4" MINIMUM THICKNESS



METHOD 2 WOOD MOULDING OF 1 1/2" MINIMUM THICKNESS



METHOD 3
BOXING OF WOOD
OF 1 1/2" MINIMUM
THICKNESS

FIGURE 2
ALTERNATE METHODS (N)

INSTALLATION:

- (A) these are minimum requirements for a permanent customer-owned fused service poles.
- (B) POLE LOCATION: THE POLE SHALL BE SET NOT MORE THAN 100 FEET, OR LESS THAN 10 FEET, FROM THE SURFACE OF THE UTILITY'S SERVICE POLE AND SO LOCATED THAT ALL REQUIRED SERVICE DROP CLEARANCES WILL BE OBTAINED FROM GROUND, BUILDINGS, AND STRUCTURES.
- (c) <u>TABLE 2</u>

SERVICE DROP MINIMUM CLEARAN	CES
LOCATION	MIN. CLEARANCE (FT) (E)
AT CENTER OF STREET OR 12'-0" FROM CURB, WHICHEVER IS LESS	18
AT CURB LINE	16
OVER COMMERCIAL OR INDUSTRIAL DRIVEWAYS, PARKING AREAS, OR AREAS CAPABLE OF BEING TRAVERSED BY VEHICLES	16
OVER RESIDENTIAL DRIVEWAYS	12 D
OVER AGRICULTURAL AREAS	15
OVER RAILROADS OR FOR OTHER SPECIAL CONDITIONS	CONSULT THE UTILITY'S PLANNER

- D MAY BE REDUCED TO 10 FEET IF SELF-SUPPORTING CABLE (SSC) SERVICE. THE UTILITY WILL USE SSC. THE TYPE OF CONSTRUCTION USE BY THE CUSTOMER IS THEIR OPTION.
- (E) WHERE CLEARANCES CANNOT BE OBTAINED WITH THE 25-FOOT POLE SHOWN, A 35-FOOT MAXIMUM POLE SHALL BE USED.
- F REFER TO SHEETS 1-5 FOR SPECIFICATIONS FOR INSTALLING CUSTOMER-OWNED AND INSTALLED WIRELESS COMMUNICATIONS ANTENNAS.
- G ALL CUSTOMER EQUIPMENT SHALL HAVE AN IDENTIFYING PLAQUE INDICATING CUSTOMER NAME, ADDRESS, OPERATION'S PHONE NUMBER, UM IDENTIFICATION NUMBER AND FUSE SIZE. THE PLAQUE SHALL BE PLASTIC WITH ENGRAVED OR MACHINE PRINTED LETTERS IN CONTRASTING COLOR TO THE PLAQUE AND SHALL BE PERMANENTLY ATTACHED TO THE FUSE BOX WITH POP RIVETS OR SCREWS. REFER TO SHEET 3 FOR TYPICAL PLAQUE CONFIGURATION.
- H. PERMIT AND INSPECTION MUST BE OBTAINED FROM THE AHJ BEFORE SERVICE WILL BE CONNECTED BY THE UTILITY.

	© 1998 - 2025 San Diego Gas & El	ectric C	Compar	າy. All ເ	rights r	eserved. Rer	noval o	of th	is copyright notice	e without permission	is not	permi	tted un	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CHAI	NGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	F								
В	EDITORIAL CHANGES	PEI/EDM	IPJ	IPJ	CZH	08/10/2021	Е								
Α	A EDITORIAL CHANGES - LSM					11/01/2017	D								
	X Indicates La	evisior	ı	Con	npletely Revi	sed		New Page	Information Re	moved	i				

SHEET 5 OF 7 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNMETERED ELECTRIC SERVICE ON CUSTOMER-OWNED SERVICE POLE

SG524.5

INSTALLATION (CONT'D):

- J. CONSULT THE UTILITY'S PLANNER FOR SERVICE REQUIREMENTS WHENEVER THREE PHASE SERVICE IS DESIRED.
- K THE UTILITY WILL FURNISH AND INSTALL THE SERVICE DROP AND SERVICE DROP RACK OR WIRE HOLDERS. ALL OTHER EQUIPMENT, INCLUDING POLE, SHALL BE FURNISHED AND INSTALLED BY THE CUSTOMER.
- L THE CUSTOMER IS TO DIG THE HOLE IN NATURAL SOIL. BACKFILL MUST BE COMPACTED TO 90% MINIMUM WITHIN A 5-FOOT RADIUS OF THE POLE. POLE DEPTH WILL BE CONFIRMED BY INSERTION OF A GROUND ROD OR SIMILAR PROBE INTO THE PVC DEPTH CONDUIT ATTACHED TO THE CLIMBABLE POLE. INSTALL A REMOVABLE CAP ON TOP OF THE DEPTH CONDUIT TO PREVENT FALLING DEBRIS FROM ENTERING THE CONDUIT.
- M ALL CONDUIT FITTINGS MUST BE RAINTIGHT. APPROVED WIRE, NOT LESS THAN 8 AWG, SHALL BE USED IN THE SERVICE ENTRANCE CONDUIT.
- (N) covering to be strapped to the pole with galvanized two-hole pipe straps spaced not to exceed 3 feet apart.
- (O) THE SERVICE GROUND IS TO COMPLY WITH ALL APPLICABLE CODES AND ORDINANCES AND BE MECHANICALLY PROTECTED IN COMPLIANCE WITH G.O. 95 PER ONE OF THE FOLLOWING METHODS:
 - 1. ENCASED IN RIGID STEEL CONDUIT
 - 2. MINIMUM NO. 8 AWG ARMORED COPPER GROUND WIRE
 - 3. COVERED BY A MINIMUM OF ONE OF THE FOLLOWING:

HARDWOOD MOLDING (OF OAK OR ROCK ELM) 3/8" IN THICKNESS

DOUGLAS FIR MOLDING 1/2" IN THICKNESS

RIGID CONDUIT OR RIGID U-SHAPE MOLDING OF A MINIMUM SCHEDULE 40 PVC

POLY-PROTECTED GROUND WIRE

- $(\,{\sf P}\,)$ customer to wire out 3 feet below top of Pole.
- (Q) PROVIDE AT LEAST 18 INCHES OF WIRE OUTSIDE OF SERVICE HEAD.

(R) **TABLE 1**

POLE SETT	ING DEPTH
POLE HEIGHT (FT)	SETTING DEPTH
25	5′-0″
30	5′-6″
35	5′-6″

- (S) bolt wood blocks to pole in 1/2-inch gains. Block not required for schedule 40 PVC plastic conduit runs.
- (T) extend protective covering over metallic conduits to bottom of service heads. Do not leave conduits exposed.
- (U) install straps below fiber conduits to prevent slipping.
- (W) CAPPED ON THE BOTTOM AND STRAPPED TO THE POLE
- $(\,\mathsf{Y}\,)$ when customer's load conductors are underground, install conduit as indicated by dashed lines.
- (Z) COVER IS TO BE NAILED TO SIDE PIECES.

0 4000 000F0 D: 0 0 FL L: 0	AU . 1	
© 1998 - 2025 San Diedo Gas & Electric Company	All rights reserved. Removal of this copyright notice w	lithout permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	F						
В	EDITORIAL CHANGES	PEI/EDM	IPJ	IPJ	CZH	08/10/2021	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 6 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNMETERED ELECTRIC SERVICE ON CUSTOMER-OWNED SERVICE POLE

SG524.6

ITEM		DESCRIPTION	QUANTITY	STANDARD PAGE	STOCK NUMBER	DESIGN UNITS
1	ANTENNA					
2	STRAP, PIPE					
3	POLE, TREATED, FULL LENGTH R	OUND, 25'-0" CLASS 5 MIN.				
		PVC, SCHEDULE 40, PLASTIC (PREFERRED)				
4	CONDUIT, SERVICE ENTRANCE	IRON, RIGID, GALV. 3/4" MIN. WITH PROTECTIVE COVERING (ALTERNATE)				
5	FUSE BOX, CUSTOMER-OWNED		AS REQ'D			
6	WOOD BLOCK, 4" X 4" X 6"					
7	REMOVABLE CAP					
8	CONDUIT, PVC, SCHEDULE 40, 6'-	-0", 3/4", POLE DEPTH				
9	EQUIPMENT, CUSTOMER-OWNED					
10	CONDUIT CAP					
11	PLAQUE, IDENTIFICATION, UM			SH 3		

NOTES:

(I) MAXIMUM LENGTH OF SERVICE DROP SPAN SHALL BE 100 FEET.

REFERENCE:

a. SEE OH645

© 1998 - 2025 San Diego Gas & Electric Company	All rights reserved. Removal of this copyright notice witho	it permission is not permitted under law
2 1000 Zozo can Biogo cao a ziocano company.	7 all righte received. I terrieval of alle copyright heace whate	at portineeren ie net permitted diader idw.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	EDM	IWA	JTM	KRG	02/07/2025	F						
В	EDITORIAL CHANGES	PEI/EDM	IPJ	IPJ	CZH	08/10/2021	Е						
A	EDITORIAL CHANGES	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 7 OF 7

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG524.7

UNMETERED ELECTRIC SERVICE ON CUSTOMER-OWNED SERVICE POLE

SCOPE: THIS STANDARD PROVIDES DIRECTION FOR ESTABLISHING EFFECTIVE METERING COMMUNICATIONS WHEN A METER LOCATION DOES NOT FACILITATE STANDARD "SMART METER" COMMUNICATION METHODS.

ATTENTION:

- * SMART METERING OPERATIONS (SMO) REQUIREMENTS FOR TYPE, PLACEMENT, AND QUANTITY OF SMART METER NETWORK DEVICES WILL VARY ACCORDING TO THE CONSTRUCTION AND LOCATION OF METERS THROUGHOUT THE CUSTOMER'S PREMISES, SO EACH PREMISE MUST BE EVALUATED BY SDG&E (UTILITY) ON A CASE-BY-CASE BASIS.
- ** FOR NETWORK DEVICE PLACEMENT, CONTACT THE NETWORK DEVICE TEAM VIA EMAIL AT

NETWORKDEVICE@SEMPRAUTILITIES.COM.

*** WHEN NEW CONSTRUCTION HAS COMMENCED, PROJECT MANAGEMENT SHALL PROVIDE NOTIFICATION OF NEW CONSTRUCTION TO THE SMART METER NETWORK EXPANSION TEAM AT

SMARTMETERNETWORKEXPANSION@SEMPRAUTILITIES.COM.

INSTALLATION:

A. NETWORK DEVICE WITH CUSTOMER POWER SOURCE:

- WHERE THE CUSTOMER WILL ALLOW THE UTILITY-OWNED SMART METER NETWORK DEVICES INSTALLED ON THE CUSTOMER PREMISES AND <u>WILL</u> PROVIDE POWER OUTLETS FOR THESE NETWORK DEVICES, THE REQUIREMENT FOR A COMMUNICATION CONDUIT CAN BE WAIVED.
- 2. THE POWER OUTLETS TO SUPPORT NETWORK DEVICES SHALL BE INSTALLED AT LOCATIONS DESIGNATED BY THE UTILITY'S METER AND NETWORK OPERATIONS PERSONNEL. FOR EACH LOCATION WITH ONE OR MORE NETWORK DEVICES, A 2-WIRE 120V AC POWER OUTLET SHALL BE CO-LOCATED. THE NETWORK DEVICE WILL BE INSTALLED WITH A HARD WIRE CONNECTION TO THE POWER OUTLET. THE POWER OUTLET CAN BE LOCATED ANYWHERE A CONDUIT CAN BE RUN FROM THE POWER OUTLET TO THE NETWORK DEVICE POWER SUPPLY.

B. NETWORK DEVICE WITHOUT CUSTOMER POWER SOURCE:

WHERE THE CUSTOMER WILL ALLOW THE UTILITY-OWNED SMART METER NETWORK DEVICES INSTALLED ON THE CUSTOMER PREMISE AND <u>WILL NOT</u> PROVIDE POWER OUTLETS FOR THESE NETWORK DEVICES, SMO HAS SPECIFIC COMMUNICATION CONDUIT REQUIREMENTS THAT MUST BE MET IN ORDER TO PROCEED. CONTACT WITH SMO MUST BE MADE PRIOR TO CONSTRUCTION IN ORDER TO OBTAIN THE SPECIFIC REQUIREMENTS AND APPLY THEM TO THE CUSTOMER'S ELECTRICAL CONDUIT INSTALLATION.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE: NONE

	© 1998 - 2025 Sa	an Diego Gas & El	ectric C	Compa	ny. All	rights ı	eserved. Rer	noval	of th	nis copyright notic	се	without permission	is not	permit	ted un	der law	·.
REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CHA	٩N	IGE	DR	BY	DSN	APV	DATE
С								F									
В	FORMAT	TING	EDM	JIK	-	-	02/07/2025	Е									
Α	NEW PA	AGE	-	LSM	BRB	TPM	11/01/2017	D									
		X Indicates L	Latest Revision Completely Revised New Page Information Removed														
	CHEET			SDG	S&E E	LECTI	RIC SERVIC	E ST	ANE	DARDS & GUID	DE	S					

SHEET 1 OF 1

METERING COMMUNICATIONS

SG525.1

600 - MEDIUM VOLTAGE ELECTRIC SERVICE & METERING EQUIPMENT

600 - MEDIUM VOLTAGE ELECTRIC SERVICE & METERING EQUIPMENT

<u>PAGE</u>	<u>SUBJECT</u>
602	MEDIUM VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT ALPHABETICAL SUBJECT INDEX
603	GENERAL INFORMATION
604	MEDIUM-VOLTAGE METERING CUBICLE
605	CONTROL POWER TRANSFORMER METERING
606	INDOOR CURRENT TRANSFORMER DIMENSIONS
607	INSTRUMENT TRANSFORMER MOUNTING SPECIFICATIONS
608	SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION
609	12KV SERVICE POINT CONNECTION FOR TROLLEY TRACTION STATION

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	11/15/2024	Е						
Α	NEW PAGE	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 1

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

MEDIUM VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT TABLE OF CONTENTS

SG601.1

<u> </u>	<u>SUBJECT</u>													<u>P</u>	<u>AGE</u>
Þ	AUXILIARY EQUIPM	ENT CONNECTE	ED AH	EAD (OF SE	RVIC	E MAIN								503.2
Е	BASIC LIGHTNING I	MPULSE INSUL	1OITA	N LEV	EL (B	IL) RA	ATING								503.4
Е	BUS DIMENSION														503.4
E	BUS MATERIAL														503.4
Е	BUS TAP DRAWINGS	S FOR APPROVA	۹L												503.3
C	CONDUCTORS PASS	SING THROUGH	COM	PARTI	MENT	WAL	LS								503.4
C	CONTROL POWER T	RANSFORMER ((CPT)	METE	ER WI	IRING	DIAGRAM								605
C	CURRENT AND VOLT	TAGE TRANSFO	RMER	INST	ΓALLA	TION	J								503.4
C	CURRENT TRANSFO	RMER, INDOOR	≀, DIM	IENSI	ONS.										606
C	CURRENT TRANSFO	RMERS AND BU	JS LIN	IK											503.5
	DOOR ACCESS TO M	1ETERING CUBI	CLES												503.4
E	ENGINEERING SPEC	CIFICATIONS													503.1
F	USE SPECIFICATIO)N													503.5
I	INSTRUMENT TRAN	SFORMER MOU	NTIN	G										603.5	, 607
N	MAIN SERVICE AND	METER DISCO	NNEC.	Т											503.1
N	MANUFACTURER'S [DRAWINGS FOR	L APPF	ROVAI	L										503.1
N	MEDIUM-VOLTAGE I	METERING CUB	ICLE.												604
	ENCLOSURE D	IMENSIONS													504.2
	FIELD MAINTE	NANCE ONLY											f	MO S	G604
	METER PANEL	LAYOUT													504.4
	METERING CU	BICLE													504.1
	PAD LAYOUT														504.1
	TEST SWITCH	LAYOUT													504.5
N	METER PANEL														503.4
F	PHASE TAPS PROTE	CTING FUSES A	AND V	OLTA	GE TI	RANSI	FORMERS .							6	503.5
9	SAFETY GROUNDING	G PROVISIONS													503.3
	© 1998 - 2024 Sa	an Diego Gas & Ele	ectric C	ompaı	ny. All	rights r	reserved. Rer	moval o	of this copyright ne	otice without permission	n is not	permit	ted und	der law.	
REV	CHANG	GE	DR	BY	DSN	APV	DATE	REV	С	HANGE	DR	BY	DSN	APV	DATE
C B	FORMAT	TING	EDM	JIK	-	_	11/15/2024	F E							
Α	EDITORIAL C		-		CTG	-	11/01/2017								
		X Indicates La	itest R				npletely Revi		New Page	Information Re	moved				
	SHEET			SDG	i&E E	LECTI	RIC SERVIC	E STA	ANDARDS & GU	JIDES			_	CC0'	n 1
	1 OF 2	MEDIUM \	√OL ⁻	ΓAGI	E EL ALP	ECT HAB	RIC SER	VICE SUB	E AND MET JECT INDE	ERING EQUIPN X	1ENT	-	5	G607	2.1

SUBJECT	<u>PAGE</u>
SERVICE POINT CONNECTION FOR 12KV TROLLEY TRACTION STATION	609
SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION	603.1, 608
UTILITY COMPARTMENT LABELING	603.3
VENTILATION	603.4
VOLTAGE TRANSFORMER DISCONNECT REQUIREMENTS	603.5
VOLTAGE TRANSFORMER FUSE SPECIFICATION	603.5
WEATHERPROOFING AND LOCKING	603.4
WORKING SPACE FOR MEDIUM-VOLTAGE SWITCHGEAR	603.3

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

								17 0					
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	1	11/15/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 2

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

MEDIUM VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT ALPHABETICAL SUBJECT INDEX

SG602.2

SCOPE: THIS STANDARD PROVIDES GENERAL INFORMATION ON MEDIUM VOLTAGE ELECTRIC SERVICE AND METERING EQUIPMENT.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. ENGINEERING SPECIFICATIONS:

- a. SDG&E (UTILITY) WILL ISSUE SPECIFICATIONS FOR EACH MEDIUM VOLTAGE SERVICE INSTALLATION. THESE SPECIFICATIONS WILL BE BASED ON THE APPLICATION FOR SERVICE, THE ELECTRICAL LOAD, SERVICE VOLTAGE PLANS AS REQUESTED BY THE CUSTOMER AND THE SERVICE RULES OF THE UTILITY. THE UTILITY'S PLANNER MAY APPROVE MEDIUM VOLTAGE SERVICE AND METERING EQUIPMENT IN AN ELECTRIC METER ROOM PROVIDED ALL REQUIREMENTS ON SG506 ARE MET. (a)
- b. THE INSTALLATION SHALL COMPLY WITH ALL APPLICABLE RULES OF THE CALIFORNIA ELECTRICAL CODE AND OTHER GOVERNING CODES AND ORDINANCES.

II. MANUFACTURER'S DRAWINGS FOR APPROVAL:

- a. THE MANUFACTURER OF MEDIUM-VOLTAGE SWITCHGEAR FOR A CUSTOMER'S SERVICE SHALL SUBMIT DRAWINGS

 ELECTRONICALLY TO SDG&E SERVICE STANDARDS FOR APPROVAL PRIOR TO FABRICATION. THE DRAWINGS MUST SHOW THE

 SERVICE CABLE TERMINATING SECTION, THE MAIN BREAKER, OR SWITCH SECTION AND THE METERING CUBICLE. SEND

 DRAWINGS TO (DRAWINGSUBMITTALS@SDGE.COM).
- b. THE JOB ADDRESS MUST BE SHOWN ON DRAWINGS FOR REVIEW AND APPROVAL. NOTIFICATION WILL BE SENT TO THE SENDER WITH APPROVALS OR CORRECTIONS AS NEEDED. WHEN A PARALLEL, STAND-BY OR EMERGENCY GENERATION SYSTEM IS EXISTING OR IS TO BE INSTALLED IN CONNECTION WITH NEW MEDIUM VOLTAGE SERVICE EQUIPMENT, A ONE-LINE ELECTRICAL DIAGRAM SHOWING THE RELATIONSHIP OF THE GENERATOR WITH THE SERVICE EQUIPMENT, INCLUDING THE TRANSFER DEVICE AND ITS SEQUENCE OF OPERATION, IS TO BE SUBMITTED WITH THE SWITCHGEAR DRAWINGS. THE ELECTRICAL ONE-LINE DIAGRAM SUBMITTAL REQUIREMENT APPLIES TO ALL MEDIUM VOLTAGE SERVICE.
- c. THIS PRACTICE WILL ENSURE YOUR SERVICE EQUIPMENT MEETS ALL OF THE UTILITY'S REQUIREMENTS AND IS ACCEPTABLE FOR INSTALLATION.
- d. APPROVALS ARE VALID FOR 3 YEARS. AFTER 3 YEARS FROM DATE OF APPROVAL, RESUBMITTAL OF SWITCHGEAR DRAWINGS DIRECTLY FROM THE MANUFACTURER WILL BE REQUIRED FOR REVIEW AND APPROVAL.

III. SWITCHGEAR UNDERGROUND SERVICE-TERMINATING PULL SECTION:

- a. ALL SWITCHGEAR TO WHICH MEDIUM VOLTAGE SERVICE IS TO BE SUPPLIED BY THE UTILITY SHALL BE EQUIPPED WITH A "SEPARATE, FULLY ENCLOSED" SWITCHGEAR UNDERGROUND SERVICE-TERMINATING PULL SECTION (UGPS). SPACE WILL BE PROVIDED FOR THE SUPPORT AND CONNECTION OF THE SERVICE CABLES TO A BUSSED SECTION WHICH HAS STANDARD NEMA DRILLINGS FOR TWO-HOLE TERMINATION LUGS. THE UTILITY WILL SPECIFY THE NUMBER OF CABLES THEY WILL INSTALL AND TERMINATE IN THE UGPS. THE UTILITY WILL FURNISH AND INSTALL THE TERMINATING LUGS. (b)
- b. THE SERVICE CABLE TERMINATING UGPS SHALL HAVE A FULL-HEIGHT HINGED DOOR THAT IS SEALABLE AND PAD-LOCKABLE.

IV. MAIN SERVICE AND METER DISCONNECT:

1 OF 6

- a. THE MANUFACTURER OR CONTRACTOR SHALL FURNISH AND INSTALL A SINGLE MAIN SERVICE AND METER DISCONNECT FOR EACH MEDIUM VOLTAGE SERVICE. THIS MAIN SERVICE AND METER DISCONNECT SHALL CONTROL ALL OF AND ONLY THE ENERGY CARRIED BY THE SERVICE AND REGISTERED BY THE MEDIUM-VOLTAGE METERING EQUIPMENT.
- b. THE SERVICE AND METER DISCONNECT SHALL COORDINATE ELECTRICALLY WITH THE UTILITY AND BE INSTALLED AND CONNECTED TO THE SERVICE ON THE SUPPLY (LINE) SIDE OF THE METERING EQUIPMENT. THIS IS REFERRED TO AS "COLD SEQUENCE METERING". GROUNDING SWITCHES SHALL NOT BE PERMITTED IN BETWEEN UTILITY PULL SECTION AND MAIN DISCONNECT.

	© 1998 - 2024 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights	eserved. Rer	noval o	of this copyright notice without permission i	s not	permit	ted und	der law	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITO	ORIA	L CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F						
В	EDITORIAL C	CHAN	IGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	EDITORIAL C	CHAN	IGES	-	JC	BRB	MDJ	07/16/2015	D						
		X	Indicates La	atest R				<u>' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' </u>		3 /1	noved				
	FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F Image: Free control of the cont								3.1						

GENERAL INFORMATION

IV. MAIN SERVICE AND METER DISCONNECT(CONT'D):

- c. THE CUSTOMER WILL PROVIDE, OWN AND MAINTAIN THEIR PREMISES DISTRIBUTION SYSTEM WHICH IS REQUIRED TO COORDINATE ELECTRICALLY WITH THE UTILITY'S SYSTEM, AND THEY WILL PROVIDE A ONE-LINE DIAGRAM OF THE MEDIUM VOLTAGE SERVICE EQUIPMENT. THIS APPLIES TO BOTH NEW SWITCHGEAR AND MODIFICATIONS TO EXISTING SWITCHGEAR.
- d. A MAIN BREAKER WITH PHASE AND GROUND RELAYS IS REQUIRED IF THE CUSTOMER DEMAND IS 2,500KW, OR ABOVE. AT THE UTILITY'S OPTION, A BREAKER MAY BE REQUIRED FOR LESSER DEMANDS TO ENSURE COORDINATION WITH THE UTILITY'S PROTECTIVE DEVICES, WHICH INCLUDES AUTOMATED SECTIONALIZING DEVICES SUCH AS SERVICE RESTORERS.
- e. IF A MULTIFUNCTION PROTECTIVE RELAY (E.G., MICROPROCESSOR, SOLID STATE, ETC.) IS USED TO PROTECT CUSTOMER'S SWITCHGEAR, THEN A REDUNDANT PROTECTION SYSTEM MUST BE INSTALLED (E.G., TWO MULTIFUNCTION PROTECTIVE RELAYS IN PARALLEL). THE REASON FOR THIS REQUIREMENT IS A FAILURE OF AN INTERNAL COMPONENT(S) (SUCH AS A POWER SUPPLY, RAM, ROM, A/D CONVERTER, ETC.) MAY DISABLE ALL PROTECTION FUNCTIONS WITHIN THE PROTECTIVE RELAY.
- f. WHEN BREAKER PROTECTION IS PROVIDED, THE CUSTOMER WILL INFORM THE UTILITY OF THE BREAKER MANUFACTURER, TYPE, SIZE, CURRENT TRANSFORMER (CT) RATIOS, PROTECTIVE RELAY MANUFACTURER, ANSI FUNCTIONS AND INSTANTANEOUS TRIP CURRENT VALUES, ETC.
- g. THE PROTECTIVE RELAY SETTINGS MUST BE APPROVED AND A WRITTEN TEST REPORT RECEIVED BY THE UTILITY'S PROTECTION ENGINEER BEFORE THE CUSTOMER'S SERVICE IS ENERGIZED.
- h. WHEN A SERVICE DISCONNECT WITH FUSED PROTECTION IS PROVIDED, THE CUSTOMER WILL INFORM THE UTILITY OF THE FUSE MANUFACTURER, TYPE, AMPACITY AND TIME CURRENT CURVES (TCC) FOR REVIEW AND APPROVAL. THE CUSTOMER WILL PERMANENTLY LABEL THE UTILITY-APPROVED FUSE SIZE AND TYPE ON THE DISCONNECT COVER PRIOR TO THE UTILITY ENERGIZING THE SERVICE. A PERMANENT PLAQUE SHALL BE AFFIXED TO THE DISCONNECT COVER STATING:

DO NOT INCREASE FUSE SIZE, TYPE OF FUSE OR MANUFACTURER WITHOUT OBTAINING PERMISSION FROM SDG&E.

V. AUXILIARY EQUIPMENT CONNECTED AHEAD OF SERVICE MAIN:

- a. VOLTAGE TRANSFORMERS (VTS) MAY BE INSTALLED ON THE SUPPLY SIDE OF THE MAIN SERVICE BREAKER FOR VOLTAGE INDICATION AND PROTECTIVE RELAYS.
- b. COGENERATION AND OTHER POWER PRODUCTION SOURCES INTERCONNECTED DIRECTLY WITH THE UTILITY MAY REQUIRE CONTROL POWER CONDUITS FOR COMMUNICATION AND/OR HIGH-END METERING. PLEASE REFER TO THE GENERATION HANDBOOK.
- c. A CONTROL POWER TRANSFORMER (CPT) USED <u>EXCLUSIVELY</u> FOR THE PROTECTIVE RELAYS AND THE CONTROL CIRCUIT <u>OF THE MAIN SERVICE BREAKER ONLY</u> MAY BE INSTALLED ON THE SUPPLY SIDE OF THE BREAKER WITHOUT THE REQUIREMENT FOR A SEPARATE 4- OR 7-CLIP METER SOCKET.
- d. Where a CPT is required for ac control circuits, space heating, lighting and other incidental use within the switchgear, the CPT may be installed in the switchgear and connected to the supply side of the service breaker. The CPT secondary load side will be separately metered. The CPT secondary leads shall be taken through test blocks to a 4- or 7-clip meter socket located on the door above the main service 15-clip meter socket.
- e. AC POWER MAY BE USED FOR BREAKER CONTROL. A CAPACITOR POTENTIAL DEVICE SHALL BE USED WITH A REDUNDANT ENERGY SOURCE, E.G. DEVICE MOUNTED BATTERIES OR UNINTERRUPTABLE POWER SUPPLY (UPS).
- f. REDUNDANT CONTROL POWER FOR OPERATING PROTECTIVE RELAYS MUST BE SUPPLIED THAT PROVIDES 72 HOURS MINIMUM SUFFICIENT POWER FOR TRIPPING OPERATIONS.
- g. VISIBLE INDICATION OF SUFFICIENT CHARGE FOR OPERATING THE SERVICE BREAKER TRIP COIL MUST BE AVAILABLE FROM THE REDUNDANT CONTROL POWER SYSTEM.
- h. NEW REDUNDANT SOURCES OF ENERGY NOT SPECIFICALLY MENTIONED IN THIS STANDARD MAY BE SUBMITTED ELECTRONICALLY TO SDG&E SERVICE STANDARDS FOR REVIEW AND APPROVAL AT (DRAWINGSUBMITTALS@SDGE.COM).

	© 1998 - 2024 Sa	an D	iego Gas & Ele	ectric C	Compa	ny. All	rights i	reserved. Rer	moval o	of this copyrigh	t notice	e without permission	is not	permit	ted und	der law.	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CHAI	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDIT	ORIA	AL CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F								
В	EDITORIAL (CHAN	NGES	-	LSM	CTG	TPM	11/01/2017	Е								
Α	EDITORIAL (CHAN	NGES	-	JC	BRB	MDJ	07/16/2015	D								
		X	Indicates La	atest R	Revisio	n	Con	npletely Revi	sed	New Pag	je	Information Re	moved	j			
C FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F B EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E																	
	JIILLI															000	

2 OF 6

GENERAL INFORMATION

SG603.2

VI. BUS TAP DRAWINGS FOR APPROVAL:

- a. BUS TAPS AHEAD OF THE MAIN SERVICE AND METER DISCONNECT ARE NOT PERMITTED EXCEPT AS SPECIFIED UNDER "AUXILIARY EQUIPMENT CONNECTED AHEAD OF SERVICE MAIN" ABOVE. PROPOSED LOAD SIDE OF METERING BUS TAPS AHEAD OF THE LOAD SIDE MAIN DISCONNECT REQUIRE UTILITY APPROVAL. PRIOR TO CONSTRUCTION, SUBMIT THE TAP DRAWING WITH A ONE-LINE DIAGRAM OF THE SWITCHGEAR ELECTRONICALLY TO SDG&E SERVICE STANDARDS AT (DRAWINGSUBMITTALS@SDGE.COM).
- b. THE BUS TAP DRAWING MUST BE PREPARED BY A QUALIFIED ENGINEER, AND THE ONE-LINE DIAGRAM MUST SHOW THE TAP LOCATION IN THE SWITCHGEAR LINEUP. THE JOB ADDRESS MUST BE SHOWN ON THE DRAWINGS IN ORDER TO PROCESS.
- c. THE CUSTOMER'S MODIFIED SYSTEM MUST COORDINATE ELECTRICALLY WITH THE UTILITY'S SYSTEM. BOTH THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) AND THE UTILITY WILL INSPECT THE BUS TAP, AND THE UTILITY MUST RECEIVE INSPECTION CLEARANCE FROM THE AHJ AS A CONDITION OF ENERGIZING.
- d. AN ACCEPTABLE SERVICE DISCONNECT WITH STANDARD ACCESS AND WORKING SPACE IS REQUIRED ON THE TAP IN IMMEDIATE PROXIMITY TO THE MAIN SWITCHGEAR.

VII. WORKING SPACE FOR MEDIUM-VOLTAGE SWITCHGEAR:

- a. MEDIUM-VOLTAGE SWITCHGEAR SHALL IN EVERY CASE (INDOOR OR OUTDOOR) BE INSTALLED WITH AT LEAST 5 FEET OF CLEAR, LEVEL AND UNOBSTRUCTED WORKING SPACE IN THE FRONT, REAR AND SIDES OF ALL SECTIONS THAT SUPPORT OR PROVIDE ACCESS TO METERING, VTS, CTS, GROUNDING BALL STUDS OR TESTING EQUIPMENT.
- b. A MINIMUM OF 8 FEET CLEAR, LEVEL AND UNOBSTRUCTED WORKING SPACE IN FRONT OF THE UGPS IS REQUIRED. FRONT IS DEFINED AS THE SECTION COVER THAT PROVIDES ACCESS TO THE UTILITY LANDING POSITION TERMINATION POINTS AND GROUNDING BALL STUDS.
- c. BECAUSE ACCESS IS REQUIRED TO BOTH THE FRONT AND REAR OF THE SWITCHGEAR, A WALKWAY OF AT LEAST 2 FEET WIDE SHALL BE PROVIDED AROUND ONE END OF THE MEDIUM VOLTAGE SERVICE AND METERING EQUIPMENT. (THIS APPLIES WHEN THE 5-FOOT WORKING SPACE PROVISION ABOVE IS NOT REQUIRED IN FRONT OF THE END SECTION.)
- d. TO MAINTAIN A SAFE, CLEAR AND LEVEL PERMANENT WORKING AREA IN FRONT OF NEW OR EXISTING METER AND SERVICE EQUIPMENT, A CONCRETE SLAB, ACCEPTABLE TO THE UTILITY INSPECTOR, IS REQUIRED. THE SLOPE OF THE WORKING SPACE FOR DRAINAGE IS NOT TO EXCEED 1/4 INCH PER FOOT SLOPING AWAY FROM THE EQUIPMENT.

VIII. UTILITY COMPARTMENT LABELING:

COMPARTMENTS OF THE METERING ENCLOSURE SHALL BE PERMANENTLY LABELED WITH MACHINE-ENGRAVED LAMINATED UV STABILIZED PLASTIC TAGS. THE LABELING SHALL BE QUARTER-INCH WHITE LETTERS AND NUMBERS ON RED-COLORED MATERIAL WHICH IS READILY VISIBLE AND MECHANICALLY ATTACHED TO THE FACE OF THE FOLLOWING DESIGNATED COMPARTMENTS SHALL BE WORDED AS FOLLOWS:

- a. UTILITY VOLTAGE TRANSFORMER COMPARTMENT
- b. UTILITY VOLTAGE TRANSFORMER FUSE COMPARTMENT
- c. UTILITY CURRENT TRANSFORMER COMPARTMENT
- d. UTILITY SERVICE TERMINATION COMPARTMENT
- e. UTILITY METERING PANEL

IX. SAFETY GROUNDING PROVISIONS:

THE BARE BUS 4 INCHES ABOVE AND BELOW THE CT SHALL BE PROVIDED TO PERMIT APPLICATION OF UTILITY MEDIUM-VOLTAGE WORKER'S SAFETY GROUNDS. GROUNDING BALL STUDS SHALL BE PROVIDED ON THE LINE AND LOAD SIDE OF THE BUS AT EACH CT LOCATION.

	© 1998 - 2024 Sar	n Diego Gas & El	ectric (Compa	ny. All	rights	reserved. Rei	moval c	of this c	copyright no	tice	without permission	n is not	permit	ted und	der law.	
REV	CHANG	ìE	DR	BY	DSN	APV	DATE	REV		СН	ΑN	IGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITO	RIAL CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F									
В	EDITORIAL CH	HANGES	-	LSM	CTG	TPM	11/01/2017	Е									
Α	EDITORIAL CH	HANGES	-	JC	BRB	MDJ	07/16/2015	D									
		X Indicates La	atest R				npletely Rev			lew Page		Information Re	emoved	l			
	SHEET			SDO	3&E E	LECT	RIC SERVIO	E STA	ANDAF	RDS & GU	IDE	ES					
2.05.6														SG603.3			
	3 01 0				(GEN	ERAL IN	FOR	MAT	ION							

XI. METER PANEL:

- a. THE UTILITY WILL INFORM THE MANUFACTURER OF THE METER PANEL LAYOUT FOR THE MEDIUM-VOLTAGE METERING
- b. THE METER PANEL AND HINGES ARE TO BE DESIGNED TO ADEOUATELY SUPPORT A 25-POUND LOAD APPLIED AT THE UNSUPPORTED END WITH 1/8 INCH MAXIMUM SAG WHEN OPEN. A #4 AWG FLEXIBLE BRAIDED BOND WIRE SHALL BE INSTALLED ACROSS THE HINGES.

XII. BASIC LIGHTNING IMPULSE INSULATION LEVEL (BIL) RATING:

BIL FOR THE METERING ENCLOSURE SHALL BE NOT LESS THAN THE BIL RATING FOR THE CUSTOMER'S ASSOCIATED SWITCHGEAR. REFERENCE SHALL BE MADE TO ANSI STANDARDS FOR THE MINIMUM ACCEPTED BIL RATINGS FOR MEDIUM-VOLTAGE SWITCHGEAR BUILT TO THE LISTED NOMINAL VOLTAGE AS SHOWN IN THE REFERENCED TABLES. (e) (f)

XIII. **VENTILATION:**

VENTILATION OPENINGS SHALL BE PROVIDED AS PER ANSI STANDARDS, AND SHALL BE LOUVERED OR SCREENED AND BE GUARDED WITH INTERNAL BARRIERS TO PREVENT ACCESS TO ENERGIZED PARTS.

XIV. DOOR ACCESS TO METERING CUBICLES:

A FULL-HEIGHT HINGED DOOR WITH A 3-POINT LOCKING MECHANISM AND PROVISIONS FOR A UTILITY-FURNISHED PADLOCK IS REQUIRED.

XV. WEATHERPROOFING AND LOCKING:

- a. THE REFERENCED ENCLOSURE DOORS SHALL BE DESIGNED TO BE SECURE IN THE OPEN POSITION 90-DEGREES OR MORE.(d)
- b. THE METER PANEL SHALL BE HINGED ON THE OPPOSITE SIDE OF THE OUTER DOOR ON THE WEATHERPROOF UNITS TO PERMIT 90-DEGREE OPENING WITH THE METERS AND TEST FACILITIES IN PLACE, OMIT THE WEATHERPROOF DOORS IF THE EQUIPMENT IS LOCATED INDOORS.
- c. IF THE OUTER DOOR IS OMITTED, FURNISH A LOCKABLE METER PANEL, THE FRONT AND REAR WEATHERPROOF DOORS SHALL BE SINGLE DOORS EQUIPPED WITH A LATCH-TYPE HANDLE FOR A UTILITY PADLOCK.

XVI. CURRENT AND VOLTAGE TRANSFORMER INSTALLATION:

CT'S, VTs, METERS, TESTING FACILITIES AND ALL SECONDARY WIRING FROM THE TRANSFORMERS TO THE METERS WILL BE FURNISHED AND INSTALLED BY THE UTILITY.

XVII. BUS MATERIAL:

ALL COPPER OR ALUMINUM BUS USED IN THE METERING ENCLOSURE SHALL BE TIN OR SILVER-PLATED TO PREVENT THE CORROSION OF THE UTILITY-SUPPLIED CTS AT THE CONNECTION POINTS TO THE BUS. THIS SHALL ALSO INCLUDE THE CT MOUNTING HARDWARE - BOLTS, WASHERS AND NUTS.

XVIII. BUS DIMENSION:

THE MAXIMUM BUS SIZE SHALL BE 3/8" X 4". MINIMUM BUS SIZE SHALL BE 1/4" X 2" UNLESS OTHERWISE INDICATED ON SPECIFIC DRAWING. A BUS SIZE OUTSIDE THESE LIMITS REQUIRES SPECIAL ENGINEERING AND CONSULTATION WITH THE UTILITY.

XIX. CONDUCTORS PASSING THROUGH COMPARTMENT WALLS:

WHERE CABLE OR BUSSES PASS THROUGH COMPARTMENT WALLS, THROUGH-THE-WALL BUSHINGS WITH FULL VOLTAGE RATING ON THE SWITCHGEAR MUST BE USED.

	© 1998 - 2024 Sa	an Di	ego Gas & Ele	ectric C	Compa	ny. All	rights i	reserved. Rei	moval o	of th	is copyright no	tice	e without permission	is not	permi	tted un	der law	
REV	CHANG	GE		DR	BY	DSN	APV	DATE	REV		Cl	IAI	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITO	ORIA	L CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F									
В	EDITORIAL C	CHAN	IGES	-	LSM	CTG	TPM	11/01/2017	Е									
Α	EDITORIAL C	CHAN	IGES	-	JC	BRB	MDJ	07/16/2015	D									
									Information Re	moved	ı							
	SHEET				SDO	G&E E	LECTI	RIC SERVIO	CE STA	AND	ARDS & GL	ID	ES					
	SHEET															S	G60	3.4

GENERAL INFORMATION

4 OF 6

XX. PHASE TAPS FOR FUSES PROTECTING VOLTAGE TRANSFORMERS:

BUSSED THROUGH-WALL INSULATORS FOR PHASE VT TAPS ARE TO BE FURNISHED WITH LUGS ON THE VT COMPARTMENT SIDE. CABLE OR BUS CONDUCTOR SHALL BE FURNISHED FOR THE TAP TO THE FUSE CARRIAGE AND TO THE VT COMPARTMENT MAINTAINING BARE BUS CLEARANCE. MECHANICAL LUGS (EQUAL TO ILSCO TA-2) FOR #6 BARE COPPER WIRE SHALL BE PROVIDED ON THE LOAD SIDE OF THE FUSE CARRIAGE CONNECTING TO THE VTS. ONE MECHANICAL LUG (EQUAL TO ILSCO TA-2) FOR #6 BARE COPPER WIRE SHALL BE PROVIDED ON THE GROUND BUS FOR CONNECTING TO THE VTS. CONDUCTORS BY SDG&E

XXI. VOLTAGE TRANSFORMER FUSE SPECIFICATION:

VT FUSES SHALL BE FURNISHED AND INSTALLED BY THE UTILITY. THE MANUFACTURER SHALL PROVIDE MOUNTING CLIPS FOR CURRENT LIMITING FUSES WITH MOUNTING CLIP SEPARATION AND FUSE FERRULE DIAMETER APPROPRIATE FOR THE VOLTAGE RATING OF THE EQUIPMENT.

XXII. VOLTAGE TRANSFORMER DISCONNECT REQUIREMENTS:

a. KEY INTERLOCKING IS REQUIRED BETWEEN THE VT DISCONNECT AND THE VT COMPARTMENT DOOR SO THAT, FOR PERSONNEL SAFETY, THE VT COMPARTMENT CANNOT BE ENTERED UNTIL THE FOLLOWING CONDITIONS ARE MET:

THE DISCONNECT IS FULLY AND VISIBLY OPEN.

WHEN THE VT DISCONNECT IS FULLY OPEN, THE DISCONNECT BLADES MUST GROUND AUTOMATICALLY.

ARCING HORNS ARE NOT PERMITTED ON NO-LOAD DISCONNECT ASSEMBLIES.

THE DISCONNECT IS LOCKED OPEN WITH A KEY INTERLOCK SYSTEM.

VT DISCONNECT SWITCH SHALL BE PAD-LOCKABLE IN THE CLOSED POSITION.

VT DISCONNECT SWITCH TO BE CONNECTED ON LINE SIDE OF CTS.

- b. THE UTILITY REQUIRES THE CUSTOMER TO PROVIDE TWO SETS OF INTERLOCK KEYS FOR UTILITY USE PRIOR TO ENERGIZING THE SERVICE. ONE OF THE KEYS WILL BE RETAINED BY THE UTILITY AND ONE WILL REMAIN WITH THE SERVICE EQUIPMENT. THE KEY INTERLOCK SYSTEM MUST PREVENT CLOSING OF THE DISCONNECT WITHOUT FIRST CLOSING AND LOCKING THE VT COMPARTMENT DOOR.
- c. PRIMARY CONTACTS FOR THE VOLTAGE DISCONNECT SHALL BE OF THE BLADE AND JAW DESIGN OR EQUIVALENT TO ENSURE CONTINUED ADEQUATE CONTACT. WIPING OR PRESSURE CONTACT IS NOT ACCEPTABLE.
- d. AS AN ALTERNATIVE, THE METER PANEL MAY BE MOUNTED IN FRONT OF THE CT COMPARTMENT, PROVIDED THAT WHEN THE METER PANEL IS OPENED, THE COMPARTMENT IS FULLY ISOLATED BY A HINGED BARRIER.

XXIII. INSTRUMENT TRANSFORMER MOUNTING:

INSTRUMENT TRANSFORMER MOUNTING SPECIFICATIONS INCLUDE CURRENT TRANSFORMER (CT) MOUNTING BASE AND VOLTAGE TRANSFORMER (VT) MOUNTING RAIL DETAIL SPECIFICATIONS.

XXIV.CURRENT TRANSFORMERS AND BUS LINK:

BUS DRILLING AND SPACING SHALL ACCOMMODATE 800A OR LESS CTS OF THE PROPER VOLTAGE INSULATION CLASS. CT CENTER PHASE POSITION SHALL BE BUSSED STRAIGHT THROUGH FOR 3-PHASE, 3-WIRE, SERVICE VOLTAGE INSTALLATIONS WITH A REMOVABLE LINK DIMENSIONED THE SAME AS THE CT BARS ON THE METERED PHASES.

XXV. FUSE SPECIFICATION:

VT FUSES SHALL BE FURNISHED AND INSTALLED BY THE UTILITY. THE MANUFACTURER SHALL PROVIDE MOUNTING CLIPS FOR CURRENT LIMITING FUSES WITH MOUNTING CLIP SEPARATION AND FUSE FERRULE DIAMETER DIMENSIONS AS INDICATED IN SG604, TABLE 1, DIMENSION U. (c)

© 1998 - 2024 Sa	an Di	iego Gas & El	ectric C	Compa	ny. All	rights	reserved. Rer	moval (of th	is copyright no	otice	without permission	n is not	permi	tted un	der law	•	
CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	HAN	IGE	DR	BY	DSN	APV	DATE	
FORMATTING/EDITO	ORIA	AL CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F										
EDITORIAL C	CHAN	NGES	-	LSM	CTG	TPM	11/01/2017	Е										
EDITORIAL C	CHAN	NGES	-	JC	BRB	MDJ	07/16/2015	D										
	Χ	Indicates La	atest R	evisio	n	Cor	npletely Revi	ised		New Page		Information Re	moved	i				
CHEET				SDO	3&E E	LECT	RIC SERVIC	E ST	AND	ARDS & GL	JIDI	ES						
															SG60	3.5		
5 OF 6						GEN	ERAL IN	FOR	MA	ATION					_	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	3.3	
	CHAN FORMATTING/EDITO EDITORIAL O	FORMATTING/EDITORIAL CHAP EDITORIAL CHAP EDITORIAL CHAP SHEET	FORMATTING/EDITORIAL CHANGES EDITORIAL CHANGES EDITORIAL CHANGES X Indicates Langes SHEET	CHANGE DR FORMATTING/EDITORIAL CHANGES EDM EDITORIAL CHANGES - EDITORIAL CHANGES - EDITORIAL CHANGES - X Indicates Latest R SHEET	CHANGE DR BY FORMATTING/EDITORIAL CHANGES EDM JTM EDITORIAL CHANGES - LSM EDITORIAL CHANGES - JC X Indicates Latest Revision SHEET	CHANGE DR BY DSN FORMATTING/EDITORIAL CHANGES EDM JTM IWA EDITORIAL CHANGES - LSM CTG EDITORIAL CHANGES - JC BRB X Indicates Latest Revision SHEET F. OF 6	CHANGE DR BY DSN APV FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG EDITORIAL CHANGES - LSM CTG TPM EDITORIAL CHANGES - JC BRB MDJ X Indicates Latest Revision Cor SDG&E ELECTION	CHANGE DR BY DSN APV DATE FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 X Indicates Latest Revision Completely Revision SDG&E ELECTRIC SERVICE SDG&E ELECTRIC SERVICE TOTAL CHANGES - SDG&E ELECTRIC SERVICE SHEET - SDG&E ELECTRIC SERVICE SHEET - SDG&E ELECTRIC SERVICE TOTAL CHANGES - LSM CTG TPM 11/01/2017 COMPLETE SERVICE SDG&E ELECTRIC SERVICE SDG&E SERVICE SDG	CHANGE DR BY DSN APV DATE REV FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised SHEET F. O.E. 6	CHANGE DR BY DSN APV DATE REV FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised SHEET F. O.E. 6	CHANGE DR BY DSN APV DATE REV CI FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised New Page SHEET	CHANGE DR BY DSN APV DATE REV CHANGE FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDING	CHANGE DR BY DSN APV DATE REV CHANGE FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised New Page Information Reserved SDG&E ELECTRIC SERVICE STANDARDS & GUIDES	CHANGE DR BY DSN APV DATE REV CHANGE DR FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised New Page Information Removed SHEET F. O.E. 6.	CHANGE DR BY DSN APV DATE REV CHANGE DR BY FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F EDITORIAL CHANGES - LSM CTG TPM 11/01/2017 E EDITORIAL CHANGES - JC BRB MDJ 07/16/2015 D X Indicates Latest Revision Completely Revised New Page Information Removed SHEET F. O.E. 6	CHANGE DR BY DSN APV DATE REV CHANGE DR BY DSN END END END END END END END END END EN	FORMATTING/EDITORIAL CHANGES EDM JTM IWA KRG 11/15/2024 F	

RE	FERENCE:															
a	SEE SG506.															
b	SEE SG608.															
C	SEE SG604.															
d) FOR EQUIPMENT WI															
e	SEE IEEE STD. C37.2															
(f)	SEE IEEE STD. C37.2	20.3-2013, TABLE	1.1-3:	: MET	AL-EN	ICLOSED S	WITC	HGEAR VO	OLTAG	SE AN	D INSULATIO	ON LE\	/ELS.			
	© 1998 - 2024 San D	Diego Gas & Electric	Compar	ıy. All ı	rights r	eserved. Rer	moval (of this copyri	ight no	tice wil	hout permissio	on is not	permit	tted un	der law	<i>′</i> .
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	of this copyri		dice wit		on is not		tted un		· DATE
С	CHANGE FORMATTING/EDITORIA	DR [AL CHANGES EDM	BY I JTM	DSN IWA	APV KRG	DATE 11/15/2024	REV	of this copyri								
C B	CHANGE FORMATTING/EDITORIA EDITORIAL CHA	IAL CHANGES EDM ANGES -	BY JTM LSM	DSN IWA CTG	APV KRG TPM	DATE 11/15/2024 11/01/2017	REV F E	of this copyri								
С	CHANGE FORMATTING/EDITORIA	IAL CHANGES EDMANGES -	BY JTM LSM JC	IWA CTG BRB	APV KRG TPM MDJ	DATE 11/15/2024 11/01/2017 07/16/2015	REV F E D		CH	ANGE		DR	BY			
C B	CHANGE FORMATTING/EDITORIA EDITORIAL CHA EDITORIAL CHA	IAL CHANGES EDM ANGES -	BY JTM LSM JC Revision	IWA CTG BRB	KRG TPM MDJ Com	DATE 11/15/2024 11/01/2017	F E D	New F	CH Page	ANGE		DR	BY			
C B	CHANGE FORMATTING/EDITORIA EDITORIAL CHA	IAL CHANGES EDMANGES -	BY JTM LSM JC Revision	IWA CTG BRB n	KRG TPM MDJ Com	DATE 11/15/2024 11/01/2017 07/16/2015 npletely Revi	F E D sed	New F	CH Page & GU	ANGE		DR	BY	DSN		DATE




TABLE 1

ENCLOSURE DIMENSIONS	TABLE	
SPECIFICATIONS	VOLTAGE	RATING
SPECIFICATIONS	4160V	7200/1200V
MINIMUM BARE BUS CLEARANCE Ø TO GROUND (IN)	3 1/2	6
MINIMUM BARE BUS CLEARANCE Ø TO Ø (IN)	5	7 1/2
Z (IN)		IIN. IAX.
Y (IN	24.1	MIN.
X (IN)	241	TIIN.
W (IN)	1 00	MIN.
V (IN)	36 1	MIN.
U - FUSE MOUNTING CLIP CENTER (IN)	8 1/2	11 1/2
U – FUSE FERRULE DIAMETER (IN)	1 5	5/8

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I THE MANUFACTURER SHALL INSTALL A 1-INCH SCHEDULE 40 PVC COMMUNICATION CONDUIT LOCATED FROM THE METER COMPARTMENT TO THE BOTTOM OF THE VT COMPARTMENT ON THE HINGED SIDE OF THE METER DOOR IN THE SWITCHGEAR.
- (II) THE CUSTOMER SHALL PROVIDE AND INSTALL A MINIMUM 1-INCH SCHEDULE 40 PVC COMMUNICATION CONDUIT FROM THE SWITCHGEAR TO THE COMMUNICATION POINT OF CONNECTION SERVICE, E.G., MAIN POINT OF ENTRY (MPOE) OR PRIVATE BRANCH EXCHANGE (PBX) LOCATION.
- (III) THE CUSTOMER SHALL PROVIDE AND INSTALL A 1-INCH LIQUID-TIGHT NON-METALLIC FLEXIBLE CONDUIT TO CONNECT SWITCHGEAR PVC CONDUIT.
- (IV) CONSULT WITH THE UTILITY BEFORE THE INSTALLATION OF THE COMMUNICATION CONDUIT. (b)
- (V) NOT A CABLE TERMINATION SECTION
- (VI) NO LOAD VOLTAGE TRANSFORMER DISCONNECT. ARCING HORNS ARE NOT PERMITTED.
- $\left(\mathsf{VII}
 ight) \mathsf{V.T., C.T., AND COMMUNICATION CONDUITS SHALL BE LOCATED ON THE SAME SIDE AS THE METER PANEL HINGES.$
- (VIII) 200 LBS. MINIMUM STRENGTH
- (IX) FOR C.T. POTENTIAL WIRES
- (XI) FOR V.T. SECONDARIES
- (XII) FOR COMMUNICATION LINE
- XIII. ALL SERVICE EQUIPMENT SHALL BE CONSIDERED 3-PHASE, 4-WIRE SERVICE.
- XIV. THE NEUTRAL CONDUCTOR SHALL BE TERMINATED IN A BUSHING-MOUNTED MECHANICAL LUG IN THE PULL SECTION.
- XV. THE BUSHING IS CONNECTED TO A NEUTRAL BUS EXTENDED TO THE MAIN SERVICE BREAKER OR FUSED SWITCH SECTION. IN AN ACCESSIBLE AREA BEHIND THE BREAKER OR FUSED SWITCH, THE NEUTRAL BUS SHALL HAVE A REMOVABLE JUMPER LINK FOR TESTING AND A DISCONNECT BONDING LINK TO THE GROUND BUS AND LABELED AS SUCH.

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/15/2024	F						
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	D						

SHEET 2 OF 6


Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG604.2

MEDIUM-VOLTAGE METERING CUBICLE

REFERENCE: (a) SEE SG608: SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION. (b) FOR ADDITIONAL REQUIREMENTS, SEE SG525: METERING COMMUNICATIONS. (c) SEE SG607. © 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV DR BY DSN APV DATE **CHANGE** DR DATE REV **CHANGE** EDITORIAL CHANGES/FORMATTING | EDM JTM IWA KRG 11/15/2024 LSM В **EDITORIAL CHANGES** CTG TPM 11/01/2017 Ε Α NO CHANGES-REAFFIRMED JC BRB MDJ 07/16/2015 **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES **SHEET** SG604.3 3 OF 6 MEDIUM-VOLTAGE METERING CUBICLE



REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/15/2024	F						
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	D						

SHEET 4 OF 6


Completely Revised Indicates Latest Revision SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page


Information Removed

MEDIUM-VOLTAGE METERING CUBICLE

SG604.4



EXAMPLE 1



EXAMPLE 2 REMOVABLE PLATE DETAIL

<u>DETAIL 2</u> TEST SWITCH LAYOUT

INSTALLATION: NONE

BILL OF MATERIALS: NONE

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/15/2024	F						
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	D						

SHEET 5 OF 6

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

MEDIUM-VOLTAGE METERING CUBICLE

SG604.5

NO	TES:												
(I	TEST-BYPASS BLOCKS SUPPLIED	BY M	1ANUF	ACTU	JRER .	and moun	ITED	ON BACK SIDE OF DOOR. (a) (b)					
(II)													
(III		IREMI	ENT V	VHEN				NDENT SYSTEM OPERATOR (ISO) I	METE	RING	IS RE	QUIR	ED.
(IV					OND 1	TEST SWIT	CH LC	OCATION.					
RE	FERENCE:												
	FOR TEST-BYPASS FACILITIES, S	SEE SO	3513.										
b	\				TER V	WIRING DIA	AGRAI	M, SEE SG605.					
•	, rok common romak namer c		. (0.	. ,				1, 522 55555					
	© 1998 - 2024 San Diego Gas & Ele	ectric C	Compa	ny. All	rights ı	reserved. Rei	noval o	of this copyright notice without permission	is not	permit	ted und	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/15/2024	F						

EDITORIAL CHANGES LSM CTG TPM 11/01/2017 E BRB MDJ 07/16/2015 D NO CHANGES-REAFFIRMED JC Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES **SHEET** SG604.6 MEDIUM-VOLTAGE METERING CUBICLE

6 OF 6

SCOPE: THIS STANDARD SHOWS A CONTROL POWER TRANSFORMER METER WIRING DIAGRAM. B PHASE LOAD **B PHASE LINE** A PHASE LOAD - A PHASE LINE **FIGURE 1** CONTROL POWER TRANSFORMER (CPT) METER (I) WIRING DIAGRAM **INSTALLATION:** NONE **BILL OF MATERIALS: NONE NOTES:** (I) VIEWED FROM INSIDE OF DOOR **REFERENCE:** NONE © 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV DR BY DSN APV DATE **CHANGE** DR DATE REV **CHANGE** С **FORMATTING EDM** JIK 11/15/2024 Ε В **EDITORIAL CHANGES** LSM CTG TPM 11/01/2017 NO CHANGES-REAFFIRMED JC BRB MDJ 07/16/2015 **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG605.1 1 OF 1

CONTROL POWER TRANSFORMER METERING

SCOPE: THIS STANDARD PROVIDES INDOOR CURRENT TRANSFORMER DIMENSIONS FOR 5KV THROUGH 15KV METERING PURPOSES.

3/4"

1/2"

MIN




FIGURE 1
MOUNTING BASE
SEE TABLE 1

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F						
В	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
										$\overline{}$		-	

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG606.1

INDOOR CURRENT TRANSFORMER DIMENSIONS

TABLE 1

		INDOOR CURF	RENT TRANSFO	\overline{V} DIMENSIONS \overline{V}	VII	_
INSULATION		Z (IN)		Y (IN)	X (1	(N) MAXIMUM
CLASS (KV) (IV)	10 – 800A	1,200 – 2,000A (VI)	10 – 800A	1,200 – 2,000A (VI)	10 – 800A	1,200 – 2,000A (VI
5.0	14		5 3/4		8	
8.7	15		8		10 1/2	
15.0	22	26	9	5 3/4	11 1/4	13

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) PRIMARY TERMINAL RATING 800A OR LESS
- (II) PRIMARY TERMINAL OVER 800A
- (III) 1/4-INCH APPLIES TO MULTIPLE BAR THICKNESS. SINGLE BAR THICKNESS MAY BE FROM 3/16-INCH TO 3/8-INCH.
- (IV) INSULATION CLASSES ARE 5, 8.7 AND 15KV. BASIC LIGHTNING IMPULSE INSULATION LEVELS (BILS) FOR THESE CLASSES ARE 60, 75 AND 110KV, RESPECTIVELY.
- (V) UNLESS OTHERWISE INDICATED, TOLERANCE PLUS OR MINUS 1/16 INCH.
- (VI) consult with SDG&E service standards before constructing.
- $\overline{ ext{(VII)}}$ 2,000A CURRENT TRANSFORMERS (CT'S) REQUIRE THE SWITCHGEAR TO HAVE THREE 1/4-INCH THICK BY 4-INCH WIDE BUS BARS PER PHASE. THIS IS TO ACCOMMODATE THE UTILITY CT'S, WHICH HAVE TWO 1/4-INCH THICK 4-INCH WIDE PADS ON EACH END TO CONNECT TO THE BUSSING.

REFERENCE: NONE

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.	
--	--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING/EDITORIAL CHANGES	EDM	JTM	IWA	KRG	11/15/2024	F						
В	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 2


Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

INDOOR CURRENT TRANSFORMER DIMENSIONS

SG606.2

SCOPE: THIS STANDARD PROVIDES SPECIFICATIONS FOR INSTRUMENT TRANSFORMER MOUNTING IN MEDIUM-VOLTAGE METERING ENCLOSURES.






FIGURE 2




FIGURE 3

VOLTAGE TRANSFORMER MOUNTING RAIL DETAIL

TOP VIEW OF CABINET

SEE TABLE 1

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/15/2024	F						
В	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
							L .						

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

INSTRUMENT TRANSFORMER MOUNTING SPECIFICATIONS

SG607.1

TABLE 1

	CABINET ITEM LIST
ITEM	DESCRIPTION
1	CHANNEL, UNISTRUT, P1000
2	NUT, P1008, 3/8"-16

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

(I) ALL HOLES TAP 3/8"-16

(II) OR EQUIVALENT TYPICAL

(III) TYPICAL 6 EACH PER CHANNEL

REFERENCE: NONE

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/15/2024	F						
В	NO CHANGES-REAFFIRMED	-	JC	BRB	MDJ	07/16/2015	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 2

Completely Revised New Page Information Removed Indicates Latest Revision SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

INSTRUMENT TRANSFORMER MOUNTING SPECIFICATIONS

SG607.2

SCOPE: THIS STANDARD PROVIDES REQUIREMENTS FOR SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTIONS (UGPS) IN THE SDG&E (UTILITY) SERVICE TERRITORY.

ATTENTION:


* THIS STANDARD APPLIES TO THE FOLLOWING VOLTAGES:


5KV CLASS: 4,160V, 3-WIRE AND 4-WIRE SERVICES

15KV CLASS: 6,900 TO 15,000V, 3-WIRE AND 4-WIRE SERVICES

** MINIMUM BARE BUS CLEARANCES:

5KV CLASS: 3 1/2 INCHES PHASE TO GROUND, 5 INCHES PHASE TO PHASE 15KV CLASS: 6 INCHES PHASE TO GROUND, 7 1/2 INCHES PHASE TO PHASE





DOUBLE FRONT VIEW

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	-	1	11/15/2024	F						
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	07/16/2015	D						

SHEET 1 OF 3


Indicates Latest Revision		Completely Revised		New Page		Information Removed
SDG&F	FI	ECTRIC SERVICE ST	ΔΝΓ	VABDS & CI	IID	FS


SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION


SG608.1

SIDE VIEW





DETAIL 1 NO. 6 – 250 KCMIL GROUND LUG



DETAIL 2 NO. 6 – 250 KCMIL NEUTRAL LUG

INSTALLATION:

(A) TERMINATE CONCENTRIC NEUTRAL ON NEUTRAL LUG FOR 4-WIRE SERVICES, AND ON THE GROUND LUG FOR 3-WIRE SERVICES.

BILL OF MATERIALS: NONE

NOTES:

- $\left(\ \mathrm{I} \ \right)$ NO. 6 250 KCMIL GROUND LUG INTENDED FOR UTILITY USE ON 3-WIRE SERVICES.
- (II) ISOLATED NEUTRAL TERMINATION CAN BE LOCATED ON RIGHT OR LEFT SIDE OF THE BACK WALL OF THE PULL SECTION. <u>NEUTRAL TO BE BONDED TO GROUND IN MAIN SERVICE DISCONNECT SECTION ONLY.</u> (a)
- III. CONSULT WITH THE UTILITY FOR THE NUMBER OF SERVICE CABLES, NUMBER, SIZE AND LOCATION OF SERVICE CONDUITS, AND TYPE OF SWITCHGEAR SERVICE TERMINATING UGPS REQUIRED.
- (IV) CONSULT WITH THE UTILITY TO DETERMINE IF THE SERVICE IS TO BE 3-WIRE OR 4-WIRE (3 PHASES AND A NEUTRAL) AND IF AN INSULATED NEUTRAL LANDING WITH A RANGE NO. 6 250 KCMIL IS REQUIRED.
- V. THE REMOVABLE ENCLOSING PANELS SHALL NORMALLY BE FRONT OR BACK. REMOVABLE PANELS SHALL BE EQUIPPED WITH TWO LIFTING HANDLES AND ATTACHED WITH STUDS AND WING NUTS. PANEL COVER SHALL NOT EXCEED 9 SQUARE FEET. CONSULT WITH SDG&E SERVICE STANDARDS FOR SPECIAL PERMISSION TO LOCATE THE REMOVABLE ENCLOSING PANELS ON THE SIDE. IF THE REMOVABLE ENCLOSING PANELS ARE LOCATED ON THE SIDE, A 12-INCH MINIMUM ACCESS DISTANCE TO BUSSES SHALL BE PROVIDED, MEASURED FROM THE BUSSES TO THE PANELS, WITH THE PANELS IN PLACE. THE UGPS MAY BE REQUIRED TO BE EQUIPPED WITH HINGED FULL OPENING, SEALABLE ACCESS DOORS, WITH PADLOCK PROVISIONS.
- (VI) MANUFACTURER TO PROVIDE THE STANDARD NEMA TWO-HOLE DRILLING PATTERN FOR HOLES ON TERMINATING BUS. CONSULT THE UTILITY FOR THE NUMBER OF LANDING POSITIONS REQUIRED PER PHASE. THE UTILITY WILL PROVIDE THE NECESSARY TERMINATING BOLTS.

 $@ 1998 - 2024 \ San \ Diego \ Gas \ \& \ Electric \ Company. \ All \ rights \ reserved. \ Removal \ of this \ copyright \ notice \ without \ permission \ is \ not \ permitted \ under \ law.$

	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	-	1	11/15/2024	F						
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	07/16/2015	D						

SHEET 2 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION

SG608.2

- (VII) FURNISH AND INSTALL ONE PIECE OF STRUCTURAL SUPPORT SYSTEM EQUAL TO UNISTRUT P1000 AS SHOWN.
- VIII. THE BASIC LIGHTNING IMPULSE INSULATION LEVEL (BIL) RATING FOR THE UGPS SHALL BE NOT LESS THAN THE BIL RATING OF THE CUSTOMER'S ASSOCIATED SWITCHGEAR.
- (IX) NO CUSTOMER CONNECTIONS OR CUSTOMER EQUIPMENT ARE PERMITTED IN THE UGPS WHERE THE UTILITY TERMINATES ITS CONDUCTORS.
- (XI) GROUNDING BALL STUD 1/2-13 THREAD, WITH INSULATING COVER. THE BALL STUD PROVIDES A PLACE FOR UTILITY MEDIUM-VOLTAGE WORKERS TO TEST AND GROUND SERVICE EQUIPMENT. LOCATE THE BALL STUD ON THE UTILITY LANDING POSITION FLAG.
- THE GROUND BUS IN THE REAR OF THE UGPS IS TO BE EXTENDED TO THE FRONT LEFT OR RIGHT SIDE. GROUNDING TERMINATION DEVICES FOR UTILITY GROUNDING AND BONDING SHALL BE ALUMINUM-BODIED MECHANICAL LUGS WITH A RANGE OF NO. 6 250 KCMIL.

REFERENCE:

a SEE SG604.

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	-	-	11/15/2024	F						
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	07/16/2015	D						

SHEET 3 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION

SG608.3

SCOPE: THIS STANDARD PROVIDES GUIDELINES FOR THE CONNECTION OF SDG&E'S 12KV DISTRIBUTION SYSTEM TO A PRIMARY METERED SERVICE POINT FOR A 600V DIRECT CURRENT (DC) TROLLEY TRACTION STATION.




FIGURE 1

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. THE FOLLOWING REQUIREMENTS SHALL BE MET WHEN MAKING THIS CONNECTION:
 - a. SDG&E (UTILITY) SHALL LOCATE ITS SUBSTRUCTURE AS CLOSE AS PRACTICABLE TO THE CUSTOMER'S GROUND GRID BUT IN NO CASE SHALL THE SUBSTRUCTURE BE IN CONTACT WITH THE CUSTOMER'S GROUND GRID (GROUNDING ELECTRODE SYSTEM).
 - b. THE CONCENTRIC NEUTRALS FROM THE UTILITY'S CABLE SHALL NOT BE CONNECTED TO THE CUSTOMER'S EQUIPMENT.
 - c. THE CABLE TERMINATION IN THE CUSTOMER'S SWITCHGEAR CABINET SHALL BE A LIVEFRONT DELTA CONNECTION.
 - d. ALL REQUIREMENTS OF THE SWITCHBOARD UNDERGROUND SERVICE TERMINATING PULL SECTION STANDARD SHALL BE MET, EXCEPT AS MODIFIED BY THIS STANDARD AS IT PERTAINS TO SERVING VOLTAGE AND GROUNDING AND BONDING OF THE SYSTEM. (a)

REFERENCE:

- (a) SEE SG608: SWITCHGEAR UNDERGROUND SERVICE TERMINATING PULL SECTION.
- b. SEE SPM254 AND UG4705.

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	11/15/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 1 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E SERVICE STANDARDS & GUIDES

12KV SERVICE POINT CONNECTION FOR TROLLEY TRACTION STATION

SG609.1

<u>PAGE</u>	<u>SUBJECT</u>
702	ELECTRIC TERMINATING ENCLOSURES, 0–600V ALPHABETICAL SUBJECT INDEX
703	GENERAL INFORMATION
704	OVERHEAD SERVICE TERMINATING ENCLOSURE
705	UNDERGROUND PULL CAN WITH OR WITHOUT MECHANICAL LUGS
706	UNDERGROUND PULL CAN WITH CABLE TERMINATION BUS STUBS
707	RESIDENTIAL SINGLE-PHASE MULTI-METER STACK
708	UNDERGROUND PULL SECTION, 0-600V
709	CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	11/18/2024	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1

evision Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES Indicates Latest Revision Information Removed

ELECTRIC TERMINATING ENCLOSURES, 0–600V TABLE OF CONTENTS

SG701.1

<u>SUBJECT</u> <u>PAGE</u>
CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS
CONDUCTOR IDENTIFICATION
GENERAL INFORMATION
GROUNDING ELECTRODE, GROUNDING ELECTRODE CONDUCTOR
LINE TRUCK ACCESS
LOCATION
OVERHEAD SERVICE TERMINATING ENCLOSURE, STANDARD SWITCHBOARD SERVICE SECTION
PHASE ARRANGEMENT
RESIDENTIAL SINGLE-PHASE MULTI-METER STACK "SPECIAL APPLICATION"
UNDERGROUND PULL CAN WITH CABLE TERMINATION BUS STUBS
UNDERGROUND PULL CAN, WITH OR WITHOUT MECHANICAL LUGS
UNDERGROUND SERVICE PULL CAN, WITH MECHANICAL LUGS
UNDERGROUND SERVICE PULL CAN, WITHOUT MECHANICAL LUGS
UNDERGROUND PULL SECTION, 0-600V

© 1998 - 2024 San Diego Gas & Electric Company.		

				•	_					•			
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1

Indicates Latest Revision

Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

ELECTRIC TERMINATING ENCLOSURES, 0–600V ALPHABETICAL SUBJECT INDEX

SG702.1

Information Removed

SCOPE: THIS STANDARD PROVIDES GENERAL INFORMATION ON 0-600V ELECTRIC TERMINATING ENCLOSURES.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. SDGE (UTILITY) WILL PULL AND TERMINATE ITS SERVICE LATERAL CONDUCTORS DIRECTLY TO THE CUSTOMER-FURNISHED SERVICE TERMINATION FACILITIES WHICH CONSIST OF A FREE STANDING UNDERGROUND PULL SECTION (UGPS) OR A WALL-MOUNTED UNDERGROUND PULL CAN. NO OTHER METHOD OF TERMINATION IN AN ENCLOSURE IS ACCEPTABLE.
- II. TERMINATING ENCLOSURES MAY BE REMOTE FROM THE METERING SECTION; CONSULT THE UTILITY AND THE APPROPRIATE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) FOR LIMITATIONS. (a)
- III. A UGPS MAY NOT COME IN CONTACT WITH THE EARTH AND MUST BE LOCATED ON A SUITABLE FOUNDATION OR SLAB.
- IV. THE GROUNDING ELECTRODE AND/OR THE GROUNDING ELECTRODE CONDUCTOR ARE NOT TO BE PERMITTED WITHIN THE UTILITY PORTION OF THE UNDERGROUND PULL CAN OR PULL SECTION. THE COVERS ARE SEALED BY THE UTILITY AND NOT READILY ACCESSIBLE FOR THE AHJ TO INSPECT. (b)

V. CONDUCTOR IDENTIFICATION:

- a. EQUIPMENT GROUNDING CONDUCTORS: GREEN, OR GREEN WITH ONE OR MORE YELLOW STRIPES
- b. GROUNDED CONDUCTORS: WHITE OR GRAY IN COLOR
- c. HIGH LEG MARKING: 4-WIRE, DELTA-CONNECTED SERVICE WHERE THE MIDPOINT OF ONE PHASE IS GROUNDED THE SERVICE ENTRANCE CONDUCTOR HAVING THE HIGHER PHASE-TO-GROUND VOLTAGE (208V) SHALL BE MARKED ORANGE IN COLOR.
- d. **GROUNDED PHASE CONDUCTOR:** 3-WIRE, DELTA-CONNECTED SERVICE WHERE "B" PHASE IS CORNER-GROUNDED "B" PHASE SHALL BE MARKED RED IN COLOR.
- e. UNGROUNDED CONDUCTORS: COLOR OTHER THAN WHITE, GRAY, GREEN OR ORANGE IF COLOR MARKINGS ARE USED

VI. PHASE ARRANGEMENT:

- a. THE PHASE ARRANGEMENT SHALL BE "ABC" FRONT TO BACK, TOP TO BOTTOM, OR LEFT TO RIGHT AS VIEWED FROM THE FRONT OF THE TERMINATING ENCLOSURE AND IN SWITCHBOARDS.
- b. ON A THREE-PHASE, 4-WIRE, 120/240V DELTA-CONNECTED SERVICE, THE HIGH LEG SHALL BE IN THE "C" PHASE POSITION ONLY. SEE HIGH LEG MARKING IDENTIFICATION REQUIREMENTS ABOVE.

REFERENCE:

- (a) FOR AN ALTERNATIVE TO LINE TRUCK ACCESS TO TERMINATING ENCLOSURES, SEE SG016.
- (b) FOR EXCEPTION, SEE SG706.


	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CHA	NGE	DR	BY	DSN	APV	DATE
С	FORMATTING	EDM	JIK	-	-	11/18/2024	F								
В	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	Е								
Α	EDITORIAL CHANGES	-	JC	BRB	MDJ	08/26/2015	D								
	X Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page	Information Re	moved				

SHEET 1 OF 1

GENERAL INFORMATION

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG703.1



INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- $(\ {
 m I}\)$ Service entrance conductors as shown in Figure 1, either cable or bus bar, are furnished and installed by CUSTOMER IN THE FOLLOWING MANNER:
 - a. WHEN SWITCHBOARDS ARE SERVED THROUGH BUS BAR CONDUCTORS, THE CONDUCTORS SHALL ENTER THROUGH THE TOP, OR AT THE SIDE OR BACK IN THE UPPER 10-INCH SECTION.
 - b. WHEN SWITCHBOARDS ARE SERVED THROUGH CABLE CONDUCTORS (800A MAXIMUM), SERVICE ENTRANCE CONDUCTORS SHALL ENTER THROUGH THE TOP OF THE SWITCHBOARD ONLY AS SHOWN IN FIGURE 1.

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DATE **CHANGE** DR BY DSN APV DATE **REV CHANGE** DR BY DSN APV C F В **FORMATTING EDM** JIK 11/18/2024 Ε LSM TPM 11/01/2017 Α **EDITORIAL CHANGES** CTG **Indicates Latest Revision** Completely Revised New Page Information Removed

SHEET 1 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD SERVICE TERMINATING ENCLOSURE

SG704.1

NOTES (CONT'D):

- (II) WHEN CUSTOMER REQUIRES INCOMING CONDUITS FROM SIDE OR REAR FOR SERVICE ENTRANCE CONDUCTORS, AN EXTENSION AS SHOWN IN FIGURE 2 MAY BE USED.
- (III) DIRECTION OF FEED IS FROM TOP TO BOTTOM IN THE STANDARD SWITCHBOARD SERVICE SECTION. LOAD CONDUCTORS SHALL LEAVE BELOW THE MAIN SWITCH OR BREAKER, AND MAY NOT BE ROUTED BACK THROUGH THE CURRENT TRANSFORMER (CT) COMPARTMENT IN ORDER TO EXIT THE SERVICE SECTION.
- $\langle ext{IV}
 angle$ GROUNDING CONNECTIONS SHALL BE MADE IN THE MAIN SWITCH OR BREAKER COMPARTMENT.
- (v) Customer Provided Service Entrance Conductors Entering Switchboard
- $\widehat{
 m VI}$ switchboard extension for customer's conductors when required
- (VII) SERVICE ENTRANCE CONDUCTORS

REFERENCE: NONE

@ 1000 2021 Can Diama Can 9 Flactuia Camanani	All winds and an and Danas, all of this as a winds to a	tiaa ssittaasst mammaiaaiam ja mat mammaittaal ssmalan lasss
© 1998 - 2024 San Diego Gas & Electric Company	All nonts reserved Removal of this convitont no	nce wilhout bermission is not bermilled under law

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 2

Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

OVERHEAD SERVICE TERMINATING ENCLOSURE

SG704.2

SCOPE: THIS STANDARD PROVIDES THE REQUIREMENTS FOR UNDERGROUND PULL CANS WITHOUT MECHANICAL LUGS FOR CABLE TERMINATION.




FIGURE 1
UNDERGROUND SERVICE PULL CAN
WITHOUT MECHANICAL LUGS

TABLE 1

IADLL 1		MINIMUM PULL CAN D	IMENSIONS	WITHOUT MECHANICA	L LUGS					
		CUSTOME	R-INSTALLED)			IIMUM PULL			
TYPE OF SERVICE	SERVICE EQUIPMENT	SERVICE ENTRANCE CONDUCTORS MAX.	PHASE	MINIMUM SIZE SERVICE LATERAL C 3W OR 4W SERV	ONDUIT	DIMENSIONS RESIDENTIAL OR COMMERCIA (IN)				
	AMPACITY	WIRE SIZE		(IN)	TCL	Z	Y	X		
COMMERCIAL	0 - 100		SINGLE	_	a	10	12			
RESIDENTIAL	0 - 125	3/0	THREE	3	a	6	18	4		
COMMERCIAL	101 - 200	2FO KOMIL	SINGLE	2		12	10	C		
RESIDENTIAL	126 - 225	250 KCMIL	THREE	3	(a)	12	18	6		
COMMERCIAL	201 - 400	FOO I/CMTI	SINGLE	3		10	24	0		
RESIDENTIAL	226 - 400	500 KCMIL T	THREE	4	4	18	24	8		

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						·
	V To Post of the					and the latest the second		N. D. J.C. J. D.					

SHEET 1 OF 5 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND PULL CAN WITHOUT MECHANICAL LUGS

INSTALLATION:

UNDERGROUND SERVICE PULL CAN WITHOUT MECHANICAL LUGS

- A. SDG&E (UTILITY) ACCEPTS UNDERGROUND PULL CANS RATED 0–600V, 0–400A MAXIMUM, WITHOUT MECHANICAL LUGS FOR RESIDENTIAL OR COMMERCIAL/INDUSTRIAL SERVICE PROVIDED THE REQUIREMENTS OF THIS STANDARD ARE MET. PULL CANS ARE REQUIRED TO BE WALL-MOUNTED.
- B. PULL CANS SHALL BE READILY ACCESSIBLE AND LOCATED IN CONFORMANCE WITH THE REQUIREMENTS FOR ELECTRIC METERS. (d)
- C. PULL CANS OF THIS TYPE ARE USED TO PULL AND SPLICE CONNECTION OF THE UTILITY'S SERVICE LATERAL CONDUCTORS TO CUSTOMER-OWNED SERVICE ENTRANCE CONDUCTORS. THE SERVICE ENTRANCE CONDUIT MUST EXIT FROM THE TOP OR WITHIN 2 INCHES OF TOP OF PULL CAN. CUSTOMER SHALL PROVIDE ENOUGH WIRE TO REACH BOTTOM OF PULL CAN.
- D. PULL CANS WITHOUT MECHANICAL LUGS MAY ONLY BE USED WHEN ALL OF THE FOLLOWING REQUIREMENTS ARE MET:
 - 1. SERVICE EQUIPMENT AMPACITY RATING AND THE SIZE OF THE CUSTOMER'S CONDUCTORS DO NOT EXCEED THE VALUES SHOWN IN TABLE 1.
 - 2. NOT MORE THAN ONE CONDUCTOR PER PHASE AND NEUTRAL OF CUSTOMER SERVICE ENTRANCE CONDUCTORS ARE INSTALLED.
 - 3. THE UTILITY'S SERVICE LATERAL CONDUCTORS DO NOT EXCEED ONE RUN OF 3/C OR 4/C NO. 500 KCMIL.
- E. WHEN ALL OF THE ABOVE CONDITIONS CANNOT BE MET, SEE SHEET 3 FOR A PULL CAN WITH MECHANICAL LUGS.

BILL OF MATERIALS: NONE

NOTES:

- I 1-INCH SIDE CLEARANCE IS REQUIRED TO ANY SIDE WALL, EQUIPMENT OR OBSTRUCTION. ANY PROJECTION WHICH EXTENDS MORE THAN THE DEPTH OF THE PULL CAN FROM THE SURFACE ON WHICH THE PULL CAN IS MOUNTED SHALL BE CONSIDERED AN OBSTRUCTION.
- ${
 m (II)}$ SERVICE LATERAL CONDUIT MUST BE FIRMLY SECURED TO PULL CAN WITH LOCK NUT, HUB OR BUSHING AND MUST ENTER THE BOTTOM OF THE PULL CAN. MAXIMUM CONDUIT INTRUSION INSIDE CAN IS 1 INCH.
- (III) EXCEPTION TO THE 7-FOOT MAXIMUM MOUNTING HEIGHT MAY BE GRANTED DUE TO SPECIAL CONDITIONS. CONSULT WITH THE UTILITY.
- (IV) PULL CAN COVERS SHALL BE REMOVABLE AND SEALABLE. (b)
- (V) 3' X 3' Clear and level working space required in Front of Pull Can. (c)

REFERENCE:

- (a) FOR 2-INCH CONDUIT EXCEPTION, SEE SG309.2.
- (b) FOR SEALING REQUIREMENTS, SEE SG503.
- (c) for additional working space clearance requirements, see SG504.
- (d) SEE SG504.

	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		СН	IAI	NGE	DR	BY	DSN	APV	DATE
С							F									
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е									
Α	EDITORIAL CHANGES	LSM	CTG	TPM	11/01/2017	D										
	X Indicates La	evision	า	Con	npletely Revi	ised		New Page		Information Rem	noved					

SHEET 2 OF 5

UNDERGROUND PULL CAN WITHOUT MECHANICAL LUGS

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SCOPE: THIS STANDARD PROVIDES THE REQUIREMENTS FOR UNDERGROUND SERVICE PULL CANS WITH MECHANICAL LUGS FOR CABLE TERMINATION.

ATTENTION:

* THE UTILITY ACCEPTS UNDERGROUND PULL CANS RATED 0-600V, 0-800A MAXIMUM, WITH MECHANICAL LUGS FOR CABLE TERMINATION FOR RESIDENTIAL OR COMMERCIAL/INDUSTRIAL SERVICE PROVIDED THE REQUIREMENTS OF THIS STANDARD ARE MET. PULL CANS ARE REQUIRED TO BE WALL-MOUNTED.





FIGURE 1

	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.													
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE	
С							F							
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е							
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D							
	V Indicates Latest Businism Consolately Duringed New Days Information Demand													

SHEET 3 OF 5

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND SERVICE PULL CAN WITH MECHANICAL LUGS






FIGURE 2 COMBINATION UNDERGROUND (C)(L)(M) PULL AND DISCONNECT CAN




FIGURE 3 MECHANICAL LUG ARRANGEMENT FOR TERMINATING FACILITIES

TABLE 2

MINIMUM	PULL CA	N DIMEN	ISIONS				
SERVICE AMPACITY	WIDTH	Z (IN)	DEPTH	LUG			
SERVICE AMPACITY	3W	4W	Y (IN)	X (IN)			
0 - 200 I	10	14	6	11			
201 - 400	10	14	6	22			
401 - 800	16	22	11	26			

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 4 OF 5 Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND SERVICE PULL CAN WITH MECHANICAL LUGS

INSTALLATION:

- (A) SERVICE LATERAL CONDUITS, FIRMLY SECURED WITH A LOCKNUT, HUB OR BUSHING, MUST ENTER BOTTOM OF PULL CAN. MAXIMUM CONDUIT INTRUSION INSIDE PULL CAN IS 1 INCH. LOAD CONDUITS MUST EXIT ABOVE SHADED AREA. $\stackrel{\frown}{a}$
- (B) BONDING CONNECTION FOR SERVICE LATERAL CONDUITS ONLY IS PERMITTED AT BOTTOM OF CAN. ANY OTHER BONDING OR GROUNDING CONNECTION MUST BE MADE ABOVE THE SHADED AREA AND NO GROUNDING OR BONDING CONDUCTOR IS PERMITTED TO PASS THROUGH SHADED AREA.
- C IN THE COMBINATION UNDERGROUND PULL AND DISCONNECT CAN (SEE FIGURE 2) THE GROUNDING ELECTRODE CONDUCTOR OR BOND JUMPER MAY BE INSTALLED IN A FULLY ENCLOSED, FACTORY-INSTALLED WIREWAY (2" X 2" MAXIMUM) LOCATED IN EITHER BACK CORNER OF THE PULL CAN AREA (SEE FIGURE 2 BOTTOM VIEW). THE RACEWAY MAY NOT IMPEDE THE REQUIRED WORKING SPACE OR REDUCE ANY SPECIFIC CLEARANCES.
- (D) SHADED AREA IS FOR UTILITY SERVICE LATERAL CONDUCTOR ONLY. (B)
- E TERMINATING FACILITIES FOR UTILITY'S SERVICE LATERAL CONDUCTORS SHALL BE ALUMINUM-BODIED MECHANICAL LUGS WITH A RANGE ACCEPTING ONE 4 AWG THROUGH 500 KCMIL CONDUCTOR. ONE LUG SHALL BE PROVIDED FOR TERMINATIONS RATED UP TO 400A AND TWO LUGS FOR TERMINATIONS RATED 401-800A. REFER TO SG707 FOR EXCEPTION THAT ALLOWS A SINGLE LUG FOR 600A SPECIAL APPLICATION. (b)
- (F) MAXIMUM HEIGHT FROM STANDING SURFACE TO CENTERLINE OF MECHANICAL LUG IS 60 INCHES. UTILITY MAY APPROVE GREATER HEIGHT DUE TO SPECIAL CIRCUMSTANCES. CONSULT WITH THE UTILITY.
- G THIS DIMENSION IS THE MINIMUM WIDTH OF PULL CAN ACCESS OPENING AND IS MEASURED BETWEEN LEFT SIDE AND RIGHT SIDE RETURN FLANGES; NOT INTERIOR WALLS OF PULL CAN.
- (H) WHEN VIEWED FROM FRONT OF PULL CAN, RETURN FLANGES SHALL NOT EXTEND CLOSER THAN 3/4-INCH FROM OUTSIDE EDGE OF MECHANICAL LUG.
- (J) 1 Inch minimum side clearance is required from side of Pull can to any other equipment or obstruction.
- (K) ALL PULL CANS SHALL HAVE FULL FRONT ACCESS. COVER PANELS SHALL BE REMOVABLE, SEALABLE, PROVIDED WITH TWO LIFTING HANDLES, AND LIMITED TO A MAXIMUM OF 9 SQUARE FEET IN AREA. SEALING PROVISIONS SHALL CONSIST OF TWO DRILLED STUD AND WING-NUT ASSEMBLIES ON OPPOSITE SIDES OF THE PANEL. A MINIMUM OF 4 INCHES IS REQUIRED FROM BUS TO INSIDE OF PANEL COVER AND 1 INCH MINIMUM FROM BOLT TERMINATION TO INSIDE OF PANEL COVER. (C)
- (L) IN PULL CANS RATED 0-800A, EITHER BUS BAR OR CABLE CONNECTIONS MAY BE USED FROM TOP OF THE CABLE TERMINATION BUS TO SERVE A CURRENT TRANSFORMER (CT) COMPARTMENT, A SINGLE MAIN DISCONNECT, AND MULTIPLE MAIN DISCONNECTS.
- (M) A MAIN SERVICE OR METER SERVICE DISCONNECT IS NOT PERMITTED ON SUPPLY (LINE) SIDE OF A SINGLE METER.

BILL OF MATERIALS: NONE

NOTES:

(I) 225A FOR RESIDENTIAL SERVICE EQUIPMENT

REFERENCE:

- (a) FOR SERVICE LATERAL CONDUIT REQUIREMENTS, SEE SG309.
- (b) SEE SG707.
- (c) FOR SEALING REQUIREMENTS, SEE SG503.
- d. FOR CONDUCTOR IDENTIFICATION AND PHASE ARRANGEMENT, SEE SG703.

	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CI	IAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	EDITORIAL CHANGE	ANGES/FORMATTING EDM JTM IWA KRG 11/18/2024 E																
Α	A EDITORIAL CHANGES				LSM	CTG	TPM	11/01/2017	D									
		Latest Revision Completely Revised New Page Inf							Information Re	noved								
SHEET SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																		

SHEET 5 OF 5

UNDERGROUND SERVICE PULL CAN WITH MECHANICAL LUGS

SCOPE: THIS STANDARD PROVIDES THE REQUIREMENTS FOR UNDERGROUND PULL CANS WITH CABLE TERMINATION BUS STUBS.

ATTENTION:

- * SDG&E (UTILITY) ACCEPTS UNDERGROUND PULL CANS RATED 0-600V, 801-1,200A MAXIMUM, WITH CABLE TERMINATION BUS STUBS FOR RESIDENTIAL OR COMMERCIAL/INDUSTRIAL SERVICE PROVIDED THE REQUIREMENTS OF THIS STANDARD ARE MET.
- ** PULL CANS ARE REQUIRED TO BE WALL-MOUNTED.




FIGURE 1
FRONT VIEW

FIGURE 1 SIDE VIEW J K d e FIGURE 2
COMBINATION
UNDERGROUND PULL
AND DISCONNECT CAN (C) L

TABLE 1

MINIMUM PULL CAN DIMENSIONS WIDTH Z (IN) DEPTH LUG SERVICE AMPACITY													
CERVICE AMRACITY	WIDTH	IZ (IN)	DEPTH	LUG									
SERVICE AMPACITY	3W	4W	Y (IN)	X (IN)									
801 – 1,200		30	11	26									

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	ı	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG706.1

UNDERGROUND PULL CAN WITH CABLE TERMINATION BUS STUBS

INSTALLATION:

- (A) SERVICE LATERAL CONDUITS, FIRMLY SECURED WITH LOCKNUT, HUB, OR BUSHING, MUST ENTER BOTTOM OF PULL CAN. MAXIMUM CONDUIT INTRUSION INSIDE PULL CAN IS 1 INCH. LOAD CONDUITS MUST EXIT ABOVE SHADED AREA. (a)
- (B) BONDING CONNECTION FOR SERVICE LATERAL CONDUITS ONLY IS PERMITTED AT BOTTOM OF CAN. ANY OTHER BONDING OR GROUNDING CONNECTION MUST BE MADE ABOVE THE SHADED AREA AND NO GROUNDING OR BONDING CONDUCTOR IS PERMITTED TO PASS THROUGH THE SHADED AREA.
- C IN THE COMBINATION UNDERGROUND PULL AND DISCONNECT CAN (SEE FIGURE 2) THE GROUNDING ELECTRODE CONDUCTOR OR BOND JUMPER MAY BE INSTALLED IN A FULLY ENCLOSED, FACTORY-INSTALLED WIREWAY (2" X 2" MAXIMUM) LOCATED IN EITHER BACK CORNER OF THE PULL CAN AREA (SEE FIGURE 2, BOTTOM VIEW). THE RACEWAY MAY NOT IMPEDE THE REQUIRED WORKING SPACE OR REDUCE ANY SPECIFIED CLEARANCES.
- D SHADED AREA IS FOR UTILITY SERVICE LATERAL CONDUCTOR ONLY. (B)
- (E) MAXIMUM HEIGHT FROM STANDING SURFACE TO CENTERLINE OF LOWEST TERMINATION BOLT IS 60 INCHES. UTILITY MAY APPROVE GREATER HEIGHT DUE TO SPECIAL CIRCUMSTANCES. CONSULT WITH THE UTILITY. 3'-0" X 3'-0" CLEAR AND LEVEL WORKING SPACE IS REQUIRED IN FRONT OF THE PULL CAN. (b)
- (F) THIS DIMENSION IS THE MINIMUM WIDTH OF PULL CAN ACCESS OPENING AND IS MEASURED BETWEEN LEFT SIDE AND RIGHT SIDE RETURN FLANGES; NOT THE INTERIOR WALLS OF THE PULL CAN.
- G WHEN VIEWED FROM FRONT OF PULL CAN, RETURN FLANGES SHALL NOT EXTEND TO CLOSER THAN 3/4-INCH FROM THE OUTSIDE EDGE OF BUS STUB.
- (H) 1-INCH MINIMUM SIDE CLEARANCE IS REQUIRED FROM SIDE OF PULL CAN TO ANY OTHER EQUIPMENT OR OBSTRUCTION.
- ALL PULL CANS SHALL HAVE FULL FRONT ACCESS. COVER PANELS SHALL BE REMOVABLE, SEALABLE, PROVIDED WITH TWO LIFTING HANDLES, AND LIMITED TO A MAXIMUM OF 9 SQUARE FEET IN AREA. SEALING PROVISIONS SHALL CONSIST OF TWO DRILLED STUD AND WING-NUT ASSEMBLIES ON OPPOSITE SIDES OF THE PANEL. A MINIMUM OF 4 INCHES IS REQUIRED FROM BUS TO INSIDE OF PANEL COVER AND 1 INCH MINIMUM FROM BOLT TERMINATION TO INSIDE OF PANEL COVER.
- (K) IN PULL CANS RATED 801–1,200A, BUS BAR CONNECTIONS ARE REQUIRED FROM TOP OF CABLE TERMINATION BUS STUBS TO SERVE A CURRENT TRANSFORMER (CT) COMPARTMENT. THE REASON FOR REQUIRING BUS BAR CONNECTIONS IS LARGE CABLE WILL QUITE OFTEN PULL CT BUSSES OUT OF THEIR VERTICAL ALIGNMENT, MAKING IT DIFFICULT OR IMPOSSIBLE TO MOUNT CTS. BUS BARS ARE NOT REQUIRED TO SERVE A MAIN DISCONNECT.
- (L) A MAIN SERVICE OR METER SERVICE DISCONNECT IS NOT PERMITTED ON THE SUPPLY (LINE) SIDE OF A SINGLE METER.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

- (a) FOR SERVICE LATERAL CONDUIT REQUIREMENTS, SEE SG309.
- (b) For additional working space clearance requirements, see SG504.
- (c) FOR SEALING REQUIREMENTS, SEE SG503.
- (d) FOR CONDUCTOR IDENTIFICATION AND PHASE ARRANGEMENT, SEE SG703.
- (e) FOR BUS AND BOLT DETAILS, SEE SG709.

	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		CHAI	NGE		DR	BY	DSN	APV	DATE
С							F									
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е									
Α	EDITORIAL CHANGES	LSM	CTG	TPM	11/01/2017	D										
	V Indicates La	ovicio	n	Con	nnletely Pevi	hasi		New Page	In	formation Per	noved					

SHEET 2 OF 2

UNDERGROUND PULL CAN WITH CABLE TERMINATION BUS STUBS


SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG706.2

SCOPE: THIS SPECIAL APPLICATION STANDARD PROVIDES THE REQUIREMENTS FOR A FACTORY-MANUFACTURED PULL CAN AND METER STACK(S) FOR RESIDENTIAL MULTI-FAMILY OCCUPANCY ONLY, RATED 600A MAXIMUM, SINGLE-PHASE, 3-WIRE, 120/208V OR 120/240V, WITH SIX METERS MAXIMUM.

ATTENTION:

- THIS EQUIPMENT IS REQUIRED TO BE WALL-MOUNTED.
- THIS STANDARD DOES NOT APPLY TO FIELD INSTALLED PULL CANS WITH RACEWAYS AND CABLING TO INDIVIDUAL METER PANELS.
- *** THE SDG&E PLANNER SHALL PROVIDE THE CUSTOMER WITH A COPY OF THIS STANDARD WITH THE ELECTRIC METER & SERVICE LOCATION FORM BECAUSE IT IS A SPECIAL APPLICATION. IT IS IMPORTANT FOR THE CUSTOMER TO UNDERSTAND THE EQUIPMENT MUST BE FACTORY-MANUFACTURED WITH HORIZONTAL BUSSING FROM THE PULL CAN TO THE METERING SECTION(S).






FIGURE 3 METER PANEL COVER CUTOUT DETAIL

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 2

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

RESIDENTIAL SINGLE-PHASE MULTI-METER STACK

SG707.1

TABLE 1

	RE	QUIRED DIMENS	IONS		
CEDVICE FOLITOMENT	MINIMUM SER	VICE EQUIPMEN	T DIMENSIONS	MINIMUM CONDUIT	MAXIMUM CONDUIT
SERVICE EQUIPMENT (A)	Z (IN)	Y (IN)	X (IN)	SIZE (QTY - IN)	SIZE (QTY - IN)
0 - 200	6 1/2	5 1/2	11	1 - 3	1 - 4
201 - 400	10 1/2	6	22	1 - 3	1 - 4
401 - 600	10 1/2	6	22	1 - 4	1 - 4

INSTALLATION:

- $m(\mathtt{A})$ shaded area is for utility service lateral conductor only. Bonding connection for service lateral conduits ONLY IS PERMITTED AT BOTTOM OF CAN. ANY OTHER BONDING OR GROUNDING CONNECTION MUST BE MADE ABOVE THE SHADED AREA AND NO GROUNDING OR BONDING CONDUCTOR IS PERMITTED TO PASS THROUGH THE SHADED AREA.
- (\mathtt{B}) SERVICE LATERAL CONDUITS MUST ENTER THE BOTTOM OF THE PULL CAN AND BE FIRMLY SECURED WITH A LOCKNUT, HUB OR BUSHING. THE MAXIMUM CONDUIT INTRUSION INSIDE THE SHADED AREA IS 1 INCH. (a)
- A "SINGLE LUG" FOR 600A IS PERMITTED FOR THIS APPLICATION ONLY. SERVICE_CONDUCTORS MAY CROSS OVER HORIZONTAL BUSSES PROVIDED A BARRIER IS INSTALLED OR THE BUS IS FULLY INSULATED. (b)
- (D) THE NEUTRAL LUG HEIGHT MAY BE REDUCED TO 8 1/2 INCHES.
- m (E) the pull can cover shall be independent of any other service equipment and shall be removable without DISTURBING ADJACENT PANELS. PULL CAN COVERS SHALL HAVE TWO LIFTING HANDLES AND ARE LIMITED TO 9 SQUARE FEET IN AREA. COVERS SHALL BE SEALABLE WITH TWO DRILLED STUD AND WING-NUT ASSEMBLIES ON OPPOSITE SIDES OF THE PANEL. (c)
- THIS DIMENSION IS THE MINIMUM WIDTH OF PULL CAN ACCESS OPENING AND IS MEASURED BETWEEN LEFT SIDE AND RIGHT SIDE RETURN FLANGES, NOT THE INTERIOR WALLS OF THE PULL CAN.
- (g) a minimum 3'-0" x 3'-0" clear and level working space is required in front of the pull can.(d)
- (H) BUS TAPS ARE NOT PERMITTED IN THIS SPECIAL APPLICATION.

EXCEPTION: TAPS FOR SOLAR POWER INPUT ARE PERMITTED WITH APPROVAL FROM SDG&E SERVICE STANDARDS. (f)

BILL OF MATERIALS: NONE

NOTES:

m (I) meter stack to left or right of Pull can

REFERENCE:

- (a) FOR SERVICE LATERAL CONDUIT REQUIREMENTS, SEE SG309.
- (b) FOR MECHANICAL LUG DETAILS, SEE SG705.
- (c) FOR SEALING REQUIREMENTS, SEE SG503.
- (d) FOR ADDITIONAL WORKING SPACE CLEARANCE REQUIREMENTS, SEE SG504.
- (e) FOR METER CABINET REQUIREMENTS, SEE SG509.
- (f) For approval procedure, see SG517.1.

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 2 OF 2

Completely Revised Indicates Latest Revision New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SG707.2

RESIDENTIAL SINGLE-PHASE MULTI-METER STACK

SCOPE: THIS STANDARD DESCRIBES 0-600V UNDERGROUND PULL SECTIONS.

ATTENTION:


* SDG&E (UTILITY) ACCEPTS FREE-STANDING UNDERGROUND PULL SECTIONS (UGPS), RATED 0-600V, 4,000A MAXIMUM, PROVIDED ALL REQUIREMENTS OF THIS STANDARD ARE MET.




PULL SECTION 4,000A MAXIMUM (B)(C)(D) PULL SECTION 2,000A MAXIMUM (B)(C)(D) **BOTTOM FEED ONLY** SEE TABLE 1

FIGURE 2 **BOTTOM FEED ONLY** SEE TABLE 1

FIGURE 3



EXAMPLE 1 CONDUIT PLACEMENT FOR MAXIMUM NUMBER OF CONDUITS



EXAMPLE 2 CONDUIT PLACEMENT

FIGURE 4 PLAN VIEW UGPS (G)

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 3 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND PULL SECTION, 0-600V

SG708.1

TABLE 1

	MINIMUM PULL SE	CTION DIMENSIONS	G
PULL SECTION RATING	WIDTH	ł Z (IN)	LUG HEIGHT
(AMPS)	3W	4W	Y (IN)
0 - 400	10	14	22 - 72
401 - 800	16	22	26 – 72
801 – 1,200		30	26 – 72
1,201 – 2,000		35	<mark>42</mark> - 72
2,001 – 3,000		42	60 - 72
3,001 – 4,000		44	60 - 72

INSTALLATION:

- (A) UNDERGROUND SERVICE LATERAL CONDUITS SHALL ENTER THE BOTTOM OF THE UGPS. THE GROUNDING ELECTRODE AND/OR GROUNDING ELECTRODE CONDUCTOR WILL NOT BE PERMITTED WITHIN THE UTILITY PORTION OF THE UGPS. NO OTHER CONDUCTORS, EQUIPMENT OR CONNECTIONS ARE PERMITTED IN THE SHADED AREA. (a)
- (B) BOLT TERMINATIONS ARE REQUIRED FOR ALL UGPS. SEE TABLE 1 FOR MINIMUM AND MAXIMUM TERMINATION HEIGHTS. THE UTILITY WILL PROVIDE THE TERMINATION LUGS, CONNECT THE SERVICE LATERAL CONDUCTORS TO THE TERMINATION LUGS, AND CONNECT TO THE CUSTOMER-PROVIDED TWO-BOLT TERMINATION BUS STUBS. (b)
- © BUS BARS OR CABLES MAY EXTEND FROM THE UGPS INTO SWITCHBOARD SERVICE SECTIONS RATED UP TO 800A. BUS BARS ARE REQUIRED WHEN THE SERVICE SECTION RATING EXCEEDS 800A, OR WHEN A MULTIPLE METERING SECTION(S) IS SUPPLIED.
- D SERVICE CONDUCTORS MUST TERMINATE IN THE UGPS AND SHALL NOT BE PULLED THROUGH THE UGPS TO LAND ON A MAIN OR CURRENT TRANSFORMER (CT) BUS.
- E THIS DIMENSION, SHOWN IN TABLE 1, IS THE MINIMUM WIDTH OF THE UGPS ACCESS OPENING AND IS MEASURED BETWEEN LEFT SIDE AND RIGHT SIDE RETURN FLANGES, NOT INTERIOR WALLS OF THE UGPS.
- F ALL UGPS SHALL HAVE FULL FRONT ACCESS. COVER PANELS SHALL BE REMOVABLE, SEALABLE, PROVIDED WITH TWO LIFTING HANDLES, AND LIMITED TO A MAXIMUM OF 9 SQUARE FEET IN AREA. SEALING PROVISIONS SHALL CONSIST OF TWO DRILLED STUD AND WING-NUT ASSEMBLIES ON OPPOSITE SIDES OF THE PANEL. THE MINIMUM CLEARANCE FROM ANY ENERGIZED PART TO A REMOVABLE ACCESS COVER PANEL SHALL BE 4 INCHES. THIS CLEARANCE MAY BE REDUCED TO 1 1/2 INCHES WHEN A SAFETY BARRIER IS PROVIDED BY THE MANUFACTURER AS SPECIFIED IN SG709, NOTE H. (c) h
- G THERE IS NO MINIMUM DEPTH DIMENSION SHOWN OR REQUIRED BY THE UTILITY. THE DEPTH OF THE EQUIPMENT IS DETERMINED BY MEETING BUS CLEARANCES AND PROVIDING SPACE FOR THE CONDUIT ENTRY. (d)
- (H) MAXIMUM CONDUIT INTRUSION INTO THE UGPS IS 2 INCHES.
- J UGPS THAT REQUIRE 2-INCH, 3-INCH, OR 4-INCH CONDUITS MUST ALLOW A MINIMUM OF 3 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE UGPS. UGPS REQUIRING 5-INCH CONDUITS MUST ALLOW A MINIMUM OF 6 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE UGPS. (e)
- (K) A MAIN SERVICE OR METER SERVICE DISCONNECT IS NOT PERMITTED ON THE SUPPLY (LINE) SIDE OF A SINGLE METER.

BILL OF MATERIALS: NONE

NOTES: NONE

	© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.															
REV	CHANGE	DR	BY	DSN	APV	DATE	REV		С	HAN	IGE	DR	BY	DSN	APV	DATE
С							F									
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е									
Α	EDITORIAL CHANGES	LSM	CTG	TPM	11/01/2017	D										
	X Indicates La	evisio	n	Con	npletely Revi	ised		New Page	X	Information Rem	noved					

SHEET 2 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG708.2

UNDERGROUND PULL SECTION, 0-600V

REFERENCE:

- (a) FOR SERVICE LATERAL CONDUIT REQUIREMENTS, SEE SG309.
- (b) FOR BOLT TERMINATIONS, SEE SG709.
- (c) for additional sealing requirements, see SG503.
- (d) FOR BUS CLEARANCES, SEE SG709.
- (e) For additional working space clearance requirements, see SG504.
- f. FOR ELECTRIC METER ROOM REQUIREMENTS, SEE SG506.
- g. FOR METER CABINET REQUIREMENTS, SEE SG509.
- (h) SEE SG709, NOTE H.

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						


SHEET 3 OF 3

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UNDERGROUND PULL SECTION, 0-600V

SG708.3

SCOPE: THIS STANDARD PROVIDES THE REQUIREMENTS FOR CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR UNDERGROUND PULL SECTIONS (UGPS).







FIGURE 1
TERMINATING BOLT AND F
DRILLING DETAIL

FIGURE 1
TERMINATING BOLT AND F
DRILLING DETAIL
SINGLE POSITION






FIGURE 1
TERMINATING BOLT AND DRILLING DETAIL B F
MULTIPLE POSITION

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	ı	LSM	CTG	TPM	11/01/2017	D						

SHEET 1 OF 6 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SPORE ELECTRIC SERVICE STANDARDS & GOIDES

CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS




FIGURE 2
SPACING REQUIREMENTS FOR TERMINATING FACILITIES (G)
(SIDE BY SIDE OR STAGGERED)
PULL CANS
801A – 1,200A




FIGURE 2
SPACING REQUIREMENTS FOR TERMINATING FACILITIES (E)
(SIDE BY SIDE OR STAGGERED)
SWITCHBOARD PULL SECTIONS

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
													

SHEET 2 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS



$\begin{array}{c} \textbf{FIGURE 3} \\ \text{SPACING REQUIREMENTS FOR TERMINATING FACILITIES} \\ \hline \textbf{SEE TABLE 1} \end{array}$

TABLE 1

	SPACING REQUIREMENTS DESCRIPTION LIST
ITEM	DESCRIPTION
$\langle 1 \rangle$	ACCESSIBLE FROM FRONT ONLY
2	ACCESSIBLE FROM ONE SIDE ONLY
3	ACCESSIBLE FROM EITHER SIDE
4	BOLT HOLES
(5)	BOLTS SECURED IN PLACE

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						

SHEET 3 OF 6

Indicates Latest Revision Completely Revised New Page X Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS






FIGURE 5 SPACING REQUIREMENTS FOR TOP TO BOTTOM STAGGER OF TERMINATING FACILITIES FRONT VIEW SEE TABLE 1

© 1998 - 2024 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е						
Α	EDITORIAL CHANGES	-	LSM	CTG	TPM	11/01/2017	D						
_													

SHEET 4 OF 6

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS

INSTALLATION:

- A. BOLT TERMINATIONS SHOWN IN FIGURES 1 THROUGH 5 ARE REQUIRED FOR PULL CANS RATED OVER 800A, AND ALL UGPS (FREE STANDING).
- (B) one landing position is required for each 400A, or portion thereof, of service capacity.
 - 1. EACH LANDING POSITION SHALL CONSIST OF TWO 1/2-INCH STEEL BOLTS SPACED ON 1 3/4-INCH VERTICAL CENTERS AND EXTENDING FROM 2 TO 2 1/2 INCHES FROM THE MOUNTING SURFACE. WHEN MULTIPLE POSITIONS ARE REQUIRED, PROVIDE A MINIMUM OF 2 INCHES OF HORIZONTAL SPACING BETWEEN POSITIONS.
 - 2 EXCEPTION: EDGEWISE TERMINATING FACILITIES MAY CONSIST OF 9/16-INCH HOLES HAVING THE SAME SPACING AS SPECIFIED FOR THE 1/2-INCH BOLTS ABOVE. THE UNOBSTRUCTED WORKING SPACE SHALL BE PROVIDED ON BOTH SIDES OF TERMINATION BUS.
- (C) EACH TERMINATING BOLT SHALL BE PROVIDED WITH A SPRING WASHER AND A NUT. THE SPRING WASHER MAY BE EITHER A CONE-TYPE (BELLEVILLE) WASHER OR A SPLIT-RING WASHER AND A FLAT WASHER. ALL PARTS SHALL BE PLATED TO PREVENT CORROSION. TERMINATING BOLTS SHALL NOT BE USED TO SECURE TERMINATION BUS IN PLACE.
- D TERMINATING BOLTS MUST BE SECURED IN PLACE. "SECURED IN PLACE" SHALL MEAN THAT THE STUD WILL NOT TURN, BACK OUT, OR LOOSEN IN ANY MANNER WHEN TIGHTENING OR LOOSENING TERMINAL NUTS (INCLUDING CROSS-THREADED SITUATIONS).
- (E) EACH TERMINATING FACILITY SHALL HAVE AN UNOBSTRUCTED WORKING SPACE, ACCESSIBLE FROM FRONT OF THE UGPS AS VIEWED FROM ACCESS COMPARTMENT OPENING, IN FRONT OF ENTIRE MOUNTING SURFACE AS SHOWN IN FIGURES 3 AND 4. NO MORE THAN ONE TERMINATION FACILITY MAY BE MOUNTED ALONG A SIDE WALL. WHEN VIEWED FROM FRONT OF THE PULL CAN OR UGPS, NO OTHER TERMINATION OR CABLES IN PLACE SHALL IMPAIR THE 8-INCH MINIMUM WORKING CLEARANCE. UNINSULATED BUSSES OF DIFFERENT POTENTIALS SHALL NOT BE PERMITTED BELOW OR BEHIND ANY TERMINATING POSITION AS VIEWED FROM FRONT OF THE UGPS. IF CROSS-BUSSING IS INSTALLED BELOW OR BEHIND A TERMINATING POSITION, CROSS-BUSSING SHALL BE FULLY INSULATED OR BARRIERED.
 - 1. EXCEPTION: FOR TERMINATING FACILITIES WITH BOLTS FACING THE ACCESS OPENING, THE REQUIRED 1 1/2-INCH SIDE CLEARANCE (BUS TO ACCESS OPENING RETURN FLANGE) MAY BE REDUCED TO 3/4 INCH.
- F IN THE TERMINAL MOUNTING AREA, WHICH IS DEFINED AS THE AREA OF THE TERMINATING FACILITIES, A CLEAR SPACE (BARREL OF PROXIMITY) OF A MINIMUM 1 1/2-INCH RADIALLY AND 3 INCHES ABOVE THE TOP BOLT IS REQUIRED AROUND ANY TERMINATING FACILITY INCLUDING ITS BOLTS AND BOLT HEADS, ANY OTHER BUS, ANY OTHER TERMINATING FACILITY, OR ANY GROUNDED SURFACE, EXCEPT AS FOLLOWS:
 - 1. MINIMUM CLEARANCE TO BACK OF UGPS MAY BE REDUCED TO 1 INCH.
 - 2. MINIMUM CLEARANCE TO ANY FULLY INSULATED HORIZONTAL BUS BEHIND TERMINATING FACILITY MAY BE REDUCED TO 1 INCH.
 - 3. NEUTRAL TERMINATING FACILITY MAY HAVE A MINIMUM CLEARANCE OF 1 INCH FROM ANY GROUNDED SURFACE.
 - 4. THE CLEARANCE DIRECTLY ABOVE AND MEASURED FROM THE CENTER OF THE TOP TERMINATION BOLT MAY BE REDUCED TO 1 INCH TO EITHER AN INSULATED SURFACE OR BUS OF THE SAME POTENTIAL.
- (G) FOR PULL CANS/PULL BOXES, A MINIMUM OF 4 INCHES IS REQUIRED FROM BUS TO THE INSIDE OF PANEL COVER AND 1 INCH MINIMUM FROM BOLT TERMINATION TO INSIDE OF PANEL COVER.

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CHA	AN	GE	DR	BY	DSN	APV	DATE
С								F				_					
В	EDITORIAL CHANGE	S/FORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е									
Α	EDITORIAL (CHANGES	-	LSM	CTG	TPM	11/01/2017	D									
		X Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Rea	moved				
	SHEET	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															
		CARLE TERMINATION RUC CTURC IN													S	G709	9.5
	5 OF 6		CABLE TERMINATION BUS STUBS IN														

UNDERGROUND PULL CANS OR PULL SECTIONS

INSTALLATION (CONT'D):

- H FOR SWITCHBOARD PULL SECTIONS, THE MINIMUM CLEARANCE FROM ANY ENERGIZED PART TO A REMOVABLE ACCESS COVER PANEL SHALL BE 4 INCHES. THIS CLEARANCE MAY BE REDUCED TO 1 1/2 INCHES WHEN A SAFETY BARRIER IS PROVIDED BY THE MANUFACTURER. THE SAFETY BARRIER SHALL CONFORM TO THE FOLLOWING:
 - 1. BE CONSTRUCTED OF A RIGID INSULATING MATERIAL, RESISTANT TO DAMAGE BY IMPACT OR PUNCTURE, WITH A MINIMUM THICKNESS OF 1/8-INCH.
 - 2. EXTEND A MINIMUM OF 10 INCHES BELOW TERMINATING BUS AND EXTEND UPWARD TO COVER ALL ENERGIZED PARTS THAT INFRINGE INTO THE 4-INCH MINIMUM CLEARANCE DIMENSION, AND BE REMOVABLE.

ATTENTION:

- * BRACKETS AND ASSOCIATED HARDWARE USED TO MOUNT THE SAFETY BARRIER SHALL NOT EXTEND INTO THE PROVIDED ACCESS OPENING.
- 3. HAVE A CAUTION SIGN AFFIXED TO THE BARRIER READING:

"WARNING: THE BARRIER MUST BE INSTALLED BEFORE REPLACING PULL SECTION COVERS".

- 4. HAVE ADDITIONAL CAUTION SIGNS AFFIXED TO EXTERIOR OF EACH SECTION ACCESS COVER READING: "DO NOT REPLACE PULL SECTION COVERS UNTIL SAFETY BARRIER IS IN PLACE".
- 5. SCREWS OR BOLTS REQUIRING SPECIAL TOOLS FOR INSTALLATION OR REMOVAL ARE NOT ACCEPTABLE.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

(a) FOR MINIMUM TERMINATION HEIGHTS, SEE SG706 OR SG708, WHICHEVER IS APPLICABLE.

	© 1998 - 2024 S	an Di	iego Gas & Eld	ectric C	compa	ny. All	rights r	reserved. Rer	noval	of th	nis copyright no	otice	e without permission	is not	permit	ted und	der law	-
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		С	HAI	NGE	DR	BY	DSN	APV	DATE
С									F									
В	EDITORIAL CHANGE	ES/F0	ORMATTING	EDM	JTM	IWA	KRG	11/18/2024	Е									1
Α	EDITORIAL (CHAN	NGES	-	LSM	CTG	TPM	11/01/2017	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Re	moved				
1					SDC	%F F	FCTI	RIC SERVIC	F ST	ΔΝΙ	DARDS & GI	IID	FS					

SHEET 6 OF 6

CABLE TERMINATION BUS STUBS IN UNDERGROUND PULL CANS OR PULL SECTIONS

13

<u>62</u>

13

<u>62</u>

<u>PAGE</u>	SUBJECT
802	CUSTOMER GENERATION ALPHABETICAL SUBJECT INDEX
803	GENERAL INFORMATION
804	STAND-BY GENERATOR SAFETY TRANSFER SWITCH
805	STAND-BY GENERATOR
806	DISTRIBUTED GENERATION
807	DISTRIBUTED GENERATION - METERING
808	DISTRIBUTED GENERATION - METERING SAFETY SOCKET METER CAN
809	DISTRIBUTED GENERATION - METERING TRANSFORMER RATED METER PANEL
810	DISTRIBUTED GENERATION - METERING CLEARANCE REQUIREMENTS
811	DISTRIBUTED GENERATION - METERING TYPICAL BILLING AND POWER PURCHASE METERS

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CUSTOMER GENERATION TABLE OF CONTENTS

SG801.1

<u> </u>	<u>SUBJECT</u>												<u> </u>	PAGE						
C	CUSTOMER GENERA	ATION																		
	CONNECTION	OF CUSTOMER-	OWN	ED PO	OWER	GENE	ERATORS 1	TO SD	G&E'S ELECTRICAL SYSTEM					803.1						
	DIRECTORY													803.1						
	GENERAL INFO	RMATION												803						
	NET GENERAT	ION OUTPUT MI	ETERI	NG										803.1						
	PERMANENTLY	OR TEMPORAR	RILY C	ONNI	ECTE	STA	NDBY GEN	ERAT	ORS			80	3.2 –	803.3						
	VIOLATIONS											803.2								
	WARNING STA	TEMENTS AND	LABE	LS								803.2								
С	DISCONNECTION D	EVICES										806.3 – 806.4								
	CIRCUMSTANC	ES REQUIRING	DISC	ONNE	ECTS .									806.4						
	INVERTER-BAS	SED DEVICES												806.3						
	UTILITY AC DI	SCONNECT REC	UIRE	MEN	ΓS							806.								
С	DISTRIBUTED GENE	ERATION											80	6 <mark>-811</mark>						
	ACCESSIBILITY	Y												807.6						
	BILLING POWER AND PURCHASE METERING													807.3						
	DISCONNECTI	ON DEVICES										80	6.3 –	806.4						
	DISCONNECTI	on of <mark>Genera</mark>	<mark>TOR</mark> .											<mark>807.6</mark>						
	GENERAL INFO	ORMATION												806						
	INTERCONNEC	TION PROCESS	PROCESS											806.3						
	INTERCONNEC	TION REQUEST	REQ	UIREI	MENT	S							806.3							
		INTERCONNECTION REQUEST REQUIREMENTS																		
	TELEMETERIN	G												<mark>807.6</mark>						
	TRANSFORMER	R REQUIREMEN	TS											807.6						
I																				
	•																			
									of this copyright notice without permission											
C C	CHAN	GE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE						
В	EDITORIAL CHANGE	S/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025													
Α	EDITORIAL (-	LSM			11/01/2017													
		X Indicates La	itest R	evisio	n	Con	npletely Rev	ised	New Page X Information Re	moved										
	SHEET			SDG	&E E	LECT	RIC SERVIO	E STA	ANDARDS & GUIDES			=								
	1 OF 2								ERATION JECT INDEX			SG802.1								

<u>SUBJECT</u> <u>PAGE</u>

METERING

BILLING AND PURCHASE OF ENERGY METERING
NET GENERATION OUTPUT METERING – GENERAL INFORMATION AND INSTALLATION807, 809.1
TYPICAL METERING DEVICES REQUIRED AND INSTALLED BY SDG&E
OPERATING REQUIREMENTS
STANDBY GENERATORS, PERMANENTLY OR TEMPORARILY CONNECTED
GENERAL INFORMATION 803.2
GENERATORS CONNECTED PERMANENTLY BUT NOT OPERATING IN PARALLEL WITH SDG&E'S SYSTEM
GENERATORS NOT PERMANENTLY CONNECTED
STAND-BY GENERATOR SAFETY TRANSFER SWITCH
TRANSFER SYSTEMS
VIOLATIONS
WARNING STATEMENTS AND LABELS
WORKING CLEARANCE REQUIREMENTS FROM SDG&E-OWNED ELECTRIC METER AND GAS METER ASSEMBLY

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	LSM	TPM	11/01/2017	D						
	X Indicates La	atest R	evisio	n	Con	npletely Revi	sed	New Page X Information Ren	noved				

SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

CUSTOMER GENERATION ALPHABETICAL SUBJECT INDEX

SG802.2

SCOPE: THIS STANDARD DISCUSSES INSTALLATION REQUIREMENTS FOR CUSTOMER-OWNED GENERATORS.

ATTENTION:

- ALL INSTALLATIONS OF CUSTOMER-OWNED ELECTRIC ENERGY PRODUCTION EQUIPMENT (HEREINAFTER REFERRED TO AS GENERATOR OR GENERATORS) REQUIRE ADHERENCE TO RULES FOR SAFEGUARDING OF PERSONNEL, SDG&E-OWNED, AND CUSTOMER-OWNED EQUIPMENT.
- SDG&E (UTILITY) SHALL BE CONSULTED BEFORE A GENERATOR IS CONNECTED TO ANY CIRCUIT WHICH IS, OR CAN BE SUPPLIED FROM THE UTILITY'S ELECTRICAL SYSTEM. THIS IS TO ENSURE AGAINST ANY UNANTICIPATED BACKFEED OF ELECTRICITY INTO THE UTILITY'S SYSTEM, AND COMPLIANCE WITH THE UTILITY'S TARIFFS.
- *** THIS STANDARD DOES NOT APPLY TO PORTABLE GENERATORS UNDER CIRCUMSTANCES WHEN A CUSTOMER'S CORD AND PLUG APPLIANCES ARE CONNECTED DIRECTLY TO THE GENERATOR'S RECEPTACLES.

DEFINITIONS:

POSITIVE MEANS: A DEVICE WHICH, BY ITS USE OR OPERATION, INTERRUPTS OR PREVENTS THE FLOW OF CURRENT TO OR FROM THE ELECTRICAL SYSTEM AND WHICH PROVIDES THE DEVICE OPERATOR OR USER A VISUAL OR OTHER DEFINITE INDICATION OF THE EXISTING CONDITION OR STATE OF THE ELECTRICAL SYSTEM.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. DIRECTORY:

A PERMANENT PLAOUE OR DIRECTORY, SPECIFYING ALL ELECTRICAL POWER SOURCES ON OR IN THE PREMISES, SHALL BE INSTALLED AT EACH SERVICE EQUIPMENT LOCATION (SERVICE DELIVERY POINT) OF ALL GENERATORS CAPABLE OF BEING INTERCONNECTED TO THE UTILITY'S ELECTRICAL SYSTEM. INSTALLATIONS WITH MULTIPLE GENERATORS MAY BE DESIGNATED IN GROUPS ON THE PLAQUE. (a)

II. NET GENERATION OUTPUT METERING:

EXCEPT FOR EMERGENCY OR STANDBY GENERATORS USED SOLELY DURING UTILITY OUTAGES AND NOT CAPABLE OF OPERATING IN PARALLEL WITH THE UTILITY'S SYSTEM, CUSTOMER-OWNED GENERATORS MAY REQUIRE THE INSTALLATION OF NET GENERATION OUTPUT METERING (NGOM) TO SATISFY REQUIREMENTS ASSOCIATED WITH OTHER SERVICES APPLICABLE TO OR REQUESTED BY A CUSTOMER. UNDER CIRCUMSTANCES WHEN NGOM IS REQUIRED, SUCH REQUIREMENTS MAY BE WAIVED WHERE LESS INTRUSIVE AND/OR MORE COST EFFECTIVE OPTIONS ARE AVAILABLE FOR PROVIDING GENERATOR PRODUCTION DATA TO THE UTILITY.(b)

III. CONNECTION OF CUSTOMER-OWNED GENERATORS TO SDG&E'S ELECTRICAL SYSTEM:

- a. THE LEGISLATURE OF THE STATE OF CALIFORNIA INTENDED TO PREVENT ELECTRICITY GENERATED BY PERMANENT OR PORTABLE ELECTRIC GENERATORS FROM BACK FEEDING INTO A UTILITY ELECTRICAL SYSTEM BY ENACTING THE CALIFORNIA HEALTH AND SAFETY CODE, DIVISION 104, PART 15, CHAPTER 5, SECTIONS 119075 THROUGH 119090. (c)
- b. IN ADDITION, CALIFORNIA CODE OF REGULATIONS, TITLE 8, SECTION 2320.9, STATES:

NO ELECTRICAL POWER SOURCE, PERMANENT OR TEMPORARY, SHALL BE CONNECTED TO A PREMISES WIRING SYSTEM, OR PARTS OF SUCH A SYSTEM, UNLESS POSITIVE MEANS ARE USED TO PREVENT THE TRANSMISSION OF ELECTRICITY BEYOND THE PREMISES WIRING SYSTEM, OR BEYOND ANY INTENTIONALLY SEGREGATED PARTS OF SUCH A SYSTEM. EXCEPTION: WHEN AN INTERCONNECTION HAS BEEN AUTHORIZED BY THE SERVICING UTILITY. (d)

REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		C	HAN	IGE	DR	BY	DSN	APV	DATE	
С									F										
В	EDITORIAL CHANGE	S/FORM	IATTING	EDM	IWA	JTM	KRG	02/03/2025	Е										
Α	EDITORIAL C	CHANGE	S	-	LSM	IPJ	TPM	11/01/2017	D										
	X Indicates Latest Revision Completely Revised New Page Information Removed																		
	SHEET SDG&E ELECTRIC SERVICE STANDARDS & GUIDES														7				
																S	G803	3.1	
1 OF 4 GENERAL INFORMATION														30003.1					

GENERAL INFORMATION

NOTES (CONT'D):

IV. WARNING STATEMENTS AND LABELS:

a. CALIFORNIA HEALTH AND SAFETY CODE, SECTION 119080(a), REQUIRES:

EVERY MANUFACTURER OF A PORTABLE OR PERMANENT ELECTRICAL GENERATOR THAT IS CAPABLE OF BEING CONNECTED EITHER PERMANENTLY OR TEMPORARILY TO A COMMERCIAL, INDUSTRIAL OR RESIDENTIAL STRUCTURE'S ELECTRICAL SYSTEM, SHALL INCLUDE A WARNING STATEMENT IN THE GENERATOR'S INSTRUCTION MANUAL AND A LEGIBLE WARNING LABEL ON THE GENERATOR WHICH STATES THE REQUIREMENT OF SECTION 119075 AND EXPLAINS THE ELECTRICAL HAZARDS OF BACKFEED INTO A UTILITY'S DISTRIBUTION SYSTEM. THE SAME WARNING INFORMATION SHALL BE INCLUDED IN ALL ADVERTISEMENTS OFFERING PORTABLE ELECTRICAL GENERATORS. (e)

b. CALIFORNIA HEALTH AND SAFETY CODE, SECTION 119080(a) STATES:

NO PERSON OR PUBLIC AGENCY SHALL SELL, RENT TO ANOTHER PERSON OR PUBLIC AGENCY, OR OFFER FOR SALE OR RENT TO ANOTHER PERSON OR PUBLIC AGENCY A PORTABLE ELECTRICAL GENERATOR UNLESS THE LEGIBLE WARNING LABEL IS ON A VISIBLE SURFACE OF THE GENERATOR. (f)

V. VIOLATIONS:

CALIFORNIA HEALTH AND SAFETY CODE, SECTION 119090(a), STATES:

ANY PERSON WHO VIOLATES SECTIONS 119075 TO 119085, INCLUSIVE, IS GUILTY OF A MISDEMEANOR, AND SUBJECT TO A FINE OF NOT MORE THAN FIVE HUNDRED DOLLARS (\$500) OR NOT MORE THAN SIX MONTHS' IMPRISONMENT. \boxed{q}

PERMANENTLY OR TEMPORARILY CONNECTED STANDBY GENERATORS:

VI. GENERAL INFORMATION:

- a. WHEN A GENERATOR IS PERMANENTLY OR TEMPORARILY CONNECTED TO A CUSTOMER'S ELECTRIC SYSTEM, IT HAS THE POTENTIAL TO ENERGIZE THE BUILDING'S WIRING. THIS TYPE OF INSTALLATION REQUIRES A DEVICE THAT ISOLATES THE GENERATOR FROM THE UTILITY'S ELECTRICAL SYSTEM. REFER TO NOTE IX, TRANSFER SYSTEMS, FOR THE REQUIREMENTS OF SUCH ISOLATION DEVICES.
- b. THE GENERATOR MUST BE 60-HERTZ ALTERNATING CURRENT. IF A DIRECT CURRENT GENERATOR IS USED, THE INSTALLATION MUST BE ARRANGED SO THAT ALL MOTORS, RADIOS, AND OTHER EQUIPMENT THAT WILL NOT OPERATE ON DIRECT CURRENT ARE DISCONNECTED FROM CIRCUITS BEFORE THE CIRCUITS ARE ENERGIZED FROM THE GENERATOR.
- c. ONLY A QUALIFIED PROFESSIONAL, SUCH AS A LICENSED ELECTRICAL CONTRACTOR, SHOULD INSTALL A PERMANENTLY OR TEMPORARILY CONNECTED STANDBY GENERATOR.
- d. A PERMIT AND INSPECTION BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) ARE REQUIRED FOR ALL PERMANENT AND TEMPORARY CONNECTIONS OF GENERATORS TO THE CUSTOMER'S ELECTRICAL SYSTEM(S).
- e. WHEN INSTALLATION IS COMPLETE, THE CUSTOMER MUST CALL THE UTILITY AT (800) 411-SDGE (7343) AND PROVIDE THE ADDRESS OF THE GENERATOR LOCATION.

VII. GENERATORS **NOT** PERMANENTLY CONNECTED (TEMPORARY CONNECTIONS):

a. ANY PORTABLE ELECTRIC GENERATOR CONNECTED TO SDG&E MUST COMPLY WITH CALIFORNIA HEALTH & SAFETY CODE, SECTION 119075. SECTION 119075(b) STATES:

ANY PORTABLE ELECTRICAL GENERATOR THAT IS CAPABLE OF BEING CONNECTED TEMPORARILY TO A CUSTOMER'S ELECTRICAL SYSTEM, THAT IS NORMALLY SUPPLIED BY AN ELECTRICAL CORPORATION OR STATE OR LOCAL PUBLIC AGENCY, SHALL BE CONNECTED ONLY AFTER OPENING THE CUSTOMER'S MAIN SWITCH SO AS TO ISOLATE THE CUSTOMER'S ELECTRICAL SYSTEM FROM THAT OF THE ELECTRICAL CORPORATION OR STATE OR LOCAL AGENCY. (h)

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		СН	IAN	IGE	DR	BY	DSN	APV	DATE	
С								F										
В	EDITORIAL CHANGE	S/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е										
Α	EDITORIAL C	-	LSM	IPJ	TPM	11/01/2017	D											
	X Indicates Latest Revision Completely Revised New Page Information Removed																	
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	
SHEET SHOULD SHANDANDS & GOIDES														S	G803	3.2		
	2 OF 4					GEN	ERAL IN	F∩R	МΔ	ATION					SG803.2			

NOTES (CONT'D):

PERMANENTLY OR TEMPORARILY CONNECTED STANDBY GENERATORS (CONT'D):

VII. GENERATORS **NOT** PERMANENTLY CONNECTED (TEMPORARY CONNECTIONS) (CONT'D):

b. ARTICLE 702.5 OF THE 2014 NATIONAL ELECTRICAL CODE (NEC) REQUIRES TRANSFER EQUIPMENT "SUITABLE FOR THE INTENDED USE AND DESIGNED AND INSTALLED [SO AS] TO PREVENT THE INADVERTENT INTERCONNECTION OF NORMAL AND ALTERNATE SOURCES OF SUPPLY IN ANY OPERATION OF THE TRANSFER EQUIPMENT." A MAIN BREAKER OR FUSE, WHICH IS NOT LISTED AS SUITABLE FOR USE AS TRANSFER EQUIPMENT, CANNOT BE USED AS THE TRANSFER DEVICE BETWEEN TEMPORARILY CONNECTED PORTABLE GENERATORS AND THE UTILITY'S SYSTEM. THIS APPLIES TO ANY GENERATOR CONNECTED AS A TEMPORARY (NON-ROUTINE, NONSCHEDULED) OR EMERGENCY SOURCE OF ELECTRIC ENERGY. ANY PORTABLE ELECTRIC GENERATOR USED AS A TEMPORARY SOURCE OF POWER SHALL BE CONNECTED AS DESCRIBED IN NOTE IX, TRANSFER SYSTEMS.

VIII. GENERATORS CONNECTED PERMANENTLY BUT **NOT** OPERATING IN PARALLEL WITH SDG&E:

ALL GENERATORS IN THIS CATEGORY ARE TO BE CONNECTED IN ACCORDANCE WITH SDG&E'S CPUC-APPROVED TARIFFS AND CALIFORNIA HEALTH AND SAFETY CODE 119075(c), WHICH STATES:

ANY ELECTRICAL GENERATOR, OTHER THAN A GENERATOR DESIGNED TO RUN IN PARALLEL WITH THE SYSTEM OF THE SERVICING UTILITY AND APPROVED BY THAT UTILITY, THAT IS CAPABLE OF BEING PERMANENTLY CONNECTED TO A CUSTOMER'S ELECTRICAL SYSTEM SHALL BE CONNECTED ONLY BY MEANS OF A DOUBLE THROW SWITCH SO AS TO ISOLATE THE CUSTOMER'S ELECTRICAL SYSTEM FROM THAT OF THE ELECTRICAL CORPORATION OR STATE OR LOCAL AGENCY.

IX. TRANSFER SYSTEMS:

a. SERVICE EQUIPMENT RATED TRANSFER:

TRANSFER SWITCHES LISTED AND LABELED AS SUITABLE FOR USE AS SERVICE EQUIPMENT ARE PERMITTED FOR USE AS MAIN SERVICE EQUIPMENT UPON PRIOR APPROVAL FROM THE UTILITY. ALL OTHER TRANSFER SWITCHES SHALL BE CONNECTED ON THE LOAD SIDE OF THE MAIN SERVICE EQUIPMENT.

b. OPEN-TRANSITION SWITCHING:

A DOUBLE THROW SWITCH WITH A MECHANICALLY DRIVEN BREAK-BEFORE-MAKE SEQUENCE SHALL NORMALLY BE PROVIDED TO TRANSFER ALL UNGROUNDED CONDUCTORS OF AN EMERGENCY LIGHTING OR POWER LOAD TO EITHER THE GENERATOR OR THE NORMAL SUPPLY. MANUAL TRANSFER SWITCH INSTALLATIONS DO NOT REQUIRE REVIEW AND APPROVAL BY THE UTILITY PRIOR TO INSTALLATION. $\binom{1}{k}$

c. CLOSED-TRANSITION SWITCHING AND AUTO TRANSFER:

REQUESTS FOR CLOSED-TRANSITION SWITCHING (MAKE-BEFORE-BREAK) AND AUTOMATIC TRANSFER SYSTEMS, WITH A SOLID STATE OR PROGRAMMABLE LOGIC CONTROLLER, REQUIRE SPECIFICATION SUBMITTAL AND MUST BE APPROVED BY THE UTILITY. THE CUSTOMER'S SUBMITTAL SHALL INCLUDE ALL OF THE FOLLOWING: SYSTEM DESCRIPTION, ONE-LINE RELAY FUNCTIONAL DIAGRAM, LOGIC CONTROLLER PROGRAM, AND BILL OF MATERIALS. CLOSED-TRANSITION SWITCHING LIMITING PARALLEL OPERATION WITH THE UTILITY TO NO GREATER THAN 1 SECOND (60 CYCLES) DOES NOT REQUIRE A WRITTEN AGREEMENT WITH THE UTILITY. THE CUSTOMER WILL RECEIVE AN APPROVAL OR REQUEST FOR CHANGES AFTER THE UTILITY'S REVIEW OF THE REQUEST HAS BEEN COMPLETED. SUBMITTALS SHOULD BE SENT ELECTRONICALLY TO: DRAWINGSUBMITTALS@SDGE.COM

d. SEPARATELY DERIVED SYSTEMS:

WHEN AN AC GENERATOR IS INSTALLED AS A SEPARATELY DERIVED SYSTEM, GROUNDING OF THE NEUTRAL CONDUCTOR SHALL BE IN ACCORDANCE WITH THE CALIFORNIA ELECTRICAL CODE. SEPARATELY DERIVED SYSTEMS REQUIRE A SWITCHED NEUTRAL CONDUCTOR AT THE TRANSFER SWITCH. FIGURES ON SG804 AND SG805 DO NOT SHOW THIS SYSTEM CONFIGURATION. (k)

e. KIRK KEY INTERLOCKS ARE NOT AN ACCEPTABLE SUBSTITUTE FOR A DOUBLE THROW TRANSFER SWITCH TO PREVENT INADVERTENT INTERCONNECTION WITH THE SERVING UTILITY.

REV	CHAN	CE.	DR	BY	Y DSN	A DV		REV	of this copyright notice without permission CHANGE				DR	BY	DCN	A DV	DATE	
KEV	CHAN	GE	DK	ы	DSM	APV	DATE	KEV		C	ПАІ	NGE	DK	ы	DSN	APV	DATE	
С								F										
В	EDITORIAL CHANGE	EDM	IWA	JTM	KRG	02/03/2025	Е											
Α	EDITORIAL C	-	LSM	IPJ	TPM	11/01/2017	D											
	X Indicates Latest Revision Completely Revised New									New Page	X	Information Re	moved					
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	
	SHEET SHOULD SHAND & GOIDES													SG803.3				
	3 OF 4					CEN.	EDAL TAI	-		TTON					56803.3			
	J O I I					(¬HN	ERAL IN	+() R	MΔ									

REFERENCE:

- (a) FOR PLAQUE SPECIFICATIONS, SEE SG017.
- (b) FOR ADDITIONAL INFORMATION ABOUT NGOM, SEE SG806.
- (c) SEE CALIFORNIA HEALTH AND SAFETY CODE, DIVISION 104, PART 15, CHAPTER 5, SECTIONS 119075 THROUGH 119090.
- (d) SEE CALIFORNIA CODE OF REGULATIONS, TITLE 8, SECTION 2320.9.
- (e) SEE CALIFORNIA HEALTH AND SAFETY CODE, SECTION 119080(a).
- (f) SEE CALIFORNIA HEALTH AND SAFETY CODE, SECTION 119080(b).
- (g) SEE CALIFORNIA HEALTH AND SAFETY CODE, SECTION 119090(a).
- (h) SEE CALIFORNIA HEALTH & SAFETY CODE, SECTION 119075.
- (i) See the <mark>2020</mark> National Electrical Code (NEC), Article 702.5.
- (j) SEE CALIFORNIA HEALTH & SAFETY CODE, SECTION 119075(c).
- (k) FOR TYPICAL CONNECTIONS, SEE SG805.
- (I) SEE SG804.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 4

Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GENERAL INFORMATION

SG803.4

SCOPE: THIS STANDARD SHOWS A STAND-BY GENERATOR SAFETY TRANSFER SWITCH. TO MAIN SERVICE EQUIPMENT AND UTILITY METER **NEUTRAL** LINE 1 TO DISTRIBUTION PANEL (LOAD) NEUTRAL-LINE 2 NEUTRAL BUS(III) TO GENERATOR

FIGURE 1 STAND-BY ELECTRIC GENERATOR SAFETY TRANSFER SWITCH TYPICAL LAYOUT

ATTENTION:

EQUIPMENT GROUNDING CONDUCTOR FOR BONDING PURPOSES NOT SHOWN.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. SWITCH UP POSITION FOR UTILITY POWER
- II. SWITCH DOWN POSITION FOR GENERATOR POWER
- III. MOUNTED ON SIDE WALL INSIDE ENCLOSURE
- IV. NEUTRAL WILL BE BONDED TO ENCLOSURE IF TRANSFER SWITCH IS LISTED FOR AND USED AS SERVICE EQUIPMENT.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	-	-	02/03/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 1

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG804.1

STAND-BY GENERATOR SAFETY TRANSFER SWITCH

SCOPE: THIS STANDARD DESCRIBES STAND-BY GENERATORS.




FIGURE 1

CONNECTION OF STAND-BY GENERATOR SUPPLYING CUSTOMER'S ENTIRE LOAD

SEE TABLE 1




FIGURE 2
STAND-BY GENERATOR NON-PARALLEL
OPERATION WITH UTILITY
SEE TABLE 1

FIGURE 2
STAND-BY GENERATOR NON-PARALLEL
OPERATION WITH UTILITY
ONE-LINE DIAGRAM
SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SPOKE ELECTRIC SERVICE STANDARDS & GOIDES

SG805.1

STAND-BY GENERATOR




FIGURE 3 CONNECTION OF STAND-BY GENERATOR SUPPLYING ONE 120V CIRCUIT WIRING DIAGRAM SEE TABLE 1




FIGURE 3 CONNECTION OF STAND-BY GENERATOR SUPPLYING ONE 120V CIRCUIT **ONE-LINE DIAGRAM** SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

_									 	APV	DATE
_							F				
B ED	DITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е				
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D				

SHEET 2 OF 4

Completely Revised Indicates Latest Revision New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

STAND-BY GENERATOR

SG805.2




FIGURE 4 CONNECTION OF STAND-BY GENERATOR TO A PORTION OF CUSTOMER LOAD (VII) (VIII) SERVED FROM SINGLE UTILITY SERVICE **ONE-LINE DIAGRAM** SEE TABLE 1




FIGURE 4 CONNECTION OF STAND-BY GENERATOR TO A PORTION OF CUSTOMER LOAD (VII)(VIII) SERVED FROM SINGLE UTILITY SERVICE

WIRING DIAGRAM SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C EDITORIAL CHANGES/FORMATTING EDM IWA JTM KRG 02/03/2025 E	REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
B EDITORIAL CHANGES/FORMATTING EDM IWA JTM KRG 02/03/2025 E	С							F						
	В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е						
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D	Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 4 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG805.3

STAND-BY GENERATOR

	FIGURE ITEMS
ITEM	DESCRIPTION
$\langle 1 \rangle$	PANEL, DISTRIBUTION
2	BUS, NEUTRAL
(3)	CONDUCTOR, EQUIPMENT GROUNDING (PER N.E.C.)
4	SWITCH, SAFETY, SERVICE DISCONNECT RATED, DOUBLE-THROW, 2-POLE
5	GENERATOR
6	FUSE, GENERATOR
7	UTILITY SERVICE POINT
8	METER
9	SWITCH, DOUBLE-THROW
(10)	SERVICE EQUIPMENT, MAIN (CUSTOMER'S)
$\langle 11 \rangle$	DISTRIBUTION PANEL LOAD CENTER
(12)	WALL, OUTSIDE
(13)	OPENING THROUGH WALL
14	WALL, INSIDE
(15)	FUSE
⟨16⟩	POLE, DISTRIBUTION
10	SUBSURFACE STRUCTURE
(17)	SWITCH, TRANSFER, DOUBLE-THROW, 2-POLE
(18)	BUS, GROUND
(19)	SWITCH, SAFETY, DOUBLE-THROW, 1-POLE (TRANSFER SWITCH)

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) FROM CUSTOMER'S SERVICE EQUIPMENT
- (II) CUSTOMER'S
- (III) CUSTOMER'S STAND-BY
- (IV) UTILITY
- (V) rated for intended use
- (VI) FOR WHICH STAND-BY GENERATOR IS PROVIDED
- m (VII) example shown is multiple buildings in rural areas.
- (VIII) CONNECTIONS SHOWN ARE FOR UTILITY'S SERVICE BEING SINGLE-PHASE, 3-WIRE, 120/240V.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025	Е						
A	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 4 OF 4

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG805.4

STAND-BY GENERATOR

SCOPE: THIS STANDARD PROVIDES AN OVERVIEW OF SDG&E'S REQUIREMENTS FOR INTERCONNECTING CUSTOMER-OWNED GENERATORS TO SDG&E'S ELECTRIC DISTRIBUTION SYSTEM.

ATTENTION:

- THIS STANDARD IS NOT INTENDED TO BE A SUBSTITUTE FOR THE SDG&E GENERATION INTERCONNECTION HANDBOOK (INTERCONNECTION HANDBOOK) OR SDG&E'S ELECTRIC RULE 21 (RULE 21) AND SHOULD NOT BE RELIED ON TO DETERMINE THE INTERCONNECTION REQUIREMENTS FOR ANY PROJECT. (d)
- WHERE THERE IS ANY PERCEIVED OR ACTUAL INCONSISTENCY BETWEEN THIS DOCUMENT AND THE REQUIREMENTS OF RULE 21 OR THE INTERCONNECTION HANDBOOK, RULE 21 SHALL GOVERN. (d)




FIGURE 1 TYPICAL SELF-CONTAINED METER < 30 KW AC (II)(III)(XIE) **SEE TABLE 1**




FIGURE 2 TYPICAL SELF-CONTAINED METER \geq 30 KW AC (II \setminus IV \setminus XIe \setminus b) **SEE TABLE 1**

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025
	37				_								

SHEET 1 OF 5 Indicates Latest Revision | Completely Revised | New Page | X | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG806.1

DISTRIBUTED GENERATION




FIGURE 3 TYPICAL INSTRUMENT TRANSFORMER RATED METERING INSTALLATION (II) (IV) (XIe) b) SEE TABLE 1

	FIGURE ITEMS
ITEM	DESCRIPTION
<u>(1)</u>	DISTRIBUTION SYSTEM (SDG&E)
(2)	METER, POINT OF COMMON COUPLING
(3)	BREAKER, MAIN
4	BREAKER, PV
(5)	GENERATOR
6	DISCONNECT, AC
7	METER, CURRENT TRANSFORMER

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- CUSTOMERS PLANNING TO INSTALL A GENERATOR THAT WILL OPERATE IN PARALLEL WITH SDG&E'S ELECTRIC DISTRIBUTION SYSTEM FOR THE PURPOSE OF (1) ONLY SERVING THEIR OWN ELECTRICAL LOAD, (2) SERVING THEIR OWN ELECTRICAL LOAD AND EXPORTING EXCESS POWER TO THE GRID OR (3) ONLY EXPORTING POWER TO THE GRID, MUST SUBMIT AN APPLICATION FOR INTERCONNECTION AND RECEIVE WRITTEN AUTHORIZATION FROM SDG&E TO INTERCONNECT AND OPERATE IN PARALLEL.
- ${
 m (II)}$ A SITE PLACARD IS REQUIRED AT THE SERVICE AND METERING EQUIPMENT. ${
 m (a)}$
- $\widehat{
 m (III)}$ A DISCONNECT SWITCH IS HIGHLY RECOMMENDED BUT NOT REQUIRED. REFER TO FIGURE 2 IF INSTALLING A DISCONNECT SWITCH.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C EDITORIAL CHANGES ARC JIK IPJ KRG 01/09/2023 F	APV DATE	I AP	DSN	BY	DR	CHANGE	REV	DATE	APV	DSN	BY	DR	ANGE	CHANGE	REV
							F	01/09/2023	KRG	IPJ	JIK	ARC	L CHANGES	EDITORIAL CHA	С
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D EDITORIAL CHANGES/FORMATTING EDM IWA JTM KRG							Е	11/01/2019	CZH	IPJ	IPJ	-	L CHANGES	EDITORIAL CHA	В
	KRG 02/03/20	KRC	JTM	IWA	EDM	EDITORIAL CHANGES/FORMATTING	D	11/01/2017	TPM	IPJ	LSM	-	L CHANGES	EDITORIAL CHA	Α

SHEET 2 OF 5 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION

SG806.2

 $({
m iv})$ customer shall install a placard on the AC disconnect switch labeled "PV system disconnect for utility OPERATION" OR "WIND TURBINE, FUEL CELL, BATTERY, ETC., SYSTEM DISCONNECT FOR UTILITY OPERATION", AS APPROPRIATE. THE AC DISCONNECT SHALL BE IDENTIFIED THE SAME ON THE SITE PLACARD.

V. INTERCONNECTION PROCESS:

INTERCONNECTION CAN BE ACHIEVED BY MEANS OF EITHER THE RULE 21 PROCESS OR THE WHOLESALE DISTRIBUTION OPEN ACCESS TARIFF (WDAT) PROCESS. BOTH INTERCONNECTION PROCESSES REQUIRE THE CUSTOMER TO COMPLETE A GENERATING FACILITY TECHNICAL REVIEW OR STUDY AND EXECUTE AN INTERCONNECTION AGREEMENT WITH SDG&E BEFORE THE GENERATING FACILITY IS AUTHORIZED TO INTERCONNECT AND OPERATE IN PARALLEL WITH SDG&E'S ELECTRIC SYSTEM. (c)(d)(e)(f)

VI. INTERCONNECTION REQUEST REQUIREMENTS:

- a. SINGLE-LINE DIAGRAM A SINGLE-LINE REPRESENTATION OF THE PROPOSED INTERCONNECTION SYSTEM THAT CLEARLY DISTINGUISHES EXISTING EQUIPMENT FROM PROPOSED EQUIPMENT.
- b. COMPLETED INTERCONNECTION APPLICATION, INCLUDING A COMPLETE SET OF SPECIFICATIONS AS FOLLOWS:

MAXIMUM KW RATING

NOMINAL OUTPUT VOLTAGE

ALL NECESSARY RELAYS

POWER FACTOR

MAXIMUM FAULT CURRENT CONTRIBUTION

KWH RATING FOR ENERGY STORAGE PROJECTS

MAKE AND MODEL OF INVERTER, IF AN INVERTER WILL BE USED

- APPLICABLE FEES AND/OR DEPOSITS
- DOCUMENTATION DEMONSTRATING PROOF OF SITE EXCLUSIVITY/CONTROL

VII. OPERATING REQUIREMENTS:

THE CUSTOMER SHALL OPERATE THE GENERATING FACILITY, WHETHER PERMANENT OR TEMPORARY, IN ACCORDANCE WITH THE INTERCONNECTION AGREEMENT, SDG&E'S ELECTRIC SERVICE REQUIREMENTS, SDG&E'S CPUC-APPROVED TARIFFS, AND ALL APPLICABLE LAWS, CODES AND ORDINANCES. THE CUSTOMER SHALL NOT BE PERMITTED TO ENERGIZE ANY DE-ENERGIZED PORTION OF SDG&E'S DISTRIBUTION SYSTEM.

DISCONNECTION DEVICES:

VIII. INVERTER-BASED SYSTEMS:

- a. CUSTOMERS INSTALLING INVERTER-BASED SYSTEMS LESS THAN 30KW CEC AC WILL NO LONGER BE REQUIRED TO INCLUDE AN AC DISCONNECT SWITCH WHEN THE FACILITY HAS A SELF-CONTAINED BILLING METER (I.E., 0-225A SOCKET-BASED METER OR A 400A CLASS 320 SOCKET-BASED METER). THESE TYPES OF METERS ARE NOT CURRENT TRANSFORMER (CT) RATED AND ARE USED FOR THE VAST MAJORITY OF ALL SDG&E CUSTOMERS.
- b. IN LIEU OF AN AC DISCONNECT, THE BILLING METER MAY TEMPORARILY BE REMOVED BY SDG&E TO ISOLATE THE CUSTOMER'S INVERTER FROM THE ELECTRIC DISTRIBUTION SYSTEM TO MAINTAIN OPERATING SAFETY NEEDS DURING AN EMERGENCY OR MAINTENANCE ON SDG&E'S SYSTEM. REMOVAL OF THE BILLING METER WILL RESULT IN LOSS OF ELECTRICAL SERVICE TO THE CUSTOMER'S FACILITY OR RESIDENCE FOR THE DURATION OF TIME THAT WORK IS ACTIVELY IN PROGRESS. HOWEVER, IT IS HIGHLY RECOMMENDED TO INSTALL AN AC DISCONNECT ON ALL GENERATING FACILITIES, REGARDLESS OF SIZE.

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	ompa	ny. All	rights r	reserved. Rer	moval (of thi	is copyright notice	without permission	is not	permit	ted und	der law	<i>I</i> .
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CHAN	GE	DR	BY	DSN	APV	DATE
С	EDITORIAL (CHAN	IGES	ARC	JIK	IPJ	KRG	01/09/2023	F								
В	EDITORIAL (CHAN	IGES	-	IPJ	IPJ	CZH	11/01/2019	Е								
Α	EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D EDITORIAL CHANGES/FORMATTING EDM														JTM	KRG	02/03/2025
	Indicates Latest Revision Completely Revised New Page X Information Removed																
	SHEET				SDG	S&E E	LECTI	RIC SERVIC	E ST	AND	ARDS & GUIDE	:S					
				•				•							S	G80	6.3
	3 OF 5					D.	CTD	TRUTED	GEN	VIE [DΛTTΛN						

DISTRIBUTED GENERATION

IX. CIRCUMSTANCES REQUIRING DISCONNECTS:

- a. INVERTER-BASED SYSTEMS 30KW CEC AC AND LARGER.
- b. INVERTER-BASED INTERCONNECTIONS HAVING A CT RATED METER, I.E., ALL METER PANELS OR SWITCHBOARDS EMPLOYING THE USE OF POTENTIAL AND/OR PTS/CTS.
- c. NON-INVERTER-BASED GENERATORS, INCLUDING ROTATING OR MACHINE-BASED GENERATORS, REGARDLESS OF WHETHER THE SERVICE METER CONFIGURATION IS CT RATED OR SELF-CONTAINED.

XI. UTILITY AC DISCONNECT REQUIREMENTS:

THE CUSTOMER SHALL FURNISH, INSTALL, OWN AND MAINTAIN AN AC DISCONNECT IN COMPLIANCE WITH THE FOLLOWING:

a. A SINGLE, VISIBLE OPEN, LOCKABLE AC DISCONNECT IS REQUIRED TO ISOLATE ALL GENERATION WITHOUT IMPACTING CUSTOMER LOAD. A SINGLE, VISIBLE OPEN, LOCKABLE AC DISCONNECT MUST BE INSTALLED NEAR THE POINT OF COMMON COUPLING (PCC), ALSO REFERRED TO AS THE SERVICE AND METERING EQUIPMENT, AT A LOCATION APPROVED BY SDG&E. ACCEPTABLE METER LOCATIONS ARE GENERALLY:

INSIDE THE ELECTRIC METER ROOM.

IMMEDIATELY OUTSIDE THE ELECTRIC METER ROOM AT A LOCATION APPROVED BY SDG&E AND THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ). (g)h (v)

- b. WHEN ADDING GENERATION TO A FACILITY THAT CURRENTLY HAS GENERATION, THE ADDED GENERATION MUST BE CONNECTED TO THE EXISTING DISCONNECTING DEVICE, OR THE REPLACEMENT DISCONNECTING DEVICE IF A LARGER AMPACITY DEVICE IS REQUIRED SO THAT ALL GENERATION CAN BE ISOLATED WITHOUT IMPACTING CUSTOMER LOAD.
- c. CONSISTENT WITH METER ROOM ACCESS REQUIREMENTS, ALL DEVICES USED TO DISCONNECT THE GENERATING FACILITY SHALL BE READILY ACCESSIBLE UNDER ALL CONDITIONS AND AT ALL TIMES, 24 HOURS A DAY. THE SWITCH OPERATION SHALL UTILIZE AN OPEN AIR GAP AND SHALL PROVIDE VISIBLE VERIFICATION. (h)

SWITCH BLADES' JAWS, AND THE AIR-GAP BETWEEN THEM, SHALL BE CLEARLY VISIBLE WHEN THE DISCONNECT IS IN THE OPEN POSITION.

THE VISIBLE AIR-GAP MUST BE OBSERVED WITHOUT DISASSEMBLING THE DEVICE.

d. THE SWITCH SHALL BE LOCKABLE IN THE OPEN POSITION.

THE LOCKING OPERATION SHALL BE ACCOMPLISHED WITH A SINGLE SDG&E LOCK.

THE SWITCH PANEL COVER SHALL NOT BE REMOVABLE WITH THE SWITCH PADLOCKED IN THE OPEN POSITION.

- (e) CUSTOMERS SHALL INSTALL PLAQUES AT ALL AC DISCONNECTS CLEARLY STATING THEIR PURPOSE IS FOR OPERATION BY THE UTILITY OR AUTHORIZED EMERGENCY RESPONDERS.
- (VII) SELF-CONTAINED
- EXCEPTION TO THE SINGLE DISCONNECT LIMITATION: WHEN MULTIPLE CUSTOMER GENERATION TECHNOLOGIES ARE INSTALLED ON A PREMISES, I.E. SOLAR, WIND TURBINE, FUEL CELL, BATTERY, ETC., A SINGLE DISCONNECT PER TECHNOLOGY ALL GROUPED AT ONE LOCATION IS ACCEPTABLE WITH ADVANCE SDG&E APPROVAL PRIOR TO FINAL DESIGN AND CONSTRUCTION. UTILITY DISCONNECT TYPE AND LOCATION REQUIRE SDG&E APPROVAL PRIOR TO INSTALLATION.

REFERENCE:

- (a) FOR SITE PLACARD REQUIREMENTS, SEE SG017.
- (b) FOR DISCONNECT REQUIREMENTS, SEE SG511.
- c FOR DETAILED INFORMATION ADDRESSING THE INTERCONNECTION OF CUSTOMER-OWNED GENERATORS, SEE SDG&E'S WEBSITE: HTTPS://WWW.SDGE.COM/MORE-INFORMATION/CUSTOMER-GENERATION.

	© 1998 - 2025 Sa	an Di	ego Gas & Ele	ectric C	compa	ny. All	rights ı	eserved. Rer	noval	of th	is copyright notic	ce '	without permission	is not	permit	ted und	der law	<i>'</i> .
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		СНА	١N	GE	DR	BY	DSN	APV	DATE
С	EDITORIAL (CHAN	IGES	ARC	JIK	IPJ	KRG	01/09/2023	F									
В	B EDITORIAL CHANGES - IPJ IPJ CZH 11/01/2019 E																	
Α	EDITORIAL (CHAN	IGES	-	LSM	IPJ	TPM	11/01/2017	D	EC	DITORIAL CHAN	GE	ES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025
X Indicates Latest Revision Completely Revised New Page Information Removed																		
i					SDC	%F F	I FCTI	RIC SERVIC	F ST	ΔΝΓ	DARDS & CHIT)F	:ς					

SHEET 4 OF 5

DISTRIBUTED GENERATION

SG806.4

REFERENCE (CONT'D): (d) FOR RULE 21 INFORMATION AND DOCUMENTS, SEE HTTPS://WWW.SDGE.COM/MORE-INFORMATION/CUSTOMER-GENERATION/ELECTRIC-RULE-21. (e) FOR WDAT INFORMATION AND DOCUMENTS, SEE HTTPS://WWW.SDGE.COM/MORE-INFORMATION/CUSTOMER-GENERATION/WHOLESALE-GENERATOR-TRANSMISSION-INTERCONNECTIONS (f) FOR SDG&E GENERATION INTERCONNECTION HANDBOOK, SEE HTTPS://WWW.SDGE.COM/MORE-INFORMATION/CUSTOMER-GENERATION/ELECTRIC-RULE-21/DISTRIBUTION-INTERCONNECTION-**HANDBOOK** (g) FOR UNACCEPTABLE METER LOCATIONS, SEE SG504. (h) FOR ELECTRIC METER ROOM ACCESS REQUIREMENTS, SEE SG506. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	С	HAN	IGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F								
В	EDITORIAL CHANGES		IPJ	IPJ	CZH	11/01/2019	Е								
Α	EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D	EDITORIAL CH	ANG	ES/FORMATTING	EDM	IWA	JTM	KRG	02/03/2025
	V Indicates La	test R	evisio	1	Con	nletely Revi	sed	New Page		Information Rer	noved				

SHEET 5 OF 5

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION

SG806.5

SCOPE: THIS STANDARD DISCUSSES METERING OF DISTRIBUTED GENERATION.




FIGURE 1

NET GENERATION OUTPUT METERING (NGOM) ON LOAD SIDE OF BILLING METER (IXa)

ONE-LINE DIAGRAM

SEE TABLE 1




FIGURE 2

NET GENERATION OUTPUT METERING (NGOM) ON LINE SIDE OF SDG&E BILLING METERS (IVa) FOR PHOTOVOLTAIC (PV) AND/OR WIND TURBINE (WT) GENERATION VIRTUAL NET METERING AND AGGREGATION ONE-LINE DIAGRAM SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
							_						_

SHEET 1 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION METERING

	FIGURE ITEMS
ITEM	DESCRIPTION
1	DISTRIBUTION SYSTEM (SDG&E)
2	METER, POINT OF COMMON COUPLING
3	LOADS, CUSTOMER'S HOST
4	DISCONNECT FOR UTILITY OPERATION
(5)	METERING, NET GENERATION OUTPUT (NGOM)
6	LOADS, AUXILIARY, GENERATING FACILITY
7	GENERATING FACILITY
8	MAIN BREAKER AHEAD OF MULTIPLE METERS
9	DISCONNECT
(10)	DISCONNECT, PHOTO-VOLTAIC/WIND TURBINE
(11)	CO-GENERATING FACILITY, PHOTO-VOLTAIC/WIND TURBINE
12	TRANSFORMER, STEP DOWN, CUSTOMER OWNED

DEFINITIONS:

• NET GENERATION OUTPUT METERING (NGOM): METERING OF THE NET ELECTRICAL POWER OUTPUT IN KW OR ENERGY IN KWH, RESPECTIVELY, FROM A GIVEN GENERATING FACILITY. THIS MAY ALSO BE THE MEASUREMENT OF THE DIFFERENCE BETWEEN THE TOTAL ELECTRICAL ENERGY PRODUCED BY A GENERATOR AND THE ELECTRICAL ENERGY CONSUMED BY THE AUXILIARY EQUIPMENT NECESSARY TO OPERATE THE GENERATOR. FOR A GENERATOR WITH NO HOST LOAD AND/OR SECTION 218 LOAD, METERING THAT IS LOCATED AT THE PCC. FOR A GENERATOR WITH HOST LOAD AND/OR SECTION 218 LOAD, METERING THAT IS LOCATED AT THE GENERATOR BUT AFTER THE POINT OF AUXILIARY LOAD(S) AND PRIOR TO SERVING HOST LOAD AND/OR SECTION 218 LOAD.

INSTALLATION:

- (A) FOR METERING PURPOSES, THE GENERATOR CONDUCTORS SHALL BE CONNECTED TO THE LINE SIDE OF THE NGOM SOCKET.
- (B) BUS TAP AHEAD OF MAIN BREAKER TO SERVE ONLY THE CO-GENERATOR FACILITY.
- C NGOM PANELS AND DEVICES ARE NORMALLY REQUIRED TO BE GROUPED WITH THE BILLING METER AT THE PCC (ALSO REFERRED TO AS THE SERVICE AND METERING EQUIPMENT).
- (D) VISIBLE OPEN AND LOCKABLE DISCONNECTS ARE REQUIRED ON EACH SIDE OF THE NGOM EXCEPT AS NOTED IN FIGURES 1 AND 2. (b)
- E A SITE PLACARD IS REQUIRED AT THE SERVICE AND METERING EQUIPMENT. SEE PAGE SG 017.1 FOR SITE PLACARD REQUIREMENTS. IF NGOM IS NOT LOCATED IN LINE OF SITE OF THE SERVICE AND METERING EQUIPMENT, AN ADDITIONAL SITE PLACARD IS REQUIRED ON THE NGOM DENOTING THE LOCATION OF THE SERVICE AND METERING EQUIPMENT.
- $(\mathsf{\,f\,})$ an address placard is required on the front of the NGOM panel.
- $(\mathsf{G}\,)$ a placard shall be installed on the utility side disconnect labeled:
 - "PV (OR WT) SYSTEM DISCONNECT FOR UTILITY OPERATION UTILITY SIDE."
- (H) A PLACARD SHALL BE INSTALLED ON THE GENERATOR SIDE DISCONNECT LABELED:
 - "PV (OR WT) SYSTEM DISCONNECT FOR UTILITY OPERATION GENERATOR SIDE."
- $(\ {\sf J}\)$ CONDUCTORS TERMINATING IN THE NGOM PANEL SHALL BE LABELED "UTILITY" AND "GENERATOR".

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
													•

SHEET 2 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DICTRIBUTED CENTRATION

SG807.2

DISTRIBUTED GENERATION METERING

INSTALLATION (CONT'D):

- (K) FOR INSTRUMENT TRANSFORMER RATED CT NGOM PANELS, A "CURRENT FLOW" PLACARD WITH AN ARROW POINTING TOWARDS THE UTILITY SIDE DISCONNECT SHALL BE INSTALLED ON THE INSIDE SIDE WALL OF PANEL OR ON THE OUTSIDE FRONT OF NGOM PANEL.
- $(\ \mathsf{L}\)$ in no case shall any of the host load be connected to the generator side of a ngom panel.
- M CUSTOMER OWNED TRANSFORMERS FOR STEPPING VOLTAGE UP OR DOWN FOR INTERCONNECTION:
 - 1. FOR SERVING VOLTAGES LESS THAN 600 VOLTS, CUSTOMER OWNED TRANSFORMERS INSTALLED TO STEP VOLTAGE UP OR DOWN TO INTERCONNECT WITH THE SDG&E SERVICE AT THE NET GENERATOR OUTPUT METER (NGOM), THE TRANSFORMER SHALL BE LOCATED ON THE GENERATOR SIDE (LINE SIDE) OF THE NGOM. IN KEEPING WITH THE GOVERNING CPUC FILED RULES, THE TRANSFORMER SHALL NOT BE INSTALLED ON THE UTILITY SIDE (LOAD SIDE) OF THE NGOM.
 - THE TRANSFORMER SHALL ALSO NOT BE INSTALLED BETWEEN THE NGOM AND THE REQUIRED LINE SIDE VISIBLE OPEN DISCONNECT.
 - 3. THE NGOM SHALL BE THE SAME PHASE AND VOLTAGE AS THE SERVING METER WITH WHICH IT IS INTERCONNECTED.

BILL OF MATERIALS: NONE

NOTES:

- (I) UTILITY SIDE
- $({\scriptscriptstyle
 m II})$ generator side

METERING:

III. BILLING AND POWER PURCHASE METERING:

SDG&E WILL PROVIDE AND INSTALL METERING, AT A LOCATION ACCEPTABLE TO SDG&E TO COMPLY WITH APPLICABLE CPUC-APPROVED TARIFFS, POWER PURCHASE CONTRACTS, AND SDG&E'S REQUIREMENTS. THE INSTALLATION, OPERATION, AND MAINTENANCE COSTS OF THESE METERING FACILITIES SHALL BE BORNE BY THE CUSTOMER IN ACCORDANCE WITH ELECTRIC RULES 21 AND 2. REFER TO EXAMPLES OF TYPICAL BILLING AND POWER PURCHASE METERING IN TABLE 3. THE CUSTOMER WILL PROVIDE AND MAINTAIN ALL SERVICE EQUIPMENT AND SWITCHBOARDS IN ACCORDANCE WITH SDG&E'S REQUIREMENTS. (c) (d)

IV. NET GENERATION OUTPUT METERING – GENERAL INFORMATION AND INSTALLATION: (k)

Indicates Latest Revision

- a A NGOM IS ALWAYS INSTALLED IN THE ELECTRICAL CIRCUITRY USED TO INTERCONNECT A CUSTOMER'S GENERATING FACILITY WITH HOST LOAD. MORE SPECIFICALLY, IT IS LOCATED IN THE CIRCUITRY AT A LOCATION AFTER ANY CONNECTIONS USED TO SERVE THE "AUXILIARY LOADS" USED TO OPERATE THE GENERATING FACILITY, BUT BEFORE ANY CONNECTION TO THE HOST LOAD.
- b. WHEN SELF-CONTAINED METERING IS USED FOR NGOM, THE METER PANEL MAY BE EITHER A SAFETY SOCKET CAN WITH FACTORY INSTALLED TEST-BYPASS FACILITIES OR, IF THE AVAILABLE FAULT CURRENT AT THE NGOM LOCATION DOES NOT EXCEED 10,000A, A RESIDENTIAL SELF-CONTAINED METER PANEL MAY BE USED. WHEN INSTRUMENT TRANSFORMER RATED METERING IS USED FOR NGOM PURPOSES, THE METERING EQUIPMENT SHALL MEET SDG&E'S REQUIREMENTS FOUND IN SG SECTION 600 FOR MEDIUM VOLTAGE METERING, OR SG SECTION 500 FOR LOW VOLTAGE METERING. TERMINATING SECTIONS UTILIZED FOR DELIVERY OF SDG&E SERVICE LATERAL CABLES SHALL MEET APPLICABLE REQUIREMENTS OF SG SECTIONS 500, 600 AND 700, WHICHEVER IS APPLICABLE. SWITCHBOARDS AND SWITCHGEAR USED FOR NGOM PURPOSES SHALL NOT EXCEED STANDARD AMPACITIES APPROVED BY SDG&E. (e) f (g) i j
- c. THE SERVICE SECTIONS MUST BE DESIGNED SO THAT THE METERING SECTION CAN BE ISOLATED BY A LOCKABLE OPEN OR RACKABLE CIRCUIT BREAKER AND A VISIBLY OPEN AND LOCKABLE DISCONNECT SWITCH. THE LOCKABLE OPEN DEVICES NEED TO BE LOCATED ON EACH SIDE OF THE METERING SECTION.
- d. NGOM PANELS AND DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH ALL OF SDG&E'S APPLICABLE SERVICE STANDARD CLEARANCES AND SPECIFICATIONS AND BE INSPECTED AND APPROVED BY THE AHJ OVER THE CUSTOMER'S FACILITIES PRIOR TO THE INSTALLATION OF THE METER(S).

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.													
REV	REV CHANGE DR BY DSN APV DATE REV CHANGE DR BY DSN APV D											DATE		
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F							
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е							
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025	

SHEET 3 OF 6

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

DISTRIBUTED GENERATION METERING

Completely Revised

METERING (CONT'D):

V. PURPOSE AND USE OF NET GENERATION OUTPUT METERING:

- a. GENERATING FACILITIES MAY REQUIRE AN NGOM FOR EVALUATION, MONITORING, AND VERIFICATION PURPOSES (I.E., SYSTEM PERFORMANCE MEASUREMENTS UNDER AN INCENTIVE PROGRAM). NGOM MAY ALSO BE REQUIRED TO PARTICIPATE IN CERTAIN CPUC-APPROVED TARIFF PROGRAMS, SUCH AS NEM AGGREGATION AND VIRTUAL NEM. NGOM IS USEFUL FOR DETERMINING ANY APPLICABLE DEMAND CHARGES FOR CUSTOMERS RECEIVING STANDBY SERVICE AND TO PRECISELY CALCULATE ANY APPLICABLE NON-BYPASSABLE DEPARTING LOAD CHARGES, TO SATISFY APPLICABLE CALIFORNIA INDEPENDENT SYSTEM OPERATOR (CAISO) RELIABILITY REQUIREMENTS, AND FOR DISTRIBUTION SYSTEM PLANNING AND OPERATIONS. WHEN NGOM IS REQUIRED, GENERATING FACILITIES ARE NOT REQUIRED TO USE A NGOM WHERE LESS INTRUSIVE AND/OR MORE COST EFFECTIVE OPTIONS, FOR PRODUCER/CUSTOMER, ARE AVAILABLE FOR PROVIDING GENERATOR DATA TO SDG&E. CUSTOMERS MAY ELECT TO INSTALL A NGOM OR HAVE SDG&E INSTALL A NGOM AT THE CUSTOMER'S EXPENSE.
- b. When a customer installs a generating facility to supplement the electric service received from SDG&E, SDG&E recommends the installation of a ngom because both SDG&E and the customer typically need to know when and how much energy is produced by the generator(s). In each case, the data provided by the metering installation must be readily compatible with the data acquisition and management systems used to process the data provided by the metering and convert it to useful and timely information for the user. Common uses for ngom are: tariff administration some tariffs, such as SDG&E's schedule e-depart deporting load non-bypassable charges, use the kwh production of a generator serving a customer's load. Revenue grade metering is the preferred way to acquire this information. SDG&E's schedule s Standby will also use ngom in determining demand charges that may be applicable.
- c. WHEN SDG&E'S CHARGES ARE CALCULATED BASED ON METERED QUANTITIES, THE ACCURACY AND QUALITY OF THE METERING USED IS SUBJECT TO REGULATION BY THE CPUC. IF THE CUSTOMER CHOOSES NOT TO INSTALL AN NGOM, SDG&E WILL ESTIMATE THE DEPARTING LOAD.

DISTRIBUTION SYSTEM PLANNING – A CUSTOMER'S GENERATOR MAY BE OPERATED IN SUCH A MANNER THAT IT REDUCES THE LOADING ON SDG&E'S DISTRIBUTION SYSTEM. NGOM DATA CAN BE USED BY SDG&E TO INTEGRATE CUSTOMER GENERATING FACILITY OPERATIONAL AND ENERGY PRODUCTION INFORMATION WITH DISTRIBUTION CIRCUIT LOADING INFORMATION TO BETTER PLAN FOR THE LOADING OF SDG&E'S DISTRIBUTION CIRCUITS.

DISTRIBUTION SYSTEM OPERATION – SDG&E'S DISTRIBUTION CIRCUIT OPERATION AND SWITCHING DECISIONS CAN BE IMPROVED WITH TIMELY (I.E., REAL-TIME OR NEAR REAL-TIME) INFORMATION REGARDING THE AMOUNT OF GENERATION OPERATING AT ANY POINT IN TIME ON A PARTICULAR SECTION OF A DISTRIBUTION CIRCUIT. NGOM DATA CAN BE INTEGRATED WITH A COMMUNICATION CIRCUIT AND DATA MANAGEMENT PROGRAM TO PROVIDE A VERY CURRENT SNAPSHOT OF THE NATURE OF A CIRCUIT'S LOAD, THEREBY ALLOWING FOR MORE FINELY TUNED OPERATIONS OF SDG&E'S DISTRIBUTION SYSTEM.

CUSTOMER GENERATION OPERATION AND MONITORING – GENERATION OPERATION, ENERGY PRODUCTION, AND SALES NEED TO BE MEASURED BY THE CUSTOMER AND, IN MANY CASES, THIRD PARTIES WHO ARE EITHER SELLING THE ENERGY PRODUCED BY THE GENERATOR(S) TO THE CUSTOMER OR WHO HAVE PROVIDED FINANCIAL INCENTIVES TIED TO CERTAIN PERFORMANCE CRITERIA BASED ON THE ENERGY PRODUCED. NGOM CAN BE USED WITH VARIOUS DATA MANAGEMENT PROGRAMS TO PROVIDE BOTH REAL-TIME AND CUMULATIVE DATA THAT CAN BE USED FOR THESE PURPOSES.

MULTIPLE TARIFF METERING – WHERE A GENERATING FACILITY INCLUDES MULTIPLE GENERATORS ELIGIBLE FOR SERVICE UNDER MORE THAN ONE NET ENERGY METERING (NEM) RATE SCHEDULE (E.G. NEM OR NEM-FC), OR WHERE A GENERATING FACILITY CONSISTS OF ONE OR MORE NEM-ELIGIBLE GENERATORS IN COMBINATION WITH ONE OR MORE NON-NEM ELIGIBLE GENERATORS WITHOUT NON-EXPORT RELAYS, METERING WILL BE REQUIRED AT THE PCC AND AT EACH OF THE NEM-ELIGIBLE GENERATOR GROUPS TO ENSURE PROPER TARIFF ADMINISTRATION. WHERE A GENERATING FACILITY CONSISTS OF ONE OR MORE NEM-ELIGIBLE GENERATOR GROUPS IN COMBINATION WITH ONE OR MORE NON-NEM GENERATORS, METERING OF THE NON-NEM GENERATORS IS NOT REQUIRED.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
				_									

SHEET 4 OF 6 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

DISTRIBUTED GENERATION METERING

Completely Revised

Indicates Latest Revision

VI. EXCEPTIONS TO SDG&E'S NGOM REQUIREMENTS:

- a. NGOM IS NOT NORMALLY REQUIRED FOR SMALL (<10 KW) GENERATING FACILITIES THAT ARE ELIGIBLE FOR SERVICE UNDER SDG&E'S NET ENERGY METERING (NEM) TARIFF. SHOULD SDG&E DETERMINE IT NECESSARY THAT NGOM IS REQUIRED AT A NEM-ELIGIBLE LOCATION, SUCH METERING WILL BE INSTALLED AT SDG&E'S EXPENSE.
- b. NGOM IS NOT REQUIRED FOR GENERATORS THAT ARE INSTALLED ONLY FOR EMERGENCY OR BACK-UP SERVICE AND ARE NOT AUTHORIZED TO BE OPERATED IN PARALLEL OUTSIDE OF A MOMENTARY TRANSFER. SDG&E WILL SCREEN GENERATING FACILITY INTERCONNECTION APPLICATIONS AND ADVISE CUSTOMERS ON THE USE OF NGOM.
- c. AN NGOM IS NOT USUALLY REQUIRED FOR GENERATING FACILITIES THAT ONLY EXPORT POWER TO SDG&E'S ELECTRIC DISTRIBUTION SYSTEM. SDG&E WILL INSTALL A METER THAT IS CAPABLE OF RECORDING BOTH THE GENERATING FACILITY'S ENERGY CONSUMPTION AND POWER EXPORTED TO THE ELECTRIC DISTRIBUTION SYSTEM.
- VII. TABLE 2 LISTS THE TYPE OF METERS AND RELATED MONITORING EQUIPMENT SDG&E MAY REQUIRE TO MEASURE THE NET ENERGY OUTPUT OF A CUSTOMER'S GENERATING FACILITY AND, IN SOME CASES, TO MONITOR THE STATUS OF THE CUSTOMER'S EQUIPMENT USED TO INTERCONNECT THE GENERATING FACILITY. UNLESS OTHERWISE AGREED TO BETWEEN SDG&E AND THE CUSTOMER, THE CUSTOMER WILL SUPPLY THE METERING PANEL AND RELATED HARDWARE AND SDG&E WILL PROVIDE THE METERS OR MONITORING EQUIPMENT AT THE CUSTOMER'S EXPENSE.
 - a. SDG&E'S CHARGES FOR SUCH DEVICES ARE REGULATED BY THE CPUC.

TABLE 2

IADLE Z	
	TYPICAL METERING DEVICES REQUIRED AND INSTALLED BY SDG&E
TOTAL RATED KW OF GENERATING FACILITY	TYPICAL METERING DEVICES INSTALLED BY SDG&E
< 200	NON-TIME OF USE (TOU) REVENUE GRADE METERS MEASURING NET GENERATION OUTPUT. INTERVAL DATA RECORDING (IDR) METERS MAY BE REQUIRED TO DETERMINE COMPLIANCE UNDER VARIOUS INCENTIVE PROGRAMS.
200 <u><</u> X < 1000	REVENUE GRADE LDR METERS MEASURING NET GENERATION OUTPUT AND CUSTOMER LOAD. NO TELEMETRY REQUIRED.
1,000 <u><</u> X < 10,000	REVENUE GRADE REAL-TIME ENERGY METERING (RTEM) METERS CAPABLE OF NEAR REAL-TIME TELEMETRY MEASURING NET GENERATION OUTPUT AND CUSTOMER LOAD, WATTS, VARS, WATT-HOUR, VAR HOUR, AMPS AND VOLTS.
WIND PROJECTS ≥ 1,000	REVENUE GRADE IDR METERS MEASURING NET GENERATION OUTPUT AND CUSTOMER LOAD, PLUS REAL-TIME (SCADA) TELEMETRY REQUIRED TO MEASURE/MONITOR TOTAL WATTS, VARS, CIRCUIT BREAKER (CB) STATUS AND VOLTAGE OF GENERATING FACILITY. REAL-TIME TELEMETERING REQUIREMENTS FOR WIND PROJECTS LESS THAN 10 MW WILL BE EVALUATED ON A CASE-BY-CASE BASIS.
≥10,000	REVENUE GRADE IDR METERS MEASURING NET GENERATION OUTPUT AND CUSTOMER LOAD, PLUS REAL-TIME (SCADA) TELEMETRY REQUIRED TO MEASURE AT LEAST TWO OF THE FOLLOWING THREE PARAMETERS: (1) TOTAL GROSS GENERATION, (2) CUSTOMER LOAD, OR (3) NET FLOW TO/FROM UTILITY INTERFACE. SCADA TELEMETRY ALSO REQUIRED TO MONITOR WATTS, VARS, AMPS, VOLTS (GENERATOR BUS) AND INTERFACE CB STATUS. ACTUAL POINTS WILL VARY DEPENDING ON CUSTOMER CONFIGURATION.
GENERATING FACILITIES WHERE ANY SINGLE GENERATOR > 10,000	REVENUE GRADE IDR METERS MEASURING NET GENERATION OUTPUT AND CUSTOMER LOAD, PLUS REAL-TIME (SCADA) TELEMETRY WILL BE REQUIRED TO MEASURE/MONITOR EACH INDIVIDUAL UNIT'S WATTS, VARS, AMPS, VOLTS (GENERATOR BUS) AND UNIT CB STATUS.

VIII. WHERE GENERATION IS CONNECTED DIRECTLY TO SDG&E THROUGH A CUSTOMER OR SDG&E SWITCHYARD INTERFACE AT 69 KV AND ABOVE, SDG&E ALSO REQUIRES REAL-TIME (SCADA) TELEMETRY FOR SWITCHYARD CB STATUS, BUS VOLTS, AND LINE WATTS AND VARS.

IX. VOLTAGE STANDARDS:

IF A CUSTOMER INSTALLS A GENERATOR UTILIZING A VOLTAGE NOT LISTED IN SDG&E'S SERVICE STANDARDS & GUIDE, THEN THE CUSTOMER WILL BE REQUIRED TO INSTALL, OWN AND MAINTAIN A TRANSFORMER TO MATCH THE UTILITY'S SERVICE VOLTAGE. NGOM PANELS OR SWITCHGEAR MUST BE LOCATED ON THE UTILITY SIDE OF THE VOLTAGE-MATCHING TRANSFORMER.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
							_						_

SHEET 5 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION METERING

XI. INSPECTION:

ALL CONDITIONS SPECIFIED IN THESE REQUIREMENTS MUST BE MET AND VERIFIED BY AN AUTHORIZED SDG&E REPRESENTATIVE. IN ADDITION, APPROVAL FROM THE AHJ, FOR PORTIONS OF THE ELECTRIC SYSTEM UNDER THEIR JURISDICTION, IS REQUIRED BEFORE INTERCONNECTION IS ALLOWED.

XII. DISCONNECTION OF GENERATOR:

WHENEVER IT IS DETERMINED BY SDG&E THAT THE CUSTOMER'S GENERATOR IS ADVERSELY AFFECTING ITS ELECTRIC DISTRIBUTION SYSTEM, SDG&E RESERVES THE RIGHT TO DISCONNECT THE GENERATOR FROM ITS SYSTEM UNTIL THE CUSTOMER HAS CORRECTED THE PROBLEM. UNDER EMERGENCY CONDITIONS, SDG&E RESERVES THE RIGHT TO DISCONNECT THE CUSTOMER'S GENERATOR FROM ITS ELECTRIC DISTRIBUTION SYSTEM WITHOUT NOTIFICATION.

XIII. ACCESSIBILITY:

ALL DEVICES USED TO DISCONNECT THE GENERATOR SHALL BE ACCESSIBLE UNDER ALL CONDITIONS AND AT ALL TIMES, 24 HOURS A DAY, TO SDG&E'S AUTHORIZED EMPLOYEES OR AGENTS.

XIV. TRANSFORMER REQUIREMENTS:

WHERE SERVICE IS PROVIDED AT OR BELOW 480V, THE CUSTOMER IS TO BE SERVED BY A DEDICATED TRANSFORMER WITH THE FOLLOWING EXCEPTIONS:

- EXCEPTION 1: NOT REQUIRED FOR GENERATION UNDER 10 KW
- EXCEPTION 2: NOT REQUIRED FOR INDUCTION GENERATION UNDER 100 KW

XV. TELEMETERING:

FOR GENERATION FACILITIES THAT ARE RATED ONE MEGAWATT AND ABOVE, SDG&E REQUIRES TELEMETERING EQUIPMENT AT THE SOURCE (AT THE CUSTOMER'S EXPENSE), TO PROVIDE CONTINUOUS GENERATION OUTPUT DATA TO SDG&E'S OPERATIONS PERSONNEL. THE CUSTOMER SHALL PROVIDE A DEDICATED COMMUNICATION SERVICE AND 120-VOLT UNINTERRUPTABLE POWER SOURCE AT EACH TELEMETERING INSTALLATION.

REFERENCE:

- (a) FOR BUS TAPS, SEE SG517.
- (b) FOR DISCONNECT REQUIREMENTS, SEE SG511.
- (c) SEE RULE 21.
- (d) SEE RULE 2.
- (e) for medium voltage metering, see SG section 600.
- (f) FOR LOW VOLTAGE METERING, SEE SG SECTION 500.
- (g) SEE SG SECTION 700.
- (h) FOR ADDRESS AND PLACARD REQUIREMENTS, SEE SG017.
- (i) FOR A SELF-CONTAINED METER EXAMPLE, SEE SG808.
- (j) FOR EXAMPLES OF CT METERING USING A COMBINATION CT AND METER SOCKET CAN, COMMONLY REFERRED TO AS AN EXO CAN, SEE SG809.
- (k) FOR THE WORKING SPACE AND CLEARANCE REQUIREMENTS FROM SDG&E-OWNED ELECTRIC METER AND GAS METER SET ASSEMBLY STANDARD, SEE SG810.
- SEE RULE 16 B.1.

0 1000 000F0 D: 0 0 FL 1: 0 AH: 11	
© 1998 - 2025 San Diego Gas & Electric Company. All rights rese	erved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025

SHEET 6 OF 6

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION METERING

Completely Revised

SG807.6

Information Removed




	FIGURE ITEMS	
ITEM	DESCRIPTION	DETAILS
<u>(1)</u>	BARRIERS, INSULATING, RIGID	
2	ALTERNATE NEUTRAL LUG POSITION	
3	LUG, DOUBLE NEUTRAL, VERTICAL LAY-IN	NO. 250 MCM CU-AL WIRE CAPACITY
4	STUDS, UPPER TEST CONNECTOR	

INSTALLATION:

- (a) hubs capped off if used for underground feed.
- (B) MOUNTED ON EITHER SIDEWALL
- $({ t C})$ Test-bypass blocks shall be bussed or wired to socket Jaws or Terminals. $({ t d})$
- (D) ALL COVERS SHALL BE INDEPENDENTLY REMOVABLE. UPPER COVER SHALL BE NON-REMOVABLE WHEN METER IS IN PLACE. METER SOCKET SHALL BE MOUNTED ON SUPPORT AND ATTACHED TO PANEL. LOWER COVER SHALL BE SEALABLE AND PERMANENTLY LABELED:

"DO NOT BREAK SEALS. NO FUSES INSIDE." (e)

- (E) FOR 3-PHASE, 4-WIRE, CONNECT SEVENTH JAW TO BODY OF NEUTRAL LUG WITH A #12 COPPER WIRE, WHITE IN COLOR.
- (F) FOR 3-PHASE, 4-WIRE DELTA, IDENTIFY RIGHT HAND TEST-BYPASS BLOCK (2 POLES) AS POWER LEG, ORANGE IN COLOR (C-PHASE).
- G FOR 3-PHASE, 3-WIRE, INSTALL BUS TO CONNECT LINE AND LOAD POLES TOGETHER AT TOP OF CENTER TEST-BYPASS BLOCK AND CONNECT FIFTH JAW TO THIS BUS USING A #12 WIRE, RED IN COLOR.
- (H) FOR SINGLE-PHASE, 3-WIRE, PROVIDE TWO TEST-BYPASS BLOCKS MOUNTED IN THE OUTER POSITIONS AND A 4-JAW SOCKET.
- J FOR SINGLE-PHASE, 3-WIRE, 120/208 VOLTS, PROVIDE TWO TEST-BYPASS BLOCKS MOUNTED IN THE OUTER POSITIONS AND A 5-JAW SOCKET. CONNECT FIFTH JAW OF METER SOCKET TO BODY OF NEUTRAL LUG WITH A NO. 12 COPPER WIRE, WHITE IN COLOR.
- (K) PERMANENT LABELS INDICATING LINE AND LOAD CONNECTIONS FOR THE TEST BLOCKS ON INSIDE BACK OF ENCLOSURE IN 3/4-INCH (MINIMUM) HIGH BLOCK LETTERS. (b)
- L LABEL CONDUCTORS IN METER PANEL LINE SIDE AS "GENERATOR" AND LOAD SIDE AS "UTILITY".
- (M) AN ADDRESS PLACARD IS REQUIRED ON THE FRONT OF THE NGOM PANEL. A SITE PLACARD IS REQUIRED AT THE SERVICE AND METERING EQUIPMENT. IF NGOM IS NOT LOCATED IN LINE OF SITE OF THE SERVICE AND METERING EQUIPMENT, AN ADDITIONAL SITE PLACARD IS REQUIRED ON THE NGOM SHOWING THE LOCATION OF THE SERVICE AND METERING EQUIPMENT. (a)

BILL OF MATERIALS: NONE

NOTES:

(I) LOWER COVER REMOVED

REFERENCE:

- (a) FOR ADDRESS AND SITE PLACARD REQUIREMENTS, SEE SG017.
- $(\,\mathsf{b}\,)\,$ for 100A and 200A safety socket can specifications, see SG514.

Indicates Latest Revision

(c)SEE SG513.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025

SHEET 2 OF 3

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION

New Page

Information Removed

SG808.2

METERING
SAFETY SOCKET METER CAN

Completely Revised

REFERENCE (CONT'D): (d) FOR METER SOCKET CLIP REQUIREMENTS, SEE SG516. (e) FOR SEALING REQUIREMENTS, SEE SG503. (f) FOR TEST-BYPASS BLOCK DETAIL, SEE SG513, FIGURE 1. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV DATE DR BY DSN APV REV CHANGE DATE **CHANGE** С **EDITORIAL CHANGES** ARC JIK IPJ KRG 01/09/2023 В Ε **EDITORIAL CHANGES** IPJ IPJ CZH 11/01/2019 LSM TPM 11/01/2017 EDM | IWA | JTM | KRG | 02/03/2025 Α **EDITORIAL CHANGES** IPJ MOVED FROM SG806 **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG808.3 DISTRIBUTED GENERATION 3 OF 3

METERING SAFETY SOCKET METER CAN

SCOPE: THIS STANDARD DISCUSSES THE TRANSFORMER RATED METER PANEL IN DISTRIBUTED GENERATION METERING. (1)(A)(G)(I)(E) $\langle 2 \rangle$ 10" 2" I.D. - 1/8" 4 X c 3" 00 (B)(3)3'-6" MIN. MIN. (F) 5 (III)(IV) b (H)1'-6" 4)(c) 3" 3 1/2" 3" MAX. (D)5" Ø (E)(A)(G)(II)MAX. **FIGURE 1** NET GENERATION OUTPUT METERING (NGOM) ONLY COMBINATION CURRENT TRANSFORMER AND METER SOCKET CAN, 0-600V, 800A MAXIMUM SEE TABLES 1 AND 2 TABLE 1




FIGURE 2 "CURRENT FLOW" PLACARD

MINIMUM DIMENSIONS									
CONFIGURATION	Z (MIN.)								
3Ø 3-WIRE									
4-WIRE	36"								
Y									
1Ø	24"								

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
		L		ч,—		l .							

SHEET 1 OF 2 Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION

METERING

TRANSFORMER RATED METER PANEL

SG809.1

	FIGURE ITEMS											
ITEM	DESCRIPTION	DETAILS										
$\langle 1 \rangle$	CONDUCTORS											
2	STUDS, SEALABLE	(4 PLACES)										
(3)	HANDLES											
4	PERCH, TEST, REMOVABLE											
(5)	BASE, MOUNTING, TRANSFORMER											

INSTALLATION:

- $(\mathtt{A}$) GENERATOR AND UTILITY SIDE CONDUCTORS MUST ENTER ABOVE THE TEST PERCH AND BELOW THE CT MOUNTING BASE. $(\mathtt{a}$)
- $(\mathsf{B}\,)$ cover shall have two lifting handles, be a maximum of 9 square feet, and have a caution sign that reads, "DO NOT BREAK SEALS, NO FUSES INSIDE."
- (c) install "current flow" placard on inside side panel or outside front of meter panel. Current flow arrow SHOULD BE POINTED TOWARD UTILITY SIDE CONDUCTOR.
- $(extsf{D})$ provision shall be made in the CT compartment for a mechanical LUG bondable termination of the utility's NEUTRAL. THIS TERMINATION MAY BE INSTALLED ON THE CT MOUNTING BASE. THE GROUNDING ELECTRODE CONDUCTOR MAY NOT ENTER OR TERMINATE INSIDE THE PANEL.
- (ϵ) bond equipment grounding conductor to the bonding lug on the bushing.
- F NO CONDUCTORS PERMITTED IN SHADED AREA.
- G) LABEL CONDUCTORS IN METER PANEL: LINE SIDE AS "GENERATOR" AND LOAD SIDE AS "UTILITY".
- (H) AN ADDRESS PLACARD IS REQUIRED ON THE FRONT OF THE NGOM PANEL. A SITE PLACARD IS REQUIRED AT THE SERVICE AND METERING EQUIPMENT. IF NGOM IS NOT LOCATED IN LINE OF SITE OF THE SERVICE AND METERING EQUIPMENT, AN ADDITIONAL SITE PLACARD IS REQUIRED ON THE NGOM SHOWING THE LOCATION OF THE SERVICE AND METERING EQUIPMENT.
- J USE TOP PERCH ONLY.

BILL OF MATERIALS: NONE

NOTES:

- $(\ { ilde {
 m I}}\)$ utility side
- (II) GENERATOR SIDE
- (III) FURNISHED BY CUSTOMER
- (IV) INSTALLED BY CUSTOMER

REFERENCE:

- a) FOR OVERHEAD-FED AND UNDERGROUND-FED CANS, SEE SG515.
- $(\,\mathsf{b}\,)$ FOR TRANSFORMER MOUNTING BASE DETAILS, SEE SG515.
- (c) SEE SG515.9, NOTE III.
- FOR ADDRESS AND PLACARD REQUIREMENTS, SEE SG017.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025

New Page

Information Removed

SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES DISTRIBUTED GENERATION **METERING**

TRANSFORMER RATED METER PANEL

Completely Revised

SG809.2

SCOPE: THIS STANDARD DISCUSSES METERING CLEARANCE REQUIREMENTS IN DISTRIBUTED GENERATION METERING.




FIGURE 1 WORKING CLEARANCE REQUIREMENTS FROM SDG&E-OWNED ELECTRIC METER AND GAS METER SET ASSEMBLY FRONT VIEW




FIGURE 1 WORKING CLEARANCE REQUIREMENTS FROM SDG&E-OWNED ELECTRIC METER AND GAS METER SET ASSEMBLY C I PLAN VIEW SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
													•

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION
METERING CLEARANCE REQUIREMENTS

SG810.1

	FIGURE ITEMS									
ITEM	DESCRIPTION									
$\langle 1 \rangle$	CLEAR ZONE									
2	PANEL, METER, ELECTRIC									
3	TRENCH									
4	RISER, SDG&E									

INSTALLATION:

- (A) WALL AREA BEHIND METER SET ASSEMBLY INCLUDING HEADERS, MUST BE FREE OF ANY OBSTRUCTIONS SUCH AS WATER PIPES, HOSE BIBS, SEWER CLEAN OUTS, DRAIN SPOUTS, ELECTRIC CONDUITS, ETC. NO BUILDING VENT, WINDOW OR OTHER OPENINGS, COVERED OR UNCOVERED, ARE ALLOWED WITHIN 18 INCHES FROM THE UTILITY GAS RISER VENT, AND FROM FINAL GRADE TO A HEIGHT OF 10 FEET. FIXED WINDOWS ARE ACCEPTABLE. EQUIPMENT, SUCH AS BUT NOT LIMITED TO, CABLE TV, TELEPHONE, INVERTERS, DISCONNECTING DEVICES, TRANSFER SWITCHES, ETC., ARE ALSO NOT ALLOWED WITHIN 36 INCHES RADIALLY OF THE UTILITY GAS RISER VENT, AND FROM FINAL GRADE TO A HEIGHT OF 10 FEET ABOVE THE GAS METER SET ASSEMBLY AS INDICATED BY THE CLEAR ZONE.
- (B) MAINTAIN 36 INCHES CLEAR AND LEVEL WORKING SPACE IN FRONT OF GAS AND ELECTRIC METERS.
- © ELECTRIC BONDING TO OR USE OF THE UTILITY'S GAS SERVICE PIPING, GAS RISERS OR METER FACILITIES FOR ELECTRIC GROUNDING IS NOT PERMITTED.

BILL OF MATERIALS: NONE

NOTES:

(I) SIZE AND DIMENSIONS OF PANELS MAY VARY. ILLUSTRATION IS NOT TO SCALE.

REFERENCE:

a. FOR MORE INFORMATION ABOUT GENERAL CLEARANCE REQUIREMENTS AROUND GAS METER SET ASSEMBLIES, SEE SG1007.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
													•

Indicates Latest Revision | Completely Revised | New Page | Information Removed


SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


DISTRIBUTED GENERATION
METERING CLEARANCE REQUIREMENTS

SG810.2

SCOPE: THIS STANDARD DISCUSSES TYPICAL BILLING AND POWER PURCHASE METERS IN DISTRIBUTED GENERATION METERING.



EXAMPLE 1 METERING ADAPTER (TYPICAL) (A)



EXAMPLE 2 SAFETY SOCKET CAN (TYPICAL)

EXAMPLE 3 C.T. PANEL (TYPICAL)

FIGURE 1 EXAMPLES OF TYPICAL BILLING AND POWER PURCHASE METERS (I) SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025
													•

SHEET 1 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

> DISTRIBUTED GENERATION **METERING**

SG811.1

TYPICAL BILLING AND POWER PURCHASE METERS

	FIGURE ITEMS												
ITEM	DESCRIPTION	DETAILS											
$\langle 1 \rangle$	PANEL, METER												
2	SWITCH, TEST												
3	MAIN SWITCH	OR BREAKER COMPARTMENT											

INSTALLATION:

- (A) THE HORIZONTAL SERIES METER ADAPTER MUST HAVE THE BILLING METER IN THE LEFT-HAND SOCKET AND THE POWER PURCHASE METER IN THE RIGHT-HAND SOCKET. THE VERTICAL SERIES METER ADAPTER MUST HAVE THE BILLING METER IN THE TOP SOCKET AND THE POWER PURCHASE METER IN THE BOTTOM SOCKET.
- (B) WIRING BETWEEN SAFETY SOCKET CANS BY CUSTOMER.
- (c) NEW METER SOCKET AND RING INSTALLED BY CUSTOMER.

BILL OF MATERIALS: NONE

NOTES:

(I) DETENTED METERS WILL BE REQUIRED ON ALL INSTALLATIONS.

REFERENCE: NONE

@ 4000 000E 0 Di 0 0 Fl 0	. All		4 ! 44
© 1998 - 2025 San Diego Gas & Electric Company	, All tights reserved. Removal of this co	nnvriant notice without hermission is	not permitted linder law
e 1000 Zozo dan biego das a Electric Company	. 7 th rights reserved. I terrioval of this of	pyright house without permission is	not pomitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES	ARC	JIK	IPJ	KRG	01/09/2023	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	11/01/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D	MOVED FROM SG806	EDM	IWA	JTM	KRG	02/03/2025

SHEET 2 OF 2

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

DISTRIBUTED GENERATION

SG811.2

METERING
TYPICAL BILLING AND POWER PURCHASE METERS

78

52

+©

78

52

+©

<u>PAGE</u>	SUBJECT
1002	GAS ALPHABETICAL SUBJECT INDEX
1003	GENERAL INFORMATION
1004	GAS TRENCH ONLY FOR SAN DIEGO COUNTY
1005	GAS METER CAPACITY AND SELECTION
1006	GAS SERVICE POLICIES AND METER LOCATIONS
1007	UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION
1008	METER CABINET FOR SINGLE RESIDENTIAL GAS METER
1009	GAS SERVICE RISER AND HOUSELINE SPACING, CLEARANCES AND MINIMUM WORKING SPACE
1010	GAS METERS GROUPED ON METER HEADERS
1011	GAS SERVICE AND METER BEHIND WING WALLS
1012	BUILDING RECESS FOR GAS SERVICE AND METERS
1013	MOBILE HOME METER PAD
1014	BARRICADES FOR GAS METER SETS
1015	GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	LSM	TPM	11/01/2017	D						

SHEET 1 OF 1

Completely Revised New Page Indicates Latest Revision Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS TABLE OF CONTENTS

SG1001.1

<u>S</u>	SUBJECT .	<u>PAGE</u>													
Α	CCESS TO CUSTON	MER'S PREMISE	S										.1003	.1 – 1	003.3
Α	LCOVE													1	003.1
Α	SSISTANCE AND II	NFORMATION F	OR E	QUIPN	MENT	SELE	CTION ANI) ENE	RGY SAVINGS					1	003.2
В	ARRICADES FOR G	SAS METER SETS	S												1014
В	ILLING ACCOUNT	ESTABLISHMEN	т											1	003.2
С	USTOMER RESPON	ISIBILITY FOR A	APPLI	ANCE	S									1	003.2
D	EFINITION OF TER	RMS											100	3.1, 1	009.2
Е	LECTRIC BONDING	AND GROUND	ING C)F GA	S PIP	E								1	003.4
E	STABLISHING THE	GAS METER LO	CATI	ON A	ND LO	DCAT]	ON OF CUS	STOM	ER'S HOUSELINE					1	003.2
G	AS FACILITIES NE	ar undergroi	JND F	PADM	OUNT	ED E	QUIPMENT	OR S	UBSTRUCTURES						1015
G	AS METER CAPACI	TY AND SELECT	ΓΙΟΝ.												1005
G	AS METERS GROU	PED ON METER	HEAL	DERS.											1010
	ADEQUATE SU	PPORT FOR WA	LL MO	TNUC	ED M	ETER	HEADERS.							1	010.8
	CUSTOMER BU	ILT HEADER SU	JPPOF	RT										1	010.6
ACCESS TO CUSTOMER'S PREMISES															
	RIGHT HAND H	HEADERS											101	0.1, 1	010.4
G	AS SERVICE AND I	METERING												1	003.1
	BEHIND WING	WALLS													1011
	BUILDING REC	ESS FOR GAS S	ERVI	CE AN	ID ME	TERS									1012
	METER CABINE	ET FOR SINGLE	RESII	DENT	IAL G	AS MI	ETER								1008
G	AS SERVICE POLIC	CIES AND METE	R LOC	CATIC	NS										1006
	EXISTING GAS	SERVICE – CUS	STOM	ER RE	EQUES	STS F	OR ADDITI	ONAL	SERVICES					1	006.3
	GAS METER AS	SEMBLY INSTA	LLATI	ON											1007
	GAS SERVICE A	AND METERING												1	003.1
	METER LOCATI	ONS												1	006.1
1								_			1		_		
	CHAN	GE	DR	ВҮ	DSN	APV	DATE		CHA	ANGE	DR	ВҮ	DSN	APV	DATE
В	FORMAT	TTING EDM JIK JTM KRG 03/31/2025 E													
Α	EDITORIAL C	CHANGES	-	LSM	LSM	TPM	11/01/2017	D							
	SHEET			SDG	5&E E	LECTI	RIC SERVIC	E STA	Andards & Guii	DES			SC1002.1		
	1 OF 2							AS_					50	יוחר	JZ.1
	·				ALP	HAB	ETICAL	SUB.	JECT INDEX						

<u> </u>	<u>SUBJECT</u>															<u>F</u>	PAGE
	METER AND SE	ERVICE LOCATIO)N													1	006.1
	NUMBER OF SE	ERVICES ALLOWE	ED T	ОАВ	UILD	ING –	NEW PRO	JECTS	S							1	006.2
	SERVICE LOCA	TIONS														1	006.4
G	GAS SERVICE RISER	R AND HOUSELIN	NE SP	'ACIN	G, CL	.EARA	NCES AND	MINI	MU	JM WORKIN	IG S	SPACE					1009
	CLEAR AND LE	VEL WORKING S	SPACE	≣												1	009.2
	CLEARANCES F	ROM BUILDING	WAL	LS AN	ID CC	RNER	RS									1	009.1
	INSTALLATION	SPACE AND DIM	MENS	IONS												1	009.2
G	GAS TRENCH ONLY	FOR SAN DIEGO) COL	JNTY													1004
H	HIGH-PRESSURE METERING																
F	HOUSELINE MODIFICATIONS																
L	LARGE GAS FIELD SERVICE VEHICLE ACCESS																
Ν	MARKOUT SERVICE																
M	METER SET ASSEMBLY (MSA)																
M	MOBILE HOME METER PAD																
C	DRANGE COUNTY D	ISTRICT METER	. CLE/	ARAN	CES											1	007.6
C	OWNERSHIP AND M	IAINTENANCE OF	F UTI	iLITY'	S FAC	CILITI	ES									1	003.3
R	RECESS (BUILDING))			•••••										10	03.1,	1012
R	RESALE OF NATURA	L GAS			•••••											1	003.4
S	SIGNAGE REQUIREN	MENTS FOR GAS	SER\	VICE I	LOCA	TION:	S ON MULT	TI-TEN	NAN	NT BUILDIN	IGS					1	003.2
S	STANDARD CUBIC F	EET PER HOUR ((SCF	H)		•••••										1	003.1
ι	JTILITY PLACEMEN	T IN JOINT TRE	NCH .	AND (GAS N	METEF	R ASSEMBL	Y INS	STA	LLATION							1007
٧	/ENT					•••••										1	003.1
٧	/ENTED APPLIANCE															1	003.1
٧	/ENTED DECORATI\	VE APPLIANCE														1	003.2
٧	/ENTING SYSTEM															1	003.2
REV	© 1998 - 2025 Sa	an Diego Gas & Elec	ctric C		ny. All	_	eserved. Rer	moval o	1			e without permissio	n is not		ted und		DATE
C	СПАН	JE .	DK	БТ	DSN	AFV	DATE	F			л	MAGE	DK	ы	DSN	APV	DATE
B A	FORMATT EDITORIAL C		EDM				03/31/2025 11/01/2017										
Λ	EDITORIAL	X Indicates Late	est R	l l			npletely Revi	L .		New Page		Information R	emoved				
	SHEET			SDG	&E E	LECTF	RIC SERVIC	E ST/	ANI	DARDS & G	UIC	DES			C.	2100	22.2
	2 OF 2						G	AS							S(G100	12.2

2 OF 2

GAS ALPHABETICAL SUBJECT INDEX

SCOPE: THE GAS SECTION PRESENTS GENERAL AND DETAILED INFORMATION CONCERNING THE LOCATION, ACCESSIBILITY, AND VENTILATION OF GAS METERS, RISERS, SERVICE REGULATORS AND GAS SERVICES FOR NEW INSTALLATIONS AND RELOCATIONS.

ATTENTION:

* THE SERVICE STANDARDS & GUIDE GAS SECTION IS FOR USE BY PLUMBERS, ARCHITECTS, BUILDERS AND OTHERS INTERESTED IN DESIGNING AND BUILDING A PROPER GAS SERVICE AND METER(S) INSTALLATION.

DEFINITIONS:

- ACCESSIBLE: CAPABLE OF BEING REACHED QUICKLY AND CONVENIENTLY 24 HOURS A DAY FOR CONSTRUCTION, OPERATION,
 MAINTENANCE, INSPECTION, TESTING OR READING, WITHOUT REQUIRING THOSE SEEKING ACCESS TO CLIMB OVER OR REMOVE
 OBSTACLES; OR TO OBTAIN SPECIAL PERMISSION OR SECURITY CLEARANCES.
- ALCOVE: AN ENCLOSED, NORMALLY RECESSED, AREA WHERE GAS METERS ARE INSTALLED. ENCLOSED ALCOVES ARE NOT
 PERMITTED FOR ANY NEW PROJECT SUBMITTED TO THE UTILITY. EXISTING ALCOVES ARE GRANDFATHERED. IF MODIFICATIONS
 ARE MADE TO THE CUSTOMER'S GAS SYSTEM, SUCH AS LOAD ADDITIONS REQUIRING A LARGER GAS METER, THE GAS METER WILL
 NOT BE ALLOWED TO STAY IN THE ALCOVE.
- HIGH-PRESSURE METERING: GAS PRESSURE HIGHER THAN THE STANDARD 7-INCH WATER COLUMN
- LARGE GAS FIELD SERVICE VEHICLE ACCESS: A MINIMUM 16 FEET WIDE "ALL WEATHER" DRIVEN WAY OF SUFFICIENT STRENGTH TO SUPPORT TRUCK WEIGHT CLASS H20 (20 TONS), WITH A CLEAR HEIGHT OF 13'-6" AND A 40-FOOT MINIMUM TURNING RADIUS MEASURED FROM INSIDE CURB.
- METER SET ASSEMBLY (MSA): SERVICE RISER, REGULATOR, METER, AND ASSOCIATED PIPING
- **RECESS:** AN INDENTATION OF A BUILDING WALL, FOUNDATION, AND FLOOR. A RECESS IS OPEN ON THE FRONT SO THAT THE METER SET ASSEMBLY IS VISIBLE. NO DOORS, LATTICE WORK, OR COVERS OF ANY TYPE ARE PERMITTED. THE BUILDING FOUNDATION MUST NOT CROSS ANY PORTION OF THE RECESS. (a)
- STANDARD CUBIC FEET PER HOUR (SCFH): A UNIT OF MEASURE TO REPRESENT THE RATE OF FLOW OF GAS, ADJUSTED TO STANDARD TEMPERATURE AND PRESSURE CONDITIONS.
- VENT: A LISTED FACTORY-MADE VENT PIPE AND VENT FITTINGS FOR CONVEYING FLUE GASES TO THE OUTSIDE ATMOSPHERE
- VENTED APPLIANCE: AN APPLIANCE THAT REQUIRES A VENTING SYSTEM. SEE DEFINITION OF VENTING SYSTEM.
- VENTED DECORATIVE APPLIANCE: A VENTED APPLIANCE WHOSE ONLY FUNCTION IS PROVIDING AN AESTHETIC EFFECT OF FLAMES. IN VERY RARE CASES WHEN THE HEAT VALUE OF THE VENTED DECORATIVE APPLIANCE (FIREPLACE OR GAS LOG APPLIANCE) IS BEING USED IN THE SPACE HEATING CALCULATIONS FOR TITLE 24 ENERGY CALCULATIONS, THE APPLIANCE IS NO LONGER CONSIDERED "DECORATIVE ONLY" AND WILL REQUIRE INDIVIDUAL GAS METERING BY THE UTILITY. WHEN THIS OCCURS, ALL INDIVIDUAL VENTED AND UN-VENTED GAS APPLIANCES SERVING A DWELLING UNIT MUST BE INDIVIDUALLY METERED BY THE UTILITY.
- VENTING SYSTEM: CONSISTS OF THE VENT OR CHIMNEY AND ITS CONNECTORS, ASSEMBLED TO FORM A CONTINUOUS OPEN
 PASSAGEWAY FROM AN APPLIANCE TO THE OUTSIDE ATMOSPHERE FOR THE PURPOSE OF REMOVING PRODUCTS OF COMBUSTION.
 THIS DEFINITION SHALL ALSO INCLUDE A VENTING ASSEMBLY WHICH IS AN INTEGRAL PART OF AN APPLIANCE.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. GAS SERVICE AND METERING:

a. EACH NEW SINGLE OR MULTI-FAMILY RESIDENTIAL DWELLING UNIT, WHERE THE TENANT CAN USE GAS DIRECTLY IN GAS APPLIANCES WHICH REQUIRE VENTING, SHALL BE INDIVIDUALLY METERED BY THE UTILITY.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV REV** DSN APV DR BY DSN APV DATE **CHANGE** DR BY DATE **CHANGE** С EDITORIAL CHANGES/FORMATTING **EDM IWA** JTM KRG 03/31/2025 F LSM В **EDITORIAL CHANGES** _ IPJ TPM 11/01/2017 Ε NO CHANGES - REAFFIRMED JC TPM MDJ 07/23/2015 D Α Information Removed **Indicates Latest Revision** Completely Revised New Page SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG1003.1 1 OF 4 GENERAL INFORMATION

I. GAS SERVICE AND METERING (CONT'D):

- EXCEPTION: IF THE ONLY VENTED APPLIANCES SERVING THE DWELLING UNITS ARE DECORATIVE APPLIANCES THE UNIT IS NOT REQUIRED TO BE SEPARATELY METERED AND MAY RECEIVE ITS GAS SUPPLY THROUGH A MASTER METER EFFECTIVE JANUARY 1, 2005. SEE VENT-RELATED DEFINITIONS ABOVE. THIS EXCEPTION DOES NOT APPLY TO LOG LIGHTERS. LOG LIGHTERS ARE A VENTED APPLIANCE, AND ARE NOT CONSIDERED TO BE DECORATIVE.
- c. THE UTILITY SUPPLIES NATURAL GAS AT A HEATING VALUE THAT MAY CHANGE FROM TIME TO TIME DUE TO THE SUPPLY FROM VARIOUS GAS FIELDS AS GATHERED AND TRANSMITTED TO THE UTILITY.

II. ESTABLISHING THE GAS METER LOCATION AND LOCATION OF CUSTOMER'S HOUSELINE:

- a. WHEN BUILDING PLANS HAVE BEEN COMPLETED AND GAS LOADS ARE KNOWN, THE UTILITY'S PROJECT PLANNER SHOULD BE CONTACTED. AFTER REVIEWING BUILDING PLANS AND GAS LOAD INFORMATION, THE PROJECT PLANNER WILL PROVIDE A WRITTEN "GAS SERVICE AND METER LOCATION" FORM. THIS WILL ESTABLISH WHERE THE GAS METER(S) AND HOUSELINE(S) ARE TO BE LOCATED. BUILDINGS REQUIRING MULTIPLE METERS SHALL HAVE ALL METERS LOCATED AT ONE LOCATION. ALL HOUSELINES SHALL BE CLEARLY AND PERMANENTLY MARKED BY THE CONTRACTOR OR CUSTOMER TO IDENTIFY THE UNIT TO BE SERVED. $\begin{pmatrix} b \\ c \end{pmatrix}$
- b. When any gas design load is over 1,000 scfh, or "high pressure" gas service is required, the utility will initiate a gas load study. This study will be based on information supplied by the customer or their representative. The utility will confirm the results of the load study to the customer or their representative via certified mail. The utility's project planner will advise if large gas field service vehicle access will be required. See definition on sheet 1. Extensions of gas mains and services will be made in accordance with the utility's filed rules.

III. SIGNAGE REQUIREMENTS FOR GAS SERVICE LOCATIONS ON MULTI-TENANT BUILDINGS:

- a. IDENTIFICATION PLAQUES ARE REQUIRED FOR EACH GAS SERVICE/HEADER SERVING A MULTI-TENANT BUILDING. THEY ARE TO HAVE A DIRECTORY DIAGRAM SHOWING ALL THE GAS SERVICE POINTS AND METER LOCATIONS FOR THE BUILDING, AND MUST IDENTIFY THE PARTICULAR SERVICE POINT BEING IDENTIFIED WITH THE SERVING PRESSURE TO THE HEADER, AND A LISTING OF THE UNITS/SUITES SERVED BY IT. \bigcirc
- b. IN ADDITION TO THE INFORMATION SPECIFIED ABOVE, PLAQUES FOR 2-PSIG SERVICES TO MULTI-FAMILY BUILDINGS ARE TO SHOW THE LOCATION AND ACCESS ROUTE TO THE 7-INCH WATER COLUMN REGULATORS FOR EACH UNIT SERVED BY THE HEADER BEING IDENTIFIED.
- c. THE PLAQUE IS TO BE PERMANENTLY AFFIXED TO THE WALL OF THE BUILDING SERVED IN IMMEDIATE PROXIMITY TO THE HEADER, OR IT IS TO BE INSTALLED AS A PERMANENT SELF-SUPPORTING SIGN NEXT TO THE HEADER IN A MANNER THAT DOES NOT IMPEDE REQUIRED CLEARANCES AND WORKING SPACE REQUIREMENTS FOR THE HEADER/METER SET ASSEMBLY.

IV. BILLING ACCOUNT ESTABLISHMENT:

A REQUEST TO THE UTILITY FOR ELECTRIC AND/OR GAS SERVICE IS DIFFERENT THAN AN INQUIRY INTO THE AVAILABILITY OF OR CHARGES FOR SUCH SERVICE. CONTACT THE UTILITY'S CUSTOMER CONTACT CENTER AT (800) 411-7343, TO MAKE AN APPLICATION FOR A BILLING ACCOUNT AS SOON AS THE STREET ADDRESS HAS BEEN ASSIGNED BY THE CITY/COUNTY.

V. CUSTOMER RESPONSIBILITY FOR APPLIANCES:

- a. THE CUSTOMER WILL MAINTAIN ALL GAS PIPING AND EQUIPMENT IN GOOD SAFE CONDITION BEYOND THE POINT OF SERVICE CONNECTION TO THE HOUSELINE. THE UTILITY WILL NOT BE RESPONSIBLE FOR ANY LOSS OR DAMAGE CAUSED BY THE CUSTOMER'S NEGLIGENCE, WANT OF PROPER CARE, OR WRONGFUL ACT IN MAINTAINING THE EQUIPMENT.
- b. THE UTILITY HAS THE RIGHT TO REFUSE OR TO CEASE TO DELIVER GAS TO ANY CUSTOMER IF ANY PART OF THE PIPING, APPLIANCES OR APPARATUS SHALL AT ANY TIME BE UNSAFE OR IF USE IS PROHIBITED UNDER ANY LAW, MUNICIPAL ORDINANCE OR REGULATION.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN		3	DR	_	DSN	_		REV				NGE	DR		DSN		DATE
С	EDITORIAL CHANGE	S/F	ORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F									
В	EDITORIAL C	CHA	NGES	-	LSM	IPJ	TPM	11/01/2017	Е									
Α	NO CHANGES - F	FFIRMED	-	JC	TPM	MDJ	07/23/2015	D										
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Re	moved				
	SHEET				SDC	S&E E	LECTI	RIC SERVIC	E STA	٩NE	DARDS & GL	JIDI	ES					
													SG1003.2					
2 OF 4 GENERAL INFORMATION																		

V. CUSTOMER RESPONSIBILITY FOR APPLIANCES (CONT'D):

- c. THE UTILITY DOES NOT ASSUME THE DUTY OF INSPECTING THE CUSTOMER'S PIPING, APPLIANCES OR EQUIPMENT AND THEREFORE, ASSUMES NO LIABILITY.
- d. GAS SERVICE WILL NOT BE SUPPLIED TO APPARATUS OR APPLIANCES WHERE THEIR OPERATION WILL BE DETRIMENTAL TO OUR GAS SYSTEM OR OTHER CUSTOMERS. GAS SERVICE WILL BE DISCONTINUED TO CUSTOMERS WHO CONTINUE TO USE SUCH APPARATUS OR EQUIPMENT AFTER BEING NOTIFIED.

VI. UTILITY'S RIGHT OF ACCESS TO CUSTOMER'S PREMISES:

THE UTILITY SHALL AT ALL TIMES HAVE THE RIGHT TO ENTER AND LEAVE APPLICANT'S PREMISES FOR ANY PURPOSE CONNECTED WITH THE FURNISHING OF GAS SERVICE (METER READING, INSPECTION, TESTING, ROUTINE REPAIRS, REPLACEMENT, MAINTENANCE, EMERGENCY WORK, ETC.) AND THE EXERCISE OF ANY AND ALL RIGHTS SECURED TO IT BY LAW, OR UNDER UTILITY'S TARIFF SCHEDULES. THESE RIGHTS INCLUDE BUT ARE NOT LIMITED TO:

- a. THE USE OF A UTILITY-APPROVED LOCKING DEVICE, IF APPLICANT DESIRES TO PREVENT UNAUTHORIZED ACCESS TO UTILITY'S FACILITIES.
- b. SAFE AND READY ACCESS FOR UTILITY PERSONNEL FREE FROM UNRESTRAINED ANIMALS.
- c. UNOBSTRUCTED READY ACCESS FOR UTILITY'S VEHICLES AND EQUIPMENT TO INSTALL, REMOVE, REPAIR OR MAINTAIN ITS FACILITIES.
- d. REMOVAL OF ANY AND ALL OF ITS PROPERTY INSTALLED ON APPLICANT'S PREMISES AFTER THE TERMINATION OF SERVICE.

VII. OWNERSHIP AND MAINTENANCE OF UTILITY'S FACILITIES:

- a. SERVICE PIPE, METERS, HEADERS, REGULATORS AND OTHER FACILITIES FURNISHED AND INSTALLED BY THE UTILITY WILL CONTINUE TO BE THE PROPERTY OF THE UTILITY. THEY MAY BE REPAIRED OR REPLACED BY THE UTILITY AT ANY TIME AND MAY BE REMOVED ON TERMINATION OF SERVICE. NO RENT OR OTHER CHARGE MAY BE MADE AGAINST THE UTILITY FOR PLACING OR MAINTAINING ITS FACILITIES ON THE CUSTOMER'S PREMISES. THE CUSTOMER WILL EXERCISE REASONABLE CARE TO PREVENT THE FACILITIES FROM BEING DAMAGED OR DESTROYED.
- b. IN THE EVENT THAT THE CUSTOMER FINDS THE GAS SERVICE TO BE DEFECTIVE, THEY SHOULD NOTIFY THE UTILITY IMMEDIATELY BY CALLING (800) 411-SDGE (7343).
- c. A TYPICAL METER INSTALLATION CONSISTS OF THE SERVICE RISER COMING UP OUT OF THE GROUND TO THE PRESSURE REGULATOR WHICH CONNECTS TO THE METER. THE HOUSELINE, INSTALLED BY THE CUSTOMER'S PLUMBER, IS CONNECTED BY THE UTILITY TO THE OUTLET SIDE OF THE METER. ANY CHANGES TO THE HOUSELINE THEREAFTER WILL BE MADE BY THE CUSTOMER OR THEIR PLUMBER AT THE CUSTOMER'S EXPENSE IN ACCORDANCE WITH APPLICABLE CODES AND REGULATIONS. ADEQUATE WORKING SPACE AND ACCESS MUST BE PROVIDED 24 HOURS PER DAY FOR INSPECTION AND SERVICING BY THE UTILITY.
- d. Large Meters (8C or larger) must be located so as to be available for servicing with large gas field service vehicle access to the meter location. See definition on sheet 1. In all cases, it is highly advisable that a meter location be established by the utility before detailed design of the building and awarding of the plumbing contract is done.

VIII. HOUSELINE MODIFICATIONS:

- a. IN CASES WHERE A CUSTOMER'S PLANNED IMPROVEMENT OR ALTERATION TO A BUILDING REQUIRES RELOCATION OR CHANGE TO THEIR HOUSELINE, SUCH WORK MUST BE DONE BY THE CUSTOMER PRIOR TO THE UTILITY RE-ROUTING ITS SERVICE PIPE. IT IS THE CUSTOMER'S RESPONSIBILITY TO TIE-IN A NEW HOUSELINE(S) TO THE EXISTING HOUSELINE(S). IT IS ALSO THE CUSTOMER'S RESPONSIBILITY TO PAY TO THE UTILITY ANY RELOCATION CHARGES FOR ANY SERVICE PIPE WHICH IS RELOCATED.
- b. AN INSPECTION CLEARANCE FROM THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) IS REQUIRED BEFORE A NEW HOUSELINE CAN BE CONNECTED OR AN ALTERED HOUSELINE CAN BE RECONNECTED.

												_							
-	© 1998 - 2025 Sa	an Di	iego Gas & Ele	ectric C	compa	ny. All	rights	reserved. Rer	moval c	of th	is copyright not	ice	without permission	is not	permit	ted und	der law		
REV	CHAN	GE		DR	BY	DSN	APV	DATE	REV		CHANGE DR B					DSN	APV	DATE	
С	EDITORIAL CHANGE	S/F0	ORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F										
В	EDITORIAL (CHAN	NGES	-	LSM	IPJ	TPM	11/01/2017	Е										
Α	NO CHANGES - F	REAF	FIRMED	-	JC	TPM	MDJ	07/23/2015	D										
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page		Information Re	moved					
	CHEET				SDC	S&E E	LECTI	RIC SERVIC	E STA	NE	DARDS & GUI	DE	ES						
	SHEET SHOULD SHANDARDS & GOLDES														SG1003.3				
	3 OF 4		GENERAL INFORMATION												301003.3				
							<u></u>	L II •	. 510	,									

VIII. HOUSELINE MODIFICATIONS (CONT'D):

- c. Should it be necessary to extend or enlarge a houseline because of added load, call the Project Planner at the Design and Project management regional office nearest your job location prior to connecting the houseline. Large added gas loads, such as pool heaters, may require the replacement of the existing gas meter with a larger one to assure adequate pressure and flow. (b)
- d. In Many Instances, a "hot change tee" has been installed on the outlet side of the gas meter. This tee is used to improve our service to the customer by allowing a meter change or test to be performed without interrupting the customer's gas service. The tee is designed for <u>use by the utility only and must not be</u> used for any other purpose by the customer or their plumber.

IX. RESALE OF NATURAL GAS:

IT IS NOT PERMISSIBLE FOR A CUSTOMER TO RESELL ANY OF THE GAS RECEIVED FROM THE UTILITY TO ANY OTHER PERSON, FIRM OR CORPORATION, EXCEPT THAT THE OWNER OR LESSEE OF ANY EXISTING "MASTER METERED" MOBILE HOME PARK MAY RESELL TO THEIR TENANTS. SUCH RESALE OF GAS MUST BE AT RATES IDENTICAL TO THOSE RATES THE UTILITY WOULD APPLY IN THE EVENT THAT GAS WAS SUPPLIED TO THE SUB-CONSUMER DIRECTLY BY THE UTILITY.

XI. ELECTRIC BONDING AND GROUNDING OF GAS PIPE:

THE FOLLOWING ARE NOT PERMITTED:

- a. ELECTRIC BONDING TO THE UTILITY'S GAS SERVICE PIPING, GAS RISERS, OR METER FACILITIES.
- b. USING THE UTILITY'S GAS SERVICE PIPING, GAS RISERS, OR METER FACILITIES FOR ELECTRICAL GROUNDING, OR IN A MANNER THAT THE GAS PIPING OR OTHER GAS FACILITIES BECOME CURRENT-CARRYING CONDUCTORS.

XII. MARKOUT SERVICE:

BEFORE YOU BEGIN DIGGING AT YOUR BUILDING SITE, CONTACT DIGALERT FOR MARKOUT SERVICE, TO AVOID CONFLICT WITH EXISTING UNDERGROUND FACILITIES. $\stackrel{\frown}{e}$

REFERENCE:

- (a) FOR MINIMUM REQUIREMENTS FOR A RECESS, SEE SG1012.
- (b) FOR CONTACT INFORMATION, SEE SG021.
- (c) FOR INFORMATION ON ADDITIONAL SERVICES, SEE SG1006.
- $(\, {
 m d}\,)$ for plaque specifications, with the exception that all letter sizes may be reduced to 1/8", see SG017.
- (e) CONTACT DIGALERT BY CALLING 811, MONDAY THROUGH FRIDAY, 6:00 A.M. 7:00 P.M., OR VISIT THEIR WEBSITE, <u>HTTPS://www.digalert.org/.</u> FOR EMERGENCY MARKOUT SERVICE ONLY, CALL SERVICE DISPATCH AT (619) 725-5100.

	© 1000 Z020 Gail Diego Gas & Eli	como c	Jonnpa	11y . 7 WI	ngnto i	Cocived. Itel	iiovai (or this copyright house without permission	13 1100	pomin	ica and	JCI IUW	•
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES - REAFFIRMED	_	1C	TPM	MD1	07/23/2015	D						

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this convright notice without permission is not permitted under law

SHEET 4 OF 4 Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GENERAL INFORMATION

SG1003.4

SCOPE: THIS STANDARD DESCRIBES GAS TRENCH ONLY FOR SAN DIEGO COUNTY.

ATTENTION:

THIS STANDARD APPLIES TO NEW 3-INCH OR SMALLER GAS SERVICES TAPPED OFF A 4-INCH OR SMALLER GAS MAIN OR SERVICE. THE TRENCH AND TIE-IN HOLE (WELD HOLE) IN WHICH YOUR SERVICE WILL BE INSTALLED MUST CONFORM TO THIS MINIMUM STANDARD.





FIGURE 1 TIE-IN HOLE DIMENSIONS SEE TABLES 1 AND 3



DETAIL 1 GAS TRENCH ONLY SEE TABLES 2 AND 3

TABLE 1

TIE-I	IN HOLE DIMENSIONS ©
DEPTH W (IN)	12 BELOW EXISTING GAS MAIN
WIDTH Y (IN)	60 MIN.
LENGTH X (IN)	60 MINIMUM FOR MAIN UP TO 4 INCH DIAMETER
	60 MINIMUM FOR 1 1/4 INCH DUPONT MAIN
	72 MINIMUM FOR STEEL TO POLYETHYLENE TRANSITION FITTINGS

TABLE 2

MINIMUM DIMENSIONS FOR WIDTH OF TRENCH													
GAS PIPE SIZE (IN)	WIDTH Z (IN)												
<u><</u> 1	9												
2	12												
3 <mark>& 4</mark>	12 B												

TABLE 3

IADEE	<u> </u>
	FIGURE ITEMS
ITEM	DESCRIPTION
1	SPOIL
2	BACKFILL
3	SHADING MATERIAL
4	GAS MAIN, EXISTING
(5)	TRENCH, GAS SERVICE
6	GAS SERVICE, NEW
7	BASE

INSTALLATION:

- 24-INCH MINIMUM COVER ON PRIVATE PROPERTY. 30-INCH MINIMUM IN STREET/PARKWAY AREAS. 42-INCH MAXIMUM COVER.
- WIDTH AT COUPLING LOCATIONS MUST BE INCREASED TO 18 INCHES FOR 5 FEET ON EACH END OF COUPLING.
- THE SDG&E INSPECTOR WILL ADVISE IF FIELD CONDITIONS WARRANT ADDITIONAL EXCAVATION.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	Е						
Α	EDITORIAL CHANGES	-	JC	TPM	MDJ	09/16/2015	D						

SHEET 1 OF 2 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS TRENCH ONLY FOR SAN DIEGO COUNTY

SG1004.1

INSTALLATION (CONT'D):

- D. A 3-INCH BASE IS REQUIRED TO PREVENT DAMAGE FROM ROCKS, SAGS OR POCKETS. IMPORTED MATERIAL CONSISTING OF NATURAL SAND OR MANUFACTURED SAND, EXISTING NATIVE MATERIAL OR COMBINATIONS MAY BE USED FOR BASE AND SHADING MATERIAL PROVIDED IT COMPLIES WITH SDG&E (UTILITY) STANDARDS AND THE COMPACTION REQUIREMENTS OF THE GOVERNMENTAL AGENCIES. SHADING MATERIAL MUST HAVE A MIXTURE OF PARTICLE SIZES ALL SMALLER THAN 1/2 INCH. A MINIMUM COVER OF 12 INCHES OF COMPACTED SHADING MATERIAL (12 INCHES AFTER COMPACTION) SHALL BE INSTALLED ABOVE GAS PIPE. SHADING STARTS FROM THE BOTTOM OF THE PIPE AND EXTENDS TO A MINIMUM OF 12 INCHES ABOVE THE PIPE OR FACILITY. THE SHADING MATERIAL MUST BE INSTALLED BEFORE THE TRENCH IS BACKFILLED TO PREVENT DAMAGE FROM ROCKS, ETC. THE BACKFILL MATERIAL SHALL MEET THE REQUIREMENTS OF ALL APPLICABLE CODES, ORDINANCES, AND THE UTILITY'S STANDARDS AND BE FREE OF DEBRIS AND ORGANIC MATTER. THE COARSE MATERIAL SHALL BE WELL DISTRIBUTED THROUGHOUT THE FINER MATERIAL. ALL BASE, SHADING AND BACKFILL MUST BE APPROVED BY THE UTILITY'S INSPECTOR.
- E. AFTER THE UTILITY'S INSPECTOR APPROVES THE TRENCH, TIE-IN EXCAVATION, BASE SHADING AND BACKFILL MATERIAL, THE UTILITY WILL INSTALL AND ENERGIZE THE GAS SERVICE. WHEN THE GAS SERVICE IS ENERGIZED, IT MUST BE COVERED DURING THE SAME WORKING DAY. THE UTILITY'S INSPECTOR MUST APPROVE INSTALLATION OF SHADING MATERIAL PRIOR TO BACKFILLING.
- F WHERE UTILITY EMPLOYEES, OR THEIR CONTRACTORS, ARE REQUIRED TO ENTER THE TRENCH, SPOIL MUST BE PLACED A MINIMUM OF 24 INCHES FROM EDGE OF TRENCH. SEE DETAIL 1. IF EXCAVATION AT THE GAS MAIN IS 5 FEET OR MORE IN DEPTH, ALL SAFETY REQUIREMENTS, INCLUDING SHORING THE TIE-IN HOLE (WELD HOLE), MUST BE MET.
- (G) NO WET UTILITIES, SUCH AS WATER, SEWER OR IRRIGATION PIPES ARE ALLOWED IN THE SERVICE TRENCH. A MINIMUM 12 INCHES HORIZONTAL SEPARATION OF UNDISTURBED SOIL IS REQUIRED BETWEEN YOUR SERVICE TRENCH AND ANY WATER, SEWER OR DRAIN PIPE. A MINIMUM 6 INCHES VERTICAL SEPARATION IS REQUIRED FOR CROSSINGS.
- H. ALL TRENCH RESURFACING SHALL BE DONE ACCORDING TO THE GOVERNMENTAL AGENCIES' REQUIREMENTS.
- (J) SIDE WALL FUSIONS NOT ALLOWED FOR 1 1/4 INCH DUPONT.
- (K) 12-INCH WARNING MESH REQUIRED 12 INCHES MINIMUM ABOVE GAS SERVICES AND MAINS OPERATING AT 60 PSIG, AND 18 INCHES ABOVE GAS SERVICES AND MAINS OPERATING AT GREATER THAN 60 PSIG.

BILL OF MATERIALS: NONE

NOTES:

I. CUSTOMER TO CONTACT THE LOCAL CITY OR COUNTY FOR AN EXCAVATION PERMIT AND THEIR REQUIREMENTS PRIOR TO EXCAVATION IN THE PUBLIC RIGHT-OF-WAY. STATE LAW REQUIRES YOU TO CONTACT DIGALERT AT 811 OR VISIT www.digalert.org, AT LEAST 2 WORKING DAYS PRIOR TO EXCAVATION.

REFERENCE:

a. SEE SDGE GAS DISTRIBUTION STANDARD D7403 AND D7428.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHAN		DR	BY	DSN	APV	DATE	REV		С	HAN	IGE	DR	BY	DSN	APV	DATE	
С	EDITORIAL CHANGE	ES/F	ORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F									
В	EDITORIAL (CHAI	NGES	-	LSM	IPJ	TPM	11/01/2017	Е									
Α	A EDITORIAL CHANGES				JC	TPM	MDJ	09/16/2015	D									
	X Indicates Latest Revision Completely Revised										New Page	X	Information Re	moved				
	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES																	

SHEET 2 OF 2

GAS TRENCH ONLY FOR SAN DIEGO COUNTY

SG1004.2

SCOPE: THIS STANDARD DESCRIBES GAS METER CAPACITY AND SELECTION.

TABLE 1

STANDARD 7-INCH	WATER COLUMN (WC) SERVI	CE PRESSURE GAS METER CAPA	CITY AND SECTION
METER TYPE AND SIZE D = DIAPHRAGM R = ROTARY	METER CAPACITY AT 7-INCH WC IN SCFH	MINIMUM SDG&E RISER SIZE AT 7-INCH WC (IN)	SDG&E RISER TO HOUSELINE SPACING DIMENSION (IN)
D 250-275	250-275		
D 400	400	3/ CTL V 1/ DE	10
D 630	630	- 34 STL X 1⁄2 PE	19
D 800	800		
R 8C	800		30
R 11C 175	1,100		
R 15C 175	1,500		30
R 2M 175	2,000	1	40
R 3M 175	3,000		48
R 5M 175	5,000		75
R 7M 175	7,000		75

TABLE 2

HIGH PRESS	SURE (5 PSIG) SERVICE PRES	SURE GAS METER CAPACITY AN	D SECTION
METER TYPE AND SIZE D = DIAPHRAGM R = ROTARY	METER CAPACITY AT 5 PSIG IN SCFH	MINIMUM SDG&E RISER SIZE AT 5 PSIG (IN)	SDG&E RISER TO HOUSELINE SPACING DIMENSION (IN)
D 400	1,030		
R 8C	1,100		
D 630	1,500		48
R 2M 175	2,600	1	
R 3M 175	4,000		
R 5M 175	6,600		75
R 7M 175	9,200		75
R 11M 175	14,500	2	00
R 16M 175	21,100	2	90

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. ROTARY TYPE METERS REQUIRE TRUCK ACCESS FOR INSTALLATION AND MAINTENANCE.
- II. FOR ALL NEW OR REPLACED SERVICES, ALL SERVICE PIPE, FITTINGS AND RISER, MUST REMAIN THE SAME SIZE AS THE EXCESS FLOW VALVE (EFV) OUTLET INSTALLED. USE THE "MINIMUM SDG&E RISER SIZE" COLUMN IN THE APPROPRIATE TABLE ABOVE TO MAKE YOUR SELECTION.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	TABLE UPDATE	YZZ	JTM	JTM	JTM	05/30/2025	F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D		·	·			•

SHEET 1 OF 2

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG1005.1

GAS METER CAPACITY & SELECTION

NOTES (CONT'D):

- III. THE HOUSELINE SHOULD BE LOCATED TO THE RIGHT OF THE METER SET ASSEMBLY. THE FLOW OF GAS FROM INLET TO OUTLET SHOULD BE LEFT TO RIGHT.
- IV. USE THE TOTAL DIVERSIFIED LOAD WHEN SIZING THE METER. ONLY USE 90% OF THE METER CAPACITY.
- V. REQUESTS FOR SERVING PRESSURES GREATER THAN 7 INCHES W. C. MUST BE SUBMITTED TO GAS DISTRIBUTION ENGINEERING FOR REVIEW AND APPROVAL. THE REQUEST TO GAS DISTRIBUTION ENGINEERING SHALL INCLUDE THE MANUFACTURER'S EQUIPMENT SPECIFICATIONS, PLUMBING DIAGRAMS, AND THE EXPECTED LOADS.

REFERENCE: NONE

© 1998 - 2025 San Diego Gas & Flectric Compa	ny All rights reserved. Removal of this convright no	otice without permission is not permitted under law.
© 1990 - 2020 Sali Diego Gas & Electric Compa	ny. An ngnis reserveu. Nemovai oi inis copyngni n	dice williout permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	TABLE UPDATE	YZZ	JTM	JTM	JTM	05/30/2025	F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	ı	LSM	IPJ	TPM	11/01/2017	D						

Completely Revised

SHEET 2 OF 2

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page

Information Removed

GAS METER CAPACITY & SELECTION

SG1005.2

SCOPE: THIS STANDARD DESCRIBES GAS SERVICE POLICIES AND METER LOCATIONS.

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

I. METER AND SERVICE LOCATION:

- a. LOCATION FOR GAS METERS AND SERVICES SHALL COMPLY WITH THE PROVISIONS OF THIS MANUAL AND APPLICABLE CODES, LAWS, AND ORDINANCES OF THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) FOR INSPECTION.
- b. IT IS NECESSARY THAT THE LOCATION FOR THE METER AND SERVICE BE APPROVED IN WRITING BY AN SDG&E PROJECT PLANNER. THIS CAN BE ACCOMPLISHED BY THE CUSTOMER OR CONTRACTOR CONTACTING THE UTILITY'S NEAREST SERVICE PLANNING OR DESIGN AND PROJECT MANAGEMENT REGIONAL OFFICE BY TELEPHONE OR THE INTERNET AND REQUESTING A "METER AND SERVICE LOCATION" FORM. (a)

METER LOCATIONS:

- II. GAS METERS AND REGULATORS MUST BE INSTALLED BY THE UTILITY IN A READILY ACCESSIBLE LOCATION, APPROVED BY THE UTILITY ON THE CUSTOMER'S PREMISES. THEY MUST BE CAPABLE OF BEING REACHED QUICKLY AND CONVENIENTLY 24 HOURS A DAY BY AN UNOBSTRUCTED ACCESS ROUTE FOR CONSTRUCTION, OPERATION, MAINTENANCE, INSPECTION, TESTING OR READING, AND WITHOUT REQUIRING THOSE SEEKING ACCESS TO CLIMB OVER OR REMOVE OBSTACLES, OR OBTAIN SPECIAL PERMISSION OR SECURITY CLEARANCES. THE ACCESS ROUTE MUST NOT BE PRONE TO FLOODING, OR PLANTED WITH ANYTHING OTHER THAN GRASS OR ARTIFICIAL TURF.
- III. THE UTILITY'S GAS METERS AND SERVICE PIPE ARE <u>NOT PERMITTED</u> ON, IN, OVER OR UNDER A HOUSE, BUILDING, UNDERGROUND STRUCTURE, BREEZEWAY, PATIO, WOOD DECK, ASPHALT, CONCRETE PAD, CARPORT, BIO-RETENTION FACILITY, AWNING, ENCLOSURE, OR ANY OVERHANG LARGER THAN A STANDARD EAVE (24 INCHES).
- IV. LARGE METERS (8C OR LARGER) MUST BE LOCATED SO AS TO BE AVAILABLE FOR SERVICING WITH LARGE GAS FIELD SERVICE VEHICLES. (b)
- V. DOORS, GATES OR OTHER SUCH FACILITIES WHICH RESTRICT ACCESS TO ANY METER LOCATION, MUST BE LOCKED ONLY WITH LOCKING DEVICES ACCEPTABLE TO THE UTILITY.
- VI. FOR SINGLE AND MULTIPLE OCCUPANCY BUILDINGS, METER AND METERING EQUIPMENT MAY BE INSTALLED:
 - a. OUTDOORS AND ADJACENT TO A BUILDING
 - b. BEHIND A WING WALL
- VII. FOR MULTIPLE OCCUPANCY BUILDINGS, METERS AND METERING EQUIPMENT ARE TO BE GROUPED AT ONE LOCATION.
- VIII. FOR MOBILE HOME LOTS, METERS AND METERING EQUIPMENT MAY BE INSTALLED:
 - a. AT OR NEAR THE CORNER OF THE MOBILE HOME, CLOSEST TO THE UTILITY'S SOURCE
 - b. ON A PERMANENTLY INSTALLED STRUCTURE NEAR THE FRONT LOT LINE OF THE MOBILE HOME LOT
 - c. AT OR NEAR THE CORNER OF THE MOBILE HOME LOT, CLOSEST TO THE UTILITY'S SOURCE
 - METERS SHALL NOT DEPEND ON A FLEX GAS HOUSELINE FOR SUPPORT. A POST, BRACKET OR OTHER MEANS OF RIGID SUPPORT IS TO BE PROVIDED BY THE CUSTOMER WHEN REQUIRED BY THE APPROPRIATE AHJ OR UTILITY. (c)
- IX. METER HEADERS ARE LIMITED TO TWO TIERS TO ENSURE SAFETY OF PERSONNEL AND METER ACCESSIBILITY.
- XI. METERS MUST BE LOCATED IN A VENTILATED AREA.
- XII. A MINIMUM OF 3 FEET CLEAR AND LEVEL WORKING SPACE IS REQUIRED DIRECTLY IN FRONT OF ANY PORTION OF THE METER SET ASSEMBLY (MSA) OR RECESS. (d)

	© 1998 - 2025 San Diego Gas & Ele	ectric C	ompai	ny. All	rights r	eserved. Rer	noval o	of this copyright n	otice	without permission	is not	permit	ted und	der law	
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	C	HAN	GE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F								
В	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	Е								
Α	NO CHANGES - REAFFIRMED	-	JC	TPM	MDJ	07/23/2015	D								
	X Indicates La	evisio	n	Con	npletely Revi	sed	New Page		Information Ren	noved					

SHEET 1 OF 4 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG1006.1

GAS SERVICE POLICIES AND METER LOCATIONS

NOTES (CONT'D):

- XIII. GAS REGULATORS MUST BE LOCATED AWAY FROM OPENINGS INTO A BUILDING IN ORDER TO ALLOW GAS TO ESCAPE FREELY TO THE OUTSIDE ATMOSPHERE IN THE EVENT OF A LEAK. THE UTILITY IS INSTALLING SERVICE REGULATORS WITH INTERNAL RELIEF VALVES FOR OVER PRESSURE PROTECTION WHICH MAY RELEASE GAS THROUGH THE REGULATOR VENT OPENING. $\stackrel{\frown}{e}$
- XIV. GAS METERS AND SERVICE REGULATORS MUST BE PROTECTED FROM DAMAGE DUE TO CORROSION, EXTREME TEMPERATURES, VEHICULAR TRAFFIC AND MOISTURE. EXPOSURE TO POOL CHEMICALS, DRYER VENTS, LAWN SPRINKLERS, ETC., MUST BE AVOIDED.

GAS SERVICE POLICY FOR NEW PROJECTS – NUMBER OF SERVICES ALLOWED:

XV. MULTI-FAMILY RESIDENTIAL BUILDINGS - LESS THAN 3 STORIES HIGH:

- (a) ONE SERVICE PER BUILDING WILL TYPICALLY BE GRANTED. AT THE UTILITY'S DISCRETION, AND WITH APPROVAL FROM THE AHJ, A SECOND SERVICE MAY BE GRANTED IF SPACE IS NOT AVAILABLE TO GROUP ALL METERS AT ONE LOCATION. GAS RULE 16 WILL APPLY AND RESIDENTIAL ALLOWANCES WILL BE APPLIED TO THE COST OF THE SECOND SERVICE. $\binom{1}{f}$
- (b) THE 300-FOOT RULE THAT APPLIES TO ELECTRIC SERVICE POLICIES <u>DOES NOT APPLY TO GAS</u>. JUSTIFICATION FOR A SECOND SERVICE IS BASED ON SPACE CONSTRAINTS FOR METERS, BUILDING LAYOUT, ETC.

XVI. RESIDENTIAL OR MIXED USE BUILDINGS – 3 STORIES OR GREATER: (XVa)(XVb)

XVII. RESIDENTIAL CONTIGUOUS DWELLINGS - TOWNHOUSES (ROW HOMES):

- a. EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A <u>PARCEL OF LAND BOUNDED BY LEGAL PROPERTY LINES</u> MUST BE PROVIDED WITH AN INDIVIDUAL GAS SERVICE AND METER(S) LOCATED ON THE PROPERTY SERVED.
- b. EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A <u>SINGLE PARCEL OF PROPERTY DIVIDED WITH "ASSUMED PROPERTY LINES"</u> WITH APPROVAL FROM THE AHJ MAY BE PROVIDED WITH:

AN INDIVIDUAL GAS SERVICE AND METER(S) LOCATED ON THE TOWNHOUSE BOUNDED BY ASSUMED PROPERTY LINES, OR

MAY BE SERVED THROUGH A SINGLE GAS SERVICE, WITH METERS GROUPED AT ONE LOCATION IN A COMMON AREA. THE HEADER MUST BE SUPPORTED INDEPENDENT OF THE BUILDINGS CONTAINING DWELLING UNITS.

(c) EASEMENTS WILL BE REQUIRED TO BE ESTABLISHED AND RECORDED IN THE DEED OF EVERY TOWNHOUSE ALLOWING FOR PRIVATELY-OWNED GAS LINES TO CROSS ASSUMED PROPERTY LINES. THE UTILITY IS NOT INVOLVED IN THE EASEMENT PROCESS BUT IT IS IMPORTANT FOR DEVELOPERS TO UNDERSTAND THIS REQUIREMENT.

XVIII. SINGLE PREMISE – MULTIPLE NON-RESIDENTIAL ENTERPRISES (SUCH AS SHOPPING CENTERS & OFFICE BUILDINGS): (N/b)

ONE SERVICE PER BUILDING WILL TYPICALLY BE GRANTED. AT THE UTILITY'S DISCRETION, AND WITH APPROVAL FROM THE AHJ, A SECOND SERVICE MAY BE GRANTED IF SPACE IS NOT AVAILABLE TO GROUP ALL METERS AT ONE LOCATION. GAS RULE 16 WILL APPLY AND NON RESIDENTIAL ALLOWANCES WILL BE APPLIED TO THE COST OF THE SECOND SERVICE.

XIX. SINGLE PREMISE - SINGLE NON-RESIDENTIAL ENTERPRISE (CUSTOMER):

ONE SERVICE PER PREMISE SERVING A SINGLE ENTERPRISE WILL BE GRANTED. IF A SECOND SERVICE IS APPROVED, THE CUSTOMER WILL BE REQUIRED TO PAY THE TOTAL ESTIMATED INSTALLED COST AS A NON-REFUNDABLE PAYMENT. NO ALLOWANCES WILL BE GRANTED FOR THE SECOND SERVICE.

XX. SINGLE PREMISE - MULTIPLE RESIDENTIAL CUSTOMERS:

EACH SEPARATE STRUCTURE CONTAINING TWO OR MORE LEGAL DWELLING UNITS MUST BE INDIVIDUALLY SERVED BY THE UTILITY. EACH DWELLING UNIT MUST BE INDIVIDUALLY METERED BY THE UTILITY. GAS RULE 16 FOR SERVICE EXTENSIONS AND THE RESIDENTIAL ALLOWANCES PER RULE 15 FOR EACH DWELLING UNIT WILL APPLY TO EACH SERVICE. APPROVAL BY THE AHJ IS REQUIRED. f g

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.																	
REV	CHANGE			DR	BY	DSN	APV	DATE	REV		CHANGE			DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGE	S/F	ORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F									
В	EDITORIAL (L CHANGES			LSM	IPJ	TPM	11/01/2017	Е									
Α	NO CHANGES -	NO CHANGES - REAFFIRMED - JC 7				TPM	MDJ	07/23/2015	D									
		X	Indicates La	atest R	evisio	n	Con	npletely Revi	sed		New Page		Information Removed					
	a				SDC	%F F	LECTI	RIC SERVIC	E ST	ANI	DARDS & GL	JTDI	FS					

SHEET 2 OF 4

GAS SERVICE POLICIES AND METER LOCATIONS

SG1006.2

NOTES (CONT'D):

GAS SERVICE POLICY FOR EXISTING CUSTOMERS – REQUESTS FOR ADDITIONAL SERVICE:

XXI. MULTI-FAMILY RESIDENTIAL BUILDINGS – LESS THAN 3 STORIES HIGH:

 $(\,\mathfrak{a}\,)$ THE CUSTOMER SHOULD BE INSTRUCTED TO PLUMB TO THE EXISTING METER LOCATION. IF FIELD CONDITIONS MAKE IT IMPRACTICAL, A SECOND SERVICE CAN BE GRANTED. THE CUSTOMER WILL BE BILLED TOTAL INSTALLED COST. MASTER TO INDIVIDUAL REQUESTS REQUIRING A SECOND SERVICE TO ACCOMMODATE ALL OF THE INDIVIDUAL METERS WILL BE BILLED TOTAL INSTALLED COST.

XXII. RESIDENTIAL OR MIXED USE BUILDINGS - 3 STORIES OR GREATER: (Ma)

XXIII. RESIDENTIAL CONTIGUOUS DWELLINGS – TOWNHOUSES (ROW HOMES): (MIC)

- a. EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A PARCEL OF LAND BOUNDED BY LEGAL PROPERTY LINES MUST BE PROVIDED WITH AN INDIVIDUAL GAS SERVICE AND METER(S) LOCATED ON THE PROPERTY SERVED.
- b. EACH INDIVIDUAL TOWNHOUSE OR DUPLEX LOCATED ON A SINGLE PARCEL OF PROPERTY DIVIDED WITH "ASSUMED PROPERTY LINES" MAY BE PROVIDED WITH:

AN INDIVIDUAL GAS SERVICE AND METER(S) LOCATED ON THE TOWNHOUSE BOUNDED BY ASSUMED PROPERTY LINES, OR MAY BE SERVED THROUGH A SINGLE GAS SERVICE, WITH METERS GROUPED AT ONE LOCATION IN A COMMON AREA. THE HEADER MUST BE SUPPORTED INDEPENDENT OF THE BUILDINGS CONTAINING DWELLING UNITS.

XXIV. SINGLE PREMISE - MULTIPLE NON-RESIDENTIAL ENTERPRISES (SUCH AS SHOPPING CENTERS & OFFICE BUILDINGS):

THE CUSTOMER SHOULD BE INSTRUCTED TO PLUMB TO THE EXISTING METER LOCATION IF SAME PRESSURE. IF HIGH PRESSURE IS REQUIRED, SET NEW METER ADJACENT TO EXISTING METER LOCATION. ALLOWANCES WILL BE GRANTED TOWARDS RULE 16 COSTS.(f)

XXV. SINGLE PREMISE, SINGLE NON-RESIDENTIAL ENTERPRISE (CUSTOMER):

THE CUSTOMER SHOULD BE INSTRUCTED TO PLUMB TO THE EXISTING METER LOCATION IF SAME PRESSURE. IF HIGH PRESSURE IS REQUIRED, SET NEW METER ADJACENT TO EXISTING METER LOCATION. ALLOWANCES WILL BE GRANTED TOWARDS RULE 16 COSTS. IF REINFORCEMENT IS REQUIRED, CUSTOMER WILL PAY INCREMENTAL COST OF REINFORCEMENT LESS THE ALLOWANCE FOR NEW LOAD. AT THE UTILITY'S DISCRETION, A NEW SERVICE MAY BE LESS EXPENSIVE THAN THE REINFORCEMENT OF THE EXISTING SERVICE. IF SO, THE CUSTOMER WOULD PAY THE COST FOR THE NEW SERVICE LESS THE ALLOWANCE GRANTED FOR THE NEW LOAD.(f)

XXVI. SINGLE PREMISE - MULTIPLE RESIDENTIAL CUSTOMERS:

THE CUSTOMER SHOULD BE INSTRUCTED TO PLUMB TO THE EXISTING METER LOCATION. FOR NEW SERVICE REQUESTS, EACH SEPARATE STRUCTURE CONTAINING TWO OR MORE LEGAL DWELLING UNITS MUST BE INDIVIDUALLY SERVED BY THE UTILITY. EACH DWELLING UNIT MUST BE INDIVIDUALLY METERED BY THE UTILITY. GAS RULE 16 FOR SERVICE EXTENSIONS AND THE RESIDENTIAL ALLOWANCES PER RULE 15 FOR EACH DWELLING UNIT WILL APPLY TO EACH SERVICE. APPROVAL BY THE AHJ IS REQUIRED. (f) q

REFERENCE:

- (a) FOR CONTACT INFORMATION, SEE SG021.
- (b) FOR DEFINITION OF "LARGE GAS FIELD SERVICE VEHICLE ACCESS", SEE SG1003.
- (c) FOR MOBILE HOME METER PAD INFORMATION, SEE SG1013.

Indicates Latest Revision

- $\left(\mathsf{d} \right)$ for minimum working space requirements for a building recess, see SG1012.
- e) FOR SPECIFIC REQUIREMENTS, SEE SG1007.
- (f)<mark>SEE GAS RULE 16.</mark>
- (g)<mark>SEE RULE 15.</mark>

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	Е						
Α	NO CHANGES - REAFFIRMED	-	JC	TPM	MDJ	07/23/2015	D						

SHEET 3 OF 4 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


New Page

Completely Revised

GAS SERVICE POLICIES AND METER LOCATIONS

SG1006.3

SCOPE: THIS STANDARD DESCRIBES REQUIREMENTS FOR LOCATING GAS SERVICE.






FIGURE 1 (E)(F)

FIGURE 2 (E)(G)

INSTALLATION:

SERVICE LOCATIONS:

- A. GAS SERVICES ARE TO BE INSTALLED ALONG THE SHORTEST MOST PRACTICAL ROUTE FROM THE UTILITY'S CLOSEST SOURCE TO THE METER LOCATION ACCEPTABLE TO THE UTILITY. INSTALL SERVICES PERPENDICULAR TO THE GAS MAIN. DIAGONAL INSTALLATION SHALL NOT BE PERMITTED. A JOINT SERVICE IS LIMITED TO TWO RISERS PER SERVICE LINE. (a)
- B. EACH GAS SERVICE MUST HAVE A SHUTOFF VALVE LOCATED OUTSIDE OF THE BUILDING IN A READILY ACCESSIBLE LOCATION. THE SHUTOFF VALVE IS NOT PERMITTED IN A LOCKED SECURITY AREA.
- C. LOCATION OF THE UTILITY'S GAS SERVICE PIPE WILL BE DESIGNED TO AVOID HAZARDS OR OBSTRUCTIONS (PARTICULARLY RETAINING WALLS, TREES, PLOWED LAND, EXCESSIVE MOISTURE, AND STEEP BANKS).
- D. SERVICE PIPE MUST NOT BE RUN UNDER OR THROUGH A BUILDING, UNDERGROUND STRUCTURE, BREEZEWAY, PATIO (ASPHALT, CONCRETE PAD, OR WOOD DECKING) OR CARPORT.
- É) THE ROUTE OF THE GAS SERVICE PIPE MUST BE ACCESSIBLE FOR LEAKAGE PATROL AND MAINTENANCE. THE SERVICE PIPE MUST NOT BE INSTALLED IN A STEEP BANK THAT IS HIGHER THAN 8 FEET AND HAS A SLOPE GREATER THAN A 3-TO-1 RATIO. THE UTILITY MUST APPROVE INSTALLATION IN SLOPES GREATER THAN 3-TO-1.
- (F) for banks 8 feet high or less, all slopes are acceptable.
- (G) gas services may be installed in banks higher than 8 feet if the slope is 3 to 1 (33 percent) or less.
- H. DURING CONSTRUCTION, IF THE AREA AROUND THE RISER IS TO BE PAVED, A 4-INCH MINIMUM DIAMETER OR SQUARE OPENING AROUND THE RISER IS REQUIRED. THIS INCLUDES MOBILE HOME METER PADS. THIS MUST BE PROVIDED TO PREVENT DAMAGE TO THE RISER AND TO PROVIDE AN ESCAPE ROUTE IN THE EVENT OF A GAS LEAK.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

(a) FOR METER LOCATIONS, SEE SG1006.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	Е						
A	NO CHANGES - REAFFIRMED	-	JC	TPM	MDJ	07/23/2015	D						

SHEET 4 OF 4

Completely Revised Indicates Latest Revision New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


GAS SERVICE POLICIES AND METER LOCATIONS

SG1006.4

SCOPE: THIS STANDARD PROVIDES TYPICAL PREFERRED AND ALTERNATE UTILITY PLACEMENT IN A JOINT TRENCH FOR GAS AND ELECTRIC SERVICE AND METER INSTALLATIONS, AND GAS METER SET ASSEMBLY SEPARATION REQUIREMENTS FROM ELECTRIC METERS, COMMUNICATION EQUIPMENT, BUILDING OPENINGS, AND MISCELLANEOUS EQUIPMENT SUCH AS, BUT NOT LIMITED TO, TANKLESS WATER HEATERS.

ATTENTION:

* THE ILLUSTRATIONS SHOWN ARE TYPICAL FOR A RESIDENTIAL SINGLE METER INSTALLATION, BUT MAY BE MODIFIED FOR MULTIPLE GAS METER HEADER INSTALLATIONS AND COMMERCIAL/INDUSTRIAL PREMISES.



TYPICAL INSTALLATION WITH SERVICES AND METERING ON RIGHT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED LEFT OF THE GAS METER (PREFERRED LOCATION)

FRONT VIEW
SEE TABLE 1




FIGURE 1

TYPICAL INSTALLATION WITH SERVICES AND METERING ON RIGHT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED LEFT OF THE GAS METER (PREFERRED LOCATION)
PLAN VIEW
SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	10/15/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	08/16/2016	D						
		•											

SHEET 1 OF 6 Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION




FIGURE 2

TYPICAL INSTALLATION WITH SERVICES AND METERING ON RIGHT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED RIGHT OF THE GAS METER (ALTERNATE LOCATION) FRONT VIEW **SEE TABLE 1**




FIGURE 2

TYPICAL INSTALLATION WITH SERVICES AND METERING ON RIGHT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED RIGHT OF THE GAS METER (ALTERNATE LOCATION) PLAN VIEW

SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	10/15/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	08/16/2016	D						

SHEET 2 OF 6 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION




FIGURE 3

TYPICAL INSTALLATION WITH SERVICES AND METERING ON LEFT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED RIGHT OF THE GAS METER (PREFERRED LOCATION)

FRONT VIEW
SEE TABLE 1




FIGURE 3

TYPICAL INSTALLATION WITH SERVICES AND METERING ON LEFT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED RIGHT OF THE GAS METER (PREFERRED LOCATION)

PLAN VIEW

SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C EDITORIAL CHANGES/FORMATTING EDM IWA JTM KRG 03/31/2025 F IPJ IPJ CZH 10/15/2019 E	REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
	С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
A EDITORIAL CHANGES - LSM BRB TPM 08/16/2016 D	В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	10/15/2019	Е						
	Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	08/16/2016	D						

SHEET 3 OF 6

Indicates Latest Revision | Completely Revised | New Page | Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG1007.3

UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION




FIGURE 4

TYPICAL INSTALLATION WITH SERVICES AND METERING ON LEFT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED LEFT OF THE GAS METER (ALTERNATE LOCATION) FRONT VIEW SEE TABLE 1




FIGURE 4

TYPICAL INSTALLATION WITH SERVICES AND METERING ON LEFT SIDE OF STRUCTURE AND ELECTRIC METER LOCATED LEFT OF THE GAS METER (ALTERNATE LOCATION) PLAN VIEW


SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	10/15/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	08/16/2016	D						

SHEET 4 OF 6 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION




DETAIL 1 TYPICAL RISER PLACEMENT SEE TABLE 1



DETAIL 2 TYPICAL JOINT SERVICE TRENCH SEE TABLE 1



DETAIL 3 TYPICAL RISER PLACEMENT SEE TABLE 1



DETAIL 4 TYPICAL JOINT SERVICE TRENCH SEE TABLE 1

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	-	IPJ	IPJ	CZH	10/15/2019	Е						
Α	EDITORIAL CHANGES	-	LSM	BRB	TPM	08/16/2016	D						
		•											

SHEET 5 OF 6

Indicates Latest Revision | Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION

TABLE 1

	FIGURE ITEMS
ITEM	DESCRIPTION
$\langle 1 \rangle$	METER PANEL, ELECTRIC
2	CATV, TELCO (TYPICAL)
3	RISER, SDG&E
4	TRENCH
(5)	SOURCE OF IGNITION CLEARANCE
6	VENT
7	WATER HEATER, TANKLESS
8	CLEAR ZONE
9	MUDSILL
(10)	SLEEVE, PROTECTIVE
(11)	SHADING MATERIAL, ACCEPTABLE
(12)	FRONT OF HOUSE
(13)	RISER, GAS

INSTALLATION:

- A. SIZE AND DIMENSIONS OF PANELS MAY VARY. FIGURES AND DETAILS ARE NOT TO SCALE.
- (B) WALL AREA BEHIND METER SET ASSEMBLY INCLUDING HEADERS, MUST BE FREE OF ANY OBSTRUCTIONS SUCH AS WATER PIPES, HOSE BIBS, SEWER CLEAN OUTS, DRAIN SPOUTS, ELECTRIC CONDUITS, ETC. NO BUILDING VENT, WINDOW OR OTHER OPENINGS, COVERED OR UNCOVERED, ARE ALLOWED WITHIN 18 INCHES FROM THE UTILITY GAS RISER VENT, AND FROM FINAL GRADE TO A HEIGHT OF 10 FEET AS INDICATED BY THE CLEAR ZONE. FIXED WINDOWS ARE ACCEPTABLE. EQUIPMENT, SUCH AS BUT NOT LIMITED TO, CABLE TV, TELEPHONE, INVERTERS, DISCONNECTING DEVICES, TRANSFER SWITCHES, ETC., ARE ALSO NOT ALLOWED WITHIN THE CLEAR ZONE, AND ARE NOT ALLOWED WITHIN 36 INCHES RADIALLY OF THE UTILITY GAS RISER VENT.
- (C) MAINTAIN 36-INCH CLEAR AND LEVEL WORKING SPACE IN FRONT OF GAS AND ELECTRIC METERS.
- D. ELECTRIC BONDING TO OR USE OF THE UTILITY'S GAS SERVICE PIPING, GAS RISERS OR METER FACILITIES FOR ELECTRIC GROUNDING IS NOT PERMITTED.
- E TANKLESS WATER HEATERS REQUIRE A MINIMUM 36-INCH RADIAL CLEARANCE FROM THE UTILITY GAS RISER VENT AND OUTSIDE CLEAR ZONE. A MINIMUM 12-INCH SIDE CLEARANCE TO THE ELECTRIC METER PANEL IS REQUIRED. THE TANKLESS WATER HEATER IS NOT TO BE INSTALLED DIRECTLY UNDER ELECTRICAL SERVICE AND METERING EQUIPMENT.
- F. UTILITY LOCATIONS AT PROPERTY LINE CONNECTION POINT MAY VARY.
- G. TRENCH DEPTH OR WIDTH MAY VARY ACCORDING TO WHAT UTILITIES ARE INSTALLED. CONTACT THE SDG&E PLANNER OR INSPECTOR FOR FURTHER INFORMATION.
- (H) THE MINIMUM DISTANCE BETWEEN THE GAS RISER AND THE BUILDING EXTERIOR IS 12 INCHES.(b)

BILL OF MATERIALS: NONE

NOTES:

I. FOR RELOCATIONS OR UPGRADES ON EXISTING INSTALLATIONS, CONTACT AN SDG&E PLANNER.

REFERENCE:

- a. SEE D7103.
- (b) FOR ADDITIONAL INFORMATION ON MINIMUM CLEARANCES FROM BUILDING WALLS AND CORNERS AND FOR GAS RISER TO WALL SPACING FOR LARGER METERS, SEE SG1009.


© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С	EDITORIAL CHANGES/FORMATTING	EDM	IWA	JTM	KRG	03/31/2025	F						
В	EDITORIAL CHANGES	1	IPJ	IPJ	CZH	10/15/2019	Е						
Α	EDITORIAL CHANGES	ı	LSM	BRB	TPM	08/16/2016	D						

SHEET 6 OF 6

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

UTILITY PLACEMENT IN JOINT TRENCH AND GAS METER SET ASSEMBLY INSTALLATION





REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 3 Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

METER CABINET FOR SINGLE RESIDENTIAL GAS METER

SG1008.2

INSTALLATION:

- A. OVERALL DIMENSIONS ARE 39 1/2" X 24". MAXIMUM DISTANCE BETWEEN BOTTOM OF CABINET AND MUDSILL IS 16 INCHES. ALLOW HOUSELINE STUB TO EXTEND 3 INCHES OUTSIDE OF STUCCO. CENTER OF SDG&E RISER SHOULD BE 4 1/2 INCHES FROM STUCCO. METER SIZES D 250 630 WILL FIT IN THE CABINET.
- B. THE CABINET IS DESIGNED TO FIT BETWEEN STUDS ON 16-INCH CENTERS. ADD A SECOND 2" X 4" ON EACH SIDE OF THE BAY TO SUPPORT THE FLANGE. CABINET BACK FITS FLUSH AGAINST INSIDE WALL.
- C. WALL AREA BEHIND METER CABINET MUST BE FREE OF ANY OBSTRUCTIONS SUCH AS WATER PIPES, SPIGOTS, CLEAN OUTS, DRAIN SPOUTS, ELECTRIC CONDUITS, ETC.
- D. MAINTAIN 3 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF GAS METER CABINET.
- E. NO BUILDING VENT, WINDOW, CATV, TELCO OR OTHER OPENINGS (COVERED OR UNCOVERED) ARE ALLOWED WITHIN 36 INCHES FROM SDG&E METER CABINET GAS RISER, AND 5 FEET FROM TOP OF METER CABINET. FIXED WINDOWS ARE ACCEPTABLE.
- F. THE HORIZONTAL DISTANCE BETWEEN THE ELECTRIC PANEL AND GAS RISER MUST BE A MINIMUM OF 36 INCHES.
- G. METER CABINET MUST BE A MINIMUM OF 6 INCHES FROM EDGE OF BUILDING.
- H. THE CABINET COVER MAY BE PAINTED TO MATCH THE BUILDING.

BILL OF MATERIALS: NONE

NOTES:

I. THE PREFABRICATED AMERICAN GAS PRODUCTS (AGP) ABS PLASTIC CABINET, PART NUMBER J-40 (WITH SOLID COVER), IS AN APPROVED CABINET. (b)

REFERENCE:

- a. SEE GAS D7103
- (b) FOR MORE INFORMATION, VISIT THE AMERICAN GAS PRODUCTS WEBSITE AT https://www.americangasproducts.com/, or contact american gas products (agp) inc., p.o. box 4777, anaheim, ca 92803, via phone at (714) 235-6007 or email at agp4777@gmail.com.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.														
REV	CHANGE	BY	DSN	APV	DATE	REV		CHANGE		DR	BY	DSN	APV	DATE	
С						F									
В	FORMATING	EDM	JIK	JTM	KRG	03/31/2025	Е								
Α	A EDITORIAL CHANGES		LSM	IPJ	TPM	11/01/2017	D								
	X Indicates La	atest R	evisio	n	Con	npletely Revi	ised		New Page In	formation Rer	noved				

SHEET 3 OF 3 SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SG1008.3

METER CABINET FOR SINGLE RESIDENTIAL GAS METER

SCOPE: THIS STANDARD PROVIDES SERVICE RISER AND HOUSELINE SPACING, CLEARANCES AND MINIMUM WORKING SPACE REQUIREMENTS FOR SINGLE AND MULTIPLE GAS METER INSTALLATIONS. (II)1'-0" MIN. HOUSELINE SDG&E RISER (II)1'-0" MIN. HOUSELINE MIN. SDG&E RISER (I)**CONFIGURATION 1 CONFIGURATION 2 OUTSIDE BUILDING CORNER** INSIDE BUILDING CORNER HOUSELINE (II)1'-0" MIN. MIN. HOUSELINE SDG&E RISER (II) 1'-0" MIN. 6" MIN. DG&E RISER **CONFIGURATION 4 CONFIGURATION 3** INSIDE BUILDING CORNER **OUTSIDE BUILDING CORNER** MINIMUM CLEARANCE FROM BUILDING WALLS AND CORNERS © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. REV DSN APV **CHANGE** DR BY DATE **REV CHANGE** DR DSN APV DATE BY С F EDM В TABLE UPDATE DR JTM KRG 03/31/2025 Ε Α **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 **Indicates Latest Revision** Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG1009.1 GAS SERVICE RISER & HOUSELINE SPACING,

CLEARANCES & MINIMUM WORKING SPACE

1 OF 3



DEFINITIONS:

- HIGH PRESSURE METERING: GAS PRESSURE ABOVE 7-INCH WATER COLUMN (WC) (1/4 PSIG).
- STANDARD PRESSURE METERING: GAS PRESSURE EQUAL TO 7-INCH WC (1/4 PSIG AT THE METER OUTLET).

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- $oxed{(I\)}$ 18 inches may be reduced if there is no tripping hazard due to the building configuration.
- ${
 m (II)}$ the SDG&E RISER FOR GROUPED METERS IS TO BE INSTALLED 18 INCHES OUT FROM BUILDING WALL. ${
 m (b)}$
- III. REFER TO TABLE 1 (SINGLE STANDARD (7" WC) PRESSURE METER OUTSIDE INSTALLATIONS) AND TABLE 2 (SINGLE HIGH PRESSURE (5 PSIG) METER OUTSIDE INSTALLATION) FOR DIMENSIONS AND SPACING REQUIREMENTS.
- IV. MINIMUM CLEAR AND LEVEL WORKING SPACE IS THE AREA DIRECTLY IN FRONT OF THE METER SET ASSEMBLY AND EXTENDS 6'-6" ABOVE GRADE. REFER TO TABLES 1 AND 2.
- V. THE DISTRIBUTION ENGINEERING AND GAS PLANNING SECTIONS OF GAS ENGINEERING MUST BE CONSULTED AT LEAST EIGHT (8) WEEKS PRIOR TO THE PROPOSED METER INSTALLATION DATE FOR THE FOLLOWING CASES:
 - a. ANY METER LARGER THAN AN 11M ROOTS METER.
 - b. ANY METER WITH A SERVING PRESSURE GREATER THAN 5 PSIG.
 - c. ALL PROPOSED VAULT AND CURB METER BOX INSTALLATIONS.
 - d. THE PROPOSED INSTALLATION OF A GAS HEADER OPERATING AT 5 PSIG.
 - e. THE PROPOSED USE OF A GAS METER ROOM.

© 1998 - 2025 San Diego Gas & Ele	ectric Company. Al	rights reserved	d. Removal of this co	pyright notice without permiss	on is not permi	tted under law	1.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 3

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS SERVICE RISER & HOUSELINE SPACING, CLEARANCES & MINIMUM WORKING SPACE

SG1009.2

TABLE 1

	SINGLE STANDARI) (7-INCH WATER CO	LUMN (WC))	PRESSURE MI	TER – OUTSI	DE INSTALLATION
METER CITE	METER SIZE RISER TO WALL (IN)	RISER TO HOUSELINE	INS	TALLATION S	PACE	MINIMUM CLEAR AND LEVEL WORKING SPACE –
METER SIZE	(IN)	(HORIZONTAL) (IN)	HEIGHT (IN)	WIDTH (IN)	DEPTH (IN)	78" HEIGHT X WIDTH X 36" DEEP (IN)
250- <mark>800</mark>	12	19		37	18	78 X 37 X 36
8C		30	42			
11C		30	42	57		78 X 57 X 36
15C		<mark>30</mark>			25	
2M175	14	<mark>48</mark>	48	77	25	78 X 77 X 36
3M175		40	40	//		76 X 77 X 36
5M175		75	54	95		78 X 95 X 36
7M175		75	34	95	30	76 × 95 × 36

TABLE 2

METER SIZE RISER TO WALL (IN)	RISER TO HOUSELINE	INS	TALLATION S	MINIMUM CLEAR AND LEVEL WORKING SPACE –		
METER SIZE	(IN)	(HORIZONTAL) (IN)	HEIGHT (IN)	WIDTH (IN)	DEPTH (IN)	78" HEIGHT X WIDTH X 36" DEEP (IN)
<mark>400</mark> -630	12	<mark>48</mark>	36	77	20	78 X 77 X 36
8C TQM					28	78 X 68 X 36
2M TQM		48	52	68		78 X <mark>68</mark> X 36
зм том	14				25	78 X 68 X 36
5M175		75		95		78 X 95 X 36
7M175		75	56	95	30	78 X 95 X 36
11M175	18	90		111	30	78 X 111 X 36
16M175	18	90	56	111	30	78 X 111 X 36

ATTENTION:

* FOR SERVING PRESSURES GREATER THAN 5 PSIG AND FOR 16M METERS, CONSULT WITH SDG&E PLANNER WHO WILL COORDINATE WITH SDG&E GAS DISTRIBUTION ENGINEERING.

REFERENCE:

- a. SEE GAS D9157.
- (b) SEE SG1010.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 3

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS SERVICE RISER & HOUSELINE SPACING, CLEARANCES & MINIMUM WORKING SPACE

SG1009.3




FIGURE 1
TYPICAL GROUPED GAS METERS (RESIDENTIAL)

TABLE 1

TYPICAL	RIGHT HAND HEADER FOR SIZE 250-400 GAS	S METERS
QUANTITY OF METERS	RISER TO 1 ST HOUSELINE SPACING (IN)	ADDITIONAL HOUSELINE SPACING (IN)
2-24	19	16
2-24 WITH 1 LARGE GAS METER IN 1 ST POSITION (11C MAX. SIZE)	27	16

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
A	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						_

SHEET 1 OF 9

Completely Revised Indicates Latest Revision New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS




FIGURE 2 DUAL TIER HEADER WITH LARGE METER (V)




FIGURE 3
DUAL TIER HEADER (V)

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.
--

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 2 OF 9

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS HOUSELINE SPACING FOR DUAL TIER LEFT HAND HEADERS




FIGURE 4SINGLE TIER HEADER FOR 4 WITH LARGE METER




FIGURE 5 SINGLE TIER HEADER

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 3 OF 9

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SG1010.3

GAS METERS GROUPED ON METER HEADERS HOUSELINE SPACING FOR SINGLE TIER LEFT HAND HEADERS




FIGURE 6
SINGLE TIER HEADER FOR 4 WITH LARGE METER




FIGURE 7
SINGLE TIER HEADER

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 4 OF 9 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS HOUSELINE SPACING FOR SINGLE TIER RIGHT HAND HEADERS




FIGURE 8
DUAL TIER HEADER WITH LARGE METER (V)




FIGURE 9 DUAL TIER HEADER V

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 5 OF 9

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS HOUSELINE SPACING FOR DUAL TIER RIGHT HAND HEADERS

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- I. METER HEADERS ARE LIMITED TO TWO TIERS TO ENSURE METER ACCESSIBILITY AND SAFETY OF PERSONNEL.
- II. WALL AREA FOR GAS METERS MUST BE ENTIRELY FREE OF ANY OBSTRUCTIONS SUCH AS WATER PIPES, FAUCETS, SEWER CLEANOUTS, DRAIN SPOUTS, ELECTRICAL CONDUITS, CABLE TV OR TELEPHONE EQUIPMENT.
- III. THE SDG&E SERVICE RISER IS TO BE INSTALLED 18 INCHES OUT FROM BUILDING WALL ON GROUPED METER LOCATIONS.
- IV. SEE SHEET 9 FOR ADEQUATE SUPPORT FOR WALL MOUNTED METER HEADERS.
- (V) use bottom row for odd houseline.

REFERENCE:

a. SEE GAS D9157.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 6 OF 9

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

SCOPE: THIS STANDARD DESCRIBES A CUSTOMER-BUILT HEADER SUPPORT.




FIGURE 1 TOP VIEW




FIGURE 1 ELEVATION VIEW




FIGURE 2 RISER PLACEMENT FOR LEFT HAND HEADER **TOP VIEW**

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 7 OF 9

Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS **CUSTOMER-BUILT HEADER SUPPORT**

INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) 60-INCH MAXIMUM TO CENTER OF EACH STANCHION.
- (II) 2" X 6" TREATED DOUGLAS FIR BACKING FOR HEADER. SEE TABLE 1 FOR SIZING.
- $\left(\mathrm{III} \right) \,$ 2 1/2-INCH STEEL PIPE (MINIMUM) SET IN CONCRETE.
- (IV) MINIMUM ATTACHMENT IS TWO 3/8-INCH THROUGH BOLTS PER STANCHION.

REFERENCE:

a. SEE GAS D7107.

TABLE 1

1775-1											
			CUST	OMER-B LI	UILT HE ENGTH (IPPORT				
NUMBER OF METERS	2	3	4	5	6	7	8	9	10	11	12
RIGHT HAND HEADER	57	73	89	105	121	137	153	169	185	201	217
LEFT HAND HEADER	53	69	85	101	117	133	149	165	181	197	213

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						

SHEET 8 OF 9

Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS CUSTOMER-BUILT HEADER SUPPORT

SCOPE: THE PURPOSE OF THIS STANDARD IS TO SPECIFY REQUIREMENTS WHICH CUSTOMERS/BUILDERS MUST MEET TO PROVIDE ADEQUATE SUPPORT FOR WALL-MOUNTED METER HEADERS.



INSTALLATION:

- A. WHEN A HEADER IS REQUIRED TO SERVE A NEWLY CONSTRUCTED STRUCTURE, IT IS THE CUSTOMER'S/BUILDER'S RESPONSIBILITY TO PROVIDE ADEQUATE BACKING FOR THE HEADER ATTACHMENT.
- B. THE MOUNTING WALL MUST MEET ONE OF THE FOLLOWING REQUIREMENTS:
 - 1. VOID-FILLED CONCRETE BLOCK
 - 2. SOLID CONCRETE (3 1/2-INCH MINIMUM THICKNESS)
 - $(\,3\,)$ 2" X 12" LUMBER BLOCKING INSTALLED BETWEEN STUDS ALONG HEADER WALL AND 2-INCHES ABOVE ALL HOUSELINES
- C. MOUNTING WALL MUST BE FREE FROM ANY OBSTRUCTIONS FOR MOUNTING THE HEADER SUCH AS WATER PIPES, WATER SPIGOTS, CLEAN OUTS, DRAIN SPOUTS, ELECTRIC CONDUITS, DECORATIVE WALL FINISHES WITH IRREGULAR SURFACES, ETC.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

a. SEE GAS D9157.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	NEW PAGE	-	LSM	BRB	TPM	11/01/2017	D						


SHEET 9 OF 9


Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS METERS GROUPED ON METER HEADERS
ADEQUATE SUPPORT FOR WALL MOUNTED METER HEADERS

SCOPE: THIS STANDARD PROVIDES THE REQUIREMENTS FOR METER LOCATIONS BEHIND WING WALLS.





INSTALLATION: NONE

BILL OF MATERIALS: NONE

NOTES:

- (I) NO DOOR OR ROOF ALLOWED
- $\overline{\mathrm{(II)}}$ when possible, wing wall height should not exceed 5 feet.
- $ar{ ext{(III)}}$ length and width of meter location are determined by size and number of meters to be installed.

REFERENCE:

- (a) FOR RISER AND HOUSELINE POSITIONS, SEE SG1012.
- b. SEE GAS D7103.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 1 Indicates Latest Revision Completely Revised New Page Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS SERVICE AND METER BEHIND WING WALLS

SG1011.1

Z(IN)

48

METER SIZE


250-275

415 AND LARGER

SCOPE: THIS STANDARD DESCRIBES BUILDING RECESS FOR GAS SERVICE AND METERS.

ATTENTION:

* FOR DIMENSION REQUIREMENTS OF METER RECESSES REFER TO SHEETS 2-4.






FIGURE 2
TYPICAL RIGHT HAND HEADER

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

C F			
B TABLE UPDATE EDM DR JTM KRG 03/31/2025 E			
A EDITORIAL CHANGES - LSM IPJ TPM 11/01/2017 D			

SHEET 1 OF 4

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

BUILDING RECESS FOR GAS SERVICE & METERS
GAS METER RECESS DIMENSIONS, RISER & HOUSELINE SPACING
FOR TYPICAL HEADER INSTALLATIONS

SG1012.1




FIGURE 3
TYPICAL LEFT HAND HEADER

TABLE 1

SING		ESS DIMENSIONS, RI PRESSURE - 7-INCH			G
	RISER TO	RISER TO	RECESS D	IMENSIONS ((FIGURE 1)
METER SIZE	BACK WALL (IN)	HOUSELINE (IN)	HEIGHT (IN)	WIDTH (IN)	DEPTH (IN)
250-630	12	19		37	18
8C		30	42		
11C		30	42	57	
15C		<mark>30</mark>			25
2M	14	48	40	77	25
3M		48	48	77	
5M		75	F4	0.5	
7M		75	54	95	30

TABLE 2

SING		ESS DIMENSIONS, RI HIGH PRESSURE – 5		LINE SPACIN	G
	RISER TO	RISER TO	RECESS D	IMENSIONS ((FIGURE 1)
METER SIZE	BACK WALL (IN)	HOUSELINE (IN)	HEIGHT (IN)	WIDTH (IN)	DEPTH (IN)
<mark>400</mark> -630	12	<mark>48</mark>	36	77	<mark>28</mark>
8C					
2M		48	52	68	<mark>25</mark>
3M	14				25
5M		75		O.F.	
7M		75	56	95	20
11M	18	90		111	30

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	TABLE UPDATE	EDM	DR	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 4

Indicates Latest Revision | Completely Revised | New Page | X | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

BUILDING RECESS FOR GAS SERVICE & METERS GAS METER RECESS DIMENSIONS, RISER & HOUSELINE SPACING FOR TYPICAL HEADER INSTALLATIONS

SG1012.2

INSTALLATION:

- A. <u>BUILDING RECESS</u>" IS AN INDENTATION OF BUILDING WALL, FOUNDATION AND FLOOR. A RECESS IS OPEN ON THE FRONT SO THAT THE METER SET ASSEMBLY IS VISIBLE. NO DOORS, LATTICE WORK, OR COVERS OF ANY TYPE ARE PERMITTED. THE BUILDING FOUNDATION MUST NOT CROSS ANY PORTION OF THE RECESS.
- B. ONLY GAS-RELATED FACILITIES WILL BE PERMITTED IN THE RECESS. FOREIGN EQUIPMENT (E.G. GROUND RODS, WIRES, CONDUIT, ELECTRIC EQUIPMENT, CATV AND TELCO PANELS, SPRINKLER CONTROLS, WATER AND WASTE PIPING, BUILDING WINDOWS, VENTS, ETC.) IS PROHIBITED. ELECTRIC BONDING TO OR USE OF SDG&E GAS SERVICE PIPING, GAS RISERS OR METER FACILITIES FOR ELECTRIC GROUNDING IS NOT PERMITTED. GAS RECESSES ARE NOT TO BE USED FOR STORAGE AREAS.
- C. THE INTERIOR OF THE GAS METER RECESS MUST BE GAS TIGHT. THE RECESS SHALL BE SEALED BY THE CUSTOMER AT ALL INTERIOR SEAMS, CORNERS, OPENINGS, ETC., TO PREVENT GAS FROM MIGRATING INTO ANY PORTION OF THE BUILDING OR STRUCTURE. THE INTERIOR OF THE RECESS SHALL BE THE SAME MATERIAL USED ON THE BUILDING EXTERIOR PROVIDED IT IS GAS TIGHT. ACCEPTABLE SEALING MATERIALS INCLUDE SILICONE-BASED AND POLYURETHANE-BASED COMPOUNDS (E.G. TRADE NAMES GE SILICONE, SIKAFLEX 1A OR EQUIVALENTS). REQUESTS FOR OTHER MATERIALS FOR RECESS INTERIOR MAY BE APPROVED UPON PRIOR REVIEW BY SDG&E.
- D THE ENTIRE OPENING OF THE RECESS MUST BE CLEAR FOR INSTALLATION AND MAINTENANCE OF THE METER SET ASSEMBLY. A MINIMUM 3-FOOT CLEAR AND LEVEL WORKING SPACE MUST BE MAINTAINED IN FRONT OF THE RECESS OPENING. THE HEIGHT OF THE WORKING SPACE EXTENDS 6'-6" MINIMUM ABOVE FINAL GRADE. THE WALL AREA ABOVE THE RECESS MUST BE FREE OF PROJECTIONS THAT PRESENT A HAZARD TO PERSONNEL SERVICING THE METER SET ASSEMBLY.
- E. ELECTRIC METERING IS NOT PERMITTED ABOVE A GAS RECESS.
- F. THE WALLS AND CEILING OF THE RECESS MUST BE FLUSH WITH THE EXTERIOR WALLS. RETURNS OR JAMS ON THE SIDE WALLS OR CEILING ARE PROHIBITED. THE CEILING MUST BE LEVEL OR SLOPE UPWARDS FROM BACK TO FRONT WITH A 1-INCH RISE PER 12-INCH DEPTH.
- G. THE DEPTH OF THE RECESS MUST NOT EXCEED THE DEPTH LISTED FOR THE PARTICULAR METER SIZE FOR WHICH THE RECESS WAS DESIGNED TO ACCOMMODATE. WHEN A RECESS IS USED ON A NON-RESIDENTIAL STRUCTURE AND THE GAS LOAD IS UNKNOWN, THE MINIMUM INTERIOR HEIGHT OF THE RECESS SHALL BE 66 INCHES AND THE INSIDE DEPTH MUST NOT EXCEED 30 INCHES.
- H. THE BOTTOM OR FLOOR OF THE RECESS MAY BE DIRT OR PAVED, AND IT MUST BE GRADED TO PREVENT WATER FROM COLLECTING INSIDE THE RECESS. DURING TIME OF CONSTRUCTION, IF THE RECESS FLOOR IS TO BE PAVED, AN OPENING 4-INCH IN DIAMETER OR 4-INCH SQUARE MUST BE PROVIDED AROUND THE SDG&E RISER.
- J. FOR A RECESS HOUSING A SINGLE METER, THE SDG&E RISER SHALL BE 12 INCHES FROM THE LEFT SIDE WALL. FOR THE RISER TO BACK WALL DIMENSION, REFER TO TABLE 1 AND TABLE 2. THE CUSTOMER HOUSELINE SHALL NOT BE CLOSER THAN 6 INCHES TO THE RIGHT SIDE WALL.
- K. FOR METER SIZES UP TO AND INCLUDING 11C, HOUSELINE(S) MUST BE 18 INCHES ABOVE FINAL GRADE. THE HOUSELINES FOR THE UPPER LEVEL OF A TIER HEADER MUST BE 40 INCHES ABOVE THE FINAL GRADE (22 INCHES ABOVE LOWER LEVEL HOUSELINES).
- L. FOR SERVING PRESSURES GREATER THAN 5 PSIG AND FOR 16M METERS, THE PROJECT PLANNER WILL CONSULT WITH GAS DISTRIBUTION ENGINEERING.

BILL OF MATERIALS: NONE

NOTES:

ADDITIONAL REQUIREMENTS FOR MULTIPLE METERS

- I. METER HEADERS MUST BE LIMITED TO TWO TIERS TO ENSURE METER ACCESSIBILITY AND SAFETY OF PERSONNEL.
- II. SDG&E RISER PLACEMENT FOR ALL HEADERS TO BE 12 INCHES FROM BACK WALL AND 18 INCHES FROM SIDEWALL.
- III. DEPTH OF MULTIPLE METER RECESS FOR 250-400 METERS IS 18 INCHES MAXIMUM; FOR 675-11C METERS 28 INCHES MAXIMUM.
- $({
 m IV})$ height of recess for single level header is 48 inches minimum above final grade.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** DR BY DSN APV DATE REV DR BY DSN APV DATE **CHANGE CHANGE** С F В TABLE UPDATE **EDM** DR JTM KRG 03/31/2025 Ε **EDITORIAL CHANGES** LSM IPJ TPM 11/01/2017 Α Completely Revised **Indicates Latest Revision** New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES


SHEET 3 OF 4

BUILDING RECESS FOR GAS SERVICE & METERS
GAS METER RECESS DIMENSIONS, RISER & HOUSELINE SPACING
FOR TYPICAL HEADER INSTALLATIONS

SG1012.3

(V) HEIGHT OF RECESS FOR TWO TIER HEADER IS 66 INCHES MINIMUM ABOVE FINAL GRADE. (VI) WIDTH OF RECESS FOR RIGHT HAND HEADERS. SINGLE AND DUAL TIER - 18-INCH RISER TO LEFT SIDEWALL, 19-INCH RISER TO FIRST HOUSELINE, 6-INCH LAST HOUSELINE TO RIGHT SIDE WALL, PLUS 16 INCHES FOR EACH ADDITIONAL HOUSELINE (250-400 METERS). $(extsf{VII})$ WIDTH OF RECESS FOR LEFT HAND HEADERS. SINGLE AND DUAL TIER – 18-INCH RISER TO RIGHT SIDEWALL, 6-INCH RISER TO FIRST HOUSELINE, 24-INCH LAST HOUSELINE TO LEFT SIDE WALL, PLUS 16 INCHES FOR EACH ADDITIONAL HOUSELINE (250-400 METERS). **REFERENCE:** a. FOR HOUSELINE SPACING NOT GIVEN IN THIS STANDARD, SEE SG1010. b. SEE GAS D9157. © 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law. **REV** BY DSN APV **REV** DSN APV DATE **CHANGE** DR DATE **CHANGE** DR BY С F В TABLE UPDATE **EDM** DR JTM KRG 03/31/2025 Ε LSM TPM 11/01/2017 Α **EDITORIAL CHANGES** IPJ Completely Revised New Page Information Removed **Indicates Latest Revision** SDG&E ELECTRIC SERVICE STANDARDS & GUIDES SHEET SG1012.4 BUILDING RECESS FOR GAS SERVICE & METERS 4 OF 4 GAS METER RECESS DIMENSIONS, RISER & HOUSELINE SPACING FOR TYPICAL HEADER INSTALLATIONS

SCOPE: THIS STANDARD DESCRIBES MOBILE HOME GAS METER REQUIREMENTS.



INSTALLATION:

- A 18 INCHES MINIMUM HORIZONTAL CLEARANCE SHALL BE MAINTAINED ON ALL SIDES OF THE GAS METER, EXCLUDING THE GAS SERVICE RISER AND HOUSELINE.
- (B) IF AREA AROUND GAS RISER IS TO BE PAVED, A 4-INCH MINIMUM DIAMETER OR 4-INCH MINIMUM SQUARE OPENING MUST BE PROVIDED AROUND THE RISER.
- (C) METER AND METERING EQUIPMENT MAY BE INSTALLED IN THE FOLLOWING LOCATIONS:
 - 1. AT OR NEAR THE MOBILE HOME CLOSEST SDG&E'S (UTILITY) SOURCE
 - 2. ON A PERMANENTLY INSTALLED STRUCTURE NEAR THE FRONT LOT LINE OF THE MOBILE HOME
 - 3. AT OR NEAR THE CORNER OF THE MOBILE HOME LOT CLOSEST TO THE UTILITY'S SOURCE
- D THE GAS METER SET SHALL NOT DEPEND ON A FLEX GAS HOUSELINE FOR SUPPORT. A POST, BRACKET OR OTHER MEANS OF SUPPORT IS TO BE PROVIDED BY THE CUSTOMER WHEN REQUIRED BY THE GOVERNMENTAL AUTHORITY HAVING JURISDICTION (AHJ) OR THE UTILITY.
- (E) MINIMUM CLEARANCE AROUND RISER
- (F) MINIMUM CLEARANCE AROUND SUPPORT
- (G) 1-INCH GALVANIZED PIPE TOP WITH 1-INCH GALVANIZED TEE OR EQUIVALENT

BILL OF MATERIALS: NONE

NOTES: NONE REFERENCE:

a. SEE GAS D7103.4.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 1 OF 1

Indicates Latest Revision		Completely Revised		New Page		Information Removed
SDG&	FF	FCTRIC SERVICE ST	ΔΝΓ	VABUS & CI	IID	FS

SG1013.1

MOBILE HOME METER PAD




TABLE 1

	BARRICADE PARTS LIST, NOTES, AND SIZING REQUIREMENTS										
ITEM	DESCRIPTION	LIGHT/HEAVY DUTY	PIPE SIZE (IN)	MIN. WALL THICKNESS (IN)	DIAMETER (IN)	DEPTH (IN)	PIPE LENGTH (IN)				
1	BARRICADE, STEEL POST, BLACK OR GALV.	LIGHT HEAVY	3 4	0.216 0.237	-	-	<mark>66</mark> 84				
2	FOOTING, CONCRETE	LIGHT HEAVY	-	-	12 15	36 42	<u>-</u> -				
3	BRACE, PIPE, HORIZONTAL G	LIGHT HEAVY	2 4	0.154 0.237	-	-					
4	PLATE, STEEL, BLACK OR GALV., 12" X 12" X 1/4" MIN.	-	-	-	-	-	-				
5	WELD, FILLET, 1/4"	-	-	-	-	-	-				
6	BOLT (4 EA), CADMIUM COATED STEEL, 4" X 5/8"	-	-	-	-	-	-				
7	WASHER (4 EA), FLAT, CADMIUM COATED STEEL, 5/8"	-	-	-	-	-	-				

DEFINITIONS (GUIDELINE KEY):

- METER SET ASSEMBLY (MSA): A METER, SERVICE REGULATOR(S), AND ALL APPURTENANCES NECESSARY TO MAKE METER
 CONNECTIONS BETWEEN A RISER AND CUSTOMER HOUSELINE
- RESIDENTIAL PREMISES: ANY SINGLE-FAMILY RESIDENCE, MOBILE HOME PARK OR DUPLEX
- NON-RESIDENTIAL PREMISES: ANY COMMERCIAL, INDUSTRIAL, GOVERNMENT BUILDINGS, CHURCHES, HOSPITALS, SCHOOLS,
 PLACES OF PUBLIC GATHERING, OR MULTI-UNIT RESIDENTIAL HOUSING WITH MORE THAN TWO UNITS
- LOW SPEED AREAS: AREAS SUCH AS ALLEY WAYS, DRIVEWAYS AND PARKING AREAS WHERE VEHICLES SHOULD NOT BE MOVING AT HIGH SPEEDS
- TRAFFIC SPEED AREAS: ANY AREA OR ROADWAY WHERE VEHICLES TRAVEL AT SPEEDS HIGHER THAN 15 MILES PER HOUR

INSTALLATION:

A. METERS LOCATED ON A WALL ADJACENT TO ANY PARKING AREA, OR AREA ACCESSIBLE TO VEHICULAR TRAFFIC, MUST BE PROTECTED BY NON-REMOVABLE BARRICADE POSTS. WHEEL STOPS AND REMOVABLE BARRICADE POSTS ARE NOT ACCEPTABLE SUBSTITUTES. MAINTAIN A MINIMUM OF 3 FEET CLEAR AND LEVEL WORKING SPACE IN FRONT OF THE GAS METER SET ASSEMBLY. SDG&E'S INSPECTOR WILL DETERMINE IF A BARRICADE CAN BE OMITTED WHEN EXISTING STRUCTURES CAN PROTECT PERSONNEL AND EQUIPMENT. METERS WILL NOT BE SET UNTIL THE BARRICADES ARE INSTALLED.

BARRIER POST PROTECTION FOR SERVICE EQUIPMENT GUIDELINE (REFER TO DEFINITIONS (GUIDELINE KEY):

THE SDG&E PROJECT PLANNER WILL EVALUATE THE GAS MSA LOCATION TO DETERMINE IF THERE IS A RISK OF DAMAGE BY MOVING VEHICLES OR EQUIPMENT. BARRIER POSTS WILL BE REQUIRED WHEN A RESIDENTIAL MSA LOCATION IS WITHIN 3 FEET OF LOW SPEED AREAS, A NON-RESIDENTIAL MSA LOCATION IS WITHIN 10 FEET OF LOW SPEED AREAS, OR A NON-RESIDENTIAL MSA LOCATION IS WITHIN CLOSE PROXIMITY OF TRAFFIC SPEED AREAS AS FOLLOWS:

- 1. THE MSA IS WITHIN 20 FEET OF EDGE OF PAVEMENT OR CURB FACE OF ANY LOCAL ROADWAY (RESIDENTIAL STREET), OR
- 2. THE MSA IS WITHIN 40 FEET OF EDGE OF PAVEMENT OR CURB FACE OF ANY ROADWAY OTHER THAN A LOCAL ROADWAY.

LIGHT DUTY BARRIER POSTS - ARE DESIGNED TO PROTECT A GAS METER SET ASSEMBLY THAT IS EXPOSED TO POTENTIAL DAMAGE ADJACENT TO PRIVATE DRIVES, PASSENGER CAR PARKING, ETC.

HEAVY DUTY BARRIER POSTS - ARE DESIGNED TO PROTECT A GAS METER SET ASSEMBLY THAT IS EXPOSED TO POTENTIAL DAMAGE ADJACENT TO HEAVY COMMERCIAL/INDUSTRIAL VEHICULAR TRAFFIC AND THAT EXCEEDS WHAT IS COVERED BY THE LIGHT DUTY BARRIER POST.

	© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.												
REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING/DRAWING UPDATE	EDM	IWA	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

Completely Revised

SHEET 2 OF 3

Indicates Latest Revision

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

New Page X

Information Removed

BARRICADES FOR GAS METER SETS

SG1014.2

INSTALLATION (CONT'D):

- (B) barricade height shall extend 3 inches above the meter set assembly $rac{f with a minimum height of 3 feet above the <math>f v}$ FINAL GRADE FOR LIGHT DUTY POSTS OR 4 FEET ABOVE FINAL GRADE FOR HEAVY DUTY POSTS.
- $(\,{\sf C}\,)$ for New Meter installations, the barricade post separation shall not exceed 4 feet.
- (D) for New Meter installations, the barricade posts must be a minimum of 3 feet from the face of the meter set.
- (E) all barricade post tops at the same site shall be finished in the same manner using one of the following three **METHODS:**
 - 1. TACK WELDED STEEL CAP OR BLANK
 - 2. LIGHT DUTY AND HEAVY DUTY BARRIER POSTS SHALL BE CONCRETE FILLED, AND MAY BE CROWNED WITH CONCRETE IF A STEEL CAP OR BLANK IS NOT INSTALLED.
 - 3. POST TOP MAY BE THREADED AND FINISHED WITH A MALLEABLE IRON CAP.
- (F) WELDED AND BLACK IRON AREAS OF THE COMPLETED BARRICADE POST(S) SHALL BE PRIMED AND PAINTED WHITE.
- (G) WHEN A STRONGER BARRICADE IS NEEDED, HORIZONTAL BRACES ARE TO BE INSTALLED AS FOLLOWS:
 - 1. BOTTOM HORIZONTAL BRACE 18 INCHES ABOVE FINAL GRADE
 - 2. TOP HORIZONTAL BRACE NO MORE THAN 1/2-INCH BELOW TOP OF POST
 - 3. IF THE BARRICADE POSTS ARE TOPPED WITH THREADED IRON CAPS, THE TOP HORIZONTAL BRACE SHALL BE NO MORE THAN 1/2-INCH BELOW BOTTOM OF CAP.
- $(\,\mathsf{H}\,)$ post shall extend 3 inches above the meter set assembly or 45 inches above final grade, whichever is less.
- (J)THE POST SHALL BE <mark>CONCRETE FILLED AND TOPPED OFF</mark> WITH ONE OF THE FOLLOWING:
 - 1. TACK WELDED STEEL CAP OR BLANK
 - 2. FORMING THE CONCRETE FILL INTO A CROWN TOP
 - 3. POST TOP MAY BE THREADED AND FINISHED WITH AN IRON CAP
- $^{'}$ K $^{'}$ WELDED AND BLACK IRON AREAS OF THE COMPLETED BARRICADE POST SHALL BE PRIMED AND PAINTED WHITE.
- \langle L angle all precautions must be taken to protect workers and passerby from resulting fumes if choosing to weld on GALVANIZED METAL.

BILL OF MATERIALS: NONE

NOTES:


- I. BARRICADE POSTS ARE USED TO PROTECT METER AND SERVICE EQUIPMENT AND PERSONNEL FROM VEHICULAR CONTACT AND TO PROHIBIT ENCROACHMENT INTO THE WORKING SPACE, FOR EXAMPLE: LOADING ZONES, DRIVEWAYS, CONGESTED AREAS, ALLEYS, OFF STREET PARKING SUCH AS SIDE YARDS, ETC.
- ${
 m (II)}$ light duty bolt-down barricade posts shall be used only for existing residential and mobile home park meter ${
 m (II)}$ SETS. BOLT-DOWN BARRICADES ARE ALLOWED TO PROTECT AN EXISTING SINGLE METER OR HEADERS FOR TWO METERS ONLY. BOLT-DOWN BARRICADES SHALL BE INSTALLED ONLY ON GOOD CONCRETE AND WHERE THERE IS POTENTIAL DANGER OF DAMAGING UNDERGROUND FACILITIES WHEN EXCAVATING, OR WHEN THE CUSTOMER DOES NOT WANT THEIR PAVING DISTURBED.
- (III) HILTI "KWIK BOLT" OR EQUIVALENT

REFERENCE:

a. SEE SDG&E GAS DISTRIBUTION STANDARD D7115.

REV	CHAN	GE	DR	BY	DSN	APV	DATE	REV		CI	HAN	IGE	DR	BY	DSN	APV	DATE
С								F									
В	FORMATTING/DRA	WING UPDATE	EDM	IWA	JTM	KRG	03/31/2025	Е									
Α	EDITORIAL C	CHANGES	-	LSM	IPJ	TPM	11/01/2017	D									
•		X Indicates Latest Revision Completely Revised New Page Information Removed															
	SHEET	SDG&E ELECTRIC SERVICE STANDARDS & GUIDES															
											SG1014.3						
3 OF 3 BARRICADES FOR GAS METER SETS										٥.	J101	1.5					

BARRICADES FOR GAS METER SETS






FIGURE 3

3313 INSTALLATION 200A, 6.9KV 1-PHASE (E)(F)

SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 2 OF 8

Indicates Latest Revision Completely Revised New Page Information Removed SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES





FIGURE 4 3512 INSTALLATION 1-PHASE FUSED SWITCHING CABINET SEE TABLE 1

FIGURE 5 3522 INSTALLATION 3-PHASE CABLE TERMINATOR SEE TABLE 1

FIGURE 6
3414 INSTALLATION
CAPACITOR ROD
SEE TABLE 1



© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 3 OF 8

Indicates Latest Revision Completely Revised New Page Information Removed


SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES



SHEET 4 OF 8

GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES







FIGURE 13
3426 INSTALLATION – 3314 SECTIONS
3-PHASE TRANSFORMER
SEE TABLE 1



SEE TABLE 1




FIGURE 15
3427 INSTALLATION – 3314 SECTIONS
3-PHASE TRANSFORMER
SEE TABLE 1

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.


REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CH	IANGE	DR	BY	DSN	APV	DATE
С							F							
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е							
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D							


SHEET 5 OF 8

Indicates Latest Revision | Completely Revised | New Page | Information Removed

SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES








FIGURE 23
TELEPHONE FEEDER DISTRIBUTION
CABINET, TYPE 40 C OR D
SEE TABLE 1

TA	BL	<u>.E</u>	1	

	FIGURE ITEMS
ITEM	DESCRIPTION
1	MAIN, GAS
2	WALL, RETAINING
3	SERVICE, GAS
4	FOOTING
(5)	SECONDARY AND/OR SERVICE, ELECTRIC
6	TELCO, TV
7	WIRE, GROUND
8	PRIMARY, ELECTRIC
9	SIDEWALK
(10)	CURB
(11)	PEDESTAL, TELEPHONE
(12)	PEDESTAL, CABLE TV, TYPICAL

INSTALLATION:

- (A) POSITIONS OF PRIMARY AND SECONDARY CONDUITS ENTERING AND LEAVING PADMOUNTED EQUIPMENT DEPEND ON TYPE OF EQUIPMENT, SUCH AS SINGLE- OR THREE-PHASE TRANSFORMERS.
- (B) MAINTAIN 12 INCHES MINIMUM HORIZONTAL SEPARATION FROM EDGE OF PAD, HANDHOLES, VAULTS, ETC., TO GAS MAIN/SERVICE TO PREVENT DAMAGE FROM DRIVEN GROUND RODS AND PROVIDE ACCESS TO MAIN/SERVICE IN THE FUTURE.
- © IF RETAINING WALL IS TO BE INSTALLED, MAINTAIN 12 INCHES HORIZONTAL SEPARATION FROM FOOTING. FOOTING WIDTH IN FIGURE 1 IS BASED ON 4-FOOT WALL HEIGHT WITH 3 TO 1 SLOPE.
- (D) GAS PIPE MUST NOT BE LOCATED UNDER ANY FACILITY SUCH AS SPLICE BOXES, EQUIPMENT PADS, FOOTINGS, ETC.
- E MINIMUM DIMENSIONS ARE SHOWN TO OBTAIN 12-INCH HORIZONTAL SEPARATION FROM GAS PIPE TO SUBSTRUCTURE OR EQUIPMENT PAD.
- (F) ADD 12 INCHES TO DIMENSIONS SHOWN IF CABLE TV, TELEPHONE AND ELECTRIC CONDUITS ARE BEING INSTALLED NEXT TO SUBSTRUCTURES OR EQUIPMENT PADS IN JOINT TRENCH WITH GAS.

BILL OF MATERIALS: NONE

NOTES: NONE

REFERENCE:

a. SEE GAS D7417.

© 1998 - 2025 San Diego Gas & Electric Company. All rights reserved. Removal of this copyright notice without permission is not permitted under law.

REV	CHANGE	DR	BY	DSN	APV	DATE	REV	CHANGE	DR	BY	DSN	APV	DATE
С							F						
В	FORMATTING	EDM	JIK	JTM	KRG	03/31/2025	Е						
Α	EDITORIAL CHANGES	-	LSM	IPJ	TPM	11/01/2017	D						

SHEET 8 OF 8 Indicates Latest Revision | Completely Revised | New Page | Information Removed | SDG&E ELECTRIC SERVICE STANDARDS & GUIDES

GAS FACILITIES NEAR UNDERGROUND PADMOUNTED EQUIPMENT OR SUBSTRUCTURES

+©

52

+©

52



San Diego Area Chapter International Code Council

Carlsbad, Chula Vista, Coronado, Del Mar, El Cajon, El Centro, Encinitas, Escondido, Imperial Beach, La Mesa, Lemon Grove, National City, Oceanside, Poway, San Diego City, San Diego County, San Marcos, Santee, Solana Beach, Vista

San Diego Area

Electrical Newsletters

January 2023
Based on the
2022 edition of
the California Electrical Code
(2020 National Electrical Code)

About the San Diego Area Electrical Newsletters

The San Diego Area Electrical Newsletters are developed through a cooperative effort of the San Diego Area Inspection Jurisdictions and are approved by the San Diego Area Chapter of the International Code Council.

The newsletters provide the local jurisdictions a resource for interpretation and enforcement of the 2022 California Electrical Code (CEC) based on the 2020 edition of the National Electrical Code (NEC) in compliance with Article 90.4 that reads in part: "The authority having jurisdiction (AHJ) for enforcement of the Code has the responsibility for making interpretations of the rules, for deciding on the approval of equipment and materials, and for granting the special permission contemplated in a number of the rules."

Examples of specific installations that are generally acceptable in the San Diego Area are included. Check with the local inspection jurisdiction before beginning any installation based on these newsletters.

The 2023 Service Standards & Guide manual published by San Diego Gas & Electric Company (Utility) is referenced to provide the Utility's electrical serving requirements as a courtesy to the electrical industry. These references are shown in boxed text.

Additional California code requirements are found in the following:

- California Green Code
- The California Energy Codes

Participating San Diego Area Inspection Jurisdictions

City of Carlsbad City of Lemon Grove City of Chula Vista City of National City City of Coronado City of Oceanside City of Del Mar City of Poway City of El Caion City of San Diego City of El Centro City of San Marcos City of Encinitas City of Santee City of Escondido City of Solana Beach

City of Imperial Beach City of Vista

City of La Mesa County of San Diego

Boxed language refers to the Utility.

San Diego Area Chapter International Code Council

Table of Contents

Code Reference	Subject	Page #
90.7, 110	Approval of Electrical Equipment	1
110.3(B),110.14(A)&(D)	Torque Requirements	2
110.26	Electrical Equipment Rooms	3
110.26(A)&(E)	Dedicated Equipment Space-Outdoor	4
200.6, 210.5(C), 215.12	Identifying Conductors	5
210.52(E)	Unconditioned Enclosed Patio	6
220	Electrical Service Plan Check Requirements	7
230.2	Number of Services	8
230.70	Service Equipment – Disconnecting Means	12
230.95	Ground-Fault Performance Testing	13
250 Part III	Grounding Electrode System & Grounding Electrode Conduc	tor15
250.52(A)(3)	Concrete-Encased Electrode (Rebar)	16
250.52(A)(5)	Ground Rods	17
342, 344, 358	Underground Metal Conduit	18
368	Busways	19
408	Switchboards & Panelboards	20
445	Generators	21
450	Transformers	23
490	Examination of Electrical Equipment Exceeding 1,000 Volts	24
625	Electric Vehicle Charging Systems (EVCS)	26
625.48	Electric Vehicle Supply Equipment (EVSE)	27
690	Solar Photovoltaic Systems	28
705.10	Alternate Sources of Power	31
Index		32

Approval of Electrical Equipment

Code Reference: 2022 California Electrical Code Article 90.7, 110

Published: January 2008 Revised: January 2020

The authority having jurisdiction (AHJ) has the responsibility for making interpretations of the requirements of the California Electrical Code. It is the intent of this newsletter to address the locally accepted requirements for the listing and labeling of electrical equipment.

Listing and labeling provides prima facie evidence that the electrical equipment is approvable by the jurisdiction. Equipment shall be listed and labeled by a Nationally Recognized Testing Laboratory (NRTL) that is recognized by the Federal Occupational Safety and Health Administration (OSHA), Department of Labor under 29 CFR 1910.7 for electrical equipment. https://www.osha.gov/dts/otpca/nrtl/

Equipment shall be installed per the manufacturer's installation instructions. Switchgear shall be installed per NEMA (National Electrical Manufacturer's Association) Standards. The equipment shall be approved by the jurisdiction for the location of the installation.

Electrical equipment installed without the required label is then required to be evaluated and labeled per this newsletter and per NFPA 790 and 791.

The AHJ may request an evaluation by an approved evaluator for equipment that does not have an acceptable testing agency label.

The following procedure is requested to be followed when a field evaluation is to be done:

- 1. Field evaluator shall notify the AHJ that they have been contracted to examine equipment.
- 2. Initial letter shall include the name of the tenant/owner, the address of the location of the equipment, the type of equipment, and the standards to which the equipment will be evaluated. The letter should also indicate if a preliminary evaluation was undertaken and the results of that preliminary evaluation.
- 3. Upon completion of the evaluation, the evaluator shall notify the AHJ in writing of the results of test, provide a copy of the report, and identify that their evaluation approval label has been affixed to the equipment.

It shall be understood that a completed Field Evaluation report and affixed label to any piece of equipment may only be considered approved for that exact location/environment where it was evaluated. Henceforth, if the piece of equipment is moved to another location, then an additional Field Evaluation shall be required.

Torque Requirements

Code Reference: 2022 California Electrical Code Article 110.3 (B) and 110.14 (A) & (D)
Published: October 1987

Revised: January 2020

Standards such as NEMA, ASTM, ANSI, and UL require all terminals and lugs to pass stringent tests as a part of the listing process. The listings for terminals and lugs include specific torquing requirements—All manufacturers are required to identify appropriate torque numeric values for each type of termination as part of their installation instructions. Calibrated torque tools shall be used to achieve the indicated torque. The contractor is responsible to ensure that all terminations are properly torqued.

The local authority having jurisdiction (AHJ) has established the following inspection requirements:

- 1. The AHJ may require that torquing tools and manufacturer's torquing instructions be on the job site at the time of inspection; or
- 2. The AHJ may accept a letter from the contractor certifying that all terminations have been torqued in accordance with the manufacturer's instructions; or
- 3. The AHJ may require that the contractor obtain an approved third-party testing agency to certify the proper torquing of all terminations.

Notes:

- When equipment torque labels cannot be read, or the label is missing, it is acceptable to use values found in NFPA 70 Informative Annex I.
- If terminals have been over-torqued, then damaged equipment must be replaced.

Electrical Equipment Rooms

Code Reference: 2022 California Electrical Code Article 110.26

Published: October 1987 Revised: January 2023


Section 110.26 uses the term "equipment" instead of "switchboards and panelboards". The intent is to include any type of equipment that contains overcurrent, switching, or control devices. The local authority having jurisdiction (AHJ) has made the following interpretations regarding this section:

- 1. Section 110.26 (C)(2) applies to equipment individually listed and marked with a rating of 1200A or more and over 6 feet wide.
- Where pull sections are installed, the nameplate rating of the pull section shall determine the rating of the equipment and be included in determining the width of the equipment. Future expansion shall be included in the design of the working space and equipment layout when pull sections are rated 1200A or larger. Consult the Utility for their requirements relating to pull sections.
- 3. There shall be one entrance to and egress from the required working space not less than 24 inches wide and 6½ feet high at each end of the working space. A single entrance to and egress from the required working space shall be permitted if either a. *unobstructed egress* or b. *extra working space* is provided.
 - a. *Unobstructed egress* is defined as an egress path located entirely outside the minimum required working space area, a minimum of 36 inches in width, and is clear of any obstructions, from the equipment to a safe location outside the room or area.
 - b. Extra working space is where the depth of the working space is twice that required by 110.26 (A)(1). A single entrance is permitted provided it is located so that the distance from the equipment to the nearest edge of the entrance is not less than the minimum clear distance specified in Table 110.26 (A)(1). This is a radial measurement from the equipment. (See drawing below.)
- 4. For electrical rooms containing equipment rated 800 amperes or more, personnel doors located within 25 feet of the equipment must have a minimum clear width of 32" (See CBC 1010.1,1), shall open out (in the direction of egress) and be equipped with listed panic hardware or listed fire exit hardware.

The Utility requires all doors to an electric meter room to be a minimum of 3'-0" wide or the width of the pull section, whichever is greater, and 6'-6" high. The door shall open in the direction of egress and be equipped with "lever-operated" hardware. Lever-operated hardware is a type that permits the door to be opened from inside the room without the use of hands.

Consult with the Utility for Services rated 800 amps or more.

Note: 5" conduit requires 6' of working clearance in front of the pull section.



Dedicated Equipment Space – Outdoor

Code Reference: 2022 California Electrical Code Article 110.26 (A) and (E)

Published: August 2005 Revised: January 2023

The intent of this newsletter is to address installations where existing gas meters are located within the dedicated equipment space of electrical service equipment.

Effective January 1, 2017, it is no longer acceptable for the gas meter to be located within the dedicated equipment space or the working space of the electrical service equipment.

Where an existing gas meter is located below the electrical service equipment, you must consult the local Utility before starting any work to confirm the new installation meets current standards.

Identifying Conductors

Code Reference: 2022 California Electrical Code Article 200.6, 210.5(C), 215.12

Published: January 2008 Revised: January 2023

The objective of this newsletter is to clarify when the identification and posting of the identification means are required for grounded circuit conductors, branch circuit conductors, and feeder conductors when more than one nominal voltage supplies a premise.

For existing buildings:

• When new branch circuit wiring is extended from an existing panelboard, those new circuits shall not be required to comply with Section 210.5 (C).

Unconditioned Enclosed Patio

Code Reference: 2022 California Electrical Code Article 210.52 (E)

Published: April 1985 Revised: January 2023

Enclosed patios are not considered to be habitable rooms and need not meet the outlet spacing requirements of Sections 210.52 (A). If the existing outdoor receptacle required by 210.52(E)(1) is enclosed by new construction, an additional GFCI protected receptacle shall be installed on the exterior wall of the Enclosed Patio. If adding an additional entrance or exit with grade level access, an additional switched lighting outlet shall be installed as per Section 210.70 (A)(2)(b). A suitably located single lighting outlet can serve more than one door.

ALL LIGHTING SYSTEMS MUST COMPLY WITH CALIFORNIA TITLE 24 ENERGY EFFICIENCY REQUIREMENTS.

Electrical Service Plan Check Requirements

Code Reference: 2022 California Electrical Code Article 220

Published: April 1985 Revised: January 2023

The intent of this newsletter is to clarify the general requirements for electrical plans for installations in the San Diego area.

For new, single-family, residential services, an approved plot plan showing the size and location of the s service equipment is required. * When the service is rated over 200 amperes, additional information may be required by the authority having jurisdiction (AHJ).

For Accessory Dwelling Unit (ADU) Electric Metering Requirements Consult the serving Utility.

All commercial/Multifamily services require complete electrical plans. These plans shall include, but not limited to:

- Service Equipment- Ampacity, Voltage, Number of Phases, and location of Service Equipment
- The Short Circuit Current Rating (SCCR) of equipment
- Feeder and Branch Circuit Overcurrent Devices
- Conductor Type and Sizes
- Panel Schedules describing both New and Existing Loads
- Load Calculations
- Fault-Current Calculations (if applicable)
- Conductor Type, Size, and wiring methods to be used
- Grounding and bonding details

Calculations to justify the proposed installation must be provided. Generally, power, lighting and single-line diagrams will be required as well as plans showing the location of all proposed electrical equipment to be installed.

All electrical plans shall be signed as required by the State of California Business and Professions Code. Where applicable, electrical plans shall contain the California Energy Code Compliance document Title 24, Part 6.

Note: These general plan requirements are based on typical installations. An AHJ may find it necessary to require additional plans or calculations at any stage of design or construction.

- * Consult with an AHJ for specific requirements based on size of service.
- * Consult with Local Utility

Number of Services

(Page 1 of 4)

Code Reference: 2022 California Electrical Code Article 230.2

Published: December 1981 Revised: January 2023

Some of the multiple services permitted as exceptions to Section 230.2 conflict with other provisions of Section 230, with SDG&E policy, and with established wiring methods in the San Diego area. Such services can present a hazard in certain normal and emergency situations.

The intent of this newsletter is to establish conditions regarding the installation of multiple services that resolve such conflicts and provide for safety in both normal and emergency situations. Contact the authority having jurisdiction (AHJ) for zoning requirements that will determine whether more than one service will be allowed to a premise.

Section 230.2. Number of Services: The basic requirement of 230.2 is that a building or other structure shall be supplied by only one service. However, the use of additional services is permitted by 230.2 (A) through (D). This article describes those conditions where more than one service is permitted. If more than one service is installed, 230.2 (E) requires a permanent plaque or directory be installed at each feeder a disconnect location denoting all other feeders and branch circuits supplying that building or structure and the area served by each.

- (B) Special Occupancies. By special permission, additional services shall be permitted for [either of] the following:
 - (1) Multiple-occupancy buildings where there is no available space for service equipment accessible to all occupants ("Multiple-occupancy" is interpreted to mean "multiple-tenant")
 - (2) A single building or other structure sufficiently large* to make two or more services necessary
- * Structures Sufficiently Large: See SDG&E Service Standards & Guide, page SG 012.1-012.3, for dimensions.

Special permission for (B)(1) will not normally be granted unless the building is sufficiently large enough to qualify for a second service as outlined in (B)(2). For existing buildings, special permission will be considered on a case-by-case basis. Generally, conditions (1) and (2) above will be required as well as a plaque on each sub-panel to identify which service supplies the panel.

If the Utility agrees to provide an additional service, consult the Utility for their requirements.

Number of Services

(Page 2 of 4)

Code Reference: 2022 California Electrical Code Article 230.2

Published: December 1981 Revised: January 2023

(C) Capacity Requirements - Additional services shall be permitted under any of the following:

(1) Where the capacity requirements are in excess of 2,000 amperes at a supply voltage of 1,000 volts or less

For multiple services, consult utility and reference SDG&E Service Standards & Guide pages SG 012.1-012.3.

- (2) Where the load requirements of a single-phase installation are greater than the serving agency [local utility] normally supplies through one service, or
- (3) By special permission.

Note: The disconnect(s) for such separate services shall be grouped.

(D) Different Characteristics - Additional services shall be permitted for different voltages, frequencies, or phases, or for different uses, such as for different rate schedules.

Note: The disconnect(s) for such separate services shall be grouped. A service of a different class is not required to be grouped with another service of a different class serving the building or structure.

SDG&E will not grant a second service unless the phase-to-neutral voltage is different than that of the existing service, regardless of the number of phases, except for capacity requirements as noted in (C) above.

- (E) Identification Where a building or structure is supplied by more than one service, or any combination of branch circuits, feeders, and services, a permanent plaque or directory shall be installed at each service disconnect location denoting all other services, feeders, and branch circuits supplying that building or structure and the area served by each. See Section 225.37
- Note 1: The plaque or directory required by Section 230.2(E) shall be manufactured in metal or plastic, suitable for the environment, with engraved or machine-printed lettering or electro-photo-plating in a contrasting color. The plaque shall include a footprint of the entire building, properly oriented, with the area served by each service clearly delineated. The plaques shall be located at the service disconnect and securely fastened by permanent means acceptable to the AHJ.
- Note 2: Doors into electrical meter rooms shall be marked with a plainly visible and legible sign stating, "Electric Meter Room", "Electric Room", or " Meter Room". If there are multiple electric meter rooms, the doors must be marked "Electric Meter Room #___ of ____", as appropriate. Reference 2022 California Fire Code, Chapter 6, Section 603.4.1 Labeling.

In addition to the above requirements, when a building has more than one electric meter room, SDG&E requires that a plaque is secured to the exterior door of each electric meter room identifying the suites served by the meters in that room. Reference Service Standards & Guide, pages SG 017.1-017.3

(Page 4 of 4)

Code Reference: 2022 California Electrical Code Article 230.2

Published: December 1981 Revised: January 2023


TYPICAL PLAQUE FOR EXISTING BUILDINGS WITH INTERMIXED SERVICES



THERE IS (1) OTHER SERVICE ON THIS BUILDING AS SHOWN BELOW. EACH OF THESE SERVICES SUPPLY LOADS THROUGHOUT THE BUILDING.

CONFIRM THE ACTUAL SERVICE CONNECTIONS BEFORE BEGINNING ANY ELECTRICAL WORK IN THIS BUILDING.

PLAQUES ARE REQUIRED ON EACH DISTRIBUTION PANEL TO IDENTIFY WHICH SERVICE SUPPLIES THAT PANEL.



The plaque or directory shall be manufactured in metal or plastic, suitable for the environment, with engraved or machine-printed lettering or electro-photo-plating in a contrasting color. The plaque shall include a properly oriented footprint of the entire building. The plaques shall be located at the service disconnect and securely fastened by permanent means acceptable to the AHJ.

Service Equipment – Disconnecting Means

Code Reference: 2022 California Electrical Code Article 230.70

Published: August 2005 Revised: January 2020

The intent of this newsletter is to provide a guideline for the location of a building's service disconnecting means.

Section 230.70 (A)(1) requires that the service disconnecting means be installed in a readily accessible location either outside of a building or structure or inside nearest the point of entrance of the service conductors.

An uncontrolled length of unfused conductor or bus in other than the Utility vault room or the service equipment room represents a hazard to the structure. Some buildings, due to design restrictions cannot have the service disconnecting means immediately adjacent to the service point.

A maximum of 10 feet of unfused conductor or bus from the service point to the building's service disconnecting means is permissible.

Ground-Fault Performance Testing

Code Reference: 2022 California Electrical Code Article 230.95

Published: April 1989 Revised: January 2023

Section 230.95 requires that ground-fault protection of equipment shall be provided for solidly grounded wye electrical services of more than 150 volts to ground but not exceeding 1,000 volts phase-to-phase for each service disconnect rated 1,000 amperes or more. The grounded conductor for the solidly grounded wye system shall be connected directly to ground . . . without inserting any resistor or impedance device. Subsection (C) requires testing of such system to assure that the equipment performs its intended function. This code section does not define who is to perform these tests or what information is to be included in the written report for the authority having jurisdiction (AHJ). Additionally, the requirement that these tests be performed on the system "when first installed on-site" often results in a test of a system that is incomplete. (See boxed text.)

A ground-fault protective system includes the ground-fault device (main disconnect and fault current sensor) and all wiring supplied by this device. For this reason, performance testing should normally be accomplished after all wiring is installed to ensure that the ground-fault device functions properly.

The following standards are established to assure that performance testing of ground-fault systems is accomplished in a uniform and acceptable manner:

- 1. Performance testing shall be performed by a third-party testing company acceptable to the AHJ and capable of demonstrating both the knowledge and the equipment necessary for such tests.
- 2. The ground-fault protective system must be tested after all wiring is installed and before the building is approved for final occupancy. This test must be performed prior to the AHJ authorizing the local utility to energize the service equipment.

Exception: The use of permanent service equipment for temporary power is common in the industry. The standards established by this newsletter are intended to recognize and permit this use. Where a temporary service is allowed for construction or equipment testing, prior to the final approval of the building, it is permissible for the testing of the ground-fault protective system to be accomplished in two separate parts.

Part 1. Testing of the ground-fault protective device must be completed before the service will be energized, along with testing all neutral and ground connections installed at the time of the Part 1 testing. This provides a reasonable level of protection for the service equipment during the period that temporary wiring is in use.

Part 2. All remaining neutral and ground connections not tested in Part 1 shall then be tested after all wiring is installed and before the building is approved for final occupancy. This testing normally requires a Utility outage, but the outage may be waived at the discretion of the testing company performing the test.

Note: Most ground-fault protective device testing requires that the service be de-energized. There are fees for the Utility to disconnect and reconnect the power. This applies to Part 1 and Part 2 if the service is required to be disconnected. Contact the Utility Planner for additional information.

(Page 1 of 2)

Ground-Fault Performance Testing

Code Reference: 2022 California Electrical Code Article 230.95

Published: April 1989 Revised: January 2023

3. A written record of the testing shall be provided, by the contractor, to the AHJ and shall include:

- a. A statement that the testing was performed in accordance to the manufacturer's instructions and in accordance with the procedures of the International Electrical Testing Association (NETA)
- b. A statement that the service grounding connections are correctly installed for a ground-fault system
- c. A statement that all neutral conductors in the distribution system have been tested and found to be ungrounded (Describe the test method used)
- d. A statement that the ground-fault equipment functioned properly when tested

(Page 2 of 2)

Grounding Electrode System & Grounding Electrode Conductor

Code Reference: 2022 California Electrical Code Article 250 Part III

Published: December 1981 Revised: December 2020

This section has generated many questions regarding the use of metal underground water pipes as grounding electrodes, the type of grounding electrodes acceptable as supplements to a metal underground piping system, and the type of grounding electrode required where there is no underground water piping on the premises.

The intent of this newsletter is to interpret Sections 250.50, 250.52, and 250.53 so that the requirements for grounding electrode systems are related to typical construction methods in a practical and consistent manner.

The intent of Section 250.50 is to ensure that at least one permanent and effective grounding electrode is installed for every building or structure, and that all electrodes are at the same potential with respect to the earth.

The following requirements for the installation of grounding electrodes meet the intent of Section 250.53, are consistent with typical construction methods, and are mandatory in the San Diego area:

- 1. Any construction that includes new concrete foundations shall be provided with a concrete-encased electrode installed per the requirements of Section 250.52 (A)(3).
 - Note: Where a concrete-encased electrode of the type identified in Section 250.52 (A)(3) is not available at final, a grounding electrode consisting of a minimum 20 feet of #2 bare copper conductor buried at a depth of 30" in a trench parallel to and at least 18" away from the foundation of building may be substituted. The conductor forming the grounding electrode must be continuous, unbroken and un-spliced, and be connected to the electrical service. Ground rods are not acceptable substitutes for the required grounding electrodes for new construction. A connector is always required where the grounding electrode conductor enters the service equipment.
- 2. Other new construction shall be provided with at least one of the grounding electrodes specified in sections 250.52 and installed in compliance with section 250.53. When new or replacement services are installed for existing buildings, existing underground metal water piping systems shall be supplemented by an additional electrode.
- 3. Grounding electrodes and grounding electrode conductors shall not be installed within wiring compartments with Utility-sealed access doors or covers. When the Utility installs their seal, the compartment is no longer considered accessible for inspection by the authority having jurisdiction (AHJ).

Concrete-Encased Electrode (Rebar)

Code Reference: 2022 California Electrical Code Article 250.52 (A)(3)


Published: May 1980 Revised: December 2020

The NEC makes it clear that underground metal water pipe can no longer be relied upon to assure a permanent and effective ground. To this end, several different grounding electrodes are identified as acceptable alternatives to the water pipe. The two most commonly used are the ground rod and the concrete-encased electrode. The use of ground rods and concrete-encased electrodes has raised questions.

The intent of this newsletter is to identify the minimum requirements for an acceptable concrete-encased electrode constructed of reinforcing steel (rebar), commonly called a "ufer" ground. These minimum requirements are as follows:

- 1. The #4 (½") or larger rebar to which the grounding electrode conductor is connected must be a minimum of 20 feet long, unbroken.
- 2. The total developed length of rebar at the bottom of the foundation must be no less than 20 feet. Where splices are necessary to obtain the required 20 feet of rebar, they must be made so that the 2 bars overlap by no less than 15 inches and are secured by at least 2 steel tie wires.
- 3. The rebar may only extend out of the slab in a dry location.
- 4. The rebar must extend out of the slab at least 6 inches and no more than 18 inches and the point of connection of the grounding electrode connector must be accessible.

Exception to #4: Where the connection of the grounding electrode conductor is encased in concrete and the connector is listed for concrete encasement.



Ground Rods

Code Reference: 2022 California Electrical Code Article 250.52 (A)(5)

Published: April 1985 Revised: December 2023

The following interpretations are intended to alleviate the more common problems and establish guidelines for a ground rod installation that will be generally accepted in the San Diego area:

- 1. It is acceptable to install one or more driven ground rods so that no more than 3 inches projects above ground level. Connection of the grounding electrode conductor shall be made on this accessible portion of the rod. The portion of the rod with the listing mark and a ground rod clamp listed for this purpose shall be inspected by the authority having jurisdiction (AHJ). Ground rods should be installed in areas where they are not subject to physical damage or shall be provided with protection from such damage.
- 2. Due to adverse soil conditions in the San Diego area, galvanized ground rod and/or pipe are not acceptable. Only listed stainless steel or non-ferrous rods are acceptable.
- 3. It shall also be permissible to completely cover the ground rods or ground plates provided the connection to the electrodes is made by listed means and inspected prior to covering.

Underground Metal Conduit

Code Reference: 2022 California Electrical Code Article 342, 344, 358

Published: April 1985 Revised: January 2020

It is the finding of the authorities having jurisdiction (AHJs) in the San Diego area that the soil conditions are not suitable for the direct burial of metallic conduits. Experience has shown that direct buried metallic conduits corrode rapidly.

Therefore, the direct burial of metallic conduit is prohibited in the San Diego area.

Exception 1: Listed Rigid Metal Conduit encased in concrete may be installed underground.

Exception 2: Intermediate Metal Conduit, Rigid Metal Conduit, and Electrical Metallic Tubing with an approved "factory-applied" non-metallic coating may be installed underground according to the manufacturer's listing and installation instructions. The AHJ may approve "field-applied" materials utilizing a listed primer and wrap, or coatings, for short sections or repairs of metallic raceways.

Note: These exceptions do not apply to conduits containing Utility-owned conductors. Consult the Utility for their requirements.

Busways

Code Reference: 2022 California Electrical Code Article 368

Published: August 2005 Revised: January 2023

The intent of this newsletter is to provide information only. The guidelines for the testing and acceptance of busway installations to ensure protection against potential life-safety hazards are included.

368.1 Scope. This article covers service-entrance, feeder, and branch-circuit busways and associated fittings.

368.2 Definition. The definition in this section shall apply within this article and throughout the Code.

Busway. A raceway consisting of a metal enclosure containing factory-mounted, bare or insulated conductors, which are usually copper or aluminum bars, rods, or tubes.

Busway installations are common for customer-owned service entrance installations from the Utility's service point to the service equipment, for unmetered feeder installations, for high-rise multifamily construction with remote metering, and for metered feeder installations to accommodate multiple taps for distribution. Several incidents of transposed phase or neutral conductors have resulted in the Utility closing into a fault condition when energizing a new transformer.

Busways shall be installed to meet the requirements of Article 368 and the manufacturer's installation instructions.

The Utility requires all service entrance and unmetered feeder busways be tested in accordance with the latest edition of the International Electrical Testing Association, Inc. (NETA), Acceptance Testing Specifications for Electrical Power Distribution Equipment and System. An independent testing organization acceptable to the AHJ and the Utility shall perform a continuity test on each busway section to confirm proper phasing and connection after each section is installed. The installer of the system shall provide a written test report to the AHJ and the Utility's Inspector. The AHJ will not release an inspection clearance to the Utility, nor will the Utility energize its transformer and the service until receipt, review, and acceptance of the written test report.

Switchboards & Panelboards

Code Reference: 2022 California Electrical Code Article 408

Published: June 1990 Revised: January 2020

The testing and listing standards for switchboards and panelboards require that the manufacturer identify any equipment intended to be installed in the field. The part or catalog number on a label in the switchboard or panelboard must identify equipment intended for field installation. The manufacturer must also provide any instructions necessary for the proper installation of such equipment. These requirements specifically include terminal connectors.

Most switchboards are designed to be connected to other sections or equipment with splice and through bus. Some switchboards also provide a set of factory-installed terminals for tapping a single circuit ahead of the service main. Very few switchboards are designed for the field installation of terminals on busses in order to make cable connections. Switchboards and panelboards designed for this application will include the required markings and installation instructions at the time they are originally manufactured.

The following procedures are established to ensure that switchboards and panelboards are installed in conformance with the testing and listing standard for such equipment:

- 1. Plan reviewers will approve plans showing field connection of cable to busses when there is documentation from the original equipment manufacturer (OEM) that the equipment is suitable for the field installation of terminals.
- 2. All new switchboards and panelboards will be inspected to determine compliance with the listing and manufacturer's instructions provided with the equipment.
- 3. All installations of new cables in existing switchboards and panelboards will be inspected to determine compliance with the listing and manufacturer's instructions provided with the equipment. In some cases, this will require changes to existing cable connections. Special attention will be given to conductor bending space, the routing of the conductors for heat dissipation in close proximity to the bus, and proper conductor support independent of energized bus.
- 4. Existing switchboards and panelboards not designed and marked for the field installation of terminals may be modified in the field, when:
 - a. A third-party manufacturer certifies compliance with applicable industry standards by providing approved engineered drawings prepared by a PE registered in the State of California and through a field evaluation acceptable to the AHJ with special attention given to conductor bending space, the routing of the conductors for heat dissipation in close proximity to the bus, and proper conductor support independent of energized bus as well as isolation methods to protect against inadvertent contact to energized bus ahead of the main.

Note: The Utility requires submittal of engineered drawings for approval prior to the installation of terminals or bussing for service entrance use. An example is when a field tap is required in an existing terminating enclosure to facilitate the addition of new service and metering equipment. Reference SDG&E Service Standards & Guide page SG 517.1.

Generators (Page 1 of 2)

Code Reference: 2022 California Electrical Code Article 445

Published: August 2007 Revised: January 2023

The purpose of this newsletter is to clarify the requirements for permanently installed stationary engine generators such as stand-alone (sole source of power) and back-up generator systems. Also, see Articles 700, 701, and 702 for emergency, legally required, and optional standby systems.

Types of Generator Systems

In general, there are two types of generator systems, "Stand-Alone" and "Back-Up" generators.

"Stand-Alone" – Generator systems provide the primary source of power to the premises wiring system and are not connected to SDG&E's distribution system. There may be additional sources of power, such as solar photovoltaic and batteries, that are interconnected with a "stand-alone" generator system to provide additional reliability.

"Back-Up" – There are two types of back-up generator systems:

- 1. The "Emergency System" is intended to supply power essential for safety to human life when normal power fails. When required, the generator shall be outside of the building or in a room designed to provide equivalent protection from fire or damage. The room shall be identified "Emergency Generator Room" in 1-inch block letters on a red plaque. Such systems have stringent requirements and use a completely isolated wiring system to ensure service in an emergency.
- 2. The "Standby System" is intended to protect private business or property and may be integrated into existing wiring. These systems can be turned on manually or automatically when the primary power fails. The standby system is intended only to provide back-up electricity and not intended to permanently replace existing Utility power.

Basic Requirements for Generator Systems:

- 1. A building permit is required.
 - a. Applications for permits must include three copies of a plot plan with a detailed description of the proposed work, the location of the generator, existing structures, utilities, property lines, etc.
 - b. All installations will require a single-line drawing showing the size of the generator, location of generator disconnecting means, the overcurrent protection, grounding and wiring methods, type of transfer device, and the connection to the current premises wiring system.

Generators (Page 2 of 2)

Code Reference: 2022 California Electrical Code Article 445

Published: August 2007 Revised: January 2023

c. The generator shall have adequate capacity and rating for the supply of all equipment intended to be operated at one time. (Equipment may be lighting, motors, heating, receptacles, and any other end use equipment the generator is intended to serve.)

- d. The manufacturer's data sheet(s) for the generator and transfer device shall be submitted.
- e. The complexity of the job will dictate which disciplines (mechanical, electrical, fire, structural, noise, hazardous materials, zoning, APCD, etc.) need to review and approve the plans. All systems powered by liquid fuel shall be approved by the authority having jurisdiction (AHJ) and all appropriate agencies, i.e. fire departments, County of San Diego, Department of Environmental Health, Hazardous Materials Division, Air Pollution Control District, etc.
- Permanent stationary engine generators shall be listed or evaluated to comply with UL 2200. Engine generators evaluated for hazardous locations are evaluated to both UL 2200 and NFPA 496.
- 3. Generator systems shall comply with the property line sound level limits per applicable AHJ. An acoustical analysis may be required prior to final inspection approval.
- 4. A plaque shall be installed at the electrical service disconnect indicating type and location of the on-site generator power source(s) and its disconnect location. See the sample plaque in Newsletter 705.10.
- 5. Generator locations must also comply with Article 430.14, Location of Motors.

Note: Portable generators intended for cord and plug connections are not allowed to be hard-wired or cord-connected to a premise wiring system without a code-compliant method of isolating the wiring service from the Utility Service. In addition, portable generators do not qualify as a required stand-alone or back-up system. Electrical permits are not normally issued for portable generators. However, consult with the appropriate AHJ and the Utility for specific requirements.

In compliance with the California Health & Safety Code, the Utility shall be notified in advance of installing "back-up" systems for review and approval of the transfer device and sequence of operations.

Transformers

Code Reference: 2022 California Electrical Code Article 450

Published: December 1981 Revised: January 2023

Means of Disconnect:

Transformers, other than Class 2 or 3, are required to have means of disconnect on the primary side of the transformer. If the means of disconnect is in a remote location, the disconnect shall be lockable in accordance with Article 110.25 and the transformer must be marked with the location of the disconnecting means. The means of identifying the remote disconnect shall be a plaque made of metal or plastic, with engraved or machine-printed letters in a contrasting color to the plaque, which shall clearly identify the location of the disconnect. The plaque shall be attached to the exterior of the transformer or on an adjacent wall with a method acceptable to the authority having jurisdiction (AHJ) per Article 450.14.

Ventilation:

Transformers in enclosed spaces shall have provisions to maintain an ambient temperature that does not exceed the temperature rating of the transformer. Note: Consideration of the conductor insulation temperature rating must be given in areas containing transformers when the ambient temperature exceeds 86 degrees °F (30 degrees °C). Refer to the ampacity correction factors in Tables 310.15 (B)(1) & (2) when needed. Transformer ventilations may be accomplished by natural or mechanical ventilation, by mechanical cooling, or by other means.

- 1. Mechanical ventilation that provides for air movement of three cubic feet per minute/per kVA of transformer rating shall be acceptable.
- 2. Mechanical cooling, which can be demonstrated to maintain an ambient temperature below that of the transformer rating, shall be acceptable.
- 3. Any other means, including combinations of the above methods which can be demonstrated to maintain an ambient temperature below that of the temperature rating of the transformer, shall be acceptable.

Note: For transformer vault rooms, see Article 450 III.

SDG&E requirements for transformer vaults are contained in the SDG&E's Transformer Vault Specification manual.

Examination of Electrical Equipment Exceeding 1,000 Volts

(Page 1 of 2)

Code Reference: 2022 California Electrical Code Article 490

Published: January 2014 Revised: January 2023

Intent: The San Diego area has seen an increase in the number of primary (systems exceeding 1,000 volts) services and distribution systems in all jurisdictions. The 2016 edition of the California Electrical Code includes a number of requirements for the installation, testing, and grounding of medium-voltage equipment and systems exceeding 1,000 volts nominal. The local authority having jurisdiction (AHJ) may have specific requirements regarding these installations. Consult your local AHJ if there are questions.

Code Requirements (Reference only)

- 1. Wire methods over 1,000 volts (Article 300.31)
- 2. Conductors rated 2,001-35kV (Article 311)
- 3. Grounding of AC systems over 1kV (Article 250, Part X)
- 4. Equipment over 1,000 volts nominal (Article 490)
- 5. Surge arresters over 1kV (Article 242, Part III)
- 6. Requirements for installations over 600 volts nominal (Article 110, Part III)
- 7. Transformers (Article 450)
- 8. Outside branch circuits and feeders over 1,000 volts (Article 225, Part III)
- 9. Substation design, documentation, and required diagram (Article 490.48)
- 10. PV systems between 1,000 and 1,500 volts (Article 690.7)

Plan, Equipment, Design, & Submittal Requirements

- 1. Plan submittals are required for all work.
- 2. Equipment submittals shall be accurate.
- 3. Design submittals are required from a State of California Licensed Electrical Engineer.

Utility Requirements

- Refer to Electrical Utility Service Equipment Requirements Committee (EUSERC) drawings.
- Medium-voltage service and metering equipment See SDG&E Service Standards & Guide SG 601-609
- Consult Utility for possible additional requirements for testing.

Examination of Electrical Equipment Exceeding 1,000 Volts

(Page 2 of 2)

Code Reference: 2022 California Electrical Code Article 490

Published: January 2014 Revised: January 2023

Inspection Requirements

1. Approved plans shall be available at the time of the inspection.

- 2. Manufacturer's installation instructions shall be available at the time of the inspection.
- 3. Equipment installed shall be both listed and labeled or field evaluated by an acceptable testing agency. See Electrical Newsletter pg.1 "Approval of Electrical Equipment" for additional information.
- 4. Grounding of Equipment shall meet the requirements of Article 250, Part X.
- 5. Terminations: When required by design specifications, hi-pot testing of cables, and/or partial discharge testing (to IEEE standards) shall be performed by a qualified company who either meets NETA standards or is NETA accredited.

Existing Systems

- 1. When working on existing systems, it is necessary to verify that requirements of CEC 250.180 are met.
- 2. Minimum testing of the existing equipment shall be line-voltage meggering to verify acceptable resistance and identify blatant defects.

Electric Vehicle Charging Systems (EVCS)

Code Reference: 2022 California Electrical Code Article 625

Published: January 2017 Revised: January 2023

The intent of this newsletter is to clarify general requirements for the permitting and inspection of plugin Electric vehicles (PEV). For specific requirements, consult your authority having jurisdiction (AHJ).

Plan Review and Design Criteria

The following items shall or may, depending on the AHJ's requirements, be required to obtain a permit for an EVCS installation:

General:

- 1. Plans are required to have electrical sections and a site plan. If a commercial grade system is proposed, then typically, a registered professional engineer may be required to design the electrical system.
- 2. For residential system level two, or less, consult the AHJ for further information and permitting requirements.
- 3. Zoning and Planning approvals may require consideration for setbacks, height limitations, parking requirements, open space easements, Utility easements, etc. Consult with the local zoning technician for further information.
- 4. For PEV charging stations provided as public accommodations facilities or within covered multifamily dwelling units, the designer should consult the California Building Codes for minimum access requirements.

The Electrical Section of the submittal shall include:

- 1. Provide cover sheet with each page identified for content.
- 2. Each submitted sheet shall have a page number.
- 3. Submit the appropriate number of plan sets and supporting documents when applying for permits. Verify with the AHJ the number of plan sets required.
- 4. Plans shall include the specifications, the level of charging, physical location of the existing electrical equipment, method of wiring, and new EVCS. Plans shall also indicate the applicable design code edition.
- 5. Plans shall include an electrical line diagram showing the number of EVCS with voltage and kilowatt ratings, the size of all electrical panel bussing and the size of the circuit breaker in amperes, and short circuit rating of equipment (including energy management system when used). Include wiring methods, sizing, grounding, and calculations in conformance with Article 625 and other applicable articles of the CEC.
- 6. Plans shall also include the manufacturer's data sheets for all equipment. All electrical equipment shall be listed for this purpose. All equipment includes, but is not limited to, inverters, controllers, metering, and interconnection system equipment.

Electric Vehicle Supply Equipment (EVSE)

Code Reference: 2022 California Electrical Code Article 625.48

Published: January 2014 Revised: January 2023

The serving Utility currently supports interconnection of an Electric Vehicle (EV) as a source of electrical energy for the purpose of operating in parallel with the Utility's electrical distribution system. California Electrical Code (CEC) Article 625 will apply.

Use of an EV as an optional source of standby electrical power must meet the requirements of CEC Article 702 and Utility review and approval of the proposed transfer switch is required.

Additional related laws in the State of California are as follows:

- The legislature of the State of California has enacted the California Health and Safety Code, Division 104, Part 15, Sections 119075 through 119090, which is intended to prevent electricity generated by permanent or portable electric generator from back feeding into a Utility electrical system.
- The California Code of Regulations, Title 8, Section 2320.9 states:
 - No electrical power source, permanent or temporary, shall be connected to a premises wiring system, or parts of such a system, unless positive means are used to prevent the transmission of electricity beyond the premises wiring system, or beyond any intentionally segregated parts of such a system. You may consult with the Utility for their requirements to qualify and be approved for an EV interconnection with the Utility distribution system.

When planning for your PEV, consult the Utility for advantageous Time of Use rate schedule information specific to EV charging.

Solar Photovoltaic Systems

Code Reference: 2022 California Electrical Code Article 690

Published: August 2005 Revised: January 2023

The intent of this newsletter is to clarify general requirements for permitting and inspection of Solar Photovoltaic systems. For specific requirements, consult your authority having jurisdiction (AHJ).

Other agencies may have requirements in addition to the following building department requirements, and include, but are not limited to:

- California Center for Sustainable Energy (CSE) State rebates
- California Department of Housing and Community Development (HCD) State agency for manufactured homes
- County of San Diego Department of Environmental Health (DEH)
- Fire Districts

Plan Review and Design Criteria

The following items shall or may, depending on the AHJ's requirements, be required to obtain a permit for a PV installation:

General:

- 1. Plans are required to include both electrical and structural design. The plans shall be designed and stamped in accordance with the Business and Professions Code. www.cab.ca.gov
- 2. For stand-alone PV systems (not interconnected with the Utility's system), consult the AHJ for further information.
- 3. If the proposed system is for a manufactured home, the State of California must also be contacted. Permit and inspection will be required from the State.
- 4. If proposed system is ground-mounted and the parcel has a septic system, you must have Department of Environmental Health approval for the location.
- 5. Zoning and Planning approvals may be required for consideration of setbacks, zoning height limitations, FAA restrictions, environmentally sensitive areas, brush management areas, open space easements, Utility easements, etc.
- 6. Supply-side connections require pre-approval by the Utility, the AHJ, and must not violate the panelboard manufacturer's listing. (see newsletter on **Approval of Electrical Equipment**)

(Page 1 of 3)

Solar Photovoltaic Systems

Code Reference: 2022 California Electrical Code Article 690

Published: August 2005 Revised: January 2023

The Electrical Section shall include:

1. Provide cover sheet with each page identified for content.

- 2. Each submitted sheet shall have a page number.
- 3. Submit appropriate number of plan sets and supporting documents when applying for permits. Verify with AHJ the number of plan sets required.
- 4. Plans shall include the specifications and physical location of the existing electrical equipment and new PV system. Design plans should also indicate the applicable electrical code edition.
- 5. An electrical single-line diagram showing the number of photovoltaic panels with voltage and kilowatt output, module series fusing, all disconnects, all inverters with input and output ratings, the size of all electrical panel bussing, and the size of the PV circuit breaker in amperes. Include wiring methods, sizing, grounding, and calculations in conformance with Article 690 and other applicable articles of the CEC.
- 6. Where a PV system includes Energy Storage System (ESS), ESS equipment shall comply with CEC 706 and CFC 1207.
- 7. Plans shall also include the manufacturer's data sheets for all equipment. All electrical equipment shall be listed for this purpose. All equipment includes but is not limited to inverters, modules, converters, controllers, and interconnection system equipment.
- 8. Devices used to ground PV Modules in accordance with CEC 690.43 (A) shall be listed and labeled for use with the specific module used and installed per the module manufacture installation instructions.
- 9. A plaque identifying the location of all customer self-generation equipment, the service point, the DC disconnect(s), and the AC disconnect for Utility Operation, if required, must be installed on the service equipment per the specifications shown on page 31 of this Newsletter.

(Page 2 of 3)

Solar Photovoltaic Systems

Code Reference: 2022 California Electrical Code Article 690

Published: August 2005 Revised: January 2023

The Structural Section shall include:

Plan Review Items:

- All roof-mounted and ground-mounted solar PV arrays will require an approved plot plan with all property, setback, and easement lines properly marked. Additionally, the location of all overhead power lines shall be shown on the plot plan. Consult with the Utility for clearance requirements from power lines. If the proposed system is roof-mounted, the plans must clearly indicate fire fighter access points and pathways as required by California Building Code (CBC) 3111, California Residential Code (CRC) R324, and California Fire Code (CFC) 1205. An elevation plan may be required. Consult with the AHJ for specific requirements.
- 2. A plan view of the installation of the PV solar panels including racks or other supports, details of the supporting structure, connections to the roof framing members, and the calculated roof and wind-loading values.
- 3. A registered architect, structural engineer, or civil engineer shall also stamp any plans requiring, but not limited to, soils reports, high-strength concrete footings, shop-fabricated support structures, field-fabricated ground-mounted support structures or field welding.
- 4. Check with the AHJ regarding specific requirements.

Design Criteria Items:

- 1. Dimensioned layout of the arrays and footing details for the supporting structure.
- 2. All arrays must be attached to either an approved racking system or the proposed support structure and attachment methods must be certified by a State of California licensed civil or structural engineer or subject to AHJ structural plan review and approval.
- 3. If the roof or wind-loading values exceed 5 pounds per square foot (or 7 pounds per square foot depending on the AHJ's requirement), the engineered system's plans and calculations must be stamped by a registered architect, structural engineer, or civil engineer.

Information on the Utility's requirements for interconnection and Net Energy Metering can be found on their website at www.sdge.com/solar. The Utility may require the customer to provide an AC disconnect(s) that is/are capable of being visibly checked in the open position and be lockable. The AC disconnect(s) is/are to be located immediately adjacent to the electric service and meter location. Contact the Utility for exceptions to the location of the AC disconnect(s) location.

PV systems will not be authorized for interconnection until all Utility requirements have been completed which includes the Utility receiving an inspection clearance from the AHJ.

(Page 3 of 3)


Alternate Sources of Power

Code Reference: 2022 California Electrical Code Article 705.10

Published: August 2005 Revised: January 2023

This is a sample of the plaque or directory required when there is an alternate source of power connected to the premises wiring system. For this plaque example, a Solar photovoltaic System is the alternate source of power.

A single plaque shall properly reflect the location of all alternate power sources, the disconnects, and the utility service point(s). The plaque or directory shall be manufactured in metal or plastic, suitable for the environment, with engraved or machine-printed lettering or electro-photo-plating in a contrasting color. The plaque shall include a properly oriented footprint of the entire building. The plaques shall be located at each source disconnect location and securely fastened by a permanent means acceptable to the AHJ.



A single plaque shall properly reflect the location of all alternate power sources, the disconnects, and the utility service point(s). The plaque or directory shall be manufactured in metal or plastic, suitable for the environment, with engraved or machine-printed lettering or electro-photo-plating in a contrasting color. The plaque shall include a properly oriented footprint of the entire building. The plaques shall be located at each source disconnect location and securely fastened by a permanent means acceptable to the AHJ.

Index

<u>Subject</u>	Page #
Approval of Electrical Equipment	1
Busways	19
Concrete-Encased Electrode (Rebar)	
Electric Vehicle Charging Systems (EVCS)	
Electric Vehicle Supply Equipment (EVSE)	
Electrical Equipment Rooms	
Electrical Service Plan Check Requirements	
Examination of Electrical Equipment Exceeding 1,000 Volts	24–25
Generators	
Ground Rods	
Ground-Fault Performance Testing	
Grounding Electrode System & Grounding Electrode Conductor	15
Identifying Conductors	
Number of Services	
Dedicated Equipment Space-Outdoor	
Service Equipment – Disconnecting Means	
Solar Photovoltaic Systems	
Switchboards & Panelboards	
Torque Requirements	
Transformers	
Unconditioned Enclosed Patio	
Underground Metal Conduit	18